

STORM WATER MANAGEMENT POND CERTIFICATION AND APPROVAL

DEVELOPER'S CERTIFICATE

"I HEREBY CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF NATURAL RESOURCES APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I WILL PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN AS-BUILT PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION."

4-13-82

SIGNATURE OF DEVELOPER

DATE

ENGINEER'S CERTIFICATE

"I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE MUST PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION."

7/22/82

SIGNATURE OF ENGINEER

DATE

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.

7/22/82

U.S. SOIL CONSERVATION SERVICE

DATE

THESE PLANS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

7/22/82

HOWARD SOIL CONSERVATION DISTRICT

DATE

APPROVED:

DEPARTMENT OF PUBLIC WORKS

7-28-82

CHIEF, BUREAU OF ENGINEERING

DATE

APPROVED:

OFFICE OF PLANNING AND ZONING

7-22-82

CHIEF, DIVISION OF LAND DEVELOPMENT AND ZONING ADMINISTRATION

DATE

S.W.M. POND SPECIFICATIONS

I. SITE PREPARATION

Areas under the embankment and structural works shall be cleared, grubbed and the topsoil stripped to remove all trees, vegetation, roots or other objectionable material. To facilitate clean out and restoration, it is recommended that the permanent pool area be cleared of all brush and trees.

II. STRUCTURAL BACKFILL

Backfill material shall be of the type and quality conforming to that specified for the adjoining fill material. The fill shall be placed in horizontal layers not to exceed four inches in thickness and compacted by hand tampers or other compaction equipment. The material needs to fill completely all spaces under and adjacent to the pipe. At no time during the backfilling operation shall driven equipment be allowed to operate closer than four feet, measured horizontally, to any part of a structure. Under no circumstances shall the contractor drive equipment over any part of a concrete structure or pipe unless there is a compacted fill of twenty-four inches or greater over the structure or pipe.

III. PIPE CONDUITS

A. CORRUGATED METAL PIPE

1. Materials - Aluminum Pipe - This pipe and its appurtenances shall conform to the requirements of AASHTO Specification M-196 or M-211, with watertight coupling bands.

2. Connections - All connections with pipes must be completely watertight. The drain pipe or barrel connection to the control structure shall be welded all around. Watertight coupling bands shall be used at all joints. Anti-seep collars shall be connected to the pipe in such a manner as to be completely watertight.

3. Bedding - The pipe shall be firmly and uniformly bedded throughout its entire length. Where rock or soft, spongy or other unstable soil is encountered, all such material shall be removed and replaced with suitable earth compacted to provide adequate support.

4. Laying pipe - The pipe shall be placed with inside circumferential laps pointing downstream and with the longitudinal laps at the sides.

5. Backfilling shall conform to structural backfill as shown above.

6. Other details (anti-seep collars, valves, etc.) shall be as shown on the drawings.

IV. CONCRETE

Concrete shall meet minimum requirements set forth in Maryland State Highway Administration Specifications for Materials, Highways, Bridges, and Incidental Structures, Article 20.07 (Portland Cement Concrete Mixtures), Mix No. 3.

V. STABILIZATION

All borrow areas shall be graded to provide proper drainage and left in a slightly condition. All exposed surfaces of the embankment, spillway and borrow areas shall be stabilized by seeding and applying straw mulch in accordance with Standards and Specifications for Soil Erosion and Sediment Control in Urbanizing Areas immediately after finish grading.

All exposed areas of the embankment and pond shall be stabilized by:

a. Spreading 4" topsoil

b. Working in 1 ton of ground limestone and 1,000 pounds of 10-10-10 fertilizer per acre.

c. Seed with 40 lbs./acre of "Kentucky 31" tall fescue, and 15 lbs./acre of Crownvetch inoculated.

d. Mulch with 1-1/2 tons straw per acre.

e. Tie down mulch with emulsified asphalt @ 348 gallons/acre.

#43

FISHER, COLLINS AND CARTER, INC.
CONSULTING ENGINEERS & LAND SURVEYORS
8388 COURT AVENUE
ELLICOTT CITY, MARYLAND 21043

VICINITY MAP

Scale: 1" = 1/2 mile

0-10-88

Rev. Date

Rev. No.

ALUM. PIPE TO BIT. COATED METAL

Revision Description

COLUMBIA

MARYLAND

OWNER AND DEVELOPER

HOWARD RESEARCH AND DEVELOPMENT CORP.

PROJECT AREA

PARCEL D-I

GUILFORD INDUSTRIAL PARK

E.G.U. SUBDIVISION

PROJECT TITLE

STORM WATER MANAGEMENT POND

PLAN

Des. By

C. GROVO

Scale

1" = 50'

Dwg. No.

1 OF 2

Des. By

A. BOGDAN

Date

MARCH 10, 1982

C.C.F. No.

Chk. By

R. CARTER

Approved

STATE OF MARYLAND

DEPT. OF PUBLIC WORKS

APPROVED

DATE

7/22/82

DATE

OWNER AND DEVELOPER

THE HOWARD RESEARCH AND DEVELOPMENT CORPORATION

10275 LITTLE PATUXENT PARKWAY

COLUMBIA, MARYLAND 21044

F-82-96

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.

U.S. SOIL CONSERVATION SERVICE DATE

THESE PLANS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

Robert J. Zichner 7/22/82
HOWARD SOIL CONSERVATION DISTRICT DATE

APPROVED: DEPARTMENT OF PUBLIC WORKS

7-28-82
CHIEF, BUREAU OF ENGINEERING DATE



APPROVED: OFFICE OF PLANNING AND ZONING

7-22-82
CHIEF, DIVISION OF LAND DEVELOPMENT AND ZONING ADMINISTRATION DATE


- Site Preparation Notes
 - Harrow or disc in areas proposed to be seeded the following materials
 - Pulverized limestone at 2 tons/acre.
 - Commercial fertilizer 10-10-10 at 3/4 tons/acre.
 - Super phosphate at 600 lbs./acre.
- Seeding
 - Sow the following seed mixture at the rate of 200 lbs./acre with a mechanical spreader.
 - Permanent: 40% Marion Blue Grass, 40% South Dakota Blue Grass and 20% Penn Lawn Creeping Fescue.
 - The seeded area shall then be raked with a York Rake (a minimum of 2 passes) covered and compacted with Cultipacker or other approved method.
- Mulching
 - Seeded areas shall be uniformly mulched immediately after seeding with unweathered small grain straw at the rate of 1 1/2 - 2 tons/acre.
 - Tie mulch down with liquid asphalt at 0.1 gal./s.y. or emulsified asphalt at 0.04 gal./s.y. or mulch netting.

CONSTRUCTION SEQUENCE

- INSTALL 15" ORIFICE, RISER PIPE AND SPILLWAY PIPE. CONTRACTOR SHALL BLOCK 15" CMP IN ACCORDANCE WITH DETAIL THIS SHEET.
- CONSTRUCT PARABOLIC RIP-RAP WATERWAY AND STABILIZE WITH PERMANENT SEEDING.
- REMOVE EXISTING 24" R.C.P. PIPES.
- CONTRACTOR SHALL STABILIZE ALL DISTURBED AREAS WITH PERMANENT SEEDING.
- REMOVE SEDIMENT FROM POND AND USE FOR BACKFILL FOR BASIN AT NORTHEAST PROPERTY CORNER. STABILIZE WITH PERMANENT SEEDING.
- REMOVE EXISTING 15" PIPE THAT WAS USED FOR FIRE POND OPERATION AND OPEN 15" ORIFICE PIPE.



CONCENTRIC TRASH RACK AND ANTI-VORTEX DEVICE (not to scale)




STORM WATER MANAGEMENT POND PROFILE

SCALE: 1" = 20' HOR. 1" = 5' VERT.


NOTE: 1) ALL PIPE JOINTS SHALL BE WATERTIGHT.
2) THE 15" METAL PIPE RISER THAT WILL BE IN CONTACT WITH THE CONCRETE BASE SHALL BE PAINTED WITH ONE COAT OF ZINC CHROMATE PRIMER.

NOTE: FOR CONSTRUCTION DETAIL AND SPECIFICATIONS, SEE STANDARD DRAWING GW-1, U.S. DEPARTMENT OF AGRICULTURE STANDARDS AND SPECIFICATIONS FOR SOIL AND SEDIMENT CONTROL.




PARABOLIC RIP-RAP CHANNEL (NO SCALE)

DESIGN POINT	T	D	V	SLOPE
Q-1	11'	1.5'	4.0 fps	3.50%
EX. 60" R.C.P.	24'	1'	3.0 fps	1.00%



SECTION A-A TRENCH DETAIL (NO SCALE)

EARTH FILL
The fill material shall be free from roots, stumps, wood, rubbish, oversized stones, frozen or other objectionable materials. The embankment shall be constructed to an elevation which provides for anticipated settlement to the design elevation. The fill height all along the length of the embankment shall be increased at least 5 percent above the design elevation (including freeboard) unless otherwise shown on the plans.
Areas on which fill is to be placed shall be scarified prior to placement of fill. Fill materials shall be placed in 8-inch maximum thickness (before compaction) layers which are to be continuous over the entire length of the fill. The most porous fill material shall be placed in the downstream portions of the embankment.
Compaction
95% of Standard Proctor by A.S.T.M. 698



CORRUGATED METAL ANTI-SEEP COLLAR DETAIL

NOT TO SCALE

8-10-83	ALUM. PIPE TO BIT. COATED METAL	
Rev. Date	Rev. No.	Revision Description
COLUMBIA M A R Y L A N D OWNER AND DEVELOPER HOWARD RESEARCH AND DEVELOPMENT CORP.		
PROJECT AREA PARCEL D-1 GUILFORD INDUSTRIAL PARK E.G.U. SUBDIVISION		
PROJECT TITLE STORM WATER MANAGEMENT POND DETAIL SHEET		
Des. By: C. CROVO	Scale: AS SHOWN	Dwg. No.: 2 OF 2
Drn. By: A. BOGDAN	Date: MARCH 10, 1982	C.C.F. No.
Chk. By: R. CARTER	Approved	