

CONSTRUCTION SEQUENCE

- 1. Install tree protection and silt fence.
- 2. Remove topsoil and stockpile on site.
- 3. Excavate mitigation area to within six inches (6") below finish grade and replace with topsoil up to finish grade. Stabilize disturbed area.
- 4. Haul excess material to approved location.
- 5. Plant mitigation area in accordance with planting plan.
- 6. Remove silt fence and tree protection fence. Stabilize.

GRADING NOTES

- 1. All vegetation, trash, and debris not marked in the field or on the plans, within the limits of disturbance, are to be disposed of off site in an approved landfill site.
- 2. All topsoil and excess cut is to be removed and disposed of off site.
- 3. Grade tolerance shall be within 0.2 feet.
- 4. The mitigation area shall be excavated six inches (6") below finished grade and six inches (6") of topsoil shall be uniformly spread to finished elevation. Topsoil shall be free of stone, lumps, plants, roots, and other debris including toxic substances. Topsoil shall have a pH range of 5.0 - 7.0.
- All final elevations shall be field checked by TSA Group, Inc. prior to the contractor removing equipment from the site.

CONSTRUCTION REQUIREMENTS

The site to be restored as forested wetland shall be graded, planted, and fertilized as shown on the plans and in accordance with these special provisions:

A. Planting schedule shall conform to the following conditions:

All trees and shrubs shall be installed between March 15 to Hay 15 or as directed by TSA Group, Inc. This work shall consist of furnishing and planting trees and shrubs as shown on the plans and/or as directed by the TSA Group, Inc. and all planting operations, cure and replacement as necessary to complete the work specified.

B. Plant Haterials:

- 1) Root-stock of the plant material shall be kept moist during transport from the source to the job site and until planted.
- 2) Plant material shall be planted in the soil with each planting pit excavated to size sufficient to contain the entire root-stock or the entire root-mass without cramping.
- Fertilize as required.
- C. Planting Bed Preparation:

The contractor shall prepare the area to be planted by spreading a uniform layer of six inches (6") of topsoil over the excavated area. Planting areas shall be approved by TSA Group, Inc. prior to the installation of the plant material.

D. Clean-Up:

Final clean up shall be the responsibility of the contractor and consist of removing all trash and materials incidental to the project, and disposing or them off-site. In addition, the construction procedure shall not damage any areas of existing plants which are to remain.

- E. The planting locations are approximate and may be varied upon the approval of TSA Group, Inc.. provided the relative ratios are maintained.
- F. Plant material selections are based upon availability at time of design. It specific plants are unavailable at time of planting, substitute plants conforming to above specifications will be made. All substitute plant materials are subject to the approval of TSA Group, Inc.

TEMPORARY SEEDING NOTES

Apply to graded or cleared areas where a short-term vegetative cover is needed.

Seedbed Preparation: Loosen upper three inches (3") of soil be raking, discing or other acceptable means before seeding, if not

Soil Amendments: Apply 600 lbs. per acre 10-10-10 fertilizer (14 lbs./1000 sq. ft.).

previously loosened.

Seeding: For periods March 1 thru April 30 and from August 15 thru November 15, seed with 2 1/2 bushel per acre of annual rye (3.2 lbs./1000 sq. ft.). For the period May 1 thru August 14, seed with 3 lbs. per acre of weeping lovegrass (.07 lbs./1000 sq. ft.). For the period November 16 thru February 28, protect site by applying 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring, or use sod.

Mulching: Apply 1 1/2 to 2 tons per acre (70 to 90 lbs./1000 sq. ft.) of unrotting small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gal per acre (5 gal/1000 sq. ft.) of emulsified asphalt on flat areas. On slopes, 8 ft. or higher, use 348 gal per acre (8 gal/1000 sq. ft.) for anchoring.

PERHANENT SEEDING NOTES

Apply to graded or cleared areas not subject to immediate further disturbance where a permanent longlived vegetative cover is needed.

Seedbed Preparation: Loosen upper three inches of soil be raking, discing or other table means before seeding, it not previously loosened.

Soil Amendments: In lieu of soil test recommendations, use on of the following schedules:

- 1) Preferred Apply 2 tons per acres dolomitic limestone (92 lbs./1000 square foot) and 500 lbs. per acre 10-10-10 Fertilizer (14 three-inches of soil). At time of seeding, apply 400 lbs. per acre 30-0-0 ureaform fertilizer (9 lb.s/1000 sq. ft.).
- 2) Acceptable Apply 2 tons per acre dolomitic limestone (92 lbs./1000 sq. ft.) before seeding. Harrow or disc into upper three-inches of soil.


Seeding: For the periods March 1 thru April 30, and August 1 thru October 15, seed with 60 lbs. per acre (1.4 lbs./1000 ft.) of Kentucky 31 tall fescue. And for the period May 1 thru July 31, seed with 60 lbs. Kentucky 31 per acre and 2 lbs. per acre (.05 lbs./1000 sq. ft.) of weeping lovegrass. During the period of October 16 thru February 28, protect site by: Option (1) 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring. Option (2) use sod. Option (3) seed with 60 lbs./acre Kentucky 31 tall fescue and mulch with 2 tons/acre well anchored straw.

Mulching: Apply 1 1/2 to 2 tons per acre (70 to 90 lbs./1000 sq. ft.) or unrotted small grain straw immediately after seeding. Anchor mulch gallons per acre (5 gal/1000 sq. ft.) or emulsified asphalt on flat gal/1000 sq. ft.) for anchoring.


Maintenance: Inspect all seeded areas and make needed repairs, replacements and reseedings.

RECOMMENDED MANAGEMENT APPROACH FOR WETLAND ENHANCEMENT AREA

- Wetland area shall be pariodically monitored for altered hydrologic conditions, invasive plant species, transition of wetland species to upland plants, and cultural impacts such as human disturbance, filling, non-point and point source pollution. Management techniques recommended to stabilize unnatural ecological successions include:
 - a) Altering the hydrological regime.
 - b) Removing undesirable plant species.
 - Restricting or discouraging destructive human interaction.
- 2. Vegetation demonstrating immediate stress or dieback shall be replaced. Soil and climate factors should be analyzed in relation to plant growth. The following management techniques shall be utilized:
 - a) Replace plant species with similar vegetation.
 - Add soil amendments to enhance survivability.
 - Replace plant species with specified alternative.
 - Prune plant species to establish desired growth characteristics and enhance survivability.




NOT TO SCALE



- FOREST PROTECTION DEVICE ONLY. 2. RETENTION AREA WILL BE SET AS PART OF THE REVIEW PROCESS. 3. BOUNDARIES OF RETENTION AREA SHOULD BE STAKED AND FLAGGED PRIOR TO INSTALLATION
- . ROOT DAMAGE SHOULD BE AVOIDED. 5. PROTECTIVE SIGNAGE MAY ALSO BE USED.
 - TREE PROTECTION FENCE

6. DEVICE SHOULD BE MAINTAINED THROUGHOUT CONSTRUCTION


NOT TO SCALE




SINGLE SHRUB PLANTING

SHRUB BED PLANTING

SHRUB PLANTING DETAIL NO SCALE






CONSTRUCTION NOTES FOR FASRICATED SILT FENCE


1. Noven wire fence to be fastened securely to fence posts with wire ties or staple:

2. FILTER CLOTH TO BE FASTENED SECURELY TO


- MOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION. When two sections of filter cloth adjoin each other they shall be over-lapped by SIX Inches and Folded.
- 4. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN
 BULGES DEVELOP IN THE SILT FENCE

SILT FENCE NOT TO SCALE





SUPPLEMENTAL INFORM, ATION



P.O. BOX 417 ELLICOTT CITY, MARYLAND 21043 LOCATION: (410) 465 - 4244

DRN: DBT

DES: JME

F-91-165 TAX MAP 47 6 ELECTION DISTRICT TITLE:

SCALE: AS SHOWN

HOWARD COUNTY, MD. WETLAND MITIGATION PLAN NOTES AND DETAILS 89-WQ-0163 DATE: JANUARY 26, 1993

JULY 22, 1993 PROJECT NO. 0084

F-91-165

DRAWING 3 OF 3