




SPRING HOUSE CREEK STREAM RESTORATION BLANDAIR REGIONAL PARK HOWARD COUNTY, MARYLAND



SHEET INDEX

1	TITLE SHEET WITH LOCATION MAP
2	EXISTING CONDITIONS
3	STREAM DESIGN
4	STREAM GEOMETRY
5	TYPICAL CHANNEL DETAILS
6	TYPICAL STREAM BANK DETAILS
7	PLANTING PLAN, NOTES, AND DETAILS
8	INVASIVE SPECIES CONTROL

REVISIONS	

DEPARTMENT OF
PUBLIC WORKS
9250 BENDIX ROAD
ELLICOTT CITY, MD 21043

KEY PLAN

GRAPHIC SCALES

SIGNATURE

PROFESSIONAL CERTIFICATION.
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE
PREPARED OR APPROVED BY ME, AND THAT I AM A DULY
LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND, LICENSE NO. 40896
EXPIRATION DATE: 8/12/2015.

WR&A
WHITMAN, REQUARDT
& ASSOCIATES, LLP
9030 Stony Point Parkway, Suite 220, Richmond, VA 23235

DEPARTMENT OF PUBLIC WORKS
HOWARD COUNTY, MARYLAND.

<i>J. J. K.</i> DIRECTOR OF PUBLIC WORKS	10/30/14 DATE	<i>Thomas R. Butler</i> CHIEF, BUREAU OF ENGINEERING	10/24/14 DATE
<i>D. McManis</i> CHIEF, BUREAU OF HIGHWAYS	10-30-2014 DATE	<i>Steve Shaver</i> CHIEF, TRANSPORTATION AND SPECIAL PROJECTS DIVISION	10/21/14 DATE

TITLE SHEET



Drawing No.
SR-1

Scale: 1"=100'

Date: 3/13/14 Sheet 1 of 8

Des: RCS Drawn: ASH Check: RCS

FILENAME: N:\2013\2014\03\01\SR1-4833800.DWG



SPRING HOUSE CREEK - EXISTING CONDITIONS

SITE SUMMARY

Spring House Creek is a 1300 linear foot perennial spring-fed stream. The spring, discharging from a historical spring house provides consistent baseflows which are also augmented by the many seeps along the stream channel. The upper portion of the stream is impacted by invasive species and a lack of a healthy riparian buffer. The lower portion of the stream is impacted by a single stormwater outfall. The upper 515 linear feet of the stream is located within the Blandair Regional Park boundaries, and the lower 788 feet is located on Columbia Association Property.

UPPER REACH

Upstream of the stormwater outfall, the channel appears to be relatively stable, often with groundwater seeps along its banks, and occasional wider areas where seep wetlands have developed in the floodplain.

The upper section within the park drains approximately 33 acres of the historical farmstead and adjacent residential community. Future development in the park does not include stormwater facility discharges or active recreation (i.e. soccer and baseball fields) in this area of the park, thus there is no anticipated change in the spring flows feeding this stream.

The reach between the spring house and the stormwater culvert is approximately 1,150 linear feet long. It has a steep channel slope (3.1% average), with several steep drops over bedrock or large tree roots. However, the stream is vertically stable due to the limited spring flows and bedrock grade control. The stream banks are steep and the channel is well entrenched into its valley. Despite the steepness of the banks, they are not eroding excessively. The stream has a cobble substrate along much of its length, with finer substrates in areas of lower slope. There are wetland seeps along the bank, and occasional small wet meadow areas where the channel widens and has accumulated sediment. There is very little pool development due to the steep slope.

The primary deficiency along the upper reach of the stream is the lack of shade and canopy and the presence of invasive species.

LOWER REACH

WR&A staff conducted a geomorphic survey of the lower 190 linear feet of stream channel. An 18 inch stormwater outfall, draining approximately 3.5 acres of adjacent residential development, discharges into the stream at the upper end of the reach. Storm flows from this outfall appear to be responsible for channel incision and bank erosion downstream of the outfall. The invert of the outfall is 3 feet above the stream bed, and flows through previously placed riprap and natural stone. The stones in the discharge channel are not stable, and many have been displaced. A large willow has fallen across the outfall, creating a significant void space in the bank.

DEPARTMENT OF PUBLIC WORKS
HOWARD COUNTY, MARYLAND.

Janet K... 10/30/14
DIRECTOR OF PUBLIC WORKS DATE

Thomas R. Butler 10/24/14
CHIEF, BUREAU OF ENGINEERING DATE

Steve Sharen 10/21/14
CHIEF, TRANSPORTATION AND SPECIAL PROJECTS DIVISION DATE

REVISIONS	

DEPARTMENT OF PUBLIC WORKS
9250 BENDIX ROAD
ELLCOTT CITY, MD 21043

KEY PLAN

GRAPHIC SCALES

SIGNATURE





PROFESSIONAL CERTIFICATION
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 40896 EXPIRATION DATE: 8/12/2015

WR&A
WHITMAN, REQUARDT & ASSOCIATES, LLP
9030 Stony Point Parkway, Suite 220, Richmond, VA 23235

EXISTING CONDITIONS

Drawing No.
SR-2

Scale: 1"=50', INSET: 1"=10'
Date: 3/13/14 Sheet 2 of 8
Des: RCS Drawn: ASH Check: RCS




EROSION AND SEDIMENT CONTROL ASSOCIATED WITH BLANDAIR REGIONAL PARK - PHASE J WATER AND SEWER EXTENSION. SEE SHEET 500.1 OF CONTRACT NO. 24-4779.

PROPOSED UTILITY EASEMENT


TAMAR DRIVE

Maryland's Guidelines To Waterway Construction
DETAIL 1.2: PUMP-AROUND PRACTICE

PLAN VIEW



SECTION A-A



STREAM FEATURES

RIFFLS:

FROM	TO	LENGTH	
R1	1+12	1+21	8.7 FT.
R2	1+35	1+42	7.0 FT.
R3	1+54	1+70	16.1 FT.
R4	1+95	2+09	14.5 FT.
R5	2+24	2+50	25.8 FT.

STONE TOE:

BANK	FROM	TO	LENGTH
ST1	LEFT	1+05	15.3 FT.
ST2	RIGHT	1+21	23.9 FT.
ST3	LEFT	1+42	14.54 FT.
ST4	RIGHT	1+70	14.95 FT.

LIVE SOIL LIFTS:


BANK	FROM	TO	LENGTH @ TOE	TOTAL LENGTH
LL1	RIGHT	1+23	19.0 FT.	57.0 FT.
LL2	LEFT	1+46	15.4 FT.	69.3 FT.
LL3	RIGHT	1+74	20.8 FT.	72.8 FT.

MATting w/LIVE STAKES

BANK	FROM	TO	LENGTH @ TOE	AREA
M1	RIGHT	0+92	14+23	17.7 SQ.YD.
M2	RIGHT	1+32	1+74	21.8 FT.
M3	RIGHT	1+93	2+21	28.8 FT.
M4	LEFT	0+90	0+98	15.0 FT.
M5	LEFT	1+02	1+46	34.1 FT.
M6	LEFT	1+53	2+34	76.4 FT.

EROSION AND SEDIMENT CONTROL NOTES

- ALL LONG-TERM STOCK PILES OF ROCK AND SOIL SHALL BE PROTECTED FROM EROSION BY INSTALLING A SILT FENCE AROUND THEIR PERIMETERS.
- CLEARING AND GRADING OF BANKS SHALL BE LIMITED TO AN AREA THAT CAN BE COMPLETED AND STABILIZED IN THE SAME DAY. ALL DISTURBED AREAS SHALL BE STABILIZED AT THE END OF EACH WORK DAY.
- WHEN WORK IN THE CHANNEL IS CONDUCTED IN THE DRY, A PUMP-AROUND SHALL BE USED TO BYPASS CLEAN WATER AROUND THE WORK AREA. IF A DEWATERING PUMP IS USED TO KEEP THE WORK AREA DRY, THE WATER SHALL BE DISCHARGED THROUGH A "DIRT BAG" OR OTHER APPROVED FILTERING DEVICE.
- UPON COMPLETION OF GRADING AND INSTALLATION OF BANK PROTECTION AND BED STRUCTURES, ALL STREAM BANKS SHALL BE MATTED WITH COIR FIBER MATTING AND ALL FLOODPLAIN AREAS SHALL BE SEEDING AND MULCHED WITH STRAW.



LARGE WOODY MATERIAL PLACEMENT

- PLACEMENT WILL BE RESTRICTED TO AREAS UPSTREAM OF RESTORATION REACH.
- ENGINEER WILL SELECT THREE LOCATIONS FOR PLACEMENT IN FIELD.
- ALL WOODY MATERIAL WILL BE SALVAGED ON SITE.
- ALL WORK PLACING WOODY MATERIAL IN AND AROUND THE STREAM WILL BE CONDUCTED WITHOUT MECHANICAL EQUIPMENT IN THE STREAM.
- SEE DETAIL, SHEET 5.
- AFTER INSTALLATION, SITE TO BE SEEDING WITH CHEWINGS FESCUE, SEE SHEET 6.

STORMWATER OUTFALL/STEP-POOL DATA

OUTFALL	INV. WEIR	INV. POOL
STEP 1	388.04	385.5
STEP 2	386.0	384.5
STEP 3	385.0	383.4

DEPARTMENT OF PUBLIC WORKS
 HOWARD COUNTY, MARYLAND.


Jan 7 R 10/30/14
 DIRECTOR OF PUBLIC WORKS DATE
Thomas R. Butler 10/24/14
 CHIEF, BUREAU OF ENGINEERING DATE
Steve Shaver 10/21/14
 CHIEF, TRANSPORTATION AND DATE
 SPECIAL PROJECTS DIVISION

REVISIONS


DEPARTMENT OF PUBLIC WORKS
 9250 BENDIX ROAD
 ELLICOTT CITY, MD 21043

KEY PLAN

GRAPHIC SCALES



SIGNATURE



PROFESSIONAL CERTIFICATION
 I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 40886 EXPIRATION DATE: 8/12/2015


WR&A
 WHITMAN, REQUARDT & ASSOCIATES, LLP
 9030 Stony Point Parkway, Suite 220, Richmond, VA 23235

STREAM DESIGN

Drawing No.
SR-3

Scale: 1"=10'
 Date: 3/13/14 Sheet 3 of 8
 Des: RCS Drawn: ASH Check: RCS

FILENAME: N:\42038-90\CAD\DWG\24-4779-500.1.dwg



Number	Length	Radius	Line/Chord Direction	Start Northing	Start Easting
L10	27.607		S46° 18' 44.93"E	563297.39	1362264.30
C10	25.181	40.000	S64° 20' 50.46"E	563278.32	1362284.26
L9	4.146		S82° 22' 55.99"E	563267.60	1362306.59
C9	7.549	8.000	S55° 20' 55.95"E	563267.05	1362310.70
L8	12.518		S28° 18' 55.91"E	563262.92	1362316.68
C8	18.506	20.000	S54° 49' 26.72"E	563251.90	1362322.62
L7	3.257		S81° 19' 57.52"E	563241.61	1362337.21
C7	13.585	10.000	S42° 24' 54.18"E	563241.12	1362340.43
L6	8.696		S03° 29' 50.83"E	563231.85	1362348.91
C6	13.552	6.000	S68° 12' 12.08"E	563223.17	1362349.44
L5	7.019		N47° 05' 26.67"E	563219.14	1362359.51
C5	12.333	6.000	S74° 01' 24.85"E	563223.92	1362364.65
L4	15.942		S15° 08' 16.38"E	563221.08	1362374.53
C4	15.470	16.000	S42° 50' 10.50"E	563205.70	1362378.69
C3	9.175	16.000	S54° 06' 21.64"E	563194.79	1362388.80
L3	14.468		S37° 40' 38.65"E	563189.49	1362396.13
C2	13.214	24.000	S53° 27' 00.39"E	563178.04	1362404.98
L2	13.299		S69° 13' 22.13"E	563170.27	1362415.46
C1	8.751	80.000	S66° 05' 20.67"E	563165.55	1362427.89
L1	5.293		S62° 57' 19.21"E	563162.00	1362435.89

REVISIONS	

DEPARTMENT OF
PUBLIC WORKS
9250 BENDIX ROAD
ELLCOTT CITY, MD 21043

KEY PLAN

GRAPHIC SCALES

SIGNATURE

10-2-14

PROFESSIONAL CERTIFICATION:
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 40899, EXPIRATION DATE: 8/12/2015.

WR&A
WHITMAN, REQUARDT & ASSOCIATES, LLP
9030 Stony Point Parkway, Suite 220, Richmond, VA 23235








STREAM GEOMETRY

Drawing No.
SR-4

Scale: 1"=10'

Date: 3/13/14 Sheet 4 of 8

Des: RCS Drawn: ASH Check: RCS




DEPARTMENT OF PUBLIC WORKS
HOWARD COUNTY, MARYLAND.

Jan R 10/30/14
DIRECTOR OF PUBLIC WORKS DATE


Thomas P. Butler 10/24/14
CHIEF, BUREAU OF ENGINEERING DATE

Steve Shaver 10/21/14
CHIEF, TRANSPORTATION AND SPECIAL PROJECTS DIVISION DATE


FILENAME: \\MARB03-00\CAD\DWG\VEL-SR01_4203001.DWG




A CROSS SECTION DETAIL
SR-3 RIFFLE GRADE CONTROL NTS




C CROSS SECTION
SR-4 TYPICAL RIFFLE NTS




D CROSS SECTION
SR-4 TYPICAL POOL NTS




B PROFILE
SR-3 RIFFLE GRADE CONTROL NTS




F TYPICAL SECTION (A-A')
SR-3 STEP POOL NTS




H TYPICAL SECTION (B-B')
SR-3 STEP POOL NTS



E TYPICAL PLAN VIEW
SR-3 STEP POOL NTS



G TYPICAL PROFILE
SR-3 STEP POOL NTS



I TYPICAL FOOTER/WEIR ROCK
SR-3 STEP POOL NTS

DEPARTMENT OF PUBLIC WORKS
HOWARD COUNTY, MARYLAND.

George De... 10/30/14
DIRECTOR OF PUBLIC WORKS DATE
Thomas R. Butler 10/24/14
CHIEF, BUREAU OF ENGINEERING DATE
Steve Shaver 10/21/14
CHIEF, TRANSPORTATION AND SPECIAL PROJECTS DIVISION DATE

REVISIONS	

DEPARTMENT OF PUBLIC WORKS
9250 BENDIX ROAD
ELLCOTT CITY, MD 21043

KEY PLAN

GRAPHIC SCALES

SIGNATURE

10-2-14

PROFESSIONAL CERTIFICATION
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 40895
EXPIRATION DATE: 8/12/2015


WR&A
WHITMAN, REQUARDT & ASSOCIATES, LLP
9030 Stony Point Parkway, Suite 220, Richmond, VA 23235

TYPICAL CHANNEL DETAILS


Drawing No.
SR-5

Scale: NTS
Date: 3/13/14 Sheet 5 of 8
Des: RCS Drawn: ASH Check: RCS


FILENAME: W:\4228-DC\ACTIVITY\PEL-SR5-#28300.DWG




I CROSS SECTION
SR-3 COIR FIBER MATTING W/LIVE STAKES NTS




J TYPICAL
SR-6 DEAD STAKE DETAIL NTS




K TYPICAL SECTION
SR-3 STONE TOE WITH LIVE SOIL LIFTS NTS



L PLAN VIEW
SR-3 COIR FIBER MATTING DETAIL NTS



M LARGE WOODY MATERIAL DETAIL
SR-3 NTS



O CROSS SECTION - STONE TOE WITH
SR-3 COIR FIBER MATTING AND LIVE STAKES NTS

REVISIONS	

DEPARTMENT OF
PUBLIC WORKS
9250 BENDIX ROAD
ELLCOTT CITY, MD 21043

KEY PLAN

GRAPHIC SCALES

SIGNATURE

PROFESSIONAL CERTIFICATION.
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 40896. EXPIRATION DATE: 8/12/2015.

WR&A
WHITMAN, REQUARDT & ASSOCIATES, LLP
9030 Stony Point Parkway, Suite 220, Richmond, VA 23235

TYPICAL STREAM BANK DETAILS

Drawing No.
SR-6



Scale: NTS
Date: 3/13/14 Sheet 6 of 8
Des: RCS Drawn: ASH Check: RCS

DEPARTMENT OF PUBLIC WORKS
HOWARD COUNTY, MARYLAND.

James R. Miller 10/30/14
DIRECTOR OF PUBLIC WORKS DATE

Morris & Butler 10/24/14
CHIEF, BUREAU OF ENGINEERING DATE

Steve Shanan 10/21/14
CHIEF, TRANSPORTATION AND SPECIAL PROJECTS DIVISION DATE



LEGEND

	UPLAND BUFFER PLANTING AND SEEDING ZONE (2.6 ACRES)
	LOWER AND UPPER BANK PLANTING AND SEEDING ZONE (0.3 ACRES)

- PLANTING NOTES**
- Plants and seeds shall be obtained from a commercial supplier. The Contractor shall make arrangements with reliable sources to ensure that an adequate supply of the required plant and seed material is available.
 - In the event that a seed specified is not commercially available, the Contractor may request a substitution in writing. All requests for substitutions shall be made at least 2 months prior to seeding and be approved by the Engineer.
 - All plant material received from commercial suppliers shall conform to the current issue of the American Standard for Nursery Stock, published by the American Association of Nurserymen.
 - Requests for plant material substitution must be submitted in writing at least two months prior to planting, and the substitution must be approved by the Engineer.
 - The Contractor is responsible for installing all plant material in the appropriate season for each plant type. The planting season for container trees and shrubs shall be from October 28 through December 30 and February 1 through March 30. For all bioengineering materials (i.e. live stakes, whips) installation shall be in the dormant season, October 28 through March 30.
 - All plant material shall be uniformly shaped and have a vigorous root system. The plant material shall be healthy, vigorous, and free from defects, decay, abrasions of the bark, plant diseases, insect pest eggs, and all forms of infestations. The plant material must be fresh and free from transplant shock or visible wilt. Unhealthy plant stock and plants from cold storage are unacceptable and will be rejected.
 - All container grown stock shall have been propagated in a container long enough for the roots to have developed sufficiently to hold its soil when removed from the container. Container stock with poorly developed roots is unacceptable and will be rejected.
 - No seeding shall occur when the soil is frozen or flooded. No fescue shall be used on site.
 - The Contractor shall notify the Environmental Engineer a minimum of 48 hours prior to commencing planting or seeding operations.
 - The final location and orientation of all plant material, as well as the location of all planting zones, will be subject to the approval of the Engineer. The Contractor will be responsible for replanting or reseeding any plant material installed without the approval of the Engineer.
 - Each containerized plant shall be fertilized with 20-10-5 controlled-release tablets. Formulations vary considerably by manufacturer, and other formulations are acceptable, provided the tablets are not readily water-soluble. The tablets shall be buried within the planting pit near the plant's root system. Plant stock shall be fertilized at the following rates:

Stock	No. of Tablets
< 24"	1
2-3'	3
4-6'	4
 - During planting the Contractor shall water each plant with the following minimum quantities of water, unless otherwise directed by the Engineer:

Trees	1 gallon per plant
Shrubs	1 gallon per plant
Tubling	1 quart per plant

Live Stakes for Coir Fiber Matting

Linear Feet of matting	203
No. per Linear Foot	1
Total Live Branches	203

Scientific Name	Common Name	Indicator Status	Size	Stock	%	Quantity
<i>Cornus amomum</i>	Silky Dogwood	FACW	24"-36"	Live Stakes	100%	203

Live Branches for Live Soil Lifts

Linear Foot of Lifts	199
No. per Linear Foot	3
Total Live Branches	597

Scientific Name	Common Name	Indicator Status	Size	Stock	%	Quantity
<i>Cornus amomum</i>	Silky Dogwood	FACW	36"-48"	Live Whips	100%	597

Lower Bank Planting Zone (Approximately 1 every foot of bank)

Linear Feet	2660
Plants per linear foot	1
Total Plants	2,660

Scientific Name	Common Name	Indicator Status	Size	Stock	%	Quantity
<i>Alnus serrulata</i>	Smooth alder	FACW	8-16"	Tublings	15%	399
<i>Betula nigra</i>	River birch	FACW	8-16"	Tublings	15%	399
<i>C. occidentalis</i>	Bullnut Bush	OBL	2-3'	Live stakes	10%	266
<i>Cornus amomum</i>	Silky Dogwood	FAC	2-3'	Live stakes	20%	532
<i>Lindera benzoin</i>	Spicebush	FACW-	8-16"	Tublings	20%	532
<i>Sambucus canadensis</i>	Elderberry	FACW	8-16"	Tublings	10%	266
<i>Viburnum dentatum</i>	Arrowwood	FAC	8-16"	Tubling	10%	266
TOTAL					100%	2,660

Upper Bank Planting Zone (Approximately 1 every 5 feet of bank)


Linear Feet	2660
Plants per linear foot	0.2
Total Plants	536

Scientific Name	Common Name	Indicator Status	Size	Stock	%	Quantity
<i>Acer rubrum</i>	Red Maple	FAC	4-6'	Container	35%	187
<i>Carpinus caroliniana</i>	American Hornbeam	FAC	4-6'	Container	10%	54
<i>Cercis canadensis</i>	Redbud	FACU	3-4'	Container	10%	54
<i>Platanus occidentalis</i>	Sycamore	FACW	4-6'	Container	25%	133
<i>Sassafras albidum</i>	Sassafras	FAC	4-6'	Container	10%	54
<i>Viburnum dentatum</i>	Arrowwood	FAC	3-4'	Container	10%	54
TOTAL					100%	536


Upland Buffer Planting Zone (approx. 12' On Center)

Acres	2.63
Plants per Acre	350
Total Plants	927


Scientific Name	Common Name	Indicator Status	Size	Stock	%	Quantity
<i>Carya sp.</i>	Hickory sp.	FACU	4-6'	Container	25%	231
<i>Fagus grandifolia</i>	American Beech	FACU	4-6'	Container	5%	47
<i>Liriodendron tulipifera</i>	Tulip Poplar	FACU	4-6'	Container	35%	323
<i>Nyssa sylvatica</i>	Blackgum	FAC	4-6'	Container	10%	93
<i>Quercus alba</i>	White Oak	FACU	4-6'	Container	10%	93
<i>Quercus rubra</i>	Northern Red Oak	FACU	4-6'	Container	5%	47
<i>Viburnum prunifolium</i>	Blackhaw Viburnum	FACU	4-6'	Container	10%	93
TOTAL					100%	927



Q TYPICAL LIVE STAKE DETAIL
SR-7 NTS



R TREE AND SHRUB PLANTING CONTAINER DETAIL
SR-7 NTS




S SHRUB TUBELING/SEEDLING DETAIL
SR-7 NTS

REVISIONS

DEPARTMENT OF PUBLIC WORKS
9250 BENDIX ROAD
ELLCOTT CITY, MD 21043

KEY PLAN



SIGNATURE

10-2-14

WR&A
WHITMAN, REQUARDT & ASSOCIATES, LLP
9030 Stony Point Parkway, Suite 220, Richmond, VA 23135

PLANTING PLAN, NOTES, AND DETAILS

Drawing No. **SR-7**

Scale: 1"=40'

Date: 3/13/14 Sheet 7 of 8

Des: RCS Drawn: ASH Check: RCS

DEPARTMENT OF PUBLIC WORKS
HOWARD COUNTY, MARYLAND.

Jan 7 K 10/30/14
DIRECTOR OF PUBLIC WORKS DATE


James R. Butler 10/24/14
CHIEF, BUREAU OF ENGINEERING DATE

Steve Shaver 10/21/14
CHIEF, TRANSPORTATION AND SPECIAL PROJECTS DIVISION DATE

REVISIONS	

DEPARTMENT OF
PUBLIC WORKS
9250 BENDIX ROAD
ELLCOTT CITY, MD 21043

KEY PLAN



SIGNATURE


PROFESSIONAL CERTIFICATION:
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE
PREPARED OR APPROVED BY ME, AND THAT I AM A DULY
LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF
THE STATE OF MARYLAND, LICENSE NO. 40896
EXPIRATION DATE: 8/12/2015

WR&A
WHITMAN, REQUARDT
& ASSOCIATES, LLP
9030 Stony Point Parkway, Suite 220, Richmond, VA 23235

INVASIVE SPECIES
CONTROL

Drawing No.
SR-8

Scale: 1"=40'
Date: 3/13/14 Sheet 8 of 8
Des: RCS Drawn: ASH Check: RCS



Invasive Species Control/Management

The project includes the control of invasive plant species within a 3.0 acre riparian buffer. Contractor shall

- **Prebid Meeting:** Attend pre-bid meeting to review on-site conditions. All bidders must attend pre-bid meeting.
- **References:** Contractor shall provide references with bid submittal. Contractor shall list at least 5 references for vegetation control work in the last 3 years, including name, addresses and phone numbers. Contractor shall provide description of work for each reference.
- **Licensing:** All herbicide applicators shall be licensed as required by the state, and provide proof of licensing to Engineer/Owner. Crew leaders must be certified to apply herbicides and be on-site at all times. Documentation of licenses and certifications must be provide with bid.
- **Invasive Species Control Plan:** Contractor shall prepare an Invasive Species Management Plan and submit with Contract Bid. This plan must contain the following information:
 - The species of invasive plants that are addressed in the plan
 - The proposed method of control – mechanical and/or chemical for each species.
 - Method of control must include time of year requirements, name of herbicides to be used, all dyes, or surfactants to be used. If mechanical removal, Contractor must specify the equipment required, and how plant material will be disposed.
 - Potential impacts on non-target plant and animals.
 - Anticipated % control of target species
- **Herbicide Use:** All use of herbicides shall be in accordance with EPA regulations and all applicable state requirements. Any herbicide used along the stream banks must be labeled and approved by EPA for use along water and wetlands.
- **Local Permits:** Contractor is required to obtain any required permits from the County / Park Authority prior to the use of herbicides. Contractor is responsible for coordinating methods of control, safety requirements, time of day limits, and other requirements that the Park Authority may deem necessary.
- **Contract Duration:** The duration of this contract shall be two years, including two full growing season.
- **Performance Guarantee:** The Contractor shall achieve a minimum of 85% control of the target species at the end of the contract duration.
- **Target Species:**
 - Russian olive (*Elaeagnus angustifolia*)
 - multiflora rose (*Rosa multiflora*)
 - Japanese honeysuckle (*Lonicera japonica*)
 - garlic mustard (*Alliaria petiolata*),
 - mile-a-minute (*Persicaria perfoliata*)
 - Japanese stiltgrass (*Eulalia viminea*),
- **Non-Target Damage:** Limited damage to native herbaceous vegetation within the buffer zone is acceptable.
- **Application Log:** Contractor must maintain a log of all activities, including types of herbicides and amounts applied. Contractor must provide copies of logs to Engineer on a monthly basis.

Invasive Species Existing Conditions

The canopy and understory of the existing riparian buffer is very thin and overstory trees are young and short. The understory and thick herbaceous layer have a high presence of invasives. Invasive plant cover accounts for approximately 82% of the total vegetative cover. Dominant canopy species include black cherry (*Prunus serotina*; 48%) and black walnut (*Juglans nigra*; 35%). Other common overstory species include pin cherry (*Prunus pensylvanica*; 7%) and black locust (*Robinia pseudoacacia*; 4%). The most frequent size class of the dominant canopy species is 2"-5.9" dbh and canopy closure is 34 percent.

Common understory species include black cherry (*Prunus serotina*; 50%) and black walnut (*Juglans nigra*; 10%). Other understory species include sassafras (*Sassafras albidum*), Russian olive (*Elaeagnus angustifolia*), persimmon (*Diospyros virginiana*), dogwood (*Cornus sp.*), multiflora rose (*Rosa multiflora*), and grapevine (*Vitis sp.*). Common herbaceous species include Japanese honeysuckle (*Lonicera japonica*), garlic mustard (*Alliaria petiolata*), field garlic (*Allium vineale*), northern red oak (*Quercus rubra*), mile-a-minute (*Persicaria perfoliata*), ladysthumb (*Polygonum cespitosum*), multiflora rose (*Rosa multiflora*), cowcress (*Lepidium campestre*), poison ivy (*Toxicodendron radicans*), Japanese stiltgrass (*Eulalia viminea*), and raspberry (*Rubus sp.*). Herbaceous cover is 97 percent.

The riparian buffer, particularly in the upper portion of this reach, lacks tree canopy and there is a large number of standing dead trees. The stream bank is mostly covered with multi-floral rose and herbaceous vegetation, with very little woody vegetation. Wetland seeps along the channel do support sedges and ferns typical of headwater seep wetlands.

Removal of Dead Standing Trees

The buffer along this stream has a significant number of standing dead trees. Any tree deemed a safety hazard to the public or to the crews responsible for planting and managing the riparian buffer shall be taken down. All removals shall be coordinated with the Park.

- Contractor shall mark /flag each tree to be removed, and have them reviewed and approved by Engineer or Park Authority.
- Contractor is responsible for coordinating method of removal, safety requirements, time of day limits, and other requirements that the Park Authority may deem necessary.
- Woody material that is not used in the restoration of the site can be chipped and distributed in a natural manor throughout the buffer.

DEPARTMENT OF PUBLIC WORKS
HOWARD COUNTY, MARYLAND.

Alvin... 10/30/14
DIRECTOR OF PUBLIC WORKS DATE

M... 10/30/2014
CHIEF, BUREAU OF HIGHWAYS DATE

M... 10/21/14
CHIEF, BUREAU OF ENGINEERING DATE

Steve Sharan 10/21/14
CHIEF, TRANSPORTATION AND
SPECIAL PROJECTS DIVISION DATE