




- GENERAL NOTES:**
- All construction shall be in accordance with the latest standards and specifications of Howard County plus MSHA standards and specifications, if applicable.
 - The contractor shall notify the Department of Public Works/Bureau of Engineering, Construction Inspection Division at (410) 313-1880 at least five (5) working days prior to the start of work.
 - The contractor shall notify "Miss Utility" at 1-800-257-7777 at least 48 hours prior to any excavation work.
 - Project Background: Subject property is zoned R-20 per October 18, 1993 Comprehensive Zoning Plan. Total Tract Area: 1.5184 Ac. Number of Proposed lots: 3 Buildable.
 - Traffic control devices, markings, and signing shall be in accordance with the latest edition of the Manual on Uniform Traffic Control Devices (MUTCD). All street and regulatory signs shall be in place prior to the placement of any asphalt.
 - Topographic survey was field run at 2' contour intervals by Clark, Finetrock & Sackett, Inc., dated Sept. 1999.
 - Horizontal and vertical control based on Howard County Control Stations 36DC, elev. 381.11 and 36DD, elev. 393.25.
 - Public water and sewer are to be utilized. Middle Patuxent drainage area. Contract # exist. 8" S (20-3363), exist. 8" W (44-3182).
 - Stormwater Management for quantity control on this project is fee-in-lieu. Water quality is to be provided for the two new lots by drywells.
 - Existing utilities & improvements shown are taken from available records, where not visibly evident from field survey. Trench compaction for storm drains within the road or street rights of way limits shall be in accordance with Howard County Design Manual, Vol IV, Std. No. G-2.01.
 - All compacted fill shall be in accordance with AASHTO T-180 requirements.



STRUCTURE SCHEDULE						
Str. No	Description	Inv. (IN)	Inv. (OUT)	Top Elev.	Remarks	
S-1	Metal end section	399.80	399.80	-	Ho. Co. Std. SD-5.61 (N. 560757.5723, E. 1346454.7802)	
I-2	D-inlet (slots all around)	401.20	401.00	404.50	Ho. Co. Std. SD-4.11 (N. 560790.2621, E. 1346566.0139)	
M-3	Shallow precast MH-48 dia.	403.00	402.25	407.30	Ho. Co. Std. G-5.12 (N. 560757.4162, E. 1346595.8691)	
M-4	Shallow precast MH-48 dia.	409.00	408.75	413.80	Ho. Co. Std. G-5.12 (N. 560785.2191, E. 1346699.1939)	
M-5	Shallow brick MH-48" sq.	413.60	410.00	415.60	Ho. Co. Std. G-5.05	

PIPE SCHEDULE		
Size	Type	Length
18"	HOPE	322'

NOTE: All HOPE pipes shall meet M294 standards.

ENGINEER'S CERTIFICATE
I hereby certify that this plan for Sediment and Erosion Control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District.
G. Nelson Clark 4-27-00
G. NELSON CLARK DATE

OWNER / DEVELOPER
T.B.I. Homes, Inc.
7320 Grace Drive
Columbia, MD 21044



DEVELOPER'S/BUILDER'S CERTIFICATE
"I/We certify that all development and construction will be done according to this plan of development and plan for sediment and erosion control and that all responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District or their authorized agents, as are deemed necessary."
Neil Pan 3/9/00
NAME DATE

APPROVED: DEPARTMENT OF PUBLIC WORKS
Richard M. Daniels 5-19-00
CHIEF, BUREAU OF HIGHWAYS DATE

APPROVED: DEPARTMENT OF PLANNING & ZONING
Cindy Hamstra 6/1/00
CHIEF, DIVISION OF LAND DEVELOPMENT DATE

David Vanaman 5/24/00
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

Reviewed for HOWARD S.C.D. and meets Technical Requirements
Signature _____ Date _____
U.S. Natural Resources Conservation Service
THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.
Approved _____

CLARK • FINEFROCK & SACKETT, INC.
ENGINEERS • PLANNERS • SURVEYORS
7135 MINTREL WAY • COLUMBIA, MD 21045 • (410) 381-7500 BALT. • (301) 621-8100 WASH.

DESIGNED D.A.B.	STORM DRAINAGE OUTFALL PLAN THROUGH LOTS 1 THRU 3, BENJAMIN GLEN A RESUBDIVISION OF BASSLER SUBDIVISION LOT 15 TAX MAP 35 GRID 12 PARCEL 179 FIFTH (5th) ELECTION DISTRICT HOWARD COUNTY, MARYLAND	SCALE As Shown
DRAWN ZH / CADD		DRAWING 1 of 2
CHECKED RS		JOB NO. 99-145
DATE 12-3-99		FILE NO. 99-145-D
		FOR: T.B.I. Homes, Inc. 7320 Grace Drive Columbia, MD 21044

21.0 STANDARDS AND SPECIFICATIONS FOR TOPSOIL

Definition

Placement of topsoil over a prepared subsoil prior to establishment of permanent vegetation.

Purpose

To provide a suitable soil medium for vegetable growth. Soils of concern have low moisture content, low nutrient levels, low pH, materials toxic to plants, and/or unacceptable soil gradation.

Conditions Where Practice Applies

- 1. This practice is limited to areas having 2:1 or flatter slopes where:
a. The texture of the exposed subsoil/parent material is not adequate to produce vegetative growth.
b. The soil material is so shallow that the rooting zone is not deep enough to support plants or furnish continuing supplies of moisture and plant nutrients.
c. The original soil to be vegetated contains material toxic to plant growth.

ii. For the purpose of these Standards and Specifications, areas having slopes steeper than 2:1 require special consideration and design for adequate stabilization.

Construction and Material Specifications

- 1. Topsoil salvaged from the existing site may be used provided that it meets the standards as set forth in these specifications.
ii. Topsoil Specifications - Soil to be used as topsoil must meet the following:
i. Topsoil shall be a loam, sandy loam, clay loam, silt loam, sandy clay loam, loamy silt, or loam.
iii. Where the subsoil is either highly acidic or composed of heavy clays, ground limestone shall be spread at the rate of 4-8 tons/acre.
ii. For sites having disturbed areas under 5 acres:
i. Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section 1 - Vegetative Stabilization Methods and Materials.

- iii. For sites having disturbed areas over 5 acres:
i. On soil meeting topsoil specifications, obtain test results dictating fertilizer and lime amendments required to bring the soil into compliance with the following:
a. pH for topsoil shall be between 6.0 and 7.5.
b. Organic content of topsoil shall be not less than 1.5 percent by weight.
c. Topsoil having soluble salt content greater than 500 parts per million shall not be used.
d. No soil or seed shall be placed on soil which has been treated with soil sterilants or chemicals used for weed control until sufficient time has elapsed (14 days min.) to permit dissipation of phytotoxic materials.
NOTE: Topsoil substitutes or amendments, as recommended by a qualified agronomist or soil scientist and approved by the appropriate approval authority, may be used in lieu of natural topsoil.
ii. Place topsoil (if required) and apply soil amendments specified in 20.0 Vegetative Stabilization-Section 1-Vegetative Stabilization Methods and Materials.

V. Topsoil Application

- i. When topsoiling, maintain needed erosion and sediment control practices such as diversions, Grade Stabilization Structures, Earth Dikes, Slope Sill Fence and Sediment Traps and Basins.
ii. Grades on the areas to be topsoiled, which have been previously established, shall be maintained, albeit 4" - 8" higher in elevation.
iii. Topsoil shall be uniformly distributed in a 4" - 8" layer and lightly compacted to a minimum thickness of 4". Spreading shall be performed in such a manner that seeding or seeding can proceed with a minimum of additional soil preparation and tillage.
iv. Topsoil shall not be placed while the topsoil or subsoil is in a frozen or muddy condition.

PERMANENT SEEDING NOTES

APPLY TO GRADED OR CLEARED AREAS NOT SUBJECT TO IMMEDIATE FURTHER DISTURBANCE WHERE A PERMANENT LONG-LIVED VEGETATIVE COVER IS NEEDED.

SEEDBED PREPARATION: Loosen upper three inches of soil by raking, discing or other acceptable means before seeding, if not previously loosened.

SOIL AMENDMENTS: In lieu of soil test recommendations, use one of the following schedules:

- 1) Preferred-Apply 2 tons per acre dolomitic limestone (92 lbs/1000 sq.ft.) and 600 lbs per acre 10-10-10 fertilizer (14 lbs/1000 sq.ft.) before seeding.
2) Acceptable-Apply 2 tons per acre dolomitic limestone (92 lbs/1000 sq.ft.) and apply 1000 lbs. per acre 10-10-10 fertilizer (23 lbs./1000 sq.ft.) before seeding.

SEEDING: For the periods March 1 thru April 30, and August 1 thru October 15, seed with 60 lbs. per acre (1.4 lbs./1000 sq.ft.) of Kentucky 31 Tall Fescue.

MULCHING: Apply 1 1/2 to 2 tons per acre (70 to 90 lbs./1000 sq.ft.) of unrotted small grain straw immediately after seeding.

MAINTENANCE: Inspect all seeded areas and make needed repairs, replacements and reseedings.

TEMPORARY SEEDING NOTES

SEEDBED PREPARATION: Loosen upper three inches of soil by raking, discing or other acceptable means before seeding, if not previously loosened.

SOIL AMENDMENTS: Apply 600 lbs. per acre 10-10-10 Fertilizer (14 lbs./1000 sq.ft.)

SEEDING: For periods March 1 thru April 30 and from August 15 thru November 15, seed with 2 1/2 bushel per acre of annual ryegrass (3.2 lbs./1000 sq.ft.).

MULCHING: Apply 1 1/2 to 2 tons per acre (70 to 90 lbs./1000 sq.ft.) of unrotted small grain straw immediately after seeding.

REFER TO THE 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR RATE AND METHODS NOT COVERED.

SEDIMENT AND EROSION CONTROL NOTES



- 1. A minimum of 48 hours notice must be given to the Howard County Department of Inspections, Licenses and Permits.
2. All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the 1984 MARYLAND STANDARDS AND SPECS. FOR SOIL EROSION AND SEDIMENT CONTROL and revisions thereto.
3. Following initial soil disturbance or redistribution, permanent or temporary stabilization shall be completed within:
a) 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all slopes greater than 3:1
b) 14 days as to all other disturbed or graded areas on the project site.
4. All sediment traps/basins shown must be fenced and warning signs posted around their perimeters in accordance with Vol. 1, Chapter 7, of the HOWARD COUNTY DESIGN MANUAL, Storm Drainage.
5. All disturbed areas must be stabilized within the time period specified above, in accordance with the 1984 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for permanent seedings, soil, temporary seeding and mulching (Sec. 6).
6. All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.

Table with columns: Total Area of Site, Area Disturbed, Area to be roofed or paved, Area to be vegetatively stabilized, Total Cut, Total Fill.

- 8. Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
9. Additional sediment control must be provided, if deemed necessary by the Howard County DPN Sediment Control Inspector.
10. On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls.
11. Trenches for the construction of utilities is limited to three pipe lengths or that which shall be back-filled and stabilized within one working day, whichever is shorter.
12. The total amount of silt fence = 120 L.F.
13. The total amount of super silt fence =
14. The total amount of earth dike =

CONSTRUCTION SEQUENCE:

Table with columns: NO. OF DAYS, 1. Obtain grading permit, 2. Install stabilized construction entrance, 3. Install sediment and erosion control devices and stabilize, 4. Construct storm drain, 5. Stabilize in accordance with State and Federal, 6. Stabilize in accordance with State and Federal, 7. Upon approval of the sediment control inspector, remove sediment and erosion control devices and stabilize.



Reviewed for HOWARD S.C.D. Chief of Inspections 5/17/00. U.S. National Resources Conservation Service. Approved: John R. Robertson 5/17/00.

APPROVED: DEPARTMENT OF PUBLIC WORKS. Approved: M. Jacobs 5-19-00. Approved: DEPARTMENT OF PLANNING & ZONING. Approved: J. Hamstra 6/1/00.

DEVELOPER'S/BUILDER'S CERTIFICATE. I/we certify that all development and construction will be done according to this plan of development and plan for sediment and erosion control.

ENGINEER'S CERTIFICATE. I hereby certify that this plan for Sediment and Erosion Control represents a practical and workable plan based on my personal knowledge of the site conditions.

CLARK • FINEFROCK & SACKETT, INC. ENGINEERS • PLANNERS • SURVEYORS. 7135 MINSTREL WAY • COLUMBIA, MD 21045. BENJAMIN GLEN LOTS 1-3. TAX MAP 35 PARCEL 179.