

SHEET INDEX	
SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	OLD FREDERICK ROAD WIDENING - PLAN AND PROFILE
3-4	OLD FREDERICK ROAD WIDENING - CROSS-SECTIONS
5	PHEASANT RUN COURT - PLAN AND PROFILE
6-7	STREET TREE PLANTINGS, GRADING AND SEDIMENT CONTROL PLAN
8	GRADING AND SEDIMENT CONTROL PLAN
9	LANDSCAPE PLAN
10	STORM DRAIN PROFILES
11	STORMWATER MANAGEMENT B.M.P. No. 1 DETAILS
12	STORMWATER MANAGEMENT B.M.P. No. 2 DETAILS
13	STORMWATER MANAGEMENT NOTES AND DETAILS
14	STORM DRAIN DRAINAGE AREA MAP
15	FOREST CONSERVATION PLAN
16	SOIL BORINGS
17-18	SEDIMENT & EROSION CONTROL NOTES & DETAILS
19	TRAFFIC CONTROL PLAN & FIRE SUPPRESSION DETAILS

FINAL ROAD CONSTRUCTION, GRADING AND STORMWATER MANAGEMENT PLAN

PHEASANT RUN EAST

LOTS 1 THRU 14, CEMETERY OPEN SPACE LOT 15, BUILDABLE PRESERVATION PARCEL "A" AND NON-PRESERVATION PARCELS "B" THRU "D"

ZONING: RC-DEO

TAX MAP No. 3 GRID No. 19 PARCEL No. 29

APPROVED: DEPARTMENT OF PUBLIC WORKS
Willie R. Smith 10-9-08
 CHIEF, BUREAU OF HIGHWAYS
 APPROVED: DEPARTMENT OF PLANNING AND ZONING
Cindy Hanotta 10/20/08
 CHIEF, DIVISION OF LAND DEVELOPMENT
Walter Dammann 10/16/08
 CHIEF, DEVELOPMENT ENGINEERING DIVISION

TRAFFIC CONTROL SIGNS				
ROAD NAME	C.L. STA.	OFFSET	POSTED SIGN	SIGN CODE
PHEASANT RUN COURT	0+39	26' L	STOP	R1-1
PHEASANT RUN COURT	1+00	13' R	SPEED LIMIT 25	R2-1
PHEASANT RUN COURT	2+50	13' L	STOP AHEAD	W3-1a
OLD FREDERICK ROAD	19+00	28' L	SEE SHEET 2	W2-1
OLD FREDERICK ROAD	17+50	28' L	RIGHT LANE MUST TURN RIGHT	R3-7R

ROADWAY INFORMATION CHART				
ROAD NAME	CLASSIFICATION	DESIGN SPEED	R/W WIDTH	
PHEASANT RUN COURT	PUBLIC ACCESS PLACE	25 M.P.H.	40'	


GENERAL NOTES

- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST STANDARDS AND SPECIFICATIONS OF HOWARD COUNTY PLUS MSHA STANDARDS AND SPECIFICATIONS IF APPLICABLE.
- THE CONTRACTOR SHALL NOTIFY THE DEPARTMENT OF PUBLIC WORKS / BUREAU OF ENGINEERING / CONSTRUCTION INSPECTOR DIVISION AT (410) 313-1880 AT LEAST (5) WORKING DAYS PRIOR TO THE START OF WORK.
- THE CONTRACTOR SHALL NOTIFY "MISS UTILITY" AT 1-800-257-7777 AT LEAST 48 HOURS PRIOR TO ANY EXCAVATION WORK BEING DONE.
- TRAFFIC CONTROL DEVICES, MARKINGS AND SIGNING SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD). ALL STREET AND REGULATORY SIGNS SHALL BE IN PLACE PRIOR TO THE PLACEMENT OF ANY ASPHALT.
- COORDINATES BASED ON NAD83 MARYLAND COORDINATE SYSTEM AS PROJECTED BY HOWARD COUNTY GEODETIC CONTROL STATIONS NO. 0031 AND NO. 07CA. STATION NO. 0031 NORTH 612408.14 FEET EAST 1292800.70 FEET STATION NO. 07CA NORTH 61231.30 FEET EAST 1292223.30 FEET
- THE TRAFFIC STUDY WAS PREPARED BY THE TRAFFIC GROUP DATED MAY, 2001 AND WAS APPROVED ON 11/02/01 UNDER 01-34.
- BACKGROUND INFORMATION:
 - SUBDIVISION NAME: PHEASANT RUN EAST
 - TAX MAP No.: 3
 - PARCEL No.: 29
 - ZONING: RC-DEO
 - ELECTION DISTRICT: FOURTH
 - TOTAL TRACT AREA: 60.051 AC.±
 - NO. OF BUILDABLE LOTS: 15; 14 PROPOSED LOTS & 1 BUILDABLE PRES. PARCEL
 - NO. OF OPEN SPACE LOTS: 1 (CEMETERY)
 - NO. OF NON-BUILDABLE PRESERVATION PARCELS: 3
 - NO. OF BUILDABLE PRESERVATION PARCELS: 1
 - AREA OF BUILDABLE LOTS: 13.319 AC.±
 - AREA OF OPEN SPACE LOTS: 13.187 SQ.F.T. or 0.303 AC.± (CEMETERY)
 - AREA OF NON-BUILDABLE PRESERVATION PARCELS: 8.922 AC.±
 - AREA OF BUILDABLE PRESERVATION PARCEL "A": 33.185 AC.±
 - TOTAL AREA OF ROADWAY TO BE DEDICATED: 1.652 AC.±
 - AREA OF FLOODPLAIN: 1.46 AC.±
 - AREA OF 25% OR GREATER SLOPES: 0.00 AC.±
 - PREVIOUS FILE NOS.: S-01-034 APPROVAL DATE: 3-19-02, P-06-014 APPROVAL DATE: 4-09-07
 - DEED REFERENCE: 4439 / 585
- THERE IS AN EXISTING CEMETERY LOCATED ON LOT 15 (AREA = 0.3017 AC.). THE PLANNING BOARD APPROVED THE ACCESS AND ACCOMMODATION PLAN FOR THE EXISTING CEMETERY ON JANUARY 10, 2002. THE LAYOUT AS SHOWN HAS BEEN DETERMINED BY THE DIRECTOR OF DPZ TO BE IN COMPLIANCE WITH THE LAYOUT APPROVED BY THE PLANNING BOARD.
- ALL FILL AREAS WITHIN ROADWAYS AND UNDER STRUCTURES SHALL BE COMPACTED TO A MINIMUM OF 95% COMPACTION OF AASHTO T-180.
- THE FOREST CONSERVATION REQUIREMENTS PER SECTION 16.120 OF THE HOWARD COUNTY CODE AND THE FOREST CONSERVATION MANUAL FOR THIS SUBDIVISION WILL BE FULFILLED BY PROVIDING 11.75 AC. OF ON-SITE AFFORESTATION. THE TOTAL FOREST CONSERVATION AREA IS 11.75 ACRES. THE FOREST CONSERVATION SURETY AMOUNT TO FULFILL THE FOREST CONSERVATION OBLIGATION IS \$229,479.40 BASED ON 11.75 AC. X 43,560 SQ.F.T. X \$0.50 PER SQ.F.T. SHALL BE POSTED WITH THE DEVELOPERS AGREEMENT FOR THIS FINAL PLAN, F-08-011.
- STORMWATER MANAGEMENT WILL BE PROVIDED IN ACCORDANCE WITH HOWARD COUNTY AND MARYLAND 378 SPECIFICATIONS. WATER QUALITY WILL BE PROVIDED BY TWO MICRO-POND FACILITIES, LEVEL SPREADERS & DRIVEWAY DISCONNECTION (PARCEL "A"). CFS IS BEING PROVIDED WITHIN THE MICRO-POND FACILITIES (EMP NO. 1 & 2). BOTH STORMWATER MANAGEMENT PONDS ARE PRIVATELY OWNED BY THE H.O.A. AND JOINTLY MAINTAINED BY THE H.O.A. AND HOWARD COUNTY, MARYLAND.
- THE NON-CRITICAL FLOODPLAIN STUDY FOR THIS PROJECT WAS PREPARED BY FISHER, COLLINS & CARTER, INC. AND APPROVED ON NOVEMBER 6, 2006.
- THE PROPOSED WATER AND SEWER SYSTEMS SHALL BE PRIVATE. THE STATE WATER APPROPRIATION PERMIT NUMBERS FOR THIS PROJECT IS: Pheasant Run East - #H02066007 (01)
- THE SUBJECT PROPERTY IS LOCATED OUTSIDE OF THE METROPOLITAN DISTRICT.
- TOPOGRAPHIC INFORMATION ESTABLISHED AT TWO FOOT INTERVALS AND IS BASED ON FLOWN AERIAL SURVEY BY HARTSDORF AERIAL SURVEYS ON 2/18/06.
- FOR FLAG OR PIPESTEM LOTS, REFUSE COLLECTION, SNOW REMOVAL AND ROAD MAINTENANCE IS TO BE PROVIDED AT THE JUNCTION OF THE FLAG OR PIPESTEM AND THE ROAD RIGHT-OF-WAY AND NOT ON THE FLAG OR PIPESTEM DRIVEWAY.
- THE WETLANDS DELINEATION STUDY AND FOREST STAND DELINEATION STUDY WAS PREPARED BY ECO-SCIENCE PROFESSIONALS, INC. DATED MAY, 2001 AND WAS APPROVED ON 11/02/01 UNDER S-01-34, MARYLAND, JULY, 1988 ISSUE.
- SOILS INFORMATION TAKEN FROM SOIL MAP NO. 2, SOIL SURVEY, HOWARD COUNTY, MARYLAND, JULY, 1988 ISSUE.
- THIS SUBDIVISION PLAN IS SUBJECT TO THE AMENDED FIFTH EDITION OF THE SUBDIVISION AND LAND DEVELOPMENT REGULATIONS PER CODE TITLE 28-2003 AND THE ZONING REGULATIONS AS AMENDED BY CONSOLE BILL NO. 75-2003. DEVELOPMENT OR CONSTRUCTION ON THESE LOTS OR PARCELS MUST COMPLY WITH SETBACK AND BUFFER REGULATIONS IN EFFECT AT THE TIME OF SUBMISSION OF A BUILDING OR GRADING PERMIT APPLICATION.
- SUBJECT PROPERTY ZONED RC-DEO Per 02/02/04 COMPREHENSIVE ZONING PLAN AND THE COMP LITE ZONING AMENDMENTS EFFECTIVE 07/28/06.
- THERE ARE NO STEEP SLOPES (25% OR GREATER) LOCATED ON THIS PROPERTY AS DEFINED BY THE HOWARD COUNTY SUBDIVISION AND LAND DEVELOPMENT REGULATIONS, SECTION 16.116.B.
- AS PER SECTION 104.F.4.b OF THE ZONING REGULATIONS, ONLY ONE EASEMENT HOLDER IS REQUIRED FOR PRESERVATION PARCELS DESIGNED SOLELY FOR SWM FACILITIES OR COMMUNITY SEWERAGE DISPOSAL SYSTEMS.

A. BUILDABLE PRESERVATION PARCEL "A"	C. NON-BUILDABLE PRESERVATION PARCEL "C"
OWNED: PRIVATELY	OWNED: HOMEOWNERS ASSOCIATION
EASEMENT HOLDERS: H.O.A. AND HOWARD COUNTY, MARYLAND	EASEMENT HOLDERS: HOWARD COUNTY, MARYLAND
USE: ENVIRONMENTAL PROTECTION	USE: S.W.M.
- B. NON-BUILDABLE PRESERVATION PARCEL "B"
- D. NON-BUILDABLE PRESERVATION PARCEL "D"


OWNED: HOMEOWNER'S ASSOCIATION	OWNED: HOMEOWNER'S ASSOCIATION
EASEMENT HOLDERS: HOWARD COUNTY, MARYLAND	EASEMENT HOLDERS: HOWARD COUNTY, MARYLAND & HOWARD COUNTY CONSERVANCY
USE: S.W.M.	USE: RECREATIONAL SPACE AND ENVIRONMENTAL PROTECTION
- NO GRADING, REMOVAL OF VEGETATIVE COVER OR TREES, PAVING AND NEW STRUCTURES SHALL BE PERMITTED WITHIN THE LIMITS OF WETLANDS OR STREAMS OR THEIR REQUIRED BUFFERS, FLOODPLAIN OR FOREST CONSERVATION EASEMENT AREAS.
- PERIMETER AND STORM WATER MANAGEMENT LANDSCAPING IN ACCORDANCE WITH SECTION 16.124 OF THE HOWARD COUNTY CODE AND LANDSCAPE MANUAL SHALL BE PROVIDED AS SHOWN ON THE LANDSCAPE PLAN SHEET OF THE ROAD CONSTRUCTION DRAWINGS FOR THIS FINAL PLAN. A LANDSCAPE SURETY FOR 133 SHADE TREES & 50 EVERGREEN TREES IN THE AMOUNT OF \$47,400.00 WILL BE POSTED AS PART OF THE DEVELOPER'S AGREEMENT, UNDER THIS PLAT, F-08-011.
- ALL WELLS TO BE DRILLED PRIOR TO FINAL PLAT APPROVAL. IT IS THE DEVELOPER'S RESPONSIBILITY TO SCHEDULE THE WELL DRILLING PRIOR TO FINAL PLAT SUBMISSION. IT WILL NOT BE CONSIDERED "GOVERNMENT DELAY" IF THE WELL DRILLING HOLDS UP THE HEALTH DEPARTMENT SIGNATURE OF THE RECORD PLAT.
- ALL EXISTING STRUCTURES TO BE RAZED MUST BE REMOVED PRIOR TO FINAL PLAT SIGNATURE.
- ALL WELLS AND SEPTIC FIELDS WITHIN 100 FEET OF PROPERTY LINE HAVE BEEN SHOWN.
- ALL MOING OPERATIONS THAT INVOLVE CROSSING THE WETLANDS AND FLOODPLAIN AREA ON BUILDABLE PARCEL "A" WILL BE DONE SO WITH A RUBBER TIRE TRACTOR TO MINIMIZE DISTURBANCE OF THE WETLAND AREA.
- SIGN POSTS: ALL SIGN POST USED FOR TRAFFIC CONTROL SIGNS INSTALLED IN THE COUNTY RIGHT-OF-WAY SHALL BE MOUNTED ON A 2" GALVANIZED STEEL, PERFORATED, SQUARE TUBE POST (1/4 GAUGE) INSERTED INTO A 2-1/2" GALVANIZED STEEL, PERFORATED, SQUARE TUBE SLEEVE (1/2 GAUGE) - 3' LONG. A GALVANIZED STEEL POLE CAP SHALL BE MOUNTED ON TOP OF EACH POST.
- DRIVEWAY (S) SHALL BE PROVIDED PRIOR TO ISSUANCE OF A USE AND OCCUPANCY PERMIT FOR ANY NEW DWELLINGS TO ENSURE SAFE ACCESS FOR FIRE AND EMERGENCY VEHICLES PER THE FOLLOWING (MINIMUM) REQUIREMENTS:

A) WIDTH - 12 FEET (16 FEET SERVING MORE THAN ONE RESIDENCES)
B) SURFACE - SIX (6") INCHES OF COMPACTED CRUSHER RUN BASE WITH TAR AND CHIP COATING
C) GEOMETRY - MAXIMUM 1% GRADE CHANGE AND MINIMUM 45 FOOT TURNING RADIUS
D) STRUCTURES (CULVERTS/BRIDGES) CAPABLE OF SUPPORTING 25 GROSS TONS (4250 LBS)
E) DRAINAGE ELEMENTS - PAVING 100 YEAR FLOOD WITH NO MORE THAN 1 FOOT DEPTH OVER DRIVEWAY SURFACE
F) STRUCTURE CLEARANCES - MINIMUM 12 FEET
G) MAINTENANCE - SUFFICIENT TO INSURE ALL WEATHER USE
- A TREE MAINTENANCE EASEMENT RUNNING ALONG THE EDGE OF THE PUBLIC ROAD RIGHT OF WAY AS SHOWN ON THESE PLANS IS RESERVED UPON ALL LOTS FRONTING ON THE SAID PUBLIC ROAD RIGHT OF WAY. THIS EASEMENT ALLOWS HOWARD COUNTY THE RIGHT TO ACCESS THE PROPERTY, WHEN NECESSARY, FOR THE SPECIFIC PURPOSE OF THE INSTALLATION, REPAIR AND MAINTENANCE OF COUNTY OWNED TREES LOCATED WITHIN THE BOUNDARIES OF THE PRIVATE LOTS. NO BUILDING OR STRUCTURE OF ANY KIND SHALL BE LOCATED ON OR OVER THE SAID EASEMENT AREA.
- NO HISTORIC STRUCTURES EXIST ON THIS SITE.
- THE GROUNDWATER APPROPRIATIONS PERMIT NUMBER IS H02066007 (01).



VICINITY MAP
SCALE: 1" = 2000'

FOURTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND



PLAN VIEW
SCALE: 1" = 200'

FISHER, COLLINS & CARTER, INC.
 CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS
 CENTRAL SQUARE OFFICE PARK - 10275 BALTIMORE NATIONAL PARK
 ELLICOTT CITY, MARYLAND 21114
 (410) 461-2955




ALDO M. MANNARELLI
 I hereby certify that these documents were prepared by me, and that I am a duly Licensed Professional Engineer under the laws of the State of Maryland, License No. 20748, Expiration Date 2-22-09.

OWNERS
 MARIO MANNARELLI, SR. & SERAFINA MANNARELLI,
 RAYMOND MANNARELLI & MARIO MANNARELLI, JR.
 P.O. BOX 482
 LISBON, MD, 21765
 (410) 461-2278


DEVELOPER
 HERITAGE LAND DEVELOPMENT, INC.
 15950 NORTH AVE.
 P.O. BOX 482
 LISBON, MD, 21765
 (410) 489-7900

PHEASANT RUN EAST
 LOTS 1 THRU 14, CEMETERY OPEN SPACE LOT 15,
 BUILDABLE PRESERVATION PARCEL "A" &
 NON-PRESERVATION PARCELS "B" THRU "D"
 ZONED "RC-DEO"
 TAX MAP No. 3, GRID No. 19, PARCEL No. 29
 FOURTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND
 DATE: SEPTEMBER, 2008
 SHEET 1 OF 19

K:\Drawings\3130651_Splinterman\FINALS-EAST\22P\AV\30651_SHEET 1 TITLE SHEET.dwg, 9/22/2008 2:30:00 PM, jsmesl



NO.	DESCRIPTION	DATE
REVISIONS		
APPROVED: DEPARTMENT OF PLANNING AND ZONING		
 CHIEF, DIVISION OF LAND DEVELOPMENT		10/2/08
 CHIEF, DEVELOPMENT ENGINEERING DIVISION		10/16/08
APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS		
 CHIEF, BUREAU OF HIGHWAYS		10-9-08



NOTE:
 CONTRACTOR SHALL CONTACT PARRIS ZIRKENBACH AT HOWARD COUNTY TRAFFIC PRIOR TO STARTING ANY PAVEMENT MARKINGS.

- NOTES:**
1. ALL LANE DESIGNATION TO BE PAINT LINE STRIPING.
 2. THE RIGHT TURN LANE MARKINGS (ARROWS AND ONLY) TO BE PERFORMED HEAT APPLIED TAPE.
 3. EXISTING PAVEMENT MARKINGS SHALL BE REMOVED BY GRINDING.
 4. ALL PAVEMENT MARKINGS (PAINT LINES) SHALL BE 5" WIDE UNLESS NOTED OTHERWISE.
 5. SEE SHEET 19 FOR "MAINTENANCE OF TRAFFIC" PLANS.



923-08
 DATE
 I, ALDO M. MANARELLI, hereby certify that these documents were prepared by me, and that I am a duly Licensed Professional Engineer under the laws of the State of Maryland, License No. 20748, Expiration Date 2-22-09.

PHEASANT RUN EAST
 LOTS 1 THRU 14, CEMETERY OPEN SPACE LOT 15, BUILDABLE PRESERVATION PARCEL "A" & NON-PRESERVATION PARCELS "B" THRU "D"


TAX MAP No. 3, GRID No. 19, PARCEL No. 29
 FOURTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND

OLD FREDERICK ROAD WIDENING
 PLAN AND PROFILE

OWNERS	DEVELOPER
MARIO MANARELLI, SR. & SERAFINA MANARELLI RAYMOND MANARELLI & MARIO MANARELLI, JR. 2929 SUMMIT CIRCLE ELLICOTT CITY, MARYLAND 21043 (410) 481-2278	HERITAGE LAND DEVELOPMENT, INC. 15500 NORTH AVENUE P.O. BOX 482 URBON, MD. 21785 (410) 489-7900

SCALE: AS SHOWN DATE: SEPTEMBER, 2008 DWG. NO. 2 OF 19
 DES. R.A.I. DRN. J.C.L. CHK. A.M.V.












FISHER, COLLINS & CARTER, INC.
 CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS
 100 NATIONAL SQUARE OFFICE PARK - 10272 BALTIMORE NATIONAL PIKE
 ELLICOTT CITY, MARYLAND 21042
 (410) 661-2895



APPROVED: DEPARTMENT OF PUBLIC WORKS
Wills R. Hall 10-9-08
 CHIEF, BUREAU OF HIGHWAYS DATE

APPROVED: DEPARTMENT OF PLANNING AND ZONING
Indy Hamer 10/20/05
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE

Chris Dammann 10/16/05
 CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE



MAJOR COLLECTOR
 DESIGN SPEED = 40 M.P.H.
OLD FREDERICK ROAD CROSS-SECTIONS

SCALE: 1" = 20' HOR.
 1" = 2' VERT.



OWNERS
 MARIO MANNARELLI, SR. & SERAFINA MANNARELLI,
 RAYMOND MANNARELLI & MARIO MANNARELLI, JR.
 2929 SUMMIT CIRCLE
 ELICOTT CITY, MARYLAND 21043
 (410) 461-2278









DEVELOPER
 HERITAGE LAND DEVELOPMENT, INC.
 15950 NORTH AVE.
 P.O. BOX 482
 LISBON, MD. 21765
 (410) 489-7900

**OLD FREDERICK ROAD CROSS-SECTIONS
 PHEASANT RUN EAST**
 LOTS 1 THRU 14, CEMETERY OPEN SPACE LOT 15,
 BUILDABLE PRESERVATION PARCEL "A" &
 NON-PRESERVATION PARCELS "B" THRU "D"
 ZONED "RC-DEO"
 TAX MAP No. 3, GRID No. 19, PARCEL No. 29
 FOURTH ELECTION DISTRICT, HOWARD COUNTY, MARYLAND
 DATE: SEPTEMBER, 2008
 SHEET 3 OF 19

FISHER, COLLINS & CARTER, INC.
 CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS
 CENTENNIAL SQUARE OFFICE PARK - 10272 BALTIMORE NATIONAL PIKE
 ELICOTT CITY, MARYLAND 21042
 (410) 461-2255

APPROVED: DEPARTMENT OF PUBLIC WORKS
 With R. M. M. 10-9-08
 CHIEF, BUREAU OF HIGHWAYS
 APPROVED: DEPARTMENT OF PLANNING AND ZONING
 Cindy Hammett 10/20/08
 CHIEF, DIVISION OF LAND DEVELOPMENT
 APPROVED: 10/16/08
 CHIEF, DEVELOPMENT ENGINEERING DIVISION

SECTION NUMBER	ROAD AND STREET CLASSIFICATION	CALIFORNIA BEARING RATIO (CBR)						
		3 TO <	5 TO <	>7	3 TO <	5 TO <	>7	
P-2	PARKING DRIVE AISLES: RESIDENTIAL AND NON-RESIDENTIAL WITH NO MORE THAN 10 HEAVY TRUCKS PER DAY LOCAL ROADS: ACCESS PLACE, ACCESS STREET CUL-DE-SACS: RESIDENTIAL	HMA SUPERPAVE FINAL SURFACE 9.5 MM, PG 64-22, LEVEL 1 (ESAL)	1.5	1.5	1.5	1.5	1.5	1.5
		HMA SUPERPAVE INTERMEDIATE SURFACE 9.5 MM, PG 64-22, LEVEL 1 (ESAL)	1.0	1.0	1.0	1.0	1.0	1.0
		HMA SUPERPAVE BASE 19.0 MM, PG 64-22, LEVEL 1 (ESAL)	2.0	2.0	2.0	3.5	2.0	2.0
		GRADED AGGREGATE BASE (GAB)	8.0	4.0	3.0	4.0	4.0	4.0
P-3	PARKING DRIVE AISLES: RESIDENTIAL AND NON-RESIDENTIAL WITH NO MORE THAN 10 HEAVY TRUCKS PER DAY LOCAL ROADS: ACCESS PLACE, ACCESS STREET CUL-DE-SACS: RESIDENTIAL MINOR COLLECTORS: RESIDENTIAL	HMA SUPERPAVE FINAL SURFACE 9.5 MM, PG 64-22, LEVEL 1 (ESAL)	1.5	1.5	1.5	1.5	1.5	1.5
		HMA SUPERPAVE INTERMEDIATE SURFACE 9.5 MM, PG 64-22, LEVEL 1 (ESAL)	1.0	1.0	1.0	1.0	1.0	1.0
		HMA SUPERPAVE BASE 19.0 MM, PG 64-22, LEVEL 1 (ESAL)	3.0	3.0	3.0	4.5	3.0	2.0
		GRADED AGGREGATE BASE (GAB)	10.0	6.0	3.0	6.0	6.0	6.0



- NOTES:
- WHEN EXISTING TRAVEL LANE IS LESS THAN THE REQUIRED 12' LANE CONTRACTOR SHALL REMOVE A MINIMUM OF 1' FULL DEPTH OF THE EXISTING ROADWAY. IF CURB AND GUTTER IS INSTALLED, PROVIDE A MINIMUM OF 4' OF WIDENING FROM FACE OF GUTTER PAN.
 - THE EXISTING PAVEMENT TO BE RESURFACED SHALL BE MILLED AT DEPTH OF 1 1/2" (MINIMUM).
 - THE RESURFACING SHALL BE PLACED TO THE CENTERLINE OF THE ROADWAY.
 - RESURFACING COURSE TO BE EQUAL TO THE SURFACE COURSE OF THE TYPICAL PAVEMENT SECTION.

EXISTING ROADWAY WIDENING STRIP (R-1.08)
NO SCALE

MAJOR COLLECTOR
 DESIGN SPEED = 40 M.P.H.
OLD FREDERICK ROAD CROSS-SECTIONS
 SCALE: 1" = 20' HOR.
 1" = 2' VERT.



9-23-08
 DATE
 I, ALDO M. M., hereby certify that these documents were prepared by me, and that I am a duly Licensed Professional Engineer under the laws of the State of Maryland, License No. 20748, Expiration Date 2-22-09.

OWNERS
 MARIO MANNARELLI, SR. & SERAFINA MANNARELLI,
 RAYMOND MANNARELLI & MARIO MANNARELLI, JR.
 2929 SUMMIT CIRCLE
 ELICOTT CITY, MARYLAND 21043
 (410) 461-2278

DEVELOPER
 HERITAGE LAND DEVELOPMENT, INC.
 15950 NORTH AVE.
 P.O. BOX 482
 LISBON, MD. 21765
 (410) 489-7900

**OLD FREDERICK ROAD CROSS-SECTIONS
 PHEASANT RUN EAST**
 LOTS 1 THRU 14, CEMETERY OPEN SPACE LOT 15,
 BUILDABLE PRESERVATION PARCEL "A" &
 NON-PRESERVATION PARCELS "B" THRU "D"
 ZONED "RC-DE0"
 TAX MAP No. 3, GRID No. 19, PARCEL No. 29
 FOURTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND
 DATE: SEPTEMBER, 2008
 SHEET 4 OF 19

FISHER, COLLINS & CARTER, INC.
 CIVIL ENGINEERING, CONSULTANTS & LAND SURVEYORS
 CENTENNIAL SQUARE OFFICE PARK • 10272 BALTIMORE NATIONAL FREE
 ELICOTT CITY, MARYLAND 21042
 (410) 461-2855

TEMPORARY SEDIMENT BASIN No. 2
 INITIAL D.A. = 5.60 Ac.±
 FINAL D.A. = 11.20 Ac.±
 STORAGE REQUIRED
 WET = 1800 x 11.20 = 20,160 CuFt.
 DRY = 1800 x 11.20 = 20,160 CuFt.
 STORAGE PROVIDED
 WET = 20,160 CuFt. @ ELEV. = 581.23
 DRY = 20,160 CuFt. @ ELEV. = 582.55
 BOTTOM ELEV. = 579.00
 STORAGE DEPTH = 7.50'
 TOP OF EMBANKMENT = 587.00
 CLEAN OUT ELEV. = 580.26
 RISER CREST ELEV. = 585.10
 1 YR. ORIFICE INV. = 579.00
 01 exist = 1.03 c.f.s.
 01 prop. = 0.28 c.f.s.
 WEIR CREST ELEV. = 583.30
 BOTTOM L x W = 153' x 45'

NOTE: CONTRACTOR TO ONLY DISTURB THE LENGTH OF WIDENING AND DITCH ALONG OLD FREDERICK ROAD THAT CAN AND SHALL BE STABILIZED BY THE END OF EACH DAY.



NOTE: CONTRACTOR TO ONLY DISTURB THE LENGTH OF WIDENING AND DITCH ALONG OLD FREDERICK ROAD THAT CAN AND SHALL BE STABILIZED BY THE END OF EACH DAY.

Professional Engineer Seal for ALDO M. [Signature] dated 9/23/08.

FISHER, COLLINS & CARTER, INC.
 CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS
 CENTRAL SQUARE OFFICE PARK - 1672 BALTIMORE NATIONAL PIKE
 ELLSWORTH CITY, MARYLAND 21042
 410.661.2955

STREET TREE SCHEDULE

SYMBOL	QTY.	BOTANICAL AND COMMON NAME	SIZE	COMMENTS
(Symbol)	1232.69 x 2 / 40 = 61.63 62 TREES	PRUNUS SARGENTII SARGENT CHERRY	2 1/2" - 3" CAL.	40' APART ON PUBLIC R/W

NOTE: STREET TREE TYPES ARE ONLY A RECOMMENDATION AND MAY BE SUBSTITUTED WITH A COUNTY ACCEPTED EQUIVALENT FROM THE HOWARD COUNTY LANDSCAPE MANUAL. FINANCIAL SURETY FOR THE 62 REQUIRED STREET TREES HAS BEEN POSTED AS PART OF THE DEVELOPER'S AGREEMENT IN THE AMOUNT OF \$18,600.00

BAFFLE DESIGN
 D=45'
 A=26,492 SQ. FT.
 We=A/D=26,492/45=588.71'
 Le=L/286'
 Le/We=1286/588.71=2.18
 S OK
 L1=200' L5=150'
 L2=202' L6=148'
 L3=190' L7=118'
 L4=178' L8=110'
 TOTAL Le=1286'
 NOTE: SEE SHEET 18 FOR BAFFLE DETAIL

- LEGEND**
- SSF-SSF-SSF SUPER-SILT FENCE
 - SF-SF-SF SILT FENCE
 - TP-TP-TP TREE PROTECTION FENCE
 - S.C.E. STABILIZED CONSTRUCTION ENTRANCE
 - L.O.D. DENOTES LIMITS OF DISTURBANCE
 - E.C.M. DENOTES EROSION CONTROL MATTING
 - (Hatched Box) DENOTES PUBLIC STORMWATER MANAGEMENT CREDIT EASEMENT
 - (Cross-hatched Box) DENOTES SLOPES 25% OR GREATER
 - (Dotted Box) DENOTES SLOPES 15% TO 24.99%

NOTE:
 CONTRACTOR SHALL REMOVE ANY AND ALL JUNK, DEBRIS AND TRASH FROM WITHIN THE FLOODPLAIN, BUFFERS AND PRESERVATION PARCELS.

By The Developer:
 I/We Certify That All Development And/Or Construction Will Be Done According To These Plans, And That Any Responsible Personnel Involved In The Construction Project Will Have A Certificate Of Attendance At A Department Of The Environment Approved Training Program For The Control Of Sediment And Erosion Before Beginning The Project. I Shall Engage A Registered Professional Engineer To Supervise Pond Construction And Provide The Howard Soil Conservation District With An "As-Built" Plan Of The Pond Within 30 Days Of Completion. I Also Authorize Periodic On-Site Inspections By The Howard Soil Conservation District.

Signature Of Developer: [Signature] 9/24/08
 Printed Name Of Developer: Timothy W. Feaga

By The Engineer:
 I Certify That This Plan For Pond Construction, Erosion And Sediment Control Represents A Practical And Feasible Design Based On My Personal Knowledge Of The Site Conditions. This Plan Was Prepared In Accordance With The Requirements Of The Howard Soil Conservation District. I Have Not Observed That He/She Must Engage A Registered Professional Engineer To Supervise Pond Construction And Provide The Howard Soil Conservation District With An "As-Built" Plan Of The Pond Within 30 Days Of Completion.

Signature Of Engineer: [Signature] 9/23/08
 Printed Name Of Engineer: [Name]

These Plans For Small Pond Construction, Soil Erosion And Sediment Control Meet The Requirements Of The Howard Soil Conservation District.
 Approved: [Signature] 10/7/08
 Chief, Department Of Public Works

Approved: [Signature] 10-9-08
 Chief, Bureau Of Highways


Approved: [Signature] 10/29/08
 Chief, Division Of Land Development

Approved: [Signature] 10/16/08
 Chief, Development Engineering Division

AS-BUILT CERTIFICATION
 I Herby Certify That The Facility Shown On This Plan Was Constructed As Shown On The "As-Built" Plans And Meets The Approved Plans And Specifications.

Signature: _____ P.E. No. _____
 Date: _____

Certify Means To State Or Declare A Professional Opinion Based Upon Onsite Inspections And Material Tests Which Are Conducted During Construction. The Onsite Inspections And Material Tests Are Those Inspections And Tests Deemed Sufficient And Appropriate Commonly Accepted Engineering Standards. Certify Does Not Mean Or Imply A Guarantee By The Engineer Nor Does An Engineer's Certification Relieve Any Other Party From Meeting Requirements Imposed By Contract, Employment, Or Other Means, Including Meeting Commonly Accepted Industry Practices.



NOTE: SEE SHEET 9 FOR STORMWATER MANAGEMENT SUMMARY TABLES

PLAN
 SCALE: 1" = 50'


FINAL GRADING PLAN - BMP No. 2
 SCALE: 1" = 50'

OWNERS
 MARIO MANNARELLI, SR. & SERAFINA MANNARELLI,
 RAYMOND MANNARELLI & MARIO MANNARELLI, JR.
 2929 SUMMIT CIRCLE
 ELLICOTT CITY, MARYLAND 21043
 (410) 461-2278

DEVELOPER
 HERITAGE LAND DEVELOPMENT, INC.
 15950 NORTH AVE.
 P.O. BOX 482
 LISBON, MD. 21765
 (410) 489-7900

STREET TREE, GRADING & SEDIMENT CONTROL PLAN
PHEASANT RUN EAST
 LOTS 1 THRU 14, CEMETERY OPEN SPACE LOT 15,
 BUILDABLE PRESERVATION PARCEL "A" &
 NON-PRESERVATION PARCELS "B" THRU "D"

ZONED "RC-050"
 TAX MAP No. 3, GRID No. 19, PARCEL No. 29
 FOURTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND
 DATE: SEPTEMBER, 2008
 SHEET 6 OF 19



By The Developer:
 "I/We Certify That All Development And/Or Construction Will Be Done According To These Plans, And That Any Responsible Personnel Involved In The Construction Project Will Have A Certificate Of Attendance At A Department Of The Environment Approved Training Program For The Control Of Sediment And Erosion Before Beginning The Project. I Shall Engage A Registered Professional Engineer To Supervise Pond Construction And Provide The Howard Soil Conservation District With An "As-Built" Plan Of The Pond Within 30 Days Of Completion. I Also Authorize Periodic On-Site Inspections By The Howard Soil Conservation District."

Signature Of Developer: *[Signature]* Date: 9/24/08
 Printed Name Of Developer: Timothy W Feaga

By The Engineer:
 "I Certify That These Plans For Pond Construction, Erosion And Sediment Control Represents A Practical Based On My Personal Knowledge Of The Site Conditions. This Plan Was Prepared In Accordance With The Requirements Of The Howard Soil Conservation District. I Have Reviewed The Plans And I Certify That He/She Must Engage A Registered Professional Engineer To Supervise Pond Construction And Provide The Howard Soil Conservation District With An "As-Built" Plan Of The Pond Within 30 Days Of Completion."

Signature: *[Signature]* Date: 9/23/08
 Printed Name Of Engineer: A. J. M. [Signature]

These Plans For Small Pond Construction, Soil Erosion And Sediment Control Meet The Requirements Of The Howard Soil Conservation District.

Signature: *[Signature]* Date: 10/7/08
 Approved: Department Of Public Works

Signature: *[Signature]* Date: 10-9-08
 Chief Bureau Of Highways

Signature: *[Signature]* Date: 10/29/08
 Approved: Department Of Planning And Zoning

Signature: *[Signature]* Date: 10/14/08
 Chief, Development Engineering Division

AS-BUILT CERTIFICATION
 I Herby Certify That The Facility Shown On This Plan Was Constructed As Shown On The "As-Built" Plans And Meets The Approved Plans And Specifications.

Signature: _____ P.E. No. _____
 Date: _____

Certify Means To State Or Declare A Professional Opinion Based Upon Onsite Inspections And Material Tests Which Are Conducted During Construction. The Onsite Inspections And Material Tests Are Those Inspections And Tests Deemed Sufficient And Appropriate Commonly Accepted Engineering Standards. Certify Does Not Mean Or Imply A Guarantee By The Engineer Nor Does An Engineer's Certification Relieve Any Other Party From Meeting Requirements Imposed By Contract, Employment, Or Other Means, Including Meeting Commonly Accepted Industry Practices.

- LEGEND**
- SS—SS—SS— SUPER-SILT FENCE
 - SF—SF—SF— SILT FENCE
 - TP—TP—TP— TREE PROTECTION FENCE
 - [Symbol] S.C.E. STABILIZED CONSTRUCTION ENTRANCE
 - [Symbol] EARTH DIKE
 - L.O.D.— DENOTES LIMITS OF DISTURBANCE
 - [Symbol] E.C.M. DENOTES EROSION CONTROL MATTING
 - [Symbol] DENOTES PUBLIC STORMWATER MANAGEMENT CREDIT EASEMENT
 - [Symbol] DENOTES SLOPES 25% OR GREATER
 - [Symbol] DENOTES SLOPES 15% TO 24.99%

NOTE:
 CONTRACTOR SHALL REMOVE ANY AND ALL JUNK, DEBRIS AND TRASH FROM WITHIN THE FLOODPLAIN, BUFFERS AND PRESERVATION PARCELS.

TEMPORARY SEDIMENT BASIN No. 1
 INITIAL D.A. = 11.32 Ac.±
 FINAL D.A. = 15.57 Ac.±
 STORAGE REQUIRED
 WET = 1800 x 15.57 = 28,026 CuFt.
 DRY = 1800 x 15.57 = 28,026 CuFt.
 STORAGE PROVIDED
 WET = 28,026 CuFt. @ ELEV. = 565.10
 DRY = 28,026 CuFt. @ ELEV. = 566.63
 STORAGE DEPTH = 8.0'
 TOP OF EMBANKMENT = 569.00
 CLEAN OUT ELEV. = 563.50
 RISER CREST ELEV. = 568.20
 1" R. ORIFICE INV. = 561.00
 Q1 exist. = 1.1 c.f.s.
 Q1 prop. = 0.8 c.f.s.
 NEIR CREST ELEV. = 565.75
 BOTTOM L x W = 180' x 130'

NOTE: SEE SHEET 8 FOR STORMWATER MANAGEMENT SUMMARY TABLES

MATCH LINE SEE SHEET 6
PLAN
 SCALE: 1" = 50'

BAFFLE DESIGN
 D=66' L1=70'
 A=8,831 SQ. FT. L2=82'
 W=4'D=8831/66=133.80 L3=70'
 L=272' L4=50'
 Le/W=272/133.80=2.03 TOTAL Le=272'
 >2 IS OK
 NOTE: SEE SHEET 18 FOR BAFFLE DETAIL



FISHER, COLLINS & CARTER, INC.
 CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS
 CENTRAL SQUARE OFFICE PARK - 10272 BALTORE NATIONAL PIKE
 ELLICOTT CITY, MARYLAND 21042
 (410) 461-2995

OWNERS
 MARIO MANNARELLI, SR. & SERAFINA MANNARELLI,
 RAYMOND MANNARELLI & MARIO MANNARELLI, JR.,
 2928 SUMMIT CIRCLE
 ELLICOTT CITY, MARYLAND 21043
 (410) 461-2278

DEVELOPER
 HERITAGE LAND DEVELOPMENT, INC.
 15950 NORTH AVE.
 P.O. BOX 482
 LISBON, MD. 21765
 (410) 489-7900

STREET TREE, GRADING & SEDIMENT CONTROL PLAN
PHEASANT RUN EAST
 LOTS 1 THRU 14, CEMETERY OPEN SPACE LOT 15,
 BUILDABLE PRESERVATION PARCELS "A" &
 NON-PRESERVATION PARCELS "B" THRU "D"
 ZONED "RC-DEO"
 TAX MAP No. 3, GRID No. 19, PARCEL No. 29
 FOURTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND
 DATE: SEPTEMBER, 2008
 SHEET 7 OF 13

PHEASANT RUN EAST

SUMMARY TABLE #1

The following is a summary of the peak discharges from each of the drainage areas and study points.

Existing Condition	One-Year Storm (cfs)	Two-Year Storm (cfs)
1 to BMP#2	2.23	23.84
2 to BMP#1	11.75	173.55
3	0.85	9.75
5	0.25	4.50

Proposed Condition - with & without credit areas

Study Point	One-Year Storm (cfs)	Two-Year Storm (cfs)
1 (to BMP#2)	In: 4.94; Credit: 2.16 Out: 0.02	In: 39.87; Credit: 14.83 Out: 0.40
1B - Bypass Area	In: 1.18; Credit: 1.98 Out: 0.80	In: 8.20; Credit: 7.38 Out: 0.82
2A (to BMP #1)	In: 3.70; Credit: 3.18 Out: 0.52	In: 28.97 Out: 21.64
2B - Bypass Area	In: 19.15; Credit: 5.31 Out: 5.33	In: 40.11; Credit: 51.25 Out: 5.33
3	In: 0.25; No Credit	In: 11.01; No Credit
5	In: 0.50; No Credit	In: 5.02; No Credit

U - Unmanaged Q.
M - Managed Q.

Allowable Release Rates:


@ BMP Facility #2: 2.23 cfs for the CPv or 1-year storm to Study Point #1

@ BMP Facility #1: 11.75 cfs for the CPv or 1-year storm to Study Point #2

Proposed Release Rates:

@ BMP Facility #2: Q1 = 0.02 c.f.s. + Bypass Area of 1.98 = 2.00 c.f.s., therefore OK!! To Design Point #1.

@ BMP Facility #1: Q1 = 0.06 c.f.s. + Bypass Area of 5.31 = 5.33 c.f.s., > 11.75 therefore OK!! To Design Point #2.



PLAN
SCALE: 1" = 50'
MATCH LINE SEE SHEET 7


SUMMARY TABLE #2

The following is a summary of the Recharge, WQ, and CPv Requirements:

Type of Requirement	Volume Required	Volume Provided & Notes
Recharge (Recharge Vol. for Site)	1.04 acres % Area or 0.14 acre-feet % Volume	2.3 acres w/ % Area Method
WQ _{out}		
Study Point #1 - BMP#2	0.11 Ac. Ft.; Credit = 0.09 Ac. Ft.	0.09 Ac. Ft. @ BMP Facility #2
Study Point #2 - BMP#1	0.24 Ac. Ft.; Credit = 0.18 Ac. Ft.	0.18 Ac. Ft. @ BMP Facility #1
Study Point #3	0.17 Ac. Ft.; No Credit	0.05 Ac. Ft. @ Slope Disconnection
Study Point #5	N/A - no proposed disturbance located within this area.	N/A - no proposed disturbance located within this area.
CP _v		
Study Point #1 - BMP#2	0.2116 Ac. Ft.; Credit = 0.12 Ac. Ft.	0.12 Ac. Ft. @ BMP Facility #2
Study Point #2 - BMP#1	0.25 Ac. Ft.; Credit = 0.21 Ac. Ft.	0.21 Ac. Ft. @ BMP Facility #1
Study Point #3	N/A; Q < 2.0 c.f.s. @ 0.50 c.f.s.	N/A; Q < 2.0 c.f.s. @ 0.50 c.f.s.
Study Point #5	N/A; Q < 2.0 c.f.s. @ 0.50 c.f.s.	N/A; Q < 2.0 c.f.s. @ 0.50 c.f.s.

LEVEL SPREADER CRITERIA

For impervious surface runoff applications: The capacity for the level spreader is determined in the design of the filter strip to which it discharges. The spreader shall run linearly along the entire width of the filter strip to which it discharges. In most cases, the spreader will be the width of the contributing impervious surface. The ends of the spreader shall be tied into slope ground to prevent flow around the spreader. The minimum depth shall be 6 inches and the minimum width shall be 6 feet for the level spreader. Side slopes shall be 2:1 (horizontal to vertical) or flatter. The grade of the spreader shall be 0%. The outlet discharge area must be generally smooth and well vegetated with a minimum slope of 0%. For all applications: The spreader lip shall be constructed to a uniform height and zero grade over the length of the spreader. For depths of 4 feet or greater, a rigid lip of non-erodible material, such as pressure-treated timbers or concrete curbing, shall be used. For less than 4 feet, a vegetated lip may be used. The spreader lip shall be constructed on undisturbed soil. When using a vegetated lip, it shall be protected with an erosion control blanket to prevent erosion and allow the vegetation to become established. The blanket shall be a minimum of 4 feet wide extending a minimum of 1 foot downstream over the level lip. The blanket shall be secured with heavy-duty staples and the downstream and upstream edges shall be buried at least 6 inches deep in a vertical trench. When using a rigid lip it shall be entrenched at least 4 inches below existing ground and securely anchored to prevent displacement. An apron of Class 1 rip-rap shall be placed to the top of the rigid lip and extend downstream at least 3 feet. A filter fabric shall be placed under the coarse aggregate. Immediately after level spreader construction, seed and mulch the entire disturbed area of the spreader in accordance with the Standards and Specifications for Vegetative Stabilization. CONSIDERATIONS: The level spreader is a relatively low-cost structure to: 1. Disperse impervious surface runoff uniformly to a filter strip or 2. Release small volumes of concentrated flow from overland when conditions are suitable. To accomplish these purposes, particular care must be taken to construct the spreader lip completely level. Any depression in the lip will concentrate the flow, resulting in a loss of pollutant filtering effectiveness and/or erosion. Evaluate the outlet system to be sure that flow does not concentrate below the outlet.



AS-BUILT CERTIFICATION

I hereby certify that the Facility Shown On This Plan Was Constructed As Shown On The "As-Built" Plans And Meets The Approved Plans And Specifications.

Signature _____ P.E. No. _____
Date: _____

Certify Means To State Or Declare A Professional Opinion Based Upon Onsite Inspections And Material Tests Which Are Conducted During Construction. The Onsite Inspections And Material Tests Are Those Inspections And Tests Deemed Sufficient And Appropriate Commonly Accepted Engineering Standards. Certify Does Not Mean Or Imply A Guarantee By The Engineer Nor Does An Engineer's Certification Relieve Any Other Party From Meeting Requirements Imposed By Contract, Employment, Or Other Means, Including Meeting Commonly Accepted Industry Practices.

LEGEND

- SSF-SSF-SSF SUPER-SILT FENCE
- SF-SF-SF SILT FENCE
- TP-TP-TP TREE PROTECTION FENCE
- S.C.E. STABILIZED CONSTRUCTION ENTRANCE
- EARTH DIKE
- L.O.D. DENOTES LIMITS OF DISTURBANCE
- E.C.M. DENOTES EROSION CONTROL MATTING
- DENOTES PUBLIC STORMWATER MANAGEMENT CREDIT EASEMENT
- DENOTES SLOPES 25% OR GREATER
- DENOTES SLOPES 15% TO 24.99%

NOTE:
CONTRACTOR SHALL REMOVE ANY AND ALL JUNK, DEBRIS AND TRASH FROM WITHIN THE FLOODPLAIN, BUFFERS AND PRESERVATION PARCELS.

GRADING & SEDIMENT CONTROL PLAN
PHEASANT RUN EAST
LOTS 1 THRU 14, CEMETERY OPEN SPACE LOT 15,
BUILDABLE PRESERVATION PARCEL "A" &
NON-PRESERVATION PARCELS "B" THRU "D"

OWNERS
MARIO MANNARELLI, SR. & SERAFINA MANNARELLI,
RAYMOND MANNARELLI & MARIO MANNARELLI, JR.
2929 SUMMIT CIRCLE
ELLCOTT CITY, MARYLAND 21043
(410) 481-2278

DEVELOPER
HERITAGE LAND DEVELOPMENT, INC.
15950 NORTH AVE.
P.O. BOX 482
LISBON, MD. 21765
(410) 489-7900

TAX MAP No. 3, GRID No. 19, PARCEL No. 29
FOURTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND
DATE: SEPTEMBER, 2008
SHEET 8 OF 19

By The Developer:
I/We Certify That All Development And/Or Construction Will Be Done According To These Plans, And That Any Responsible Personnel Involved In The Construction Project Will Have A Certificate Of Attendance At A Department Of The Environment Approved Training Program For The Control Of Sediment And Erosion Before Beginning The Project. I Shall Engage A Registered Professional Engineer To Supervise Pond Construction And Provide The Howard Soil Conservation District With An "As-Built" Plan Of The Pond Within 30 Days Of Completion. I Also Authorize Periodic On-Site Inspections By The Howard Soil Conservation District.

Signature: *T. W. Feag* Date: **7/24/08**
Printed Name Of Developer: **Timothy W. Feag**

By The Engineer:
I Certify That This Plan For Pond Construction, Erosion And Sediment Control Represents A Practiced Design Plan Based On My Personal Knowledge Of The Site Conditions. This Plan Was Prepared In Accordance With The Requirements Of The Howard Soil Conservation District. I Have Reviewed The Plans And I Certify That The Plans Must Engage A Registered Professional Engineer To Supervise Pond Construction And Provide The Howard Soil Conservation District With An "As-Built" Plan Of The Pond Within 30 Days Of Completion.

Signature: *Alvin J. ...* Date: **9-23-09**
Printed Name Of Engineer: **Alvin J. ...**

These Plans For Small Pond Construction, Soil Erosion And Sediment Control Meet The Requirements Of The Howard Soil Conservation District.

Signature: *Jeff ...* Date: **10/7/08**
Howard Soil Conservation District

Approved: Department Of Public Works
Signature: *William R. ...* Date: **10-9-08**
Chief, Bureau Of Highways


Approved: Department Of Planning And Zoning
Signature: *Candy ...* Date: **10/20/08**
Chief, Division Of Land Development

Signature: *John ...* Date: **10/16/08**
Chief, Development Engineering Division


FISHER, COLLINS & CARTER, INC.
CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS
CENTRAL SQUARE OFFICE PARK - 10725 BALDWIN NATIONAL PIKE
ELLCOTT CITY, MARYLAND 21043
(410) 481-2895




DATE: **9-23-08**
Professional Engineer under the laws of the State of Maryland, License No. 20748, Expiration Date 2-22-09.




**S.W.M. FACILITY B.M.P. NO. 1
PROFILE ALONG EMBANKMENT**
SCALE: HORIZ. 1" = 30'
VERT. 1" = 3'




SECTION THRU FOREBAY
SCALE: HOR. 1" = 30'
VER. 1" = 3'




SC5 TR-46 A2 CRADLE
NO SCALE




**S.W.M. FACILITY B.M.P. NO. 1
PRINCIPLE SPILLWAY PROFILE**
SCALE: HOR. 1" = 30'
VER. 1" = 3'



GABION FOREBAY PROFILE
SCALE: HORIZ. 1" = 30'
VERT. 1" = 3'



PROFILE VIEW A
SCALE: 1" = 2'




TOP SLAB DETAIL
NO SCALE


TRASH RACK 'A'

**2nd STAGE WEIR TRASH RACK
TRASH RACK DETAIL**
NO SCALE

TYPICAL SECTION THROUGH BARREL, CRADLE AND ANTI-SEEP COLLAR




ANTI-SEEP COLLAR REBAR PLACEMENT
NO SCALE



EXPANDED METAL TRASH RACK
NOT TO SCALE

ANTI-SEEP COLLAR
NO SCALE



**PROFILE VIEW B
CONCRETE RISER DETAIL**
SCALE: 1" = 2'

**STORMWATER MANAGEMENT FACILITY B.M.P. No. 1 DETAILS
PHEASANT RUN EAST**

**LOTS 1 THRU 14, CEMETERY OPEN SPACE LOT 15,
BUILDABLE PRESERVATION PARCEL "A" &
NON-PRESERVATION PARCELS "B" THRU "D"**
ZONED "RC-100"
TAX MAP No. 3, GRID No. 19, PARCEL No. 29
FOURTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND
DATE: SEPTEMBER, 2008
SHEET 11 OF 19

By The Developer:
"I/We Certify That All Development And/Or Construction Will Be Done According To These Plans. And That Any Responsible Personnel Involved In The Construction Project Will Have A Certificate Of Attendance At A Department Of Environment Approved Training Program For The Control Of Sediment And Erosion Before Beginning The Project. I Shall Engage A Registered Professional Engineer To Supervise Pond Construction And Provide The Howard Soil Conservation District With An "As-Built" Plan Of The Pond Within 30 Days Of Completion. I Also Authorize Periodic On-Site Inspections By The Howard Soil Conservation District."
Signature Of Developer: *Timothy W. Feaga* 9/24/08
Printed Name Of Developer: Timothy W. Feaga
By The Engineer:
"I Certify That This Plan For Pond Construction, Erosion And Sediment Control Represents A Practical And Feasible Plan Based On My Personal Knowledge Of The Site Conditions. This Plan Was Prepared In Accordance With The Requirements Of The Howard Soil Conservation District. I Have Not Observed Any Conditions That Would Require A Registered Professional Engineer To Supervise Pond Construction And Provide The Howard Soil Conservation District With An "As-Built" Plan Of The Pond Within 30 Days Of Completion."
Signature: *[Signature]* 9/23/08
Printed Name Of Engineer: [Name]
These Plans For Small Pond Construction, Soil Erosion And Sediment Control Meet The Requirements Of The Howard Soil Conservation District.
Signature: *[Signature]* 10/7/08
Printed Name Of Engineer: [Name]
Howard Soil Conservation District
Approved: Department Of Public Works
Signature: *[Signature]* 10-9-08
Printed Name Of Engineer: [Name]
Chief, Bureau Of Highways
Approved: Department Of Planning And Zoning
Signature: *[Signature]* 10/24/08
Printed Name Of Engineer: [Name]
Chief, Division Of Land Development
Signature: *[Signature]* 10/16/08
Printed Name Of Engineer: [Name]
Chief, Development Engineering Division

AS-BUILT CERTIFICATION
I Herby Certify That The Facility Shown On This Plan Was Constructed As Shown On The "As-Built" Plans And Meets The Approved Plans And Specifications.
Signature: _____ P.E. No. _____
Date: _____
Certify Means To State Or Declare A Professional Opinion Based Upon On-site Inspections And Material Tests Which are Conducted During Construction. The On-site Inspections And Material Tests are Those Inspections And Tests Deemed Sufficient And Appropriate Commonly Accepted Engineering Standards. Certify Does Not Mean Or Imply A Guarantee By The Engineer Nor Does An Engineer's Certification Relieve Any Other Party From Meeting Requirements Imposed by Contract, Employment, Or Other Means, Including Meeting Commonly Accepted Industry Practices.







- NOTES:
1. CONCRETE SHALL BE MSHA MIX NO. 3 (FC > 3500 P.S.I.)
 2. REINFORCING STEEL: GRADE 60
 3. FOR WALLS OF STRUCTURE SHALL UTILIZE L.M. SCOFIELD CO. T-9055 FORM LINERS (RANDOM SPLIT-FACE ROCK) OPTIONAL.
 4. PROVIDE ROUGH BROOM FINISH.
 5. ANCHOR BOLTS SHALL BE INSTALLED IN ACCORDANCE WITH SECTION 6.07.03.59 OF THE MSHA STANDARDS AND SPECS.
 6. ALL REINFORCING SPLICES SHALL BE LAP SPLICES OF 30 BAR DIA. UNLESS OTHERWISE SHOWN.

FISHER, COLLINS & CARTER, INC.
CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS
CENTRAL SQUARE OFFICE PARK - 10722 BALTIMORE NATIONAL PIKE
ELLICOTT CITY, MARYLAND 21114
4100 461 - 2895

Professional Engineer's Seal
ALDO M. [Signature]
Professional Engineer
I hereby certify that these documents were prepared by me, and that I am a duly Licensed Professional Engineer under the laws of the State of Maryland, License No. 20748, Expiration Date 2-22-09.
DATE: 9/23/08

OWNERS
MARIO MANNARELLI, SR. & SERAFINA MANNARELLI,
RAYMOND MANNARELLI & MARIO MANNARELLI, JR.
2929 SUMMIT CIRCLE
ELLICOTT CITY, MARYLAND 21143
(410) 461-2270

DEVELOPER
HERITAGE LAND DEVELOPMENT, INC.
15950 NORTH AVE.
P.O. BOX 482
LISBON, MD. 21765
(410) 469-7900



By The Developer:
 Signature of Developer: *Timothy W. Feaga*
 Printed Name of Developer: **Timothy W. Feaga**
 Date: **9/24/08**

By The Engineer:
 Signature: *[Signature]*
 Printed Name of Engineer: **[Name]**
 Date: **9/23/08**


These Plans For Small Pond Construction, Soil Erosion And Sediment Control Meet The Requirements Of The Howard Soil Conservation District.
 Approved: Department of Public Works
 Chief Bureau Of Highways
 Date: **10/7/08**

Approved: Department Of Planning And Zoning
 Chief, Division Of Land Development
 Date: **10/24/08**

Chief, Development Engineering Division
 Date: **10/16/08**

I Herby Certify That The Facility Shown On This Plan Was Constructed As Shown On The "As-Built" Plans And Meets The Approved Plans And Specifications.
 Signature: _____ P.E. No. _____
 Date: _____

Certify Means To State Or Declare A Professional Opinion Based Upon Onsite Inspections And Material Tests Which Are Conducted During Construction. The Onsite Inspections And Material Tests Are Those Inspections And Tests Deemed Sufficient And Appropriate Commonly Accepted Engineering Standards. Certify Does Not Mean Or Imply A Guarantee By The Engineer Nor Does An Engineer's Certification Relieve Any Other Party From Meeting Requirements Imposed By Contract, Employment, Or Other Means, Including Meeting Commonly Accepted Industry Practices.



STORMWATER MANAGEMENT FACILITY B.M.P. No. 2 DETAILS PHEASANT RUN EAST
 LOTS 1 THRU 14, CEMETERY OPEN SPACE LOT 15, BUILDABLE PRESERVATION PARCEL "A" & NON-PRESERVATION PARCELS "B" THRU "D"

OWNERS
 MARIO MANNARELLI, SE & SERAFINA MANNARELLI,
 RAYMOND MANNARELLI & MARIO MANNARELLI, JR.
 2929 SUMMIT CIRCLE
 ELLICOTT CITY, MARYLAND 21043
 (410) 481-2278

DEVELOPER
 HERITAGE LAND DEVELOPMENT, INC.
 13250 NORTH AVE.
 P.O. BOX 482
 USDBO, MD. 21765
 (410) 489-7900

TAX MAP No. 3, GRID No. 19, PARCEL No. 29
 FOURTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND
 DATE: SEPTEMBER, 2008
 SHEET 12 OF 19

FISHER, COLLINS & CARTER, INC.
 CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS
 CENTRAL SQUARE OFFICE PARK, 10275 BALTIMORE NATIONAL PARK
 ELLICOTT CITY, MARYLAND 21042
 (410) 481-2855



ALDO M. [Name]
 DATE: **9/23/08**
 I, the undersigned, hereby certify that these documents were prepared by me, and that I am a duly Licensed Professional Engineer under the laws of the State of Maryland, License No. 20748, Expiration Date 2-22-09.

STORM WATER MANAGEMENT POND CONSTRUCTION SPECIFICATIONS

These specifications are appropriate to all ponds within the scope of the Standard Practice M-370. All references to ASTM and AASHTO specifications apply to the most recent version.

Site Preparation

Areas designated for borrow areas, embankment, and structural works shall be cleared, grubbed and stripped of topsoil. All trees, vegetation, roots and other objectionable material shall be removed. Channel banks and shrub breaks shall be cleared to no steeper than 1:1. All trees shall be cleared and grubbed within 15 feet of the toe of the embankment.

Areas to be covered by the reservoir will be cleared of all trees, brush, logs, fences, rubbish and other objectionable material unless otherwise designated on the plans. Trees, brush, and stumps shall be cut approximately level with the ground surface. For dry stormwater management ponds, a minimum of a 25-foot radius around the inlet structure shall be cleared.

All cleared and grubbed material shall be disposed of outside and below the limits of the dam and reservoir as directed by the owner or his representative. When specified, a sufficient quantity of topsoil will be stockpiled in a suitable location for use on the embankment and other designated areas.

EARTH FILL

Material - The fill material shall be taken from approved designated borrow areas. It shall be free of roots, stumps, wood, rubbish, stones greater than 6", frozen or other objectionable materials. Fill material for the center of the embankment and cut off trench shall conform to Unified Soil Classification G, SC, CH, or CL and must have at least 30% passing the #200 sieve. Consideration may be given to the use of other materials if approved in writing by the engineer. Special designating material shall have construction supervised by a geotechnical engineer. Materials used in the outer shell of the embankment must have the capability to support vegetation of the quality required to prevent erosion of the embankment.

Placement - Areas on which fill is to be placed shall be scarified prior to placement of fill. Fill materials shall be placed in maximum 9-inch thick (before compaction) layers which are to be continuous over the entire length of the fill. The most permeable borrow material shall be placed in the downstream portions of the embankment. The principal spillway must be installed concurrently with fill placement and not excavated into the embankment.

Compaction - The movement of the hauling and spreading equipment over the fill shall be controlled so that the entire surface of each lift shall be traversed by not less than one track of heavy equipment or compaction shall be achieved by a minimum of four complete passes of a disc harrow, roller or vibratory roller. Fill material shall contain sufficient moisture such that the required degree of compaction will be obtained with the equipment used. The fill material shall contain sufficient moisture so that if it is dried by the sun it will not crumble, yet not be so wet that water can be squeezed out.

When required by the reviewing agency the minimum required density shall not be less than 95% of maximum dry density with a moisture content within +2% of the optimum. Each layer of fill shall be compacted as necessary to obtain that density and it to be certified by the contractor. The density of the embankment shall be determined by AASHTO Method T-99 (Standard Proctor).

Cut Off Trench - The cutoff trench shall be excavated into impervious material along or parallel to the centerline of the embankment as shown on the plans. The bottom width of the trench shall be governed by the equipment used for excavation with the minimum width being 4 feet. The depth shall be at least 4 feet below existing grade or as shown on the plans. The side slopes of the trench shall be 1 to 1 or flatter. The backfill shall be compacted with construction equipment, rollers, or hand tampers to assure maximum density and minimum permeability.

Embankment Core - The core shall be parallel to the centerline of the embankment as shown on the plans. The top width of the core shall be a minimum of four feet. The height shall extend up to at least the 10 year water elevation or as shown on the plans. The side slopes shall be 1 to 1 or flatter. The core shall be compacted with construction equipment, rollers or hand tampers to assure maximum density and minimum permeability. In addition, the core shall be placed concurrently with the outer shell of the embankment.

Structure Backfill

Backfill adjacent to pipes or structures shall be of the type and quality conforming to that specified for the adjoining fill material. The fill shall be placed in horizontal layers not to exceed four inches in thickness and compacted by hand tampers or other suitable directed compaction equipment. The material needs to fill completely all spaces under and adjacent to the pipe. At no time during the backfilling operation shall driven equipment be allowed to operate closer than four feet, measured horizontally, to any part of a structure. Under no circumstances shall equipment be driven over any part of a concrete structure or pipe, unless there is a compacted fill of 24" or greater over the structure or pipe.

Structure backfill may be flowable fill meeting the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 313 as modified. The mixture shall have a 100-200 psi 28 day unconfined compressive strength. The flowable fill shall have a minimum pH of 4.0 and a minimum resistivity of 2,000 ohm-cm. Material shall be placed such that a minimum of 6 inches of concrete, perpendicular to the outside of the pipe of flowable fill shall be under (bedding), over and on the sides of the pipe. It only needs to extend up to the spring line for rigid conduits. Average slump of the flowable fill shall be 7" to assure flowability of the material. Adequate measures shall be taken (sand bags, etc.) to prevent floating the pipe. When using flowable fill all metal pipe shall be bituminous coated. Any adjoining soil fill shall be placed in horizontal layers not to exceed four inches in thickness and compacted by hand tampers or other manually directed compaction equipment. The material shall completely fill all voids adjacent to the flowable fill zone. At no time during the backfilling operation shall driven equipment be allowed to operate closer than four feet, measured horizontally, to any part of a structure. Under no circumstances shall equipment be driven over any part of a structure or pipe unless there is a compacted fill of 24" or greater over the structure or pipe. Backfill material outside the structural backfill (flowable fill) zone shall be of the type and quality conforming to the specified for the core of the embankment or other embankment materials.

Pipe Conduits

All pipes shall be circular in cross section.

Corrugated Metal Pipe - All of the following criteria shall apply for corrugated metal pipe:

1. Materials - Polymer Coated Steel Pipe - Steel pipes with polymeric coatings shall have a minimum coating thickness of 0.01 inch (10 mil) on both sides of the pipe. This pipe and its appurtenances shall conform to the requirements of AASHTO Specifications M-245 & M-246 with watertight coating bands or flanges.

Materials - Aluminum Coated Steel Pipe - This pipe and its appurtenances shall conform to the requirements of AASHTO Specification M-274 with watertight coating bands or flanges. Aluminum Coated Steel Pipe - When used with flowable fill or when soil and/or water conditions warrant the need for increased durability, shall be fully bituminous coated per requirements of AASHTO Specification M-190 Type A. Any aluminum coating damaged or otherwise removed shall be replaced with cold applied bituminous coating compound. Aluminum surfaces that are to be in contact with concrete shall be painted with one coat of zinc chromate primer or two coats of asphalt. Hot dip galvanized bolts may be used for connections. The pH of the surrounding soils shall be between 4 and 9.

Materials - (Aluminum Pipe) - This pipe and its appurtenances shall conform to the requirements of AASHTO Specification M-190 or M-211 with watertight coating bands or flanges. Aluminum pipe, when used with flowable fill or when soil and/or water conditions warrant for increased durability, shall be fully bituminous coated per requirements of AASHTO Specification M-190 Type A. Aluminum surfaces that are to be in contact with concrete shall be painted with one coat of zinc chromate primer or two coats of asphalt. Hot dip galvanized bolts may be used for connections. The pH of the surrounding soils shall be between 4 and 9.

2. Coupling bands, anti-seep collars, and sections, etc., must be composed of the same material and coatings as the pipe. Metals must be insulated from dissimilar materials with use of rubber or plastic insulating materials at least 24 mils in thickness.

3. Connections - All connections with pipes must be completely watertight. The drain pipe or barrel connection to the riser shall be welded all around when the pipe and riser are metal. Anti-seep collars shall be connected to the pipe in such a manner as to be completely watertight. Dimple bands are not considered to be watertight.

All connections shall use a rubber or neoprene gasket when joining pipe sections. The end of each pipe shall be re-rolled an adequate number of rotations to accommodate the gasket. The following type connections are acceptable for pipes less than 24-inches in diameter: flanges on both ends of the pipe with a circular 3/8 inch closed cell neoprene gasket, pre-punched to the flange bolt circle, surrounded between adjacent 12-inch wide standard pipe type band with 12-inch wide 3/8-inch thick closed cell neoprene gasket; and a 12-inch wide hugger type band with oval gaskets having a minimum diameter of 12-inch greater than the corrugation depth. Pipes 24-inches in diameter and larger shall be connected by a 24-inch long annular corrugated band using a minimum of 4 (four) rods and lags, 2 on each connecting pipe end. A 24-inch wide by 3/8-inch thick closed cell neoprene gasket will be installed on the end of each pipe. Flanged joints with 3/8-inch closed cell gaskets the full width of the flange is also acceptable.

Helicly corrugated pipe shall have either continuously welded seams or have lock seams with interlock caulking or a neoprene bead.

4. Bedding - The pipe shall be firmly and uniformly bedded throughout its entire length. Where rock or soft, spongy or other unstable soil is encountered, all such material shall be removed and replaced with suitable earth compacted to provide adequate support.

5. Backfilling shall conform to "Structure Backfill".

6. Other details (anti-seep collars, valves, etc.) shall be as shown on the drawings.

Reinforced Concrete Pipe - All of the following criteria shall apply for reinforced concrete pipe:

1. Materials - Reinforced concrete pipe shall have bell and spigot joints with rubber gaskets and shall equal or exceed ASTM C-361.

2. Bedding - Reinforced concrete pipe conduits shall be laid in a concrete bedding/grade for their entire length. This bedding/grade shall consist of high slump concrete placed under the pipe and up the sides of the pipe at least 50% of its outside diameter with a minimum thickness of 6 inches. Where a concrete grade is not needed for structural reasons, flowable fill may be used as described in the "Structure Backfill" section of this standard. Gravel bedding is not permitted.

3. Laying pipe - Bell and spigot pipe shall be placed with the bell end upstream. Joints shall be made in accordance with recommendations of the manufacturer of the material. After the joints are sealed for the entire line, the bedding shall be placed so that all spaces under the pipe are filled. Care shall be exercised to prevent any deviation from the original line and grade of the pipe. The first joint must be located within 4 feet from the riser.

4. Backfilling shall conform to "Structure Backfill".

5. Other details (anti-seep collars, valves, etc.) shall be as shown on the drawings.

Plastic Pipe

The following criteria shall apply for plastic pipe:

1. Materials - PVC pipe shall be PVC-1120 or PVC-1220 conforming to ASTM D-775 or ASTM D-2241. Corrugated High Density Polyethylene (HDPE) pipe, couplings and fittings shall conform to the following: 4" - 10" inch pipe shall meet the requirement of AASHTO M252 Type S, and 12" through 24" inch shall meet the requirement of AASHTO M294 Type S.

2. Joints and connections to anti-seep collars shall be completely watertight.

3. Bedding - The pipe shall be firmly and uniformly bedded throughout its entire length. Where rock or soft, spongy or other unstable soil is encountered, all such material shall be removed and replaced with suitable earth compacted to provide adequate support.

4. Backfilling shall conform to "Structure Backfill".

5. Other details (anti-seep collars, valves, etc.) shall be as shown on the drawings.

Drainage Diaphragms - When a drainage diaphragm is used, a registered professional engineer will supervise the design and construction inspection.

Concrete

Concrete shall meet the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 404, PSC No. 3.

Rock Riprap

Rock riprap shall meet the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 311.

Geotextile shall be placed under all riprap and shall meet the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 921.09, Class C.

Care of Water during Construction

All work on permanent structures shall be carried out in areas free from water. The contractor shall construct and maintain all temporary dikes, levees, cofferdams, drainage channels, and stream diversions necessary to protect the areas to be occupied by the permanent works. The contractor shall also fish, install, operate, and maintain all necessary pumping and other equipment required for removal of water from various parts of the work and for maintaining the excavations, foundations and other parts of the work free from water as required or directed by the engineer for constructing each part of the work. After having served their purpose, all temporary protective works shall be removed or leveled and graded to the extent required to prevent obstruction in any degree whatsoever of the flow of water to the spillway or outlet works and so as not to interfere in any way with the operation or maintenance of the structure. Stream diversions shall be maintained until the full flow can be passed through the permanent works. The removal of water from the required excavation and the foundation shall be accomplished in a manner and to the extent that will maintain stability of the excavated slopes and bottom required excavations, and will allow satisfactory performance of all construction operations. During the placing and compacting of material in required excavations, the water level at the locations being refilled shall be maintained below the bottom of the excavation at such locations which may require draining the water sumps from which the water shall be pumped.

Stabilization


All borrow areas shall be graded to provide proper drainage and left in a sightly condition. All exposed surfaces of the embankment, spillway, spoil and borrow areas, and berms shall be stabilized by seeding, liming, fertilizing and mulching in accordance with the Natural Resources Conservation Service Standards and Specifications for Critical Area Planting M-3422, or as shown on the accompanying drawings.

Erosion and Sediment Control


Construction operations will be carried out in such a manner that erosion will be controlled and water and air pollution minimized. State and local laws concerning pollution abatement will be followed. Construction plans shall detail erosion and sediment control measures.

OPERATION AND MAINTENANCE

An operation and maintenance plan in accordance with local or State Regulations will be prepared for all ponds. As a minimum, the dam inspection checklist located in Appendix A shall be included as part of the operation and maintenance plan and performed at least annually. Written records of maintenance and major repairs shall be retained in a file. The issuance of a Maintenance and Repair Permit for any repairs or maintenance that involves the modification of the dam or spillway from its original design and specifications is required. A permit is also required for any repairs or reconstruction that involve a substantial portion of the structure. All indicated repairs are to be made as soon as practical.



TYPICAL METAL BOLLARD DETAIL
NOT TO SCALE (STD. G-7.42)



EXPANDED METAL TRASH RACK
NOT TO SCALE

- NOTES:
1. TRASH RACK TO BE CENTERED OVER OPENING.
 2. STEEL TO CONFORM TO ASTM A-36.
 3. ALL SURFACES TO BE COATED WITH ZINC COLD GALVANIZING CORROSION RESISTANT PAINTED BATTERED GREY.
 4. TRASH RACK TO BE FASTENED TO THE WALL WITH 1/2" MASONRY ANCHORS, TRASH RACK TO BE REMOVABLE.

OPERATION AND MAINTENANCE SCHEDULE FOR PRIVATELY OWNED AND JOINTLY MAINTAINED STORMWATER MANAGEMENT FACILITIES FOR BMP POND #1 & #2

ROUTINE MAINTENANCE

1. Facility shall be inspected annually and after major storms. Inspections shall be performed during wet weather to determine if the pond is functioning properly.
2. Top and side slopes of the embankment shall be mowed a minimum of two (2) times a year, once in June and once in September. Other side slopes and maintenance access should be mowed as needed.
3. Debris and litter shall be removed during regular mowing operations and as needed.
4. Visible signs of erosion in the pond as well as the rip-rap or gabion outlet area shall be repaired as soon as it is noticed.
5. The off-line storm drain (M-1 to CO-2) and underground reservoir shall be inspected annually and after major storms.

NON-ROUTINE MAINTENANCE

1. Structural components of the pond such as the dam, the riser, and the pipes shall be repaired upon the detection of any damage. The components shall be inspected during routine maintenance operations.
2. Sediment shall be removed from the pond and forebay, no later than when the capacity of the pond or forebay, is half full of sediment, or when deemed necessary for aesthetic reasons, upon approval from the Department of Public Works.

POND CONSTRUCTION RECOMMENDATIONS

A. General Design Recommendations

It is recommended that the geotechnical aspects of the pond design and construction be in accordance with MD 370-2000 Section 10.0.

B. Principal Spillway

From review of the preliminary plans, it appears that principal spillways would be located below basin grade at boring locations B-1, B-6, and between B-5 and B-6. Firm soils were encountered immediately below the topsoil in B-6; however, soils were looser below to a depth of 3 feet in B-1 and to 6 feet in B-5 and B-6. Depending upon basin cut depth, it may be necessary to undercut weak soils and replace with controlled compacted fill for adequate riser and outlet pipe support.

C. Earth Slope Stability

Given the soft to barely medium stiff and loose nature of the residual soils encountered in many of the borings, it is recommended that the cut and fill slopes be no steeper than 1:1 for slope stability. These soil types are highly susceptible to erosion and the slopes may require periodic maintenance until uniformly thick mature grass cover can be established. Also, ground water seepage from the base of the slopes may result in toe instability requiring the installation of drains or underdrains and replacing failed materials with more suitable soils or aggregate. The location and extent of drains and undercuts would best be determined at the time of construction.

D. Core Trench

The core trench may be excavated to the typical MD 370-2000 specified dimensions below striped existing grade or at least 2 feet into original soils below any undercut basins, whichever depth is greater. Given the relatively gradual gentle slopes downstream of the proposed pond areas, and the expected limited height of embankment, excessive seepage beneath the slope is not expected to be a problem in embankment stability with proper core trench construction.

A review of test boring results and laboratory data indicate that Unified "C" classification soils would be available in the approximate upper 3 feet of cut at boring B-2. It has been our experience in similar geologic areas, however, that the Unified "C" classification soils are of limited quality and have excessive moisture content. Consequently, it is expected that at least some off site borrow would be required for completion of core trench and dam core fill.

E. Permanent Ground Water Control

Groundwater would be a consideration for basins excavated near or below the indicated groundwater levels. Ground water control was addressed to some extent in the slope stability section. In addition to slope drains, it may be necessary to construct pilot channels in the basins to direct seepage into a low flow outflow to prevent shallow accumulation of water.

EARTHWORK CONSTRUCTION

Prior to placement of embankment fill, we recommend that the stripped surface from toe to toe of the embankment footprint be profiled and any exceptionally soft yielding areas undercut to expose firmer soils. Undercuts of 3 to 6 feet deep could be expected at six of the nine boring locations. Any undercut should extend at least 1 foot beyond each proposed toe of slope for every foot depth of undercut. Upon achieving an acceptable surface, the undercut should be backfilled with approved soils, placed and compacted in accordance with APPENDIX L, COMPACTED FILL. Undercut backfill soils should enclose Unified CR, CW, GP, or SW materials but need not be artificially impermeable since the core trench would be extended down through the fill after embankment under and backfilling is complete. Undercut backfill should have an AASHTO T-99 minimum compacted dry density of at least 100%. Examination of the moisture/compacted density relationship test results presented on SHEETS 1 through 3, COMPACTION TEST indicates that the tested proposed cut soils have acceptably high compacted maximum dry densities, but the existing moisture at the time of sampling were approximately 6 to 10 percent above the optimum for most efficient compaction. These soils types would be suitable for use as embankment or site development fill. Only the sample from B-2 would be of suitable classification for use as core trench fill with the existing moisture averaging 8 percent over optimum. The soils would require significant drying by aeration prior to use as controlled compacted fill. Given the limited area of a core trench for drying, it may be more feasible to bring in approved off-site clay borrow for core trench fill. Given the detailed soil moisture and clayey soil types near the surface, it is imperative that earthwork operations be performed during the normally warmer drier summer and early fall construction season when more intense sun and warmer temperatures will maximize drying capabilities. Churning, grubbing, and topsoil stripping operations during wet weather may mix topsoil into the wet surface clay soils resulting in deeper surface stripping. Construction during the cooler, water

seasons of the year may make these high moisture soils unavailable for use as controlled, compacted fill, frozen construction during the cooler, water seasons of the year may result in saturated or frozen substrates requiring undercut and replacement with more suitable materials. Normal soil excavation techniques will be sufficient for removal of materials encountered in the test borings with the exception of materials with standard penetration resistances exceeding 100 blows per foot. Depending upon type of excavation, ripping and/or rock removal techniques may be required in the equivalent 100 plus blow count area at the base of borings B-5 and B-6. Temporary ground water control will be required in excavations extended below indicated ground water levels. Residual soils, seepage rates are usually low, unless a fractured rock seam is encountered, and can be controlled by a series of pits, trenches and pumps during construction.

The Maryland Department of the Environment (MDE) requires that design storm water disposal by infiltration be considered only in undisturbed native soils with an infiltration rate of at least 0.52 inches/hour. Howard County has more stringent minimum requirements of 1.02 inches/hour. It is further required that the bottom of the infiltration structure be at least 4 feet above the ground water table or rock (i.e. impermeable materials).

Ground water levels will probably design storm water disposal by infiltration in any of the three basins if basin or filter grades are within close proximity to the groundwater table. The water level in B-9 eliminated infiltration testing at the 6-foot depth.

Tests were performed in accordance with the procedures outlined in MDE storm water management manual. The test results and test procedures are presented in TABLE 2, INFILTRATION TEST DATA. The test results indicate that infiltration would be possible in the Sandy Loam soil between depths of 3 and 6 feet in B-2. We would recommend a design infiltration rate of 1.02 inches per hour.

It is our opinion that infiltration rates of soils will decrease over time as very fine sediments carried in with initial storm runoff begin to cover the infiltrating surface. Consequently, all infiltration structures should have a gravity overflow discharge directed so as not to adversely affect adjacent structures or property.

GEOTECHNICAL MONITORING

We recommend that Heibel/Benson & Associates be retained to provide the geotechnical monitoring and testing services during the earthwork and principal spillway construction phases of the work. This is to observe compliance with design concepts, specifications or recommendations and to allow design changes in the event that subsurface conditions differ from those anticipated prior to the start of construction.

The earthwork construction including stripping, undercutting, profiling and controlled fill placement shall be inspected with in-place density tests taken to verify compaction according to the specifications. Also, the principal spillway excavations shall be examined and the exposed soil conditions approved for the design bearing. We will provide the indicated geotechnical monitoring and testing services upon request.

GENERAL CONDITIONS

This report has been prepared in accordance with generally accepted geotechnical engineering practice to aid in the evaluation and design of this project. In the event of changes or modifications approved in writing by our office, the analyses and recommendations included in this report are based upon the data obtained from the test borings performed at the approximate locations indicated on the boring location plan. This report does not reflect variations which may occur between or away from the borings. The nature and extent of the variations may not become evident until the time of construction. If significant variations then become evident, it may be necessary for us to reevaluate the recommendations of this report.

AS-BUILT CERTIFICATION

I hereby certify that the Facility shown on this Plan Was Constructed As Shown On The "As-Built" Plans And Meets The Approved Plans And Specifications.

Signature _____ P.E. No. _____

Date: _____

Certify Means To State Or Declare A Professional Opinion Based Upon Onsite Inspections And Material Tests which are Conducted During Construction. The Onsite Inspections And Material Tests are Those Inspections And Tests Deemed Sufficient And Appropriate Commonly Accepted Engineering Standards. Certify Does Not Mean Or Imply A Guarantee By The Engineer Nor Does An Engineer's Certification Release Any Other Party From Meeting Requirements Imposed By Contract, Employment, Or Other Means, Including Meeting Commonly Accepted Industry Practices.

Signature _____ P.E. No. _____

Date: _____

Certify Means To State Or Declare A Professional Opinion Based Upon Onsite Inspections And Material Tests which are Conducted During Construction. The Onsite Inspections And Material Tests are Those Inspections And Tests Deemed Sufficient And Appropriate Commonly Accepted Engineering Standards. Certify Does Not Mean Or Imply A Guarantee By The Engineer Nor Does An Engineer's Certification Release Any Other Party From Meeting Requirements Imposed By Contract, Employment, Or Other Means, Including Meeting Commonly Accepted Industry Practices.

Signature _____ P.E. No. _____

Date: _____

Certify Means To State Or Declare A Professional Opinion Based Upon Onsite Inspections And Material Tests which are Conducted During Construction. The Onsite Inspections And Material Tests are Those Inspections And Tests Deemed Sufficient And Appropriate Commonly Accepted Engineering Standards. Certify Does Not Mean Or Imply A Guarantee By The Engineer Nor Does An Engineer's Certification Release Any Other Party From Meeting Requirements Imposed By Contract, Employment, Or Other Means, Including Meeting Commonly Accepted Industry Practices.

Signature _____ P.E. No. _____

Date: _____

Certify Means To State Or Declare A Professional Opinion Based Upon Onsite Inspections And Material Tests which are Conducted During Construction. The Onsite Inspections And Material Tests are Those Inspections And Tests Deemed Sufficient And Appropriate Commonly Accepted Engineering Standards. Certify Does Not Mean Or Imply A Guarantee By The Engineer Nor Does An Engineer's Certification Release Any Other Party From Meeting Requirements Imposed By Contract, Employment, Or Other Means, Including Meeting Commonly Accepted Industry Practices.

Signature _____ P.E. No. _____

Date: _____

Certify Means To State Or Declare A Professional Opinion Based Upon Onsite Inspections And Material Tests which are Conducted During Construction. The Onsite Inspections And Material Tests are Those Inspections And Tests Deemed Sufficient And Appropriate Commonly Accepted Engineering Standards. Certify Does Not Mean Or Imply A Guarantee By The Engineer Nor Does An Engineer's Certification Release Any Other Party From Meeting Requirements Imposed By Contract, Employment, Or Other Means, Including Meeting Commonly Accepted Industry Practices.

Signature _____ P.E. No. _____

Date: _____

Certify Means To State Or Declare A Professional Opinion Based Upon Onsite Inspections And Material Tests which are Conducted During Construction. The Onsite Inspections And Material Tests are Those Inspections And Tests Deemed Sufficient And Appropriate Commonly Accepted Engineering Standards. Certify Does Not Mean Or Imply A Guarantee By The Engineer Nor Does An Engineer's Certification Release Any Other Party From Meeting Requirements Imposed By Contract, Employment, Or Other Means, Including Meeting Commonly Accepted Industry Practices.

By The Developer:

"I/We Certify That All Development And/Or Construction Will Be Done According To These Plans, And That Any Responsible Personnel Involved In The Construction Project Will Have A Certificate Of Attendance At A Department Of The Environment Approved Training Program For The Control Of Sediment And Erosion Before Beginning The Project. I shall Engage A Registered Professional Engineer To Supervise Pond Construction And Provide The Howard Soil Conservation District With An "As-Built" Plan Of The Pond Within 30 Days Of Completion. I Also Authorize Periodic On-Site Inspections By The Howard Soil Conservation District."

Signature of Developer _____ 9/24/08
Date

Printed Name Of Developer
Timothy W. Feaga

By The Engineer:

"I Certify That This Plan For Pond Construction, Erosion And Sediment Control Represents A Practical And Workable Plan Based On My Personal Knowledge Of The Site Conditions. This Plan Was Prepared In Accordance With The Requirements Of The Howard Soil Conservation District. I Have Engaged The Developer That He/She Must Engage A Registered Professional Engineer To Supervise Pond Construction And Provide The Howard Soil Conservation District With An "As-Built" Plan Of The Pond Within 30 Days Of Completion."

Signature of Engineer _____ 9/23/08
Date

Printed Name Of Engineer
Arvo M. M... ..

These Plans For Small Pond Construction, Soil Erosion And Sediment Control Meet The Requirements Of The Howard Soil Conservation District.

Signature of District Engineer _____ 10/7/08
Date

Approved: Department Of Public Works
Signature _____ 10-9-08
Date

Approved: Department Of Planning And Zoning
Signature _____ 10/6/08
Date

Signature _____ P.E. No. _____

Date: _____

Certify Means To State Or Declare A Professional Opinion Based Upon Onsite Inspections And Material Tests which are Conducted During Construction. The Onsite Inspections And Material Tests are Those Inspections And Tests Deemed Sufficient And Appropriate Commonly Accepted Engineering Standards. Certify Does Not Mean Or Imply A Guarantee By The Engineer Nor Does An Engineer's Certification Release Any Other Party From Meeting Requirements Imposed By Contract, Employment, Or Other Means, Including Meeting Commonly Accepted Industry Practices.

Signature _____ P.E. No. _____

Date: _____

Certify Means To State Or Declare A Professional Opinion Based Upon Onsite Inspections And Material Tests which are Conducted During Construction. The Onsite Inspections And Material Tests are Those Inspections And Tests Deemed Sufficient And Appropriate Commonly Accepted Engineering Standards. Certify Does Not Mean Or Imply A Guarantee By The Engineer Nor Does An Engineer's Certification Release Any Other Party From Meeting Requirements Imposed By Contract, Employment, Or Other Means, Including Meeting Commonly Accepted Industry Practices.

Signature _____ P.E. No. _____

Date: _____

Certify Means To State Or Declare A Professional Opinion Based Upon Onsite Inspections And Material Tests which are Conducted During Construction. The Onsite Inspections And Material Tests are Those Inspections And Tests Deemed Sufficient And Appropriate Commonly Accepted Engineering Standards. Certify Does Not Mean Or Imply A Guarantee By The Engineer Nor Does An Engineer's Certification Release Any Other Party From Meeting Requirements Imposed By Contract, Employment, Or Other Means, Including Meeting Commonly Accepted Industry Practices.

Signature _____ P.E. No. _____

Date: _____

Certify Means To State Or Declare A Professional Opinion Based Upon Onsite Inspections And Material Tests which are Conducted During Construction. The Onsite Inspections And Material Tests are Those Inspections And Tests Deemed Sufficient And Appropriate Commonly Accepted Engineering Standards. Certify Does Not Mean Or Imply A Guarantee By The Engineer Nor Does An Engineer's Certification Release Any Other Party From Meeting Requirements Imposed By Contract, Employment, Or Other


APPROVED: DEPARTMENT OF PUBLIC WORKS
Walter F. Smith 10-9-08
 CHIEF, BUREAU OF HIGHWAYS DATE

APPROVED: DEPARTMENT OF PLANNING AND ZONING
Cindy Hamlet 10/20/08 DATE
 CHIEF, DIVISION OF LAND DEVELOPMENT

Walter Drummond 10/16/08 DATE
 CHIEF, DEVELOPMENT ENGINEERING DIVISION



DRAINAGE AREA DATA					
STRUCTURE NO.	DRAINAGE AREA	AREA	'C'	ZONED	% IMP.
I-1	A	0.61 AC.	0.47	RC-DEO	31%
I-2	B	0.78 AC.	0.45	RC-DEO	29%
I-3	C	3.84 AC.	0.33	RC-DEO	12%
I-4	D	0.18 AC.	0.52	RC-DEO	30%
I-5	E	0.41 AC.	0.45	RC-DEO	29%
I-6	F	0.39 AC.	0.42	RC-DEO	25%
I-7	G	0.42 AC.	0.44	RC-DEO	27%
I-8	H	3.21 AC.	0.32	RC-DEO	10%
I-9	I	1.07 AC.	0.47	RC-DEO	32%
I-10	J	5.05 AC.	0.29	RC-DEO	6%
I-11	K	0.14 AC.	0.39	RC-DEO	20%
I-3a	L	0.74 AC.	0.39	RC-DEO	20%
I-11a	M	2.99 AC.	0.39	RC-DEO	20%



PLAN
 SCALE: 1" = 100'



ALDO M. FISHER
 DATE 9/23/08
 I hereby certify that these documents were prepared by me, and that I am a duly Licensed Professional Engineer under the laws of the State of Maryland, License No. 20749, Expiration Date 2-22-09.


FISHER, COLLINS & CARTER, INC.
 CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS
 CENTRAL SQUARE OFFICE PARK - 10272 BALTIMORE NATIONAL PIKE
 ELLICOTT CITY, MARYLAND 21114
 (410) 461-2855

OWNERS
 MARIO MANNARELLI, SR. & SERAFINA MANNARELLI,
 RAYMOND MANNARELLI & MARIO MANNARELLI, JR.
 2929 SUMMIT CIRCLE
 ELLICOTT CITY, MARYLAND 21043
 (410) 461-2278

DEVELOPER
 HERITAGE LAND DEVELOPMENT, INC.
 15950 NORTH AVE.
 P.O. BOX 482
 LISBON, MD. 21765
 (410) 489-7900

STORMDRAIN DRAINAGE AREA MAP
PHEASANT RUN EAST
 LOTS 1 THRU 14, CEMETERY OPEN SPACE LOT 15,
 BUILDABLE PRESERVATION PARCEL "A" &
 NON-PRESERVATION PARCELS "B" THRU "D"
 ZONED "RC-DEO"
 TAX MAP No. 3, GRID No. 19, PARCEL No. 29
 FOURTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND
 DATE: SEPTEMBER, 2008
 SHEET 14 OF 19

PATTERN SPACING DIAGRAM



Planting Notes:

Planting units defined by the spacing requirements established in the FCA Manual. One planting unit is defined as 1 seedling or whip without shelter. The Manual states that 700 seedlings/whips without shelters are required per acre, or 500 whips w/shelters, or 200 1" caliper trees, or 100 2" caliper trees. By convention it has been determined that a seedling or whip without shelter = 1 unit, whip with shelter = 2 units, 1 caliper tree = 2.5 units and 2" caliper tree = 7 units. The use of plant units simplifies the plant density calculations when mixing stock size.

** - These species should not be planted within the wetland limits.

1" caliper trees should be staggered along the outer perimeter of the planting area to serve as demarcation of the boundaries. The trees should be no closer than 15 feet spacing. Planting shall be made in a consistent fashion along contours. The planting should avoid a grid appearance but should be spaced to facilitate maintenance. Multiple rows/whips brush removal/control may be required prior to installation of planting.

All whips are required to be installed with tree shelters per Howard County FCA requirements.

* - whip w/shelter 11' on center spacing
- 1" caliper tree 15' on center spacing
Species shall be randomly interspersed, rows should be planted along contours

GUARANTEE REQUIREMENTS

1. A 75 Percent Survival Rate of Forestation Plantings Will be Required At the End of The 24 Month Maintenance Period. All Plant Material Below The 75 Percent Threshold Will be Replaced At The Beginning of The Next Growing Season.

SURETY FOR FORESTATION

1. The Developer Shall Post A Surety Bond, Letter of Credit To Ensure That forestation Plantings Are Completed Upon Acceptance Of The Plantings by The County. The Bond Shall be Released.

2. The Forest Conservation Requirements Per Section 161200 Of The Howard County Code And The Forest Conservation Manual For This Subdivision Will be Fulfilled By Providing 11.75 Ac. Of On-site Afforestation. The Total Forest Conservation Area Is 11.75 Acres. The Forest Conservation Surety Amount To Fulfill The Forest Conservation Obligation Is \$25,477.40 Based On (11.75 Ac. X 43,560 Sq.Ft. X \$0.50 Per Sq.Ft.) Shall be Posted With The Developers Agreement For This Final Plan, F-08-011.

FCP NOTES:

- Any Forest Conservation Easement (FCE) area shown hereon is subject to protective covenants which may be found in the Land Records of Howard County which restrict the disturbance and use of these areas.
- Forested areas occurring outside of the FCE shall not be considered part of the FCE and shall not be subject to protective land covenants.
- Limits of disturbance shall be restricted to areas outside the limit of temporary fencing or the FCE boundary, whichever is greater.
- There shall be no clearing, grading, construction or disturbance of vegetation in the Forest Conservation Easement, except as permitted by Howard County DPZ.
- No stockpiles, parking areas, equipment clearing areas, etc. shall occur within areas designated as Forest Conservation Easements.
- Temporary fencing shall be used to protect forest resources during construction. The fencing shall be placed along all FCE boundaries which occur within 15 feet of the proposed limits of disturbance.
- Permanent signage shall be placed 50-100' apart along the boundaries of all areas included in Forest Conservation Easements.
- The Forest Conservation Act requirements for this project include 11.75 acres of forest planting. The forestation obligation will be met by providing a total planting area of 11.75 CREDITED acres.

APPROVED: DEPARTMENT OF PUBLIC WORKS

Michael R. Schall 10-9-09
CHIEF, BUREAU OF HIGHWAYS DATE

Cindy Samter 10/20/08
CHIEF, DIVISION OF LAND DEVELOPMENT DATE

John Danvers 10/16/08
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

PLANTING SCHEDULE

FCE = 11.75 Acres
Planting Units Required 8211 - 11.75 ACRES x 700 SEEDLINGS/WHIPS WITHOUT SHELTERS.
Planting Units Provided 8216

Qty	Species	Size	Spacing	Total FCA Units
24	Acer rubrum - Red maple	1" cal	15' oc.	
24	Liriodendron tulipifera - Tulip poplar **	1" cal	15' oc.	
24	Pithecellobium bicolor - Sycamore	1" cal	15' oc.	
24	Quercus alba - White oak **	1" cal	15' oc.	
96	Total 1" caliper trees	Total 1" caliper tree x 3.5 units/tree = FCA unit credit		336
600	Acer rubrum - Red maple	2-3" whip	11' oc.	
180	Diospyros virginiana - Persimmon **	2-3" whip	11' oc.	
150	Liriodendron tulipifera - Tulip poplar **	2-3" whip	11' oc.	
200	Nyssa sylvatica - Black gum	2-3" whip	11' oc.	
100	Pithecellobium bicolor - Sycamore	2-3" whip	11' oc.	
900	Prunus serotina - Black cherry **	2-3" whip	11' oc.	
900	Quercus alba - White oak	2-3" whip	11' oc.	
900	Quercus palustris - Pin oak	2-3" whip	11' oc.	
150	Ulmus rubra - Slippy Elm	2-3" whip	11' oc.	
180	Viburnum prunifolium - Blackhaw **	2-3" whip	11' oc.	
900	Total whips with shelters	Total whip plantings x 2 units / tree = FCA unit credit		7,800
				8,216

PLANTING/SOIL SPECIFICATIONS

- PLANTING OF NURSERY STOCK SHALL TAKE PLACE BETWEEN MARCH 15th, AND APRIL 30th, OR SEPTEMBER 15th, AND NOVEMBER 15th.
- A TWELVE (12) INCH LAYER OF TOPSOIL SHALL BE SPREAD OVER ALL FORESTATION AREAS IMPACTED BY SITE GRADING TO ASSURE A SUITABLE PLANTING AREA. DISTURBED AREAS SHALL BE SEEDED AND STABILIZED AS PER GENERAL CONSTRUCTION PLAN FOR PROJECT. PLANTING AREAS NOT IMPACTED BY SITE GRADING SHALL HAVE NO ADDITIONAL TOPSOIL INSTALLED.
- ALL BAREROOT PLANTING STOCK SHALL HAVE THEIR ROOT SYSTEMS DIPPED INTO AN ANTI-DESICCANT GEL PRIOR TO PLANTING.
- PLANTS SHALL BE INSTALLED SO THAT THE TOP OF ROOT MASS IS LEVEL WITH THE TOP OF EXISTING GRADE. BACKFILL IN THE PLANTING PITS SHALL CONSIST OF 3 PARTS EXISTING SOIL TO 1 PART FINE FINES OR EQUIVALENT.
- FERTILIZER SHALL CONSIST OF AGRFORM 22-0-2, OR EQUIVALENT, APPLIED AS PER MANUFACTURER'S SPECIFICATIONS.
- A TWO (2) INCH LAYER OF HARDWOOD MULCH SHALL BE PLACED OVER THE ROOT AREA OF ALL PLANTINGS.
- PLANT MATERIAL SHALL BE TRANSPORTED TO THE SITE IN A TARPED OR COVERED TRUCK. PLANTS SHALL BE KEPT MOIST PRIOR TO PLANTING.
- ALL NON-ORGANIC DEBRIS ASSOCIATED WITH THE PLANTING OPERATION SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR.

SEQUENCE OF CONSTRUCTION



- SEDPMENT CONTROL AND TREE PROTECTION DEVICES SHALL BE INSTALLED IN ACCORDANCE WITH GENERAL CONSTRUCTION PLAN FOR SITE. SITE SHALL BE GRADED IN ACCORDANCE WITH GENERAL CONSTRUCTION PLANS.
- PROPOSED FORESTATION AREAS IMPACTED BY SITE GRADING, SHALL BE TOPSOILED AND STABILIZED AS PER NOTE NO. 2 OF PLANTING/SOIL SPECIFICATIONS FOR PROJECT.
- PLANTS SHALL BE INSTALLED AS PER PLANT SCHEDULE AND THE PLANTING/SOIL SPECIFICATIONS FOR THE PROJECT.
- UPON COMPLETION OF THE PLANTING, SIGNAGE SHALL BE INSTALLED AS PER THE PROTECTION DEVICES SHOWN ON THE FOREST CONSERVATION PLAN.
- PLANTINGS SHALL BE MAINTAINED AND GUARANTEED IN ACCORDANCE WITH THE MAINTENANCE AND GUARANTEE REQUIREMENTS FOR PROJECTS.

MAINTENANCE OF PLANTINGS

- MAINTENANCE OF PLANTINGS SHALL LAST FOR A PERIOD OF 26 MONTHS.
- ALL PLANT MATERIAL SHALL BE WATERED TWICE A MONTH DURING THE 1st, GROWING SEASON. WATERING MAY BE MORE OR LESS FREQUENT DEPENDING ON WEATHER CONDITIONS. DURING 2nd, GROWING SEASON, ONCE A MONTH DURING MAY-SEPTEMBER, IF NEEDED.
- INVASIVE EXOTICS AND NOXIOUS WEEDS WILL BE REMOVED FROM FORESTATION AREAS. OLD FIELD SUCCESSIONAL SPECIES WILL BE RETAINED.
- PLANTS WILL BE EXAMINED A MINIMUM TWO TIMES DURING THE GROWING SEASON FOR SERIOUS PLANT PESTS AND DISEASES. SERIOUS PROBLEMS WILL BE TREATED WITH THE APPROPRIATE AGENT.
- DEAD BRANCHES WILL BE PRUNED FROM PLANTINGS.

FOREST CONSERVATION WORKSHEET

NET TRACT AREA	ACRES
total tract area	60.1
area within 100 year floodplain	1.46
net tract area	58.64
LAND USE CATEGORY: (from table 3.2.1, page 40, manual)	
ARA HDR IDA HDR MPD CIA	
afforestation threshold (PERCENTAGE)	20% 11.75
conservation threshold (PERCENTAGE)	25% 14.66
EXISTING FOREST COVER	
existing forest on NTA	0.00
area of forest above afforestation threshold	0.00
area of forest above conservation threshold	0.00
BREAK EVEN POINT	
forest retention above threshold with no mitigation	
BREAK EVEN POINT	
clearing permitted without mitigation	
PROPOSED FOREST CLEARING	
total area of forest to be cleared or retained outside FCE	0.00
total area of forest to be retained in FCE	0.00
PLANTING REQUIREMENTS	
reforestation for clearing above conservation threshold	0.00
reforestation for clearing below conservation threshold	0.00
credit for retention above conservation threshold	0.00
total reforestation required	0.00
total afforestation required	11.75
total reforestation and afforestation required	11.75



ON-SITE SIGNAGE

FOREST CONSERVATION EASEMENT

UNAUTHORIZED DISTURBANCE OF VEGETATION IS PROHIBITED. VIOLATORS SUBJECT TO PENALTIES UNDER THE HOWARD COUNTY FOREST CONSERVATION ACT OF 1991.

TREES FOR YOUR FUTURE

PLAN
SCALE: 1" = 100'



FOREST CONSERVATION EASEMENT NO. 1
9.97 AC.
(TO BE PLANTED)

LEGEND

- Denotes 15% - 24.99% Slopes
- Denotes Planting Area
- Denotes Public Stormwater Management Credit Easement
- TP Denotes Tree Protection Fence
- Denotes Limit of Disturbance

FISHER, COLLINS & CARTER, INC.
CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS
CENTRAL SQUARE OFFICE PARK - 10272 BALTIMORE NATIONAL PIKE
ELLICOTT CITY, MARYLAND 21114
(410) 461-2855

Eco-Science Professionals, Inc.
CONSULTING ECOLOGISTS

MD DNR Qualified Professional
USACOE Wetland Delineator
Certification # WDGP3MD0610044B
John P. Canoles 10/20/08
JOHN P. CANOLES

OWNERS
MARIO MANNARELLI, SR. & SERAFINA MANNARELLI,
RAYMOND MANNARELLI & MARIO MANNARELLI, JR.
2329 SUMMIT CIRCLE
ELLICOTT CITY, MARYLAND 21143
(410) 461-2278

DEVELOPER
HERITAGE LAND DEVELOPMENT, INC.
15950 NORTH AVE.
P.O. BOX 492
LISBON, MD. 21765
(410) 489-7900

FOREST CONSERVATION PLAN
PHEASANT RUN EAST
LOTS 1 THRU 14, CEMETERY OPEN SPACE LOT 15,
BUILDABLE PRESERVATION PARCEL "A" &
NON-PRESERVATION PARCELS "B" THRU "D"

ZONED "RC-DEP"
TAX MAP No. 3, GRID No. 19, PARCEL No. 29
FOURTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND
DATE : SEPTEMBER, 2008
SHEET 15 OF 19

APPROVED: DEPARTMENT OF PUBLIC WORKS
William R. Marshall 10-9-08
 CHIEF, BUREAU OF HIGHWAYS DATE


APPROVED: DEPARTMENT OF PLANNING AND ZONING
Cindy Hunt 10/29/05
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE

Charles D. Dumas 10/16/08
 CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE


B.M.P. No. 2

B.M.P. No. 1

HERBST/BENSON & ASSOCIATES Geotechnical Engineers



HERBST/BENSON & ASSOCIATES Geotechnical Engineers



FISHER, COLLINS & CARTER, INC.
 CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS
 CENTRAL SQUARE OFFICE PARK - 10275 BALTIMORE NATIONAL PkE
 ELKROTT CITY, MARYLAND 21042
 (410) 461-2255



ALDO
 PROFESSIONAL ENGINEER
 I hereby certify that these documents were prepared by me and that I am a duly Licensed Professional Engineer under the laws of the State of Maryland, License No. 20748, Expiration Date 9-22-09.

OWNERS
 MARIO MANNARELLI, Sr. & SERAFINA MANNARELLI
 RAYMOND MANNARELLI & MARIO MANNARELLI, JR.
 2929 SUMMIT CIRCLE
 ELLICOTT CITY, MARYLAND 21043
 (410) 461-2270

DEVELOPER
 HERITAGE LAND DEVELOPMENT, INC.
 15950 NORTH AVE.
 P.O. BOX 482
 LISBON, MD. 21765
 (410) 489-7900

SOIL BORING PROFILES
PHEASANT RUN EAST
 LOTS 1 THRU 14, CEMETERY OPEN SPACE LOT 15,
 BUILDABLE PRESERVATION PARCEL "A" &
 NON-PRESERVATION PARCELS "B" THRU "D"
 TAX MAP No. 3, GRID No. 19, PARCEL No. 29
 FOURTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND
 DATE: SEPTEMBER, 2008
 SHEET 15 OF 19

ENGINEER'S CERTIFICATE

I hereby certify that this Plan for Erosion and Sediment Control Represents a Feasible and Workable Plan Based on My Personal Knowledge of the Site Conditions and That It Was Prepared in Accordance with the Howard Soil Conservation District.

Signature of Engineer: *[Signature]* Date: 7-23-08

DEVELOPER'S CERTIFICATE

I/We Certify That All Development And Construction Will Be Done According To This Plan of Development And Plan For Erosion And Sediment Control And That All Responsible Personnel Involved In The Construction Project Will Have A Certificate of Attendance At A Department of Natural Resources Approved Training Program For The Control Of Sediment And Erosion Before Beginning The Project. I Also Authorize Periodic On-Site Inspection By The Howard Soil Conservation District Of Their Authorized Agents, As Are Deemed Necessary.

Signature of Developer: *[Signature]* Date: 7/24/08

Approved: This Development Is Approved For Erosion And Sediment Control By Howard Soil Conservation District.

Signature: *[Signature]* Date: 11/2/08

Approved: Department of Planning And Zoning

Signature: *[Signature]* Date: 11/2/08

Signature: *[Signature]* Date: 10/16/08


Approved: Howard County Department of Public Works

Signature: *[Signature]* Date: 10-9-08


Chief, Bureau of Highways

EARTH DIKE

NOT TO SCALE



DIKE A	DIKE B
a-DIKE HEIGHT 18"	30"
b-DIKE WIDTH 24"	36"
c-FLOW WIDTH 4'	6'
d-FLOW DEPTH 12"	24"





Construction Specifications

- Seed and cover with straw mulch.
- Seed and cover with Erosion Control Matting or line with sod.
- 4" - 7" stone or recycled concrete equivalent pressed into the soil 7" minimum.
- All temporary earth dikes shall have uninterrupted positive grade to an outlet. Spot elevations may be necessary for grades less than 1%.
- Runoff diverted from a disturbed area shall be conveyed to a sediment trapping device.
- Runoff diverted from an undisturbed area shall outlet directly into an undisturbed, stabilized area at a non-erosive velocity.
- All trees, brush, stumps, obstructions, and other objectionable material shall be removed and disposed of so as not to interfere with the proper functioning of the dike.
- The dike shall be excavated or shaped to line, grade and cross section as required to meet the criteria specified herein and be free of bank projections or other irregularities which will impede normal flow.
- Fill shall be compacted by earth moving equipment.
- All earth removed and not needed for construction shall be placed so that it will not interfere with the functioning of the dike.
- Inspection and maintenance must be provided periodically and after each rain event.

SILT FENCE

NOT TO SCALE





Construction Specifications

- Fence posts shall be a minimum of 35" long driven 16" minimum into the ground. Wood posts shall be 1 1/2" x 1 1/2" square (minimum cut, or 1 3/4" diameter (minimum round and shall be of sound quality hardwood. Steel posts will be standard T or U section weighting not less than 100 pound per linear foot.
 - Geotextile shall be fastened securely to each fence post with wire ties or staples at top and mid-section and shall meet the following requirements for Geotextile Class F:
- | | | |
|----------------------|---------------------------|----------------|
| Tensile Strength | 50 lbs/in (min) | Test: MSMT 509 |
| Tensile Modulus | 20 lbs/in (min) | Test: MSMT 509 |
| Flow Rate | 0.3 gal ft / minute (max) | Test: MSMT 322 |
| Filtering Efficiency | 75% (min) | Test: MSMT 322 |
- Where ends of geotextile fabric come together, they shall be overlapped, folded and stapled to prevent sediment bypass.
 - Silt Fence shall be inspected after each rainfall event and maintained when bulges occur or when sediment accumulation reached 50% of the fabric height.

STABILIZED CONSTRUCTION ENTRANCE

NOT TO SCALE





Construction Specification

- Length - minimum of 50' (*30' for single residence lot).
- Width - 10' minimum, should be flared at the existing road to provide a turning radius.
- Geotextile fabric (filter cloth) shall be placed over the existing ground prior to placing stone. **The plan approval authority may not require single family residences to use geotextile.
- Stone - crushed aggregate (2" to 3") or reclaimed or recycled concrete equivalent shall be placed at least 6" deep over the length and width of the entrance.
- Surface Water - all surface water flowing to or diverted toward construction entrances shall be piped through the entrance, maintaining positive drainage. Pipe installed through the stabilized construction entrance shall be protected with a mountable berm with 5:1 slopes and a minimum of 6" of stone over the pipe. Pipe has to be sized according to the drainage. When the SCE is located at a high spot and has no drainage to convey a pipe will not be necessary. Pipe should be sized according to the amount of runoff to be conveyed. A 6" minimum will be required.
- Location - A stabilized construction entrance shall be located at every point where construction traffic enters or leaves a construction site. Vehicles leaving the site must travel over the entire length of the stabilized construction entrance.

SUPER SILT FENCE DETAIL

NOT TO SCALE



Construction Specifications

- FENCING SHALL BE 42" HIGH CHAIN LINK CONSTRUCTED IN ACCORDANCE WITH THE LATEST MARYLAND STATE HIGHWAY ADMINISTRATION STANDARD DETAILS 690.01 AND 690.02 FOR CHAIN U FENCING. THE SPECIFICATIONS FOR A 6'-0" FENCE SHALL BE USED. SUBSTITUTING 42" FABRIC AND 2" POSTS. POSTS SHALL BE PLACED WITHOUT CONCRETE EMBEDMENT.
- CHAIN LINK FENCE SHALL BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES. THE LOWER TENSION WIRE, BRACE AND TIE RODS, ANCHORS AND POST CAPS ARE NOT REQUIRED EXCEPT ON THE ENDS OF THE FENCE.
- FILTER CLOTH TO BE FASTENED SECURELY TO CHAIN LINK FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION.
- FILTER CLOTH SHALL BE EMBEDDED A MINIMUM OF 9" INTO THE GROUND.
- WHEN TWO SECTIONS OF DIVERSION CLOTH ADJOIN EACH OTHER THEY SHALL BE OVERLAPPED BY SIX INCHES AND FOLDED.
- MAINTENANCE SHALL BE PERFORMED AS NEEDED.



Fabric Properties	Value	Test Method
Grab Tensile Strength (lbs)	90	ASTM D1682
Elongation at Failure (%)	50	ASTM D1682
Mullen Burst Strength (PSI)	190	ASTM D3786
Puncture Strength (lbs)	40	ASTM D751
Slurry Flow Rate (gal/min/ft)	0.3	Virginia DOT VM-51
Equivalent Opening Size	40-80	US Std Sieve CW-02215
Ultraviolet Radiation Stability (%)	90	ASTM G-26

Design Criteria

Slope	Slope Stipress	Slope Length (maximum)	Silt Fence Length (maximum)
0 - 10%	0 - 10%	Unlimited	Unlimited
10 - 20%	10 - 51	400 feet	1,500 feet
20 - 33%	51 - 31	300 feet	1,000 feet
33 - 50%	31 - 21	200 feet	500 feet
50% +	21 +	100 feet	250 feet

EROSION CONTROL MATTING

NOT TO SCALE




Construction Specifications

- Key-in the matting by placing the top ends of the matting in a narrow trench, 6" in depth. Backfill the trench and tamp firmly to conform to the channel cross-section. Secure with a row of staples about 4" down slope from the trench. Spacing between staples is 6".
- Staple the 4" overlap in the channel center using an 18" spacing between staples.
- Before stapling the outer edges of the matting, make sure the matting is smooth and in firm contact with the soil.
- Staples shall be placed 2" apart with 4 rows for each strip, 2 outer rows, and 2 alternating rows down the center.
- Where one roll of matting ends and another begins, the end of the top strip shall overlap the upper end of the lower strip by 4", shiplap fashion. Reinforce the overlap with a double row of staples spaced 6" apart in a staggered pattern on either side.
- The discharge end of the matting liner should be similarly secured with 2 double rows of staples.

Note: If flow will enter from the edge of the matting then the area effected by the flow must be keyed-in.




REMOVABLE PUMPING STATION



Construction Specifications

- The outer pipe should be 48" dia. or shall, in any case, be at least 4" greater in diameter than the center pipe. The outer pipe shall be wrapped with 1/2" hardware cloth to prevent backfill material from entering the perforations.
- After installing the outer pipe, backfill around outer pipe with 2" aggregate or clean gravel.
- The inside stand pipe (center pipe) should be constructed by perforating a corrugated or PVC pipe between 12" and 36" in diameter. The perforations shall be 1/2" x 6" slots or 1" diameter holes 6" on center. The center pipe shall be wrapped with 1/2" hardware cloth first, then wrapped again with Geotextile Class C.
- The center pipe should extend 12" to 18" above the anticipated water surface elevation or riser crest elevation when dewatering a basin.

SEDIMENT BASIN BAFFLES



BAFFLE DETAIL

SEDIMENT CONTROL NOTES

- A MINIMUM OF 48 HOURS NOTICE MUST BE GIVEN TO THE HOWARD COUNTY DEPARTMENT OF INSPECTIONS, LICENSING AND PERMITS, SEDIMENT CONTROL DIVISION PRIOR TO THE START OF ANY CONSTRUCTION (313-1855).
- ALL VEGETATIVE AND STRUCTURAL PRACTICES ARE TO BE INSTALLED ACCORDING TO THE PROVISIONS OF THIS PLAN AND ARE TO BE IN CONFORMANCE WITH THE MOST CURRENT MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL, AND REVISIONS THERETO.
- FOLLOWING INITIAL SOIL DISTURBANCE OR RE-DISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN: a) 7 CALENDAR DAYS FOR ALL PERMITS; SEDIMENT CONTROL STRUCTURES, DICES, PERMETER SLOPES AND ALL SLOPES STEEPER THAN 3:1; b) 14 DAYS AS TO ALL OTHER DISTURBED OR GRADED AREAS ON THE PERMITS; SEEDING, MULCHING, PERMETER SEEDING (SEC. 50), SOD (SEC. 54), TEMPORARY SEEDING (SEC. 50), AND MULCHING (SEC. 50). TEMPORARY STABILIZATION WITH MULCH ALONE CAN ONLY BE DONE WHEN RECOMMENDED SEEDING DATES DO NOT ALLOW FOR PROPER GERMINATION AND ESTABLISHMENT OF GRASSES.
- ALL SEDIMENT CONTROL STRUCTURES ARE TO REMAIN IN PLACE AND ARE TO BE MAINTAINED IN OPERATIVE CONDITION UNTIL PERMISSION FOR THEIR REMOVAL HAS BEEN OBTAINED FROM THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR.
- NOTE: TOTAL AREA OF SITE: 60.05 ACRES. AREA DISTURBED: 14.09 ACRES. AREA TO BE VEGETATIVELY STABILIZED: 10.09 ACRES. TOTAL CUT: 20,000 CU.YDS. TOTAL FILL: 20,000 CU.YDS. OFFSITE WASTE/BORROW AREA LOCATION: N/A. CU.YDS.
- ANY SEDIMENT CONTROL PRACTICE WHICH IS DISTURBED BY GRADING ACTIVITY FOR PLACEMENT OF UTILITIES MUST BE REPAIRED ON THE SAME DAY OF DISTURBANCE.
- ADDITIONAL SEDIMENT CONTROLS MUST BE PROVIDED, IF DEEMED NECESSARY BY THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR.
- ON ALL SITES WITH DISTURBED AREAS IN EXCESS OF 2 ACRES, APPROVAL OF THE INSPECTION AGENCY SHALL BE REQUESTED UPON COMPLETION OF INSTALLATION OF PERMETER EROSION AND SEDIMENT CONTROLS, BUT BEFORE PROCEEDING WITH ANY OTHER EARTH DISTURBANCE OR GRADING. OTHER BUILDING OR GRADING INSPECTION APPROVALS MAY NOT BE AUTHORIZED UNTIL THIS INITIAL APPROVAL BY THE INSPECTION AGENCY IS MADE.
- TRENCHES FOR THE CONSTRUCTION OF UTILITIES IS LIMITED TO THREE PIPE LENGTHS OR THAT WHICH SHALL BE BACK-FILLED AND STABILIZED WITHIN ONE WORKING DAY, WHICHEVER IS SHORTER.

SEDIMENT AND EROSION CONTROL DETAILS
PHEASANT RUN EAST
 LOTS 1 THRU 14, CEMETERY OPEN SPACE LOT 15,
 BUILDABLE PRESERVATION PARCEL "A" &
 NON-PRESERVATION PARCELS "B" THRU "D"

OWNERS: MARIO MANNARELLI, SR. & SERAFINA MANNARELLI, RAYMOND MANNARELLI & MARIO MANNARELLI, JR. 2923 SUMMIT CIRCLE, ELLICOTT CITY, MARYLAND 21043 (410) 461-2278

DEVELOPER: HERITAGE LAND DEVELOPMENT, INC. 15950 NORTH AVE. P.O. BOX 482 LISBON, MD. 21765 (410) 489-7900

TAX MAP No. 3, GRID No. 19, PARCEL No. 29
 FOURTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND
 DATE : SEPTEMBER, 2008
 SHEET 10 OF 19



7-23-08
 DATE

FISHER, COLLINS & CARTER, INC.
 CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS
 CENTRAL SQUARE OFFICE PARK - 10772 BALTIMORE NATIONAL PIKE
 ELICOTT CITY, MARYLAND 21042
 (410) 481-2855

