




SHEET INDEX	
NO.	DESCRIPTION
1.	TITLE SHEET
2.	PLAN AND PROFILE BRECONSHIRE ROAD
3.	PLAN AND PROFILE KINGSBRIDGE ROAD
4.	PLAN AND PROFILE NEWGATE CT.
5.	ROADWAY AND STORM DRAIN DETAILS
6.	DRAINAGE AREA MAP
7.	STORM DRAIN PROFILES
8.	DRAINAGE AREA MAP FOR SEDIMENT CONTROL
9.	SEDIMENT CONTROL PLAN
10.	SEDIMENT CONTROL DETAILS
11.	SEDIMENT CONTROL DETAILS



VICINITY MAP  
SCALE: 1" = 1/4 MILE



N 519,000  
E 834,000

W.R. & A. B.M.  
W-332

N 520,500  
E 837,500

MONUMENT  
3040001

**BENCH MARKS**

HOWARD COUNTY CONTROL POINT 3040001 - - CONCRETE MON. @ SURFACE - 25'±.  
E OF C. OF CENTENNIAL LANE.  
70'± S. OF OLD ANNAPOLIS ROAD  
ELEV. 494.422

W.R. & A. B.M. W-332 - - IRON PIPE (TRAVERSE POINT) - 140'±  
W. OF & S. 1/4 29+35± BRECONSHIRE ROAD  
ELEV. 449.16

**LOCATION PLAN**

SCALE: 1" = 200'

STATION	HORIZONTAL & VERTICAL CONTROL		ELEV.
	NORTH	EAST	
3140002	522590.105	838530.841	445.77
3140001	523547.740	838056.376	436.43

R.I.C. INDICATES 3' LONG 3/8" REBAR WITH CAP SET FLUSH WITH GROUND

STORM WATER MANAGEMENT FOR THIS PROJECT HAS BEEN PROVIDED IN BURLEIGH MANOR SECTION 1 AREA 1, F-79-93 AND SECTION 3 AREA 2, F-87-18C

NOTE:  
THE ASBUILT INFORMATION SHOWN ON THESE DRAWINGS WAS DRAFTED BY FISHER, COLLINS & CARTER, INC. THIS INFORMATION WAS TAKEN FROM THE ASBUILT RED LINE PRINTS PREPARED BY MCKEE ASSOCIATES. DATED: 6-19-91

Street Trees:  
The location, type and number of trees shown on these plans are tentative and are used for bond purposes only. The final location and variety of trees may vary to accommodate field conditions and bankers landscape program. Bond release is contingent upon Section 16.131 of Howard County Subdivision Regulations, as approved by the Office of Planning and Zoning. The type of hardwood trees to be used are Acer Rubra (Red Maple), Platanus Acerifolia (London Plane Tree) or Tilia Cordata (Little Leaf Linden).

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
*William L. F...* 5/13/88  
 CHIEF, LAND DEVELOPMENT DIVISION DATE  
*Francis W. Walcott* 5/16/88  
 CHIEF, BUREAU OF HIGHWAY DATE  
*Robert E. Ryan* 5-17-88  
 CHIEF, BUREAU OF ENGINEERING DATE

- GENERAL NOTES**
- ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE HOWARD COUNTY STANDARDS, SPECIFICATIONS AND DETAILS FOR CONSTRUCTION.
  - ALL UTILITY COMPANIES SHALL BE NOTIFIED 24 HOURS IN ADVANCE OF CONSTRUCTION.
  - ALL INLETS SHALL BE HOWARD COUNTY STANDARDS UNLESS OTHERWISE SHOWN.
  - ALL STREET CURB RETURNS SHALL HAVE A 30.0' RADIUS UNLESS OTHERWISE NOTED.
  - STORM DRAIN TRENCHES WITHIN ROAD RIGHTS-OF-WAY SHALL BE BACKFILLED AND COMPACTED IN ACCORDANCE WITH THE HOWARD COUNTY ROAD CODE.
  - APPROXIMATE LOCATION OF EXISTING UTILITIES ARE SHOWN. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PROTECT THE EXISTING UTILITIES AND TO MAINTAIN UNINTERRUPTED SERVICE. ANY DAMAGE INCURRED DUE TO CONTRACTOR'S OPERATIONS SHALL BE REPAIRED IMMEDIATELY AT THE CONTRACTOR'S EXPENSE.
  - THE CONTRACTOR SHALL TEST PIT EXISTING UTILITIES WHERE DIRECTED BY THE ENGINEER A MINIMUM OF TWO WEEKS IN ADVANCE OF ANY CONSTRUCTION.
  - TEMPORARY COMPACTED 18" HIGH EARTH FILL DIVERSION DIKES SHALL BE CONSTRUCTED ABOVE THE LIPS OF FILL SLOPES ON THE R.O.W. CONCURRENTLY WITH THE INITIAL GRADING AND DIRECTED TO UNDISTURBED SOA AREAS AT THE END OF EACH DAY.
  - CONTRACTOR TO NOTIFY THE HOWARD COUNTY DEPT. OF INSPECTIONS AND PERMITS AT LEAST 3-DAYS BEFORE STARTING WORK SHOWN ON THESE DRAWINGS. TELEPHONE NO. 792-2630.
  - ALL DISTURBED SLOPE AREAS TO BE STABILIZED AS SOON AS GRADING IS COMPLETED.
  - ALL REINFORCED CONCRETE FOR STORM DRAIN STRUCTURES SHALL HAVE A MINIMUM OF 28 DAYS STRENGTH OF 3500 P.S.I.
  - ALL SWALES AND SLOPES SHALL BE PERMANENTLY SEEDED. SEE THE SEED SPECIFICATIONS ON SHEET 10.
  - TRAFFIC CONTROL DEVICES AND THEIR INSTALLATION SHALL BE IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, 1978 REVISED EDITION.
  - STABILENKA (FILTER CLOTH T-100) OR EQUAL SHALL BE PLACED UNDER ALL STONE RIP-RAP (FULL WIDTH AND LENGTH OF STONE.)
  - STONE FOR RIP-RAP SHALL BE AS SPECIFIED ON THE DRAWINGS. ALL RIP-RAP SHALL BE UNPAVED.
  - STUBS FOR 6" P.V.C. UNDERDRAIN PIPE TO BE INSTALLED AT CENTER OF EACH WALL OF EVERY INLET.
  - LAMP POST - A 250-WATT MERCURY VAPOR LAMP PENDANT MOUNTED FIXTURE ON A 30-FOOT BRONZE ALUMINUM POLE.
  - LAMP POST - A 175 WATT MODERN MERCURY LAMP POST TOP FIXTURES ON A 12-FOOT BRONZE FIBERGLASS POLE.

REV. DATE	REV. NO.	REVISION	DESCRIPTION
12-18-87	1	AS PER PLANNING, ZONING COMMENT #13	

**BURLEIGH MANOR**  
 SECTION 3 AREA 3  
 LOTS 414-421  
**ROAD CONSTRUCTION PLANS**  
 2nd ELECTION DISTRICT OF HOWARD COUNTY, MD.  
 DEVELOPER  
 ROSE / RICHMOND JOINT VENTURE  
 BALTIMORE, MARYLAND

SHEET 1 OF 15  
 SCALE: AS SHOWN  
 DATE: 10-16-87

121

**WHITMAN, REQUARDT AND ASSOCIATES**  
 ENGINEERS  
 2315 SAINT PAUL STREET  
 BALTIMORE, MARYLAND 21218  
*Kenneth A. McCord*  
 KENNETH A. MCCORD P.E. No. 1974

**OWNER**  
 GERALD M. KATZ &  
 THOMAS J. PELLERITO, TRUSTEES  
 BALTIMORE, MARYLAND

OFFICE OF PLANNING AND ZONING  
 CHIEF, DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT  
*...* 5/20/88  
 DATE

1/24/92 AS-BUILT F-88-97



APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
 DATE 5/13/87  
 CHIEF, LAND DEVELOPMENT DIVISION  
 DATE 5/16/88  
 CHIEF, BUREAU OF HIGHWAYS  
 DATE 5-17-88  
 CHIEF, BUREAU OF ENGINEERING  
 DATE  
 OFFICE OF PLANNING AND ZONING  
 DATE 5/20/88  
 CHIEF, DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT

REV. DATE	REV. NO.	REVISION DESCRIPTION
5/6/88	3	Removed Street Tree on Kingsbridge Rd
12-18-87	2	As Per DFM Comment #5
12-18-87	1	As Per Planning & Zoning Comment #13

**BURLEIGH MANOR**  
 2<sup>ND</sup> ELECTION DISTRICT  
 HOWARD COUNTY, MARYLAND  
 DEVELOPER  
 ROSE/RICHMOND JOINT VENTURE

PROJECT AREA  
 BURLEIGH MANOR  
 SECTION 3 AREA 3

PLAN AND PROFILE  
 KINGSBRIDGE ROAD

SCALE: 1"=50' DATE: 10-16-87

WHITMAN, REQUARDT AND ASSOCIATES  
 ENGINEERS  
 BALTIMORE, MARYLAND 21218

*Kenneth A. McCord*  
 KENNETH A. MCCORD  
 Registered Engineer  
 NO. 1974




**CURVE DATA**  
 KINGSBRIDGE ROAD

PI 0+00 to P.C.C. 3+50  
 $\Delta = 50^{\circ}08'02''$  Tan = 187.09'  
 $R = 400.00'$  Ch'd = 338.94'  
 Arc = 350.00' Ch'd Brg. =  $55^{\circ}27'11''$  W



P.C.C. 3+50 to Sta. 4+91.42  
 $\Delta = 10^{\circ}07'44''$  Tan = 70.90'  
 $R = 800.00'$  Ch'd = 141.24'  
 Arc = 141.42' Ch'd Brg. =  $58^{\circ}35'04''$  W

**CURVE DATA - MEDIAN & CURB**

CURVE	$\Delta$	RADIUS	Arc	Tan	Ch'd	Ch'd Brg.
1	$16^{\circ}10'59''$	140.00'	39.54'	11.90'	39.41'	$S31^{\circ}10'36''$ W
2	$12^{\circ}36'14''$	406.00'	89.31'	44.64'	89.13'	$S45^{\circ}34'12''$ W
3	$13^{\circ}59'00''$	194.00'	47.35'	23.77'	47.23'	$S58^{\circ}52'30''$ W
4		3.00'				
5	$10^{\circ}35'28''$	394.00'	72.83'	36.52'	72.73'	$S46^{\circ}17'13''$ W
6	$13^{\circ}23'10''$	3.00'	7.04'	7.13'	5.53'	$S71^{\circ}48'51''$ E
7	$31^{\circ}56'14''$	41.31'	23.03'	11.82'	22.73'	$S40^{\circ}12'04''$ W
8	$39^{\circ}06'00''$	40.00'	27.30'	14.20'	26.77'	$S43^{\circ}46'52''$ W
9	$28^{\circ}29'00''$	50.00'	24.86'	12.69'	24.60'	$N77^{\circ}34'22''$ E
10	$35^{\circ}38'57''$	49.47'	30.78'	15.91'	30.29'	$N73^{\circ}58'23''$ E
11	$20^{\circ}08'38''$	430.00'	151.18'	76.38'	150.40'	$S46^{\circ}05'51''$ W
12	$18^{\circ}44'17''$	370.00'	121.01'	61.05'	120.47'	$S46^{\circ}48'01''$ W





For continuation of Breconshire Road see sheet 2



1721

PLAN  
 SURVEYED  
 PLOTTED  
 NOTE BOOK  
 ALLOWANCE CHECKED  
 DATE



APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

*Walter D. ...* 5/16/88

Chief, Land Development Division

*Chauville W. ...* 5/16/88

Chief, Bureau of Highways

*...* 5-17-88

Chief, Bureau of Engineering

DATE

OFFICE OF PLANNING AND ZONING

*...* 5/20/88

Chief, Division of Community Planning and Land Development

REVISION	REV. NO.	DESCRIPTION
3/26/92	4	Remove all notes and details for 4 feet Pathway. Add Open Space Bollard Detail.
12/18/87	3	As per Planning / Zoning Comment #15
12/18/87	2	As per DPW Comments #1, #2
8/14/87	1	As per DPW Comment #4

BURLEIGH MANOR  
 2<sup>ND</sup> ELECTION DISTRICT  
 HOWARD COUNTY, MARYLAND  
 DEVELOPER  
 ROSE / RICHMOND JOINT VENTURE

PROJECT AREA  
 BURLEIGH MANOR  
 SECTION 3 AREA 3



PLAN AND PROFILE  
 NEWGATE COURT

SCALE: 1"=50' DATE: 10/16/87

WHITMAN, REQUARDT AND ASSOCIATES  
 ENGINEERS  
 BALTIMORE, MARYLAND 21218

*Kenneth A. McCord*  
 KENNETH A. MCCORD  
 Registered Engineer  
 NO. # 1974

No.	Type	Top El.	Inv. In.	Inv. Out.	Location	Remarks
I-1	A-5 Inlet width 2.5' Howard County Sta. 5 D 4.11	476.29		472.50	Inlet Linear Profile Sta. 1+21.50	
I-2	Type "D" Class "C" Howard County Sta. 5 D 4.11	467.50	458.78	458.60	See Plan and Profile	4 Sides Open Inlet Opening EL. 466.70
I-1B	Type "D" Class "C" Howard County Sta. 5 D 4.11	465.00	458.44	458.24	See Plan and Profile	2 Sides Open Inlet Opening EL. 464.20
I-3	A-5 Inlet width 2.5' Howard County Sta. 5 D 4.11	458.82	454.42	454.02	Inlet Linear Profile Sta. 1+10.46	





OPEN SPACE BOLLARD DETAIL  
 No Scale

PROFILE  
 SURVEYED  
 PLOTTED  
 NOTE BOOK  
 GRADES CHECKED  
 STRUCTURE NOTATIONS CHECKED  
 DATE

721


DESIGN SPEED  
30 MPH

LOCAL STREET Zoning = S.F.L.D.




OFFICE OF PLANNING AND ZONING  
*James R. Butte*  
 CHIEF, DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT  
 DATE 5/20/88

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
*W. H. ...*  
 CHIEF, LAND DEVELOPMENT DIVISION  
*W. H. ...*  
 CHIEF, BUREAU OF HIGHWAYS  
*W. H. ...*  
 CHIEF, BUREAU OF ENGINEERING





DESIGN SPEED  
30 MPH

LOCAL STREET Zoning = S.F.L.D.




**WHEEL CHAIR RAMP DETAIL**  
No Scale






Design Speed  
Not Applicable


CUL-DE-SAC Zoning = S.F.L.D.



**STANDARD 7" COMBINATION CURB & GUTTER**  
No Scale






**MODIFIED COMBINATION CURB & GUTTER**  
No Scale



Design Speed  
35 MPH

MINOR COLLECTOR Zoning = S.F.L.D.



12-18-87	2	AS PER DPW COMMENT # 3
12-18-87	1	AS PER PLANNING ZONING COMMENT # 15
REV. DATE	REV. NO.	REVISION DESCRIPTION

**BURLEIGH MANOR**  
 2nd ELECTION DISTRICT  
 HOWARD COUNTY, MARYLAND

DEVELOPER  
 ROSE / RICHMOND JOINT VENTURE

PROJECT AREA  
**BURLEIGH MANOR**  
 SECTION 3 AREA 3



PROJECT TITLE  
 ROADWAY AND STORMDRAIN DETAILS  
 SHEET 3 OF 15

SCALE: AS SHOWN DATE:

WHITMAN, REQUARDT AND ASSOCIATES  
 ENGINEERS  
 BALTIMORE, MARYLAND

*Kenneth A. McCord*  
 KENNETH A. MCCORD  
 REGISTERED ENGINEER NO. 1974

APPROVED HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
 DATE 5/13/88  
 CHIEF, LAND DEVELOPMENT DIVISION  
 DATE 5/16/88  
 CHIEF, BUREAU OF HIGHWAYS  
 DATE 5-17-88  
 CHIEF, BUREAU OF ENGINEERING  
 DATE 5/20/88  
 OFFICE OF PLANNING AND ZONING  
 CHIEF, DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT



REV DATE	REV NO.	REVISION DESCRIPTION
12-18-91	3	Remove Proposed SWM Pond Not to be Constructed
12-18-87	2	AS PER DPW COMMENT #7, #8, #15
12-18-87	1	AS PER PLANNING/ZONING COMMENTS

**BURLEIGH MANOR**  
 2nd ELECTION DISTRICT  
 HOWARD COUNTY, MARYLAND  
 OWNER AND DEVELOPER  
 RICHMOND AMERICAN

PROJECT AREA  
**BURLEIGH MANOR**  
 SECTION 3 AREA 3

PROJECT TITLE  
**DRAINAGE AREA MAP**




SHEET 6 OF 15  
 SCALE: 1" = 100' DATE: 10-16-87

WHITMAN, REQUARDT AND ASSOCIATES  
 ENGINEERS  
 BALTIMORE, MARYLAND

*Kenneth A. McCord*  
 KENNETH A. MCCORD  
 REGISTERED ENGINEER NO. 1974

122

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
 5/13/87  
 CHIEF, LAND DEVELOPMENT DIVISION DATE  
*Rowville W. Weisand* 5/16/88  
 CHIEF, BUREAU OF HIGHWAYS DATE  
*Richard E. Deane* 5-17-88  
 CHIEF, BUREAU OF ENGINEERS DATE  
 OFFICE OF PLANNING AND ZONING  
*Joseph R. Foster* 5/30/88  
 CHIEF, DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT DATE



**NOTE:**  
 The type of bedding used for storm drain pipe shall be Class C, shaped silograde. If rock is encountered, the invert should be overexcavated 6" and the overexcavation of 6" refilled with granular material.

12-16-87	1	AS PER PLANNING & ZONING COMMENT #13
REV. DATE	REV. NO.	REVISION DESCRIPTION
BURLEIGH MANOR 2ND. ELECTION DISTRICT HOWARD COUNTY, MARYLAND		
OWNER AND DEVELOPER RICHMOND AMERICAN		
PROJECT AREA: BURLEIGH MANOR SECTION-3 AREA - 3		
PROJECT TITLE: <b>STORM DRAIN PROFILES</b>		
SHEET 7 OF 15		
SCALE: AS SHOWN		DATE: 10-16-87
WHITMAN, REQUARDT AND ASSOCIATES ENGINEERS 2315 SAINT PAUL STREET BALTIMORE, MARYLAND 21218		
<i>Kenneth A. McCard</i> KENNETH A. MCCARD REGISTERED ENGINEER NO. 1974		


721

TRAP NO.	EXISTING DRAINAGE AREA (STRIPPING)	GRADED DRAINAGE AREA	TRAP DESIGNED FOR
1	3.0 Ac.	2.9 Ac.	2.0 Ac.
2	9.1 Ac.	7.6 Ac.	9.1 Ac.

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
*Phillip H. F-138*  
 CHIEF, LAND DEVELOPMENT DIVISION DATE 5/16/88  
 CHIEF, BUREAU OF HIGHWAYS DATE 5-17-88  
 CHIEF, BUREAU OF ENGINEERING DATE  
 OFFICE OF PLANNING AND ZONING  
*James R. Bate* 5/20/88  
 CHIEF, DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT DATE

**SEQUENCE OF CONSTRUCTION**

1. OBTAIN GRADING PERMIT.
2. CLEAR AND GRUB FOR SEDIMENT AND EROSION CONTROL MEASURES OR DEVICES ON EAST SIDE OF RIDGE LINE.
3. INSTALL AND STABILIZE ALL SEDIMENT AND EROSION CONTROL MEASURES AND DEVICES ON EAST SIDE OF RIDGE LINE.
4. STRIP AND ROUGH GRADE LIMITS OF CONSTRUCTION ON EAST SIDE OF RIDGE LINE.
5. SEED ALL SLOPES WITH TEMPORARY SEEDING, SEE SEEDING NOTES ON SHEET 10 OF 11.
6. CONSTRUCT ALL UTILITIES.
7. FINE GRADE PAVED AREAS ON NEWGATE COURT AND BRECONSHIRE ROAD. CONSTRUCT CURB AND GUTTER AND PAVED AREAS ON NEWGATE COURT AND BRECONSHIRE ROAD.
8. SEED DISTURBED AREAS WITHIN RIGHT OF WAY, SEE PERMANENT SEEDING NOTES ON SHEET 10 OF 11.
9. STABILIZE SITE AS PER TEMPORARY SEEDING SPECIFICATIONS, SEE NOTES ON SHEET 10 OF 11.
10. REMOVE TEMPORARY SEDIMENT CONTROL MEASURES WHEN TEMPORARY SEEDING HAS BEEN ESTABLISHED (EXCEPT FOR SEDIMENT TRAP #2). STABILIZE ANY REMAINING AREAS.
11. CLEAR AND GRUB FOR SEDIMENT AND EROSION CONTROL MEASURES OR DEVICES AND TEMPORARY STORM WATER MANGEMENT POND ON WEST SIDE OF RIDGE LINE.
12. INSTALL AND STABILIZE ALL SEDIMENT AND EROSION CONTROL MEASURES OR DEVICES AND STORMWATER MANGEMENT POND ON WEST SIDE OF RIDGE LINE.
13. STRIP AND ROUGH GRADE LIMITS OF CONSTRUCTION.
14. SEED ALL SLOPS WITH TEMPORARY SEEDING, SEE SEEDING NOTES ON SHEET 10 OF 11.
15. CONSTRUCT CULVERT AT STA. 4+52 KINGSBRIDGE ROAD.
16. FINE GRADE PAVED AREAS. CONSTRUCT CURB AND GUTTER AND PAVED AREAS.
17. SEED DISTURBED AREAS WITHIN RIGHT OF WAY, SEE PERMANENT SEEDING NOTES ON SHEET 10 OF 11.
18. STABILIZE SITE AS PER PERMANENT SEEDING SPECIFICATION, SEE NOTES ON SHEET 10 OF 11.
19. REMOVE TEMPORARY SEDIMENT CONTROL MEASURES WHEN TEMPORARY SEEDING HAS BEEN ESTABLISHED WEST SIDE OF RIDGE LINE.
20. CONVERT SEDIMENT TRAP #1 TO TEMPORARY STORMWATER MANGEMENT POND.
21. STABILIZE ANY REMAINING AREAS.




STORMWATER MANAGEMENT FOR THIS PROJECT HAS BEEN PROVIDED IN BURLEIGH MANOR SECTION 1 AREA 1, F-79-93 AND SECTION 3 AREA 4, F-88-

12-18-87	1	As per Planning/Zoning Comment #13
REV DATE	REV NO	REVISION / DESCRIPTION
<b>BURLEIGH MANOR</b> 2nd ELECTION DISTRICT HOWARD COUNTY, MARYLAND		
DEVELOPER <b>ROSE / RICHMOND JOINT VENTURE</b>		
PROJECT AREA <b>BURLEIGH MANOR</b> SECTION 3 AREA 3		
PROJECT TITLE <b>DRAINAGE AREA MAP</b> <b>FOR SEDIMENT CONTROL</b>		
SCALE 1" = 100' DATE 10-16-87		
WHITMAN, REQUARDT AND ASSOCIATES ENGINEERS BALTIMORE, MARYLAND		
<i>Kenneth A. McCord</i> KENNETH A. MCCORD REGISTERED ENGINEER NO. 1974		

721





APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
 5-18-87  
 CHIEF, LAND DEVELOPMENT DIVISION DATE  
*James W. Williams* 5/16/87  
 CHIEF, BUREAU OF HIGHWAY DATE  
*James W. Williams* 5-17-87  
 CHIEF, BUREAU OF ENGINEERING DATE  
 OFFICE OF PLANNING  
*James W. Williams* 5/20/87  
 CHIEF, DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT DATE

Reviewed for *Howard S.C.D.*  
 and meets Technical Requirements  
*James W. Williams*  
 Signature  
 U.S. Soil Conservation Service  
 Approved *Howard S.C.D.* Date

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.  
*Howard S.C.D.*  
 Approved *Howard S.C.D.* Date

**DESIGN DATA FOR SEDIMENT TRAP #2**

Drainage Area	9.1 Ac
Disturbed Area	6.9 Ac
Volume Required	9,100 CY
Volume Available	617
Top of Berm Elev.	456.0
Weir Crest Elev.	455.0
Length of Weir	12
Storage Elev.	454.0
Bottom Trap Elev.	449.0

**DESIGN DATA FOR SEDIMENT TRAP #1**

Drainage Area	3.04 Ac
Disturbed Area	1.04 Ac
Volume Required	3,040 CY
Volume Available	215 CY
Top of Berm Elev.	475.0
Weir Crest Elev.	473.5
Length of Weir	12
Storage Elev.	472.5
Bottom Trap Elev.	471.0

NOTE: Sediment Control for the Stormwater Management Pond is provided in the Stormwater Management Plan, F-88-97.

12-18-87	3	As per Soil Conservation Dist. Comment #11
12-18-87	2	As per DPW Comments #15
12-18-87	1	As per Planning/Zoning Comment #12
REV DATE	REV NO.	REVISION DESCRIPTION

**BURLEIGH MANOR**  
 2nd ELECTION DISTRICT  
 HOWARD COUNTY, MARYLAND

DEVELOPER  
 ROSE/RICHMOND JOINT VENTURE

PROJECT AREA  
 BURLEIGH MANOR  
 SECTION 3 AREA 3

PROJECT TITLE  
 GRADING & SEDIMENT CONTROL PLAN  
 SHEET 9 OF 15

SCALE 1"=50' DATE 10/16/87

WHITMAN, REQUARDT AND ASSOCIATES  
 ENGINEERS  
 BALTIMORE, MARYLAND

*Kenneth A. McCord*  
 KENNETH A. MCCORD  
 REGISTERED ENGINEER NO. 1974

**CERTIFICATION BY THE DEVELOPER**

"I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF NATURAL RESOURCES APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT."

*David L. Carney*  
 DAVID L. CARNEY  
 10/16/87  
 DATE

**CERTIFICATION BY THE ENGINEER**

"I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION, AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT."

*Kenneth A. McCord*  
 KENNETH A. MCCORD, P.E. NO. 1974  
 10/16/87  
 DATE

**PERMANENT SEEDING NOTES**

Apply to graded or cleared areas not subject to immediate further disturbance where a permanent long-lived vegetative cover is needed.

**Seedbed Preparation:** Loosen upper three inches of soil by raking, discing or other acceptable means before seeding.

**Soil Amendments:** In lieu of soil test recommendations, use one of the following schedules

- 1) Preferred - Apply 2 tons per acre dolomitic limestone (92 lbs/1000 square ft) and 600 lbs per acre 10-10-10 fertilizer (14 lbs/1000 sq ft) before seeding. Harrow or disc into upper three inches of soil. At time of seeding, apply 400 lbs per acre 30-0-0 ureaform fertilizer (9 lbs/1000 sq ft).
- 2) Acceptable - Apply 2 tons per acre dolomitic limestone (92 lbs/1000 sq ft) and 1000 lbs per acre 10-10-10 fertilizer (23 lbs/1000 sq ft) before seeding. Harrow or disc into upper three inches of soil.

**Seeding -** For the periods March 1 thru April 30, and August 1 thru October 15, seed with 60 lbs per acre (1.4 lbs/1000 sq ft) of Kentucky 31 Tall Fescue. For the period May 1 thru July 31, seed with 60 lbs Kentucky 31 Tall Fescue per acre and 2 lbs per acre (.05 lbs/1000 sq ft) of weeping lovegrass. During the period of October 16 thru February 28, protect site by: Option (1) 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring. Option (2) Use sod. Option (3) Seed with 60 lbs/acre Kentucky 31 Tall Fescue and mulch with 2 tons/acre well anchored straw.

**Mulching -** Apply 1 1/2 to 2 tons per acre (70 to 90 lbs/1000 sq ft) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gallons per acre (5 gal/1000 sq ft) of emulsified asphalt on flat areas. On slopes 8 feet or higher, use 348 gallons per acre (8 gal/1000 sq ft) for anchoring.

**Maintenance -** Inspect all seeded areas and make needed repairs, replacements and reseeding.

**TEMPORARY SEEDING NOTES**

Apply to graded or cleared areas likely to be redisturbed where a short-term vegetative cover is needed.

**Seedbed Preparation:** Loosen upper three inches of soil by raking, discing or other acceptable means before seeding.

**Soil Amendments:** Apply 600 lbs per acre 10-10-10 fertilizer (14 lbs/1000 sq ft)

**Seeding -** For periods March 1 thru April 30 and from August 15 thru November 15, seed with 2 1/2 bushel per acre of annual rye (3.2 lbs/1000 sq ft). For the period May 1 thru August 14, seed with 3 lbs per acre of weeping lovegrass (.07 lbs/1000 sq ft). For the period November 16 thru February 28, protect site by applying 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring, or use sod.






**Mulching:** Apply 1 1/2 to 2 tons per acre (70 to 90 lbs/1000 sq ft) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gal per acre (5 gal/1000 sq ft) of emulsified asphalt on flat areas. On slopes, 8 ft or higher, use 348 gal per acre (8 gal/1000 sq ft) for anchoring.

Refer to the 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for rate and methods not covered.

**SEDIMENT CONTROL NOTES**

- 1) A minimum of 24 hours notice must be given to the Howard County Office of Inspection and Permits prior to the start of any construction. (992-2437)
- 2) All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL.
- 3) Following initial soil disturbance or redisturbance, permanent or temporary stabilization shall be completed within: a) 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all slopes greater than 3:1, b) 14 days as to all other disturbed or graded areas on the project site.
- 4) All sediment traps/basins shown must be fenced and warning signs posted around their perimeter in accordance with Vol. 1, Chapter 12, of the HOWARD COUNTY DESIGN MANUAL, Storm Drainage.
- 5) All disturbed areas must be stabilized within the time period specified above in accordance with the 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for permanent seedings (Sec. 51) sod (Sec. 54), temporary seeding (Sec. 50) and mulching (Sec. 52.) Temporary stabilization with mulch alone can only be done when recommended seeding dates do not allow for proper germination and establishment of grasses.
- 6) All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.
- 7) Site Analysis:
 

Total Area of Site	10 <sup>±</sup> Acres
Area Disturbed	5.5 <sup>±</sup> Acres
Area to be roofed or paved	1.5 <sup>±</sup> Acres
Area to be vegetatively stabilized	4.2 <sup>±</sup> Acres
Total Cut	2,200 <sup>±</sup> Cu. yds.
Total Fill	11,200 <sup>±</sup> Cu. yds.
Offsite waste/borrow area location	
- 8) Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
- 9) Additional sediment controls must be provided, if deemed necessary by the Howard County DPW sediment control inspector.
- 10) On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the inspection agency is made.



APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
 Chief, Land Development Division  
 DATE: 5/16/88  
 Chief, Bureau of Highways  
 DATE: 5-17-88  
 Chief, Bureau of Engineering  
 DATE:

OFFICE OF PLANNING  
 Chief, Division of Community Planning and Land Development  
 DATE: 5/20/88



CERTIFICATION BY THE ENGINEER  
 I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.  
 Kenneth A. McCord  
 10/16/87  
 DATE

CERTIFICATION BY THE DEVELOPER  
 I CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT AND PLAN FOR EROSION AND SEDIMENT CONTROL AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPT. OF NATURAL RESOURCES APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT OR THEIR AUTHORIZED AGENTS, AS ARE DEEMED NECESSARY.  
 Kenneth A. McCord  
 10/29/87  
 DATE


REVIEWED FOR HOWARD COUNTY S.C.D. AND MEETS TECHNICAL REQUIREMENTS.  
 James M. Helm  
 4-26-88  
 DATE  
 U.S. SOIL CONSERVATION SERVICE

12-18-87	1	As per Planning Zoning comment #13
REV. DATE	REV. NO.	REVISION DESCRIPTION
<b>BURLEIGH MANOR</b> 2nd ELECTION DISTRICT HOWARD COUNTY, MARYLAND		
DEVELOPER ROSE / RICHMOND JOINT VENTURE		
PROJECT AREA BURLEIGH MANOR SECTION 3 AREA 3		
PROJECT TITLE SEDIMENT CONTROL DETAILS		
SHEET 10 OF 15		SCALE: NO SCALE
		DATE: 10-16-87
WHITMAN, REQUARDT AND ASSOCIATES ENGINEERS BALTIMORE, MARYLAND		
APPROVED: Kenneth A. McCord 10/16/87 DATE		Kenneth A. McCord REGISTERED ENGINEER NO. 1974

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
 CHIEF, LAND DEVELOPMENT DIVISION DATE 5/16/88  
*Drayville W. Weiland*  
 CHIEF, BUREAU OF HIGHWAYS DATE  
*William S. Day* 5-11-88  
 CHIEF, BUREAU OF ENGINEERING DATE  
 OFFICE OF PLANNING AND ZONING  
*James M. Helm* 5/30/88  
 CHIEF, DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT DATE



- CONSTRUCTION SPECIFICATIONS FOR ST-VI**
- The area under embankment shall be cleared, grubbed and stripped of any vegetation and root mat. The pool area shall be cleared.
  - The fill material for the embankment shall be free of roots or other woody vegetation as well as over-sized stones, rocks, organic material or other objectionable material. The embankment shall be compacted by traversing with equipment while it is being constructed. Maximum height of embankment shall be five (5) feet, measured at centerline of embankment.
  - All fill slopes shall be 2:1 or flatter; cut slopes 1:1 or flatter.
  - Elevation of the top of any dike directing water into trap must equal or exceed the height of embankment.
  - Storage area provided shall be figured by computing the volume available behind the outlet channel up to an elevation of one (1) foot below the level weir crest.
  - Filter cloth shall be placed over the bottom and sides of the outlet channel prior to placement of stone. Sections of fabric must overlap at least one (1) foot with section nearest the entrance existing on top. Fabric shall be embedded at least six (6) inches into existing ground at entrance of outlet channel.
  - Stone used in the outlet channel shall be four (4) to eight (8) inches (riprap). To provide a filtering effect, a layer of filter cloth shall be embedded one (1) foot back into the upstream face of the outlet stone or one (1) foot thick layer of two (2) inch or finer aggregate shall be placed on the upstream face of the outlet.
  - Sediment shall be removed and trap restored to its original dimensions when the sediment has accumulated to 1/2 the design depth of the trap. Removed sediment shall be deposited in a suitable area and in such a manner that it will not erode.
  - The structure shall be inspected after each rain and repaired as needed.
  - Construction operations shall be carried out in such a manner that erosion and water pollution are minimized.
  - The structure shall be removed and the area stabilized when the drainage area has been properly stabilized.
  - Drainage area for this practice is limited to 15 acres or less.



CERTIFICATION BY THE DEVELOPER  
 I WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT AND PLAN FOR EROSION AND SEDIMENT CONTROL AND THAT ALL EMPLOYED PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPT. OF NATURAL RESOURCES APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT OR THEIR AUTHORIZED AGENTS, AS ARE DEEMED NECESSARY.

*James M. Helm* 4/26/88  
 U.S. SOIL CONSERVATION SERVICE

CERTIFICATION BY THE ENGINEER  
 I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

*Kenneth A. McCord* 10/16/87  
 KENNETH A. MCCORD

*James M. Helm* 10/29/87  
 DATE

REVIEWED FOR HOWARD COUNTY S.C.D. AND MEETS TECHNICAL REQUIREMENTS.

*Stephen L. ...*  
 APPROVED: *Stephen L. ...*  
 REGISTERED ENGINEER NO. 1974

12-18-87	1	As per Planning/Zoning comment #13
REV. DATE	REV. NO.	REVISION DESCRIPTION
<b>BURLEIGH MANOR</b>		
2nd ELECTION DISTRICT		
HOWARD COUNTY, MARYLAND		
DEVELOPER		
ROSE / RICHMOND JOINT VENTURE		
PROJECT AREA		
BURLEIGH MANOR		
SECTION 3 AREA 3		
PROJECT TITLE		
SEDIMENT CONTROL		
DETAILS		
SHEET 11 OF 15		
SCALE: NO SCALE		
DATE: 10-16-87		
WHITMAN, REQUARDT AND ASSOCIATES		
ENGINEERS		
BALTIMORE, MARYLAND		
REGISTERED ENGINEER NO. 1974		

127

STORMWATER MANAGEMENT DATA @ POND					INTERIM STORMWATER MANAGEMENT DATA @ POND					
STORM	Qi	Qout	Vs	Vr	ELEVATION	Qi	Qout	Vs	Vr	ELEVATION
	(cfs)	(cfs)	(Acft)	(Acft)	(ft)	(cfs)	(cfs)	(Acft)	(Acft)	(ft)
2	0.64	0.11	0.04	0.06	472.04	0.98	0.14	0.05	0.08	472.82
10	2.84	0.38	0.20	0.25	473.52	2.69	0.90	0.12	0.22	473.57
100	6.09	4.01	0.20	0.52	473.84	4.87	3.70	0.13	0.41	473.81

STORMWATER MANAGEMENT DATA @ DESIGN POINT			INTERIM STORMWATER MANAGEMENT DATA @ DESIGN POINT		
STORM	Qpre	Qpost	Qpre	Qpost	
	(cfs)	(cfs)	(cfs)	(cfs)	
2	0.38	0.31	0.38	0.38	
10	2.34	0.71	2.34	1.52	
100	5.58	4.14	5.58	6.27	



  

**MISCELLANEOUS DATA**

POND DRAINAGE AREA (AREA 1) = 3.05 AC.  
DESIGN POINT DRAINAGE AREA (AREAS 1 AND 2) = 3.24 AC.  
PREDEVELOPMENT CN TO DESIGN POINT = 56.8  
POSTDEVELOPMENT CN TO POND - - - = 61.3  
POSTDEVELOPMENT CN TO DESIGN POINT = 62.3  
NOTE: SEE DESIGN REPORT FOR OTHER PERTINENT DATA.

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
*[Signature]* (F-88)  
CHIEF, LAND DEVELOPMENT DIVISION DATE  
*Bronville W. Williams* 5/16/88  
CHIEF, BUREAU OF HIGHWAYS DATE  
*[Signature]* 5-17-88  
CHIEF, BUREAU OF ENGINEERING DATE

OFFICE OF PLANNING  
*[Signature]* 5/20/88  
CHIEF, DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT DATE



TEST PIT NUMBER	SAMPLE	DEPTH (FEET)	VISUAL CLASSIFICATION (UNIFIED)	WATER CONTENT
33	1.5' Below Grade		Brown Silty Clay, Trace of Sand (CL)	26.4
	3.0' Below Grade		Brown Micaceous Sandy Silt (ML)	36.9
	4.5' Below Grade		Gray-Brown Micaceous Silty Sand (SM)	21.7
	10.5' Below Grade		Yellow-Brown Sandy Silty Clay (CL) Max. Dry Density 113.3 Optimum Moisture 17.4%	-
34	1.0' Below Grade		Brown Silty Clay, Trace of Sand (CL)	24.5
	3.0' Below Grade		Red-Brown Micaceous Silty Sand (SM)	21.3
	6.0' Below Grade		Yellow-Brown Silty Sand With Gravel (SM)	16.7
	10.0' Below Grade		Light Brown Micaceous Silty Sand (SM) Max. Dry Density 112.2 Optimum Moisture 15.4%	-

REV. DATE	REV. NO.	REVISION DESCRIPTION
12-18-91	1	Removed Proposed SWM Structure
1-22-88	2	PER SCS COMMENTS, 1-21-88
1-6-88	1	CHANGED PRINCIPAL SPILLWAY AND DETAILS

**BURLEIGH MANOR**  
2nd ELECTION DISTRICT  
HOWARD COUNTY, MARYLAND

DEVELOPER  
ROSE / RICHMOND JOINT VENTURE

PROJECT AREA  
BURLEIGH MANOR  
SECTION 3 AREA 3

PROJECT TITLE  
**STORMWATER MANAGEMENT**  
SHEET 12 OF 15  
SCALE AS SHOWN DATE 2-27-87

WHITMAN, REQUARDT AND ASSOCIATES  
ENGINEERS  
BALTIMORE, MARYLAND

*Kenneth A. McCord*  
REGISTERED ENGINEER NO 1974


721  
*[Signature]* 4/26/89  
U.S. SOIL CONSERVATION SERVICE DATE

THESE PLANS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.  
APPROVED: *[Signature]* 4/26/89  
HOWARD S.C.D. DATE

**RESPONSIBLE PERSONNEL CERTIFICATION**  
"I HEREBY CERTIFY THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF NATURAL RESOURCES APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT."  
*[Signature]* 10/29/87  
DAVID L. CARNEY DATE

**CERTIFICATION BY THE DEVELOPER**  
"I CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS OF DEVELOPMENT, POND CONSTRUCTION AND EROSION AND SEDIMENT CONTROL. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT OR THEIR AUTHORIZED AGENTS, AS ARE DEEMED NECESSARY DEVIATION FROM THIS PLAN WILL NOT BE MADE UNLESS AUTHORIZED BY THE HOWARD SOIL CONSERVATION DISTRICT. I WILL PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH A RED-LINED "AS-BUILT" OF THE POND WITHIN 30-DAYS OF COMPLETION."  
*[Signature]* 10/29/87  
DAVID L. CARNEY DATE

**CERTIFICATION BY THE ENGINEER**  
"I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION, AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE MUST PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH A RED-LINED "AS-BUILT" OF THE POND WITHIN 30-DAYS OF COMPLETION."  
*[Signature]* 10/30/87  
KENNETH A. MCCORD, P.E. NO. 1974 DATE




Howard County  
Board of Education  
6/4/608



Proposed  
Burleigh Manor  
Section 2  
Gerald M. Katz and Thomas Pellerito  
9/43/646

Proposed 20' Drainage Easement.  
Pond not constructed.  
SWM Provided in Section 1 Area 1 (F 79-93)  
And Section 3 Area 2 (F 81-180)

Note: See the Stormwater Management  
Report for the contributing drainage  
area boundaries for each stage  
of construction. See Sheet 14 of 15  
for Section Details.



- NOTES:
1. INVERT SHALL BE BRICK.
  2. TOP 1" OF WALLS SHALL BE BRICK, MASONRY.
  3. WHERE DEPTH IS 3'-6" OR GREATER STANDARD MANHOLE STEPS SHALL BE INSTALLED AS SHOWN.
  4. MAXIMUM VERTICAL DEPTH OF INLET SHALL BE 8'-0"




TYPE 'D' INLET  
NO SCALE


APPROVED HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
CHIEF, LAND DEVELOPMENT DIVISION  
*Gerrit W. Weisand* 5/16/88 DATE  
CHIEF, BUREAU OF HIGHWAY  
*James R. Reed* 5-11-88 DATE  
CHIEF, BUREAU OF ENGINEERING  
OFFICE OF PLANNING  
*James R. Reed* 5/20/88 DATE  
CHIEF, DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT

SEQUENCE OF CONSTRUCTION

1. Obtain Grading Permit.
2. Clear for Sediment Control Devices.
3. Install all Sediment Control Devices.
4. Construct Storm Water Management Pond and Permanent Ditch.
5. Stabilize all Disturbed areas.
6. The Pond is now ready to function as a Sediment Basin and shall remain as such until all Contributing Drainage areas have been stabilized and permission for further construction has been obtained from the Howard County Sediment Control Inspector.
7. Clean Sediment from Basin. The Basin is ready for permanent Storm Water Management.
8. Remove any remaining Sediment Control Devices.




STORM DRAIN PROFILE  
Scales: Hor: 1"=50'  
Vert: 1"=5'




PLAN DETAIL AT S-1

PLAN  
Scale: 1"=50'




CORE TRENCH DETAIL  
No Scale


The core trench shall be constructed with the most impervious material on site.



EMERGENCY SPILLWAY PROFILE  
Scales: Hor: 1"=50'  
Vert: 1"=5'



DAM CENTER LINE PROFILE  
Scales: Hor: 1"=50'  
Vert: 1"=5'



PRINCIPAL SPILLWAY AND EXIT CHANNEL PROFILE  
SCALE: HOR: 1"=20'  
VER: 1"=5'

REV DATE	REV NO	REVISION DESCRIPTION
12-18-91	1	Remove Proposed SWM Pond
1-22-88	2	Per SC5 Comments, 1-21-88
1-6-88	1	Changed Principal Spillway and Details

**BURLEIGH MANOR**  
2nd ELECTION DISTRICT  
HOWARD COUNTY, MARYLAND  
DEVELOPER  
ROSE/RICHMOND JOINT VENTURE

PROJECT AREA  
BURLEIGH MANOR  
SECTION 3 AREA 3

PROJECT TITLE  
STORMWATER MANAGEMENT  
PLAN AND PROFILES  
SHEET 13 OF 15

SCALE AS SHOWN DATE 10/30/87

WHITMAN, REQUARDT AND ASSOCIATES  
ENGINEERS  
BALTIMORE, MARYLAND

*Jennett Q. McLeod*  
REGISTERED ENGINEER NO 1974  
DATE 10/30/87

721  
*James M. Selman*  
U.S. SOIL CONSERVATION SERVICE  
DATE 4/26/88

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION. SOIL EROSION AND SEDIMENT CONTROL.  
APPROVED: *Stephen L. Smith*  
HOWARD S.C.D. DATE 4/26/88

RESPONSIBLE PERSONNEL CERTIFICATION  
"I HEREBY CERTIFY THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF NATURAL RESOURCES APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT."  
*James M. Selman*  
DATE 10/29/87

CERTIFICATION BY THE DEVELOPER  
"I CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS OF DEVELOPMENT. POND CONSTRUCTION AND EROSION AND SEDIMENT CONTROL. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT OR THEIR AUTHORIZED AGENTS. AS ARE DEEMED NECESSARY DEVIATION FROM THIS PLAN WILL NOT BE MADE UNLESS AUTHORIZED BY THE HOWARD SOIL CONSERVATION DISTRICT. I WILL PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH A RED-LINED "AS-BUILT" OF THE POND WITHIN 30-DAYS OF COMPLETION."  
*James M. Selman*  
DATE 10/29/87

CERTIFICATION BY THE ENGINEER  
"I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION, AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE MUST PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH A RED-LINED "AS-BUILT" OF THE POND WITHIN 30-DAYS OF COMPLETION."  
*Jennett Q. McLeod*  
REGISTERED ENGINEER NO 1974  
DATE 10/30/87

SOIL CONSERVATION SERVICE  
MARYLAND  
CONSTRUCTION SPECIFICATIONS  
FOR PONDS

THESE SPECIFICATIONS ARE APPROPRIATE TO PONDS WITHIN THE SCOPE OF THE STANDARD FOR PRACTICE 378.

I. SITE PREPARATION

AREAS DESIGNATED FOR BORROW AREAS, EMBANKMENT, AND STRUCTURAL WORKS SHALL BE CLEARED, GRUBBED AND STRIPPED OF TOPSOIL. ALL TREES, VEGETATION, ROOTS, AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED. CHANNEL BANKS AND SHARP BREAKS SHALL BE SLOPED TO NO STEEPER THAN 1:1.  
AREAS TO BE COVERED BY THE POND OR RESERVOIR WILL BE CLEARED OF ALL TREES, BRUSH, LOGS, FENCES, RUBBISH AND OTHER OBJECTIONABLE MATERIAL UNLESS OTHERWISE DESIGNATED ON THE PLANS. TREES, BRUSH AND STUMPS SHALL BE CUT APPROXIMATELY LEVEL WITH THE GROUND SURFACE.  
ALL CLEARED AND GRUBBED MATERIAL SHALL BE DISPOSED OF OUTSIDE AND BELOW THE LIMITS OF THE DAM AND RESERVOIR AS DIRECTED BY THE OWNER OR HIS REPRESENTATIVE. WHEN SPECIFIED, A SUFFICIENT QUANTITY OF TOPSOIL WILL BE STOCKPILED IN A SUITABLE LOCATION FOR USE ON THE EMBANKMENT AND OTHER DESIGNATED AREAS.

II. EARTH FILL

**MATERIAL**  
THE FILL MATERIAL SHALL BE TAKEN FROM APPROVED DESIGNATED BORROW AREA OR AREAS. IT SHALL BE FREE OF ROOTS, STUMPS, WOOD, RUBBISH, OVERSIZE STONES, FROZEN OR OTHER OBJECTIONABLE MATERIALS. THE EMBANKMENT SHALL BE CONSTRUCTED TO AN ELEVATION WHICH PROVIDES FOR ANTICIPATED SETTLEMENT TO THE DESIGN ELEVATION. THE FILL HEIGHT ALL ALONG THE LENGTH OF THE EMBANKMENT SHALL BE INCREASED ABOVE THE DESIGN ELEVATION (INCLUDING FREEBOARD) AS SHOWN ON THE PLANS.

**PLACEMENT**  
AREAS ON WHICH FILL IS TO BE PLACED SHALL BE SCARIFIED PRIOR TO PLACEMENT OF FILL. FILL MATERIALS SHALL BE PLACED IN 8-INCH MAXIMUM THICKNESS (BEFORE COMPACTION) LAYERS WHICH ARE TO BE CONTINUOUS OVER THE ENTIRE LENGTH OF THE FILL. THE MOST POROUS BORROW MATERIAL SHALL BE PLACED IN THE DOWNSTREAM PORTIONS OF THE EMBANKMENT.

**COMPACTION**  
THE MOVEMENT OF THE HAULING AND SPREADING EQUIPMENT OVER THE FILL SHALL BE CONTROLLED SO THAT THE ENTIRE SURFACE OF EACH LIFT SHALL BE TRAVERSED BY NOT LESS THAN ONE TREAD TRACK OF THE EQUIPMENT OR COMPACTION SHALL BE ACHIEVED BY A MINIMUM OF FOUR COMPLETE PASSES OF A SHEEPSFOOT, RUBBER TIERED OR VIBRATORY ROLLER. FILL MATERIAL SHALL CONTAIN SUFFICIENT MOISTURE SUCH THAT THE REQUIRED DEGREE OF COMPACTION CAN BE OBTAINED WITH THE EQUIPMENT USED. WHERE A MINIMUM REQUIRED DENSITY IS SPECIFIED, EACH LAYER OF FILL SHALL BE COMPACTED AS NECESSARY TO OBTAIN THAT DENSITY AND IS TO BE CERTIFIED BY THE ENGINEER.

**CUTOFF TRENCH**  
WHERE SPECIFIED, A CUTOFF TRENCH SHALL BE EXCAVATED ALONG OR PARALLEL TO THE CENTERLINE OF THE EMBANKMENT AS SHOWN ON THE PLANS. THE BOTTOM WIDTH OF THE TRENCH SHALL BE AS SHOWN ON THE DRAWINGS, WITH THE MINIMUM WIDTH BEING FOUR FEET. THE DEPTH SHALL BE AT LEAST FOUR FEET OR AS SHOWN ON THE PLANS. THE SIDE SLOPES OF THE TRENCH SHALL BE 1 TO 1 OR FLATTER. THE BACKFILL MATERIAL FOR THE CUTOFF TRENCH SHALL BE THE MOST IMPERVIOUS MATERIAL AVAILABLE AND SHALL BE COMPACTED WITH EQUIPMENT OR ROLLER TO ASSURE MAXIMUM DENSITY AND MINIMUM PERMEABILITY.

III. STRUCTURAL BACKFILL

BACKFILL MATERIAL SHALL BE OF THE TYPE AND QUALITY CONFORMING TO THAT SPECIFIED FOR THE ADJOINING FILL MATERIAL. THE FILL SHALL BE PLACED IN HORIZONTAL LAYERS NOT TO EXCEED FOUR INCHES IN THICKNESS AND COMPACTED BY HAND TAMPERS OR OTHER COMPACTION EQUIPMENT. THE MATERIAL NEEDS TO FILL COMPLETELY ALL SPACES UNDER AND ADJACENT TO THE PIPE. AT NO TIME DURING THE BACKFILLING OPERATION SHALL DRIVEN EQUIPMENT BE ALLOWED TO OPERATE CLOSER THAN FOUR FEET, MEASURED HORIZONTALLY, TO ANY PART OF A STRUCTURE. UNDER NO CIRCUMSTANCES SHALL EQUIPMENT BE DRIVEN OVER ANY PART OF A CONCRETE STRUCTURE OR PIPE UNLESS THERE IS A COMPACTED FILL OF TWENTY-FOUR INCHES OR GREATER OVER THE STRUCTURE OR PIPE.

IV. PIPE CONDUITS

ALL PIPES SHALL BE CIRCULAR IN CROSS SECTION.

A. CORRUGATED METAL PIPE

- MATERIALS - (STEEL PIPE)** - THIS PIPE AND ITS APPURTENANCES SHALL BE GALVANIZED AND FULLY BITUMINOUS COATED AND SHALL CONFORM TO THE REQUIREMENTS OF AASHTO SPECIFICATION M-190 TYPE A WITH WATERTIGHT COUPLING BANDS. ANY BITUMINOUS COATING DAMAGED OR OTHERWISE REMOVED SHALL BE REPLACED WITH COLD APPLIED BITUMINOUS COATING COMPOUND. STEEL PIPES WITH POLYMERIC COATINGS SHALL HAVE A MINIMUM COATING THICKNESS OF 0.01 INCH (10 MIL) ON BOTH SIDES OF THE PIPE. THE FOLLOWING COATINGS ARE COMMERCIALY AVAILABLE: NEXON, PLASTI-COTE, BLAC-KLAD, AND BETH-CU-LOY. COATED CORRUGATED STEEL PIPE SHALL MEET THE REQUIREMENTS OF AASHTO M-245 AND M-246.
- MATERIALS - (ALUMINIZED STEEL PIPE)** - THIS PIPE AND ITS APPURTENANCES SHALL CONFORM TO THE REQUIREMENTS OF AASHTO SPECIFICATION M-274-791 WITH WATERTIGHT COUPLING BANDS OR FLANGES.
- MATERIALS - (ALUMINUM PIPE)** - THIS PIPE AND ITS APPURTENANCES SHALL CONFORM TO THE REQUIREMENTS OF AASHTO SPECIFICATION M-196 OR M-211 WITH WATERTIGHT COUPLING BANDS OR FLANGES. COUPLING BANDS, ANTI-SEEP COLLARS, END SECTIONS, ETC. MUST BE COMPOSED OF THE SAME MATERIAL AS THE PIPE. METALS MUST BE INSULATED FROM DISSIMILAR MATERIALS WITH USE OF RUBBER OR PLASTIC INSULATING MATERIALS AT LEAST 24 MILS IN THICKNESS. ALUMINUM SURFACES THAT ARE TO BE IN CONTACT WITH CONCRETE SHALL BE PAINTED WITH ONE COAT OF ZINC CHROMATE PRIMER. HOT DIP GALVANIZED BOLTS MAY BE USED FOR CONNECTIONS. THE PH OF THE SURROUNDING SOILS SHALL BE LESS THAN 9 AND GREATER THAN 4.
- CONNECTIONS** - ALL CONNECTIONS WITH PIPES MUST BE COMPLETELY WATERTIGHT. THE DRAIN PIPE OR BARREL CONNECTION TO THE RISER SHALL BE WELDED ALL AROUND WHEN THE PIPE AND RISER ARE METAL. WATERTIGHT COUPLING BANDS OR FLANGES SHALL BE USED AT ALL JOINTS ANTI-SEEP COLLARS SHALL BE CONNECTED TO THE PIPE IN SUCH A MANNER AS TO BE COMPLETELY WATERTIGHT. DIMPLE BANDS ARE NOT CONSIDERED TO BE WATERTIGHT.
- BEDDING** - THE PIPE SHALL BE FIRMLY AND UNIFORMLY BEDDED THROUGHOUT ITS ENTIRE LENGTH. WHERE ROCK OR SOFT, SPONGY OR OTHER UNSTABLE SOIL IS ENCOUNTERED, ALL SUCH MATERIAL SHALL BE REMOVED AND REPLACED WITH SUITABLE EARTH COMPACTED TO PROVIDE ADEQUATE SUPPORT.
- LAYING PIPE** - THE PIPE SHALL BE PLACED WITH INSIDE CIRCUMFERENTIAL LAPS POINTING DOWNSTREAM AND WITH THE LONGITUDINAL LAPS AT THE SIDES.
- BACKFILLING** SHALL CONFORM TO STRUCTURAL BACKFILL AS SHOWN ABOVE.
- OTHER DETAILS** (ANTI-SEEP COLLARS, VALVES, ETC.) SHALL BE AS SHOWN ON THE DRAWINGS.

B. REINFORCED CONCRETE PIPE

- MATERIALS** - REINFORCED CONCRETE PIPE SHALL HAVE A RUBBER GASKET JOINT AND SHALL EQUAL OR EXCEED ASTM SPECIFICATION C-361. AN APPROVED EQUIVALENT IS ANWA SPECIFICATION C-301.
- BEDDING** - ALL REINFORCED CONCRETE PIPE CONDUITS SHALL BE LAID IN A CONCRETE BEDDING FOR THEIR ENTIRE LENGTH. THIS BEDDING SHALL CONSIST OF HIGH SLUMP CONCRETE PLACED UNDER THE PIPE AND UP THE SIDES OF THE PIPE AT LEAST 10" OF ITS OUTSIDE DIAMETER WITH A MINIMUM THICKNESS OF 3", OR AS SHOWN ON THE DRAWINGS.

B. REINFORCED CONCRETE PIPE - Continued

- LAYING PIPE** - BELL AND SPIGOT PIPE SHALL BE PLACED WITH THE END UPSTREAM. JOINTS SHALL BE MADE IN ACCORDANCE WITH RECOMMENDATIONS OF THE MANUFACTURER OF THE MATERIAL. AFTER THE JOINTS ARE SEALED FOR THE ENTIRE LINE, THE BEDDING SHALL BE PLACED SO THAT ALL SPACES UNDER THE PIPE ARE FILLED. CARE SHALL BE EXERCISED TO PREVENT ANY DEVIATION FROM THE ORIGINAL LINE AND GRADE OF THE PIPE.
- BACKFILLING** SHALL CONFORM TO STRUCTURAL BACKFILL AS SHOWN ABOVE.
- OTHER DETAILS** (ANTI-SEEP COLLARS, VALVES, ETC.) SHALL BE AS SHOWN ON THE DRAWINGS.
- FOR PIPES OF OTHER MATERIALS**, SPECIFIC SPECIFICATIONS SHALL BE SHOWN ON THE DRAWINGS.

V. CONCRETE



- MATERIALS**
  - CEMENT** - NORMAL PORTLAND CEMENT SHALL CONFORM TO THE LATEST ASTM SPECIFICATION C-150.
  - WATER** - THE WATER USED IN CONCRETE SHALL BE CLEAN, FREE FROM OIL, ACID, ALKALI, SCALES, ORGANIC MATTER OR OTHER OBJECTIONABLE SUBSTANCES.
  - SAND** - THE SAND USED IN CONCRETE SHALL BE CLEAN, HARD, STRONG AND DURABLE, AND SHALL BE WELL GRADED WITH 100 PERCENT PASSING A ONE-QUARTER INCH SIEVE. LIMESTONE SAND SHALL NOT BE USED.
  - COARSE AGGREGATE** - THE COARSE AGGREGATE SHALL BE CLEAN, HARD, STRONG AND DURABLE, AND FREE FROM CLAY OR DIRT. IT SHALL BE WELL GRADED WITH A MAXIMUM SIZE OF ONE AND ONE-HALF (1-1/2) INCHES.
  - REINFORCING STEEL** - THE REINFORCING STEEL SHALL BE DEFORMED BARS OF INTERMEDIATE GRADE BILLET STEEL CONFORMING TO ASTM SPECIFICATION A-615.
- DESIGN MIX** - THE CONCRETE SHALL BE MIXED IN THE FOLLOWING PROPORTIONS, MEASURED BY WEIGHT. THE WATER-CEMENT RATIO SHALL BE 5-1/2 TO 6 U.S. GALLONS OF WATER PER 94 POUND BAG OF CEMENT. THE PROPORTION OF MATERIALS FOR THE TRIAL MIX SHALL BE 1:2:3-1/2. THE COMBINATION OF AGGREGATES MAY BE ADJUSTED TO PRODUCE A PLASTIC AND WORKABLE MIX THAT WILL NOT PRODUCE HARSHNESS IN PLACING OR HONEYCOMBING IN THE STRUCTURE.
- MIXING** - THE CONCRETE INGREDIENTS SHALL BE MIXED IN BATCH MIXERS UNTIL THE MIXTURE IS HOMOGENEOUS AND OF UNIFORM CONSISTENCY. THE MIXING OF EACH BATCH SHALL CONTINUE FOR NOT LESS THAN ONE AND ONE-HALF MINUTES AFTER ALL THE INGREDIENTS, EXCEPT THE FULL AMOUNT OF WATER, ARE IN THE MIXER. THE MINIMUM MIXING TIME IS PREDICTED ON PROPER CONTROL OF THE SPEED OF ROTATION OF THE MIXER AND OF THE INTRODUCTION OF THE MATERIALS, INCLUDING WATER, INTO THE MIXER. WATER SHALL BE ADDED PRIOR TO DURING, AND FOLLOWING THE MIXER-CHARGING OPERATIONS. EXCESSIVE OVERMIXING REQUIRING THE ADDITION OF WATER TO PRESERVE THE REQUIRED CONCRETE CONSISTENCY SHALL NOT BE PERMITTED. TRUCK MIXING WILL BE ALLOWED PROVIDED THAT THE USE OF THIS METHOD SHALL CAUSE NO VIOLATION OF ANY APPLICABLE PROVISIONS OF THE SPECIFICATIONS GIVEN HERE.
- FORMS** - THE FORMS SHALL HAVE SUFFICIENT STRENGTH AND RIGIDITY TO HOLD THE CONCRETE AND TO WITHSTAND THE NECESSARY PRESSURE, TAMPING, AND VIBRATION WITHOUT DEFLECTION FROM THE PRESCRIBED LINES. THEY SHALL BE MORTAR-TIGHT AND CONSTRUCTED SO THAT THEY CAN BE REMOVED WITHOUT HAMMERING OR PRYING AGAINST THE CONCRETE. THE INSIDE OF FORMS SHALL BE OILED WITH A NON-STAINING MINERAL OIL OR THOROUGHLY WETTED BEFORE CONCRETE IS PLACED. FORMS MAY BE REMOVED 24 HOURS AFTER THE PLACEMENT OF CONCRETE. ALL WIRE TIES AND OTHER DEVICES USED SHALL BE RECESSED FROM THE SURFACE OF THE CONCRETE.
- REINFORCING STEEL** - ALL REINFORCING MATERIAL SHALL BE FREE OF DIRT, RUST, SCALE, OIL, PAINT OR ANY OTHER COATINGS. THE STEEL SHALL BE ACCURATELY PLACED AND SECURELY TIED AND BLOCKED INTO POSITION SO THAT NO MOVEMENT OF THE STEEL WILL OCCUR DURING PLACEMENT OF CONCRETE.
- CONSOLIDATING** - CONCRETE SHALL BE CONSOLIDATED WITH INTERNAL TYPE MECHANICAL VIBRATORS. VIBRATION SHALL BE SUPPLEMENTED BY SPADING AND HAND TAMPING AS NECESSARY TO INSURE SMOOTH AND DENSE CONCRETE ALONG FORM SURFACES, IN CORNERS, AND AROUND EMBEDDED ITEMS.
- FINISHING** - DEFECTIVE CONCRETE, HONEYCOMBED AREAS, VOIDS LEFT BY THE REMOVAL OF TIE RODS, RIDGES ON ALL CONCRETE SURFACES PERMANENTLY EXPOSED TO VIEW OR EXPOSED TO WATER ON THE FINISHED STRUCTURE, SHALL BE REPAIRED IMMEDIATELY AFTER THE REMOVAL OF FORMS. ALL VOIDS SHALL BE REAMED AND COMPLETELY FILLED WITH DRY-PATCHING MORTAR.
- PROTECTION AND CURING** - EXPOSED SURFACES OF CONCRETE SHALL BE PROTECTED FROM THE DIRECT RAYS OF THE SUN FOR AT LEAST THE FIRST THREE (3) DAYS. ALL CONCRETE SHALL BE KEPT CONTINUOUSLY MOIST FOR AT LEAST TEN (10) DAYS AFTER BEING PLACED. MOISTURE MAY BE APPLIED BY SPRAYING OR SPRINKLING AS NECESSARY TO PREVENT THE CONCRETE FROM DRYING. CURING COMPOUNDS MAY ALSO BE USED.
- PLACING TEMPERATURE** - CONCRETE MAY NOT BE PLACED AT TEMPERATURES BELOW 37°F WITH THE TEMPERATURE FALLING, OR 34°F WITH THE TEMPERATURE RISING.

VI. STABILIZATION





ALL BORROW AREAS SHALL BE GRADED TO PROVIDE PROPER DRAINAGE AND LEFT IN A SLIGHTLY CONDITION. ALL EXPOSED SURFACES OF THE EMBANKMENT, SPILLWAY, SPOIL AND BORROW AREAS, AND BERMS SHALL BE STABILIZED BY SEEDING, LIMING, FERTILIZING AND MULCHING (IF REQUIRED) IN ACCORDANCE WITH THE VEGETATIVE TREATMENT SPECIFICATIONS OR AS SHOWN ON THE ACCOMPANYING DRAWINGS.

VII. EROSION AND SEDIMENT CONTROL

CONSTRUCTION OPERATIONS WILL BE CARRIED OUT IN SUCH A MANNER THAT EROSION WILL BE CONTROLLED AND WATER AND AIR POLLUTION MINIMIZED. STATE AND LOCAL LAWS CONCERNING POLLUTION ABATEMENT WILL BE FOLLOWED. CONSTRUCTION PLANS SHALL DETAIL EROSION AND SEDIMENT CONTROL MEASURES TO BE EMPLOYED DURING THE CONSTRUCTION PROCESS.



APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
CHIEF, LAND DEVELOPMENT DIVISION DATE 5/16/08  
CHIEF, BUREAU OF HIGHWAYS DATE 5-17-08  
CHIEF, BUREAU OF ENGINEERING DATE  
OFFICE OF PLANNING  
CHIEF, DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT DATE 5/20/08



REV DATE	REV NO	REVISION DESCRIPTION
1-22-88	2	Per SCS Comments, 1-21-88
1-6-88	1	Changed Principal Spillway and Details

BURLEIGH MANOR  
2nd ELECTION DISTRICT  
HOWARD COUNTY, MARYLAND

DEVELOPER  
ROSE / RICHMOND JOINT VENTURE

PROJECT AREA  
BURLEIGH MANOR  
SECTION 3 AREA 3

PROJECT TITLE  
STORMWATER MANGEMENT NOTES  
SHEET 14 OF 15

SCALE: NONE DATE: 10-30-87

WHITMAN, REQUARDT AND ASSOCIATES  
ENGINEERS  
BALTIMORE, MARYLAND

Kenneth A. McCord  
REGISTERED ENGINEER NO. 1974

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.

THESE PLANS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.  
APPROVED: Stephen L. Smith 4/26/08  
HOWARD S. C. D.

RESPONSIBLE PERSONNEL CERTIFICATION  
"I HEREBY CERTIFY THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF NATURAL RESOURCES APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT."  
DAVID L. CARNEY 10/24/87

CERTIFICATION BY THE DEVELOPER  
"I CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS OF DEVELOPMENT, POND CONSTRUCTION AND EROSION AND SEDIMENT CONTROL. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT OR THEIR AUTHORIZED AGENTS, AS ARE DEEMED NECESSARY DEVIATION FROM THIS PLAN WILL NOT BE MADE UNLESS AUTHORIZED BY THE HOWARD SOIL CONSERVATION DISTRICT. I WILL PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH A RED-LINED "AS-BUILT" OF THE POND WITHIN 30-DAYS OF COMPLETION."  
DAVID L. CARNEY 10/24/87

CERTIFICATION BY THE ENGINEER  
"I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION, AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE MUST PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH A RED-LINED "AS-BUILT" OF THE POND WITHIN 30-DAYS OF COMPLETION."  
KENNETH A. MCCORD 10/30/87

