ROAD CONSTRUCTION PLAN AUTUMN VIEW - SECTION TWO SECOND ELECTION DISTRICT HOWARD COUNTY, MARYLAND

GENERAL NOTES

- 1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST STANDARDS AND SPECIFICATIONS OF HOWARD COUNTY.
- 2. THE CONTRACTOR SHALL NOTIFY THE DEPARTMENT OF PUBLIC WORKS/CONSTRUCTION INSPECTIONS DIVISION AT (410) 313-1880 AT LEAST FIVE (5) WORKING DAYS PRIOR
- 3. THE CONTRACTOR SHALL NOTIFY THE FOLLOWING UTILITIES OR AGENCIES AT LEAST FIVE (5) DAYS PRIOR TO ANY EXCAVATION WORK:

C&P TELEPHONE COMPANY HOWARD COUNTY BUREAU OF UTILITIES AT&T CABLE LOCATION DIVISION BALTIMORE GAS & ELECTRIC STATE HIGHWAY ADMINISTRATION HOWARD COUNTY DEPT. OF PUBLIC WORKS/ CONSTRUCTION INSPECTION DIVISION

393-3533

313-4900

725-9976

1-800-257-7777

4. PROJECT BACKGROUND:

LOCATION: 2ND ELECTION DISTRICT, TAX MAP 31, P/O PARCEL 13 ZONING: R-ED TOTAL TRACT AREA: 26.40 NUMBER OF PROPOSED LOTS: 47 (46 BUILDABLE) DATE PREVIOUS PLANS APPROVED AND DPZ REFERENCE #: - S-94-01, OCTOBER 21, 1994


- 5. TWO FOOT CONTOUR TOPOGRAPHY AND EXISTING CONDITIONS BASED ON A FIELD RUN SURVEY BY FISHER, COLLINS AND CARTER, INC, DATED FEB. 1992.
- 6. HORIZONTAL AND VERTICAL DATUMS BASED ON MARYLAND STATE COORDINATE SYSTEM (NAD 27).


STA No. 2944001 STA No. 2944002 N 513669.929 E 858664.268 N 514196.358 E 858596.389

- 7. LIGHT POLES AND FIXTURES FOR STREET LIGHTS SHALL BE IN ACCORDANCE WITH THE LATEST HOWARD COUNTY DESIGN MANUAL, VOL. III, ROADS AND BRIDGES.
- 8. WATER AND SEWER ARE PUBLIC, CONTRACT #: 14-3448-D

- P-94-20, MAY 18, 1995

- 9. STORMWATER MANAGEMENT CONTROL WILL BE PROVIDED BY THE METHOD OF EXTENDED DETENTION. STORMWATER MANAGEMENT POND WILL BE PUBLIC.
- 10. GEOTECHNICAL REPORT PREPARED BY INVESTIGATIVE TESTING & ENGINEERING, INC. DATED DEC 1994.
- 11. STREET LIGHTS: 100 WATT "TRADITIONAIRE" HPS VAPOR POST TOP FIXTURE ON 14' BLACK FIBERGLASS POLE ON THE FOLLOWING LOCATION: #1 HUNTLEY DRIVE Q STA 4+64, 18' RIGHT #2 HUNTLEY DRIVE Q STA 8+00, 16' RIGHT #3 HUNTLEY DRIVE L.P. STA 1+36, 3'OF EDGE OF PAVEMENT
- 12. NO FLOODPLAINS EXIST ON SITE.
- 13. THIS SUBDIVISION IS SUBJECT TO PLANNING BOARD CASE NO. 297 DATED SEPTEMBER 1, 1994, WHICH APPROVED SKETCH PLAN S-94-01.
- 14. EXISTING UTILITIES LOCATIONS ARE BASED ON AS-BUILT DRAWINGS ON RECORD AT HOWARD COUNTY.
- 15. TRAFFIC CONTROL DEVICES, MARKINGS, AND SIGNING SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD). ALL STREET AND REGULATORY SIGNS SHALL BE IN PLACE PRIOR TO THE PLACEMENT OF ANY ASPHALT.
- 16. HOUSES NOT CONTROLED BY THE SWM POND WILL HAVE DRY WELLS AT SDP STAGE. SEE SHEET 9 OF 12 FOR DETAIL.
- 17. COMPACTION IN FILL AREAS TO BE 95% DETERMINED PER AASHTO T-180.
- 18. THE FOREST CONSERVATION EASEMENT(S) HAS BEEN ESTABLISHED TO FULFILL THE REQUIREMENTS OF SECTION 16.1200 OF HOWARD COUNTY FOREST CONSERVATION ACT. NO CLEARING, GRADING OR CONSTRUCTION IS PERMITTED WITHIN THE FOREST CONSERVATION EASEMENT, EXCEPT AS SHOWN ON AN APPROVED ROAD CONSTRUCTION DRAWING OR SITE DEVELOPMENT PLAN. HOWEVER, FOREST MANAGEMENT PRACTICES AS DEFINED IN THE DEED OF FOREST CONSERVATION EASEMENT ARE ALLOWED.





DEVELOPER

BONNIE BRANCH CORPORATION P.O. BOX 396 ELLICOTT CITY, MARYLAND 21043

SHEET INDEX	
TITLE SHEET	1
ROAD PLANS AND PROFILES	2
ROAD PLANS AND PROFILES	3
GRADING AND SEDIMENT CONTROL PLAN	4
EROSION AND SEDIMENT CONTROL NOTES & DETAILS	5
STORM DRAIN PROFILES	6
STORMWATER MANAGEMENT PLAN & PROFILES	7
STORMWATER MANAGEMENT DETAILS	8
STORMWATER MANAGEMENT SPECIFICATIONS	9
LANDSCAPE PLAN	10
DRAINAGE AREA MAP	11
FOREST CONSERVATION PLAN	12




AS BUILT CERTIFICATION ENGINEER'S SIGNATURE DATE APPROVED: DEPARTMENT OF PUBLIC WORKS 1-30-96 CHIEF, BUREAU OF HIGH WAYS APPROVED: DEPARTMENT OF PLANNING AND ZONING CHIEF, DIVISION OF LAND DEVELOPMENT 2/6/96 AND RESEARCH

of 12

SOC.

 ∇

BLOCK OTS:




DISTRICT

PROFILES

AND

INC. SSOC., MILDENBERG, BOENDER & A

2 of 12



168

MAP 31, VIEW-ROAD TAX

PROFILES

AND

PLANS

INC.SSOC. V

A

MILDENBERG BOENDER &

3 of 12

4 of 12

HOWARD SOIL CONSERVATION DISTRICT

PERMANENT SEEDING NOTES

APPLY TO GRADED OR CLEARED AREAS NOT SUBJECT TO IMMEDIATE FURTHER DISTURBANCE WHERE A PERMANENT LONG-

SEEDBED PREPARATION: LOOSEN UPPER THREE INCHES OF SOIL BY RAKING, DISKING OR OTHER ACCEPTABLE MEANS BEFORE SEEDING, IF NOT PREVIOUSLY LOOSENED.

- SOIL AMENDMENTS: IN LIEU OF SOIL TEST RECOMMENDATIONS, USE ONE OF THE FOLLOWING SCHEDULES: 1) PREFERRED - APPLY 2 TONS PER ACRES DOLOMITIC LIMESTONE (92 LBS/1000 SQ.FT.) AND 600 LBS. PER ACRE 10-10-10 FERTILIZER (14 LBS/1000 SQ.FT.) BEFORE SEEDING. HARROW OR DISK INTO UPPER THREE INCHES OF SOIL. AT TIME OF SEEDING, APPLY
 - 400 LBS. PER ACRE 30-0-0 UREAFORM FERTILIZER (9 LBS./1000 SQ.FT.). ACCEPTABLE - APPLY 2 TONS PER ACRE DOLOMITIC LIMESTONE (92 LBS./1000 SQ.FT.) AND 1000 LBS. PER ACRE 10-10-10 FERTILIZER (23 LBS./1000 SQ.FT.) BEFORE SEEDING. HARROW OR DISK INTO UPPER THREE INCHES OF SOIL.

SEEDING - FOR THE PERIODS MARCH 1 THRU APRIL 30, AND AUGUST 1 THRU OCTOBER 15, SEED WITH 60 LBS. PER ACRE 1.4 LBS/1000 SQ.FT.) OF KENTUCKY 31 TALL FESCUE. FOR THE PERIOD MAY 1 THRU JULY 31, SEED WITH 60 LBS. KENTUCKY 31 TALL FESCUE PER ACRE AND 2 LOBS. PER ACRE (.05 LBS./1000 SQ.FT.) OF WEEPING LOVEGRASS. DURING THE PERIOD OF OCTOBER 16 THRU FEBRUARY 28, PROTECT SITE BY: OPTION (1) - 2 TONS PER ACRE OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING. OPTION (2) - USE SOD. OPTION (3) -SEED WITH 60 LBS./ACRE KENTUCKY 31 TALL FESCUE AND MULCH WITH 2 TONE/ACRE WELL ANCHORED STRAW.

MULCHING - APPLY 1-1/2 TO 2 TONS PER ACRE (70 TO 90 LBS./1000 SQ.FT) OF UNROTTED SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. ANCHOR MULCH IMMEDIATELY AFTER APPLICATION USING MULCH ANCHORING TOOL OR 218 GALLONS PER ACRE (5 GAL/1000 SQ.FT.) OF EMULSIFIED ASPHALT ON FLAT AREAS. ON SLOPES 8 FEET OR HIGHER, USE 348 GALLONS PER ACRE (8 GAL/1000 SQ.FT.) FOR ANCHORING.

MAINTENANCE - INSPECT ALL SEEDING AREAS AND MAKE NEEDED REPAIRS, REPLACEMENTS AND RESEEDINGS.

TEMPORARY SEEDING NOTES

APPLY TO GRADED OR CLEARED AREAS LIKELY TO BE REDISTURBED WHERE A SHORT-TERM VEGETATIVE COVER IS NEEDED. SEEDBED PREPARATION: LOOSEN UPPER THREE INCHES OF SOIL BY RAKING, DISKING OR OTHER ACCEPTABLE MEANS BEFORE SEEDING, FOR NOT PREVIOUSLY LOOSENED.

SOIL AMENDMENTS: APPLY 600 LBS. PER ACRE 10-10-10 FERTILIZER (14 LBS./1000 SQ.FT.)

SEEDING: FOR PERIODS MARCH 1 THRU APRIL 30 AND FROM AUGUST 15 THRU OCTOBER 15, SEED WITH 2-1/2 BUSHEL PER ACRE OF ANNUAL RYE (3.2 LBS./1000 SQ.FT.) FOR THE PERIOD MAY 1 THRU AUGUST 14, SEED WITH 3 LBS, PER ACRE OF WEEPING LOVEGRASS (.07 LBS./1000 SQ.FT.). FOR THE PERIOD NOVEMBER 16 THRU NOVEMBER 28, PROTECT SITE BY APPLYING 2 TONS PER ACRÉ OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING, OR USE SOD.

MULCHING: APPLY 1-1/2 TO 2 TONS PER ACRE (70 TO 90 LBS./1000 SQ.FT.) OF UNROTTED WEED FREE SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. ANCHOR MULCH IMMEDIATELY AFTER APPLICATION USING MULCH ANCHORING TOOL OR 218 GAL PER ACRE (5 GAL/1000 SQ.FT.) OF EMULSIFIED ASPHALT ON FLAT AREAS. ON SLOPES 8 FEET OR HIGHER, USE 348 GAL PER ACRE (8 GAL/1000 SQ.FT.) FOR ANCHORING.

REFER TO THE 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR ADDITIONAL RATES AND METHODS NOT COVERED.

HOWARD SOIL CONSERVATION DISTRICT

STANDARD SEDIMENT CONTROL NOTES

- 1) A MINIMUM OF 48 HOURS NOTICE MUST BE GIVEN TO THE HOWARD COUNTY DEPARTMENT OF INSPECTIONS, LICENSES AND PERMITS, SEDIMENT CONTROL DIVISION PRIOR TO THE START OF NAY CONSTRUCTION, (313-1855).
- 2) ALL VEGETATIVE AND STRUCTURAL PRACTICES ARE TO BE INSTALLED ACCORDING TO THE PROVISIONS OF THIS PLAN AND ARE TO BE IN CONFORMANCE WITH THE MOST CURRENT "MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL", AND REVISIONS THERETO.
- 3) FOLLOWING INITIAL SOIL DISTURBANCE OR REDISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN: A) 7 CALENDAR DAYS FOR ALL PERIMETER SEDIMENT CONTROL STRUCTURES, DIKES, PERIMETER SLOPES AND ALL SLOPES GREATER THAN 3:1, B) 14 DAYS AS TO ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE.
- 4) ALL SEDIMENT TRAPS/BASINS SHOWN MUST BE FENCED AND WARNING SIGNS POSTED AROUND THEIR PERIMETER IN ACCORDANCE WITH VOL. 1, CHAPTER 12, OF THE HOWARD COUNTY DESIGN MANUAL, STORM DRAINAGE.
- 5) ALL DISTURBED AREAS MUST BE STABILIZED WITHIN THE TIME PERIOD SPECIFIED ABOVE IN ACCORDANCE WITH THE 1991 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR PERMANENT SEEDING (SEC.51), SOD (SEC. 54), TEMPORARY SEEDING (SEC. 50) AND MULCHING (SEC.52). TEMPORARY STABILIZATION WITH MULCH ALONE CAN ONLY BE DONE WHEN RECOMMENDED SEEDING DATES DO NOT ALLOW FOR PROPER GERMINATION AND ESTABLISHMENT OF GRASSES.
- 6) ALL SEDIMENT CONTROL STRUCTURES ARE TO REMAIN IN PLACE AND ARE TO BE MAINTAINED IN OPERATIVE CONDITION UNTIL PERMISSION FOR THEIR REMOVAL HAS BEEN OBTAINED FROM THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR.
- 7) SITE ANALYSIS: TOTAL AREA OF SITE: AREA DISTURBED: ___ ACRES AREA TO BE ROOFED OR PAVED AREA TO BE VEGITATIVELY STABILIZED 27,500 CU. YDS. 27,500 CU. YDS. TOTAL WASTE/BORROW AREA LOCATION
- 8) ANY SEDIMENT CONTROL PRACTICE WHICH IS DISTURBED BY GRADING ACTIVITY FOR PLACEMENT OF UTILITIES MUST BE REPAIRED ON THE SAME DAY OF DISTURBANCE.
- 9) ADDITIONAL SEDIMENT CONTROL MUST BE PROVIDED, IF DEEMED NECESSARY BY THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR.
- 10) ON ALL SITES WITH DISTURBED AREAS IN EXCESS OF 2 ACRES, APPROVAL OF THE INSPECTION AGENCY SHALL BE REQUESTED UPON COMPLETION OF INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS, BUT BEFORE PROCEEDING WITH ANY OTHER EARTH DISTURBANCE OR GRADING. OTHER BUILDING OR GRADING INSPECTION APPROVALS MAY NOT BE AUTHORIZED UNTIL THIS INITIAL APPROVAL BY THE INSPECTION AGENCY IS MADE.
- 11) TRENCHES FOR THE CONSTRUCTION OF UTILITIES IS LIMITED TO THREE PIPE LENGTHS OR THAT WHICH CAN BE BACK FILLED AND STABILIZED WITHIN ONE WORKING DAY, WHICHEVER IS SHORTER.

I HEREBY CERTIFY THAT THE FACILITY SHOWN ON THIS PLAN WAS CONSTRUCTED AS SHOWN ON THE "AS-BUILT" PLANS AND MEETS THE APPROVED PLANS AND SPECIFICATIONS.

CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ONSITE INSPECTIONS AND MATERIAL TESTS WHICH ARE CONDUCTED DURING CONSTRUCTION. THE ONSITE INSPECTIONS AND MATERIAL TESTS ARE THOSE INSPECTIONS AND TESTS DEEMED SUFFICIENT AND APPROPRIATE BY COMMONLY ACCEPTED ENGINEERING STANDARDS. CERTIFY DOES NOT MEAN OR IMPLY A GUARANTEE BY THE ENGINEER NOR DOES AN ENGINEER'S CERTIFICATION RELIEVE ANY OTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING

OPERATION, MAINTENANCE, AND INSPECTION

COMMONLY ACCEPTED INDUSTRY PRACTICES.

INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITH USDA, SCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVEILLANCE, INSPECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

SEQUENCE OF CONSTRUCTION

- 1. OBTAIN GRADING PERMIT.
- 2. CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE.
- 3. INSTALL TREE PROTECTION FENCE AS INDICATED
- 4. CLEAR AND GRUB AREAS SURROUNDING SEDIMENT CONTROL FEATURES.


6. BLOCK THE SWM POND RISER AS SHOWN IN "WEIR BLOCKING DETAIL".


- 5. CONSTRUCT PERMANENT STORMWATER MANAGEMENT POND AND SEDIMENT TRAPS AND STABILIZE USING TEMPORARY SEEDING METHOD.
- 7. CONSTRUCT SILT FENCE AND EARTH DIKES, STABILIZE EARTH DIKES WITH TEMPORARY SEEDING.
- 8. CLEAR SITE PER LIMIT INDICATED.
- 9. CONSTRUCT SITE TO GRADES INDICATED ON THE PLANS AND CONSTRUCT STORM DRAIN SYSTEM AND UTILITIES.
- 10. UPON STABILIZATION OF GRADED AREAS, ALL ACCUMULATED SEDIMENT SHALL BE REMOVED FROM THE STORM DRAIN SYSTEM.
- 11. DURING CONSTRUCTION, SEDIMENT SHALL BE REMOVED FROM THE SEDIMENT TRAPS AND STORMWATER MANAGEMENT POND WHEN THEIR CLEANOUT ELEVATIONS HAVE BEEN REACHED.
- 12. STABILIZE ALL RIGHT OF WAY AREAS WITH PERMANENT SEEDING.
- 13. INSPECT ALL SEDIMENT CONTROL DEVICES DAILY AND AFTER EACH RAINFALL, REPAIR AS NECESSARY.
- 14. WHEN ALL CONTRIBUTING AREAS TO SEDIMENT CONTROL DEVICES HAVE BEEN PERMANENTLY STABILIZED, END AFTER THE APPROVAL OF THE INSPECTOR , REMOVE SEDIMENT CONTROL DEVICES, GRADE AREAS DISTURBED, AND PROVIDE PERMANENT SEED AND MULCH.
- 15. CONTRACTOR SHALL REMOVE SEDIMENT AND FLUSH STORM DRAIN SYSTEM AT END OF CONSTRUCTION PERIOD.
- 16. CONSTRUCTOR SHALL DEWATER THE STORMWATER MANAGEMENT POND AND REMOVE ACCUMULATED SEDIMENTS. REPLACE THE PERFORATED PIPES SERVING AS DEWATERING DEVICES AND RECONSTRUCT THE RISER AS PER THE PLANS.
- 17. FOLLOWING INITIAL SOIL DISTURBANCE OR REDISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN A.) 7 CALENDAR DAYS FOR ALL PERIMETER SLOPES AND GREATER THAN 3:1


BLAZE-ORANGE PLASTIC
PROTECTION FENCE


(2) TREE PROTECTION FENCE ND SCALE


B.) 14 DAYS FOR ALL OTHER DISTURBED GRADED AREAS ON THE PROJECT SITE.


















OWNER/DEVELOPER IRVING TAYLOR & EDITH TAYLOR C/O BONNIE BRANCH CORPORATION P.O. BOX 396 ELLICOTT CITY, MD 21043






×

C

0

S

S



~ 3 3 3 3 3 3 BLOCK OTS: STORM [AP 31, VIEW-

PROFILES

AIN

DR.

MILDENBERG, BOENDER & ASSOC.


DATE

2/6/96

2/2/94

H5

6 of 12




POND DATA HAZARD CLASSIFICATION — "a" DRAINAGE AREA — 12.1 ACRES PROPOSED RCN - 79 PROPOSED TC - 0.23 HR. WATER QUALITY TYPE— EXTENDED DETENTION EXTENDED DETENTION POOL ELEVATION -445.03, Q = 0.47 CFS., V = 0.65 AC.FT.


2 YEAR STORM POOL ELEVATION -445.21, Q = 2.4 CFS, V = 1.05 AC.FT. 10 YEAR STORM POOL ELEVATION - 446.66, Q = 26.0 CFS, V = 1.05 AC.FT. 100 YEAR STORM POOL ELEVATION - 448.14, Q = 60.0 CFS, V = 1.48 AC.FT. FOREBAY VOLUME - 1,350 CF OWNERSHIP - PUBLIC

- CONSTRUCTED TOP OF DAM EL.=451.0 - SETTLED TOP OF DAM EL.=450.0 TOP OF RISER EL.=450.5 TRASH RACK-10 YR.W.S.EL = 449.92 Q = 2.6 CFS 2 YR.W.S.EL. +448.33 Q = 5.0 CFS SEDIMENT CONTROL VOLUME CUT-OFF TRENCH & CORE (SEE DETAIL E) BOTTOM OF POND EL.=438.0 DEWATERING DEVICE-(SEE SECT. 2 & 3 ON SHEET 8) —12.1'x11.4' ANTI SEEP COLLAR (SEE DETAIL A) NV. IN EL.=426.45 CONC. CRADLE-INV. OUT EL 420.0 (SEE DETAIL B) 30"RCP @ 5% (ASTM C-361) PROVIDE SCS ST'D. ROCK OUTLET PROTECTION DETAIL 27, PAGE F-18-10 La = 12' W = 14.5' $d_{50} = 0.9'$ t = 19" 0+00 1+00 2+00

PRINCIPAL SPILLWAY PROFILE


TEMPORARY S.W.M. USE





SEDIMENT BASIN DATA

DRAINAGE AREA - 12.1 ACRES PROPOSED RCN - 79 WET STORAGE REQUIRES = 0.5 AC.FT. WET STORAGE PROVIDED = 0.64 AC.FT. EL. 445.0 DRY STORAGE REQUIRED = 0.5 AC.FT. DRY STORAGE PROVIDED = PROVIDED = 0.84 AC.FT. RCN (TSWM) = 94 Q_{10} (TSWM) = 4.7 CFS. EL. = 448.33




OWNER/DEVELOPER

AS-E	BUILT CERTIFICATION
	LITY SHOWN ON THIS PLAN WAS CONSTRUCTED LANS AND MEETS THE APPROVED PLANS AND
	P.E. NO.:
SIGNATURE	DATE:
ONSITE INSPECTIONS AND MATERIAL CONSTRUCTION. THE ONSITE INSPERIENCE THOSE INSPECTIONS AND TEST COMMONLY ACCEPTED ENGINEERING MPLY A GUARANTEE BY THE ENGINGELIEVE ANY OTHER PARTY FROM	CLARE A PROFESSIONAL OPINION BASED UPON L TESTS WHICH ARE CONDUCTED DURING ECTIONS AND MATERIAL TESTS TS DEEMED SUFFICIENT AND APPROPRIATE G STANDARDS. CERTIFY DOES NOT MEAN OR NEER NOR DOES AND ENGINEER'S CERTIFICATION MEETING REQUIREMENTS IMPOSED BY CONTRACT, NCLUDING MEETING COMMONLY ACCEPTED
BY THE DEVELOPER:	
ACCORDING TO THESE PLANS, AND THE CONSTRUCTION PROJECT WILL DEPARTMENT OF THE ENVIRONMEN CONTROL OF SEDIMENT AND EROSI ENGAGE A REGISTERED PROFESSIO AND PROVIDE THE HOWARD SOIL OF THE POND WITHIN 30 DA	MENT AND/OR CONSTRUCTION WILL BE DONE THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN HAVE A CERTIFICATE OF ATTENDANCE AT A IT APPROVED TRAINING PROGRAM FOR THE ION BEFORE BEGINNING THE PROJECT. I SHALL INAL ENGINEER TO SUPERVISE POND CONSTRUCTION CONSERVATION DISTRICT WITH AN "AS-BUILT" LYS OF COMPLETION. I ALSO AUTHORIZE Y THE HOWARD SOIL CONSERVATION DISTRICT."
Maria	12195
SIGNATURE DE VELUPER	DATE
IRVING TAYLOR PRINTED NAME OF DEVELOPER	
BY THE ENGINEER:	7
CONTROL REPRESENTS A PRACTIC/ KNOWLEDGE OF THE SUT CONDITION WITH THE REQUIL WILLS OF THE NOTIFIED THE CEVELOPER MAJ ENGINEER SEPERVISE PONO CO	FOR POND CONSTRUCTION, EROSION AND SEDIMENT AL AND WORKABLE PLAN BASED ON MY PERSONAL DNS. THIS PLAN WAS PREPARED IN ACCORDANCE HOWARD SOIL CONSERVATION DISTRICT. I HAVE CYSHE MUST ENGAGE A REGISTERED PROFESSIONAL TRUCTION AND PROVIDE THE HOWARD SOIL AS BUILT PLAN OF THE POND WITHIN 30 DAYS DATE DATE
	ED FOR THE HOWARD SOIL CONSERVATION AL REQUIREMENTS FOR SMALL POND CONSTRUCTION, TROL.
Patricia Engles USDA - NATURAL RESOUTCES CO	MARVATION SERVICE 1/24/96
	CONSTRUCTION, SOIL EROSION AND SEDIMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.
APPROVED: DEPARTMENT OF PUBL	LIC WORKS
()	aneke 1-3096
CHIEF BUREAU OF HIGHWAYS	HS DATE
CHIEF BUREAU OF HIGHWAYS APPROVED: DEPARTMENT OF PLA	
APPROVED: DEPARTMENT OF PLA GINW JVWM ON CHIE, DIVISION OF LAND DEVELOR	ANNING AND ZONING 2/6/96
APPROVED: DEPARTMENT OF PLA	ANNING AND ZONING 2/6/96

7 OF 12)

F-96-13

 ω $\mathcal O$



00

F-96-13

SOC.

THESE SPECIFICATIONS ARE APPROPRIATE TO ALL PONDS WITHIN THE SCOPE OF THE STANDARD FOR PRACTICE MD 378. ALL REFERENCES TO ASTM AND AASHTO SPECIFICATIONS APPLY TO THE MOST RECENT

SITE PREPARATION

AREAS DESIGNATED FOR BORROW AREAS, EMPANYMENT, AND STRUCTURAL WORKS SHALL BE CLEARED. GRUBBED AND STRIPPED OF TOPSOIL. ALL TREES, VEGETATION, ROOTS AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED. CHANNEL BANKS AND SHARP BREAKS SHALL BE SLOPED TO NO STEEPER THAN 1:1.

AREAS TO BE COVERED BY THE RESERVOIR WILL BE CLEARED OF ALL TREES, BRUSH, LOGS, RUBBISH AND OTHER OBJECTIONABLE MATERIAL UNLESS OTHERWISE DESIGNATED TO THE PLANS. TREES, BRUSH AND STUMPS SHALL BE CUT APPROXIMATELY LEVEL WITH THE GROUND SURFACE. FOR DRY STORMWATER MANAGEMENT PONDS. A MINIMUM OF A 50 FOOT RADIUS AROUND THE INLET STRUCTURE SHALL BE CLEARED.

ALL CLEARED AND GRUBBED MATERIAL SHALL BE DISPOSED OF OUTSIDE AND BELOW THE LIMITS OF THE DAM AND RESERVOIR AS DIRECTED BY THE OWNER OR HIS REPRESENTATIVE. WHEN SPECIFIED, A SUFFICIENT QUALITY OF TOPSOIL WILL BE STOCKPILED IN A SUITABLE LOCATION FOR USE ON THE EMBANKMENT AND OTHER DESIGNATED AREAS.

EARTH FILL

MATERIAL - THE FILL MATERIAL SHALL BE TAKEN FROM APPROVED DESIGNATED BORROW AREAS. IT SHALL BE FREE OF ROOTS, STUMPS, WOOD, RUBBISH, STONES GREATER THAN 6", FROZEN OR OTHER OBJECTIONABLE MATERIALS. FILL MATERIAL FOR THE CENTER OF THE EMBANKMENT AND CUT OFF TRENCH SHALL CONFORM TO UNIFIED SOIL CLASSIFICATION GC, SC, CH, OR CL. CONSIDERATION MAY BE GIVEN TO THE USE OF OTHER MATERIALS IN THE EMBANKMENT IF DESIGN AND CONSTRUCTION ARE SUPERVISED BY A GEOTECHNICAL

PLACEMENT- AREAS ON WHICH FILL IS TO BE SHALL BE SCARIFIED PRIOR TO PLACEMENT OF FILL. FILL MATERIALS SHALL BE PLACED IN MAXIMUM 8 INCH THICK (BEFORE COMPACTION) LAYERS WHICH ARE TO BE CONTINUOUS OVER THE ENTIRE LENGTH OF THE FILL. THE MOST PERMEABLE BORROW MATERIAL SHALL BE PLACED IN THE DOWNSTREAM PORTIONS OF THE EMBANKMENT. THE PRINCIPAL SPILLWAY MUST BE INSTALLED CONCURRENTLY WITH FILL PLACEMENT AND NOT EXCAVATED INTO THE EMBANKMENT.

COMPACTION- THE MOVEMENT OF AND SPREADING EQUIPMENT OVER THE FILL SHALL BE CONTROLLED SO THAT THE ENTIRE SURFACE OF EACH LIFT SHALL BE TRAVERSE BY NOT LESS THAN ONE TREAD TRACK OF THE EQUIPMENT OR COMPACTION SHALL BE ACHIEVED BY A MINIMUM OF FOUR COMPLETE PASSES OF A SHEEPSFOOT, RUBBER TIRED OR VIBRATORY ROLLER. FILL MATERIAL SHALL CONTAIN SUFFICIENT MOISTURE SUCH THAT THE REQUIRED DEGREE OF COMPACTION WILL BE OBTAINED WITH THE EQUIPMENT USED. THE FILL MATERIAL SHALL CONTAIN SUFFICIENT MOISTURE SO THAT IF FORMED INTO A BALL IT WILL NOT CRUMBLE YET NOT BE SO WET THAT WATER CAN BE SQUEEZED OUT.

WHERE A MINIMUM REQUIRED DENSITY IS SPECIFIED, IT SHALL NOT BE LESS 95% OF MAXIMUM DRY DENSITY WITH A MOISTURE CONTENT WITHIN+- 2% OF THE OPTIMUM. EACH LAYER OF FILL SHALL BE COMPACTED AS NECESSARY TO OBTAIN THAT DENSITY, AND IS TO BE CERTIFIED BY THE ENGINEER AT THE TIME OF CONSTRUCTION. ALL COMPACTION IS TO BE DETERMINED BY AASHTO METHOD T-99

CUT OFF TRENCH- THE CUFF OFF TRENCH SHALL BE EXCAVATED INTO IMPERVIOUS MATERIAL ALONG OR PARALLEL TO THE CENTERLINE OF THE EMBANKMENT AS SHOWN ON THE PLANS. THE BOTTOM WIDTH OF THE TRENCH SHALL BE GOVERNED BY THE EQUIPMENT USED FOR EXCAVATION, WITH THE MINIMUM WIDTH BEING FOUR FEET. THE DEPTH SHALL BE AT LEAST FOUR FEET BELOW EXISTING GRADE OR AS SHOWN ON THE PLANS. THE SIDE SLOPES OF THE TRENCH SHALL BE 1 TO 1 OR FLATTER. THE BACKFILL SHALL BE COMPACTED WITH CONSTRUCTION EQUIPMENT, ROLLERS, OR HAND TAMPERS TO ASSURE MAXIMUM DENSITY AND MINIMUM PERMEABILITY.

STRUCTURE BACKFILL

BACKFILL ADJACENT TO PIPES OR STRUCTURES SHALL BE OF THE TYPE AND QUALITY CONFORMING TO THAT SPECIFIED FOR THE ADJOINING FILL MATERIAL. THE FILL MATERIAL SHALL BE PLACED IN HORIZONTAL LAYERS NOT TO EXCEED FOUR INCHES IN THICKNESS AND COMPACTED BY HAND TAMPERS OR OTHER MANUALLY DIRECTED COMPACTION EQUIPMENT. THE MATERIAL NEEDS TO FILL COMPLETELY ALL SPACES UNDER AND ADJACENT TO THE PIPE. AT NO TIME DURING THE BACKFILLING OPERATION SHALL DRIVEN EQUIPMENT BE ALLOWED TO OPERATE CLOSER THAN FOUR FEET, MEASURED HORIZONTALLY, TO ANY PART OF A STRUCTURE UNDER NO CIRCUMSTANCES SHALL EQUIPMENT BE DRIVEN OVER ANY PART OF A CONCRETE FILL OF 24" OR GREATER OVER THE STRUCTURE OR PIPE.

PIPE CONDUITS

ALL PIPES SHALL BE CIRCULAR IN CROSS SECTION.

CORRUGATED METAL PIPE- ALL OF THE FOLLOWING CRITERIA SHALL APPLY FOR CORRUGATED METAL PIPE . MATERIALS- (STEEL PIPE)- THIS PIPE AND ITS APPURTENANCE SHALL BE GALVANIZED AND FULLY BITUMINOUS COATED AND SHALL CONFORM TO THE REQUIREMENTS OF AASHTO SPECIFICATION M- 190 TYPE A WITH WATERTIGHT COUPLING BANDS. ANY BITUMINOUS COATING DAMAGED OR OTHERWISE REMOVED SHALL BE REPLACED WITH COLD APPLIED BITUMINOUS COATING COMPOUND. STEEL PIPES WITH POLYMERIC COATINGS SHALL HAVE A MINIMUM COATING THICKNESS OF 0.01 INCH (10 MIL) ON BOTH SIDES OF THE PIPE. THE FOLLOWING COATINGS OR AN APPROVED EQUAL MAY BE USED: NEXON, PLASTI-COTE, BLAC-KLAD, AND BETH-CU-LOY. COATED CORRUGATED STEEL PIPE SHALL MEET THE REQUIREMENTS OF AASHTO M-245 AND M-246

MATERIALS- (ALUMINUM COATED STEEL PIPE)- THIS PIPE AND ITS APPURTENANCES SHALL CONFORM TO THE REQUIREMENTS OF AASHTO SPECIFICATION M-274 WITH WATERTIGHT COUPLING BANDS OR FLANGES. ANY ALUMINUM COATING DAMAGED OF OTHERWISE REMOVED SHALL BE REPLACED WITH COLD APPLIED BITUMINOUS COATING COMPOUND.?

MATERIALS-(ALUMINUM PIPE)- THIS PIPE AND ITS APPURTENANCES SHALL CONFORM TO THE REQUIREMENTS OF AASHTO SPECIFICATION M-196 OR M-211 WITH WATERTIGHT COUPLINGS BANDS OR FLANGES. ALUMINUM SURFACES THAT ARE TO BE IN CONTACT WITH CONCRETE SHALL BE PAINTED WITH ONE COAT OF ZINC CHROMATE PRIMER. HOT DIP GALVANIZED BOLTS MAY BE USED FOR CONNECTIONS. THE PH OF THE SURROUNDING SOILS SHALL BE BETWEEN 4 AND 9.

2. COUPLING BANDS, ANTI-SEEP COLLARS, END SECTIONS, ETC., MUST BE COMPOSED OF THE SAME MATERIAL AS THE PIPE. METALS MUST BE INSULATED FROM DISSIMILAR MATERIALS WITH USE RUBBER OR PLASTIC INSULATING MATERIALS AT LEAST 24 MILS IN THICKNESS.

3. CONNECTIONS- ALL CONNECTIONS WITH PIPES MUST BE COMPLETELY WATERTIGHT. THE DRAIN PIPE OR BARREL CONNECTION TO THE RISER SHALL BE WELDED ALL AROUND WHEN THE PIPE AND RISER ARE METAL ANTI-STEEP COLLARS SHALL BE CONNECTED TO THE PIPE IN SUCH A MANNER AS TO BE COMPLETELY WATERTIGHT. DIMPLE BANDS ARE NOT CONSIDERED TO BE WATERTIGHT.

ALL CONNECTIONS SHALL USE A RUBBER OF NEOPRENE GASKET WHEN JOINING PIPE SECTIONS. THE END OF EACH PIPE SHALL BE-ROLLED AND ADEQUATE NUMBER OF CORRUGATIONS TO ACCOMMODATE THE BAND WDTH. THE FOLLOWING TYPE CONNECTIONS ARE ACCEPTABLE FOR PIPE LESS THAN 24" IN DIAMETER: FLANGES ON BOTH ENDS OF THE PIPE, A 12" WIDE STANDARD LAP TYPE BAND WITH 12" WIDE BY 3/8" THICK CLOSED CELL CIRCULAR NEOPRENE GASKET, AND A 12" WIDE HUGGER TYPE BAND WITH 0-RING GASKETS HAVING MINIMUM DIAMETER OF 1/2" GREATER THAN THE CORRUGATION DEPTH. PIPES 24: IN DIAMETER AND LARGER SHALL BE CONNECTED BY A 24" LONG ANNULAR CORRUGATED BAND USING RODS AND LUGS. A 12" WIDE BY 3/8" THICK CLOSED CELL CIRCULAR NEOPRENE GASKET WILL BE INSTALLED ON THE END OF EACH PIPE FOR A TOTAL OF 24"

HELICALLY CORRUGATED PIPE SHALL HAVE EITHER CONTINUOUSLY WELDED SEAMS OR HAVE LOCK SEAMS WITH INTERNAL CAULKING OR A NEOPRENE BEAD.

4. BEDDING-- THE PIPE SHALL BE FIRMLY AND UNIFORMLY BEDDED THROUGHOUT ITS ENTIRE LENGTH. WHERE ROCK OR SOFT, SPONGY OR OTHER UNSTABLE SOIL IS ENCOUNTERED ALL SUCH MATERIAL SHALL BE REMOVED AND REPLACED WITH SUITABLE EARTH COMPACTED TO PROVIDE ADEQUATE SUPPORT.

5. BACKFILLING SHALL CONFORM TO "STRUCTURE BACKFILL."

6. OTHER DETAILS (ANTI-SEEP COLLARS, VALVES, ETC.) SHALL BE AS SHOWN ON THE DRAWINGS.

REINFORCED CONCRETE PIPE- ALL OF THE FOLLOWING CRITERIA SHALL APPLY FOR REINFORCED CONCRETE

1. MATERIALS-REINFORCED CONCRETE PIPE SHALL HAVE BELL AND SPIGOT JOINTS WITH RUBBER GASKETS AND SHALL EQUAL OR EXCEED ASTM DESIGNATION C-361.

2. BEDDING - ALL REINFORCED CONCRETE PIPE CONDUITS SHALL BE LAID IN A CONCRETE BEDDING FOR THEIR ENTIRE LENGTH. THIS BEDDING SHALL CONSIST OF HIGH SLUMP CONCRETE PLACED UNDER THE PIPE AND UP THE SIDES OF THE PIPE AT LEAST 10% OF ITS OUTSIDE DIAMETER WITH A MINIMUM THICKNESS OF 3 INCHES, OR AS SHOWN ON THE DRAWINGS.

3. LAYING PIPE- BELL AND SPIGOT PIPE SHALL BE PLACED WITH THE BELL END UPSTREAM. JOINTS SHALL BE MADE IN ACCORDANCE WITH RECOMMENDATIONS OF THE MANUFACTURER OF THE MATERIAL. AFTER THE JOINTS ARE SCALED FOR THE ENTIRE LINE, THE BEDDING SHALL BE PLACED SO THAT ALL SPACES UNDER THE PIPE ARE FILLED. CARE SHALL BE EXERCISED TO PREVENT ANY DEVIATION FROM THE ORIGINAL LINE AND GRADE OF THE PIPE. THE FIRST JOINT MUST BE LOCATED WITHIN 2 FEET FROM THE RISER.

- 4. BACKFILLING SHALL CONFORM TO "STRUCTURE BACKFILL."
- 5. OTHER DETAILS (ANTI-SEEP COLLARS, VALVES, ETC.) SHALL BE AS SHOWN ON THE DRAWINGS.

POLYVINYL CHLORIDE (PVC) PIPE- ALL OF THE FOLLOWING CRITERIA SHALL APPLY FOR POLYVINYL CHLORIDE

1. MATERIALS-PVC PIPE SHALL BE PVC-1120 OR PVC-1220 CONFORMING TO ASTM D-1785 OR ASTM D- 2241.

- 2. JOINTS AND CONNECTIONS TO ANTI-SEEP COLLARS SHALL BE COMPLETELY WATERTIGHT.
- 3. BEDDING-- THE PIPE SHALL BE FIRMLY AND UNIFORMLY BEDDED THROUGHOUT ITS ENTIRE LENGTH. WHERE ROCK OR SOFT, SPONGY OR OTHER UNSTABLE SOIL IS ENCOUNTERED, ALL SUCH MATERIAL SHALL BE REMOVED AND REPLACED WITH SUITABLE EARTH COMPACTED TO PROVIDE ADEQUATE SUPPORT.
- 4. BACKFILLING SHALL CONFORM TO "STRUCTURE BACKFILL."
- 5. OTHER DETAILS (ANTI-SEEP COLLARS, VALVES, ETC.) SHALL BE AS SHOWN ON THE DRAWINGS. CONCRETE

CONCRETE SHALL MEET THE REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION, STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION 9C5.

THE RIPRAP SHALL BE PLACED TO THE REQUIRED THICKNESS IN ONE OPERATION. THE ROCK SHALL BE DELIVERED AND PLACED IN A MANNER THAT WILL INSURE THE RIPRAP IN PLACE SHALL BE REASONABLY HOMOGENOUS WITH THE LARGER ROCKS UNIFORMLY DISTRIBUTED AND FIRMLY IN CONTACT ONE TO ANOTHER WITH THE SMALLER ROCKS FILLING THE VOIDS BETWEEN THE LARGER ROCKS. FILTER CLOTH SHALL BE REPLACED UNDER ALL RIPRAP AND SHALL MEET THE REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION, STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION

CARE OF WATER DURING CONSTRUCTION

ALL WORK ON THE PERMANENT STRUCTURES SHALL BE CARRIED OUT IN AREAS FREE FROM WATER. THE CONTRACTOR SHALL CONSTRUCT AND MAINTAIN ALL TEMPORARY DIKES, LEVEES, COFFERDAMS, DRAINAGE CHANNELS, AND STREAM DIVERSIONS NECESSARY TO PROTECT THE AREAS TO BE OCCUPIED BY THE PERMANENT WORKS. THE CONTRACTOR SHALL ALSO FURNISH, INSTALL, OPERATE AND MAINTAIN ALL NECESSARY PUMPING AND OTHER EQUIPMENT REQUIRED FOR REMOVAL OF WATER FROM THE VARIOUS PARTS OF THE WORK AND FOR MAINTAINING THE EXCAVATIONS, FOUNDATION AND OTHER PARTS OF THE WORK FREE FROM WATER AS REQUIRED OR DIRECTED BY THE ENGINEER FOR CONSTRUCTING EACH PART OF THE WORK. AFTER HAVING SERVED THEIR PURPOSE, ALL TEMPORARY PROTECTIVE WORKS SHALL BE REMOVED OR LEVELED AND GRADED TO THE EXTENT REQUIRED TO PREVENT OBSTRUCTION IN ANY DEGREE WHATSOEVER OF THE FLOW OF WATER TO THE SPILLWAY OR OUTLET WORKS AND SO AS NOT TO INTERFERE IN ANY WAY WITH THE OPERATION OR MAINTENANCE OF THE STRUCTURE. STREAM DIVERSIONS SHALL BE MAINTAINED UNTIL THE FULL FLOW CAN BE PASSED THROUGH THE PERMANENT WORKS. THE REMOVAL OF WATER FROM THE REQUIRED EXCAVATION AND THE FOUNDATION SHALL BE ACCOMPLISHED IN A MANNER AND TO THE EXTENT THAT WILL MAINTAIN STABILITY OF THE EXCAVATED SLOPES AND BOTTOM OF THE REQUIRED EXCAVATIONS AND WILL ALLOW SATISFACTORY PERFORMANCE OF ALL AND CONSTRUCTION OPERATIONS. DURING THE PLACING AND COMPACTING OF MATERIAL IN REQUIRED EXCAVATIONS, THE WATER LEVEL AT THE LOCATIONS BEING REFILLED SHALL BE MAINTAINED BELOW THE BOTTOM OF THE EXCAVATION AT SUCH LOCATIONS WHICH MAY REQUIRE DRAINING THE WATER TO SUMPS FROM WHICH THE WATER SHALL BE PUMPED.

STABILIZATION

ALL BORROW AREAS SHALL BE GRADED TO PROVIDE PROPER DRAINAGE AND LEFT IN A SLIGHTLY CONDITIO ALL EXPOSED SURFACES OF THE EMBANKMENT, SPILLWAY, SPOIL AND BORROW AREAS, AND BERMS SHALL BE STABILIZED BY SEEDING, LIMING, FERTILIZING AND MULCHING IN ACCORDANCE WITH THE MARYLAND SOIL CONSERVATION SERVICE STANDARDS AND SPECIFICATIONS FOR CRITICAL AREA PLANTING (MD-342) OR AS SHOWN ON THE ACCOMPANYING DRAWINGS.

EROSION AND SEDIMENT CONTROL

CONSTRUCTION OPERATIONS WILL BE CARRIED OUT IN SUCH A MANNER THAT EROSION WILL BE CONTROLLED AND WATER AND AIR POLLUTION MINIMIZED. STATE AND LOCAL LAWS CONCERNING POLLUTION ABATEMENT WILL BE FOLLOWED. CONSTRUCTION PLANS SHALL DETAIL EROSION AND SEDIMENT CONTROL MEASURES TO BE EMPLOYED DURING THE CONSTRUCTION PROCESS

OPERATION, MAINTENANCE AND INSPECTION

INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, SCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND THE HEIRS SUCCESSORS OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVEILLANCE, INSPECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

SUPPLEMENTAL SPECIFICATIONS

- I. AT LOCATIONS WHERE REMOVAL OF VEGETATION AND OBTECTIONABLE
 MATERIAL RESULTS IN AN OPENING GREATER THAN 12.0 INCHES IN
 DEPTH, THEY SHOULD BE BACKFILLED WITH SOIL COMPACTED TO
 A MINIMUM OF 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED
 BY THE STANDARD MOISTURE-DENSITY RELATIONSHIP TEST (ASTM D-698).
- E. CORE AND DIKE EMBANKMENT FILL AND BACKFILL SOLS SHOULD BE COMPACTED TO A MINIMUM OF 95% OF THE MAXIMUM DRY DENSITY (ASTM D-G98).
- 3. THE UNPAVED ACCESS ROADS SHOULD BE DESIGNED AND CONSTRUCTED TO SUPPORT THE CONTACT TIKE PRESSURE AND AXLE LOAD EXERTED BY THE SERVICE TRAFFIC ANTICIPATED, WE RECOMMENDED SUBGRADE SOIL WITH SUFFICIENT SHEAR STRENGTH TO SUPPORT CONTACT PRESSURE OF 80 PSI AND 8 KIP AXLE LOAD. THE SUBGRADE IN THE ACCESS ROAD AREA SHOULD BE CONSTRUCTED WITH ON-SITE SANDY SOILS COMPACTED TO A MINIMUM OF 95% OF THE MAXIMUM DRY DENSITY (ASTM D-G98) AND WITH A MINIMUM SOAKED CALIFORNIA BEARING RATIO (CBR) OF 5:0
- 4. THE PRINCIPAL SPILLWAY STRUCTURE SHOULD BE FOUNDED ON SUBGRADE SOIL WITH AN ALLOWABLE SOIL PRESSURE OF NO LESS THAN 2000 FOUNDS PER SQUARE FOOT AND SHOULD BE VERIFIED DURING FOUNDATION CONSTRUCTION.

AUTUMN VIEW - SECTION 2 HOWARD COUNTY, MARYLAND TTE PROJECT NO. 20-4018G

STORMWATER MANAGEMENT FACILITY

SUMMARY OF TEST PIT

TEST PIT	DEPTH (FT)	SOIL DESCRIPTION	REMARKS
B-1	0.0 - 6.0	Olive green micaceous, fine SAND	Topsoil: not present
		USC: SM USDA: LOAMY SAND	Groundwater not encountered.
	6.0 - 10.0	Light olive green fine SAND and weathered rock fragments USC: SM	

USDA: LOAMY SAND

Bottom of Test Pit at 10.0 feet depth.

Test Pit backfilled upon completion of observations.

B-2	0.0 - 2.0	Yellowish Brown Clayey SAND USC: SC USDA: SANDY LOAM	Topsoil: not present Groundwater not encountered.
	2.0 - 10.0	Olive green fine SAND, trace mica, rock fragments USC: SM USDA: LOAMY SAND	

Bottom of Test Pit at 10.0 feet depth.

Test Pit backfilled upon completion of observations

· · · · · · · · · · · · · · · · · · ·			
B-3	0.0 - 5.0	Yellowish brown claycy SAND	Topsoil: not present
		USC: SC USDA: SANDY LOAM	Rock fragment below 4.0' · · · depth.
			Groundwater not encountered.
	5.0 - 8.0	Olive green fine SAND USC: SM USDA: SANDY LOAM	Hard digging at 8.5 feet.
	8.0 - 8.5	Yellowish brown SAND and rock fragments USC: SM-GP	
		USDA: LOAMY SAND	

Backhoe refusal at 8.5 feet. Bottom of Test Pit at 8.5 feet. - ROOF LEADER -SURCHARGE PIP ---SPLASH BLOCK -PERFORATED PIPE TRIRIRIRING STRING STRI FILTER FABRIC- \sim STONE (1.5"-3") 6"SAND -BUILDING FOUNBDATION 4'x4'x4' DRY WELL

TYP. DETAIL

DRY WELLS ARE TO BE CONSTRUCTED UNDER THE SDP STAGE

LOTS: 28, 34, 35, 36, 37, 38, 39, 40, 55, 56, 57, 58, 59,

60, 61, 62, 63, 64, 65 - 1 DRY WELL PER HOUSE.

LOTS: 29, 30, 31, 32, 33 - 2 DRY WELLS PER HOUSE

AS-BUILT CERTIFICATION HEREBY CERTIFY THAT THE FACILITY SHOWN ON THIS PLAN WAS CONSTRUCTED AS SHOWN ON THE "AS-BUILT" PLANS AND MEETS THE APPROVED PLANS AND SIGNATURE CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ONSITE INSPECTIONS AND MATERIAL TESTS WHICH ARE CONDUCTED DURING CONSTRUCTION. THE ONSITE INSPECTIONS AND MATERIAL TESTS ARE THOSE INSPECTIONS AND TESTS DEFMED SUFFICIENT AND APPROPRIATE

RELIEVE ANY OTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING COMMONLY ACCEPTED BY THE DEVELOPER: "I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A

DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE

CONTROL OF SEDIMENT AND FROSION REFORE REGINNING THE PROJECT. I SHALL

COMMONLY ACCEPTED ENGINEERING STANDARDS. CERTIFY DOES NOT MEAN OR

IMPLY A CHARANTEE BY THE ENCINEER NOR DOES AND ENCINEER'S CERTIFICATION

APPROVED: DEPARTMENT OF PLANNING AND ZONNING

ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. LALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT." IRVING TAYLOR PRINTED NAME OF DEVELOPER BY THE ENGINEER "I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE STE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE SETHE HOWARD SOIL CONSERVATION DISTRICT. I HAVE CONSTRUCTION AND PROVIDE THE HOWARD SOIL PLAN OF THE POND WITHIN 30 DAYS 10-4-95 THESE PLANS HAM BEET STITE WED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION 1-30-96

9 of 12

 \mathcal{O}

 \forall

 \supset

|

RM

10

2 80

 \vdash

INC

C


0

S

S


Y


MILDENBE! BOENDER



SSO

 $10\,\text{OF}\,12$ F-96-13





 ω $\mathcal O$ BLOCK OTS FORES TA M

MILDENBERG,
BOENDER & ASSOC
Engineers Planners Surveyors
O72 Dorsey Hall Drive, Suite 202, Ellicott City, Maryland

 $(12 \circ 12)$