


Sheet Index

SHEET	DESCRIPTION
1	COVER SHEET
2	SW SITE GRADING & SEDIMENT & EROSION CONTROL
3	NW SITE GRADING & SEDIMENT & EROSION CONTROL
4	SE SITE GRADING & SEDIMENT & EROSION CONTROL
5	NE SITE GRADING & SEDIMENT & EROSION CONTROL
6	SEDIMENT & EROSION CONTROL DETAILS
7	SEDIMENT & EROSION CONTROL DETAILS
8	SEDIMENT & EROSION CONTROL DETAILS
9	DRAINAGE AREA MAP/LANDSCAPE PLANT LIST & SPECS.
10	DRAINAGE AREA MAPS
11	STORM WATER MANAGEMENT PLAN & NOTES
12	STORM WATER MANAGEMENT DETAILS
13	STORM WATER MANAGEMENT DETAILS
14	STORM WATER MANAGEMENT DETAILS
15	NW FOREST CONSERVATION/AFFORESTATION PLAN
16	SE FOREST CONSERVATION/AFFORESTATION PLAN
17	NE FOREST CONSERVATION/AFFORESTATION PLAN
18	FOREST CONSERVATION/AFFORESTATION DETAILS & NOTES

ADDRESS CHART	
LOT NUMBER	STREET ADDRESS
129,125	10902 JOHN HOPKINS ROAD

Site Development Plan for Montpelier Research Park

Howard County Maryland




LOCATION MAP
SCALE: 1" = 200'

HORIZONTAL CONTROL
THE COURSES AND COORDINATES SHOWN HEREON ARE BASED UPON THE NAD 83 MARYLAND COORDINATE SYSTEM AND ARE DERIVED FROM THE FOLLOWING HOWARD COUNTY SURVEY CONTROL STATIONS:

NO.	NORTH	EAST
0020	54370.96	1343822.16
4113	544492.88	1344177.82
41EA	544825.81	1338217.44
41EB	546222.26	1337778.18

VERTICAL CONTROL
ELEVATIONS SHOWN HEREON ARE REFERRED TO THE NATIONAL GEODETIC VERTICAL DATUM (NVD29) WITH LOCAL REFERENCE TO HOWARD COUNTY SURVEY CONTROL STATIONS:

NO.	ELEVATION
0020	403.62
4113	391.65
41EA	407.73



LINE TABLE

NAME	BEARING	DISTANCE
L35	N 64° 13' 12" E	78.11'
L36	N 14° 01' 30" E	75.00'
L40	N 64° 13' 12" E	59.81'
L41	N 14° 01' 30" E	86.71'
L42	N 14° 01' 30" E	125.00'
L43	N 17° 28' 33" W	36.67'
L44	N 17° 28' 33" W	79.67'
L45	N 75° 58' 30" W	20.93'
L46	N 75° 58' 30" W	249.90'
L47	N 75° 58' 30" W	264.73'
L48	S 22° 56' 10" W	116.71'

CURVE TABLE

NAME	DELTA	RADIUS	LENGTH	BEARING	CHORD	TANGENT
C1	02° 45' 59"	1713.76'	82.75'	S 36° 23' 23" W	82.74'	41.38'
C2	04° 36' 45"	1382.38'	109.68'	S 35° 58' 37" W	109.65'	54.87'
C3	76° 42' 33"	80.00'	107.11'	N 52° 22' 47" E	99.28'	63.30'
C4	58° 29' 58"	105.00'	107.21'	N 43° 16' 28" E	102.61'	58.80'
C5	47° 27' 50"	130.00'	107.68'	N 37° 45' 26" E	104.64'	57.15'
C7	41° 37' 54"	550.00'	399.63'	S 43° 45' 07" W	390.90'	209.10'
C8	01° 29' 51"	550.00'	14.37'	S 65° 18' 59" W	14.37'	7.18'
C9	50° 27' 14"	500.00'	440.28'	S 40° 50' 18" W	426.21'	235.57'

NOTE: THERE IS NO C6

Site Analysis Data Chart

- General Site Data
 - Present Zoning: PEC
 - Applicable DPZ File References: BA 96-31 E, WP97-21, PB 190, VP 86-64, WP 91-93, ZB 802 & 767, S 86-47, FDP #1, SDP 88-197, SDP 89-88, WP 98-12, F-98-45
 - Proposed Use of Site or Structure(s): UNDETERMINED - MASS GRADING ONLY
 - Proposed Water and Sewer Systems: X Public
 - Water and Sewer contract number 30-1757D
- Area Tabulation
 - Total Project Area: ± 104 Acres (Indicate by Section and Area As Shown on Final Plat or As Shown on Deed)
 - Net Area of Site: 97.99 Acres (Indicate by Section and Area As Shown on Final Plat)
 - Area of This Plan Submission: 43.5 Acres
 - Limit of Disturbed Area: 43.5 Acres
 - Building Coverage of Site: NA Acres and 0 % of Gross Area (Proposed)
- Open Space Data: N/A
- Parking Space Data: N/A

General Notes

- All construction shall be performed in accordance with the latest standards and specifications of Howard County, plus MSHA standards and specifications if applicable or as specified.
- Approximate location of existing utilities are based solely on available records. Contractor shall verify the location of any utilities which may be impacted by the work. The contractor shall take all necessary precautions to protect the existing utilities and maintain uninterrupted service. Any damage incurred due to contractor's operation shall be repaired immediately at the contractor's expense.
- The contractor shall test pit existing utilities at least five (5) days before starting work shown on these drawings to verify their location and elevation. The contractor shall notify the engineer immediately if location of utilities is other than shown.
- The contractor shall notify 'Miss Utility' at 1-800-257-7777 at least 48 hours prior to any excavation work being done, and shall notify the Department of Public Works/Bureau of Engineering/Construction Inspection Division at (410) 313-1880 at least five (5) working days prior to the start of work.
- Any damage caused by the Contractor to existing public right-of-way, existing paving, existing curb and gutter, existing utilities, etc. shall be repaired at the Contractors expense.
- Topography derived from aerial photogrammetry by Photogrammetric Data Services in June 1986. Stream crossing sections field run by DMW in May, 1997.
- All hydraulic data is for the 10-year storm unless otherwise noted.
- The subsurface exploration and geotechnical engineering analysis for this project was made by Hillis Carnes, Inc. on Jan 31, 1997.
- All fill areas shall be compacted to a minimum of 95% of the maximum dry density as determined and verified in accordance with AASHTO T-180.
- The coordinates shown hereon are based upon the Howard County geodetic control which is based upon the NAD83 Maryland Coordination System. Howard County monument nos. 0020, 4113, 41EA, 41EB were used for this project (See Location Map).
- Storm water management quantity and quality is provided by a retention facility for the site.
- 100 year floodplain limits per DMW floodplain study. Wetland delineation on Jan. 29, 1988 by Envrins; jurisdictional determination reconfirmed by Corps of Engineers in April 1996.
- There are no known cemeteries or burial grounds on this site. However, should evidence of a burial site be discovered, the project will be subject to Section 16.1305 of the Subdivision Regulations.
- No traffic study is required for this project.
- Electric, gas, cable and telephone lines designed by others.
- State & Federal permit tracking number 199785674, GRANTED NOV. 6, 1997.
- WP98.12 granted on 8-22-97 for deferral of landscaping requirements to Final and/or Site Development Plans and for waiver of Sketch & Preliminary Plan for initial stage of subdivision.
- The existing septic system must be properly abandoned prior to disturbance by any proposed grading. Proposed grading may complicate the establishment of a new septic area for a relocated sales trailer.
- A portion of the Forest Conservation obligations incurred by this development have been met by the payment of \$15,682.00 to the Howard County Forest Conservation Fund. With any further development of the site, the remaining obligation of 2.08 acres, must be addressed.

Overall Property Outline
Scale: 1" = 200'

APPROVED: HOWARD COUNTY DEPT. OF PLANNING & ZONING

CHIEF, DEVELOPMENT ENGINEERING DIVISION *10/29/97* DATE

Conda Hammit *10/29/97* DATE
CHIEF, DIVISION OF LAND DEVELOPMENT

Joseph St. John *10/29/97* DATE
DIRECTOR

Date	No.	Revision Description
3-2-98	1	LIMIT OF DISTURBANCE

**Montpelier
Research Park**
HOWARD COUNTY MARYLAND

OWNER/DEVELOPER: HOPKINS ROAD LIMITED PARTNERSHIP
9030 RED BRANCH ROAD, SUITE 200, COLUMBIA, MD 21046


DMW
Daft · McCune · Walker, Inc.
A Team of Land Planners, Landscape Architects, Engineers, Surveyors & Environmental Professionals
200 East Pennsylvania Avenue
Towson, Maryland 21286
410 296 3333
Fax 296 4705



SECTION	AREA	LOT/FACILITY
Montpelier	SECTION AREA	LOT/FACILITY
PLAT/LOT OR BLOCK	ZONING MAP	ELECT DISTRICT
L3601, F506	17 PEC	5th
WATER CODE	SEWER CODE	CENSUS TRACT
E 21	6440000	6051.02

TITLE: **COVER SHEET**

Des By: TPC	Scale: As Shown	Proj. No. 941715
Drn By: TPC, MSS	Date: 10-9-97	
Chk By: MM	Approved:	1 OF 18



MATCHLINE SEE SHEET 2

MATCHLINE SEE SHEET 3




MATCHLINE SEE SHEET 5

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

MARYLAND DEPARTMENT OF ENVIRONMENT
WATER MANAGEMENT ADMINISTRATION

C-9-88

STONE / RIP-RAP OUTLET SEDIMENT TRAP - ST IV



U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

MARYLAND DEPARTMENT OF ENVIRONMENT
WATER MANAGEMENT ADMINISTRATION

C-9-88

STONE / RIP-RAP OUTLET SEDIMENT TRAP - ST IV

- Construction Specifications
- The area under embankment shall be cleared, grubbed and stripped of any vegetation and root mat. The pool area shall be cleared.
 - The fill material for the embankment shall be free of roots or other woody vegetation as well as over-sized stones, rocks, organic material or other objectionable material. The embankment shall be compacted by traversing with equipment while it is being constructed. Maximum height of embankment shall be 4', measured at centerline of embankment.
 - All cut and fill slopes shall be 2:1 or flatter.
 - Elevation of the top of any dike directing water into trap must equal or exceed the height of trap embankment.
 - Storage area provided shall be figured by computing the volume measured from top of excavation. (For storage requirements see Table 9).
 - Geotextile Class C shall be placed over the bottom and sides of the outlet channel prior to placement of stone. Section of fabric must overlap at least 1' with section nearest the entrance placed on top. Fabric shall be embedded at least 6" into existing ground at entrance of outlet channel.
 - 4" - 1" stone shall be used to construct the weir and 4" - 12" or Class 1 rip-rap shall be used to construct the outlet channel.
 - Outlet - An outlet shall include a means of conveying the discharge in an erosion free manner to an existing stable channel. Protection against scour at the discharge point shall be provided as necessary.
 - Outlet channel must have positive drainage from the trap.
 - Sediment shall be removed and trap restored to its original dimensions when the sediment has accumulated to 1/2 of the wet storage depth of the trap (900 cu/ft). Removed sediment shall be deposited in a suitable area and in such a manner that it will not erode.
 - The structure shall be inspected periodically after each rain and repaired as needed.
 - Construction of traps shall be carried out in such a manner that sediment pollution is abated. Once constructed, the top and outside face of the embankment shall be stabilized with seed and mulch. Points of concentrated inflow shall be protected in accordance with Grade Stabilization Structure criteria. The remainder of the interior slopes should be stabilized (one time) with seed and mulch upon trap completion and monitored and maintained erosion free during the life of the trap.
 - The structure shall be dewatered by approved methods, removed and the area stabilized when the drainage area has been properly stabilized.

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

MARYLAND DEPARTMENT OF ENVIRONMENT
WATER MANAGEMENT ADMINISTRATION

C-9-88A

STONE / RIP-RAP OUTLET SEDIMENT TRAP - ST IV

NOTE: THIS PLAN SUPERSEDES SDP-98-011,
APPROVED ON 10-29-98.

3-10-98
Date



KEY SHEET

LEGEND

SYMBOL	DESCRIPTION
(Solid line)	PROPOSED CONTOURS
(Dashed line)	PROPOSED INTERMEDIATE CONTOURS
(Wavy line)	STREAM
(Dashed line with dots)	LIMIT OF MSHA ROW RESERVATION
(Dotted line)	EXISTING CONTOURS
(Tree symbol)	EXISTING TREES/TREE LINE
(Wavy line with dots)	WETLAND/STREAM BUFFER
(Wavy line with dots)	WETLAND
(Dashed line)	TEMPORARY CONTOUR
(Line with 'SF')	SILT FENCE
(Line with 'SSF')	SUPER SILT FENCE
(Arrow)	A-2 DIKE
(Dotted line)	LIMIT OF DISTURBANCE
(Gibbernet symbol)	GABION INFLOW PROTECTION (GIMP)
(Line with 'B')	BAFFLE
(Stippled area)	STABILIZED CONSTRUCTION ENTRANCE

APPROVED: HOWARD COUNTY DEPT. OF PLANNING & ZONING

Richard Blood
CHIEF, DEVELOPMENT ENGINEERING DIVISION 5/18/98 DATE

Richard Blood
CHIEF, DIVISION OF LAND DEVELOPMENT TC 5/15/98 DATE

Joseph Smith
DIRECTOR 5/18/98 DATE

Date	No.	Revision Description

Montpelier
Research Park
HOWARD COUNTY MARYLAND

OWNER/DEVELOPER: HOPKINS ROAD LIMITED PARTNERSHIP
9030 RED BRANCH ROAD, SUITE 200 COLUMBIA, MD 21045

DMW
Daft McCune Walker, Inc.
A Team of Land Planners, Landscape Architects, Engineers, Surveyors & Environmental Professionals

200 East Pennsylvania Avenue
Towson, Maryland 21286
410 298 3333
Fax 298 4705

SUBDIVISION NAME: Montpelier SECTION AREA: 124.125 & ROAD BED
PLAT OR REFERENCE MAP: L3691, F505 17 PEC DATE: 4/15/98
WATER CODE: E 21 BEVER CODE: 6440000

TITLE: REVISED SE SITE GRADING & SEDIMENT & EROSION CONTROL

Des By: ZAL Scale: 1" = 50' Proj. No. 941715
Dwn By: TPC Date: 3-4-98
Chk By: Approved: 4 OF 18

Professional Engr. No. 124125

DEVELOPER'S CERTIFICATION:
I HEREBY CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN, AND THAT THE PERSONNEL INVOLVED IN THE CONSTRUCTION OF THIS PROJECT ARE QUALIFIED AND TRAINED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING. I ALSO CERTIFY THAT THE PROJECT WILL BE MAINTAINED PERIODICALLY ON-SITE INSPECTION BY THE HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING.

Howard L. Reesack
DATE: 4/29/98

ENGINEER'S CERTIFICATION:
I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING.



John W. Rancich, Sr.
DATE: 3/10/98

REVIEWED FOR HOWARD S.C.D. AND MEETS TECHNICAL REQUIREMENTS

Cliff Starnes 5/2/98
U.S. NATURAL RESOURCE CONSERVATION SERVICE

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING.

John W. Rancich, Sr. 5/2/98
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING



Temporary S&E Pipe Profile
Scale: Hor. 1" = 50'
Vert. 1" = 5'

BASIN #2 TABLE		BASIN #2	
BASIN NUMBER	2	DESIGN FLOW SUMMARY	
EXISTING DRAINAGE AREA AC.	NA	FOND 1/BASIN 2 / STUDY PT. 10 2-YEAR	50.72
INTERIM DRAINAGE AREA AC.	NA	PROPOSED INFLOW (CFS)	6.25
PROPOSED DRAINAGE AREA AC.	30	ALLOWABLE RELEASE (CFS)	1.70
STORAGE REQUIRED C.F.	WET 54,000	PROPOSED OUTFLOW (CFS)	389.50
	DRY 54,000	STORAGE PROVIDED (AC - FT)	3.59
	TOTAL 108,000		
STORAGE PROVIDED C.F.	WET 199,069	STUDY POINT 9	2-YEAR
	DRY 313,198	EXISTING PEAK (CFS)	18.46
	TOTAL 512,268	PROPOSED PEAK (CFS)	10.43
EXISTING GROUND ELEV.	368.00		
TOP EMBANKMENT ELEV.	378.00		
RISER CREST ELEV.	371.50		
WET STORAGE / OUTFLET ELEV.	366.00		
CLEANOUT ELEV.	361.00		
BOTTOM ELEV.	356.00		
Q INTO BASIN C.F.S. 10 yr. (10 YR CLOGGED)	129.70		
Q OUT BARREL C.F.S. 10 yr. (10 YR CLOGGED)	25.94		
BASIN DEPTH	WET 12.0		
	DRY 7.5		
	TOTAL 19.5		
DESIGN HIGHWATER (10 YR. CLOGGED)	373.51		
FREEBOARD PROVIDED	2.49		
BASIN SIDE SLOPES	3 : 1		
BARREL DIAMETER	36"		
RISER INSIDE DIMENSIONS	4' SQ.		
WET STORAGE ZONE ELEV.	356.00 - 366.00		
DRY STORAGE ZONE ELEV.	366.00 - 371.50		
BOTTOM DIMENSION	NA		
DIMENSION FROM CLEANOUT ELEV. TO RISER TOP	14.5'		
START PERFORATIONS AT ELEV.	366		

KEY SHEET

LEGEND

SYMBOL	DESCRIPTION
(Solid line)	PROPOSED CONTOURS
(Dashed line)	PROPOSED INTERMEDIATE CONTOURS
(Wavy line)	STREAM
(Line with 'RIP RAP')	RIP RAP INFLOW PROTECTION (RRP)
(Dotted line)	EXISTING CONTOURS
(Line with trees)	EXISTING TREES / TREE LINE
(Line with wavy buffer)	WETLAND / STREAM BUFFER
(Line with wavy buffer)	WETLAND
(Dashed line)	TEMPORARY CONTOUR
(Line with 'SF')	SILT FENCE
(Line with 'SF')	SUPER SILT FENCE
(Arrow)	A-2 DIKE
(Dashed line)	LIMIT OF DISTURBANCE
(Square with 'X')	REMOVABLE PUMPING STATION (RPS)
(Line with 'GIMP')	GABION INFLOW PROTECTION (GIMP)
(Line with 'LIMIT OF MSHA ROW RESERVATION')	LIMIT OF MSHA ROW RESERVATION
(Line with 'BAFFLE')	BAFFLE
(Line with 'STABILIZED CONSTRUCTION ENTRANCE')	STABILIZED CONSTRUCTION ENTRANCE
(Circle with tree)	PROPOSED TREES, & SHRUBS
(Circle with 'DRAW DEVICE')	DRAW DEVICE
(Circle with 'VERTICAL DRAINAGE DEVICE')	VERTICAL DRAINAGE DEVICE

Conditions and Management Practices for Working in Nontidal Wetlands and Buffers

- REMOVE EXCAVATED MATERIAL, CONSTRUCTION MATERIAL OR DEBRIS TO AN UPLAND DISPOSAL AREA OUTSIDE OF ANY WATERWAY, FLOODPLAIN, NONTIDAL WETLAND, OR BUFFER;
- IF BACKFILL IS OBTAINED, USE CLEAN MATERIAL FREE OF WASTE METAL PRODUCTS, UNSIGHTLY DEBRIS, TOXIC MATERIAL, OR ANY OTHER DEleterious SUBSTANCE;
- PLACE MATERIALS IN A LOCATION AND MANNER WHICH DOES NOT ADVERSELY IMPACT SURFACE OR SUBSURFACE WATER FLOW INTO OR OUT OF THE NONTIDAL WETLAND;
- MAINTAIN THE HYDROLOGIC REGIME OF NONTIDAL WETLANDS OUTSIDE THE LIMITS OF DISTURBANCE;
- RECTIFY ANY NONTIDAL WETLANDS AND BUFFERS TEMPORARILY IMPACTED BY THE PERMITTED ACTIVITY. ALL STABILIZATION IN THE WETLAND AND BUFFER SHALL BE OF THE FOLLOWING RECOMMENDED SPECIES: ANNUAL RYEGRASS (*Lolium multiflorum*), MILLET (*Syntherisma italica*), OATS (*Avena sp.*) AND AOR RYE (*Syntherisma cereale*). OTHER NON-PERSISTENT VEGETATION MAY BE ACCEPTABLE, BUT MUST BE APPROVED BY THE NONTIDAL WETLANDS AND WATERWAYS DIVISION, KENTUCKY 31 FESCUE SHALL NOT BE UTILIZED IN THE WETLAND OR BUFFER. ALL TEMPORARY FILLS SHALL BE REMOVED IN THEIR ENTIRETY ON OR BEFORE THE COMPLETION OF CONSTRUCTION;
- TO PROTECT IMPORTANT AQUATIC SPECIES, IN-STREAM WORK IS PROHIBITED AS DETERMINED BY THE CLASSIFICATION OF THE STREAM AS FOLLOWS:
USE 1 WATERS. IN-STREAM WORK MAY NOT BE CONDUCTED DURING THE PERIOD MARCH 1 - JUNE 15 INCLUSIVE, DURING ANY YEAR.
- NO REMOVAL OF VEGETATION, GRADING, FILLING, DRAINING, OR OTHER ALTERATION OF THE NONTIDAL WETLANDS OR BUFFER OUTSIDE THE LIMITS OF DISTURBANCE SHALL OCCUR WITHOUT WRITTEN AUTHORIZATION FROM THE WATER MANAGEMENT ADMINISTRATION.

APPROVED: HOWARD COUNTY DEPT. OF PLANNING & ZONING

Richard B. Boral 5/18/98
CHIEF, DEVELOPMENT ENGINEERING DIVISION
DATE

Richard B. Boral 5/18/98
CHIEF, DIVISION OF LAND DEVELOPMENT
DATE

Richard B. Boral 5/18/98
DIRECTOR
DATE

Montpelier Research Park
HOWARD COUNTY MARYLAND
OWNER/DEVELOPER: HOPKINS ROAD LIMITED PARTNERSHIP
9030 RED BRANCH ROAD, SUITE 200 COLUMBIA, MD 21045

DMW
Darr McCune - Walker, Inc.
A Team of Land Planners, Landscape Architects, Engineers, Surveyors & Environmental Professionals
200 East Pennsylvania Avenue
Towson, Maryland 21286
410 296 3333
Fax 296 4705

REVISIONS:
1. 10-29-97 REVISD PAVEDRY AND STRUCTURE MP.
Date No. Revision Description

Montpelier
PLAT # OR LF BLOCK # ZONE 13661/PS05 | 17 | PEC
TAXING MAP 41
WATER CODE 6440000
SECTION AREA 124.125 & ROAD BED
CENSUS TRACT 8051.02

TITLE: **REVISED NE SITE GRADING & SEDIMENT & EROSION CONTROL**
Des By: ZAL Scale: 1" = 50' Proj. No. 941715
Dm By: TPC, MSS Date: 3-4-98
Chk By: MM Approved: **5** OF 18

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.

Carol Simms 5/7/98
DISTRICT ENGINEER

THESE PLANS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF HOWARD SOIL CONSERVATION DISTRICT.

John W. Ransohoff 5/7/98
DISTRICT ENGINEER

DEVELOPERS CERTIFICATE:
I HEREBY CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT SHALL HAVE A CERTIFICATE OF ATTENDANCE AT A CONSERVATION DISTRICT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZED PERSONS ON-SITE REPRESENTING BY THE HOWARD SOIL CONSERVATION DISTRICT.

Howard L. Ransohoff 4/29/98
DATE
SIGNATURE OF DEVELOPER
PRINT NAME BELOW SIGNATURE

ENGINEERS CERTIFICATE:
I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION.


John W. Ransohoff 5/10/98
DATE
SIGNATURE OF ENGINEER
PRINT NAME BELOW SIGNATURE

NOTE:

- SEE SHEET 9 FOR LANDSCAPE DETAILS, SPECIFICATION & PLANT LIST.
- PLANT LOCATIONS MAY BE FIELD ADJUSTED TO MAINTAIN SIGHT LINE TO SOUTH SIDE.
- REQUIREMENT - SWM PLANTING-TYPE B 360 LF 7 SHADE TREES, 9 EVERGREEN PROVIDED: 6 SHADE TREES, 9 EVERGREEN, 25 SHRUBS (SUBSTITUTE 25 SHRUBS FOR 2 SHADE TREES).
- ALL REQUIRED PLANTINGS ARE BONDED AS PART OF THE DEVELOPERS AGREEMENT.


NOTE: THIS PLAN SUPERSEDES SDP-98-011, APPROVED 10-29-97.






Profile Along C Line of Dam Basin #1

SCALE HOR. 1" = 20'
VER. 1" = 4'



Profile Along Principal Spillway Basin #1

SCALE HOR. 1" = 10'
VER. 1" = 4'



Super Fence Diversion NOT TO SCALE

Temporary Sediment Basin* Construction Specifications

- Site Preparation:** Perimeter sediment control devices must be installed prior to clearing and grubbing. Areas where the embankment is to be placed shall be cleared, grubbed, and stripped of topsoil to remove trees, vegetation, roots or other objectionable material. The pool area shall not be cleared until completion of the dam embankment unless the pool area is to be used for borrow. In order to facilitate clean-out and restoration, the pool area (measured at the top of the pipe spillway) shall be cleared of all brush, trees, and other objectionable materials.
- Cut-off Trench:** A cut-off trench shall be excavated along the centerline of earth fill embankments. The minimum depth shall be four feet. The cut-off trench shall extend up both abutments to the riser crest elevation. The minimum bottom width shall be two feet, but wide enough to permit operation of excavation and compaction equipment. The side slopes shall be no steeper than 1:1. Compaction requirements shall be the same as those for the embankment. The trench shall be dewatered during the backfilling-compaction operations. For dewatering, see Section D. Note: All water encountered during core trench construction shall be pumped from trench.
- Embankment:** The fill material shall be taken from approved areas shown on the plans. It shall be clean mineral soil free of roots, woody vegetation, oversized stones, rocks, or other objectionable material. Relatively pervious materials such as sand or gravel (Unified Soil Classes GW, GP, SW, and SP) or organic materials (Unified Soil Classes OL and OH) shall not be placed in the embankment. Areas on which fill is to be placed shall be scarified prior to placement of fill. The fill material shall contain sufficient moisture so that it can be formed by hand into a ball without crumbling. If water can be squeezed out of the ball, it is too wet for proper compaction. Fill material shall be placed in six-inch to eight-inch thick continuous lifts over the entire length of the fill. Compaction shall be obtained by routing and hauling the construction equipment over the fill


- Vegetative Treatment:** Stabilize the embankment in accordance with the appropriate vegetative Standard and Specifications immediately following construction. In no case shall the embankment remain unstabilized for more than seven (7) days. Once constructed, the top and outside face of the embankment shall be stabilized with seed and mulch. The remainder of the interior slopes should be stabilized (one time) with seed and mulch upon basin completion and monitored and maintained erosion-free during the life of the basin.
- Safety:** Local requirements concerning fencing and signs shall be met warning the public of hazards of soft sediment and floodwater.
- Maintenance:** Repair all damage caused by soil erosion and construction equipment at or before the end of each working day. Sediment shall be removed from the basin when it reaches the specified distance below the top of the riser as shown on the riser. This sediment shall be placed in such a manner that it will not erode from the site. The sediment shall not be deposited downstream from the embankment, adjacent to the stream or floodplain. Disposal areas must be stabilized.
- Final Disposal:** When temporary structures have served their intended purpose and the contributing drainage areas has been properly stabilized, the embankment and resulting sediment deposits are to be leveled or otherwise disposed of in accordance with the approved sediment control plan. The proposed use of a sediment basin site will often dictate final disposition of the basin and any sediment contained therein. If the site is scheduled for future construction, then the basin material and trapped sediments must be removed and safely disposed of and the basin shall be backfilled with a structural fill. When the basin areas is to remain open space, the pond may be pumped dry (using methods in Section D - Dewatering), graded, and backfilled.

so that the entire surface of each layer of the fill is traversed by at least one wheel or tread track of the equipment or by the use of a compactor. The embankment shall be constructed to an elevation 10 percent higher than the design height to allow for settlement.

- Principal Spillway:** Steel risers shall be securely attached to the barrel or barrel stub by welding the full circumference making a watertight structural connection. Concrete risers shall be poured with the principal spillway in place or precast with voids around the principal spillway filled with concrete or strik proof grout for watertight connection. The barrel stub must be attached to the riser at the same percent (angle) of grade as the outlet conduit. The connection between the riser and the riser base shall be watertight. All connections between barrel sections must be achieved by approved watertight band assemblies. The barrel and riser shall be placed on a firm, smooth foundation of impervious oil as the embankment is constructed. Breaching the embankment to install the barrel is unacceptable. Pervious materials such as sand, gravel, or crushed stone shall not be used as backfill around the pipe or anti-seep collars. The fill material around the pipe spillway shall be placed in four-inch lifts and hand compacted under and around the pipe to at least the same density as the adjacent embankment. A depth of 1.5 times the pipe diameter (min.) shall be backfilled over the principal spillway and hand compacted before crossing it with construction equipment.


Sequence of Construction

SEQUENCE	NUMBER OF DAYS
1. OBTAIN A GRADING PERMIT.	7
2. INSTALL SEDIMENT BASIN #2 AND TRAP #3.	21
3. INSTALL STORM DRAINS S-1 THROUGH M-2 AND TEMPORARY PIPE ES-6 THROUGH M-2. INSTALL EARTH DIKES, SUPER FENCE DIVERSION AND SLOPE STABILIZATION TO ES-6.	21
4. INSTALL EARTH DIKE AND SWALE; GRADE TO PROVIDE POSITIVE DRAINAGE TO BASIN #2.	14
5. INSTALL REMAINING SEDIMENT AND EROSION CONTROLS AND STABILIZE.	7
6. ROUGH GRADE ROAD, CONTRACTOR SHALL MAINTAIN POSITIVE DRAINAGE FROM EARTH DIKE AND SWALE TO BASIN #2 AT THE END OF EACH WORKING DAY.	21
7. ROUGH GRADE REMAINDER OF SITE.	21
8. STABILIZE ALL AREAS IN ACCORDANCE WITH STANDARDS AND SPECIFICATIONS.	14
9. UPON APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR, REMOVE ALL EROSION AND SEDIMENT CONTROL MEASURES AND STABILIZE.	7
10. CONVERT BASIN #2 TO SWM POND UPON APPROVAL OF THE SEDIMENT CONTROL INSPECTOR AND STABILIZE.	14



Vertical Draw-Down Device NOT TO SCALE

- CONSTRUCTION SPECIFICATIONS**
- DEWATERING DEVICE SHALL BE 6" MINIMUM DIAMETER METAL PIPE EXTENDING INTO BASIN AREA.
 - PIPE SHALL BE WELDED OR CEMENTED TO RISER AND HAVE A 6" MINIMUM DIAMETER PERFORATED METAL PIPE WELDED AT END PERPENDICULAR TO BARREL WITH A METAL CAP WELDED ONTO END OF PIPE UNLESS ABOVE ELEV. OF PRIMARY RISER CREST.
 - PIPE SHALL BE SECURELY WRAPPED WITH APPROVED FILTER CLOTH AND COVERED ON ALL SIDES WITH NO. 24 STONE TO THE CLEANOUT ELEV.
 - CLEAN OUT ELEVATION FOR BASIN WILL BE DESIGNATED BY A 6" PIECE OF 1/2" DIAMETER ROD BOLTED OR WELDED TO RISER AT THE PROPER ELEVATION. ROD SHOULD BE CLEARLY VISIBLE FROM TOP OF DAM. PLEASE NOTE THAT THE 4" CLEAN OUT HOLE HAS BEEN ELIMINATED.
 - SEDIMENT SHALL BE REMOVED AND BASIN RESTORED TO ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO THE CLEAN-OUT ELEVATION. REMOVED SEDIMENT SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.
 - THE STRUCTURE WILL BE INSPECTED AFTER EACH RAIN AND REPAIRS MADE AS NEEDED.
 - CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND WATER POLLUTION IS MINIMIZED. U.S. DEPT. OF AGRICULTURE SOIL CONSERVATION SERVICE COLLEGE PARK, MD. 1980-9



Rip-Rap Inflow Protection NOT TO SCALE

- CONSTRUCTION SPECIFICATIONS**
- Rip-rap lined inflow channels shall be 1' in depth, have a trapezoidal cross section with 2:1 or flatter side slopes and 3' minimum bottom width. The channel shall be lined with 4" to 12" rip-rap to a depth of 18".
 - Filter cloth shall be installed under all rip-rap. Filter cloth shall be Geotextile Class C.
 - Entrance and exit sections shall be installed as shown on the detail section.
 - Rip-rap used for the lining may be recycled for permanent outlet protection if the basin is to be converted to a stormwater management facility.
 - Gabion inflow Protection may be used in lieu of Rip-rap inflow Protection.
 - Rip-rap should blend into existing ground.
 - Rip-rap Protection shall be used where the slope is between 4:1 and 10:1, for slopes flatter than 10:1 use Earth Dike or Temporary Swale lining criteria.

DEVELOPER'S CERTIFICATION:
"I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I/WE ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT."

Signature: Howard K. Resneck
Date: 10-9-97

ENGINEER'S CERTIFICATION:
"I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT."


Signature: Max Kantzer
Date: 10-9-97

REVIEWED FOR HOWARD S.C.D. AND MEETS TECHNICAL REQUIREMENTS

Signature: Charles K. Summire
Date: 10-20-97

Signature: Robert W. Ziehm
Date: 11/27/97

* Refer to "Conditions and Management Practices for Working in Nontidal Wetlands and Their Buffers" prior to impacting stream, wetland or buffer.



APPROVED: HOWARD COUNTY DEPT. OF PLANNING & ZONING	
CHEIEF, DEVELOPMENT ENGINEERING DIVISION	10/29/97 DATE
CHEIEF, DIVISION OF LAND DEVELOPMENT	11/29/97 DATE
DIRECTOR	10/29/97 DATE
3-11-98	1 REVISED SOC
Date	No. Revision Description

Montpelier Research Park
HOWARD COUNTY MARYLAND

DMW
Daft - McCune - Walker, Inc.
A Team of Land Planners, Landscape Architects, Engineers, Surveyors & Environmental Professionals


200 East Pennsylvania Avenue
Towson, Maryland 21286
410 296 3333
Fax 296 4705

SUBDIVISION NAME	Montpelier	SECTION/AREA	LOT/WATER
PLAT/ OR L.P. BLOCK #	17	TAXING MAP	124, 125, & ROAD BED
WATER CODE	E 21	RELAY DISTRICT	5th
		CENSUS TRACT	6051.02
		SEWER CODE	8440000

TITLE: **SEDIMENT & EROSION CONTROL DETAILS**


Des By: ZAL	Scale: As Shown	Proj. No. 941715
Drn By: TPC	Date: 10-9-97	
Chk By: MM	Approved:	6 OF 18

Professional Engr. No. 16872




**DEVELOPED CONDITIONS
LAND USE LEGEND**

- | SYMBOL | DESCRIPTION |
|--------|------------------------------|
| | WOODS |
| | MEADOW |
| | OPEN SPACE |
| | 2 ACRE LOTS |
| | 70% IMPERVIOUS |
| | 90% IMPERVIOUS |
| | RIGHT-OF-WAY, 20% IMPERVIOUS |
| | RIGHT-OF-WAY, 45% IMPERVIOUS |
| | STREAM |
| | SOILS |
| | D' SOILS |
| | DRAINAGE AREA |
| | EXISTING CONTOURS |
| | PROPOSED CONTOURS |
| | FLOOD PLAIN |



LOCATION MAP
SCALE: 1" = 200'

DEVELOPED CONDITIONS



**EXISTING CONDITIONS
LAND USE LEGEND**

- | SYMBOL | DESCRIPTION |
|--------|------------------------------|
| | WOODS |
| | MEADOW |
| | 2 ACRE LOTS |
| | RIGHT-OF-WAY, 20% IMPERVIOUS |
| | RIGHT-OF-WAY, 45% IMPERVIOUS |
| | COMMERCIAL, 85% IMPERVIOUS |
| | STREAM |
| | SOILS |
| | D' SOILS |
| | DRAINAGE AREA |
| | EXISTING CONTOURS |

APPROVED: HOWARD COUNTY DEPT. OF PLANNING & ZONING

[Signature] 10/29/97
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

[Signature] 10/29/97
Cindy Hamilton, CHIEF, DIVISION OF LAND DEVELOPMENT DATE


[Signature] 10/29/97
DIRECTOR DATE

3-4-98	1	REVISED DEVELOPED CONDITIONS DRAINAGE AREA
Date	No.	Revision Description

Montpelier
Research Park
HOWARD COUNTY MARYLAND
OWNER/DEVELOPER: HOPKINS ROAD LIMITED PARTNERSHIP
9030 RED BRANCH ROAD, SUITE 200 COLUMBIA, MD 21045

DMW
Daft McCune Walker, Inc.
A Team of Land Planners, Landscape Architects, Engineers, Surveyors & Environmental Professionals

200 East Pennsylvania Avenue
Towson, Maryland 21286
410 296 3333
Fax 296 4705



**STORMWATER MANAGEMENT
DRAINAGE AREA MAPS**


Des By: ZAL Scale: 1" = 200' Proj. No. 941715
Drm By: MSS Date: 10-9-97
Chk By: Approved: **10** OF 18

NOTE: D.A. TRAP #3, IS A SUB-D.A. OF E.

NOTE:
PRIOR TO STAKEOUT OF S-500, CONTRACTOR TO VERIFY CROSS SECTION AND INVERT OF STREAM AND NOTIFY ENGINEER IF THERE ARE DISCREPANCIES.

IF UNSUITABLE (PERVIOUS) MATERIAL IS ENCOUNTERED AT TIME OF CUT-OFF TRENCH INSTALLATION DEEPER THAN FOUR (4) FEET, IT WILL BE NECESSARY TO EXTEND THE CUT-OFF TRENCH DOWN UNTIL SUITABLE MATERIAL IS ENCOUNTERED AS DETERMINED BY A GEOTECHNICAL ENGINEER. FILL MATERIAL FOR THE CUT-OFF TRENCH AND IMPERVIOUS CORE SHALL CONFORM TO UNIFIED SOIL CLASSIFICATION GC, SC, CH OR CL. CONSIDERATION MAY BE GIVEN TO THE USE OF OTHER MATERIALS IN THE EMBANKMENT IF DESIGN AND CONSTRUCTION ARE SUPERVISED BY A GEOTECHNICAL ENGINEER.

NOTE TO CONTRACTOR:
CLAY MATERIAL WILL NEED TO BE IMPORTED FROM OFFSITE, WITH AMPLE TESTING BY THE GEOTECHNICAL ENGINEER.



LEGEND

SYMBOL	DESCRIPTION
(Symbol)	FOREST CONSERVATION EASEMENT
(Symbol)	STREAM
(Symbol)	SOIL BORING LOCATION
(Symbol)	EXISTING CONTOURS
(Symbol)	EXISTING TREES/TREE LINE
(Symbol)	WETLAND/STREAM BUFFER
(Symbol)	WETLAND
(Symbol)	PROPOSED CONTOURS

- General Notes:**
- This facility is privately owned and shall be privately maintained.
 - This facility lies within the Middle Patuxent River watershed.
 - This facility is hazard class A.

INSPECTION SCHEDULE

Prior notification shall be given to the engineer so that inspections may be made at the following stages:

- Upon completion of excavation to subfoundation and where required, installation of structural supports or reinforcement for structures, including but not limited to:
 - Core trenches for structural embankments
 - Inter-socket structures and anti-seep structures, watertight connectors on pipes; and
 - Trenches for enclosed storm drainage facilities.
 - During placement of structural fill, concrete, and installation of piping and catch basins;
 - During backfill of foundations and trenches;
 - During embankment construction; and
 - Upon completion of final grading and establishment of permanent stabilization.
- No work shall proceed until engineer inspects and approves the work previously completed.

MAINTENANCE SCHEDULE

Routine Maintenance

- The facilities shall be inspected annually and after major storms. Inspections should be performed during wet weather to determine if the ponds are functioning properly. The facilities shall be inspected in accordance with the checklist and requirements contained within USDA, NRCS "Standards and Specifications for Ponds" (MD-378). The pond owner(s) and any heirs, successors, or assigns shall be responsible for the safety of the ponds and the continued operation, surveillance, inspection, and maintenance thereof. The pond owner(s) shall promptly notify the Soil Conservation District of any unusual observations that may be indicators of distress such as excessive seepage, turbid seepage, slaking or slumping.
- The top and side slopes of the embankments shall be mowed a minimum of two (2) times a year, once in June and once in September. Other side slopes, the bottom of the pond, and maintenance access should be mowed as needed.
- Debris and litter next to the outlet structure shall be removed during regular mowing operations and as needed.
- Visible signs of erosion in the ponds as well as rip rap outlet areas shall be repaired as soon as it is noticed.

Non-Routine Maintenance

- Structural components of the ponds such as the dam, the riser, and the pipes shall be repaired upon the detection of any damage. The components should be inspected during routine maintenance operations.
- Sediment should be removed when its accumulation significantly reduces the design storage, interferes with the function of the riser, when deemed necessary for aesthetic reasons, or when deemed necessary by Howard County's Department(s) of Public Works/Zoning.

GEOTECH RECOMMENDATIONS

- The earthwork operations should be accomplished during the drier seasons - preferably during the summer months when rainfall is less.
- Construct earth berms or other appropriate features along the top of any newly created or existing slope, where possible, to control surface run-off and minimize the formation of gullies down the face of the slope until slope stabilization is achieved.
- Immediately after final grading, the slopes should be seeded, fertilized and covered with an appropriate mulch and binder.
- Periodic examination of the slope areas during and after construction to locate and regrade any slope areas subjected to scouring from excessive surface run-off.

DESIGN FLOW SUMMARY

Pond 1	2-Year	10-Year	100-Year
Proposed Inflow (cfs)	142.27	206.11	307.43
Allowable Release (cfs)	N/A	N/A	N/A
Proposed Outflow (cfs)	1.97	15.52	24.63
Water Surface Elevation (ft)	370.57	372.47	374.12
Storage Provided (AC - ft)	5.33	8.57	11.45



Structure Type	Retention, Wet Ponds
Structure Classification	A
Structure Location	Urban
Watershed Area to Facility (Ac.)	45.6
Maximum Height of Fill (ft.)	10.0
Minimum Top of Dam Width (ft.)	12
Freeboard Provided (ft.)	2.06

Study Point 5

	2-Year	10-Year
Existing Peak (cfs)	18.46	22.27
Proposed Peak (cfs)	18.44	22.18


Study Point 10

	D.A.	RCN	To	2-Year	10-Year
Existing Peak (cfs)	25.1	58	25	8.25	33.12
Proposed Peak (cfs)	44.1	88	19	1.97	15.52



PRINCIPAL SPILLWAY - PROFILE
Scale: Horiz. = 1" = 50'
Vert. = 1" = 5'

SWM POND #1 & SEC BASIN #2



PROFILE ALONG C OF EMERGENCY SPILLWAY
Scale: Horiz. 1" = 50'
Vert. 1" = 5'

APPROVED: HOWARD COUNTY DEPT. OF PLANNING & ZONING
CHIEF, DEVELOPMENT ENGINEERING DIVISION
CHIEF, DIVISION OF LAND DEVELOPMENT
DIRECTOR

Date	No.	Revision Description
10-21-98	2	REVISED FOREBAY & STRUCTURE M-P.
3-4-98	1	REVISED WSE & GRADING

Montpelier Research Park
HOWARD COUNTY MARYLAND
OWNER/DEVELOPER: HOPKINS ROAD LIMITED PARTNERSHIP
9030 RED BRANCH ROAD, SUITE 200 COLUMBIA, MD 21045

DMW
Daft • McCune • Walker, Inc.
A Team of Land Planners, Landscape Architects, Engineers, Surveyors & Environmental Professionals
200 East Pennsylvania Avenue
Towson, Maryland 21286
410 296 3333
410 296 4705

PROJECT NAME	SECTION/AREA	LOTP/BLK
Montpelier		124,125 & ROAD BED
PLAT # OR LP	BLOCK # ZONE	ELECT. DISTRICT
L3890, F505	17 PEC	41
WATER CODE	SEWER CODE	CENSUS TRACT
E 21	6440000	6051.02

TITLE
STORM WATER MANAGEMENT PLAN & NOTES

Des By: ZAL	Scale: 1" = 50'	Proj. No. 941715
Drn By: TPC, MSS	Date: 10-9-97	
Chk By:	Approved:	11 OF 18

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.

Charles K. ...
DATE: 10-21-97

DEVELOPER'S CERTIFICATE:
I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION OF THE PROJECT SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN BY THE POND WITHIN 30 DAYS OF COMPLETION. I/WE AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Howard L. ...
DATE: 10-9-97


ENGINEER'S CERTIFICATE:
I/CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL, REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE FOREST CONSERVATION ACT AND TEMPORARY SIGNAGE DETAILS PRIOR TO THE INSTALLATION OF SEDIMENT AND EROSION CONTROL DEVICES OR THE BEGINNING OF ANY CONSTRUCTION ACTIVITY. FENCING SHALL NOT BE CONSIDERED INSTALLED CORRECTLY UNTIL REVIEWED BY A LANDSCAPE ARCHITECT OR QUALIFIED NATURAL RESOURCE PROFESSIONAL FAMILIAR WITH THE PLAN ATTACHMENT OF SIGNS TO TREES IS PROHIBITED. ROOT PRUNING WILL BE PERFORMED AS SPECIFIED ON THIS PLAN (SEE ROOT PRUNING DETAIL).

Max Kantzer
DATE: 10-9-97


THE FOREST CONSERVATION EASEMENT HAS BEEN ESTABLISHED TO FULFILL THE REQUIREMENTS OF SECTION 16-200 OF THE HOWARD COUNTY CODE FOR FOREST CONSERVATION ACT. NO CLEARING, GRADING OR CONSTRUCTION IS PERMITTED WITHIN THE FOREST CONSERVATION EASEMENT HOWEVER, FOREST MANAGEMENT PRACTICES AS DEFINED IN THE DEED OF FOREST CONSERVATION EASEMENT ARE ALLOWED.

Note: Trees, shrubs and other woody vegetation not allowed within twenty (20) feet of any portion of the embankment.







A Riser Structure - Plan with Top Slab Removed
Scale: 1/2" = 1'-0"




D Anti-Seep Collar - Elevation
Not to Scale




E Anti-Seep Collar - Section A-A
Not to Scale




H Riser Structure - Top Slab
Scale: 1/2" = 1'-0"




I A-2 Cradle
Not to Scale



B Riser Structure - Section X-X
Scale: 1/2" = 1'-0"



C Riser Structure - Section Y-Y
Scale: 1/2" = 1'-0"



F Head Wall for 6" DIP Orifice Pipe
Scale: 1/2" = 1'-0"

APPROVED: HOWARD COUNTY DEPT. OF PLANNING & ZONING
 CHIEF, DEVELOPMENT ENGINEERING DIVISION
 CHIEF, DIVISION OF LAND DEVELOPMENT
 DIRECTOR

3-4-98 1 REVISED W.S.E.
 Date No. Revision Description

Montpelier Research Park
 HOWARD COUNTY MARYLAND

DMW
 Daft · McCune · Walker, Inc.
 A Team of Land Planners, Landscape Architects, Engineers, Surveyors & Environmental Professionals

SUBDIVISION: Montpelier
 SECTION: 41
 BLOCK: 17
 LOT: 17
 ZONE: 41
 TAX: 17
 DISTRICT: 5th
 CENSUS TRACT: 605102
 WATER CODE: E 21
 SEWER CODE: 6440000


TITLE
STORM WATER MANAGEMENT NOTES & DETAILS

Des By: ZAL Scale: As Shown Proj. No. 941715
 Dwn By: TPC Date: 10-9-97
 Chk By: MM Approved: 12 OF 18

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.
 APPROVED: *Charles E. Siskind* 10-28-97
 U.S.D.A. NATURAL RESOURCES CONSERVATION SERVICE DATE
 THESE PLANS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF HOWARD SOIL CONSERVATION DISTRICT.
 APPROVED: *Charles E. Siskind* 10/27/97
 HOWARD SOIL CONSERVATION DISTRICT DATE

DEVELOPERS CERTIFICATE:
 I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I/WE SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I/WE ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.
 SIGNATURE OF DEVELOPER: *Howard L. Rasmussen* DATE: 10/1/97
 PRINT NAME BELOW SIGNATURE

ENGINEERS CERTIFICATE:
 I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION.
 SIGNATURE OF ENGINEER: *Max Hantzer* DATE: 10-9-97
 PRINT NAME BELOW SIGNATURE



STORMWATER MANAGEMENT FOND

GENERAL CONSTRUCTION SPECIFICATIONS

1. GENERAL
All stormwater management facilities shall be constructed in accordance with Baltimore County's "Standard Specifications and Details for Construction (1985)" and the S.C.S. Maryland "Standards and Specifications for Ponds" (MD-378, 1992).

These specifications are appropriate to all ponds within the scope of the Standard practice MD-378. All references to ASTM and AASHTO specifications apply to the most recent version.

2. SITE PREPARATION
Areas designated for borrow areas, embankment, and structural works shall be cleared, grubbed and stripped of topsoil. All trees, vegetation, roots and other objectionable material shall be removed. Channel banks and sharp breaks shall be sloped to no steeper than 1:1.

Areas to be covered by the reservoir will be cleared of all trees, brush, logs, fences rubbish and other objectionable material unless otherwise designated on the plans. Trees, brush and stumps shall be cut approximately level with the ground surface. For dry stormwater management ponds, a minimum of a 50 foot radius around the inlet structure shall be cleared.

All cleared and grubbed material shall be disposed of outside and below the limits of the dam and reservoir as directed by the owner or his representative. When specified, a sufficient quantity of topsoil will be stockpiled in a suitable location for use on the embankment and other designated areas.

3. EARTH FILL

MATERIAL. The fill material shall be taken from approved designated borrow area. It shall be free of roots, stumps, wood, rubbish, stones greater than 6", frozen or other objectionable materials. Fill material for the center of the embankment and cut-off trench shall conform to Unified Soil Classification GC, SC, CH or CL. Consideration may be given to the use of other materials in the embankment if design and construction are supervised by a geotechnical engineer.

PLACEMENT. Areas on which fill is to be placed shall be scarified prior to placement of fill. Fill materials shall be placed in maximum 8 inch thick (before compaction) layers which are to be continuous over the entire length of the fill. The most permeable borrow material shall be placed in the downstream portions of the embankment. The principal spillway must be installed concurrently with fill placement and not excavated into the embankment.

COMPACTION. The movement of the hauling and spreading equipment over the fill shall be controlled so that the entire surface of each lift shall be traversed by not less than one tread track of the equipment or compaction shall be achieved by a minimum of four complete passes of a sheepfoot, rubber tired or vibratory roller. Fill material shall contain sufficient moisture such that the required degree of compaction will be obtained with the equipment used. The fill material shall contain sufficient moisture so that if formed into a ball it will not crumble yet not be so wet that water can be squeezed out.

All compaction is to be not less than 95 percent of the maximum dry density as determined by AASHTO Specification T-99 (Standard Proctor) with a moisture content within 2 percent of optimum. Each layer of fill shall be compacted as necessary to obtain that density, and is to be certified by the Engineer at the time of construction.

CUTOFF TRENCH AND IMPERVIOUS CORE. The cutoff trench shall be excavated into impervious material along or parallel to the centerline of the embankment as shown on the plans. The bottom width of the trench shall be governed by the equipment used for excavation, with the minimum width being:

four feet. The depth shall be at least 4 feet below existing grade or as shown on the plans. The side slopes of the trench shall be 1 to 1 or flatter. The top width of the impervious core shall be 4 feet minimum. The height of the core shall be as shown on the plans. The side slopes of the core shall be 1 to 1 or flatter. The backfill shall be compacted with construction equipment, rollers, or hand tampers to assure maximum density and minimum permeability.

EMBANKMENT AND CUT-OFF TRENCH CONSTRUCTION

The site should be stripped of topsoil and any other unsuitable materials from the embankment or structure area in accordance with Soil Conservation Guidelines. After stripping operations have been completed, the exposed subgrade materials should be proffiled with a loaded dump truck or similar equipment in the presence of a geotechnical engineer or his representative as indicated in Section 5.1. For areas that are not accessible to a dump truck, the exposed materials should be observed and tested by a geotechnical engineer or his representative utilizing a Dynamic cone Penetrometer. Any excessively soft or loose materials identified by proffiling or penetrometer testing should be excavated to suitable firm soil, and then grades re-established by backfilling with suitable soil.

A representative of the Geotechnical Engineer should be present to monitor placement and compaction of fill for the embankment and cut-off trench. In accordance with Maryland Soil Conservation Specification 378, soils considered suitable for the center of the embankment and cut-off trench shall conform to Unified Soil Classification GC, SC, CH, or CL. A review of the site borings did not indicate core or cut-off trench materials in the cut areas of the site. All fill materials must be placed and compacted in accordance with MD SCS 378 specifications.

4. STRUCTURAL BACKFILL

Backfill adjacent to pipes or structures shall be of the type and quality conforming to that specified for the adjoining fill material. The fill shall be placed in horizontal layers not to exceed 4 inches in thickness and compacted by hand tampers or other manually directed compaction equipment. The material needs to fill completely all spaces under and adjacent to the pipe. At no time during the backfilling operation shall driven equipment be allowed to operate closer than 4 feet, measured horizontally, to any part of a structure. Under no circumstances shall equipment be driven over any part of a concrete structure or pipe, unless there is a compacted fill of 24 inches or greater over the structure or pipe.

5. REMOVAL AND REPLACEMENT OF DEFECTIVE FILL
Fill placed at densities lower than specified minimum density or at moisture contents outside the specified acceptable range of moisture content or otherwise not conforming to the requirements of the specifications shall be reworked to meet the requirements or removed and replaced by acceptable fill. The bottoms of such excavations shall be finished flat or gently curving and at the sides of such excavations the adjacent sound fill shall be trimmed to a slope not steeper than 3 feet horizontally to 1 foot vertically extending from the bottom of the excavation to the fill surface.

6. PIPE CONDUITS
All pipes shall be circular in cross section. All perforated pipe shall have a minimum of 3.21 square inches of opening per square foot of pipe surface (ex. 30 3/8 inch holes per square foot). Perforations are to be uniformly spaced around the full periphery of the pipe. Any holes blocked or partially blocked by bituminous coating shall be opened prior to installation.

REINFORCED CONCRETE PIPE. All of the following criteria shall apply for reinforced concrete pipe:

- Materials - Reinforced concrete pipe shall have bell and spigot joints with rubber gaskets and shall equal or exceed ASTM Designation C-381.
- Cradle - All reinforced concrete pipe conduits shall be laid in a concrete cradle for their entire length. This cradle shall consist of high slump concrete placed under the pipe and up the sides of the pipe at least 50 percent of its outside diameter with a minimum thickness of 6 inches, or as shown on the drawings.
- Laying Pipe - Bell and spigot pipe shall be placed with the bell end upstream. Joints shall be made in accordance with recommendations of the manufacturer of the material. After the joints are sealed for the entire line, the cradle shall be placed so that all spaces under the pipe are filled. Care shall be exercised to prevent any deviation from the original line and grade of the pipe. The first joint must be located within 2 feet from the riser.
- Backfilling shall conform to "Structural Backfill".
- Connections - All connections (to anti-seep collars, riser, etc.) shall be watertight.
- Other details (anti-seep collars, valves, etc.) shall be as shown on the drawings.

7. CAST-IN-PLACE CONCRETE STRUCTURES

1. Specifications: Maryland Department of Transportation, State Highway Administration (SHA) "Standard Specifications for Construction and Materials", October, 1993 edition, for materials and construction, including all interim specifications.

AASHTO "Standard Specifications for Highway Bridges", dated 1989, for design, including all interim specifications. Concrete design by the "Service Load Design Method".

2. Concrete: Shall meet the requirements of SHA Sections 414 and 902, Mix No. 3.


Contractor shall add color mix at plant in accordance with manufacturer recommendation "C-42 Mass Pigment" as manufactured by L. M. Scofield Company (213) 723-5285.

Contractor shall supply mix design for approval prior to application. Load and mix tickets shall be supplied for each truck delivery. No partial field mixes shall be allowed.

All concrete shall attain a minimum compressive strength of 3,500 PSI at 28 days. Design $f_c = 1,200$ PSI.

All exposed edges shall be chamfered 3/4" x 3/4". All construction keys are shown nominal size.

3. Reinforcing Steel: Reinforcing steel shall conform to ASTM A-615, Grade 60. Where not indicated, bar lap splices shall be in accordance with AASHTO specifications. The minimum concrete cover shall be 2 inches unless otherwise noted. Design $f_s = 24,000$ PSI.



(A) Stone Outlet Protection III
Not to Scale

Stone Outlet Protection Specifications

4. Foundation: Presumed soil bearing capacity = 2,500 PSF. The engineer must approve all foundations prior to concrete placement. If unsuitable material is encountered, the material shall be undercut and backfilled with structural backfill.

8. ROCK RIP-RAP
Rock rip-rap shall meet the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 901.02.

The rip-rap shall be placed to the required thickness in one operation. The rock shall be delivered and placed in a manner that will insure the rip-rap in place shall be reasonably homogeneous with the larger rocks uniformly distributed and firmly in contact one to another with the smaller rocks filling the voids between the larger rocks. Filter cloth shall be placed under all rip-rap and shall meet the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 921.09.

9. CARE OF WATER DURING CONSTRUCTION

All work on permanent structures shall be carried out in areas free from water. The Contractor shall construct and maintain all temporary dikes, levees, cofferdams, drainage channels, and stream diversions necessary to protect the areas to be occupied by the permanent works. The contractor shall also furnish, install, operate, and maintain all necessary pumping and other equipment required for removal of water from the various parts of the work and

for maintaining the excavations, foundation, and other parts of the work free from water as required or directed by the engineer for constructing each part of the work. After having served their purpose, all temporary protective works shall be removed or leveled and graded to the extent required to prevent obstruction in any degree whatsoever of the flow of water to the spillway or outlet works and so as not to interfere in any way with the operation or maintenance of the structure. Stream diversions shall be maintained until the full flow can be passed through the permanent works. The removal of water from the required excavation and the foundation shall be accomplished in a manner and to the extent that will maintain stability of the excavated slopes and bottom of required excavations and will allow satisfactory performance of all construction operations. During the placing and compacting of material in required excavations, the water level at the locations being refilled shall be maintained below the bottom of the excavation at such locations which may require draining the water to sumps from which the water shall be pumped.

10. STABILIZATION

All borrow areas shall be graded to provide proper drainage and left in a slightly condition. All exposed surfaces of the embankment, spillway, and borrow areas, and berms shall be stabilized by seeding, liming, fertilizing and mulching in accordance with the Maryland Soil Conservation Service Standards and Specifications for Critical Area Planting (MD-342) or as shown on the accompanying drawings.

11. EROSION AND SEDIMENT CONTROL

Construction operations will be carried out in such a manner that erosion will be controlled and water and air pollution minimized. State and local laws concerning pollution abatement will be followed. Construction plans shall detail erosion and sediment control measures to be employed during the construction process.

12. RECOMMENDED ADDITIONAL SERVICES

Additional soil and foundation engineering, testing, and consulting services recommended for this project are summarized below:

Site Preparation and Proffiling: A Geotechnical Engineer or experienced Soils Inspector should inspect the site after it has been stripped and excavated. The inspector should determine if any undercutting or in-place densification is necessary to prepare a subgrade for fill placement.

Fill Placement and Compaction: A Geotechnical Engineer or experienced Soils Inspector should witness any required filling operations and should take sufficient in-place density tests to verify that the specified degree of fill compaction is achieved. He should observe and approve borrow materials used and should determine if their existing moisture contents are suitable.

- SEE SHEET 9 FOR TOPSOIL SPECIFICATIONS.
- SEE SHEET 8 FOR PERMANENT AND TEMPORARY SEEDING SPECIFICATIONS.

15. CONTRACTOR SHALL IMPORT CLAY MATERIAL FROM OFFSITE, WITH AMPLE TESTING BY THE GEOTECHNICAL ENGINEER.


Construction Specifications
1. The subgrade for the filter, rip-rap, or gabion shall be prepared to the required lines and grades. Any fill required in the subgrade shall be compacted to a density of approximately that of the surrounding undisturbed material.

2. The rock or gravel shall conform to the specified grading limits when installed respectively in the rip-rap or filter.


3. Geotextile class C shall be protected from punching, cutting, or tearing. Any damage other than an occasional small hole shall be repaired by placing another piece of geotextile over the damaged part or by completely replacing the geotextile. All overlaps whether for repairs or for joining two pieces of geotextile shall be a minimum of one foot.

4. Stone for the rip-rap or gabion outlets may be placed by equipment. They shall be constructed to the full course thickness in one operation and in such a manner as to avoid displacement of underlying materials. The stone for rip-rap or gabion outlets shall be delivered and placed in a manner that will ensure that it is reasonably homogeneous with the smaller stones and spalls filling the voids between the larger stones. Rip-rap shall be placed in a manner to prevent damage to the filter blanket or geotextile. Hand placement will be required to the extent necessary to prevent damage to the permanent works.


5. The stone shall be placed so that it blends in with the existing ground. If the stone is placed too high then the flow will be forced out of the channel and scour adjacent to the stone will occur.



(B) Profile Along C of Dam
Scale: Horiz. 1" = 50'
Vert. 1" = 5'



Forebay Conveyance Window for Structure S-1
Not to Scale



(C) Storm Drain Profile
Scale: Horiz. 1" = 50'
Vert. 1" = 5'

APPROVED: HOWARD COUNTY DEPT. OF PLANNING & ZONING
CHIEF, DEVELOPMENT ENGINEERING DIVISION
CHIEF, DIVISION OF LAND DEVELOPMENT
DIRECTOR

Date	No.	Revision Description
10/21/97	1	REVISED STRUCTURE SCHEDULE AND FOREBAY.
3-4-98	1	REVISED WSE

Montpelier Research Park
HOWARD COUNTY MARYLAND

DMW
Daft McCune Walker, Inc.
A Team of Land Planners, Landscape Architects, Engineers, Surveyors & Environmental Professionals
200 East Pennsylvania Avenue
Towson, Maryland 21286
410 286 3333
Fax 286 4706

SUBDIVISION NAME	SECTION/AREA	LOT/PARCEL
Montpelier	124,125, & ROAD BED	

TITLE
STORM WATER MANAGEMENT DETAILS

Des By: ZAL Scale: As Shown Proj. No. 941715
Dwn By: TPC, MSS Date: 10-9-97
Chk By: Approved: 13 OF 18

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.
U.S.D.A. NATIONAL RESOURCE CONSERVATION SERVICE
10-29-97
DATE
10/27/97
DATE
HOWARD SOIL CONSERVATION DISTRICT

DEVELOPERS CERTIFICATE:
I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT AND PLANNING TRAINING COURSE FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I/SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I/ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

ENGINEERS CERTIFICATE:
I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL, REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION.

STRUCTURE SCHEDULE

NO.	TYPE	SIZE	LOCATION		REMARKS
			EAST	NORTH	
M-1	MODIFIED A-10 INLET	72"	361.50	377.50	
S-1	CONCRETE END SECTION	72"	360.11	360.00	HOWARD CO. STD. DETAIL SD 5.1
S-601	RISER STRUCT. (SEE DETAILS)				SEE DETAIL SHEET 12
S-602	HEADWALL SUPPORT DETAIL FOR 6" D.I.P.		364.00	365.5	SEE DETAIL SHEET 12
S-600	TYPE 'A' HEADWALL FOR 36" PIPE		351.30	355.8	HOWARD CO. STD. DETAIL SD 5.11

Professional Engr. No. 16872

10-9-97
Date

Professional Engr. No. 16872

Professional Engr. No. 16872

0.5± ACRES
POTENTIAL
AFFORESTATION

1.4± ACRES EXISTING FOREST
0.7± ACRES CLEARED
0.7± ACRES RETAINED

0.8± ACRES
FOREST
CONSERVATION
AREA A

0.5± ACRES
POTENTIAL
AFFORESTATION
MgC3

0.1± ACRES
AFFORESTATION
PLANTING ZONE 1

0.2± ACRES EXISTING FOREST
0.0 ACRES CLEARED
0.2± ACRES RETAINED


0.1± ACRES
AFFORESTATION
PLANTING ZONE 1

NO GRADING
PROPOSED
AT THIS TIME

0.3± ACRES
FOREST
CONSERVATION
AREA B

NOTE:
THE FOREST CONSERVATION EASEMENTS HAVE BEEN ESTABLISHED TO FULFILL THE REQUIREMENTS OF SECTION 16.1200 OF THE HOWARD COUNTY CODE, FOREST CONSERVATION ACT. NO CLEARING, GRADING OR CONSTRUCTION IS PERMITTED WITHIN THE FOREST CONSERVATION EASEMENT; HOWEVER, FOREST MANAGEMENT PRACTICES AS DEFINED IN THE DEED OF FOREST CONSERVATION EASEMENT ARE ALLOWED.


Johns Hopkins University
Applied Physics Laboratory
4009625
P 289



KEY SHEET

LEGEND

SYMBOL	DESCRIPTION
[Stippled pattern]	SLOPES = >25%
[Cross-hatched pattern]	SLOPE = 15%-25%
[Wavy line]	STREAM
[M33, M32, M31]	SOILS
[Dashed line]	EXISTING CONTOURS
[Circle with dot]	APPROX. LOCATION SPECIMEN TREE
[Dotted line]	EXISTING TREES/ TREE LINE
[Wavy line with dots]	WETLAND/STREAM BUFFER
[Dotted area]	WETLAND
[Dashed line]	PROPOSED CONTOURS
[Thick dashed line]	FLOODPLAIN
[Thin dashed line]	LIMIT OF DISTURBANCE
[Dotted line]	FOREST CONSERVATION EASEMENT
[Thick solid line]	20' WIDE UTILITY EASEMENT
[Cross-hatched area]	FOREST TO BE CLEARED
[Dotted area]	EXISTING FOREST TO BE RETAINED
[Cloud-like pattern]	AFFORESTATION
[Dotted area]	POTENTIAL AFFORESTATION
[Line with crosses]	FOREST PROTECTION FENCE



MATCHLINE SEE SHEET 16 MATCHLINE SEE SHEET 17



APPROVED: HOWARD COUNTY DEPT. OF PLANNING & ZONING	
CHIEF, DEVELOPMENT ENGINEERING DIVISION	10/29/97 DATE
CHIEF, DIVISION OF LAND DEVELOPMENT	10/29/97 DATE
DIRECTOR	10/29/97 DATE

Date No. Revision Description



Montpelier
Research Park
HOWARD COUNTY MARYLAND
OWNER/DEVELOPER: HOPKINS ROAD LIMITED PARTNERSHIP
9030 RED BRANCH ROAD, SUITE 200 COLUMBIA, MD 21046

DMW Daft · McCune · Walker, Inc. A Team of Land Planners, Landscape Architects, Engineers, Surveyors & Environmental Professionals		200 East Pennsylvania Avenue Towson, Maryland 21286 410 296 3333 Fax 296 4705
PROJECT NAME Montpelier	SECTION AREA 124,125, & ROAD BED	LOT/PARCEL # 6051.02
PLAT OR LP L3691, F508	BLOCK # 41	TAXZONE MAP SUN
WATER CODE E 21	SEWER CODE 6440000	

10.9.97
Date

Landscape Architect No. 551

TITLE NW FOREST CONSERVATION AFFORESTATION PLAN		
Des By: JAR	Scale: 1" = 50'	Proj. No. 941715
Drn By: TPC	Date: 10-9-97	15 OF 18
Chk By:	Approved:	



LEGEND

SYMBOL	DESCRIPTION
[Dark Gray Shaded Area]	SLOPE = >25%
[Medium Gray Shaded Area]	SLOPE = 15%-25%
[Blue Line]	STREAM
[Dotted Pattern]	SOILS
[Dashed Line]	EXISTING CONTOURS
[Solid Line]	APPROX. LOCATION
[Circle with 'X']	EXISTING TREES/ TREE LINE
[Wavy Line]	WETLAND/STREAM BUFFER
[Blue Area]	WETLAND
[Thin Solid Line]	PROPOSED CONTOURS
[Dotted Line]	FLOODPLAIN
[Dashed Line]	LIMIT OF DISTURBANCE
[Thick Dashed Line]	FOREST CONSERVATION EASEMENT
[Thick Solid Line]	20' WIDE UTILITY EASEMENT
[Cross-hatch Pattern]	FOREST TO BE CLEARED
[Dotted Pattern]	EXISTING FOREST TO BE RETAINED
[Circle with 'X']	AFFORESTATION
[Dotted Pattern]	POTENTIAL AFFORESTATION
[Dashed Line]	FOREST PROTECTION FENCE

APPROVED: HOWARD COUNTY DEPT. OF PLANNING & ZONING

CHIEF, DEVELOPMENT ENGINEERING DIVISION *[Signature]* 10/29/97 DATE

CHIEF, DIVISION OF LAND DEVELOPMENT *[Signature]* 10/29/97 DATE

DIRECTOR *[Signature]* 10/29/97 DATE

Date	No.	Revision	Description


Montpelier Research Park
 HOWARD COUNTY MARYLAND
 OWNER/DEVELOPER: HOPKINS ROAD LIMITED PARTNERSHIP
 9030 RED BRANCH ROAD, SUITE 200 COLUMBIA, MD 21045



DMW
 Daf - McCune - Walker, Inc.
 A Team of Land Planners, Landscape Architects, Engineers, Surveyors & Environmental Professionals
 200 East Pennsylvania Avenue, Towson, Maryland 21286
 410 286 3333 Fax 286 4705

SUBDIVISION NAME: Montpelier	SECTION AREA: 124.125 & ROAD BED
PLAT # OR L.P. BLOCK # ZONE: 13691, P505, 17, PEC	FAVORABLE MAP: 41
WATER CODE: E 21	SEWER CODE: 6440000
DATE: 10-9-97	DATE: 10-9-97

TITLE: SE FOREST CONSERVATION AFFORESTATION PLAN

Des By: JAR Scale: 1" = 50' Proj. No. 941715
 Drn By: TPC Date: 10-9-97
 Chk By: Approved: **16 OF 18**





LEGEND

SYMBOL	DESCRIPTION
[Dark Gray Box]	SLOPE = >25%
[Medium Gray Box]	SLOPE = 15%-25%
[Blue Line]	STREAM
[Dotted Pattern]	SOILS
[Dashed Line]	EXISTING CONTOURS
[Dotted Circle]	APPROX. LOCATION SPECIMEN TREE
[Dotted Line]	EXISTING TREES/TREE LINE
[Wavy Line]	WETLAND/STREAM BUFFER
[Green Area]	WETLAND
[Dashed Line]	PROPOSED CONTOURS
[Dotted Line]	FLOODPLAIN
[Dashed Line]	LIMIT OF DISTURBANCE
[Dotted Line]	FOREST CONSERVATION EASEMENT
[Thick Dashed Line]	20' WIDE UTILITY EASEMENT
[Cross-hatch Pattern]	FOREST TO BE CLEARED
[Dotted Pattern]	EXISTING FOREST TO BE RETAINED
[Dotted Circle]	AFFORESTATION
[Dotted Circle]	POTENTIAL AFFORESTATION
[Dashed Line]	FOREST PROTECTION FENCE

Johns Hopkins University
Applied Physics Laboratory
4000625
P 289

APPROVED: HOWARD COUNTY DEPT. OF PLANNING & ZONING

CHIEF, DEVELOPMENT ENGINEERING DIVISION	10/29/97 DATE
CHIEF, DIVISION OF LAND DEVELOPMENT	11/21/97 DATE
DIRECTOR	10/29/97 DATE

Date	No.	Revision Description

Montpelier
Research Park
HOWARD COUNTY MARYLAND
OWNER/DEVELOPER: HOPKINS ROAD LIMITED PARTNERSHIP
9030 RED BRANCH ROAD, SUITE 200 COLUMBIA, MD 21045

DMW
Daft · McCune · Walker, Inc.
A Team of Land Planners, Landscape Architects, Engineers, Surveyors & Environmental Professionals
200 East Pennsylvania Avenue
Towson, Maryland 21286
410 296 3333
Fax 296 4705

SUBDIVISION NAME	Montpelier	SECTION/AREA	124,125, & ROAD BED
PLAY # OR LP	13891, P505	BLOCK #/ZONE	17 / PEC
TAXATION MAP	41	SUBJECT DISTRICT	5th
WATER CODE	E 21	SEWER CODE	6440000
CENSUS TRACT	6051.02		



TITLE: **NE FOREST CONSERVATION/AFFORESTATION PLAN**

Des By: JAR	Scale: 1" = 50'	Proj. No. 941715
Drn By: TPC	Date: 10-9-97	17 OF 18
Chk By:	Approved:	

10.9.97
Date

Landscape Architect No. 521






- NOTES:
1. THIS DETAIL IS FOR FOREST PROTECTION FENCE ONLY.
 2. FOREST RETENTION AREA WILL BE SET AS PART OF THE REVIEW PROCESS.
 3. BOUNDARIES OF FOREST RETENTION AREA SHOULD BE STAKED AND FLAGGED PRIOR TO INSTALLING THE DEVICE.
 4. ROOT DAMAGE SHALL BE AVOIDED.
 5. PROTECTION SIGNAGE MAY ALSO BE USED.
 6. FOREST PROTECTION FENCE SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.


Forest Protection Fence

Not To Scale



Planting of Container Grown Material


Not To Scale



SIGNS TO BE PLACED ON METAL POSTS 5'-6" ABOVE FINISH GRADE. PLACE SIGNS EVERY 50' AROUND PERIMETER OF FOREST CONSERVATION AREA.

Permanent Signage

Not To Scale



SIGNS TO BE PLACED ON METAL POSTS 5'-6" ABOVE FINISH GRADE. PLACE SIGNS EVERY 50' AROUND PERIMETER OF FOREST RETENTION AREA.

Temporary Signage

Not To Scale

GOALS & OBJECTIVES

Development of the Montpelier site under the current Forest Conservation Act requires the reforestation of approximately 14.4 acres. Approximately 10.4 acres of afforestation / reforestation will occur on site. Potentially 2.8 acres of additional afforestation / reforestation is available on site. The remaining 1.2 acres will be satisfied by fee-in-lieu payment at a rate of \$0.30 per square foot of forest cover, or \$15,962.00.

A portion of the forest conservation mitigation requirements have been fulfilled by the forest conservation plan for this project. With any further subdivision or site development plans, the remaining obligations must be satisfied.

The objective of afforestation / reforestation at Montpelier is to establish a fast growing hardwood forest which mirrors the species composition of the surrounding existing forests. Exotic, invasive plant material will be removed from the afforestation / reforestation area prior to any planting. (Then the soil will be stabilized with a warm season grass (annual ryegrass). Within two years post-construction stabilization young container grown stock will be installed, as studies indicate significantly higher survival rates for such plants. Afforestation / reforestation plantings will be established adjacent to the stream, wetland and floodplain resources in an effort to augment the existing vegetation thereby increasing the functional value of subject areas and providing a higher level of buffering protection to adjacent water resources. A portion of the plantings will be established in the stream water management facility to provide shade and improve water quality. A Forest Conservation Easement will be placed on portions of the existing forest to remain and on all afforestation / reforestation areas.

FOREST RETENTION

Tree retention/Soil Protection areas will be delineated with temporary signage as appropriate. See Temporary Signage Detail prior to the beginning of any construction activity. Attachment of signs to trees is prohibited.

Forest protection fencing and retention area signage to be installed during later phases of construction where grading has not been indicated.

PRECONSTRUCTION MEETING/CONSTRUCTION PERIOD PRACTICES

Before construction begins, a required preconstruction meeting shall be held. The principle contractor, engineer, Howard County Inspector and a qualified forest professional familiar with the plan shall be present. All items pertaining to forest retention, tree preservation and construction period practices shall be discussed.

Any changes to the plan due to on-site conditions must be approved by the Howard County Department of Planning and Zoning. No grading, excavation, utility placement, sediment and erosion control activities, or vehicular traffic will occur within forest retention areas. Storage of equipment and materials shall not be permitted in the forest retention areas. There will be no burial or disposal of discarded material on-site within the retention area. There will be no open burning within 100 feet of woodlands. Temporary structures including, but not limited to construction trailers, sanitary facilities, etc shall not be placed within the forest retention areas. Employee parking shall not be permitted in the forest retention areas.

POST CONSTRUCTION MANAGEMENT/MAINTENANCE BY CONTRACTOR

All dead trees or tree limbs which pose an immediate safety hazard will be felled. Trees dropped within the forest retention area will not be removed. All temporary forest protection structures will be removed after construction and permanent signage will be placed where indicated on the plan. A 2-year Contractor's Maintenance and Monitoring Period shall begin at mobilization. Seventy five percent surety must be guaranteed for this period. The site shall be inspected at the end of the two year period to ascertain survivorship and provide for replacement if necessary.

The Contractor's maintenance of new planting shall consist of watering, cultivating, weeding, and mulching as necessary to insure survival. Contractor shall protect planting areas and plants at all times against damage of all kinds for duration of maintenance period. Maintenance includes temporary protection barriers and signs as required for protection. If any plants become damaged or injured, because sufficient protection was not provided, treat or replace as directed by Landscape Architect at no additional cost to Owner.

ALL FOREST RETENTION & AFFORESTATION AREAS SHOWN ON THIS PLAN TO BE PLACED IN FOREST CONSERVATION EASEMENT (POTENTIAL AFFORESTATION AREA NOT INCLUDED)

STANDARDS AND SPECIFICATIONS FOR PLANTING

1. PLANT MATERIAL SELECTION
 - A. Nursery grown plant materials greater than 1" caliper should meet or exceed the requirements of the American Nurseryman Specifications, i.e. should be typical of the species and variety, have a normal habit of growth, be first quality, sound, vigorous, well-branched, have healthy, well-furnished root systems, and be free of disease, insect pests and mechanical injuries.
 - B. Planting stock less than 1" caliper should meet the following standards:
 - Seedlings:
 - Hardwoods - 14" to 12" caliper with roots not less than 8" long
 - Shrubs - 16" or larger caliper with 5" root system.
2. PLANTING SITE PREPARATION
 - Soils shall not be disturbed outside the area necessary for planting individual specimens and the removal of exotic invasive plant material. These areas should be stabilized as shown on the temporary seeding notes on sheet 6.
3. PLANTING PERIOD
 - All material shall be planted between September 15 and May 31. Material shall not be installed when ground is frozen.
4. PLANT MATERIAL STORAGE
 - Plants should be planted within 24 hours of delivery if possible. Plant material which are left unplanted for more than 24 hours shall be protected from direct sun and weather and kept moist. Nursery stock should not be left unplanted for more than two weeks.
5. ON-SITE INSPECTION
 - Prior to planting, planting stock shall be inspected by the landscape architect or other qualified professional familiar with this plan. Plant material not conforming to standard nurseryman specifications for size, form, vigor, roots, trunk wounds, insects and disease should be replaced.
6. TOPSOIL FOR PLANTING SOIL
 - A. On-site material or imported from same source as topsoil used on site for finish grading.
 - 1. Uniform composition, free of subsoil, clay lumps, stones, stumps, roots or similar objects larger than 1 inch.
 - 2. Topsoil must be free of plants or plant parts of bermudagrass, quackgrass, Johnsongrass, nutcrackergrass, nutcrackergrass, ryegrass, Canada thistle, or others as specified.
 - 3. All topsoil shall be tested by a recognized laboratory for pH and soluble salts. A pH of 4.5 to 7.5 is required. Soluble salts shall not be higher than 500 parts per million.
7. ADDITIVE FOR BACKFILL MIX
 - A. Wood Residues:
 - 1. Source shall be well composed, not chemically treated.
 - 2. Physical properties - grading:

U.S. Size	Dry Weight Percent Passing
No. 4	100
No. 10	95 - 100
No. 15	90 - 100
No. 35	65 - 100
No. 60	0 - 50
No. 100	0 - 30
No. 200	0 - 7
 - B. Sand:
 - 1. Physical Properties - Grading:

U.S. Size	Dry Weight Percent Passing
No. 4	100
No. 10	95 - 100
No. 15	90 - 100
No. 35	65 - 100
No. 60	0 - 50
No. 100	0 - 30
No. 200	0 - 7
 - C. Chemistry:
 - Saturation Extract Conductivity (EC) _____ NI - 3.0
 - Sodium Absorption Ratio (SAR) _____ NI - 6.0
 - Boron (B) - ppm in saturation extract solution _____ NI - 1.0
 - Reaction (pH) _____ 6.0 - 7.5
 - 5. Salinity: Maximum saturation extract conductivity 1.0 millimhos per cm at 25 degrees centigrade.

10. LAYOUT AND EXCAVATION OF PLANTING AREAS

- A. Plants shall be placed in each zone at random locations shown at spacing as indicated on the plan.
- B. The Landscape Architect or qualified professional will check location of plants in the field and shall adjust to exact position before planting begins.
- C. Subsoil shall not be worked when moisture content is so great that excessive compaction will occur, nor when it is so dry that clods will not readily break. Water shall be applied, if necessary, to bring soil to an optimum moisture content before tilling and planting.
- D. Tree pits shall not be excavated more than 24 hours in advance of planting operation. Tree pits shall be excavated to the following dimensions:

Excavation for	Width	Depth
Container Trees	Can + 12 in.	Can + 4 in.
B&B Trees	Can + 12 in.	Ball + 4 in.

11. PREPARING PLANT MATERIALS FOR PLANTING

- A. Container stock shall be removed carefully after care has been cut on two sides with approved cutter. Do not use spade to cut cans. Do not lift or handle container plants by tops, stems or tanks at any time.
- B. Do not bend or handle any plant with wire or rope at any time so as to damage bark or break branches. Lift and handle plants only from bottom of ball.
- C. Balled and burlapped (B&B) plants shall have firm balls of earth. Plants moved with a ball will be accepted if the ball is cooled or broken before or during planting operations. B&B material shall be dug only when dormant. Pre-dug stored B&B material shall be inspected and approved at the storage site.
- D. Do not root for bare rooted trees into excavated pits - custom dig pits to receive roots without deformation.

12. MIXING

- A. Mix soil base, amendments and chemical additives by mechanical means.
- B. Soil and sand bases shall be completely pulverized and free of lumps or aggregated material. Moisture content of base materials shall not be such that chemical granular or pelletized additives become dissolved during the mixing process.
- C. Mix media in quantities of not less than 20 cubic yards or mix total quantity required if less than 20 cubic yards. The Contractor shall be responsible for continuity between batches.
- D. Contaminating backfill mix with unsorted soil in backfill mixing lots shall be avoided.

13. INSTALLATION OF CONTAINERIZED PLANT MATERIAL

- A. Scarify the walls and bottom of all plant pits immediately prior to the placement of plant and backfill mix. The Contractor shall remove all glazing of soil caused by an auger or mechanical tillage digger.
- B. Place B&B plants carefully in the prepared planting pit. Do not disturb soil ball or roots when or during until backfill settlement is complete and tree is seated, if applicable. Fill planting pit by bedding such 8 inches of backfill for balls greater than 24 inch diameter. Fill plant pits with soil mix to depth to receive plant root ball, so that top of balls 2 inches above finished grade. Wrap trunks with double layer of tree wrap.
- C. Wells around trees and shrubs, after planting is complete, form a soil well 3 inches high around each plant, extending to the outer limit of the plant pit in accordance with planting details shown on the Drawings.
- D. Smooth planted areas to conform to specified grades after full settlement as occurred. Contractor shall bear final responsibility for proper surface drainage of planted areas. Any discrepancy in the drawings or specifications, obstructions on the site, or prior work done by another party, which Contractor feels precludes establishing proper drainage shall be brought to the attention of the Landscape Architect in writing.
- E. Water all plants immediately after planting.
- F. Spread mulch in required areas to the compacted depth of 2 inches.

GUARANTEE:


A MINIMUM SURVIVAL RATE OF 75% IS TO BE GUARANTEED BY THE DEVELOPER AT THE END OF THE TWO YEAR MAINTENANCE PERIOD.

Reforestation Planting

Species	Size	Spacing	Quantity
ZONE 1 (same slopes)			
Acer rubrum	24" white / Cort.	8'-11' min.	200
Prunus serotina	24" white / Cort.	8'-11' min.	200
Fragaria pennsylvanica	24" white / Cort.	8'-11' min.	200
Quercus alba	24" white / Cort.	8'-11' min.	200
Aster sp.	24" white / Cort.	8'-11' min.	200
Liriodendron tulipifera	24" white / Cort.	8'-11' min.	200
Liriodendron tulipifera	24" white / Cort.	8'-11' min.	200
Quercus coccinea	24" white / Cort.	8'-11' min.	200
Sesuvium album	24" white / Cort.	8'-11' min.	200
Viburnum acerifolium	24" white / Cort.	8'-11' min.	200
Lindera benzoin	24" white / Cort.	8'-11' min.	200
Hamamelis virginiana	24" white / Cort.	8'-11' min.	200
Viburnum acerifolium	24" white / Cort.	8'-11' min.	200
Total			2900
ZONE 2 (wetland)			
Quercus alba	24" white / Cort.	8'-11' min.	20
Acer rubrum	24" white / Cort.	8'-11' min.	20
Sida sp.	24" white / Cort.	8'-11' min.	20
Magnolia virginiana	24" white / Cort.	8'-11' min.	20
Liquidambar styraciflua	24" white / Cort.	8'-11' min.	20
Sida sp.	24" white / Cort.	8'-11' min.	20
Vaccinium corymbosum	24" white / Cort.	8'-11' min.	20
Viburnum acerifolium	24" white / Cort.	8'-11' min.	20
Total			160
ZONE 3 (pond road)			
Acer rubrum	1" cal / Cort.	8'-11' min.	30
Prunus serotina	1" cal / Cort.	8'-11' min.	30
Fragaria pennsylvanica	1" cal / Cort.	8'-11' min.	30
Liriodendron tulipifera	1" cal / Cort.	8'-11' min.	30
Quercus coccinea	1" cal / Cort.	8'-11' min.	30
Lindera benzoin	1" cal / Cort.	8'-11' min.	30
Hamamelis virginiana	1" cal / Cort.	8'-11' min.	30
Total			240

Forest Conservation Chart

7.5± ACRES EXISTING FOREST
3.8± ACRES TO BE CLEARED
3.7± ACRES TO BE RETAINED
14.4± ACRES AFFORESTATION/REFORESTATION REQUIRED
10.4± ACRES AFFORESTATION/REFORESTATION ON SITE
2.8± ACRES POTENTIAL AFFORESTATION/REFORESTATION
1.2± ACRES FEE IN-LIEU
15.3± ACRES FOREST CONSERVATION EASEMENT
.8± ACRES AREA A
.3± ACRES AREA B
1.0± ACRES AREA C
8.3± ACRES AREA D
4.9± ACRES AREA E



Typical Tree Planting (For container grown)

Not To Scale

Forest Conservation Worksheet


1. BASIC SITE DATA
 - Gross Site Area: 104.0 Acres
 - Area within 100 year floodplain: 1.2 Acres
 - Area within MSHA row reservation: 7.5 Acres
 - Net tract area: 95.3 Acres
 - Land use category (R-RLD, R-RMD, R-S, CVO, I): PEC
2. INFORMATION FOR CALCULATIONS
 - a. Net tract area: 95.3 Acres
 - b. Reforestation threshold 15% x A: 14.3 Acres
 - c. Afforestation threshold 15% x A: 14.3 Acres
 - d. Existing forest on net tract area: 7.5 Acres
 - e. Forest areas to be cleared: 3.8 Acres
 - f. Forest areas to be retained: 3.7 Acres
3. DETERMINING REQUIREMENTS: AFFORESTATION OR REFORESTATION
 - AFFORESTATION: If existing forest areas are less than the afforestation minimum (if D is less than C), afforestation requirements apply.
4. AFFORESTATION CALCULATIONS
 - a. Net tract area: 95.3 Acres
 - b. Afforestation minimum 15% x A: 14.3 Acres
 - c. Existing forest on net tract area: 7.5 Acres
 - d. Forest areas to be cleared: 3.8 Acres
 - e. Forest areas to be retained: 3.7 Acres

Clearing below the Minimum

If existing forests are less than the afforestation minimum (if D is less than C) and clearing is proposed, the following calculations apply:

Afforestation for unforested areas below minimum C-D = 6.8 Acres
afforestation for clearing below minimum E-C = 7.8 Acres
Total afforestation required C-D + E-C = 14.4 Acres

Afforestation requires the total forest area to be equal to the minimum and it requires compensation for clearing.



Planting Design Schematic

Not To Scale

Conditions and Management Practices for Working in Nontidal Wetlands and Buffers

- A. REMOVE EXCAVATED MATERIAL, CONSTRUCTION MATERIAL OR DEBRIS TO AN UPLAND DISPOSAL AREA OUTSIDE OF ANY WATERWAY, FLOODPLAIN, NONTIDAL WETLAND, OR BUFFER.
- B. IF BACKFILL IS OBTAINED, USE CLEAN MATERIAL FREE OF WASTE METAL PRODUCTS, UNSIGHTLY DEBRIS, TOXIC MATERIAL OR ANY OTHER DELETERIOUS SUBSTANCE.
- C. PLACE MATERIALS IN A LOCATION AND MANNER WHICH DOES NOT ADVERSELY IMPACT SURFACE OR SUBSURFACE WATER FLOW INTO OR OUT OF THE NONTIDAL WETLAND;
- D. MAINTAIN THE HYDROLOGIC REGIME OF NONTIDAL WETLANDS OUTSIDE THE LIMITS OF DISTURBANCE.
- E. RECTIFY ANY NONTIDAL WETLANDS AND BUFFERS TEMPORARILY IMPACTED BY THE PERMITTED ACTIVITY. ALL STABILIZATION IN THE WETLAND AND BUFFER SHALL BE OF THE FOLLOWING RECOMMENDED SPECIES: ANNUAL RYEGRASS (Lolium multiflorum), MILLET (Seteria italica), OATS (Urtica sp.) AND/OR RYE (Secale cereale). OTHER NON-PERSISTENT VEGETATION MAY BE ACCEPTABLE BUT MUST BE APPROVED BY THE NONTIDAL WETLANDS AND WATERWAYS DIVISION, KENTUCKY 31 FISCUSE SHALL NOT BE UTILIZED IN THE WETLAND OR BUFFER. ALL TEMPORARY FILLS SHALL BE REMOVED IN THEIR ENTIRETY ON OR BEFORE THE COMPLETION OF CONSTRUCTION.
- F. TO PROTECT IMPORTANT AQUATIC SPECIES, IN-STREAM WORK IS PROHIBITED AS DETERMINED BY THE CLASSIFICATION OF THE STREAM AS FOLLOWS.
- G. NO REMOVAL OF VEGETATION, GRADING, FILLING, DRAINING, OR OTHER ALTERATION OF THE NONTIDAL WETLANDS OR BUFFER OUTSIDE THE LIMITS OF DISTURBANCE SHALL OCCUR WITHOUT WRITTEN AUTHORIZATION FROM THE WATER MANAGEMENT ADMINISTRATION.

USE 1/2" WATERS, IN-STREAM WORK MAY NOT BE CONDUCTED DURING THE PERIOD MARCH 1 - JUNE 15 INCLUSIVE, DURING ANY YEAR.

10. 9. 97
Date

LANDSCAPE ARCHITECT

STATE OF MARYLAND
1651
LANDSCAPE ARCHITECT

LANDSCAPE ARCHITECT No. 551

APPROVED: HOWARD COUNTY DEPT. OF PLANNING & ZONING

CHIEF, DEVELOPMENT ENGINEERING DIVISION
10/29/97
DATE

CHIEF, DIVISION OF LAND DEVELOPMENT
10/29/97
DATE

DIRECTOR
11/20/97
DATE

Date	No.	Revision	Description

Montpelier
Research Park
HOWARD COUNTY MARYLAND

DMW
Daft - McCue - Walker, Inc.
A Team of Land Planners, Landscape Architects, Engineers, Surveyors & Environmental Professionals
200 East Pennsylvania Avenue
Towson, Maryland 21286
410 296 3333
Fax 296 4705

SUBDIVISION NAME: Montpelier SECTION/AREA: REVISION # 41
PLAT # OR OF BLOCK # ZONE: L3691.5505 17 REC. ELEC DISTRICT: 5th CENSUS TRACT: 6051.02
WATER CODE: E 21 SEWER CODE: 6440000

TITLE: FOREST CONSERVATION AFFORESTATION DETAILS & NOTES

Des By: JAR Scale: Proj. No. 941715
Drn By: TPC Date: 10-9-97
Chk By: Approved: 18 OF 18