



STORMWATER MANAGEMENT SUMMARY TABLE			
PRIVATE SWM RETENTION POND			
TOTAL DRAINAGE AREA = 66.4 ACRES			
STORAGE REQUIREMENT	VOLUME	REMARKS	
WQv	Required: 135,918 cu. ft.	Approx. 43%	
	Provided: 58,477 cu. ft.	of WQv prov'd	
REv	Required: 33,979 cu. ft.	Included as part	
	Provided: 33,979 cu. ft.	of WQv	
Cpv	Required: 176,575 cu. ft.	"	
	Provided: 0.00 cu. ft.		
Qp10	Required: N/A	10 Yr passed	
	Provided:	w/ 2.19' freeboard	
Qp100	Required: N/A	100 Yr passed	
	Provided:	w/ 1.29' freeboard	

** The CFv storage cannot be provided due to the spatial constraints and the requirement to pass the 5 year storm below the emergency spillway crest elevation.

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

Frank J. Coyle 4/22/03
DIRECTOR

Cindy Hamel 4/16/03
CHIEF, DIVISION OF LAND DEVELOPMENT

Charles R. ... 4/16/03
DEVELOPMENT ENGINEERING DIVISION

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL.

Jin ... 4/9/03
NATURAL RESOURCE CONSERVATION SERVICE

THIS DEVELOPMENT PLAN IS APPROVED FOR POND CONSTRUCTION SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

[Signature] 4/9/03
HOWARD SOIL CONSERVATION DISTRICT

ENGINEER'S CERTIFICATE

I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL, REPRESENTS A PRACTICAL AND MEASURABLE PLAN BASED ON MY PERSONAL OBSERVATION OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REGULATIONS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT THIS PLAN HAS BEEN REVIEWED BY A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION.

Bruce D. Burt 4/1/03
REGISTERED PROFESSIONAL ENGINEER

DEVELOPER'S CERTIFICATE

I HEREBY CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF EROSION AND SEDIMENT BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Charles R. ... 4-1-03
SIGNATURE OF DEVELOPER




REVISIONS		
No.	Date	Description

Subdivision Name: Village of Oakland Mills		Sect/Area: 2/3 & 5/1		Parcel No.: 55, Lots 4 & P/O Parcel 310, Parcel 2 Open Space Lots 4 & 8.5	
Plan No.: 5742-07	Block No.: P.B. 17, Folio 91	Zone: 3 & 9 NEW-TOWN	Tax Map No.: 36	Election District: 6th	County Tract: 6066.03
Water Code: N/A			B sewer Code: N/A		

LDE, INC.
9250 Rumsey Road, Suite 106, Columbia, MD. 21045
(410) 715-1070 (301) 596-3424 (410) 715-9540 (Fax)

DESIGNED: S.D.H.	Site Development Plan BOWL POND Village of Oakland Mills Stevens Forest Capital Project #D-1127 Section Two - Area Three Open Space Lot 4 & P/O Parcel 310, Parcel D and Section Five - Area One Open Space Lot 8.5 Tax Map 36 6th Election District - Howard County, Maryland Previous Submittals:	SCALE: 1"=30'
DRAWN: J.D.R., M.B.J.		DRAWING: 2 of 11
CHECKED: S.W.C.		JOB NO.: 01-008
DATE: 3/20/02 Rev 9/02 Rev 1/03		OWNER/DEVELOPER: COLUMBIA ASSOCIATION 10221 Winthrop Circle, Suite 100 Columbia, Maryland 21044-3410 (410) 381-0691



BASIN DESIGN DATA SUMMARY

Top of Wet Storage Volume, Elev:	335.80
Cleanout Elev:	335.30
Top of Dry Storage Vol., Elev:	336.70
Top of 10" Draw Down Standpipe, Elev:	336.70
Basin Perforations on Draw Down Standpipe, Elev:	335.80
Proposed 2 Year Peak Discharge (inflow):	4.2 cfs
Proposed 10 Year Peak Discharge (inflow):	12.7 cfs
Proposed 2 Year Peak Discharge (outflow):	0.60 cfs
Proposed 10 Year Peak Discharge (outflow):	0.80 cfs
2 Year Peak Elevation:	336.54
10 Year Peak Elevation:	338.23

Basin Outfall Data:
 2YR: Q= 0.60 cfs / V= 3.16 fps
 10YR: Q= 0.80 cfs / V= 3.45 fps
 100YR: Q= 0.90 cfs / V= 3.57 fps

(Per latest approved
 Howard County
 Little Patuxent
 River study dated
 September, 1986)
 See Sheet 1 for
 Floodplain Line Table

Patricia M. Inwood &
 John W. Hunt J.P.
 L. 1055 P.E.
 Zone: New Town

LEGEND

- Limit of disturbance for Dam construction
- No Woody Vegetation Zone
- Silt Fence
- Super Silt Fence
- Limit of disturbance for Sewer relocation and Pond/Forebay storage areas @ Proposed Treeline
- Stabilized Construction Entrance

Subdivision Name:	Village of Oakland Mills	Sect/Area:	2/3 & 5/1	Parcel No.:	6066.03
Plat No.:	15746-47	Block No.:	3 & 9	Zone:	NEW-TOWN
Plat No.:	15746-47	Block No.:	36	Election District:	6th
Plat No.:	15746-47	Block No.:	36	Census Tract:	6066.03
Water Code:	N/A	Sewer Code:	N/A		

LDE, INC.
 9250 Rumsey Road, Suite 106, Columbia, MD, 21045
 (410) 715-1070 (301) 596-3424 (410) 715-9540 (Fax)

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

Dan K. Lytle 7/22/03
 DIRECTOR

Cindy Hancock 7/16/03
 CHIEF, DIVISION OF LAND DEVELOPMENT

Chris P. ... 4/15/03
 ...

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL

Jan Myers 4/1/03
 NATURAL RESOURCE CONSERVATION

THIS DEVELOPMENT PLAN IS APPROVED FOR POND CONSTRUCTION SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

John ... 4/9/03
 HOWARD SOIL CONSERVATION DISTRICT

ENGINEER'S CERTIFICATE

I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REGULATIONS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT THE HOWARD SOIL CONSERVATION DISTRICT ENGINEER TO SUPERVISE POND CONSTRUCTION AND THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION.

Bruce D. ... 4/1/03
 SIGNATURE OF ENGINEER

DEVELOPER'S CERTIFICATE

I WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Charles ... 4-1-03
 SIGNATURE OF DEVELOPER

STATE OF MARYLAND
 PROFESSIONAL ENGINEER
 BRUCE D. ...
 4/1/03

REVISIONS

No.	Date	Description

NO WORK IS ALLOWED WITHIN THE ONSITE CLASS I STREAMS FROM MARCH 1st THRU JUNE 15th PER MDE REQUIREMENTS.

HOWARD SOIL CONSERVATION DISTRICT
STANDARD SEDIMENT CONTROL NOTES

- A minimum of 48 hours notice must be given to the Howard County Department of Inspections, Licenses and Permits, Sediment Control Division prior to the start of any construction, (313-1655).
- All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the most current "MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL", and revisions thereto.
- Following initial soil disturbance or redistribution, permanent or temporary stabilization shall be completed within: a) 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all slopes greater than 3:1, b) 14 days as to all other disturbed or graded areas on the project site.
- All sediment traps/basins shown must be fenced and warning signs posted around their perimeter in accordance with Vol. 1, Chapter 7, of the HOWARD COUNTY DESIGN MANUAL, Storm Drainage.
- All disturbed areas must be stabilized within the time period specified above in accordance with the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL (Section G) for permanent seeding, sod, temporary seeding, and mulching. Temporary stabilization with mulch alone can only be done when recommended seeding dates do not allow for proper germination and establishment of grasses.
- All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.
- Site Analysis:

Total Area of Site	3.00 Acres
Area Disturbed	1.98 Acres
Area to be roofed or paved	0.14 Acres
Area to be vegetatively stabilized	1.24 Acres
Total Cut	5722 Cu. Yds.
Total Fill	1867 Cu. Yds.
Offsite waste/borrow area location	3756 Cu. Yds. to be trucked to an offsite location with an active grading plan.

- Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
- Additional sediment control must be provided, if deemed necessary by the Howard County Sediment Control Inspector.
- On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the inspection agency is made.
- Trenches for the construction of utilities is limited to three pipe lengths or that which can be back filled and stabilized within one working day, whichever is shorter.

HOWARD SOIL CONSERVATION DISTRICT
PERMANENT SEEDING NOTES

Apply to graded or cleared areas not subject to immediate further disturbance where a permanent long-lived vegetative cover is needed.

SEEDBED PREPARATION: Loosen upper three inches of soil by raking, disking, or other acceptable means before seeding, if not previously loosened.

SOIL AMENDMENTS: In lieu of soil test recommendations, use one of the following schedules:

- PREFERRED -- Apply 2 tons per acre dolomitic limestone (92 lbs/1000sq. ft.) and 600 lbs per acre 10-10-10 fertilizer (14 lbs/1000 sq. ft.) before seeding. Harrow or disk into upper three inches of soil. At time of seeding, apply 400 lbs per acre 30-0-0 ureaform fertilizer (9 lbs/1000sq. ft.)
- ACCEPTABLE -- Apply 2 tons per acre dolomitic limestone (92 lbs/1000sq. ft.) and 1000 lbs per acre 10-10-10 fertilizer (23 lbs/1000 sq. ft.) before seeding. Harrow or disk into upper three inches of soil.

SEEDING -- For the periods March 1 thru April 30, and August 1 thru October 15, seed with 60 lbs per acre (1.4 lbs/1000sq. ft.) of Kentucky 31 Tall Fescue. For the period May 1 thru July 31, seed with 60 lbs per acre (1.4 lbs/1000sq. ft.) of Kentucky 31 Tall Fescue and 2 lbs. per acre (.05 lbs/1000sq. ft.) of weeping lovegrass. During the period of October 16 thru February 28, protect site by: Option (1) - 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring. Option (2) - Use sod. Option (3) - Seed with 60 lbs. per acre Kentucky 31 Tall Fescue and mulch 2 tons / acre well anchored straw.

MULCHING -- Apply 1-1/2 to 2 tons per acre (70 to 90 lbs/1000sq. ft.) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 210 gallons per acre (5 gal/1000sq. ft.) of emulsified asphalt on flat areas. On slopes 8 feet or higher, use 340 gallons per acre (8 gal/1000sq. ft.) for anchoring.

MAINTENANCE -- Inspect all seeding areas and make needed repairs, replacements and reseedings.

HOWARD SOIL CONSERVATION DISTRICT
TEMPORARY SEEDING NOTES

Apply to graded or cleared areas likely to be redistributed where a short-term vegetative cover is needed.

SEEDBED PREPARATION: -- Loosen upper three inches of soil by raking, disking, or other acceptable means before seeding, if not previously loosened.

SOIL AMENDMENTS: -- Apply 600 lbs per acre 10-10-10 fertilizer (14 lbs/1000sq. ft.).

SEEDING -- For periods March 1 thru April 30, and from August 15 thru October 15 seed with 2-1/2 bushels per acre of annual rye (3.2 lbs/1000sq. ft.). For the period May 1 thru August 14, seed with 3 lbs. per acre of weeping lovegrass (.07 lbs/1000sq. ft.). For the period November 16 thru February 28, protect site by applying 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring, or use sod.

MULCHING -- Apply 1-1/2 to 2 tons per acre (70 to 90 lbs/1000sq. ft.) of unrotted weed free small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 210 gallons per acre (5 gal/1000sq. ft.) of emulsified asphalt on flat areas. On slopes 8 feet or higher, use 340 gallons per acre (8 gal/1000sq. ft.) for anchoring.

Refer to the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for additional rates and methods not covered.

21.0 STANDARD AND SPECIFICATIONS FOR TOPSOIL

Definition
Placement of topsoil over a prepared subsoil prior to establishment of permanent vegetation.

Purpose
To provide a suitable soil medium for vegetative growth. Soils of concern have low moisture content, low nutrient levels, low pH, materials toxic to plants, and/or unacceptable soil gradation.

- Conditions Where Practice Applies
- This practice is limited to areas having 2:1 or flatter slopes where:
 - The texture of the exposed subsoil/parent material is not adequate to produce vegetative growth.
 - The soil material is so shallow that the rooting zone is not deep enough to support plants or furnish continuing supplies of moisture and plant nutrients.
 - The original soil to be vegetated contains material toxic to plant growth.
 - The soil is so acidic that treatment with limestone is not feasible.
 - For the purpose of these Standards and Specifications, areas having slopes steeper than 2:1 require special consideration and design for adequate stabilization. Areas having slopes steeper than 2:1 shall have the appropriate stabilization shown on the plans.

Construction and Material Specifications

- Topsoil salvaged from the existing site may be used provided that it meets the standards as set forth in these specifications. Typically, the depth of topsoil to be salvaged for a given soil type can be found in the representative soil profile section in the Soil Survey published by USDA-SGS in cooperation with Maryland Agricultural Experimental Station.

- Topsoil Specifications - Soil to be used as topsoil must meet the following:
 - Topsoil shall be a loam, sandy loam, clay loam, silt loam, sandy clay loam, loamy sand. Other soils may be used if recommended by an agronomist or soil scientist and approved by the appropriate approval authority. Regardless, topsoil shall not be a mixture of contrasting textured subsoils and shall contain less than 5% by volume of cinders, stones, slag, coarse fragments, gravel, sticks, roots, trash, or other materials larger than 1-1/2" in diameter.
 - Topsoil must be free of plants or plant parts such as bermuda grass, quackgrass, Johnsongrass, nutgrass, poison ivy, thistle, or others as specified.
 - Where the subsoil is either highly acidic or composed of heavy clays, ground limestone shall be spread at the rate of 4-8 tons/acre (200-400 pounds per 1,000 square feet) prior to the placement of topsoil. Lime shall be distributed uniformly over designated areas and worked into the soil in conjunction with tillage operations as described in the following procedures.

- For sites having disturbed areas under 5 acres:
 - Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section I - Vegetative Stabilization Methods and Materials.

- For sites having disturbed areas over 5 acres:
 - On soil meeting Topsoil specifications, obtain test results dictating fertilizer and lime amendments required to bring the soil into compliance with the following:
 - pH for topsoil shall be between 6.0 and 7.5. If the tested soil demonstrates a pH of less than 6.0, sufficient lime shall be prescribed to raise the pH to 6.5 or higher.
 - Organic content of topsoil shall be not less than 1.5 percent by weight.
 - Topsoil having soluble salt content greater than 500 parts per million shall not be used.
 - No sod or seed shall be placed on soil which has been treated with soil sterilants or chemicals used for weed control until sufficient time has elapsed (14 days min.) to permit dissipation of phytotoxic materials.
 - Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section I - Vegetative Stabilization Methods and Materials.

Note: Topsoil substitutes or amendments, as recommended by a qualified agronomist or soil scientist and approved by the appropriate approval authority, may be used in lieu of natural topsoil.

- Topsoil Application
 - When topsoiling, maintain needed erosion and sediment control practices such as diversions, Grade Stabilization Structures, Earth Dikes, Slope Silt Fence and Sediment Traps and Basins.
 - Grades on the areas to be topsoiled, which have been previously established, shall be maintained, albeit 4" - 8" higher in elevation.
 - Topsoil shall be uniformly distributed in a 4" - 8" layer and lightly compacted to a minimum thickness of 4". Spreading shall be performed in such a manner that sodding or seeding can proceed with a minimum of additional soil preparation and tillage. Any irregularities in the surface resulting from topsoiling or other operations shall be corrected in order to prevent the formation of depressions or water pockets.
 - Topsoil shall not be placed while the topsoil or subsoil is in a frozen or muddy condition, when the subsoil is excessively wet or in a condition that may otherwise be detrimental to proper grading and seedbed preparation.

Alternative for Permanent Seeding - Instead of applying the full amount of lime and commercial fertilizer, composted sludge and amendments may be applied as specified below:

- Composted Sludge Material for use as a soil conditioner for sites having disturbed areas over 5 acres shall be tested to prescribe amendments and for sites having disturbed areas under 5 acres shall conform to the following requirements:
 - Composted sludge shall be supplied by, or originate from, a person or persons that are permitted (at the time of acquisition of the compost) by the Maryland Department of the Environment under COMAR 26.04.06.
 - Composted sludge shall contain at least 1 percent nitrogen, 1.5 percent phosphorus, and 0.2 percent potassium and have a Ph of 7.0 to 8.0. If compost does not meet these requirements, the appropriate constituents must be added to meet the requirements prior to use.
 - Composted sludge shall be applied at a rate of 1 ton/1,000 square feet.
- Composted sludge shall be amended with a potassium fertilizer applied at the rate of 4 lb./1,000 square feet, and 1/3 the normal lime application rate.

References: Guideline Specifications, Soil Preparation and Sodding. MD-YA, Pub #1, Cooperative Extension Service, University of Maryland and Virginia Polytechnic Institutes. Revised 1973.

SEQUENCE OF CONSTRUCTION

- Obtain grading permit. 1 Day
- Notify the Howard County Department of Public Works Construction Inspection Division at 410-313-1855 at least 48 hours prior to beginning construction. 1 Day
- Field staking limits of disturbance in accordance with the approved grading and sediment control plan. (Sheet 3) 1 Day

Note: MDE requires the closure of the onsite streams from March 1 through June 15. No in-stream work is allowed during the closure period.

PHASE I - SEDIMENT CONTROL FOR POND RECONSTRUCTION

- Excavate for and construct #8" sewer. Utilize the filter bag device during trench construction. Note: In the event the material excavated from the proposed sewer trench is unsuitable to use for backfill, the material shall be removed from the site and trucked to an approved spoil location. Material may not be stockpiled within the wetlands, wetland buffers, streams or stream buffers or 100 year floodplain. 3 Days
- Excavate for and construct #8" public sewer. Utilize the filter bag device during trench construction. Note: In the event the material excavated from the proposed sewer trench is unsuitable to use for backfill, the material shall be removed from the site and trucked to an approved spoil location. Material may not be stockpiled within the wetlands, wetland buffers, streams or stream buffers or 100 year floodplain. 8 Days
- Immediately stabilize all disturbed areas at the end of each day in accordance with the temporary seeding notes. Daily
- Once the relocated sewer is fully operational and with the permission of the sediment control inspector, remove all site fence along the sewer alignment that may interfere with the construction of the pond. 1 Day


PHASE II - SEDIMENT CONTROL FOR POND RECONSTRUCTION

- Install perimeter controls, including silt fence, silt fence, sandbag/stone diversions, RFS, and temporary diversion pipes. 5 Days
- Clear and grub for pond sediment basin. Excavate basin to final bottom elevation (334.5). Install 24" RCP (5-3 to 5-4). 1 Week
- Proposed dam shall not be constructed until:
 - The body of the pond is dredged, formed and permanent stabilized.
 - All barns, riers, embankments and other principal spillway materials are onsite.
 - There is a 5 day clear (no precipitation) weather forecast from the National Weather Service.
 - Permission is granted by the sediment control inspector to proceed.

- Install embankment core trench. Utilize filter bag during trench construction.
- Install pond riser and barrel (8-1 to 8-2), anti-slope collars, endwall, Rip-rap in existing plunge pool, and concrete riser base in accordance with the notes and specifications on sheets 6.7, 6.8, & 9.
- Install 10" D.I.P. pond riser and attach temporary drawdown device. Install removable pumping station. 2 Weeks
- Install embankment cutoff trench and remainder of embankment to constructed top elevation. 1 Day
- Grade remainder of basin/pond, including emergency spillway, 5' safety bench, and 12' maintenance bench in accordance with the approved grading plan (sheet 3). Immediately stabilize all disturbed areas in accordance with the temporary seeding notes. 2 Weeks
- Grade fordrays B & C in accordance with the approved grading plan (sheet 3). Install fordray gabions and fordray willow protection for fordrays B and C only per detail on sheet 3. Install fordray willow protection. 1 Week
- Establish final grade in and around pond/ basin area, fordrays and emergency spillway. Install rip-rap on emergency spillway outlet channel. Immediately stabilize all disturbed areas in accordance with the permanent seeding notes. 1 Week
- Once all disturbed areas are completely stabilized in accordance with the Permanent Seeding notes and with the permission of the sediment control inspector, convert basin into permanent pond:
 - Remove temporary drawdown device from 10" D.I.P. pond drain pipe.
 - Excavate any accumulated sediment from basin to final design bottom elevation of 334.5.
 - Install trashracks on all four (4) faces of concrete riser structure in accordance with the details on sheet 3.
 - Close gate valve on 12" pond drain.
- Stabilize all remaining disturbed areas in accordance with the permanent seeding notes. With the permission of the sediment control inspector, remove all remaining sediment control devices, including silt fence, silt fence, sandbag/stone dams and temporary diversion pipes. Install fordray "A". 1 Week
- Install landscaping. 1 Week

Total Estimated Construction Time: 3 1/2 Months

SOILS LEGEND		
MAP SYMBOL	SOIL GROUP NAME	HYDROLOGIC TYPE
GIB2	Glenelg	B
GID2	Glenelg	B
GIC2	Glenelg	B
GnB2	Glenville	C
ChB2	Chester	B
MIB2	Manor	B
MIC2	Manor	B
MID3	Manor	B



Drainage Area & Soils Map
1" = 200'

LEGEND	
HYDROLOGIC SOIL GROUP BOUNDARY	---
SUB-AREA DRAINAGE DIVIDE	---
DRAINAGE AREA TO POND	---
TC FLOW PATH	---

Subdivision Name: Village of Oakland Mills	Sect/Area: 2/3 & 5/1	Parcel No. (15 - 4 - 10) Parcel 23, Parcel 24, Parcel 25, Parcel 26, Parcel 27, Parcel 28, Parcel 29, Parcel 30, Parcel 31, Parcel 32, Parcel 33, Parcel 34, Parcel 35, Parcel 36, Parcel 37, Parcel 38, Parcel 39, Parcel 40, Parcel 41, Parcel 42, Parcel 43, Parcel 44, Parcel 45, Parcel 46, Parcel 47, Parcel 48, Parcel 49, Parcel 50, Parcel 51, Parcel 52, Parcel 53, Parcel 54, Parcel 55, Parcel 56, Parcel 57, Parcel 58, Parcel 59, Parcel 60, Parcel 61, Parcel 62, Parcel 63, Parcel 64, Parcel 65, Parcel 66, Parcel 67, Parcel 68, Parcel 69, Parcel 70, Parcel 71, Parcel 72, Parcel 73, Parcel 74, Parcel 75, Parcel 76, Parcel 77, Parcel 78, Parcel 79, Parcel 80, Parcel 81, Parcel 82, Parcel 83, Parcel 84, Parcel 85, Parcel 86, Parcel 87, Parcel 88, Parcel 89, Parcel 90, Parcel 91, Parcel 92, Parcel 93, Parcel 94, Parcel 95, Parcel 96, Parcel 97, Parcel 98, Parcel 99, Parcel 100			
Plan No. 15746-47	Block No. 3 & 9	Zone NEW-TOWN	Tax Map No. 36	Election District 6th	Census Tract 6066.03
P.B. 17, Folio 91	P.B. 15, Folio 95	Water Code	Sewer Code	N/A	

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

James A. Long 4/22/02
DIRECTOR DATE

Cindy Hammett 4/24/02
CHIEF, DIVISION OF LAND DEVELOPMENT DATE

Chris D. ... 4/15/02
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL

Jim ... 4/9/02
NATURAL RESOURCE CONSERVATION SERVICE DATE

THIS DEVELOPMENT PLAN IS APPROVED FOR POND CONSTRUCTION SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

... 4/9/02
HOWARD SOIL CONSERVATION DISTRICT DATE

ENGINEER'S CERTIFICATE

I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL INSPECTION OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REGULATIONS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT THIS PLAN IS SUBJECT TO THE SUPERVISORY JURISDICTION OF THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION.

Bruce D. ... 4/1/03
SIGNATURE OF ENGINEER DATE

DEVELOPER'S CERTIFICATE

I WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Charles ... 4-1-03
SIGNATURE OF DEVELOPER DATE

STATE OF MARYLAND
REGISTERED PROFESSIONAL ENGINEER
4/1/03








REVISIONS		
No.	Date	Description

LDE, INC.
9250 Rumsey Road, Suite 106, Columbia, MD. 21045
(410) 715-1070 (301) 596-3424 (410) 715-9540 (Fax)

DESIGNED: S.D.H.
DRAWN: J.D.R., M.B.J.
CHECKED: B.D.B.
DATE: 3/2/002
Rev 9/02
Rev 1/03

OWNER/DEVELOPER: COLUMBIA ASSOCIATION
10221 Wincopin Circle, Suite 100
Columbia, Maryland 21044-3410
(410) 381-0931

SCALE: As Shown
DRAWING: 4 of 11
JOB NO: 01-008
FILE NO: SDP-02-131



BEST MANAGEMENT PRACTICES FOR WORKING IN NONTIDAL WETLANDS, WETLAND BUFFERS, WATERWAYS, AND 100-YEAR FLOODPLAINS

- No excess fill, construction material, or debris shall be stockpiled or stored in nontidal wetlands, nontidal wetland buffers, waterways, or the 100-year floodplain.
- Place materials in a location and manner that does not adversely impact surface or subsurface water flow into or out of nontidal wetlands, nontidal wetland buffers, waterways, or the 100-year floodplain.
- Do not use the excavated material as backfill if it contains waste metal products, unsightly debris, toxic material, or any other deleterious substance. If additional backfill is required, use clean material free of waste metal products, unsightly debris, toxic material, or any other deleterious substance.
- Place heavy equipment on mats or suitably operate the equipment to prevent damage to nontidal wetlands, nontidal wetland buffers, waterways, or the 100-year floodplain.
- Repair and maintain any serviceable structure or fill so there is no permanent loss of nontidal wetlands, nontidal wetland buffers, or waterways, or permanent modification of the 100-year floodplain in excess of that lost under the originally authorized structure or fill.
- Rectify any nontidal wetlands, wetland buffers, waterways, or 100-year floodplain temporarily impacted by any construction.
- All stabilization in the nontidal wetland and nontidal wetland buffer shall consist of the following species: Annual Ryegrass (*Lolium multiflorum*), Millet (*Setaria italica*), Barley (*Hordeum sp.*), Oats (*Avena sp.*), and/or Rye (*Secale cereale*). These species will allow for the stabilization of the site while also allowing for the voluntary revegetation of natural wetland species. Other non-persistent vegetation may be acceptable, but must be approved by the Nontidal Wetlands and Waterways Division. Kentucky 31 fescue shall not be utilized in wetland or buffer areas. The area should be seeded and mulched to reduce erosion after construction activities have been completed.
- After installation has been completed, make post-construction grades and elevations the same as the original grades and elevations in temporarily impacted areas.
- To protect aquatic species, in-stream work is prohibited as determined by the classification of the stream:
 - Use 1 waters: In-stream work shall not be conducted during the period March 1 through June 15, inclusive, during any year.
- Stormwater runoff from impervious surfaces shall be controlled to prevent the washing of debris into the waterway.
- Culverts shall be constructed and any riprap placed so as not to obstruct the movement of aquatic species, unless the purpose of the activity is to impound water.



Subdivision Name: Village of Oakland Mills		Sect/Area: 2/3 & 5/1		Parcel No. 201, Lot 4 & P/O Parcel 310	
Plan No. 15746-47	Block No. 3 & 9	Zone: NEW-TOWN	Tax Map No. 36	Election District: 6th	Census Tract: 6066.03
P.B. 17, Folio 91					
P.B. 15, Folio 96					
Water Code: N/A				Sewer Code: N/A	

LDE, INC.
9250 Rumsey Road, Suite 106, Columbia, MD. 21045
(410) 715-1070 (301) 596-3424 (410) 715-9540 (Fax)

DESIGNED: S.D.H.	Sediment Control Detail & Notes BOWL POND Village of Oakland Mills Steven's Forest Capital Project #D-1127 Section Two - Area Three Open Space Lot 4 & P/O Parcel 310, Parcel D and Section Five - Area One Open Space Lot 85 Tax Map 36 6th Election District - Howard County, Maryland Previous Submittals:	SCALE: As Shown
DRAWN: J.D.R., M.B.J.		DRAWING: 5 of 11
CHECKED: B.D.B.		JOB NO.: 01-008
DATE: 3/20/02, Rev 9/02, Rev 1/03		OWNER/DEVELOPER: COLUMBIA ASSOCIATION 10221 Winocoin Circle, Suite 100 Columbia, Maryland 21044-3410 (410) 381-0291

REVISIONS		
No.	Date	Description

ENGINEER'S CERTIFICATE

I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REGULATIONS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT I AM A REGISTERED PROFESSIONAL ENGINEER IN THE STATE OF MARYLAND AND I AM AUTHORIZED TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

DEVELOPER'S CERTIFICATE

I WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATEENANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL EMPAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL.

APPROVED FOR POND CONSTRUCTION SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

APPROVED FOR POND CONSTRUCTION SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

POND CONSTRUCTION SPECIFICATIONS

These specifications are appropriate to all ponds within the scope of the Standard for practice MD-378. All references to ASTM and AASHTO specifications apply to the most recent version.

SITE PREPARATION

Areas designated for borrow areas, embankment and structural works shall be cleared grubbed, and stripped of topsoil. All trees, vegetation, roots, and other objectionable material shall be removed. Channel banks and sharp breaks shall be sloped to no steeper than 1:1. All trees shall be cleared and grubbed within 15 feet of the toe of the embankment.

Areas to be covered by the reservoir will be cleared of all trees, brush, logs, fences, rubbish, and other objectionable material unless otherwise designated on the plans. Trees, brush and stumps shall be cut approximately level to the ground surface. For dry stormwater management ponds, a minimum of a 25 foot radius around the inlet structure shall be cleared.

All cleared and grubbed material shall be disposed of outside and below the limits of the dam and reservoir as directed by the owner or his representative. When specified, a sufficient quantity of topsoil will be stockpiled in a suitable location for use on the embankment and other designated areas.

EARTH FILL

Material - The fill material shall be taken from approved designated borrow areas. It shall be free of roots, stumps wood, rubbish, stones greater than 6", frozen or other objectionable materials. Fill material for the center of the embankment and cut off trench shall conform to Unified Soil Classification GC, SC, CH, or CL and must have at least 30% passing the #200 sieve. Consideration may be given to the use of other materials in the embankment if designed by a geotechnical engineer. Such special designs must have construction supervised by a geotechnical engineer.

Materials used in the outer shell of the embankment must have the capability to support vegetation of the quality required to prevent erosion of the embankment.

Placement - Areas on which fill is to be placed shall be scarified prior to the placement of fill. Fill materials shall be placed in maximum 6 inch thick (before compaction) layers which are to be continuous over the entire length of fill. The most permeable borrow material shall be placed in the downstream portions of the embankment. The principal spillway must be installed concurrently with fill placement and not excavated into the embankment.

Compaction - The movement of the hauling and spreading equipment over the fill shall be controlled so that the entire surface of each lift shall be traversed by not less than one tread track of heavy equipment or compaction shall be achieved by a minimum of four complete passes of a sheepsfoot, rubber tired, or vibratory roller. Fill material shall contain sufficient moisture such that the required degree of compaction will be obtained with the equipment used. The fill material shall contain sufficient moisture so that if formed into a ball it will not crumble yet not be so wet that water can be squeezed out.

When required by the reviewing agency the minimum required density shall not be less than 95% of maximum dry density with a moisture content within +/- 2% of the optimum. Each layer of fill shall be compacted as necessary to obtain that density, and is to be certified by the Engineer at the time of construction. All compaction is to be determined by AASHTO Method T-99 (Standard Proctor).

Cut off Trench - The cutoff trench shall be excavated into impervious material along or parallel to the centerline of the embankment as shown on the plans. The bottom width of the trench shall be governed by the equipment used for excavation, with the minimum width being four feet. The depth shall be at least four feet below existing grade or as shown on the plans. The side slopes of the trench shall be 1 to 1 of flatter. The backfill shall be compacted with construction equipment, rollers, or hand tampers to assure maximum density and minimum permeability.

Embankment Core - The core shall be parallel to the centerline of the embankment as shown on the plans. The top width of the core shall be a minimum of four feet. The height shall extend up to at least the 10 year water elevation or as shown on the plans. The side slopes shall be 1 to 1 or flatter. The core shall be compacted with construction equipment, rollers, or hand tampers to assure maximum density and minimum permeability. In addition, the core shall be placed concurrently with the outer shell of the embankment.

STRUCTURAL BACKFILL

Backfill adjacent to pipes or structures shall be of the type and quality conforming to that specified for the adjoining fill material. The fill shall be placed in horizontal layers not to exceed four inches in thickness and compacted by hand tampers or other manually directed compaction equipment. The material needs to fill completely all spaces under and adjacent to the pipe. At no time during the backfilling operation shall driven equipment be allowed to operate closer than four feet measured horizontally, to any part of a structure. Under no circumstances shall equipment be driven over any part of a concrete structure or pipe, unless there is compacted fill of 24" or greater over the structure or pipe.

Structure backfill may be flowable fill meeting the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 315 as modified. The mixture shall have a 100-200 psi; 28 day unconfined compressive strength. The flowable fill shall have a minimum pH of 4.0 and a minimum resistivity of 2,000 ohm-cm. Material shall be placed such that a minimum of 6" (measured perpendicular to the outside of the pipe) of flowable fill shall be under (bedding), over and, on the sides of the pipe. It only needs to extend up to the spring line for rigid conduits. Average slump of the fill shall be 7" to assure flowability of the material. Adequate measures shall be taken (sand bags, etc.) to prevent floating the pipe. When using flowable fill, all metal pipe shall be bituminous coated. Any adjoining soil fill shall be placed in horizontal layers not to exceed four inches in thickness and compacted by hand tampers or other manually directed compaction equipment. The material shall completely fill all voids adjacent to the flowable fill zone. At no time during the backfilling operation shall driven equipment be allowed to operate closer than four feet, measured horizontally, to any part of a structure. Under no circumstances shall equipment be driven over any part of a structure or pipe unless there is compacted fill of 24" or greater over the structure or pipe. Backfill outside the structural backfill (flowable fill) zone shall be of the type and quality conforming to that specified for the core of the embankment or other embankment materials.

PIPE CONDUITS

All pipes shall be circular in cross section.

Corrugated Metal Pipe - All of the following criteria shall apply for corrugated metal pipe:

1. **Materials** - (Polymer Coated steel pipe) - Steel pipes with polymeric coatings shall have a minimum coating thickness of 0.01 inch (10 mil) on both sides of the pipe. This pipe and its appurtenances shall conform to the requirements of AASHTO Specifications M-245 & M-246 with watertight coupling bands or flanges.

Materials - (Aluminum Coated Steel Pipe) - This pipe and its appurtenances shall conform to the requirements of AASHTO Specification M-274 with watertight coupling bands or flanges. Aluminum Coated Steel Pipe, when used with flowable fill or when soil and/or water conditions warrant the need for increased durability, shall be fully bituminous coated per requirements of AASHTO Specification M-190 Type A. Any aluminum coating damaged or otherwise removed shall be replaced with cold applied bituminous coating compound. Aluminum surfaces that are to be in contact with concrete shall be painted with one coat of zinc chromate primer or two coats of asphalt.

Materials - (Aluminum Pipe) - This pipe and its appurtenances shall conform to the requirements of AASHTO Specifications M-196 or M211 with watertight coupling bands or flanges. Aluminum Pipe, when used with flowable fill or when soil and/or water conditions warrant for increased durability, shall be fully bituminous coated per requirements of AASHTO Specifications M-190 Type A. Aluminum surfaces that are to be in contact with concrete shall be painted with one coat of zinc chromate primer. Hot dip galvanized bolts may be used for connections. The pH of the surrounding soils shall be between 4 and 9.

2. **Coupling bands, anti seep-collars, end sections, etc.**, must be composed of the same material and coatings as the pipe. Metals must be insulated from dissimilar materials with use of rubber or plastic insulating materials at least 24 mils in thickness.

3. **Connections** - All connections with pipes must be completely watertight. The drain or barrel connection to the riser shall be welded all around when the pipe and riser are metal. Anti-seep collars shall be connected to the pipe in such a manner as to be completely watertight. Dimple bands are not considered to be watertight.

All connections shall use a rubber or neoprene gasket when joining pipe sections. The end of each pipe shall be re-rolled an adequate number of corrugations to accommodate the band width. The following type connections are acceptable for pipes less than 24" in diameter: flanges on both ends of the pipe, with a circular 3/8" closed cell neoprene gasket, pre-punched to the flange bolt circle, sandwiched between adjacent flanges; a 12 inch wide standard lap type band with 12" wide by 3/8" thick closed cell circular neoprene gasket; and a 12 inch wide hugger type band with O-ring gaskets having a minimum diameter of 1/2 inch greater than the corrugated depth. Pipes 24" in diameter and larger shall be connected by a 24" long annular corrugated band using a minimum of 4 (four) rods and lugs, 2 on each connecting pipe end. A 24" wide by 3/8" thick closed cell circular neoprene gasket will be installed with 12 inches on the end of each pipe. Flanged joints with 3/8" closed cell gaskets the full width of the flange is also acceptable.

Helically corrugated pipe shall have either continuously welded seams or have lock seams with internal caulking or a neoprene bead.

4. **Bedding** - The pipe shall be firmly and uniformly bedded throughout its entire length. Where rock or soft, spongy or other unstable soil is encountered, all such material shall be removed and replaced with suitable earth compacted to provide adequate support.

5. Backfilling shall conform to "Structure Backfill."

6. Other details (anti-seep collars, valves, etc.) shall be as shown on the drawings.

Reinforced Concrete Pipe - All of the following criteria shall apply for reinforced concrete pipe:

1. **Materials** - Reinforced concrete pipe shall have bell and spigot joints with rubber gaskets and shall equal or exceed ASTM Designation C-361.

2. **Bedding** - Reinforced concrete pipe conduits shall be laid in a concrete bedding/cradle for their entire length. This bedding/cradle shall consist of high slump concrete placed under the pipe and up the sides of the pipe at least 50 % of its outside diameter with a minimum thickness of 6 inches. Where a concrete cradle is not needed for structural reasons, flowable fill may be used as described in "Structure Backfill" section of this standard. Gravel bedding is not permitted.

3. **Laying pipe** - Bell and spigot pipe shall be placed with the bell end upstream. Joints shall be made in accordance with recommendations of the manufacturer of the material. After the joints are sealed for the entire length, the bedding shall be placed so that all spaces under the pipe are filled. Care shall be exercised to prevent any deviation from the original line and grade of the pipe. The first joint must be located within 4 feet from the riser.

4. Backfilling shall conform to "Structure Backfill."

5. Other details (anti-seep collars, valves, etc.) shall be as shown on the drawings.

Plastic Pipe - The following criteria shall apply for plastic pipe.

1. **Materials** - PVC pipe shall be PVC-1120 or PVC-1220 conforming to ASTM D-1785 or ASTM D-2241. Corrugated High Density Polyethylene (HDPE) pipe, couplings and fittings shall conform to the following: 4" - 10" pipe shall meet the requirements of AASHTO M252 Type 5, and 12" through 24" shall meet the requirements of AASHTO M294 Type 5.

2. Joints and connections to anti-seep collars shall be completely watertight.

3. **Bedding** - The pipe shall be firmly and uniformly bedded throughout its entire length. Where rock or soft, spongy or other unstable soil is encountered, all such material shall be removed and replaced with suitable earth compacted to provide adequate support.

4. Backfilling shall conform to "Structure Backfill."

5. Other details (anti-seep collars, valves, etc.) shall be as shown on the drawings.

DRAINAGE DIAPHRAGMS - When a drainage diaphragm is used, a registered professional engineer will supervise the design and construction inspection.

CONCRETE:

Concrete shall meet the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 414, Mix No. 3.


ROCK RIPRAP:

Rock riprap shall meet the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 311.


Geotextile shall be placed under all riprap and shall meet the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 921.09, Class C.

CARE OF WATER DURING CONSTRUCTION:

All work on permanent structures shall be carried out in areas free from water. The Contractor shall construct and maintain all temporary dikes, levees, cofferdams, drainage channels, and stream diversions necessary to protect the areas to be occupied by the permanent works. The contractor shall also furnish, install, operate and maintain all necessary pumping and other equipment required for removal of water from the various parts of the work and for maintaining the excavations, foundation, and other parts of the work free from water as required or directed by the engineer for constructing each part of the work. After having served their purpose, all temporary protective works shall be removed or leveled and graded to the extent required to prevent obstruction in any degree whatsoever of the flow of water to the spillway or outlet works and so as not to interfere in any way with the operation or maintenance of the structure. Stream diversions shall be maintained until the full flow can be passed through the permanent works. The removal of water from the required excavation and the foundation shall be accomplished in a manner and to the extent that will maintain stability of the excavated slopes and bottom required excavations and will allow satisfactory performance of all construction operations. During the placing and compacting of material in required excavations, the water level at the locations being refilled shall be maintained below the bottom of the excavation at such locations which may require draining the water to sumps from which the water shall be pumped.



Profile Along Centerline of Principal Spillway and Across Pond (Section B-B)



Profile Along Centerline of Embankment

OPERATION, MAINTENANCE, AND INSPECTION
Inspection of the pond shown hereon shall be performed at least annually, in accordance with the checklist and requirements contained within USDA, SC5 'Standards and Specifications For Ponds' (MD 378). The pond owner(s) and their heirs, successors, or assigns shall be responsible for the safety of the pond and the continued operation, surveillance, inspection and maintenance thereof. The pond owner(s) shall promptly notify the Soil Conservation District of any unusual observations that may be indications of distress such as excessive seepage, turbid seepage, sliding or slumping.

OPERATION AND MAINTENANCE SCHEDULE
STORMWATER MANAGEMENT FACILITY
PRIVATELY OWNED
OWNERS MAINTENANCE RESPONSIBILITIES:

- Top and side slopes of the embankment shall be mowed a minimum of two (2) times a year, once in June and once in September. Other side slopes, and maintenance access should be mowed as needed.
- Debris and litter shall be removed during regular mowing operations as needed.
- When deemed necessary for aesthetic reasons, sediment should be removed from the pond. Approval of the Howard County Department of Public Works and Maryland Department of the Environment is required.

REVISIONS		
No.	Date	Description

Subdivision Name: Village of Oakland Mills	Section/Arms: 2/3 & 5/1	Parcel No. (to be used for Parcel 30, Parcel D Open Space Lots 4 & 8): 6066.03
Map No. 15746-47 P.B. 17, Folio 96	Block No. 3 & 9	Zone NEW-TOWN
Water Code N/A	Tax Map No. 36	Election District 6th
	Sewer Code N/A	

DESIGNED S.D.H.	Storm Water Management Notes & Details BOWL POND Village of Oakland Mills Steven's Forest Capital Project #D-1127 Section Two - Area Three Open Space Lot 4 & P/O Parcel 310, Parcel D and Section Five - Area One Open Space Lot 85	SCALE As Shown
DRAWN J.D.R.		DRAWING 6 of 11
CHECKED B.D.B.	6th Election District - Howard County, Maryland Previous Submittals:	JOB NO. 01-008
DATE 3/2002 Rev 9/02 Rev 1/03	OWNER/DEVELOPER COLUMBIA ASSOCIATION 10221 Winopin Circle, Suite 100 Columbia, Maryland 21044-3410 (410) 381-0501	FILE NO.

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING
Danah L. Coyle
DIRECTOR
DATE: **3/12/03**

Cathy Hanada
CHIEF, DIVISION OF LAND DEVELOPMENT
DATE: **4/4/03**

Charles D. Blum
CHIEF, DIVISION OF ENGINEERING DIVISION
DATE: **4/1/03**





THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL
Jim Ryan
NATURAL RESOURCE CONSERVATION
DATE: **4/9/03**

THIS DEVELOPMENT PLAN IS APPROVED FOR POND CONSTRUCTION SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.
Charles D. Blum
DATE: **4/1/03**

ENGINEER'S CERTIFICATE
I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION...
BRUCE D. BURTON
REGISTERED PROFESSIONAL ENGINEER
DATE: **4/1/03**

DEVELOPER'S CERTIFICATE
I HAVE CERTIFIED THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERFORMING ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.
Charles D. Blum
DATE: **4-1-03**

PAUL STATE OF MARYLAND
PROFESSIONAL ENGINEER
BRUCE D. BURTON
DATE: **4/1/03**



GEOTECHNICAL RECOMMENDATIONS

EVALUATIONS AND RECOMMENDATIONS

Based on the information obtained from the borings it is our professional opinion that the current pond is not constructed with a suitable cut off trench and core trench per current Md. 37b specifications.

Given the presence of groundwater at or above the proposed bottom of pond elevations stormwater management practices via infiltration are not recommended. Consideration should be given to the design of wet ponds.

It is our understanding that documentation reflecting compliance with current Md. 37b existing pond is not available. Although the borings did encounter some Clay materials within the embankment a core trench extending below the pre-existing natural ground.






EMBANKMENT AND CUT-OFF TRENCH CONSTRUCTION

The existing pond embankment should be removed to natural ground. Any topsoil encountered should be removed and stockpiled for re-spreading. Any other unsuitable materials such as large rock materials, trees and wood should be removed from the embankment area in accordance with Soil Conservation Guidelines. The existing riser and barrel should also be removed. After stripping operations have been completed, the exposed subgrade materials should be profiled with a loaded dump truck or similar equipment in the presence of a geotechnical engineer or his representative. For areas that are not accessible to a dump truck, the exposed materials should be observed and tested by a geotechnical engineer or his representative utilizing a Dynamic Cone Penetrometer. Any excessively soft or loose materials identified by profiling or penetrometer testing should be excavated to suitable firm soil, and then grades re-established by backfilling with suitable soil.

Based on the groundwater levels identified in the borings dewatering of excavations should be anticipated. A representative of the Geotechnical Engineer should be present to monitor placement and compaction of fill for the embankment and cut off trench. In accordance with Maryland Soil Conservation Specification 37b soils considered suitable for the center of embankment and cut off trench shall conform to Unified Soil Classification GC, SC, CH, or CL. These soil materials were identified in the soil borings however, the quantity of these materials could not be determined from the borings. Additional exploration with test pits conducted at the time of construction and laboratory testing should be conducted prior to construction to identify and quantify existing core trench materials within the embankment. All fill materials must be placed and compacted in accordance with MD 5C5 37b specifications.

CONCRETE RISER AND STRUCTURE CONSTRUCTION

Based on the surface elevations at borings B-1 through B-3 in correlation with the proposed grades it is our professional opinion that the riser foundation may be designed for a maximum allowable bearing pressure of 2000 lbs per square foot (psf). Water should not be allowed to pond or collect within the foundation excavations, as this can cause a reduction in the bearing capacity of the soils. As indicated previously dewatering during excavation should be anticipated prior to excavations. A geotechnical engineer or his representative should observe foundation excavations and conduct dynamic cone penetrometer testing (DCP) of the bearing surfaces to depths of three feet.



Subdivision Name: Village of Oakland Mills	Sect/Area: 2/3 & 5/1	Parcel No.: 05 Lx 14.00 Parcel 20
Plat No.: 59246-47	Block No.: 3 & 9	Zone: NEW-TOWN
P.B. 17, Folio 91	Tax Map No.: 36	Election District: 6th
P.B. 16, Folio 98		Census Tract: 6066.03
Water Code: N/A	Sewer Code: N/A	

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

Director 2/2/03

Chief, Division of Land Development 4/6/03

Development Engineering Division 4/15/03

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL

Jim Mynka 4/9/03

THIS DEVELOPMENT PLAN IS APPROVED FOR POND CONSTRUCTION SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

Paul Saly 4/9/03

ENGINEER'S CERTIFICATE

I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT THE REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION IN ACCORDANCE WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION.

Bruce D. Brown 4/1/03

DEVELOPER'S CERTIFICATE

I HAVE CERTIFIED THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Charles R. Rasmussen 4-1-03


STATE OF MARYLAND REGISTERED PROFESSIONAL ENGINEER

Bruce D. Brown 4/1/03


No.	Date	Description

LDE, INC.
9250 Rumsey Road, Suite 106, Columbia, MD. 21045
(410) 715-1070 (301) 596-3424 (410) 715-9540 (Fax)

DESIGNED: S.D.H.	Storm Water Management Notes & Details	SCALE: As Shown
DRAWN: J.D.R.	BOWL POND Village of Oakland Mills Steven's Forest Capital Project #D-1127 Section Two - Area Three Open Space Lots 4 & F10 Parcel 310, Parcel D and Section Five - Area One Open Space Lot 25 Tax Map 36	DRAWING: 7 of 11
CHECKED: B.D.B.	6th Election District - Howard County, Maryland Previous Submittals:	JOB NO.: 01-008
DATE: 3/20/02 Rev 9/02 Rev 1/03	OWNER/DEVELOPER: COLUMBIA ASSOCIATION 10221 Wincopin Circle, Suite 100 Columbia, Maryland 21044-3410 (410) 381-0591	FILE NO.:




Note: 1. The steel used in the trashrack shall be galvanized and painted battleship grey after fabrication.
 2. The #5 rebar to be welded to the 1/2"x3" steel bar and bolted to the face of riser.
 3. All bolts used to fasten trash rack to the riser structure shall be galvanized.




SIZE	CLASS	TOTAL LENGTH*
36"	ASTM C-261 Conc.	87
24"	RCP, Class IV	60
10"	D.I.P.	25

* The total length of pipe does not take into account the slope of the pipe. This total is for linear feet only.




30" Temporary Pipe Profile South Side of Pond




FOREBAY DETAIL/INFLOW PROTECTION DETAIL

Structure No.	Type	Inv. In.	Inv. Out.	Top of Wall/ Pipe	Detail	Location	Remarks
S-1	Type 'C' Endwall	333.03	333.00	336.50	SD 5.21	N 561528.01 / E 1354666.82	Type 'C' for 36" pipe
S-2	Conc. Riser	334.00	334.00	345.53		N 561532.71 / E 1354756.92	See Riser Details
S-3	24" Conc. End sect.	343.50	343.40	345.50	SD 5.51	N 561485.35 / E 1354768.39	24" Conc. End Section
S-4	Type 'D' Inlet	344.00	344.00	-	SD 4.11	N 561445.82 / E 1354774.56	See Detail, Sht 5
S-5	24" Conc. End sect.	344.10	344.10	346.10	SD 5.51	N 561416.47 / E 1354779.93	24" Conc. End Section
S-6	24" Conc. End sect.	344.30	344.30	346.30	SD 5.51	N 561389.66 / E 1354783.15	24" Conc. End Section


STORM DRAIN STRUCTURE SCHEDULE




24" Temporary Pipe Profile South Side of Pond




4" RISER FRAME AND COVER DETAIL



EMERGENCY SPILLWAY TYPICAL SECTION



Detail of Anti Seep Collar (Use (3) 10.37\"/>



TYPICAL FOREBAY DETAIL

Forebay No.	Crest Elev.	Bottom Elev.
"A"	347.00	346.00
"B"	347.00	346.00
"C"	346.50	344.00

Forebays B & C only PLAN VIEW

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING
 Director: *David L. Leight* DATE: 4/24/03
 Chief, Division of Land Development: *Candy Hammett* DATE: 4/14/03
 Chief, Development Engineering Division: *Chad Deane* DATE: 4/15/03

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL.
 Natural Resource Conservation Service: *Jim Myer* DATE: 4/9/03
 THIS DEVELOPMENT PLAN IS APPROVED FOR POND CONSTRUCTION SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.
 Howard Soil Conservation District: *John A. Sely* DATE: 4/9/03

ENGINEER'S CERTIFICATE
 I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION AND EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON A REASONABLE INVESTIGATION OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER OF THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.
 Signature of Engineer: *Bruce D. Evans* DATE: 4/1/03
 DEVELOPER'S CERTIFICATE
 I CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL EMPLOY A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.
 Signature of Developer: *Chad Deane* DATE: 4-1-03


STATE OF MARYLAND
 PROFESSIONAL ENGINEER
 Bruce D. Evans
 4/1/03

No.	Date	Description

Subdivision Name: Village of Oakland Mills	Section Area: 2/3 & 5/1	Parcel No. 310, 4 & 110 Parcel 310, Parcel 17, Folio 91
Map No. 15748-47	Block No. 3 & 9	Zone NEW-TOWN
Folio 91	Parcel No. 36	Election District 6th
Water Code	N/A	Sanitary Code 6066.03


LDE, INC.
 9250 Rumsey Road, Suite 106, Columbia, MD. 21045
 (410) 715-1070 (301) 596-3424 (410) 715-9540 (Fax)
 DESIGNED: S.D.H.
 DRAWN: J.D.R.
 CHECKED: B.D.B.
 DATE: 3/2002 Rev 9/02 Rev 1/03
 OWNER/DEVELOPER: COLUMBIA ASSOCIATION
 10221 Winthrop Circle, Suite 100
 Columbia, Maryland 21044-3410
 (410) 391-0691
 SCALE: As Shown
 DRAWING: 8 of 11
 JOB NO.: 01-008
 FILE NO.:

Maryland's Guidelines To Waterway Construction
DETAIL 1.4: DIVERSION PIPE




TEMPORARY EROSION CONTROL MEASURES
REVISION NOVEMBER 2000
PAGE 14 - 2
MARYLAND DEPARTMENT OF THE ENVIRONMENT
WATER MANAGEMENT ADMINISTRATION


Maryland's Guidelines To Waterway Construction
DETAIL 1.5: SANDBAG/STONE DIVERSION



TEMPORARY EROSION CONTROL MEASURES
REVISION NOVEMBER 2000
PAGE 15 - 1
MARYLAND DEPARTMENT OF THE ENVIRONMENT
WATER MANAGEMENT ADMINISTRATION



TEMPORARY EROSION CONTROL MEASURES
REVISION NOVEMBER 2000
PAGE 16 - 1
MARYLAND DEPARTMENT OF THE ENVIRONMENT
WATER MANAGEMENT ADMINISTRATION



TEMPORARY EROSION CONTROL MEASURES
REVISION NOVEMBER 2000
PAGE 17 - 4
MARYLAND DEPARTMENT OF THE ENVIRONMENT
WATER MANAGEMENT ADMINISTRATION

MGWC 1.4: DIVERSION PIPE

DESCRIPTION
The work should consist of installing flow diversion pipes in combination with sandbag or stone diversions when construction activities occur within the stream channel.

EFFECTIVE USES & LIMITATIONS
Diversion pipes with an insufficient flow capacity can cause the channel diversion to fail thereby resulting in severe erosion of the disturbed channel section under construction. Therefore, in-channel construction activities should occur only during periods of low flow.

MATERIAL SPECIFICATIONS
Materials for sandbag and stone stream diversions should meet the following requirements:
• Strapping: Rippage should be washed and have a minimum diameter of 6 inches (0.15 meters).
• Sandbags: Sandbags should consist of materials which are resistant to ultraviolet radiation, tearing, and puncture and should be woven tightly enough to prevent leakage of the fill material (i.e., sand, fine gravel, etc.).
• Sheeting: Sheeting should consist of polyethylene or other materials which are impervious and resistant to puncture and tearing.

INSTALLATION GUIDELINES
All erosion and sediment control devices including mandatory dewatering basins should be installed as the first order of business according to a plan approved by the WMA or local authority. Installation should proceed from upstream to downstream during periods of low flow. If necessary, silt fence or straw bales should be installed around the perimeter of the work area.
Diversion pipes with sandbag or stone barriers should be completed as follows (refer to Detail 1.4):

- Sandbag/stone barriers should be sized and installed as detailed in MGWC 1.5: Sandbag/Stone Diversion. The materials should be sized to withstand baseflow velocities.
- All excavated material should be deposited and stabilized in an approved area outside the 100-year floodplain unless otherwise authorized by the WMA.
- Sediment-laden water from the construction area should be pumped to a dewatering basin.
- The diversion pipe should have a minimum capacity sufficient to convey the 2-year flow for projects with a duration of two weeks or greater. For projects of shorter duration, the capacity of the pipe can be reduced accordingly.
- If necessary, silt fence or straw bales should be installed around the perimeter of the work area.
- Sediment control devices are to remain in place until all disturbed areas are stabilized and the inspecting authority approves their removal.

MGWC 1.5: SANDBAG/STONE CHANNEL DIVERSION

DESCRIPTION
The work should consist of installing a sandbag or stone flow diversion for the purpose of erosion control when construction activities occur within stream channel.

EFFECTIVE USES & LIMITATIONS
Diversion pipes are used to isolate work areas from flow during the construction of in-stream projects. Diversion which have an insufficient flow capacity can fail and severely erode the disturbed channel section under construction. Therefore, in-channel construction activities should occur only during periods of low rainfall. This temporary measure may not be practical in large channels.

MATERIAL SPECIFICATIONS
Materials for sandbag and stone stream diversions should meet the following requirements:
• Strapping: Rippage should be washed and have a minimum diameter of 6 inches (0.15 meters).
• Sandbags: Sandbags should consist of materials which are resistant to ultraviolet radiation, tearing, and puncture and should be woven tightly enough to prevent leakage of the fill material (i.e., sand, fine gravel, etc.).
• Sheeting: Sheeting should consist of polyethylene or other materials which are impervious and resistant to puncture and tearing.

INSTALLATION GUIDELINES
All erosion and sediment control devices, including dewatering basins, should be implemented as the first order of business according to a plan approved by the WMA or local authority. Installation should proceed from upstream to downstream during periods of low flow. If necessary, silt fence or straw bales should be installed around the perimeter of the work area.
Sandbag/stone diversions can be used independently or as components of other stream diversions techniques. Installation of this measure should proceed as follows (refer to Detail 1.5):

- The diversion structure should be installed from upstream to downstream.
- The height of the sandbag/stone diversion should be a function of the duration of the project in the stream reach. For projects with a duration less than 2 weeks, the height of the diversion should be one-half the streambank height, measured from the channel bed plus 1 foot (0.3 meters) or bankfull height, whichever is greater. For projects of longer duration, the top of the sandbag or stone diversion should correspond to bankfull height. For diversion structures utilizing sandbags, the stream bed should be hand prepared prior to placement of the base layer of sandbags in order to ensure a water-tight fit. Additionally, it may be necessary to prepare the bank in a similar fashion.
- All excavated material should be deposited and stabilized in an approved area outside the 100-year floodplain unless otherwise authorized by the WMA.
- Sediment-laden water from the construction area should be pumped to a dewatering basin.
- Sheeting on the diversion should be positioned such that the upstream portion covers the downstream portion with at least a 10-inch (0.45 meters) overlap.
- Sandbag or stone diversions should not obstruct more than 45% of the stream width. Additionally, bank stabilization measures should be placed in the constricted section if accelerated erosion and bank scour are observed during the construction time or if project time expected to last more than 2 weeks.
- Prior to removal of these temporary structures, any accumulated sediment should be removed, deposited and stabilized in an approved area outside the 100-year floodplain unless authorized by the WMA.
- Sediment control devices are to remain in place until all disturbed areas are stabilized in accordance with an approved sediment and erosion control plan and the inspecting authority approves their removal.

FIGURE 2 TEMPORARY SEDIMENT BASIN DESIGN DATA SHEET

Computed by: S.D.H. Date: 3/4/02 Checked by: _____ Date: _____
Project name: Bowl Pond Basin #1 Location: VOM, Columbia, Maryland

Total area draining to basin: 0.64 acres (2.80 Acres)

Note: 1. Also see Surface Area Design #20, this form.
2. To convert ft² to yd², divide ft² by 9.
3. To convert ft³ to yd³, divide ft³ by 27.

- Minimum required volume = 3,600 ft³/ac x 2.8 ac drainage = 10,080 ft³.
- Actual Volume of basin = 9,477 ft³.
- Excavate 10,080 ft³ (275 yd³) to obtain required capacity.
- Volume at dewatering elevation = 1,000 ft³/ac x 2.8 ac = 2,800 ft³.
- Volume of basin at cleanout = 9,000 ft³/ac x 2.8 ac = 25,200 ft³.
- Elevation corresponding to minimum required volume of basin (riser crest elevation) = 336.20 ft.
- Permanent pool elevation = 335.20 ft. (Basin only).
- Distance from riser crest elevation to permanent pool elevation = 0.90 ft. (Top basin riser = 336.70)
- Basin cleanout elevation = 335.20 ft.
- Distance from riser crest elevation to cleanout elevation = 1.00 ft.
- *Small sediment basin riser-not permanent concrete riser.

SPILLWAY DESIGN N/A
(Emergency spillway will not function during construction due to large storage volume available in basin.)

11. $Q = 0.85 C_d Q_p$ (peak discharge from 10-year, 24-hour storm event, attach computations)
(Permanent basin)

PRINCIPAL SPILLWAY (Q_p) (See Detail 11)
(Permanent basin)

- Design Principal Spillway (Barrel) discharge, Design $Q_p = 0.85 C_d Q_p$ (minimum 10% of 10-year peak or 8" Diameter Pipe)
14. H₁ = 11.5 ft; Barrel length = 27 ft
- Barrel Diameter = 36 inch. Note: Q_p must equal or exceed design Q_p .
- $Q_p = Q$ (from Table 10 or 14) (length correction factor) 0.97 = 9.7 cfs.
- Riser Diameter = 60x30 inch; Riser Height = 11.5 ft; Riser Head (H₁) = 0 ft.
- Trash Rack Diameter = 30 inch; Trash Rack Height = 18 inch.

EMERGENCY SPILLWAY (Q_e) N/A

17. Emergency spillway cap, $Q_e = Q_p - Q_p =$ _____ cfs.
18. Width, ft: top _____ ft.
19. Entrance channel slope _____ %
20. Exit channel slope _____ %

ANTI-SLEEP COLLAR DESIGN (If required)

21. $y_1 = 13.8$ ft; $z = 4$; pipe slope = 1.15%; $L = 74$ ft.
22. Use 2" collars, 9" x 7" inch square projection = 2.54 ft.

DESIGN ELEVATIONS (Permanent Pond)


Top elevation = 345.53 ft	24. Design High Water = 348.00 ft (100-year)
23. Riser crest elevation = 344.00 ft	25. Minimum at risk top of dam = 343.00 ft
26. Emergency Spillway Crest = 343.00 ft	26. Minimum at risk top of dam = 343.00 ft
27. Permanent pool = 335.20 ft	28. Bottom of basin = 334.50 ft
29. Draw-down office invert = 336.70 ft	

SURFACE AREA DESIGN

30. Minimum basin surface area: $5A = 0.0035 \times Q_p = 0.0035 \times 10 \text{ cfs} = 0.0035 \text{ ac}$.
(Actual surface area at elevation 335.10 = 0.0037 ac.)
Top of wet storage, Elev = 335.90 = 0.116 ac.

DRAW-DOWN DEVICE

31. Draw-down device orifice diameter = 4 inch (From Table 11)
32. $A =$ Total area of perforations > 4" (Use 1" Diameter holes)
 $A =$ (4 of perforation/foot) (0.0055 ft²) (0.90 ft)
 $A = 0.345 \text{ ft}^2$
 $A =$ Internal office area (from Table 11 or computed) (0.55 ft²)
Funch 74, 1" Diameter holes in 10" Pipe, 0.30 High



APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

Mark A. Long 4/22/02
DIRECTOR DATE

Cindy Hamstra 4/4/02
CHIEF, DIVISION OF LAND DEVELOPMENT DATE

Chris D. Williams 4/15/02
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL.

Jim Meyer 4/9/02
NATURAL RESOURCE CONSERVATION SERVICE DATE

THIS DEVELOPMENT PLAN IS APPROVED FOR POND CONSTRUCTION SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

John S. Shy 4/9/02
HOWARD SOIL CONSERVATION DISTRICT DATE

ENGINEER'S CERTIFICATE

I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY VISUAL INSPECTION OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REGULATIONS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 90 DAYS OF COMPLETION. ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Bruce D. Bunker 4/1/03
REGISTERED PROFESSIONAL ENGINEER DATE

DEVELOPER'S CERTIFICATE

I WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 90 DAYS OF COMPLETION. ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Charles H. Harkness 4-1-03
SIGNATURE OF DEVELOPER DATE

DEWATERING / DRAW DOWN DEVICE CONCRETE BASE DETAIL

Exp 4/1/03
REGISTERED PROFESSIONAL ENGINEER DATE

REVISIONS

No.	Date	Description


Subdivision Name: Village of Oakland Mills Sect/Area: 2/3 & 5/1 Parcel No.: 023 Lot # 4 110 Parcel 310 Parcel 02 Open Space, lots 4 & 5

Plan No.: 15746-47 Block No.: 3 & 9 Zone: NEW-TOWN Tax Map No.: 36 Election District: 6th Census Tract: 6066.03

Water Code: N/A Sewer Code: N/A

LDE, INC.
9250 Rumsey Road, Suite 106, Columbia, MD. 21045
(410) 715-1070 (301) 596-3424 (410) 715-9540 (Fax)

DESIGNED: S.D.H.	Sediment Basin Notes & Details BOWL POND Village of Oakland Mills Steven's Forest Capital Project #D-1127 Section Two - Area Three Open Space Lot 4 & F10 Parcel 310, Parcel D and Section Five - Area One Open Space Lot 83 Tax Map 36 6th Election District - Howard County, Maryland Previous Submittals:	SCALE: As Shown
DRAWN: J.D.R.		DRAWING: 9 of 11
CHECKED: B.D.B.		JOB NO.: 01-008
DATE: 3/2/02 Rev 9/02 Rev 1/03		OWNER/DEVELOPER: COLUMBIA ASSOCIATION 10221 Winopin Circle, Suite 100 Columbia, Maryland 21044-3410 (410) 381-0591



Subdivision Name: Village of Oakland Mills		Sect/Area: 2/3 & 5/1	Parcel No.: 25, Lot 4 & P/O Parcel 240, Parcel D Open Space Lots 4 & 83
Plat No.: 15746-47	Block No.: 3 & 9	Zone: NEW-TOWN	Tax Map No.: 36
P.B. 17, Folio 91			Election District: 6th
P.B. 15, Folio 96			Census Tract: 6066.03
Water Code: N/A		Sewer Code: N/A	

LDE, INC.
 9250 Rumsey Road, Suite 106, Columbia, MD. 21045
 (410) 715-1070 (301) 596-3424 (410) 715-9540 (Fax)

DESIGNED: S.D.H.	Existing Conditions Plan BOWL POND Village of Oakland Mills Steven's Forest Capital Project #D-1127 Section Two - Area Three Open Space Lot 4 & P/O Parcel 310, Parcel D and Section Five - Area One Open Space Lot 83 Tax Map 36 6th Election District - Howard County, Maryland Previous Submittals:	SCALE: 1"=30'
DRAWN: J.D.R.		DRAWING: 10 of 11
CHECKED: B.D.B.		JOB NO.: 01-008
DATE: 3/20/02 Rev 9/02 Rev 1/03		OWNER/DEVELOPER: COLUMBIA ASSOCIATION 10221 Wincopin Circle, Suite 100 Columbia, Maryland 21044-3410 (410) 381-0591

REVISIONS		
No.	Date	Description

ENGINEER'S CERTIFICATE
 I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON A REVIEW OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT THE HOWARD SOIL CONSERVATION DISTRICT HAS REVIEWED THIS PLAN AND APPROVED IT. I AM A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION IN THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

BRUCE D. BULLOCK 4/1/03
 SIGNATURE OF ENGINEER DATE

DEVELOPER'S CERTIFICATE
 I HEREBY CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Charles R. Randall 4-1-03
 SIGNATURE OF DEVELOPER DATE



APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

David D. Wynn 4/2/03
 DIRECTOR DATE

Cindy Hamstra 4/14/03
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE


Chad Dammann 4/15/03
 CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL

Jim Myers 4/4/03
 NATIONAL RESOURCE CONSERVATION SERVICE DATE

THIS DEVELOPMENT PLAN IS APPROVED FOR POND CONSTRUCTION SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.



Shirley L. ... 4/4/03
 HOWARD SOIL CONSERVATION DISTRICT DATE



LANDSCAPE SCHEDULE					
HERBACIOUS WETLAND PLANTINGS					
QNTY	COMMON NAME	SCIENTIFIC NAME	SIZE	*MIDE ZONE	FORM
1175 sq. ft.	Blue flag iris	Iris virginica	Container	2	Perennial
1175 sq. ft.	arrowhead / duck potato	Sagittaria latifolia	Container	2	Perennial
1175 sq. ft.	water lobelia	Lobelia dortmanna	Container	2	Perennial
1175 sq. ft.	lushy beardgrass	Andropogon glomeratus	Seed mixture	2	grass
1175 sq. ft.	flowering bulrush	Ilex glabra	Seed mixture	2	grass
1175 sq. ft.	softrush	Juncus effusus	Seed mixture	2,3	grass
919 sq. ft.	forget-me-not	Myosotis arvensis	Container	3	Perennial
612 sq. ft.	shallow sedge	Carex lurida	Seed mixture	3	grass
612 sq. ft.	short-leaf flatsedge	Cyperus brevifolius	Seed mixture	3	grass
919 sq. ft.	new england aster	Aster novae-angliae	Container	3	Perennial
612 sq. ft.	rice cutgrass	Leersia oryzoides	Seed mixture	3	grass
919 sq. ft.	marsh marigold	Galthia palustris	Container	3	Perennial
4882 sq. ft.	birds foot trefoil	Lotus corniculatus	Container	4	Perennial
2628 sq. ft.	partridge-berry	Mitchella repens	Seed / Container	4	Groundcover
4882 sq. ft.	orange coneflower	Rudbeckia fulgida	Container	4	Perennial
2628 sq. ft.	perennial ryegrass	Lolium perenne	Seed / Container	4	Groundcover

* Refer to the pond hydrologic planting zone listed in Appendix A of the "2000 Maryland Stormwater Design Manual, Volume 1 and 2".
 ** See Zone legend, This sheet.
 NOTES: 1) The required stormwater management area landscaping includes 20 shade trees and 34 evergreen trees. Only the required landscape materials will be bonded. The remainder of the proposed landscape materials shown are above the Howard County Landscape requirements and are therefore, not required to be bonded.
 2) Perennial plants shall be planted at a rate of approximately 2.0 / sq. ft.
 3) Quantities of perennials and grasses are expressed in square foot areas and equate to the corresponding symbol (shading or hatch patterns) shown on the plan view.


LANDSCAPE SCHEDULE					
TREES					
SYMBOL	QNTY	COMMON NAME	BOTANICAL NAME	SIZE	REMARKS
	10	Red Maple	Acer rubrum	2" - 2 1/2" Caliper	B & B
	10	October Glory	Quercus palustris	2" - 2 1/2" Caliper	B & B
EVERGREENS					
	17	American Holly	Ilex Opaca	5' - 6' HT.	B & B
	17	Eastern White Pine	Pinus Strobus	5' - 6' HT.	B & B
TOTAL = 54					



SCHEDULE D STORMWATER MANAGEMENT AREA LANDSCAPING	
Linear Feet of Perimeter	1,290 LF.
Number of Plants Required	Based on Total = 926'
Shade Trees	20 Shade
Evergreen Trees	34 Evergreen
Credits for Existing Vegetation (Yes, No and %)	Yes - 364 LF.
Credits for Existing Landscaping (Yes, No and %)	No
Number of Trees Provided	
Shade Trees	20 Shade
Evergreen Trees	34 Evergreen
Other Trees (2:1 substitution)	

Note: Total Type 'C' Buffer Required = 411 LF. (10 Shade/ 21 Evergreen)
 Total Type 'C' Buffer Required = 515 LF. (10 Shade/ 13 Evergreen)

HYDROLOGIC PLANTING ZONE AREAS	
ZONE DESIGNATION	AREAS / DESCRIPTIONS
ZONE 1	Pond - 6,165 sq. ft. / Forebay C - 3,735 sq. ft.
ZONE 2	Pond - 1,683 sq. ft. / Forebay B - 4,311 sq. ft. / Forebay C - 1,044 sq. ft.
ZONE 3	Pond - 2,151 sq. ft. / Forebay B - 1,503 sq. ft. / Forebay C - 340 sq. ft.
ZONE 4	Pond - 13,026 sq. ft. / Forebay A - 1,935 sq. ft.



DEVELOPER'S/ BUILDER'S CERTIFICATE
 I/ We certify that the landscaping shown on this plan will be done according to the plan, Section 16.124 of the Howard County Code and the Howard County Landscape Manual. (We further certify that upon completion a Certification of Landscape Installation, accompanied by an executed one year guarantee of plant materials, will be submitted to the Department of Planning and Zoning.)
 Charles Blushard 4-1-03
 Name Date

- LANDSCAPE NOTES
- This plan has been prepared in accordance with the provisions of Section 16.124 of the Howard County Subdivision and Land Development Regulations and the Howard County Landscape Manual.
 - The Owner/Developer is responsible for the planting of all plant material required to meet the standards established by the Howard County Landscape Manual.
 - Plant materials shall conform to the American Association of Nurserymen's publication, American Standard Nursery Stock.
 - The Owner/Developer shall be responsible for the maintenance of the plant materials.
 - All plant materials shall conform to the American Association of Nurserymen's publication, American Standard Nursery Stock.
 - THIS PLAN IS FOR LANDSCAPING PURPOSES ONLY.
 - Please see sheet-4 for seeding notice to be used for NON-LANDSCAPING AREAS.

REVISIONS		
No.	Date	Description

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING
 Director: [Signature] 4/2/03
 Chief, Division of Land Development: [Signature] 4/1/03
 Chief, Development Engineering Division: [Signature] 4/1/03

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL.
 Natural Resource Conservation Service: [Signature] 4/9/03
 THIS DEVELOPMENT PLAN IS APPROVED FOR POND CONSTRUCTION SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.
 [Signature] 4/9/03

ENGINEER'S CERTIFICATE
 I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL, REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL OBSERVATION OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE HOWARD COUNTY LANDSCAPE MANUAL. I HAVE NOTIFIED THE DEVELOPER THAT UPON COMPLETION OF THE PROJECT, I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 90 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.
 Bruce D. [Signature] 4/1/03
 SIGNATURE OF ENGINEER DATE

DEVELOPER'S CERTIFICATE
 I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 90 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.
 Charles Blushard 4-1-03
 SIGNATURE OF DEVELOPER DATE


PROFESSIONAL ENGINEER
 [Signature] 4/1/03

Subdivision Name: Village of Oakland Mills	Sect/Area: 2/3 & 5/1	Parcel No. 03-14-170 Parcel 30, Parcel 3 Open Space Lots A & B
Plot No. 15746-47	Block No. 3 & 9	Zone NEW-TOWN
P.B. 17, Folio 98	Tax Map No. 36	Election District 6th
P.B. 15, Folio 98		Census Tract 6066.03
Water Code N/A	Sewer Code N/A	

LDE, INC.
 9250 Rumsey Road, Suite 106, Columbia, MD, 21045
 (410) 715-1070 (301) 596-3424 (410) 715-9540 (Fax)

DESIGNED: S.D.H.	Scale: 1"=30'
DRAWN: J.D.R.	DRAWING: 11 of 11
CHECKED: B.D.B.	JOB NO: 01-008
DATE: 3/20/02 Rev 9/02 Rev 1/03	FILE NO:



OWNER/DEVELOPER: COLUMBIA ASSOCIATION
 10221 Wincopin Circle, Suite 100
 Columbia, Maryland 21044-3410
 (410) 361-0591



LANDSCAPE SCHEDULE					
HERBACIOUS WETLAND PLANTINGS					
QNTY	COMMON NAME	SCIENTIFIC NAME	SIZE	*MDE ZONE	FORM
3519 sq. ft.	arrowhead / duck potato	Sagittaria latifolia	Container	2	Perennial
3519 sq. ft.	softrush	Juncus effusus	Seed mixture	2, 3	grass
2297 sq. ft.	shallow sedge	Carex lurida	Seed mixture	3	grass
2297 sq. ft.	new england aster	Aster novae-angliae	Container	3	Perennial
7511 sq. ft.	cardinal flower		Container	4	Perennial
7511 sq. ft.	perennial ryegrass	Lolium perenne	Seed / Container	4	Groundcover

* Refers to the pond hydrologic planting zones listed in Appendix A of the "2000 Maryland Stormwater Design Manual, Volumes I and II".
 ** See Zone legend, this sheet.
 NOTES: 1) The required stormwater management area landscaping includes 20 shade trees and 34 evergreen trees. Only the required landscape materials will be bonded. The remainder of the proposed landscape materials shown are above the Howard County Landscape requirements and are therefore, not required to be bonded.
 2) Perennial plants shall be planted at a rate of approximately 4.0' sq. ft. Δ
 3) Quantities of perennials and grasses are expressed in square foot areas and equate to the corresponding symbol (shading or hatch patterns) shown on the plan view.

LANDSCAPE SCHEDULE					
TREES					
SYMBOL	QNTY	COMMON NAME	BOTANICAL NAME	SIZE	REMARKS
	10	Red Maple	Acer rubrum	2" - 2 1/2" Caliper	B & B
	10	October Glory	Quercus pallustris	2" - 2 1/2" Caliper	B & B
	17	American Holly	Ilex Opaca	5' - 6' HT.	B & B
	17	Eastern White Pine	Pinus strobus	5' - 6' HT.	B & B
TOTAL = 54					




- PLANTING NOTES**
- Notify "Miss Utility" 72 hours prior to the installation of plant material.
 - Plant installation must conform to minimum standards cited in the latest edition of "Landscape Specification Guidelines" by the Landscape Contractors Association.
 - Plants to be located in the field by the owner or owner's representative. Notify owner 72 hours in advance of planting.
 - A Certification of Landscape Installation is required as per the Howard County Landscape ordinance.
 - Contract Landscape Architect regarding the substitution of plant material. The number, size and location of plants shall not be changed. Substitutions must be included in the recommended plant list.
 - Street tree locations have been shown wherever possible. Drive aprons of proposed unit do not allow the typical 1 tree : 40 feet.

SCHEDULE D STORMWATER MANAGEMENT AREA LANDSCAPING	
Linear Feet of Perimeter	1290 L.F.
Number of Plants Required	Based on Total = 926'
Shade Trees	20 Shade
Evergreen Trees	34 Evergreen
Credit for Existing Vegetation (Yes, No and %)	Yes - 264 L.F.
Credit for Existing Landscaping (Yes, No and %)	No
Number of Trees Provided	
Shade Trees	20 Shade
Evergreen Trees	34 Evergreen
Other Trees (2:1 substitution)	

Note: Total Type 'C' Buffer Required = 411 L.F. (10 Shade/ 21 Evergreen)
 Total Type 'C' Buffer Required = 515 L.F. (10 Shade/ 13 Evergreen)

HYDROLOGIC PLANTING ZONE AREAS	
ZONE DESIGNATION	AREAS / DESCRIPTIONS
ZONE 1	Pond - 6,165 sq. ft. / Forebay C - 3,735 sq. ft.
ZONE 2	Pond - 1,683 sq. ft. / Forebay B - 4,311 sq. ft. / Forebay C - 1,044 sq. ft.
ZONE 3	Pond - 2,151 sq. ft. / Forebay B - 1,503 sq. ft. / Forebay C - 940 sq. ft.
ZONE 4	Pond - 13,086 sq. ft. / Forebay A - 1,935 sq. ft.



DEVELOPER'S/ BUILDER'S CERTIFICATE

I/We certify that the landscaping shown on this plan will be done according to the plan, Section 16.124 of the Howard County Code and the Howard County Landscape Manual. I/We further certify that upon completion a Certification of Landscape Installation, accompanied by an executed one year guarantee of plant materials, will be submitted to the Department of Planning and Zoning.

Charles Blackwood 4-1-03
 Name Date

- LANDSCAPE NOTES**
- This plan has been prepared in accordance with the provisions of Section 16.124 of the Howard County Subdivision and Land Development Regulations and the Howard County Landscape Manual.
 - The Owner/Developer is responsible for the planting of all plant material required to meet the standards established by the Howard County Landscape Manual.
 - Plant materials shall be selected from the American Association of Nurserymen's publication, American Standard Nursery Stock.
 - The Owner/Developer shall be responsible for the maintenance of the plant materials.
 - All plant materials shall conform to the American Association of Nurserymen's publication, American Standard Nursery Stock.
 - THIS PLAN IS FOR LANDSCAPING PURPOSES ONLY.
 - Please see sheet 4 for seeding notes to be used for NON-LANDSCAPING AREAS.

ENGINEER'S CERTIFICATE

I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL OBSERVATION OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE STANDARDS AND SPECIFICATIONS OF THE HOWARD COUNTY SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT THE HOWARD COUNTY SOIL CONSERVATION DISTRICT WILL CONDUCT PERIODIC ON-SITE INSPECTIONS OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD COUNTY SOIL CONSERVATION DISTRICT.

Royce D. Brown 4/1/03
 SIGNATURE OF ENGINEER DATE

DEVELOPER'S CERTIFICATE

I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD COUNTY SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD COUNTY SOIL CONSERVATION DISTRICT.

Charles Blackwood 4-1-03
 SIGNATURE OF DEVELOPER DATE

PROFESSIONAL ENGINEER

ROYCE D. BROWN
 1998
 REGISTERED PROFESSIONAL ENGINEER
 STATE OF MARYLAND
 4/1/03

REVISIONS		
No.	Date	Description
1	June, 2005	Reduced Pond planting, species & spacing.

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

David Single 4/24/03
 DIRECTOR DATE

Gary Hamilton 4/14/03
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE

John D. ... 4/15/03
 CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL.

Jim ... 4/9/03
 NATION'S RESOURCE CONSERVATION SERVICE DATE

THIS DEVELOPMENT PLAN IS APPROVED FOR POND CONSTRUCTION SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

... 4/9/03
 HOWARD SOIL CONSERVATION DISTRICT DATE

Subdivision Name: Village of Oakland Mills	Block No. 3 & 9	Zone NEW-TOWN	Tax Map No. 36	Election District 6th	Census Tract 6066.03
Parcel No. 015, 016, 017, 018, 019, 020, 021, 022, 023, 024, 025, 026, 027, 028, 029, 030, 031, 032, 033, 034, 035, 036, 037, 038, 039, 040, 041, 042, 043, 044, 045, 046, 047, 048, 049, 050, 051, 052, 053, 054, 055, 056, 057, 058, 059, 060, 061, 062, 063, 064, 065, 066, 067, 068, 069, 070, 071, 072, 073, 074, 075, 076, 077, 078, 079, 080, 081, 082, 083, 084, 085, 086, 087, 088, 089, 090, 091, 092, 093, 094, 095, 096, 097, 098, 099, 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000					

LDE, INC.
 9250 Rumsey Road, Suite 106, Columbia, MD, 21045
 (410) 715-1070 (301) 596-3424 (410) 715-9540 (Fax)

DESIGNED	S.D.H.	SCALE	1"=30'
DRAWN	J.D.R.	DRAWING	11 of 11
CHECKED	B.D.B.	JOB NO.	01-008
DATE	3/20/02 Rev 9/02 Rev 1/03	OWNER/DEVELOPER	COLUMBIA ASSOCIATION 10221 Wincopin Circle, Suite 100 Columbia, Maryland 21044-3410 (410) 321-0591

HOWARD SOIL CONSERVATION DISTRICT
STANDARD SEDIMENT CONTROL NOTES

- A minimum of 48 hours notice must be given to the Howard County Department of Inspections, Licenses and Permits, Sediment Control Division prior to the start of any construction. (CS-1855).
- All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the most current "MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL", and revisions thereto.
- Following initial soil disturbance or redistribution, permanent or temporary stabilization shall be completed within: a) 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all slopes greater than 2:1, b) 14 days as to all other disturbed or graded areas on the project site.
- All sediment traps/basins shown must be fenced and warning signs posted around their perimeter in accordance with Vol. 1, Chapter 7, of the HOWARD COUNTY DESIGN MANUAL, Storm Drainage.
- All disturbed areas must be stabilized within the time period specified above in accordance with the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL (Section G) for permanent seeding, sod, temporary seeding, and mulching. Temporary stabilization with mulch alone can only be done when recommended seeding dates do not allow for proper germination and establishment of grasses.
- All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.
- Site Analysis:

Total Area of Site	3.00 Acres
Area Disturbed	2.25 Acres
Area to be roofed or paved	0.14 Acres
Area to be vegetatively stabilized	1.24 Acres
Total Cut	5723 Cu. Yds.
Total Fill	1927 Cu. Yds.
Offsite waste/borrow area location	2756 Cu. Yds. to be trucked to VCC 3/2, Open Space Lot 152.

- Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
- Additional sediment control must be provided, if deemed necessary by the Howard County Sediment Control Inspector.
- On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the inspection agency is made.
- Trenches for the construction of utilities is limited to three pipe lengths or that which can be back filled and stabilized within one working day, whichever is shorter.

HOWARD SOIL CONSERVATION DISTRICT
PERMANENT SEEDING NOTES

Apply to graded or cleared areas not subject to immediate further disturbance where a permanent long-lived vegetative cover is needed.

SEEDBED PREPARATION: Loosen upper three inches of soil by raking, disking, or other acceptable means before seeding, if not previously loosened.

SOIL AMENDMENTS: In lieu of soil test recommendations, use one of the following schedules:

- PREFERRED -- Apply 2 tons per acre dolomitic limestone (92 lbs/1000sq. ft.) and 600 lbs per acre 10-10-10 fertilizer (14 lbs/1000 sq. ft.) before seeding. Harrow or disk into upper three inches of soil. At time of seeding, apply 400 lbs per acre 30-0-0 ureaform fertilizer (9 lbs/1000sq. ft.).
- ACCEPTABLE -- Apply 2 tons per acre dolomitic limestone (92 lbs/1000sq. ft.) and 1000 lbs per acre 10-10-10 fertilizer (23 lbs/1000 sq. ft.) before seeding. Harrow or disk into upper three inches of soil.

SEEDING -- For the periods March 1 thru April 30, and August 1 thru October 15, seed with 60 lbs per acre (14 lbs/1000sq. ft.) of Kentucky 31 Tall Fescue. For the period May 1 thru July 31, seed with 60 lbs per acre (14 lbs/1000sq. ft.) of Kentucky 31 Tall Fescue and 2 lbs. per acre (.05 lbs/1000sq. ft.) of weeping lovegrass. During the period of October 16 thru February 28, protect site by: Option (1) - 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring. Option (2) - Use sod. Option (3) - Seed with 60 lbs. per acre Kentucky 31 Tall Fescue and mulch 2 tons / acre well anchored straw.

MULCHING -- Apply 1-1/2 to 2 tons per acre (70 to 90 lbs/1000sq. ft.) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 210 gallons per acre (5 gal/1000sq. ft.) of emulsified asphalt on flat areas. On slopes 2 feet or higher, use 340 gallons per acre (8 gal/1000sq. ft.) for anchoring.

MAINTENANCE -- Inspect all seeding areas and make needed repairs, replacements and reseedings.

HOWARD SOIL CONSERVATION DISTRICT
TEMPORARY SEEDING NOTES

Apply to graded or cleared areas likely to be redistributed where a short-term vegetative cover is needed.

SEEDBED PREPARATION: -- Loosen upper three inches of soil by raking, disking, or other acceptable means before seeding, if not previously loosened.

SOIL AMENDMENTS: -- Apply 600 lbs per acre 10-10-10 fertilizer (14 lbs/1000sq. ft.).

SEEDING -- For periods March 1 thru April 30, and from August 15 thru October 15 seed with 2-1/2 bushels per acre of annual rye (3.2 lbs/1000sq. ft.). For the period May 1 thru August 14, seed with 3 lbs. per acre of weeping lovegrass (.07 lbs/1000sq. ft.). For the period November 16 thru February 28, protect site by applying 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring, or use sod.

MULCHING -- Apply 1-1/2 to 2 tons per acre (70 to 90 lbs/1000sq. ft.) of unrotted weed free small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 210 gallons per acre (5 gal/1000sq. ft.) of emulsified asphalt on flat areas. On slopes 2 feet or higher, use 340 gallons per acre (8 gal/1000sq. ft.) for anchoring.

Refer to the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for additional rates and methods not covered.

21.0 STANDARD AND SPECIFICATIONS FOR TOPSOIL

Definition
Placement of topsoil over a prepared subsoil prior to establishment of permanent vegetation.

Purpose
To provide a suitable soil medium for vegetative growth. Soils of concern have low moisture content, low nutrient levels, low pH, materials toxic to plants, and/or unacceptable soil gradation.

- Conditions Where Practice Applies
- This practice is limited to areas having 2:1 or flatter slopes where:
 - The texture of the exposed subsoil/parent material is not adequate to produce vegetative growth.
 - The soil material is so shallow that the rooting zone is not deep enough to support plants or furnish continuing supplies of moisture and plant nutrients.
 - The original soil to be vegetated contains material toxic to plant growth.
 - The soil is so acidic that treatment with limestone is not feasible.

- For the purpose of these Standards and Specifications, areas having slopes steeper than 2:1 require special consideration and design for adequate stabilization. Areas having slopes steeper than 2:1 shall have the appropriate stabilization shown on the plans.

Construction and Material Specifications

- Topsoil salvaged from the existing site may be used provided that it meets the standards as set forth in these specifications. Typically, the depth of topsoil to be salvaged for a given soil type can be found in the representative soil profile section in the Soil Survey published by USDA-SCS in cooperation with Maryland Agricultural Experimental Station.

- Topsoil Specifications - Soil to be used as topsoil must meet the following:
 - Topsoil shall be a loam, sandy loam, clay loam, silt loam, sandy clay loam, loamy sand. Other soils may be used if recommended by an agronomist or soil scientist and approved by the appropriate approval authority. Regardless, topsoil shall not be a mixture of contrasting textured subsoils and shall contain less than 5% by volume of cinders, stones, slag, coarse fragments, gravel, sticks, roots, trash, or other materials larger than 1-1/2" in diameter.
 - Topsoil must be free of plants or plant parts such as bermuda grass, quackgrass, Johnsongrass, nutsedge, poison ivy, thistle, or others as specified.
 - Where the subsoil is either highly acidic or composed of heavy clays, ground limestone shall be spread at the rate of 4-8 tons/acre (200-400 pounds per 1,000 square feet) prior to the placement of topsoil. Lime shall be distributed uniformly over designated areas and worked into the soil in conjunction with tillage operations as described in the following procedures.

- For sites having disturbed areas under 5 acres:
 - Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section I - Vegetative Stabilization Methods and Materials.

- For sites having disturbed areas over 5 acres:
 - On soil meeting Topsoil specifications, obtain test results dictating fertilizer and lime amendments required to bring the soil into compliance with the following:
 - pH for topsoil shall be between 6.0 and 7.5. If the tested soil demonstrates a pH of less than 6.0, sufficient lime shall be prescribed to raise the pH to 6.5 or higher.
 - Organic content of topsoil shall be not less than 15 percent by weight.
 - Topsoil having soluble salt content greater than 500 parts per million shall not be used.
 - No sod or seed shall be placed on soil which has been treated with soil sterilants or chemicals used for weed control until sufficient time has elapsed (14 days min.) to permit dissipation of phytotoxic materials.

Note: Topsoil substitutes or amendments, as recommended by a qualified agronomist or soil scientist and approved by the appropriate approval authority, may be used in lieu of natural topsoil.

- Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section I - Vegetative Stabilization Methods and Materials.

V. Topsoil Application

- When topsoiling, maintain needed erosion and sediment control practices such as diversions, Grade Stabilization Structures, Earth Dikes, Slope Silt Fence and Sediment Traps and Basins.
- Grades on the areas to be topsoiled, which have been previously established, shall be maintained, albeit 4" - 8" higher in elevation.
- Topsoil shall be uniformly distributed in a 4" - 8" layer and lightly compacted to a minimum thickness of 4". Spreading shall be performed in such a manner that sodding or seeding can proceed with a minimum of additional soil preparation and tillage. Any irregularities in the surface resulting from topsoiling or other operations shall be corrected in order to prevent the formation of depressions or water pockets.
- Topsoil shall not be placed while the topsoil or subsoil is in a frozen or muddy condition, when the subsoil is excessively wet or in a condition that may otherwise be detrimental to proper grading and seedbed preparation.


- Alternative for Permanent Seeding - Instead of applying the full amounts of lime and commercial fertilizer, composted sludge and amendments may be applied as specified below:

- Composted Sludge Material for use as a soil conditioner for sites having disturbed areas over 5 acres shall be tested to prescribe amendments and for sites having disturbed areas under 5 acres shall conform to the following requirements:
 - Composted sludge shall be supplied by, or originate from, a person or persons that are permitted (at the time of acquisition of the compost) by the Maryland Department of the Environment under COMAR 26.04.06.
 - Composted sludge shall contain at least 1 percent nitrogen, 15 percent phosphorus, and 0.2 percent potassium and have a Ph of 7.0 to 8.0. If compost does not meet these requirements, the appropriate constituents must be added to meet the requirements prior to use.
 - Composted sludge shall be applied at a rate of 1 ton/1,000 square feet.
- Composted sludge shall be amended with a potassium fertilizer applied at the rate of 4 lb/1,000 square feet, and 1/3 the normal lime application rate.


References: Guideline Specifications, Soil Preparation and Sodding, MD-VA, Pub.#1, Cooperative Extension Service, University of Maryland and Virginia Polytechnic Institutes, Revised 1973.

SEQUENCE OF CONSTRUCTION

- Obtain grading permit. 1 Day
 - Notify the Howard County Department of Public Works Construction Inspection Division at 410-313-1855 at least 48 hours prior to beginning construction. 1 Day
 - Final stake limits of disturbance in accordance with the approved grading and sediment control plan. (Sheet 3) 1 Day
- Note: MDE requires the closure of the onsite streams from March 1 through June 15. No in-stream work is allowed during the closure period.
- PHASE I - SEDIMENT CONTROL FOR 8" SEWERMAIN
- Excavate for and construct 8" public sewer. Utilize the filter bag device during trench construction. Note: In the event the material excavated from the proposed sewer trench is unsuitable to use for backfill, the material shall be removed from the site and trucked to an approved spoil location. Material may not be stockpiled within the wetlands, wetland buffers, streams or stream buffers or 100 year floodplain. 3 Days
 - Immediately stabilize all disturbed areas at the end of each day in accordance with the temporary seeding notes. 8 Days
 - Once the relocated sewer is fully operational and with the permission of the sediment control inspector, remove all silt fence along the sewer alignment that may interfere with the construction of the pond. 1 Day
- PHASE II - SEDIMENT CONTROL FOR POND RECONSTRUCTION
- Install perimeter controls, including silt fence, super silt fence, sandbag/ stone diversions, RPS, and temporary diversion pipes. 5 Days
- Note: The temporary sandbag/ stone dams and diversion pipes shall be checked after every storm event to insure they are operating properly. The temporary diversion pipes shall remain in place until all disturbed areas are completely stabilized and the basin is converted to a permanent pond.
- Clear and grub for pond/ sediment basin. Excavate basin to final bottom elevation (334.15). Install 24" RCP (5'-3 to 5'-4). 1 Week
 - Proposed dam shall not be constructed until:
 - The body of the pond is dredged, formed and permanent stabilized.
 - All barrel, riser, endwalls and other principal spillway materials are onsite.
 - There is a 5 day clear (no precipitation) weather forecast from the National Weather Service.
 - Permission is granted by the sediment control inspector to proceed.
 - Install embankment core trench. Utilize filter bag during trench construction. 2 Weeks
 - Install pond riser and barrel (5-1 to 5-2), anti-seep collars, endwall, Rip-rap in existing plunge pool, and concrete riser base in accordance with the notes and specifications on sheets 6, 7, 2, & 3. 1 Day
 - Install 12" D.I.P. pond drain and attach temporary drawdown device. Install removable pumping station. 1 Week
 - Install embankment cutoff trench and remainder of embankment to constructed top elevation. 1 Week
 - Grade remainder of basin/ pond, including emergency spillway, 5' safety bench, and 12' maintenance bench in accordance with the approved grading plan (sheet 3). Immediately stabilize all disturbed areas in accordance with the temporary seeding notes. 2 Weeks
 - Grade forebays B & C in accordance with the approved grading plan (sheet 3). Install forebay gabions and forebay inflow protection for forebays B and C only per details on sheet 6. Install forebay inflow protection. 1 Week
 - Establish final grade in and around pond/ basin area, forebays and emergency spillway. Install rip-rap on emergency spillway outlet channel. Immediately stabilize all disturbed areas in accordance with the permanent seeding notes. 1 Week
 - Once all disturbed areas are completely stabilized in accordance with the Permanent seeding notes and with the permission of the sediment control inspector, convert basin into permanent pond:
 - Remove temporary drawdown device from 12" D.I.P. pond drain pipe.
 - Excavate any accumulated sediment from basin to final design bottom elevation of 334.15.
 - Install trashracks on all four (4) faces of concrete riser structure in accordance with the details on sheet 6.
 - Close gate valve on 12" pond drain.
 - Stabilize all remaining disturbed areas in accordance with the permanent seeding notes. With the permission of the sediment control inspector, remove all remaining sediment control devices, including silt fence, super silt fence, sandbag/ stone dams and temporary diversion pipes, install forebay 'A'. 1 Week
 - Install landscaping. 1 Week
- Total Estimated Construction Time: 3 1/2 Months



Drainage Area & Soils Map
1" = 200'



Subdivision Name:	Village of Oakland Mills	Sect/Area:	2/3 & 5/1	Parcel No.:	6066.03
Plan No.:	15746-47	Block No.:	3 & 9	Zone:	NEW-TOWN
P.B. 17, Folio 91				Tax Map No.:	36
P.B. 15, Folio 96				Election District:	6th
Water Code:	N/A	Sewer Code:	N/A	Census Tract:	

LDE, INC.
9250 Rumsey Road, Suite 106, Columbia, MD. 21045
(410) 715-1070 (301) 596-3424 (410) 715-9540 (Fax)

DESIGNED:	S.D.H.	Sediment Control Notes & Details & Drainage Area Map	SCALE:	As Shown	
DRAWN:	J.D.R. M.B.J.	BOWL POND Village of Oakland Mills Steven's Forest Capital Project #D-1127 Section Two - Area Three Open Space Lot 4 & P/O Parcel 310, Parcel D and Section Five - Area One Open Space Lot 83	DRAWING:	4 of 11	
CHECKED:	B.D.B.	6th Election District - Howard County, Maryland Previous Submittals:	JOB NO.:	01-008	
DATE:	3/2/02 Rev 9/02 Rev 1/03	OWNER/DEVELOPER:	COLUMBIA ASSOCIATION 10221 Wincoop Circle, Suite 100 Columbia, Maryland 21044-3410 (410) 381-0591	FILE NO.:	

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

David A. Lutz 4/22/02
DIRECTOR DATE

Cindy Hamant 4/16/02
CHIEF, DIVISION OF LAND DEVELOPMENT DATE

Chris Dammann 4/15/02
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL.

Jim Angelo 4/9/02
NATURAL RESOURCE CONSERVATION DATE

THIS DEVELOPMENT PLAN IS APPROVED FOR POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

Yvonne Lee 4/9/02
HOWARD SOIL CONSERVATION DISTRICT DATE

ENGINEER'S CERTIFICATE

I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT ANY REVISIONS TO THIS PLAN MUST BE APPROVED BY A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION.

Bruce D. Burk 4/1/03
SIGNATURE OF ENGINEER DATE

DEVELOPER'S CERTIFICATE

"I WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.


Chris Dammann 4-1-03
SIGNATURE OF DEVELOPER DATE

REVISIONS

No.	Date	Description
1	June, 2005	Added unsuitable material disposal location.

GENERAL NOTES

- THE PURPOSE OF THIS SITE DEVELOPMENT PLAN IS TO PROVIDE CONSTRUCTION DOCUMENTS FOR THE RECONSTRUCTION OF AN EXISTING POND LOCATED ON COLUMBIA ASSOCIATION OPEN SPACE.
- All construction shall be in accordance with the latest standards and specifications of Howard County Design Manual Vol. IV and current MDE and MSHA standards & specifications.
- Project Background:
 - Location: Village of Oakland Mills, Columbia, Maryland
 - Map: Map 26
 - Open Space Lot 83, VOM 5/1, Open Space Lot 4
 - Grid: 9
 - Election District: 6th
- Existing zoning: New Town- Credited Open Space Land use per FDP 60 and FDP 79-A-III.
- Current Plat and Deed References:
 - VOM 2/3, Open Space Lot 4: Plat Book 17, Folio 91; Deed L. 663, F. 307
 - VOM 5/1, Open Space Lot 83; Plat Book 15, Folio 96; Deed L. 563, F. 624
- The Boundary shown hereon is based on the above referenced plats. Plat Book 17, Folio 91 recorded among the Land Records of Howard County on November 24, 1969. Plat Book 15, Folio 96 recorded among the Land Records of Howard County on February 7, 1969.
- Horizontal and vertical datum's are related to the Maryland State Plane Coordinate System as projected from Howard County control stations No. 36BA and 36BB (NAD 83).
- Any damage caused by the contractor to existing Camelback Lane public right-of-way, existing paving, existing curb and gutter, existing utilities, etc. shall be corrected at the contractor's expense.
- The existing utilities shown hereon are located from field surveys and construction drawings of record. The contractor shall locate existing utilities to his own satisfaction and well in advance of any construction activities. Additionally, the contractor shall take all necessary precautions to protect all existing utilities and maintain uninterrupted service. Any damage incurred to utilities or existing features due to contractor's operation shall be repaired immediately at the contractor's expense.
- There may be additional utilities not shown on these plans. The engineer assumes no responsibility for utility locations not shown and it shall be the responsibility of the contractor to verify the locations of all existing utilities within the limits of construction and notify the engineer of any discrepancies, prior to the start of construction.
- Site Analysis Data:
 - a. Total Project Area: 0.5, Lot 4 - 1.791 Ac; 0.5, Lot 83 - 0.1783 Ac (1.9693 Ac total)
 - b. Existing Offsite Drainage easement area: 0.37 Acres
 - c. Proposed Additional offsite Drainage easement area: 0.66 Acres
 - d. Area of Plan Submission: 3.00 Acres
 - e. Limit of Disturbed Area: 2.25 Acres
 - f. Present Use: Open Space - filled in pond
 - g. Proposed Use: Open Space - Reconstructed SWM Pond
 - h. Applicable DPZ File References: F-60-94c, F-70-29, FDP 60, FDP 79-A-III, F-03-66 (Plat Nos. 15746-47)
- A wetland study for the subject site was completed by LDE, Inc. in February, 1997.
- A Wetland Permit and Water Quality Certification from the U.S. Army Corps of Engineers and the Maryland Department of the Environment, is required for the proposed disturbances to the onsite nontidal wetlands, wetland buffers and 100 year floodplain prior to beginning construction. The required permit applications have been completed and submitted to MDE. The assigned MDE tracking number is 02-NI-02501/200264247. Permit issued March 18, 2003.
- This project is located on existing New Town Open Space lots recorded prior to 1992. Therefore, this project is exempt from the forest conservation requirements. For informational purposes, the total area of existing forest to be retained on the two (2) open space lots is 40,000 square feet. See Subdivision, Subtitle Section 16.1202(b)(1)(iv).
- This project is subject to the Howard County Landscaping requirements per Section 16.124 of the Land Development and Subdivision Regulations. Landscaping for the proposed reconstructed pond will be provided in accordance with the Howard County Landscaping Manual.
- Adjustments to the sequence of construction shall be approved by the Howard County Department of Inspections, Licenses and Permits, prior to such adjustments.
- The contractor shall notify the Department of Public Works/Bureau of Engineering/Construction Inspection at (410) 313-1880 at least five (5) working days prior to the start of work.
- The contractor shall notify "Miss Utility" at 1-800-257-7777 at least forty-eight (48) hours prior to any excavation work.
- The existing "D" public sewer located within the existing and proposed Pond will be relocated as shown on the site development plan. Refer to Water and Sewer Contract C-268, sheet 5B of D for plan and profile of the relocated sewer.
- The reconstructed Bowl Pond was designed as a wet pond (MDE Code P-2) to provide 75% water quality and partial quantity management in accordance with the Maryland Department of the Environment "2000 Maryland Stormwater Design Manual, Volumes I & II" and the latest version of "Howard County Design Manual, Volume I - Storm Drainage".
- Three (3) forebays, located at the pond inflow points will provide pre-treatment for the reconstructed Bowl Pond.
- The stormwater management pond shall be privately owned and maintained by the Columbia Association.
- All fill shall be rolled to a minimum degree of compaction of 95% of the dry unit weight as determined by AASHTO T- 190.
- The existing floodplain limit shown hereon is taken from the approved Howard County Little Patuxent River Study. The 100 year elevations in the pond and forebays is based on TR-20.
- A Geotechnical Report was completed by Hillis Carnes Engineering Associates for the existing pond embankment in March, 1997. Refer to boring logs and recommendations on sheet 7.
- Earthwork quantities shown on this plan are estimated and should not be used for bid purposes. Contractors should perform independent earthwork analysis for bid purposes.
- Deviations from these plans and specifications without prior written consent of the civil engineer may cause the work to be unacceptable.
- The dimensioned distances shall govern if scaled and dimensioned distances on this plan are found to be in disagreement.
- No clearing, grading or construction is permitted within the nontidal wetlands or their buffers until the MDE Permit is issued.
- All unsuitable material excavated from the site (dredge spoils) shall be trucked to an approved offsite location. No material shall be stockpiled onsite within the wetlands or their buffers. Unsuitable material shall be trucked to VKC 3/2, Open Space Lot 192.
- Clearing, grading or construction is not permitted within the limit of wetlands, 25' wetlands buffer, streams or 50' stream buffer, floodplain, except as shown on this plan approved by the Department of Planning and Zoning.
- The existing topography shown hereon within the limits of disturbance is taken from a field run survey with two foot contour intervals prepared by LDE, Inc. in March, 1997 and supplemented in February, 2002. The remainder of the topography shown was compiled from Howard County Aerial Topography.
- The gravel access road shown off Camelback Lane on Open Space Lot 83 shall remain after the completion of construction.
- Capital project number related to the Bowl Pond site:
 - a.) D-1127, pond reconstruction/ drainage improvements.
 - b.) W-8212, relocation of existing 8" sewer. Contract No. 268 W & S.
- A temporary grading easement and permanent stormwater management access, drainage and utility easement have been obtained by the Columbia Association from Comerstone/ Stevens Forest, Inc.. The easements are shown on a subdivision plat titled "Revision Plat, Columbia, Village of Oakland Mills-Stevens Forest, Section 2, Area 3 O.S. Lot 4 and P/O Parcel D & Section 5, Area 1, O. S. Lot 83", dated October, 2002 and recorded among the Land Records of Howard County as plat No. 15746-47.
- The Howard County Council approved the abandonment of the portion of the existing public sewer easement of the existing public sewer easement shown hereon to be abandoned at the October 30, 2002 meeting. Resolution No. 163-2002.
- The Department of Planning and Zoning granted approval for all "necessary disturbances" shown within the 100 year floodplain, nontidal wetlands, wetland buffers, and streams in June, 2002.
- The Department of Public Works approved Design Manual Waivers from Volume I, Chapter 5, Sections 5.2.1.A, 5.2.3.B.1, 5.2.4.1, 5.2.5.P and 5.2.6.D.5 by letter dated June 7, 2002.
- The Department of Public Works approved a Design Manual Waiver from Volume I, Chapter 5, Section 5.2.4.1 by letter dated November 13, 2002 to allow the relocated sewer to be within 25' of the toe of the pond embankment.



LOCATION MAP
Scale: 1" = 600'


SITE DEVELOPMENT PLAN BOWL POND RECONSTRUCTION

Columbia
Village of Oakland Mills
Steven's Forest
Section Two - Area Three
Open Space Lot 4 and P/O Parcel 310, Parcel D &
Section Five - Area One
Open Space Lot 83

6th ELECTION DISTRICT HOWARD COUNTY, MARYLAND

BENCHMARKS

- Howard County Control Station 36BA. Elevation= 417.47
Standard stamped disk set on a 3' deep cylindrical concrete base 15' south of an existing 4' asphalt driveway, 61 L.F. southwest of an existing storm drain inlet.
N. 561235.523 E. 1355751.64
- Howard County Control Station 36BB. Elevation= 409.97
Standard stamped disk set on a 3' deep cylindrical concrete base 6.5 L.F. north of face of curb of Santiago Road south of the Oakland Mills Interfaith Center.
N. 561235.523 E. 1356203.68



VICINITY MAP
Scale: 1" = 2000'

SHEET INDEX	
Sheet Number	Description
1	Cover Sheet
2	Site Development Plan
3	Grading & Sediment and Erosion Control Plan
4	Sediment Control Notes & Details & Drainage Area Map
5	Sediment Control Notes & Details
6	Stormwater Management Notes & Details
7	Stormwater Management Notes & Details
8	Stormwater Management Details
9	Sediment Basin Plan, Notes, & Details
10	Existing Conditions Plan
11	Landscape Plan

LEGEND	
EXISTING CONTOUR	---
PROPOSED CONTOUR	---
EXISTING STREAM	---
EXISTING TREELINE	---
PROPOSED TREELINE/ PROPOSED LIMIT OF DISTURBANCE	---
EXISTING PIPE	---
PROPOSED PIPE	---
RIP-RAP OUTLET APRON	---
LIMIT OF DISTURBANCE (For dam construction only)	---
STABILIZED CONSTRUCTION ENTRANCE	---
SILT FENCE	---
EARTH DIKE	---
NON-TIDAL WETLAND LIMIT	---
WETLAND BUFFER LIMIT	---
APPROX. FLOOD PLAIN LIMIT	---
75' STREAM BUFFER	---
NO WOODY VEGETATION ZONE	---

PUBLIC 100 YEAR FLOODPLAIN DRAINAGE & UTILITY EASEMENT LINE TABLE			
NO.	BEARING	DISTANCE	
F1	N1°42'34"W	12.04	
F2	N52°07'36"W	30.63	
F3	N2°07'32"W	16.76	
F4	N5°15'14"W	17.02	
F5	S77°11'11"W	18.97	
F6	N33°58'19"W	9.74	
F7	N24°00'54"E	9.06	
F8	N54°36'51"E	36.06	
F9	N44°47'50"E	29.38	
F10	N41°10'59"E	15.14	
F11	N10°24'08"E	12.99	
F12	N26°17'08"E	12.97	
F13	N06°42'48"E	11.30	
F14	N26°27'11"W	15.32	
F15	N78°48'23"W	7.63	
F16	S59°56'02"W	22.22	
F17	S63°47'48"W	33.01	
F18	S62°46'39"W	40.07	
F19	S48°59'27"W	25.81	
F20	S40°02'54"W	37.16	
F21	S6°02'04"W	22.06	
F22	S73°20'03"W	9.02	
F23	S88°45'55"W	14.83	
F24	N77°06'36"W	16.43	
F25	N55°08'45"W	56.64	
F26	N67°36'28"W	22.28	
F27	N28°18'25"E	10.55	
F28	N52°26'08"E	25.64	
F29	N25°22'50"E	13.18	
F30	N1°32'26"E	16.05	
F31	N49°33'16"E	17.78	
F32	N51°27'16"E	14.80	
F33	N69°48'28"E	36.38	
F34	N59°00'23"E	23.75	
F35	N66°07'29"E	8.69	
F36	N74°09'25"E	70.93	
F37	N70°52'12"E	92.33	
F38	N64°24'51"E	35.72	
F39	N34°50'30"E	12.65	
F40	N07°48'07"E	16.08	
F41	N05°46'59"E	71.72	
F42	N01°36'16"E	138.31	
F43	N25°24'27"E	68.92	
F44	N33°06'12"E	88.16	
F45	N25°48'05"E	90.22	
F46	N24°41'59"E	95.26	
F47	N18°23'58"E	91.12	
F48	N12°02'34"E	46.92	
F49	N28°35'48"E	105.47	
F50	N22°39'56"E	43.88	
F51	N15°58'12"E	20.77	
F52	N09°29'43"E	107.36	

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

Frank A. Singh 7/24/02
DIRECTOR DATE

Cindy Hamer 4/6/03
CHIEF, DIVISION OF LAND DEVELOPMENT DATE

Charles D. Burton 4/15/03
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL.

John Angelo 4/9/03
NATURAL RESOURCE CONSERVATION DATE

THIS DEVELOPMENT PLAN IS APPROVED FOR POND CONSTRUCTION SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

John Angelo 4/9/03
NATURAL RESOURCE CONSERVATION DATE

ENGINEER'S CERTIFICATE

I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL OBSERVATION OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REGULATIONS OF THE HOWARD COUNTY SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT I AM A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND I HAVE PROVIDED THE DEVELOPER WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION.

Bruce D. Burton 4/1/03
SIGNATURE OF ENGINEER DATE

DEVELOPER'S CERTIFICATE

"I WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT."

Charles D. Burton 4-1-03
SIGNATURE OF DEVELOPER DATE

ADDRESS CHART

5976	CAMELBACK LANE
------	----------------

REVISIONS

No.	Date	Description
1	June, 2005	Added disposal site location to note 30.

Subdivision Name: Village of Oakland Mills	Sec. 2/3 & 5/1	Parcel No. 6066.03
Map No. 15746-47	Block No. 3 & 9	Zone NEW-TOWN
P.B. 17, Folio 91	Map No. 36	Election District 6th
P.B. 15, Folio 96	Water Code N/A	Sewer Code N/A

LDE, INC.
9250 Rumsey Road, Suite 106, Columbia, MD. 21045
(410) 715-1070 (301) 596-3424 (410) 715-9540 (Fax)

DESIGNED: S.D.H.	As Shown
DRAWN: J.D.R. MBJ	1 of 11
CHECKED: B.D.B.	JOB NO. 01-008
DATE: 3/2002 Rev 9/02 Rev 1/03	FILE NO.
OWNER/DEVELOPER: COLUMBIA ASSOCIATION 10221 Winthrop Circle, Suite 100 Columbia, Maryland 21044-3410 (410) 381-0591	