




PLAN VIEW OF STEP-POOL  
SCALE: 1"=4'




STEP POOL PROFILE (TYPICAL)  
SCALE: 1"=2'




SECTION A- WEIR CROSS SECTION (TYPICAL)  
SCALE: 1"=2'



SECTION B- POOL CROSS SECTION (TYPICAL)  
SCALE: 1"=2'



CHANNEL CROSS SECTION (TYPICAL)  
SCALE: 1"=2'



STONE TOE PROTECTION DETAIL  
SCALE: 1"=2'

NOTE: VOID SPACE IN CHANNEL COBBLE WILL BE FILLED BY WASHING IN EXISTING SAND AND GRAVEL MATERIAL OR NO. 57 STONE

GRANULAR FILTER MATERIAL	
% LESS THAN	U.S. STANDARD SIEVE SIZE
100	2 1/2 IN. (64 mm)
85-100	1 IN. (25 mm)
60-100	1/2 IN. (13 mm)
35-70	No. 10
20-50	No. 40
3-20	No. 200

NOTE: MATERIAL CAN BE MADE BY MIXING  
25% CRUSHER RUN AGGREGATE (OR NO. 2 STONE)  
25% 67 STONE  
25% PEA GRAVEL  
25% SAND/FINE AGGREGATE

NATURAL FIBER MATTING SPECIFICATION:	
MATERIAL:	WOVEN COIR FIBER YARN OR TWINE
MINIMUM THICKNESS:	0.25 IN.
ELONGATION (DRY/WET):	9%/ 35% (APPROXIMATE)
MINIMUM WEIGHT:	20 OZ/SY
MAXIMUM OPEN AREA:	50%
FLOW VELOCITY THAT MATTING MUST WITHSTAND:	8 FT/SEC. OR GREATER
MAXIMUM ALLOWABLE SHEAR STRESS:	4.5 LBS/SQ FT
LIFE EXPECTANCY:	3 YRS
RECOMMENDED:	KOIR MAT 700 (NEDIA ENTERPRISES INC.) OR EQUIVALENT

APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

*Michael J. ...* 12/17/04  
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

*Cindy Hamilton* 12/21/04  
CHIEF, DIVISION OF LAND DEVELOPMENT DATE

*Daphne ...* 12/27/04  
DIRECTOR DATE

DATE: \_\_\_\_\_

NO. REVISIONS DESCRIPTION: \_\_\_\_\_

ENGINEERS: \_\_\_\_\_  
PLANNERS: \_\_\_\_\_  
SCIENTISTS: \_\_\_\_\_  
CONSTRUCTION MANAGERS: \_\_\_\_\_

**KCI**  
TECHNOLOGIES www.kci.com

CHERRY TREE FARM  
SECTION 1, AREA 2  
OPEN SPACE LOT 170  
STREAM RESTORATION  
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
STORMWATER MANAGEMENT DIVISION  
6781 COLUMBIA GATEWAY DRIVE  
COLUMBIA, MARYLAND 21046

STEP POOL/  
WEIR DETAILS

SCALE: AS NOTED  
DATE: 11-08-04  
KCI JOB NO.: 01-01128.c  
CAPITAL PROJECT NO.: D-1132 (PONDS)  
D-1128 (STREAM)  
PERMIT ISSUE:  
CONSTRUCTION ISSUE:

**C7**  
SHEET NO.: 14 OF 36


SDP-04-123

**LEGEND**

- DRAINAGE AREA DIVIDE
- 380 --- EXISTING MAJOR CONTOUR (GIS)
- SOIL BOUNDARY
- MIC2 SOIL TYPE
- EXISTING MAJOR CONTOUR (SURVEY)
- EXISTING MINOR CONTOUR (SURVEY)
- PROPERTY BOUNDARY
- EXISTING 100-YEAR FLOODPLAIN
- PROPOSED 100-YEAR FLOODPLAIN
- EXISTING WOODS LINE
- LOD --- LOD LIMIT OF DISTURBANCE

TOTAL AREA OF DISTURBANCE - 87,169 S.F. ± OR 2.00 AC. ±

NOTE: DRAINAGE AREA MAP SHOWS OVERALL LAYOUT OF SITE EROSION AND SEDIMENT CONTROL. SEE SHEETS ES2 TO ES5 FOR MORE DETAILED DEPICTION OF INDIVIDUAL FEATURES.



REVIEWED FOR HOWARD SCD AND MEETS TECHNICAL REQUIREMENTS

*Jim Mayo* / *lee* 12/13/04  
 USDA - NATURAL RESOURCES CONSERVATION SERVICE DATE

THIS DEVELOPMENT IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

*Sally* / *Lee* 12/13/04  
 HOWARD SCD DATE

**ENGINEER'S CERTIFICATE**

"I CERTIFY THAT THIS PLAN FOR SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD COUNTY SOIL CONSERVATION DISTRICT."

*Kerry B. Rexroad* 11-10-04  
 SIGNATURE OF ENGINEER (PRINT NAME BELOW SIGNATURE) DATE  
 KERRY B. REXROAD, P.E.

**DEVELOPER'S CERTIFICATE**

"I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN FOR SEDIMENT AND EROSION CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE THE BEGINNING OF THE PROJECT. I/ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD COUNTY SOIL CONSERVATION DISTRICT."

*Howard E. Saltzman* 11-29-04  
 SIGNATURE OF DEVELOPER (PRINT NAME BELOW SIGNATURE) DATE  
 Howard E. Saltzman

APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

*Allen* / *Williams* 12/17/04  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

*Cindy* / *Hamilton* 12/21/04  
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE

*Dorothy* / *Kalff* 12/27/04  
 DIRECTOR (PLANNING) DATE

SOILS TABLE		
SYMBOL	NAME	TYPE
Ba	BAILE SILT LOAM	D
ChB2	CHESTER SILT LOAM	B
GIB2	GLENELG LOAM	B
MIB2	MANOR LOAM	B
MIC2	MANOR LOAM	B
MID3	MANOR LOAM	B

NO.	REVISIONS DESCRIPTION	DATE

ENGINEERS  
 PLANNERS  
 SCIENTISTS  
 CONSTRUCTION MANAGERS

**KCI**  
 TECHNOLOGIES www.kci.com

KCI FILE: M:\2001\010112B.C \ Drawings \ sgd\cherry.dgn



CHERRY TREE FARM  
 SECTION 1, AREA 2  
 OPEN SPACE LOT 170

STREAM RESTORATION & WORKS  
 HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING  
 STOP WATER MANAGEMENT DIVISION  
 6751 COLUMBIA GATEWAY DRIVE  
 COLUMBIA, MARYLAND 21046

**EROSION & SEDIMENT CONTROL DRAINAGE AREA MAP**

SCALE: 1" = 100'  
 DATE: 11-08-04  
 KCI JOB NO.: 01-0112B.C  
 CAPITAL PROJECT NO.: D-1132 (PONDS) D-1128 (STREAM)  
 PERMIT ISSUE:  
 CONSTRUCTION ISSUE:

**ES1**  
 SHEET NO.: 15 OF 36

PLOTTED: 01:49 PM on Monday, November 08, 2004  
 FILE: M:\2001\010112B.C \ Drawings \ sgd\cherry.dgn

MATCHLINE - SEE SHEET ES3



NOTE: 1. PROPOSED GRADING GRAYSCALED FOR CLARITY OF E & S CONTROL FEATURES.

2. ALL WATER COLLECTED WITHIN THE LIMIT OF DISTURBANCE (WITH THE EXCEPTION OF WATER PUMPED FROM ABOVE THE CLEAN WATER DIKE) SHALL BE PUMPED THROUGH THE FILTER BAG.

3. STREAM ACCESS POINT (A) SHALL ONLY BE OPENED FOR PHASE 4 WORK. FOR PHASE 5, CLOSE AND STABILIZE ACCESS POINT (A) AND OPEN UP ACCESS POINT (B) ONLY. FOR PHASE 6 & 7, CLOSE AND STABILIZE ACCESS POINT (B) AND OPEN UP ACCESS POINT (C) ONLY. ACCESS POINTS (A), (B), AND (C) CAN BE CLEARED AS PART OF INITIAL CLEARING, BUT GRUBBING OF EACH ACCESS POINT SHALL ONLY BE PERFORMED IMMEDIATELY BEFORE THE SPECIFIC ACCESS POINT IS NEEDED.

4. WITH PERMISSION OF THE SEDIMENT CONTROL INSPECTOR, CONTRACTOR MAY ADJUST SANDBAGS FOR PUMP AROUND TO 5 FEET +/- OF THE PHASE LINE.

5. CONTRACTOR SHALL ONLY HAVE ONE PHASE OPEN AT A TIME.

REVIEWED FOR HOWARD SCD AND MEETS TECHNICAL REQUIREMENTS

*Cim Myers* 12/13/04  
USDA - NATURAL RESOURCES CONSERVATION SERVICE DATE

THIS DEVELOPMENT IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

*Keith Selig* 12/13/04  
HOWARD SCD DATE

ENGINEER'S CERTIFICATE

"I CERTIFY THAT THIS PLAN FOR SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD COUNTY SOIL CONSERVATION DISTRICT"

*Kerry B. Rexroad* 11-19-04  
SIGNATURE OF ENGINEER (PRINT NAME BELOW SIGNATURE) DATE  
KERRY B. REXROAD, P.E.

DEVELOPER'S CERTIFICATE

"I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN FOR SEDIMENT AND EROSION CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE THE BEGINNING OF THE PROJECT. I/ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD COUNTY SOIL CONSERVATION DISTRICT"

*Howard E. Saltzman* 11-24-04  
SIGNATURE OF DEVELOPER (PRINT NAME BELOW SIGNATURE) DATE  
Howard E. Saltzman

APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

*William Danaher* 12/17/04  
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

*Cindy Hamilton* 12/21/04  
CHIEF, DIVISION OF LAND DEVELOPMENT DATE

*Joseph Lafferty* 12/27/04  
DIRECTOR DATE

NO.	REVISIONS DESCRIPTION	DATE

ENGINEERS  
PLANNERS  
SCIENTISTS  
CONSTRUCTION MANAGERS

TECHNOLOGIES www.kci.com

CHERRY TREE FARM  
SECTION 1, AREA 2  
OPEN SPACE LOT 170

STREAM RESTORATION  
HOWARD COUNTY DEPT. OF PUBLIC WORKS  
STORMWATER MANAGEMENT DIVISION  
8751 COLUMBIA GATEWAY DRIVE  
COLUMBIA, MARYLAND 21046

EROSION & SEDIMENT CONTROL PLAN - AREA A

SCALE: 1" = 20'

DATE: 11-08-04

KCIJOB NO.: 01-01128.c

CAPITAL PROJECT NO.: D-1132 (PONDS)  
D-1128 (STREAM)

PERMIT ISSUE:

CONSTRUCTION ISSUE:

**ES2**

SHEET NO.: 16 OF 36


SDP-04-123

PLOTTED: 01:49 PM on Monday, November 08, 2004  
FILE: \\001\01128.C - 01128.C.dwg  
PLOT FILE: \\001\01128.C - 01128.C.dwg

D  
C  
B  
A

**NOTES:**

1. ALL WATER COLLECTED WITHIN THE LIMIT OF DISTURBANCE (WITH THE EXCEPTION OF WATER PUMPED FROM ABOVE THE CLEAN WATER DIKE) SHALL BE PUMPED THROUGH THE FILTER BAG.
2. WITH PERMISSION OF THE SEDIMENT CONTROL INSPECTOR, CONTRACTOR MAY ADJUST SANDBAGS FOR PUMP AROUND TO 5 FEET / OF THE PHASE LINE.
3. CONTRACTOR SHALL ONLY HAVE ONE PHASE OPEN AT A TIME.
4. THE TEMPORARY DEWATERING PIPES IN THE PONDS SHALL BE CONSTRUCTED THE SAME AS SHOWN ON SHEET SW4 WITH THE EXCEPTION THAT THE PERFORATED PIPE SHALL BE WRAPPED WITH 1/2" HARDWARE CLOTH AND GEOTEXTILE FABRIC CLASS E DURING SEDIMENT CONTROL. WHEN THE POND HAS BEEN STABILIZED AND IS READY TO CONVERT TO FINAL STORMWATER MANAGEMENT, REMOVE THE HARDWARE CLOTH AND GEOTEXTILE CLASS E, AND RECONSTRUCT THE PERMANENT DEWATERING PIPE AS PER DETAILS ON SHEET SW4.



REVIEWED FOR HOWARD SCD AND MEETS TECHNICAL REQUIREMENTS

USDA - NATURAL RESOURCES CONSERVATION SERVICE *in Memo* 12/13/04 DATE

THIS DEVELOPMENT IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

HOWARD SCD *John* 12/13/04 DATE

**ENGINEER'S CERTIFICATE**

"I CERTIFY THAT THIS PLAN FOR SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD COUNTY SOIL CONSERVATION DISTRICT"

*Kerry B. Rexroad* 11-10-04 DATE  
SIGNATURE OF ENGINEER (PRINT NAME BELOW SIGNATURE)  
KERRY B. REXROAD, P.E.

**DEVELOPER'S CERTIFICATE**

"I WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN FOR SEDIMENT AND EROSION CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE THE BEGINNING OF THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD COUNTY SOIL CONSERVATION DISTRICT"

*Howard E. Saltzman* 11-24-09 DATE  
SIGNATURE OF DEVELOPER (PRINT NAME BELOW SIGNATURE)  
Howard E. Saltzman

APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

*Mr. Dammann* 12/17/04 DATE  
CHIEF, DEVELOPMENT ENGINEERING DIVISION

*Cindy Horvath* 12/16/04 DATE  
CHIEF, DIVISION OF LAND DEVELOPMENT

*Steve Kelly* 12/21/04 DATE  
DIRECTOR (PLANNING)



NO.	REVISIONS DESCRIPTION	DATE

ENGINEERS  
PLANNERS  
SCIENTISTS  
CONSTRUCTION MANAGERS

**KCI**  
TECHNOLOGIES www.kci.com

CHERRY TREE FARM  
SECTION 1, AREA 2  
OPEN SPACE LOT 170

STREAM RESTORATION INC. WORKS  
HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING  
STORMWATER MANAGEMENT DIVISION  
8751 COLUMBIA GATEWAY DRIVE  
COLUMBIA, MARYLAND 21046

EROSION & SEDIMENT CONTROL PLAN - AREA B

SCALE: 1" = 20'  
DATE: 11-08-04  
KCI JOB NO.: 01-01128.c  
CAPITAL PROJECT NO.: D-1132 (PONDS)  
D-1128 (STREAM)  
PERMIT ISSUE:  
CONSTRUCTION ISSUE:

**ES3**  
SHEET NO.: 17 OF 36

SDP-04-123


PLOTTED: 01:49 PM on Monday, November 08, 2004  
FILE: \\s01\01128\01128.dwg  
PLOT FILE: \\s01\01128\01128.dwg












### TEMPORARY ACCESS CULVERT

Construction Specifications

- Restrictions - No construction or removal of a temporary access culvert will be permitted between October 1 through April 30 for Class III and Class IV Trout Waters or between March 1 through June 15 for non-trout waterways.
- Culvert Strength - All culverts shall be strong enough to support their cross sectional area under maximum expected loads.
- Culvert Size - The size of the culvert pipe shall be the largest pipe diameter that will fit into the existing channel without major excavation of the waterway channel or without major approach fills. If a channel width exceeds 3 feet, additional pipes may be used until the cross sectional area of the pipes is greater than 60 percent of the cross sectional area of the existing channel. The minimum size culvert that may be used is a 12" diameter pipe. In all cases, the pipe(s) shall be large enough to convey normal stream flows.
- Culvert Length - The culvert(s) shall extend a minimum of one foot beyond the upstream and downstream toe to the aggregate placed around the culvert. In no case shall the culvert exceed 40 feet in length.
- Filter Cloth - Filter cloth shall be placed on the streambed and streambanks prior to placement of the pipe culvert(s) and aggregate. The filter cloth shall cover the streambed and extend a minimum six inches and a maximum one foot beyond the end of the culvert and bedding material. Filter cloth reduces settlement and improves crossing stability.
- Culvert Placement - The invert elevation of the culvert shall be installed on the natural streambed grade to minimize interference with fish migration (free passage of fish).
- Culvert Protection - The culvert(s) shall be covered with a minimum of one foot of aggregate. If multiple culverts are used they shall be separated by at least 12" of compacted aggregate fill.
- Stabilization - All areas disturbed during culvert installation shall be stabilized within 14 calendar days of the disturbance in accordance with the Standard for "Critical Area Stabilization With Permanent Seeding."

U. S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE PAGE H - 29 - 12A MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION



LOCATION	NUMBER OF PIPES	DIAMETER* (INCHES)	PIPE MATERIAL
NORTH OF PHASE 3	2	42" X 27"	RCP, CL IV

\* ALL TEMPORARY ACCESS CULVERTS TO BE SET AT 1.0% (MIN.)

### HOWARD COUNTY CONSERVATION DISTRICT STANDARD SEDIMENT CONTROL NOTES

- A minimum of 48 hours notice must be given to the Howard County Department of Inspections, Licenses and Permits, Sediment Control Division prior to the start of any construction (410 313-1855).
  - All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the most current MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL and revisions thereto.
  - Following initial soil disturbance or re-disturbance, permanent or temporary stabilization shall be completed within: a) 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all slopes greater than 3:1, b) 14 days as to all other disturbed or graded areas on the project site.
  - All sediment traps/basins shown must be fenced and warning signs posted around their perimeter in accordance with Vol 1, Chapter 12 of the HOWARD COUNTY DESIGN MANUAL, Storm Drainage.
  - All disturbed areas must be stabilized within the time period specified above in accordance with the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for permanent seeding (Sec. 51), sod (Sec. 54), temporary seeding (Sec. 50) and mulching (Sec. 52). Temporary stabilization with mulch alone can only be done when recommended seeding dates do not allow for proper germination and establishment of grasses.
  - All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.
  - Site Analysis:
 

Total Area of Site	4.90	Acre
Area Disturbed	2.00	Acre
Area to be roofed or paved	0.0	Acre
Area to be vegetatively stabilized	2.90	Acre
Total Cut	1947.47	Cu. Yds.
Total Fill	638.98	Cu. Yds.
Offsite waste/borrow area location	UNKNOWN*	
  - Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
  - Additional sediment control must be provided, if deemed necessary by the Howard County Sediment Control Inspector.
  - On all sites with disturbed areas in excess of 2 acres, approval of the Inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the inspection agency is made.
  - Trenches for the construction utilities is limited to three pipe lengths or that which shall be back-filled and stabilized by the end of each work day, whichever is shorter.
- \* OFFSITE WASTE/BORROW AREA, IF NEEDED, SHALL HAVE AN APPROVED EROSION AND SEDIMENT CONTROL PLAN AND ACTIVE PERMIT.

### TIME RESTRICTION NOTES:

- Pumping is not permitted between the hours of 7:00 PM and 7:00 AM, Monday through Friday.
- Construction equipment shall not be started nor run between the hours of 7:00 PM and 7:00 AM, Monday through Friday.
- For Saturday work, the above hours shall be 5:00 PM and 9:00 AM, respectively.
- No work shall be done on Sunday.

### 21.0 STANDARD AND SPECIFICATIONS FOR TOPSOIL

**Definition**  
Placement of topsoil over a prepared subsoil prior to establishment of permanent vegetation.

**Purpose**  
To provide a suitable soil medium for vegetative growth. Soils of concern have low moisture content, low nutrient levels, low pH, materials toxic to plants, and/or unacceptable soil gradation.

- Conditions Where Practice Applies**
- This practice is limited to areas having 2:1 or flatter slopes where:
    - The texture of the exposed subsoil/parent materials is not adequate to produce vegetative growth.
    - The soil materials so shallow that the rooting zone is not deep enough to support plants or furnish continuing supplies of moisture and plant nutrients.
    - The original soil to be vegetated contains material toxic to plant growth.
    - The soils so acidic that treatment with limestone is not feasible.
  - For the purpose of these Standards and Specifications, areas having slopes steeper than 2:1 require special consideration and design for adequate stabilization. Areas having slopes steeper than 2:1 shall have the appropriate stabilization shown on the plans.

### Construction and Material Specifications

- Topsoil salvaged from the existing site may be used provided that it meets the standards as set forth in these specifications. Typically, the depth of topsoil to be salvaged for a given soil type can be found in the representative soil profile section in the Soil Survey published by USDA-SCS in cooperation with Maryland Agricultural Experiment Station.
    - Topsoil Specifications - Soil to be used as topsoil must meet the following:
      - Topsoil shall be a loam, sandy loam, clay loam, silt loam, sandy clay loam, loamy sand. Other soils may be used if recommended by an agronomist or soil scientist and approved by the appropriate approval authority. Regardless, topsoil shall not be a mixture of contrasting textured subsoils and shall contain less than 5% by volume of cinders, stones, slag, coarse fragments, gravel, sticks, roots, trash, or other materials larger than 1 1/2" in diameter.
      - Topsoil must be free of plants or plant parts such as bermuda grass, quackgrass, Johnsongrass, nuttseed, poison ivy, thistle, or others as specified.
      - Where the subsoils either highly acidic or composed of heavy clays, ground limestone shall be spread at the rate of 4-8 tons/acre (200-400 pounds per 1,000 square feet) prior to the placement of topsoil. Lime shall be distributed uniformly over designated areas and worked into the soil in conjunction with tillage operations as described in the following procedures.
  - For sites having disturbed areas under 5 acres:
    - Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section - Vegetative Stabilization Methods and Materials.
  - For sites having disturbed areas over 5 acres:
    - On soil meeting Topsoil specifications, obtain test results dictating fertilizer and lime amendments required to bring the soil into compliance with the following:
      - pH for topsoil shall be between 6.0 and 7.5, if the tested soil demonstrates a pH of less than 6.0, sufficient lime shall be prescribed to raise the pH to 6.5 or higher.
      - Organic content of topsoil shall be not less than 1.5 percent by weight.
      - Topsoil having soluble salt content greater than 500 parts per million shall not be used.
      - No sod or seed shall be placed on soil which has been treated with soil sterilants or chemicals used for weed control until sufficient time has elapsed (14 days min.) to permit dissipation of phyto-toxic materials.
- Note:** Topsoil substitutes or amendments, as recommended by a qualified agronomist or soil scientist and approved by the appropriate approval authority, may be used in lieu of natural topsoil.

### V. Topsoil Application

- When topsoiling, maintain needed erosion and sediment control practices such as diversions, Grade Stabilization Structures, Earth Dikes, Slope Silt Fence and Sediment Traps and Basins.
- Grades on the areas to be topsoiled, which have been previously established, shall be maintained, albeit 4" - 8" higher in elevation.
- Topsoil shall be uniformly distributed in a 4" - 8" layer and lightly compacted to a minimum thickness of 4". Spreading shall be performed in such a manner that sodding or seeding can proceed with a minimum of additional soil preparation and tillage. Any irregularities in the surface resulting from topsoiling or other operations shall be corrected in order to prevent the formation of depressions or water pockets.
- Topsoil shall not be placed while the topsoil or subsoil is in a frozen or muddy condition, when the subsoil is excessively wet or in a condition that my otherwise be detrimental to proper grading and seedbed preparation.

### HOWARD SOIL CONSERVATION DISTRICT

### TEMPORARY SEEDING NOTES\*\*

Apply to graded or cleared areas likely to be re-disturbed where a short-term vegetative cover is needed.

**Seedbed Preparation:** - Loosen upper three inches of soil by raking, disking or other acceptable means before seeding, if not previously loosened.

**Soil Amendments:** - Apply 600 lbs/acre 10-10-10 fertilizer (14 lbs/1000 sq. ft.).

**Seeding:** - For periods March 1 - April 30 and from August 15 - October 15, seed with 2-12 bushel per acre of annual ryegrass (3.2 lbs/1000 sq. ft.). For the period May 1 - August 14, seed with 3 lbs/acre of weeping lovegrass (07 lbs/1000 sq. ft.). For the period November 16 - February 28, protect site by applying 2 tons/acre of well-anchored straw mulch and seed as soon as possible in the spring, or use sod.

**Mulching:** - Apply 1-1/2 to 2 tons/acre (70 to 90 lbs/1000 sq. ft.) of unrotted weed-free, small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool. No asphalt emulsion shall be used for anchoring. Only a non-toxic, latex backing materials is allowed.

**Soil Amendments:** In lieu of soil test recommendations, use one of the following schedules:

- Preferred** - Apply 2 tons/acre dolomitic limestone (92 lbs/1000 sq. ft.) and 600 lbs/acre 10-10-10 fertilizer (14 lbs/1000 sq. ft.) before seeding. Harrow or disk into upper three inches of soil. At time of seeding, apply 400 lbs/acre 30-0-0 ureaformal fertilizer @ 1000 sq. ft.)
- Acceptable** - Apply 2 tons/acre dolomitic limestone (92 lbs/1000 sq. ft.) and 1000 lbs/acre 10-10-10 fertilizer (23 lbs/1000 sq. ft.) before seeding. Harrow or disk into upper three inches of soil.

Refer to the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for additional rates and methods not covered.

\*\* Contractor shall perform a soil test at the site as a first order of business. The results shall be reviewed by the Department of Recreation and Parks to determine appropriate soil amendments and fertilization needs for this project. No fertilizer or soil amendments shall be added without approval of Department of Recreation and Parks.

### SEQUENCE OF CONSTRUCTION

- | NO.     | REVISIONS DESCRIPTION   | DATE |
|---------|---|------|
| 1 DAY   | 1. OBTAIN GRADING PERMIT, STREAM CLOSURE PERIOD IS MARCH 1-JUNE 15, INCLUSIVE. MORE PERMIT TRACKING NO. 20048320. PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITIES, A VIDEO TAPE AND PHOTOGRAPHS OF THE PROPOSED WORK AREA FROM THE UPPER SAND CHERRY LANE TO THE LOWER SAND CHERRY LANE SHALL BE TAKEN.  |      |
| 5 DAYS  | 2. NOTIFY THE MARYLAND DEPARTMENT OF THE ENVIRONMENT'S NONTIDAL WETLANDS AND WATERWAYS INSPECTIONS AND COMPLIANCE DIVISION AT LEAST FIVE (5) DAYS PRIOR TO ANY EARTH MOVING CONSTRUCTION WITHIN NONTIDAL WETLANDS AND/OR THEIR BUFFERS. THE CONTRACTOR SHALL NOTIFY "MISS UTILITY" AT 1-800-267-7777 AT LEAST FIVE (5) WORKING DAYS PRIOR TO ANY WORK BEING DONE. THE CONTRACTOR SHALL NOTIFY THE HOWARD COUNTY CONSTRUCTION INSPECTION DIVISION (410-313-1880) A MINIMUM OF 24 HOURS PRIOR TO THE START OF ANY CONSTRUCTION. NOTE: TIME RESTRICTION NOTES ON THIS SHEET. |      |
| 1 WEEK  | 3. CONSTRUCT ORANGE SAFETY FENCE AS SHOWN ON THE PLANS, HOWARD COUNTY DEPARTMENT OF RECREATION AND PARKS SHALL REVIEW AND APPROVE THE LOCATION OF THE ORANGE SAFETY FENCE PRIOR TO ANY EARTH MOVING OR REMOVING OF EXISTING TREES OR SHRUBS.  |      |
| 2 DAYS  | 4. CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE AT NORTH END OF SITE.   |      |
| 3 DAYS  | 5. INSTALL TEMPORARY ACCESS CULVERTS UPSTREAM OF PHASE 3.   |      |
| 2 DAYS  | 6. CLEAR AND GRUB FOR AND INSTALL EROSION AND SEDIMENT CONTROL MEASURES OR DEVICES FOR PHASE 1 CONSTRUCTION.  |      |
| 5 DAYS  | 7. UPON APPROVAL OF HOWARD COUNTY SEDIMENT CONTROL INSPECTOR, CLEAR AND GRUB WITHIN LIMIT OF DISTURBANCE FOR PHASE 1 CONSTRUCTION.  |      |
| 4 WEEKS | 8. CONSTRUCT STORMWATER MANAGEMENT POND C, INCLUDING OUTLET STRUCTURE, DEWATERING DEVICE, AND SLOPE PROTECTION ACCORDING TO CONSTRUCTION PLANS.   |      |
| 3 DAYS  | 9. UPON COMPLETION OF STORMWATER MANAGEMENT POND C, PERMANENTLY STABILIZE ACCORDING TO PERMANENT SEEDING SCHEDULE.  |      |
| 2 DAYS  | 10. WITH PERMISSION OF THE SEDIMENT CONTROL INSPECTOR, REMOVE ALL TEMPORARY MEASURES WITHIN PHASE 1 AND PERMANENTLY STABILIZE THE AREA.   |      |
| 2 DAYS  | 11. CLEAR AND GRUB FOR AND INSTALL EROSION AND SEDIMENT CONTROL MEASURES OR DEVICES FOR PHASE 2 CONSTRUCTION.   |      |
| 3 DAYS  | 12. UPON APPROVAL OF HOWARD COUNTY SEDIMENT CONTROL INSPECTOR, CLEAR AND GRUB WITHIN LIMIT OF DISTURBANCE FOR PHASE 2 CONSTRUCTION.   |      |
| 3 WEEKS | 13. CONSTRUCT STORMWATER MANAGEMENT POND B, INCLUDING OUTLET STRUCTURE, DEWATERING DEVICE, AND SLOPE PROTECTION ACCORDING TO CONSTRUCTION PLANS.  |      |
| 3 DAYS  | 14. UPON COMPLETION OF STORMWATER MANAGEMENT POND B, PERMANENTLY STABILIZE ACCORDING TO PERMANENT SEEDING SCHEDULE.   |      |
| 2 DAYS  | 15. WITH PERMISSION OF THE SEDIMENT CONTROL INSPECTOR, REMOVE ALL TEMPORARY MEASURES WITHIN PHASE 2 AND PERMANENTLY STABILIZE THE AREA.   |      |
| 2 DAYS  | 16. CLEAR AND GRUB FOR AND INSTALL EROSION AND SEDIMENT CONTROL MEASURES OR DEVICES FOR PHASE 3 CONSTRUCTION.   |      |
| 3 DAYS  | 17. UPON APPROVAL OF HOWARD COUNTY SEDIMENT CONTROL INSPECTOR, CLEAR AND GRUB WITHIN LIMIT OF DISTURBANCE FOR PHASE 3 CONSTRUCTION.   |      |
| 3 WEEKS | 18. CONSTRUCT STORMWATER MANAGEMENT POND A, INCLUDING OUTLET STRUCTURE, DEWATERING DEVICE, AND SLOPE PROTECTION ACCORDING TO CONSTRUCTION PLANS.  |      |
| 2 DAYS  | 19. UPON COMPLETION OF STORMWATER MANAGEMENT POND A, PERMANENTLY STABILIZE ACCORDING TO PERMANENT SEEDING SCHEDULE.   |      |
| 5 DAYS  | 20. WITH PERMISSION OF THE SEDIMENT CONTROL INSPECTOR, REMOVE ALL TEMPORARY MEASURES WITHIN PHASE 3 AND PERMANENTLY STABILIZE THE AREA.   |      |
| 2 DAYS  | 21. CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE AT SOUTH END OF SITE.  |      |
| 7 DAYS  | 22. CLEAR AND GRUB FOR AND INSTALL EROSION AND SEDIMENT CONTROL MEASURES OR DEVICES FOR PHASE 4 CONSTRUCTION.   |      |
| 2 DAYS  | 23. UPON APPROVAL OF HOWARD COUNTY SEDIMENT CONTROL INSPECTOR, CLEAR AND GRUB WITHIN LIMIT OF DISTURBANCE FOR PHASE 4 CONSTRUCTION.   |      |
| 7 DAYS  | 24. PERFORM GRADING AND RESTORATION WORK IN THE PHASE 4 AREA ON THE CONTRACT DRAWINGS, PERMANENTLY STABILIZE THE WORK AREA AS NOTED ON THE CONTRACT DRAWINGS, INCLUDING LANDSCAPING.  |      |
| 5 DAYS  | 25. WITH PERMISSION OF THE SEDIMENT CONTROL INSPECTOR, CLEAR AND GRUB FOR EROSION AND SEDIMENT CONTROL MEASURES OR DEVICES FOR PHASE 5 CONSTRUCTION, REMOVE ALL TEMPORARY MEASURES WITHIN PHASE 5, INSTALL EROSION AND SEDIMENT CONTROL MEASURES IN PHASE 5, AND PERMANENTLY STABILIZE THE AREA IN PHASE 5 DISTURBED BY THE OPERATION.  |      |
| 2 DAYS  | 26. UPON APPROVAL OF HOWARD COUNTY SEDIMENT CONTROL INSPECTOR, CLEAR AND GRUB WITHIN LIMIT OF DISTURBANCE FOR PHASE 5 CONSTRUCTION.   |      |
| 7 DAYS  | 27. PERFORM GRADING AND RESTORATION WORK IN THE PHASE 5 AREA ON THE CONTRACT DRAWINGS, PERMANENTLY STABILIZE THE WORK AREA AS NOTED ON THE CONTRACT DRAWINGS, INCLUDING LANDSCAPING.  |      |
| 5 DAYS  | 28. WITH PERMISSION OF THE SEDIMENT CONTROL INSPECTOR, CLEAR AND GRUB FOR EROSION AND SEDIMENT CONTROL MEASURES OR DEVICES FOR PHASE 6 CONSTRUCTION, REMOVE ALL TEMPORARY MEASURES WITHIN PHASE 6, INSTALL EROSION AND SEDIMENT CONTROL MEASURES IN PHASE 6, AND PERMANENTLY STABILIZE THE AREA IN PHASE 6 DISTURBED BY THE OPERATION.  |      |
| 2 DAYS  | 29. UPON APPROVAL OF HOWARD COUNTY SEDIMENT CONTROL INSPECTOR, CLEAR AND GRUB WITHIN LIMIT OF DISTURBANCE FOR PHASE 6 CONSTRUCTION.   |      |
| 7 DAYS  | 30. PERFORM GRADING AND RESTORATION WORK IN THE PHASE 6 AREA ON THE CONTRACT DRAWINGS, PERMANENTLY STABILIZE THE WORK AREA AS NOTED ON THE CONTRACT DRAWINGS, INCLUDING LANDSCAPING.  |      |
| 5 DAYS  | 31. WITH PERMISSION OF THE SEDIMENT CONTROL INSPECTOR, CLEAR AND GRUB FOR EROSION AND SEDIMENT CONTROL MEASURES OR DEVICES FOR PHASE 7 CONSTRUCTION, REMOVE ALL TEMPORARY MEASURES WITHIN PHASE 7, INSTALL EROSION AND SEDIMENT CONTROL MEASURES IN PHASE 7, AND PERMANENTLY STABILIZE THE AREA IN PHASE 7 DISTURBED BY THE OPERATION.  |      |
| 2 DAYS  | 32. UPON APPROVAL OF HOWARD COUNTY SEDIMENT CONTROL INSPECTOR, CLEAR AND GRUB WITHIN LIMIT OF DISTURBANCE FOR PHASE 7 CONSTRUCTION.   |      |
| 7 DAYS  | 33. PERFORM GRADING AND RESTORATION WORK IN THE PHASE 7 AREA ON THE CONTRACT DRAWINGS, PERMANENTLY STABILIZE THE WORK AREA AS NOTED ON THE CONTRACT DRAWINGS, INCLUDING LANDSCAPING.  |      |
| 2 DAYS  | 34. WITH PERMISSION OF THE SEDIMENT CONTROL INSPECTOR, REMOVE ALL TEMPORARY MEASURES WITHIN PHASE 7 AND PERMANENTLY STABILIZE THE AREA.   |      |
| 3 WEEKS | 35. INSTALL REMAINING LANDSCAPING AS SPECIFIED ON THE PLAN.   |      |
| 7 DAYS  | 36. WHEN VEGETATION IS ESTABLISHED AND WITH PERMISSION OF THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR, REMOVE ALL REMAINING EROSION AND SEDIMENT CONTROL MEASURES AND PERMANENTLY STABILIZE THOSE AREAS DISTURBED BY THIS PROCESS.   |      |
| 4 WEEKS | 37. CONDUCT FINAL "AS-BUILT" SURVEY OF STORM WATER MANAGEMENT FACILITIES AND STREAM PROFILE WITHIN RESTORATION AREA AND SUBMIT "AS-BUILT" PLANS TO THE APPROPRIATE AGENCIES WITHIN 30 DAYS OF COMPLETION OF CONSTRUCTION.   |      |

FOR AREAS WITH LOD WITH NO DESIGNATED PLANTING AREA, SYMBOL USE PERMANENT SEEDING BELOW. FOR ALL AREAS DENOTED BY SYMBOL SEE SHEET LS-5 FOR PERMANENT SEEDING.

### HOWARD SOIL CONSERVATION DISTRICT

### PERMANENT SEEDING NOTES\*\*

**Seeding:** - For the periods March 1 - April 30, and August 1 - October 15, seed with 60 lbs/acre (14 lbs/1000 sq. ft.) of Kentucky 31 Tall Fescue. For the period May 1 - July 31, seed with 60 lbs Kentucky 31 Tall Fescue per acre and 2 lbs/acre (.05 lbs/100sq. ft.) of weeping lovegrass. During the period of October 16 - February 28, protect site by applying 2 tons per acre of well-anchored straw mulch and seed as soon as possible in the spring. Option 2 - Use sod. Option 3 - Seed with 60 lbs/acre Kentucky 31 Tall Fescue and mulch with 2 tons/acre well-anchored straw.

**Mulching:** - Apply 1-1/2 to 2 tons per acre (70 to 90 lbs/1000 sq. ft.) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool. No asphalt emulsion shall be used for anchoring. Only a non-toxic, latex backing material is allowed.

**Maintenance:** - Inspect all seeding areas and make needed repairs, replacements and reseedings.

DATE: 11-08-04

SCALE: N/A

KCI JOB NO.: 01-01128.c

CAPITAL PROJECT NO.: D-1132 (POND) D-1128 (STREAM)

PERMIT ISSUE:

CONSTRUCTION ISSUE:


ENGINEERS: PLANNERS: SCIENTISTS: CONSTRUCTION MANAGERS:

www.kci.com

ES8

SHEET NO.: 22 OF 36

SDP-04-123



**CONTROL POINTS OF POND A**

POINT	COORDINATES	
	NORTH	EAST
1	536670.74	1341494.80
2	536660.37	1341450.17
3	536659.57	1341444.40
4	536655.20	1341346.14
5	536606.64	1341465.78
6	536701.97	1341443.63
7	536797.51	1341429.77
8	536852.02	1341418.86
9	536681.90	1341406.50
10	536601.10	1341426.40


**PLAN VIEW - POND A**  
SCALE: 1" = 20'

**S.W.M. DESIGN SUMMARY**


DESIGN STORM	FACILITY INFLOW (cfs)	FACILITY OUTFLOW (cfs)	STAGE	STORAGE VOLUME AC. FT.
1-Year	10.1	2.8	373.59	0.25
2-Year	16.8	10.9	374.01	0.31
5-Year	29.7	26.4	374.49	0.39
10-Year	42.1	40.7	374.75	0.44
100-Year	73.7	72.4	375.12	0.51

STRUCTURE TYPE: DRY EXTENDED DETENTION POND  
 SURFACE AREA: 0.27 AC.  
 STRUCTURE HAZARD CLASSIFICATION: "A"  
 STORAGE-HEIGHT PRODUCT: 2.16  
 WATERSHED AREA TO FACILITY (ACRES): 14.53  
 THIS FACILITY SHALL BE PUBLICLY MAINTAINED BY HOWARD COUNTY.


WATERSHED: CHERRY CREEK  
 STREAM CLASS: 1  
 FREEBOARD: 1.38 FT.  
 WATER QUALITY: N/A  
 LEVEL OF MANAGEMENT PROVIDED BY FACILITY: 1-YEAR (QUANTITY)




**POND A OUTLET PROTECTION**  
SCALE: 1" = 10'



**PROFILE ALONG PRINCIPAL SPILLWAY**  
SCALE: HOR. 1" = 20', VERT. 1" = 2'



**PROFILE ALONG EMERGENCY SPILLWAY**  
SCALE: HOR. 1" = 20', VERT. 1" = 2'



**PROFILE ALONG C OF DAM**  
SCALE: HOR. 1" = 20', VERT. 1" = 2'

APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

*[Signatures]*  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION  
 CHIEF, DIVISION OF LAND DEVELOPMENT  
 DIRECTOR




**ENGINEER'S CERTIFICATE**  
 "I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION."  
 Signature: *[Signature]* DATE: 11-10-04  
 KERRY B. REXROAD, P.E.

**DEVELOPER'S CERTIFICATE**  
 "I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT."  
 Signature: *[Signature]* DATE: 11-29-04  
 Howard & Saltzman

THIS PLAN HAS BEEN REVIEWED FOR HOWARD SOIL CONSERVATION DISTRICT AND MEETS TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.  
 Signature: *[Signature]* DATE: 12/12/04  
 USDA - NATURAL RESOURCES CONSERVATION SERVICE

THIS PLAN FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.  
 Signature: *[Signature]* DATE: 12/12/04  
 HOWARD SOIL CONSERVATION DISTRICT

DATE: \_\_\_\_\_  
 NO. REVISIONS DESCRIPTION: \_\_\_\_\_  
 ENGINEERS: \_\_\_\_\_  
 PLANNERS: \_\_\_\_\_  
 SCIENTISTS: \_\_\_\_\_  
 CONSTRUCTION MANAGERS: \_\_\_\_\_  
 TECHNOLOGIES www.kci.com  
 KCI  
 CHERRY TREE FARM SECTION 1 AREA 2 OPEN SPACE LOT 170  
 STREAM RESTORATION  
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
 STORMWATER MANAGEMENT DIVISION  
 6751 COLUMBIA GATEWAY DRIVE  
 COLUMBIA, MARYLAND 21046  
 POND A PLAN, PROFILES, AND DETAILS  
 SCALE: AS SHOWN  
 DATE: 11-08-04  
 KCI JOB NO.: 01-01128.c  
 CAPITAL PROJECT NO.: D-1132 (PONDS) D-1128 (STREAM)  
 PERMIT ISSUE:  
 CONSTRUCTION ISSUE:  
 SW1  
 SHEET NO.: 23 OF 36  
 SDP-04-123




PLAN VIEW - POND B  
SCALE: 1" = 20'

PROFILE ALONG  $\phi$  OF DAM  
SCALE: HOR. 1" = 20', VERT. 1" = 2'

PROFILE ALONG PRINCIPAL SPILLWAY  
SCALE: HOR. 1" = 20', VERT. 1" = 2'


DESIGN STORM	FACILITY INFLOW (cfs)	FACILITY OUTFLOW (cfs)	STAGE	STORAGE VOLUME AC. FT.
1-Year	3.1	1.5	364.99	0.15
2-Year	12.1	8.3	365.40	0.19
5-Year	30.0	26.1	366.02	0.27
10-Year	46.5	43.5	366.68	0.36
100-Year	83.2	82.7	367.11	0.43

POINT	COORDINATES	
	NORTH	EAST
①	536472.01	1341543.83
②	536460.04	1341514.10
③	536452.16	1341473.88
④	536452.49	1341446.92
⑤	536412.58	1341502.03
⑥	536504.37	1341484.06
⑦	536578.85	1341473.55
⑧	536609.46	1341467.25



ARTICULATED CONCRETE BLOCK NOTES

- SEE SHEET SW5 FOR ARTICULATED CONCRETE BLOCK DETAILS AND SHEET SW6 FOR ARTICULATED CONCRETE BLOCK NOTES.
- ARTICULATED CONCRETE BLOCKS ARE TO BE HAND PLACED WITHIN THE LIMITS SHOWN ON THIS PLAN. CABLES ARE TO BE SET AFTER BLOCKS ARE PLACED.
- ARTICULATED CONCRETE BLOCKS ARE TO BE PLACED DIRECTLY ON GEOTEXTILE FABRIC (MIRAFIW500 MONOFILAMENT GEOTEXTILE).
- GROUT SEAMS ARE NOT REQUIRED BUT MAY BE USED AS SHOWN ON SHEET SW5.



STRUCTURE TYPE: DRY EXTENDED DETENTION POND  
SURFACE AREA: 0.19 AC.  
STRUCTURE HAZARD CLASSIFICATION: "A"  
STORAGE-HEIGHT PRODUCT: 1.32  
WATERSHED AREA TO FACILITY (ACRES): 16.80  
THIS FACILITY SHALL BE PUBLICLY MAINTAINED BY HOWARD COUNTY.

WATERSHED: CHERRY CREEK  
STREAM CLASS: I  
FREEBOARD: 1.39 FT.  
WATER QUALITY: N/A  
LEVEL OF MANAGEMENT PROVIDED BY FACILITY: 1-YEAR (QUANTITY)

APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

*Michael DeLuca* 12/17/04  
CHIEF, DEVELOPMENT ENGINEERING DIVISION

*Cindy Hanisch* 12/16/04  
CHIEF, DIVISION OF LAND DEVELOPMENT

*Barbara Lelland* 12/27/04  
DIRECTOR OF ACTIVITIES

ENGINEER'S CERTIFICATE

"I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION."

*Kerry B. Rexroad, P.E.* 11-10-04  
SIGNATURE OF ENGINEER (PRINT NAME BELOW SIGNATURE)  
KERRY B. REXROAD, P.E.

DEVELOPER'S CERTIFICATE

"I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I/WE ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I/WE ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT."

*Howard E. Saltzman* 11-24-04  
SIGNATURE OF DEVELOPER (PRINT NAME BELOW SIGNATURE)  
Howard E. Saltzman

THIS PLAN HAS BEEN REVIEWED FOR HOWARD SOIL CONSERVATION DISTRICT AND MEETS TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.

*Jim Moore, P.E.* 12/13/04  
USDA - NATURAL RESOURCES CONSERVATION SERVICE

THIS PLAN FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

*Howard E. Saltzman* 12/13/04  
HOWARD SOIL CONSERVATION DISTRICT

NO.	REVISIONS DESCRIPTION	DATE

ENGINEERS  
PLANNERS  
SCIENTISTS  
CONSTRUCTION MANAGERS

**KCI**  
TECHNOLOGIES www.kci.com

KC FILE: M:\2001\010128\Drawings\swm02.dgn



CHERRY TREE FARM  
SECTION 1, AREA 2,  
OPEN SPACE, LOT 170  
STREAM RESTORATION  
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
STORMWATER MANAGEMENT DIVISION  
6700 COLUMBIA UNIVERSITY DRIVE  
COLUMBIA, MISSOURI 65206

POND B PLAN,  
PROFILES, AND  
DETAILS


SCALE:	AS SHOWN
DATE:	11-08-04
KCI JOB NO.:	01-01128.c
CAPITAL PROJECT NO.:	D-1132 (PONDS) D-1128 (STREAM)
PERMIT ISSUE:	
CONSTRUCTION ISSUE:	

**SW 2**

SHEET NO.: 24 OF 36









NOTES:  
 1. INSTALL PYRAMAT (OR EQUAL) TURF REINFORCEMENT MAT (OR EQUAL) AND SOIL FILL.  
 2. SECURE LONGITUDINAL ANCHOR TRENCH AT 1 FT INTERVALS O/C. BACKFILL AND COMPACT SOIL.

**LONGITUDINAL ANCHOR TRENCH**  
NOT TO SCALE




NOTE:  
 1. SECURE AT 1 FT INTERVALS O/C. BACKFILL AND COMPACT SOIL.

**INTERMITTENT CHECK SLOT DETAIL**  
NOT TO SCALE




NOTE:  
 1. SECURE AT 1 FT INTERVALS O/C. BACKFILL AND COMPACT SOIL.

**TERMINAL CHANNEL ANCHOR TRENCH DETAIL**  
NOT TO SCALE



NOTE:  
 1. SECURE AT 1 FT INTERVALS O/C. BACKFILL AND COMPACT SOIL.

**INITIAL ANCHOR TRENCH DETAIL**  
NOT TO SCALE



NOTES:  
 1. PLACE 2 1/2 ANCHORS / SY FOR CHANNELS.  
 2. 12" METAL PINS SHALL BE USED TO ANCHOR TURF REINFORCEMENT MATS TO THE GROUND SURFACE.

**ANCHOR PATTERN FOR CHANNELS**  
NOT TO SCALE

**INSTALLATION GUIDELINES**

**SITE PREPARATION**

1. GRADE AND COMPACT AREA OF INSTALLATION.
2. PREPARE SEEDBED BY LOOSENING 2-3 INCHES OF TOPSOIL ABOVE FINAL GRADE.
3. INCORPORATE AMENDMENTS SUCH AS LIME AND FERTILIZER INTO SOIL.
4. REMOVE ALL ROCKS, CLDS, VEGETATION OR OTHER OBSTRUCTIONS SO THAT THE INSTALLED PYRAMAT WILL HAVE DIRECT CONTACT WITH SOIL SURFACE.
5. DO NOT MULCH AREAS WHERE MAT IS TO BE PLACED.

**SEEDING**

1. APPLY SEED TO THE SOIL SURFACE BEFORE INSTALLING PYRAMAT OR AFTER INSTALLATION FOR ENHANCED PERFORMANCE PRIOR TO SOIL FILLING (PREFERABLE).
2. WHEN SEEDING PRIOR TO PYRAMAT INSTALLATION, ALL CHECK SLOTS AND OTHER AREAS DISTURBED MUST ALSO BE RE-SEED.
3. SEED PYRAMAT AND ENTIRE DISTURBED AREA AFTER INSTALLATION, PRIOR TO FILLING MAT WITH SOIL.

**PYRAMAT PLACEMENT FOR CHANNELS**

1. EXCAVATE AN INITIAL ANCHOR TRENCH (SEE DETAIL THIS SHEET) 12 INCHES DEEP AND 6 INCHES WIDE ACROSS THE CHANNEL AT THE LOWER END OF THE PROJECT AREA.
2. EXCAVATE INTERMITTENT CHECK SLOTS (SEE DETAIL THIS SHEET) 6 INCHES DEEP AND 6 INCHES WIDE ACROSS THE CHANNEL AT 30 FOOT INTERVALS ALONG THE CHANNEL.
3. CUT LONGITUDINAL CHANNEL ANCHOR SLOTS (SEE DETAIL THIS SHEET) 4 INCHES DEEP AND 4 INCHES WIDE ALONG BOTH SIDES OF THE INSTALLATION TO BURY EDGES OF PYRAMAT. WHENEVER POSSIBLE, EXTEND MAT 2-3 FEET ABOVE CREST OF CHANNEL SIDE SLOPES.
4. BEGINNING AT THE CENTER OF DOWNSTREAM END OF CHANNEL, PLACE THE END OF THE FIRST ROLL IN THE ANCHOR TRENCH AND SECURE WITH FASTENING DEVICES AT 1 FOOT INTERVALS.
5. IN SAME MANNER, POSITION ADJACENT ROLLS IN ANCHOR TRENCH, OVERLAPPING THE PRECEDING ROLL A MINIMUM OF 3 INCHES.
6. AGAIN, SECURE AT 1 FOOT INTERVALS, BACKFILL, AND COMPACT SOIL.
7. UNROLL PYRAMAT OVER THE COMPACTED TRENCH. STOP AT NEXT CHECK SLOT OR TERMINAL ANCHOR SLOT.
8. UNROLL ADJACENT ROLLS UPSTREAM TO MAINTAIN A 3 INCH OVERLAP AND ANCHORING EVERY 18 INCHES.
9. FOLD AND SECURE ALL PYRAMAT ROLLS SNUGLY INTO INTERMITTENT CHECK SLOTS. LAY PYRAMAT IN THE BOTTOM AND FOLD BACK AGAINST ITSELF. ANCHOR THROUGH BOTH LAYERS OF MAT AT 1 FOOT INTERVALS, THEN BACKFILL AND COMPACT SOIL. CONTINUE ROLLING PYRAMAT UPSTREAM OVER THE COMPACTED SLOT TO THE NEXT CHECK SLOT OR TERMINAL ANCHOR TRENCH.
10. OVERLAP ROLL ENDS A MINIMUM OF 1 FOOT WITH UPSTREAM PYRAMAT ON TOP. BEGIN ALL NEW ROLLS IN A CHECK SLOT. ANCHOR OVERLAPPED AREA BY PLACING TWO ROWS OF ANCHORS, 1 FOOT APART ON 1 FOOT INTERVALS.
11. PLACE OUTER EDGE OF PYRAMAT IN PREVIOUSLY EXCAVATED LONGITUDINAL SLOTS. ANCHOR USING PRESCRIBED STAPLE PATTERN, BACKFILL AND COMPACT SOIL.
12. ANCHOR BACKFILL AND COMPACT UPSTREAM END OF PYRAMAT IN A 12 X 6 INCH TERMINAL TRENCH.
13. SECURE PYRAMAT TO GROUND SURFACE USING 12" METAL PINS.
14. SEE ANCHOR PATTERN DETAIL THIS SHEET FOR APPROPRIATE NUMBER AND PATTERN OF ANCHORS.
15. SEED AND FILL PYRAMAT WITH SOIL.

**GROUND ANCHORING DEVICES**

12" METAL PINS SHALL BE USED TO ANCHOR PYRAMAT TO THE GROUND SURFACE. METAL PINS SHOULD BE AT LEAST 3/16 INCH DIAMETER STEEL WITH A 1 1/2 INCH STEEL WASHER AT THE HEAD OF THE PIN. METAL PINS SHOULD BE DRIVEN FLUSH TO THE SOIL SURFACE AND HAVE SUFFICIENT GROUND PENETRATION TO RESIST PULLOUT.

**TURF REINFORCEMENT MATTING DETAILS AND NOTES**

APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

*Madhusudan*  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION  
 DATE: 12/17/04

*Carole Hamilton*  
 CHIEF, DIVISION OF LAND DEVELOPMENT  
 DATE: 12/17/04

*Dirck Walker*  
 DIRECTOR (ACTING)  
 DATE: 12/21/04

**ENGINEER'S CERTIFICATE**

"I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION."

SIGNATURE OF ENGINEER (PRINT NAME BELOW SIGNATURE) *Kerry B. Rexroad, P.E.* DATE: 11-10-04

**DEVELOPER'S CERTIFICATE**

"I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT."


SIGNATURE OF DEVELOPER (PRINT NAME BELOW SIGNATURE) *Howard E. Saltzman* DATE: 11-24-04

THIS PLAN HAS BEEN REVIEWED FOR HOWARD SOIL CONSERVATION DISTRICT AND MEETS TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.

USDA - NATURAL RESOURCES CONSERVATION SERVICE *Jim Mays* DATE: 12/13/04

THIS PLAN FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.


HOWARD SOIL CONSERVATION DISTRICT *John Saltzman* DATE: 12/13/04



NOTE: ON INSIDE POND SLOPE, TOE ONLY ONE BLOCK INTO GROUND.


COPYRIGHT © ARMORTEC 2001 ALL RIGHTS RESERVED.

TITLE: ARMORFLEX STANDARD DETAIL	PREPARED BY: ARMORTEC
DESCRIPTION: MAT ANCHORED TO WALL	DATE: 1-11-00
TOE OF SLOPE DETAIL	SCALE: 1"=1'-0"
	DATE: 11-15-00




COPYRIGHT © ARMORTEC 2002 ALL RIGHTS RESERVED.

TITLE: ARMORFLEX STANDARD DETAIL	PREPARED BY: ARMORTEC
DESCRIPTION: MAT ANCHORED TO WALL	DATE: 1-14-00
	SCALE: 1"=1'-0"
	DATE: N.T.S.




COPYRIGHT © ARMORTEC 2001 ALL RIGHTS RESERVED.

TITLE: ARMORFLEX STANDARD DETAIL	PREPARED BY: ARMORTEC
DESCRIPTION: ARMORFLEX 5-CLASS OPEN BLOCK	DATE: 1-12-00
	SCALE: 1"=1'-0"
	DATE: N.T.S.




COPYRIGHT © ARMORTEC 2001 ALL RIGHTS RESERVED.

TITLE: ARMORFLEX STANDARD DETAIL	PREPARED BY: ARMORTEC
DESCRIPTION: GROUT SEAM BETWEEN MATS	DATE: 1-11-00
	SCALE: 1"=1'-0"
	DATE: N.T.S.



COPYRIGHT © ARMORTEC 2002 ALL RIGHTS RESERVED.

TITLE: ARMORFLEX CHANNEL DETAIL	PREPARED BY: ARMORTEC
DESCRIPTION: CHANNEL CHANNEL WITH ARMORFLEX LINING	DATE: 1-11-00
	SCALE: 1"=1'-0"
	DATE: N.T.S.



COPYRIGHT © ARMORTEC 2001 ALL RIGHTS RESERVED.

TITLE: ARMORFLEX STANDARD DETAIL	PREPARED BY: ARMORTEC
DESCRIPTION: GENERAL OPEN 5-CLASS MAT	DATE: 1-11-00
	SCALE: 1"=1'-0"
	DATE: N.T.S.

**ARTICULATED CONCRETE BLOCK DETAILS**

NO.	REVISIONS DESCRIPTION	DATE

ENGINEERS  
 PLANNERS  
 SCIENTISTS  
 CONSTRUCTION MANAGERS

www.kci.com



CHERRY TREE FARM  
 SECTION 1, AREA 2,  
 OPEN SPACE LOT 170  
 STREAM RESTORATION  
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  
 STORMWATER MANAGEMENT DIVISION  
 6751 COLUMBIA GATEWAY DRIVE  
 COLUMBIA, MARYLAND 21046

STORMWATER  
 MANAGEMENT  
 DETAILS

SCALE: N/A  
 DATE: 11-08-04  
 KCI JOB NO.: 01-01128.c  
 CAPITAL PROJECT NO.: D-1132 (PONDS)  
 D-1128 (STREAM)  
 PERMIT ISSUE:  
 CONSTRUCTION ISSUE:

**SW5**  
 SHEET NO. 27 OF 36  
 SDP-04-123

PLOTTED: 01:50 PM on Monday, November 08, 2004  
 Plot File: S:\pds\div\01128\c\swm5.dgn  
 PLOT: 11/08/04 01:50 PM

SWM POND CONSTRUCTION SPECIFICATIONS (MARYLAND CODE 378 POND - JANUARY 2000)

THESE SPECIFICATIONS ARE APPROPRIATE TO ALL PONDS WITHIN THE SCOPE OF THE STANDARD FOR PRACTICE MD-378. ALL REFERENCES TO ASTM AND AASHTO SPECIFICATIONS APPLY TO THE MOST RECENT VERSIONS.

SITE PREPARATION

AREAS DESIGNATED FOR BORROW AREAS, EMBANKMENT, AND STRUCTURAL WORKS SHALL BE CLEARED, GRUBBED AND STRIPPED OF TOPSOIL. ALL TREES, VEGETATION, ROOTS AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED. CHANNEL BANKS AND SHARP BREAKS SHALL BE SLOPED TO NO STEEPER THAN 1:1. ALL TREES SHALL BE CLEARED AND GRUBBED WITHIN 15 FEET OF THE TOE OF THE EMBANKMENT.

AREAS TO BE COVERED BY THE RESERVOIR WILL BE CLEARED OF ALL TREES, BRUSH, LOGS, FENCES, RUBBISH AND OTHER OBJECTIONABLE MATERIAL UNLESS OTHERWISE DESIGNATED ON THE PLANS. TREES, BRUSH, AND STUMPS SHALL BE CUT APPROXIMATELY LEVEL WITH THE GROUND SURFACE FOR STORMWATER MANAGEMENT PONDS. A MINIMUM OF A 25-FOOT RADIIUS AROUND THE INLET STRUCTURE SHALL BE CLEARED.

ALL CLEARED AND GRUBBED MATERIAL SHALL BE DISPOSED OF OUTSIDE AND BELOW THE LIMITS OF THE DAM AND RESERVOIR AS DIRECTED BY THE OWNER OR HIS REPRESENTATIVE. WHEN SPECIFIED, A SUFFICIENT QUANTITY OF TOPSOIL WILL BE STOCKPILED IN A SUITABLE LOCATION FOR USE ON THE EMBANKMENT AND OTHER DESIGNATED AREAS.

EARTH FILL

MATERIAL - THE FILL MATERIAL SHALL BE TAKEN FROM APPROVED DESIGNATED BORROW AREAS. IT SHALL BE FREE OF ROOTS, STUMPS, WOOD, RUBBISH, STONES, GREATER THAN 6" FROZEN OR OTHER OBJECTIONABLE MATERIAL. FILL CONFORM TO THE CENTER OF THE EMBANKMENT, AND CUTOFF TRENCH SHALL CONFORM TO UNIFIED SOIL CLASSIFICATION SO, SC, CH, OR CL, AND MUST HAVE AT LEAST 30% PASSING THE #200 SIEVE. CONSIDERATION MAY BE GIVEN TO THE USE OF OTHER MATERIALS IN THE EMBANKMENT IF DESIGNED BY A GEOTECHNICAL ENGINEER. SUCH SPECIFIC DESIGNS MUST HAVE CONSTRUCTION SUPERVISED BY A GEOTECHNICAL ENGINEER. MATERIALS USED IN THE OUTER SHELL OF THE EMBANKMENT MUST HAVE THE CAPABILITY TO SUPPORT VEGETATION OF THE QUALITY REQUIRED TO PREVENT EROSION OF THE EMBANKMENT.

PLACEMENT - AREAS ON WHICH FILL IS TO BE PLACED SHALL BE SCARIFIED PRIOR TO PLACEMENT OF FILL. FILL MATERIALS SHALL BE PLACED IN MAXIMUM 8 INCH THICK (OR FORTHER COMPACTED) LAYERS WHICH ARE TO BE CONTINUOUS OVER THE ENTIRE LENGTH OF THE FILL. THE MOST PERMEABLE BORROW MATERIAL SHALL BE PLACED IN THE DOWNSTREAM PORTIONS OF THE EMBANKMENT. THE PRINCIPAL SPILLWAY MUST BE INSTALLED CONCURRENTLY WITH FILL PLACEMENT AND NOT EXCAVATED INTO THE EMBANKMENT.

COMPACTION - THE MOVEMENT OF THE HAULING AND SPREADING EQUIPMENT OVER THE FILL SHALL BE CONTROLLED SO THAT THE ENTIRE SURFACE OF EACH LIFT SHALL BE TRAVERSED BY NOT LESS THAN ONE TREAD TRACK OF HEAVY EQUIPMENT OR COMPACTION SHALL BE ACHIEVED BY A MINIMUM OF FOUR COMPLETE PASSES OF A SHEEPSFOOT, RUBBER Tired OR VIBRATORY ROLLER. FILL MATERIAL SHALL CONTAIN SUFFICIENT MOISTURE SUCH THAT THE REQUIRED DEGREE OF COMPACTION WILL BE OBTAINED. IF TOPSOIL IS USED, THE FILL MATERIAL SHALL CONTAIN SUFFICIENT MOISTURE SO THAT IF FORMED INTO A BALL IT WILL NOT CRUMBLE, YET NOT BE SO WET THAT WATER CAN BE SQUEEZED OUT.

WHEN REQUIRED BY THE REVIEWING AGENCY THE MINIMUM REQUIRED DENSITY SHALL NOT BE LESS THAN 95% OF MAXIMUM DRY DENSITY WITH A MOISTURE CONTENT WITHIN +/- 2% OF THE OPTIMUM. EACH LAYER OF FILL SHALL BE COMPACTED AS NECESSARY TO OBTAIN THAT DENSITY, AND IS TO BE CERTIFIED BY THE ENGINEER AT THE TIME OF CONSTRUCTION. ALL COMPACTION IS TO BE ACCORDING TO THE STANDARD TEST METHOD (ASTM D 1557).

CUT OFF TRENCH - THE CUTOFF TRENCH SHALL BE EXCAVATED INTO IMPERVIOUS MATERIAL ALONG OR PARALLEL TO THE CENTERLINE OF THE EMBANKMENT AS SHOWN ON THE PLANS. THE BOTTOM WIDTH OF THE TRENCH SHALL BE GOVERNED BY THE EQUIPMENT USED FOR EXCAVATION WITH THE MINIMUM WIDTH OF 18 INCHES. THE TRENCH SHALL BE AT LEAST FOUR FEET BELOW EXISTING GRADE OR AS SHOWN ON THE PLANS. THE SIDE SLOPES OF THE TRENCH SHALL BE 1 TO 1 FLATTER. THE BACKFILL SHALL BE COMPACTED WITH CONSTRUCTION EQUIPMENT. ROLLERS OR HAND TAMPERS TO ASSURE MAXIMUM DENSITY AND MINIMUM PERMEABILITY.

EMBANKMENT CORE - THE CORE SHALL BE PARALLEL TO THE CENTERLINE OF THE EMBANKMENT AS SHOWN ON THE PLANS. THE TOP WIDTH OF THE CORE SHALL BE A MINIMUM OF FOUR FEET. THE HEIGHT SHALL EXTEND UP TO AT LEAST THE 10 YEAR WATER ELEVATION OR AS SHOWN ON THE PLANS. THE SIDE SLOPES SHALL BE 1 TO 1 FLATTER. THE CORE SHALL BE COMPACTED WITH CONSTRUCTION EQUIPMENT. ROLLERS OR HAND TAMPERS TO ASSURE MAXIMUM PERMEABILITY. IN ADDITION THE CORE SHALL BE PLACED CONCURRENTLY WITH THE OUTER SHELL OF THE EMBANKMENT.

STRUCTURE BACKFILL

BACKFILL ADJACENT TO PIPES OR STRUCTURES SHALL BE OF THE TYPE AND QUALITY CONFORMING TO THAT SPECIFIED FOR THE ADJOINING FILL MATERIAL. THE FILL SHALL BE PLACED IN HORIZONTAL LAYERS NOT TO EXCEED FOUR INCHES IN THICKNESS AND COMPACTED BY HAND TAMPERS OR OTHER MANUALLY DIRECTED COMPACTION EQUIPMENT. THE MATERIAL NEEDS TO FILL COMPLETELY ALL SPACES UNDER AND ADJACENT TO THE STRUCTURE. THE BACKFILL SHALL BE COMPACTED WITH CONSTRUCTION EQUIPMENT. ROLLERS OR HAND TAMPERS TO ASSURE MAXIMUM PERMEABILITY. IN ADDITION THE CORE SHALL BE PLACED CONCURRENTLY WITH THE OUTER SHELL OF THE EMBANKMENT.

STRUCTURE BACKFILL MAY BE FLOWABLE FILL MEETING THE REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION, STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATION FOR CONSTRUCTION AND MATERIALS, SECTION 315 AS MODIFIED. THE MIXTURE SHALL HAVE A 100-200 PSI 28 DAY UNCONFINED COMPRESSIVE STRENGTH. THE FLOWABLE FILL SHALL HAVE A MINIMUM PH OF 4.0 AND A MINIMUM RESISTIVITY OF 2,000 OHM-CM. MATERIAL SHALL BE PLACED SUCH THAT A MINIMUM OF 6" MEASURED PERPENDICULAR TO THE OUTSIDE OF THE PIPE) OF FLOWABLE FILL SHALL BE UNDER (BEDDING) OVER AND ON THE SIDES OF THE PIPE. IT ONLY NEEDS TO EXTEND UP TO THE SPRING LINE FOR RIGID CONDUITS. AVERAGE SLUMP OF THE FILL SHALL BE 7" TO ASSURE FLOWABILITY OF THE MATERIAL. ADEQUATE MEASURES SHALL BE TAKEN (SAND BAGS, ETC.) TO PREVENT FLOATING THE PIPE. WHEN USING FLOWABLE FILL, ALL METAL PIPE SHALL BE BITUMINOUS COATED. ANY ADJOINING SOIL FILL SHALL BE PLACED IN HORIZONTAL LAYERS NOT TO EXCEED FOUR INCHES IN THICKNESS AND COMPACTED BY HAND TAMPERS OR OTHER MANUALLY DIRECTED COMPACTION EQUIPMENT. THE MATERIAL SHALL COMPLETELY FILL ALL VOIDS ADJACENT TO THE FLOWABLE FILL ZONE. AT NO TIME DURING THE BACKFILLING OPERATION SHALL DRIVEN EQUIPMENT BE ALLOWED TO OPERATE CLOSER THAN FOUR FEET, MEASURED HORIZONTALLY, TO ANY PART OF A STRUCTURE. UNDER NO CIRCUMSTANCES SHALL EQUIPMENT BE DRIVEN OVER ANY PART OF A STRUCTURE OR PIPE UNLESS THERE IS A COMPACTED FILL OF 24" OR GREATER OVER THE STRUCTURE OR PIPE. BACKFILL MATERIAL OUTSIDE THE STRUCTURE BACKFILL (FLOWABLE FILL) ZONE SHALL BE OF THE TYPE AND QUALITY CONFORMING TO THAT SPECIFIED FOR THE CORE OF THE EMBANKMENT OR OTHER EMBANKMENT MATERIALS.

PIPE CONDUITS

ALL PIPES SHALL BE CIRCULAR IN CROSS SECTION. CORRUGATED METAL PIPE - ALL OF THE FOLLOWING CRITERIA SHALL APPLY FOR CORRUGATED METAL PIPE:  
1. MATERIALS - (POLYMER COATED STEEL PIPE) - STEEL PIPES WITH POLYMERIC COATINGS SHALL HAVE A MINIMUM COATING THICKNESS OF 0.01 INCH (1 MIL) ON BOTH SIDES OF THE PIPE. THIS PIPE AND ITS APPURTENANCES SHALL CONFORM TO THE REQUIREMENTS OF AASHTO SPECIFICATIONS M-245 AND M-246 WITH WATER TIGHT COUPLING BANDS OR FLANGES.

MATERIALS - (ALUMINUM COATED STEEL PIPE) - THIS PIPE AND ITS APPURTENANCES SHALL CONFORM TO THE REQUIREMENTS OF AASHTO SPECIFICATION ON M-274 WITH WATER TIGHT COUPLING BANDS OR FLANGES. ALUMINUM COATED STEEL PIPE, WHEN USED WITH FLOWABLE FILL OR WHEN SOIL AND/OR WATER CONDITIONS WARRANT FOR INCREASED DURABILITY, SHALL BE FULLY BITUMINOUS COATED. REQUIREMENTS FOR DURABILITY SHALL BE FULLY BITUMINOUS COATED. ANY ALUMINUM COATING DAMAGED OR OTHERWISE REMOVED SHALL BE REPLACED WITH WILD APPLIED BITUMINOUS COATING COMPOUND. ALUMINUM SURFACES THAT ARE TO BE IN CONTACT WITH CONCRETE SHALL BE PAINTED WITH ONE COAT OF ZINC CHROMATE PRIMER OR TWO COATS OF ASPHALT.

APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

*Michael Daneman*  
CHIEF, DEVELOPMENT ENGINEERING DIVISION

*Stephen Hanitsch*  
CHIEF, DIVISION OF LAND DEVELOPMENT

*Stephen Lefkowitz*  
DIRECTOR (Acting)

12/17/04

12/24/04

12/22/04

STABILIZATION

ALL BORROW AREAS SHALL BE GRADED TO PROVIDE PROPER DRAINAGE AND LEFT IN A SLIGHTLY CONCAVE. ALL EXPOSED SURFACES OF THE EMBANKMENT, SPILLWAY, SOIL AND BORROW AREAS, AND BERMS SHALL BE STABILIZED BY SEEDING, LIMING, FERTILIZING AND MULCHING IN ACCORDANCE WITH THE NATURAL RESOURCES CONSERVATION SERVICE STANDARDS AND SPECIFICATIONS FOR CRITICAL AREA PLANTING (MD-242) OR AS SHOWN ON THE ACCOMPANYING DRAWINGS.

EROSION AND SEDIMENT CONTROL

CONSTRUCTION OPERATIONS WILL BE CARRIED OUT IN SUCH A MANNER THAT EROSION WILL BE CONTROLLED AND WATER AND AIR POLLUTION MINIMIZED. STATE AND LOCAL LAWS CONCERNING POLLUTION ABATEMENT WILL BE FOLLOWED. CONSTRUCTION PLANS SHALL DETAIL EROSION AND SEDIMENT CONTROL MEASURES.

FENCE AND GATE (142-INCH HEIGHT)

CONSTRUCT FENCING IN ACCORDANCE WITH THE STATE HIGHWAY ADMINISTRATION STANDARD DETAILS 690.01 AND 690.02. USE SPECIFICATIONS FOR A 6-FOOT FENCE, SUBSTITUTING 42-INCH FABRIC AND 6-FOOT 8-INCH LINE POSTS. CONSTRUCT THE GATE IN ACCORDANCE WITH STATE HIGHWAY ADMINISTRATION STANDARD DETAIL 692.01 WITH 42-INCH FABRIC. THE FABRIC USED FOR THE FENCE AND GATE MUST CONFORM TO AASHTO DESIGNATION M8174.

FILTER CLOTH

FILTER CLOTH SHALL BE MIRAFL1405, DUPONT TYPAR #3341 OR APPROVED EQUAL.

GARBONS

ALL GARBONS SHALL BE CLASS IV PVC COATED.

WOODY VEGETATION NOTE

TREES, SHRUBS, OR OTHER WOODY VEGETATION WILL NOT BE ALLOWED WITHIN A 25' RADIUS OF THE INLET STRUCTURE IN THE POOL AREA, AND NOT ALLOWED ON, OR WITHIN 15' OF ANY PORTION OF THE EMBANKMENT.

CONSULTANT'S HAZARD CLASS CERTIFICATION (PONDS A, B, AND C)

"I CERTIFY THAT THIS POND MEETS ALL REQUIREMENTS FOR HAZARD CLASS (A, B, OR C). REQUIREMENTS AS STATED IN THE USDA NATURAL RESOURCES CONSERVATION SERVICE - MARYLAND CONSERVATION PRACTICE STANDARD FOR POND, CODE 378, JANUARY 2000. ALL NECESSARY INVESTIGATIONS AND COMPUTATIONS HAVE BEEN PERFORMED TO VERIFY THIS FINDING. A COPY OF SAID INFORMATION HAS BEEN SUPPLIED TO N.R.C.S./H.C.S.C.P."

SIGNATURE: *Kerry B. Rexroad* DATE: 11-10-04  
PRINT NAME: Kerry B. Rexroad MD LICENSE NO. 18 470

CONTRACTOR'S NOTE

THE CONSTRUCTION SHOWN HEREON MUST BE CERTIFIED TO THE HOWARD COUNTY SOIL CONSERVATION DISTRICT. CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE MD STANDARD AND SPECIFICATION FOR PONDS (CODE 378) AND THE SET OF STANDARD DRAWINGS FOR POND CONSTRUCTION. A REGISTERED PROFESSIONAL ENGINEER MUST BE NOTIFIED SUFFICIENTLY IN ADVANCE OF CONSTRUCTION SO THAT HE CAN ARRANGE FOR:  
1. INSPECTION OF THE PIPE, TRENCH, BEDDING, AND CONCRETE RISER.  
2. SUPERVISION OF EMBANKMENT CONSTRUCTION AND COMPACTION TESTING.  
3. COMPLETION OF AS-BUILT SURVEY AND STUDY AT TIME OF CONVERSION TO STORM WATER MANAGEMENT AND SUBMIT TO APPROPRIATE AGENCIES WITHIN 30 DAYS AFTER COMPLETION.

SEQUENCE OF CONSTRUCTION

SEE SHEET ESB FOR DETAILED SEQUENCE OF CONSTRUCTION.

CONSTRUCTION NOTE:

- UNLESS OTHERWISE NOTED, ALL CONSTRUCTION AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH:
- 1. HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS STANDARD SPECIFICATIONS AND DETAILS FOR CONSTRUCTION IV, OCTOBER, 1990, ERRATA & ADDENDA.
- 2. SOIL CONSERVATION SERVICE OF MARYLAND STANDARDS AND SPECIFICATIONS, POND, CODE 378, JANUARY, 2000.
- 3. MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION, JANUARY, 2001, STANDARD SPECIFICATION FOR CONSTRUCTION AND MATERIAL.

GENERAL NOTES

- 1. UTILITIES AND TOPOGRAPHICAL FEATURES SHOWN ON THESE PLANS ARE ONLY FOR THE CONVENIENCE OF THE USER AND THERE IS NO WARRANTY OR GUARANTEE OF THE CORRECTNESS OR THE COMPLETENESS OF THE INFORMATION GIVEN. THE USER OF THESE DRAWINGS MUST VERIFY ALL SUCH INFORMATION TO HIS OWN SATISFACTION.
- 2. AS-BUILT PLANS & CERTIFICATION ARE REQUIRED FOR THE STORM WATER MANAGEMENT FACILITIES. THESE MUST BE PREPARED AND SEALED BY A REGISTERED PROFESSIONAL ENGINEER. HOWARD COUNTY WILL NOT PERFORM THE INSPECTION OR PREPARE THE AS-BUILT PLANS OR CERTIFICATION.
- 3. IN ORDER TO PREPARE THE REQUIRED AS-BUILT PLANS & CERTIFICATION, THIS STORM WATER MANAGEMENT FACILITY MUST BE INSPECTED BY THE ENGINEER AT SPECIFIC STAGES DURING CONSTRUCTION AS REQUIRED BY THE CURRENT HOWARD COUNTY STORM WATER MANAGEMENT POLICY AND DESIGN MANUAL. THE CONTRACTOR SHALL NOTIFY THE ENGINEER AT LEAST FIVE (5) WORKING DAYS PRIOR TO STARTING ANY WORK SHOWN ON THESE PLANS.

OPERATION AND MAINTENANCE SCHEDULE FOR EXTENDED DETENTION STORMWATER PONDS

ROUTINE MAINTENANCE:  
A. FACILITY SHALL BE INSPECTED ANNUALLY AND AFTER MAJOR STORMS. INSPECTIONS SHALL BE PERFORMED DURING WET WEATHER TO DETERMINE IF THE POND IS FUNCTIONING PROPERLY.  
B. TOP AND SIDE SLOPES OF THE EMBANKMENT SHALL BE MOWED A MINIMUM OF TWO (2) TIMES PER YEAR, ONCE IN JUNE AND ONCE IN SEPTEMBER. OTHER SIDE SLOPES AND MAINTENANCE ACCESS SHALL BE MOWED AS NEEDED.  
C. DEBRIS AND LITTER SHALL BE REMOVED DURING REGULAR MOWING OPERATIONS AND AS NEEDED.  
D. VISIBLE SIGNS OF EROSION IN THE POND AS WELL AS THE RIP-RAP OUTLET SHALL BE REPAIRED AS SOON AS IT IS NOTICED.

NON-ROUTINE MAINTENANCE:

- 1. STRUCTURAL COMPONENTS OF THE POND SUCH AS THE DAM, THE RISERS, AND THE PIPES SHALL BE REPAIRED UPON THE DETECTION OF ANY DAMAGE. THE COMPONENTS SHALL BE INSPECTED DURING ROUTINE MAINTENANCE OPERATIONS.
- 2. SEDIMENT SHALL BE REMOVED FROM THE POND NO DEEPER THAN WHEN THE CAPACITY OF THE POND IS HALF FULL OF SEDIMENT, OR WHEN DEEMED NECESSARY FOR AESTHETIC REASONS, UPON APPROVAL FROM THE DEPARTMENT OF PUBLIC WORKS.

ENGINEER'S CERTIFICATE

"I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL, REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD COUNTY SOIL CONSERVATION DISTRICT. I HAVE NOTICED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD COUNTY SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION."

SIGNATURE OF ENGINEER (PRINT NAME BELOW SIGNATURE): *Kerry B. Rexroad, P.E.* DATE: 11-10-04

DEVELOPER'S CERTIFICATE

"I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I/SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD COUNTY SOIL CONSERVATION DISTRICT WITHIN 30 DAYS OF COMPLETION. I/ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD COUNTY SOIL CONSERVATION DISTRICT."

SIGNATURE OF DEVELOPER (PRINT NAME BELOW SIGNATURE): *Howard E. Saiteman* DATE: 11-29-04

"AS-BUILT" CERTIFICATION-FACILITY "A"

HEREBY CERTIFY THAT THE FACILITY SHOWN ON THIS PLAN WAS CONSTRUCTED AS SHOWN ON THE "AS-BUILT" PLANS AND MEETS THE APPROVED PLANS AND SPECIFICATIONS.

SIGNATURE: \_\_\_\_\_ P.E.No. \_\_\_\_\_  
PRINT NAME: \_\_\_\_\_ DATE: \_\_\_\_\_

CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ON-SITE INSPECTIONS AND MATERIAL TESTS WHICH ARE CONDUCTED DURING CONSTRUCTION. THE ON-SITE INSPECTIONS AND MATERIAL TEST ARE THOSE INSPECTIONS AND TEST DEEMED SUFFICIENT AND APPROPRIATE BY COMMONLY ACCEPTED ENGINEERING STANDARDS. CERTIFY DOES NOT MEAN OR IMPLY A GUARANTEE BY THE ENGINEER NOR DOES AN ENGINEER'S CERTIFICATION RELIEVE ANY OTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING COMMONLY ACCEPTED PRACTICES.

"AS-BUILT" CERTIFICATION-FACILITY "B"

HEREBY CERTIFY THAT THE FACILITY SHOWN ON THIS PLAN WAS CONSTRUCTED AS SHOWN ON THE "AS-BUILT" PLANS AND MEETS THE APPROVED PLANS AND SPECIFICATIONS.

SIGNATURE: \_\_\_\_\_ P.E.No. \_\_\_\_\_  
PRINT NAME: \_\_\_\_\_ DATE: \_\_\_\_\_

CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ON-SITE INSPECTIONS AND MATERIAL TESTS WHICH ARE CONDUCTED DURING CONSTRUCTION. THE ON-SITE INSPECTIONS AND MATERIAL TEST ARE THOSE INSPECTIONS AND TEST DEEMED SUFFICIENT AND APPROPRIATE BY COMMONLY ACCEPTED ENGINEERING STANDARDS. CERTIFY DOES NOT MEAN OR IMPLY A GUARANTEE BY THE ENGINEER NOR DOES AN ENGINEER'S CERTIFICATION RELIEVE ANY OTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING COMMONLY ACCEPTED PRACTICES.

ARMORFLEX® CELLULAR CONCRETE MAT (OR APPROVED EQUAL) SPECIFICATION FOR OVERTOPPING APPLICATIONS

PART 1: GENERAL  
1. Manufacturer  
A. Scope of Work  
The Contractor shall furnish all labor, materials, equipment, and incidentals required and perform all operations in connection with the installation of cellular concrete erosion control mats in accordance with the lines, grades, design and dimensions shown on the Contract Drawings as specified herein.

PART 2: PRODUCTS  
A. General  
All cellular concrete mats shall be manufactured as an assembly of concrete blocks with specific hydraulic apertures, bound into place by the use of reentrant bolts. Cellular concrete mats may be assembled on-site by interlocking individual blocks with subsequent installation of reentrant bolts.

Individual blocks in the cellular mats shall be staggered and interlocked for enhanced stability. The open cell version of the blocks have two (2) vertical openings of rectangular cross section on each side that reduce the flexibility of the cellular mats or become damaged or broken when the mats are lifted during shipment or placement. Once the mats are in place, the interlocking surfaces prevent the lateral displacement of the blocks even if the joints should become damaged or broken. The mats shall be able to flex a minimum of 2 degrees between any given row or column of blocks in the uplift direction and a minimum of 45 degrees in the downwind direction.

The gross area of each individual block in direct contact with the protected substrate shall be no less than one square foot. Each block shall incorporate interlocking surfaces that prevent lateral displacement of the blocks within the mats when they are lifted by the longitudinal reentrant bolts. The interlocking surfaces must not protrude beyond the perimeter of the blocks to such an extent that they reduce the flexibility of the cellular mats or become damaged or broken when the mats are lifted during shipment or placement. Once the mats are in place, the interlocking surfaces prevent the lateral displacement of the blocks even if the joints should become damaged or broken. The mats shall be able to flex a minimum of 2 degrees between any given row or column of blocks in the uplift direction and a minimum of 45 degrees in the downwind direction.

The cellular concrete mats shall be placed in a filler fabric as specified herein. Under no circumstances shall the filler fabric be placed (i.e., chemically) bonded to the blocks to the matrix in a manner in which would jeopardize the functionality of the filler fabric. The functionality of the filler fabric shall be independent of the blocks.

B. Cellular Concrete Blocks  
1. Scope  
1.1 This specification covers concrete blocks for erosion control mats used in restraints, storm channels, etc. and for soil stabilization.  
Note 1 - Concrete units covered by this specification are made from lightweight or normal weight aggregates, or both.  
Note 2 - The values stated in U.S. customary units are to be regarded as the standard.

2. Materials  
2.1 Constituent Materials - Materials shall conform to the following applicable ASTM specifications:  
2.1.1 Portland Cements - Specification C 150, for Portland Cement.  
2.1.2 Blended Cements - Specification C 595, for Blended Hydraulic Cements.  
2.1.3 Hydrated Lime Types - Specification C 201, for Hydrated Lime Types.  
2.1.4 Pozzolans - Specification C 618, for Fly Ash and Raw or Calcined Natural Pozzolans for use in Portland Cement Mortar.  
2.2 Aggregates shall conform to the following ASTM specifications, except that grading requirements shall not exceed 10% 99.75.

2.2.1 Nominal Weight - Specification C 33, for Concrete Aggregates.  
3. Physical Requirements  
3.1 At the time of delivery to the work site, the units shall conform to the physical requirements prescribed in Table 1 below.

TABLE 1. PHYSICAL REQUIREMENTS

Compressive Strength (psi)	Water Absorption, % (100% dry)
Avg. of Individual Units	Avg. of Individual Units
4,000 (27.6)	3.50 (0.25)
10,000 (69.0)	1.00 (0.07)

3.2 Durability. The manufacturer shall satisfy the purchaser by proven field performance that the concrete units have adequate durability even if they are to be subjected to a freeze-thaw environment.  
3.3 Sample and test units in accordance with ASTM 688-04, Standard Specification for Materials and Methods of Testing Concrete Block (Masonry Units).

4. Visual Inspection  
4.1 All units shall be sound and free of defects that would interfere with the proper placing of the unit or impair the strength or performance of the construction. Surface cracks (independent of the usual methods of manufacture, or surface cracking resulting from customary methods of handling in shipment or delivery) shall not be deemed ground for rejection.  
4.2 Cracks exceeding 0.25 inches (6.35 mm) in width and/or 1.0 inch (25.4 mm) in depth shall be deemed ground for rejection.  
4.3 Chipping resulting in a weight loss exceeding 10% of the average weight of the blocks shall be deemed ground for rejection.

4.4 Blocks rejected prior to delivery from the point of manufacture shall be replaced at the manufacturer's expense. Blocks rejected at the job site shall be repaired with structural grout at the expense of the contractor.  
5. Sampling and Testing  
5.1 The purchaser or his authorized representative shall be accorded proper access to facilities to inspect and sample the units of the plant of manufacture from lots ready for delivery.

6. Impact of Tests  
Additional testing, other than that provided by the manufacturer, shall be borne by the purchaser.

"AS-BUILT" CERTIFICATION-FACILITY "C"

HEREBY CERTIFY THAT THE FACILITY SHOWN ON THIS PLAN WAS CONSTRUCTED AS SHOWN ON THE "AS-BUILT" PLANS AND MEETS THE APPROVED PLANS AND SPECIFICATIONS.

SIGNATURE: \_\_\_\_\_ P.E.No. \_\_\_\_\_  
PRINT NAME: \_\_\_\_\_ DATE: \_\_\_\_\_

CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ON-SITE INSPECTIONS AND MATERIAL TESTS WHICH ARE CONDUCTED DURING CONSTRUCTION. THE ON-SITE INSPECTIONS AND MATERIAL TEST ARE THOSE INSPECTIONS AND TEST DEEMED SUFFICIENT AND APPROPRIATE BY COMMONLY ACCEPTED ENGINEERING STANDARDS. CERTIFY DOES NOT MEAN OR IMPLY A GUARANTEE BY THE ENGINEER NOR DOES AN ENGINEER'S CERTIFICATION RELIEVE ANY OTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING COMMONLY ACCEPTED PRACTICES.

OPERATION, MAINTENANCE, AND INSPECTION

HOWARD COUNTY WILL OWN, OPERATE, AND MAINTAIN THE STORMWATER MANAGEMENT FACILITIES. INSPECTION OF THE PONDS SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, SCSS "STANDARDS AND SPECIFICATIONS FOR PONDS" (CODE 378). HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS AND ANY HEIRS, SUCCESSORS, OR ASSIGNEES SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND CONTINUED OPERATION, SURVEILLANCE, INSPECTION, AND MAINTENANCE THEREOF. HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING, OR SLUMPING.

Final acceptance of the filtration geotextile by the Engineer shall be dependent upon the filtration performance when tested in accordance with ASTM 6516, Standard Test Method for Measuring the Soil-Coefficient System (Geotextile) by the Gradient Ratio Test or the Hydraulic Conductivity Ratio Test. Soil characteristics such as grain size distribution and plasticity shall be determined for every 200,000 square feet of geotextile installed, or for each square of borrow material used during construction. Significant differences in soil characteristics shall require further performance testing by either the gradient ratio or the hydraulic conductivity ratio tests as specified in the contract documents. The location for such testing to be tested is established shall be approved by the Engineer. The contractor shall provide the site-specific soil and geotextile test results to the Engineer. The Engineer shall be responsible for the performance of the test by a certified independent laboratory experienced in performing such tests. The test shall be performed under the actual field soil conditions or as otherwise required by the Engineer.

At the time of installation, the filter fabric shall be rejected if it has been removed from its protective cover for over 72 hours or has defects, tears, punctures, flow deterioration, or damage greater than the slope specified in the contract drawings. The manufacturer or manufacturer's representative shall be responsible for the performance of the test by a certified independent laboratory experienced in performing such tests. The test shall be performed under the actual field soil conditions or as otherwise required by the Engineer.

F. Size of Cellular Concrete Mats  
The cellular concrete blocks and fittings shall be fabricated at the manufacturer or another approved location into mats with a width of up to eight (8) feet and a length, which is approved by the Engineer.

PART 3: FOUNDATION PREPARATION, GEOTEXTILE AND MAT PLACEMENT  
A. Foundation Preparation  
Contractor areas on which filter fabric and cellular concrete blocks are to be placed shall be constructed to the lines and grades shown on the Contract Drawings and to the tolerances specified in the Contract Documents, and approved by the Engineer.

Grading. The slope shall be graded to a smooth plane surface to ensure that intimate contact between the slope and the geotextile is maintained. The geotextile shall be placed on the entire bottom surface of the cellular concrete blocks. All slope deformities, roots, grade holes, ruts, or other defects shall be repaired. The slope shall be graded to a minimum of 1.0 inch in depth normal to the local slope and with a maximum spacing of 1.0 foot in any direction shall be permitted. Where such areas are evident, they shall be brought to grade by placing compacted aggregate material. The slope and stone cover shall be compacted, and the depth of layers, homogeneity of soil, and amount of compaction shall be as required by the Engineer.

Excavation and preparation for anchor trenches, side trenches, and toe trenches or areas shall be done in accordance to the lines, grades and dimensions shown in the Contract Drawings. The anchor trench highpoint on the top of the slope shall be uniformly graded so that no dips or depressions greater than 1/8 inch exist in the final rock cover. The width of the anchor trench highpoint shall also be graded uniformly to assure intimate contact between all cellular concrete blocks and the underlying grade of the slope.

Inspection. Immediately prior to placing the filter fabric and cellular concrete blocks, the prepared area shall be inspected by the Engineer, the owner's representative, and by the manufacturer's representative. No fabric or blocks shall be placed thereon until that area has been approved by each of these parties.

B. Placement of Geotextile Filter Fabric  
Contractor. Filter fabric, or filtration geotextile, as specified elsewhere, shall be placed within the limits shown on the Contract Drawings.  
Placement. The filtration geotextile shall be placed directly on the prepared area. In intimate contact with the aggregate, and free of folds or wrinkles. The geotextile filter fabric shall not be written on or disturbed when the result is a loss of intimate contact between the cellular concrete block and the geotextile or between the geotextile and the aggregate. The geotextile filter fabric shall be placed so that the upstream strip of fabric overlaps the downstream strip. The longitudinal and transverse joints shall be overlapped at least one (1) foot. The geotextile shall extend at least one foot beyond the top and bottom treatment termination points. If cellular concrete blocks are assembled and placed as large matresses, the top lap edge of the geotextile shall not occur in the same location as a splice between cellular concrete mats unless the splice is concrete filled.

C. Placement of Cellular Concrete Blocks/Mats  
Contractor. Cellular concrete blocks/mats, as specified in Part 2 of these Specifications, shall be constructed within the specified lines and grades shown on the Contract Drawings.  
Placement. No individual block within the plane of placed cellular concrete blocks shall protrude more than one-half inch above the top surface of the aggregate. To ensure that the cellular concrete blocks are flush and develop intimate contact with the substrate, the blocks shall be "seated" with a roller or other means as approved by the Engineer.

If assembled and placed as large matresses, the cellular concrete mats shall be attached to a spreader bar or other approved device to aid in the lifting and placing of the mats in their proper position by the use of a crane or other approved equipment. The equipment used should have adequate capacity to place the mats without breaking, dropping, tearing or otherwise damaging the underlying fabric. The mats shall be placed side by side and/or end to end, so that the mats abut each other. Joint seams or overlaps between mats greater than 1/2 inches shall be filled with grout. Whether placed by hand or in large matresses, distinct changes in grade that results in a discontinuous treatment surface in the direction of flow shall require a grain seam in the grade change location so as to produce a continuous surface.

Anchor trenches and side trenches shall be backfilled and compacted flush with the top of the blocks. The integrity of a soil trench backfill must be maintained so as to ensure a surface that is flush with the top surface of the cellular concrete blocks for its entire service life. Toe trench shall be backfilled as shown on the Contract Drawings. Backfilling and compaction of trenches shall be completed in a timely fashion. No more than 50 (fifty) feet of placed cellular concrete blocks with non-completed anchor and/or toe trenches shall be permitted at any time.

Finishing. The cells or openings in the cellular concrete blocks shall be backfilled and compacted immediately with suitable material to assure that there are no voids and that compacted material extends from the filter fabric to one-inch above the surface of the cellular concrete blocks. Backfilling and compaction shall be completed in a timely manner such that no more than 50 (fifty) feet of placed cellular concrete blocks with non-completed anchor and/or toe trenches shall be permitted at any time.

Consultation. The manufacturer of the cellular concrete blocks/mats shall provide design and construction advice during the design and initial installation phases of the project, when required.









TABLE 2. STANDARD SIZES FOR ARMORFLEX® BLOCKS

Class	Type	lbs./sq. ft.	Length (inches)	Width (inches)	Height (inches)	Open Area %
30 S	Open	31-33	32-34	15.0	11.6	4.75 20

The ARMORFLEX® cellular concrete blocks shall have the following nominal characteristics:

C. Reentrant Cable and Fittings  
Polyester Reentrant Cable and Fittings. Reentrant cable shall be constructed of high tenacity, low elongation, continuous filament polyester fibers. Cable shall consist of a core construction outer layer of parallel fibers contained within an outer jacket or cover. The weight of the parallel core shall be between 85% to 105% of the total weight of the cable. The reentrant cable shall have the following physical characteristics:

Nominal Cable Dia.	Approx. Area (sq.inches)	Min. Uls. (kg)	Max. Uls. (kg)
1/2"	3.700 (16.4)	2.47 (1.04)	2.74 (1.04)
3/8"</			



APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

*[Signature]* 12/17/04  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION

*[Signature]* 12/24/04  
 CHIEF, DIVISION OF LAND DEVELOPMENT

*[Signature]* 12/21/04  
 DIRECTOR

ENGINEER'S CERTIFICATE

"I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION."

*[Signature]* 11-10-04  
 SIGNATURE OF ENGINEER (PRINT NAME BELOW SIGNATURE)  
 KERRY B. REXROAD, P.E.

DEVELOPER'S CERTIFICATE

"I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I/SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT."

*[Signature]* 11-24-04  
 SIGNATURE OF DEVELOPER (PRINT NAME BELOW SIGNATURE)  
 Howard E. Saltzman

THIS PLAN HAS BEEN REVIEWED FOR HOWARD SOIL CONSERVATION DISTRICT AND MEETS TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.

*[Signature]* 12/13/04  
 USDA - NATURAL RESOURCES CONSERVATION SERVICE

THIS PLAN FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

*[Signature]* 12/13/04  
 HOWARD SOIL CONSERVATION DISTRICT

DATE: \_\_\_\_\_

NO. REVISIONS DESCRIPTION: \_\_\_\_\_

ENGINEERS  
 PLANNERS  
 SCIENTISTS  
 CONSTRUCTION MANAGERS

**KCI**  
 TECHNOLOGIES www.kci.com

STATE OF MARYLAND  
 PROFESSIONAL ENGINEER  
 KERRY B. REXROAD  
 No. 10000000000000000000

CHERRY TREE FARM  
 SECTION 1, AREA 2,  
 OPEN SPACE LOT 170  
 STREAM RESTORATION OF PUBLIC WORKS  
 HOWARD COUNTY DEPT. OF PUBLIC WORKS  
 STORMWATER MANAGEMENT DIVISION  
 6751 COLUMBIA GATEWAY DRIVE  
 COLUMBIA, MARYLAND 21046

SCALE: \_\_\_\_\_ N/A

DATE: 11-08-04

KCI JOB NO.: 01-0128.C

CAPITAL PROJECT NO.: D-1132 (PONDS)  
 D-1128 (STREAM)

PERMIT ISSUE: \_\_\_\_\_

CONSTRUCTION ISSUE: \_\_\_\_\_

**SW7**

SHEET NO. 29 OF 36

SDP-04-123













