

GENERAL NOTES

- PREMISE ADDRESS: 8010 HARRIET TUBMAN LANE, COLUMBIA, MD 21044
- SUBJECT PROPERTY IS ZONED "R-20" PER THE 2/02/04 COMPREHENSIVE ZONING PLAN AND THE "COMP-LITE" ZONING AMENDMENTS EFFECTIVE 7/2005.
- GROSS AREA OF PROPERTY = 0.214 AC. ±
- PROPERTY IS WITHIN THE METROPOLITAN DISTRICT.
- PUBLIC WATER AND PUBLIC SEWER WILL BE USED WITHIN THIS SITE.
- THE CONTRACTOR SHALL NOTIFY THE FOLLOWING UTILITY COMPANIES OR AGENCIES AT LEAST FIVE (5) WORKING DAYS BEFORE STARTING WORK SHOWN ON THESE PLANS:
 - STATE HIGHWAY ADMINISTRATION 410.531.5533
 - BGE (CONTRACTOR SERVICES) 410.550.4630
 - BGE UNDERGROUND DAMAGE CONTROL 410.787.9068
 - MISS UTILITY 1.800.257.7777
 - COLONIAL PIPELINE COMPANY 410.795.1390
 - HOWARD COUNTY, DEPT. OF PUBLIC WORKS, BUREAU OF UTILITIES 410.313.4500
 - HOWARD COUNTY HEALTH DEPARTMENT 410.313.2640
 - AT&T 1.800.252.1133
 - VERIZON 1.800.743.0033/410.224.9210
- PREVIOUS HOWARD COUNTY FILE NUMBER: CONTR.#34-3273; BA CASE# 08-050V
- FIELD RUN BOUNDARY SURVEY PREPARED BY SILL, ADCOCK & ASSOCIATES, LLC IN OCTOBER, 2006. ON-SITE TOPOGRAPHY IS BASED ON A FIELD RUN TOPOGRAPHIC SURVEY PREPARED BY SILL, ADCOCK & ASSOCIATES, LLC IN OCTOBER, 2006. OFF-SITE TOPOGRAPHY IS INTERPOLATED FROM A HOWARD COUNTY AERIAL SURVEY FLOWN IN 1998.
- THE CONTRACTOR SHALL NOTIFY MISS UTILITY AT 1-800-257-7777 AT LEAST 48 HOURS PRIOR TO ANY EXCAVATION WORK BEING DONE.
- ANY DAMAGE TO PUBLIC RIGHT-OF-WAYS, PAVING OR EXISTING UTILITIES WILL BE CORRECTED AT THE CONTRACTOR'S EXPENSE.
- THE CONTRACTOR SHALL NOTIFY THE DEPARTMENT OF PUBLIC WORKS/BUREAU OF ENGINEERING, CONSTRUCTION INSPECTION DIVISION AT (410) 313-1880 AT LEAST FIVE (5) WORKING DAYS PRIOR TO THE START OF WORK.
- THE LOT SHOWN HEREON COMPLYS WITH THE MINIMUM OWNERSHIP, WIDTH AND LOT AREA AS REQUIRED BY THE MARYLAND STATE DEPARTMENT OF THE ENVIRONMENT.
- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST STANDARDS AND SPECIFICATIONS OF HOWARD COUNTY IN ADDITION TO MSHA STANDARDS AND SPECIFICATIONS IF APPLICABLE.
- THIS PROJECT IS IN CONFORMANCE WITH THE LATEST HOWARD COUNTY STANDARDS UNLESS WAIVERS HAVE BEEN APPROVED.
- EXISTING UTILITIES ARE LOCATED BY THE USE OF ANY OR ALL OF THE FOLLOWING: ROAD CONSTRUCTION PLANS, FIELD SURVEYS, PUBLIC WATER AND SEWER PLANS AND OTHER AVAILABLE RECORD DRAWINGS. APPROXIMATE LOCATION OF THE EXISTING UTILITIES ARE SHOWN FOR THE CONTRACTOR'S INFORMATION. CONTRACTOR SHALL LOCATE EXISTING UTILITIES WELL IN ADVANCE OF CONSTRUCTION ACTIVITIES AND TAKE ALL NECESSARY PRECAUTIONS TO PROTECT THE EXISTING UTILITIES AND TO MAINTAIN UNINTERRUPTED SERVICE. ANY DAMAGE INCURRED DUE TO THE CONTRACTOR'S OPERATION SHALL BE REPAIRED IMMEDIATELY AT THE CONTRACTOR'S EXPENSE.
- SOIL COMPACTION SPECIFICATIONS, REQUIREMENTS, METHODS AND MATERIALS ARE TO BE IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE PROJECT GEOTECHNICAL ENGINEER. DRIVEWAY PAVING TO BE HOWARD COUNTY STANDARD P-1 PAVING SECTION (SEE DETAIL, THIS SHEET). GEOTECHNICAL ENGINEER TO CONFIRM ACCEPTABILITY OF PROPOSED PAVING SECTION, BASED ON SOIL TEST, PRIOR TO CONSTRUCTION.
- ALL TRAFFIC CONTROL DEVICES, MARKINGS AND SIGNING SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).
- THE COORDINATES SHOWN HEREON ARE BASED UPON THE HOWARD COUNTY GEODETIC CONTROL WHICH IS BASED ON THE MARYLAND STATE PLANE COORDINATE SYSTEM. HOWARD COUNTY MONUMENTS 3518 AND 41CC, WERE USED FOR THIS PROJECT.
- IN ACCORDANCE WITH SECTION 128 OF THE HOWARD COUNTY ZONING REGULATIONS, BAY WINDOWS, CHIMNEYS OR EXTERIOR STAIRWAYS NOT MORE THAN 16 FEET IN WIDTH MAY PROJECT NOT MORE THAN 4 FEET INTO ANY SETBACKS, PORCHES OR DECKS, OPEN OR ENCLOSED MAY PROJECT NOT MORE THAN 10 FEET INTO THE FRONT OR REAR YARD SETBACK.
- DRIVEWAY(S) SHALL BE PROVIDED PRIOR TO ISSUANCE OF A USE AND OCCUPANCY PERMIT FOR ANY NEW DWELLINGS TO ENSURE SAFE ACCESS FOR FIRE AND EMERGENCY VEHICLES PER THE FOLLOWING REQUIREMENTS:
 - WIDTH - 12 FEET (16 FEET SERVING MORE THAN ONE RESIDENCE);
 - SURFACE - SIX (6) INCHES OF COMPACTED CRUSHER RUN BASE WITH TAR AND CHIP COATING (1-1/2" MINIMUM);
 - GEOMETRY - MAXIMUM 14% GRADE, MAXIMUM 10% GRADE CHANGE AND 45-FOOT TURNING RADIUS;
 - STRUCTURES (CULVERTS/BRIDGES) - CAPABLE OF SUPPORTING 25 GROSS TONS (H25-LOADING);
 - DRAINAGE ELEMENTS - CAPABLE OF SAFELY PASSING 100 YEAR FLOOD WITH NO MORE THAN 1 FOOT DEPTH OVER DRIVEWAY SURFACE;
 - MAINTENANCE - SUFFICIENT TO ENSURE ALL WEATHER USE
- DRIVEWAY ENTRANCE TO BE PER HOWARD COUNTY STANDARD DETAIL R-6.06.
- SEWER HOUSE CONNECTION (SHC) TO BE AT 2.0% UNLESS OTHERWISE NOTED. CLEANOUTS ARE TO BE PROVIDED AT ALL BENDS. SEWER HOUSE CONNECTION ELEVATIONS SHOWN ARE LOCATED AT THE PROPERTY LINE.
- EXISTING WATER HOUSE CONNECTION (WHC) IS COPPER. EXISTING SEWER HOUSE CONNECTION (SHC) IS PVC. EXISTING WATER AND SEWER HOUSE CONNECTIONS TO BE UTILIZED AND EXTENDED TO PROPOSED HOUSE.
- NO GRADING, REMOVAL OF VEGETATIVE COVER OR TREES, PAVING AND NEW STRUCTURES SHALL BE PERMITTED WITHIN THE REQUIRED WETLANDS, STREAM(S) OR THEIR BUFFERS, FOREST CONSERVATION EASEMENT AREAS AND 100 YEAR FLOODPLAIN.
- THERE ARE NO WETLANDS, FLOODPLAINS, HISTORIC STRUCTURES, STEEP SLOPES OR CEMETERIES LOCATED ON-SITE.
- THIS PLAN HAS BEEN PREPARED IN ACCORDANCE OF SECTION 16.124 OF HOWARD COUNTY CODE AND LANDSCAPE MANUAL. FINANCIAL SURETY FOR THE REQUIRED LANDSCAPING WILL BE POSTED AS PART OF THE GRADING PERMIT IN THE AMOUNT OF \$2,100.00 (7 SHADE TREES @ \$300.00 EACH).
- THIS PROJECT IS EXEMPT FROM THE REQUIREMENTS OF SECTION 16.1200 OF THE HOWARD COUNTY CODE FOR FOREST CONSERVATION BECAUSE WE ARE A SINGLE LOT SMALLER THAN 40,000 SQUARE FEET PER SECTION 16.1202(B) OF THE COUNTY CODE.
- IN ACCORDANCE WITH THE MARYLAND STORMWATER DESIGN MANUAL, PROJECTS SHALL BE EXEMPT FROM STORMWATER MANAGEMENT OBLIGATIONS IF IT HAS LESS THAN 5,000 SQUARE FEET OF LAND COVER CHANGE. THIS PLAN PROPOSES 810 SQ.FT. OF LAND COVER CHANGE AND THEREFORE IS EXEMPT FROM PROVIDING STORMWATER MANAGEMENT.
- BASED UPON HOWARD COUNTY BOARD OF APPEALS HEARING, BA CASE NO. 06-050V, DATED: MARCH 8, 2007, THE PETITION OF MARTIN KOLLAR FOR A VARIANCE TO REDUCE THE REQUIRED 50 FOOT SETBACK FROM A COLLECTOR PUBLIC STREET RIGHT-OF-WAY TO 21 FEET FOR A PROPOSED SINGLE-FAMILY DETACHED DWELLING TO BE LOCATED IN AN R-20 (RESIDENTIAL-SINGLE) ZONING DISTRICT WAS HEREBY GRANTED, AND IS SUBJECT TO THE FOLLOWING CONDITION:
 - PROVIDED, HOWEVER, THAT THE VARIANCE WILL APPLY ONLY TO THE USES AND STRUCTURES AS DESCRIBED IN THE PETITION SUBMITTED, AND NOT TO ANY OTHER ACTIVITIES, USES, STRUCTURES, OR ADDITIONS ON THE PROPERTY.
 - SHC ELEVATIONS HAVE BEEN SHOWN ALONG THE PROPOSED SHC.
- IF ANY EXISTING WELL OR SEPTIC SYSTEMS ARE ENCOUNTERED DURING CONSTRUCTION THEY SHALL BE PROPERLY SEALED AND ABANDONED BY A LICENSED WELL DRILLER IN ACCORDANCE WITH HOWARD COUNTY HEALTH DEPARTMENT REGULATIONS AND GUIDELINES.
- PER WATER AND SEWER CONTRACT NO. 34-3273, HARRIET TUBMAN LANE (FORMERLY GULFORD ROAD) HAS A 40' PRESCRIPTIVE RIGHT OF WAY. SINCE THE EXISTING WATER AND SEWER FALLS WITHIN THIS RIGHT OF WAY, NO EASEMENTS ARE NECESSARY.
- PROFESSIONAL CERTIFICATION: I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, PAUL M. SILL, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 32225, EXPIRATION DATE: JUNE 05, 2009.

NOTES

- CONSULT INTERNATIONAL SOCIETY OF ARBORICULTURE GUIDELINES FOR FURTHER DETAILS OF PLANTING SPECIFICATIONS OR CONSULT WITH A QUALIFIED PROFESSIONAL.
- EACH TREE SHALL BE PLANTED SUCH THAT THE TRUNK FLARE IS VISIBLE AT THE TOP OF THE ROOT BALL.
- STAKES SHALL BE REMOVED NO LATER THAN THE END OF THE FIRST GROWING SEASON AFTER PLANTING.
- PLACE UPRIGHT STAKES PARALLEL TO WALKS & BUILDINGS.
- KEEP MULCH 1" FROM TRUNK
- SEE ARCHITECTURAL PLANS FOR ADDITIONAL PLANTINGS WHICH EXCEED HOWARD COUNTY MINIMUM REQUIREMENTS.
- TREES ARE NOT TO BE PLANTED OVER PRIVATE SEWAGE EASEMENT.

TYPICAL TREE PLANTING AND STAKING

DECIDUOUS TREES UP TO 2-1/2" CALIPER NOT TO SCALE

LANDSCAPE SCHEDULE

KEY	QUANTITY	BOTANICAL NAME	SIZE	NOTE
(+)	4	ACER RUBRUM OCTOBER GLORY RED MAPLE	2 1/2"-3" CAL.	B & B
(O)	3	QUERCUS COCCINEA SCARLET OAK	2 1/2"-3" CAL.	B & B

LANDSCAPE NOTES

- AT THE TIME OF INSTALLMENT, ALL SHRUBS AND OTHER PLANTINGS HERewith LISTED AND APPROVED FOR THIS SITE, SHALL BE OF THE PROPER HEIGHT REQUIREMENTS IN ACCORDANCE WITH THE HOWARD COUNTY LANDSCAPING MANUAL. IN ADDITION, NO SUBSTITUTIONS OR RELOCATION OF REQUIRED PLANTINGS MAY BE MADE WITHOUT PRIOR REVIEW AND APPROVAL FROM THE DEPARTMENT OF PLANNING AND ZONING. ANY DEVIATION FROM THIS APPROVED LANDSCAPE PLAN MAY RESULT IN DENIAL OR DELAY IN THE RELEASE OF LANDSCAPE SURETY UNTIL SUCH TIME AS ALL REQUIRED MATERIALS ARE PLANTED AND/OR REVISIONS ARE MADE TO APPLICABLE PLANS AND CERTIFICATES.
- THE OWNER, TENANT, AND/OR THEIR AGENTS SHALL BE RESPONSIBLE FOR MAINTENANCE OF THE REQUIRED LANDSCAPING, INCLUDING BOTH PLANT MATERIALS AND BERMS, FENCES AND WALLS. ALL PLANT MATERIALS SHALL BE MAINTAINED IN GOOD GROWING CONDITION, AND WHEN NECESSARY, REPLACED WITH NEW MATERIALS TO ENSURE CONTINUED COMPLIANCE WITH APPLICABLE REGULATIONS. ALL OTHER REQUIRED LANDSCAPING SHALL BE PERMANENTLY MAINTAINED IN GOOD CONDITION, AND WHEN NECESSARY, REPAIRED OR REPLACED.
- FINANCIAL SURETY FOR THE REQUIRED LANDSCAPING WILL BE POSTED AS PART OF THE GRADING PERMIT IN THE AMOUNT OF \$2,100.00 (7 SHADE TREES @ \$300.00 EACH).



SCHEDULE A PERIMETER LANDSCAPE EDGE

CATEGORY	ADJACENT TO PERIMETER ROADWAYS				ADJACENT TO PERIMETER PROPERTIES			
	1	2	3	4	1	2	3	4
PERIMETER/FRONTAGE DESIGNATION	N/A(1)							
LANDSCAPE TYPE	A							
LINEAR FEET OF ROADWAY FRONTAGE/PERIMETER	95	153	29	160				
CREDIT FOR EXISTING VEGETATION (YES, NO, LINEAR FEET)	NO	NO	NO	YES(2)				
REMAINING PERIMETER LENGTH CREDIT FOR WALL, FENCE OR BERM (YES, NO, LINEAR FEET)	NO	NO	NO	NO				
REMAINING PERIMETER LENGTH								
NUMBER OF PLANTS REQUIRED								
SHADE TREES		1:60.3	1:60.1	1:60.3				
EVERGREEN TREES		-	-	-				
SHRUBS		-	-	-				
NUMBER OF PLANTS PROVIDED								
SHADE TREES		3	1	3				
EVERGREEN TREES		-	-	-				
OTHER TREES (2:1 SUBSTITUTION)		-	-	-				
SHRUBS (10:1 SUBSTITUTION)		-	-	-				
(DESCRIBE PLANT SUBSTITUTION CREDITS BELOW IF NEEDED)								

NOTES:

- HOUSE FRONTS ON ROAD

LEGEND



VICINITY MAP
SCALE: 1"=2000'

BENCHMARKS

NUMBER	NORTHING	EASTING	ELEVATION	DESCRIPTION
3513	553,573.6950	1,346,098.1180	415.392	12' NORTH OF FIRE HYDRANT, 38.7' NORTHEAST OF BGE #334579, 39.7' NORTHWEST OF STOP SIGN
41CC	552,494.2746	1,347,062.4314	400.005	4.6' FROM SOUTH EDGE OF MARTIN ROAD, 16.8' EAST OF G&E 280554

SITE ANALYSIS DATA CHART

TOTAL PROJECT AREA	AREA OF SUBMISSION	DISTURBED AREA	PRESENT ZONING
0.214 AC.±	0.214 AC.±	0.11 AC	R-20
PROPOSED USE	FLOOR SPACE PER USE	TOTAL UNITS ALLOWED	TOTAL UNITS PROPOSED
RESIDENTIAL	954.80 SF	1	1
MAX. # EMPLOYEES/TENANTS	PARKING SPACES REQ.	PARKING SPACES PROV.	HC SPACES PROVIDED
NA	2	2	NA
OPEN SPACE REQUIRED	OPEN SPACE PROVIDED	REC. O.S. REQUIRED	REC. O.S. PROVIDED
NA	NA	NA	NA
BUILDING COVERAGE	FLOOR AREA RATIO	DPZ FILE REFERENCES	
954.80 SF	NA	CONTR.#34-3273; BA CASE# 06-050V	

PERMIT INFORMATION CHART

SUBDIVISION NAME		SECTION / AREA		LOT / PARCEL #	
N/A		NA		130	
PLAT / DEED	GRID #	ZONING	TAX MAP #	ELECT. DIS.	CENSUS TRACT
L. 10249 F. 87	24	R-20	35	5TH	6056.02
WATER CODE			SEWER CODE		
E29			6580000		

ADDRESS CHART

PARCEL	STREET ADDRESS
130	8010 HARRIET TUBMAN LANE

SHEET INDEX

SHEET NO.	DESCRIPTION
1	SITE DEVELOPMENT AND LANDSCAPE PLAN
2	SEDIMENT AND EROSION CONTROL PLAN, NOTES AND DETAILS

PAVING SECTIONS

SEC. NO.	ROAD AND STREET CLASSIFICATION	CALIFORNIA BEARING RATIO (CBR)	3 TO 4.5 TO <7		7 TO 4.5 TO <7	
			MIN	HMA WITH GAB	HMA WITH CONSTANT GAB	HMA WITH CONSTANT GAB
P-1	PARKING BAYS: RESIDENTIAL AND NON-RESIDENTIAL PARKING DRIVE AISLES: RESIDENTIAL AND NON-RESIDENTIAL WITH NO MORE THAN 2 HEAVY TRUCKS PER DAY	HMA SUPERPAVE FINAL SURFACE 9.5 MM, PG 64-22, LEVEL 1 (ESAL)	1.5	1.5	1.5	1.5
		HMA SUPERPAVE INTERMEDIATE SURFACE (NA)	NA	NA	NA	NA
		HMA SUPERPAVE BASE 19.0 MM, PG 64-22 LEVEL 1 (ESAL)	2.0	2.0	2.0	3.0
		GRADED AGGREGATE BASE (GAB)	8.5	7.0	5.0	4.0

- NOTES:**
- HEAVY TRUCKS ARE DEFINED AS THOSE WITH SIX (6) WHEELS OR MORE INCLUDING GARBAGE TRUCKS
 - HMA SUPERPAVE LAYERS SHALL BE PLACED IN APPROPRIATE COMPACTED LIFT THICKNESS: 19.0 MM BASE (2.0" MIN TO 4.0" MAX), 12.5 MM SURFACE (1.5" MIN TO 3.0" MAX), AND 9.5 MM SURFACE (1.0" MIN TO 2.0" MAX)
 - GRADED AGGREGATE BASE (GAB) TO BE PLACED AND COMPACTED IN 6" MAX COMPACTED THICKNESS LAYERS
 - THE INTERMEDIATE SURFACE COURSE LAYER MUST BE PLACED WITHIN 2 WEEKS OF PLACEMENT OF BASE COURSE, AND IS REQUIRED PRIOR TO SUBSTANTIAL COMPLETION INSPECTION AND ROAD REDUCTION.
 - IN LIEU OF PLACING THE INTERMEDIATE SURFACE COURSE LAYER FOR COMMERCIAL/INDUSTRIAL ENTRANCE APRONS WITHIN THE COUNTY RIGHT-OF-WAY WHERE AUXILIARY LANES ARE NOT REQUIRED, THE THICKNESS OF THE INTERMEDIATE PAVEMENT LAYER CAN BE ADDED TO THE REQUIRED THICKNESS OF THE BASE ASPHALT LAYER.
 - THE CONSTRUCTION DRAWINGS SHALL SHOW THE PAVING SECTION, ROAD CLASSIFICATION CBR VALUE FOR EACH ROADWAY.

DEVELOPER'S BUILDER'S CERTIFICATE

I CERTIFY THAT THE LANDSCAPING SHOWN ON THIS PLAN WILL BE DONE ACCORDING TO THE PLAN, SECTION 16.124 OF THE HOWARD COUNTY CODE AND THE HOWARD COUNTY LANDSCAPE MANUAL. I FURTHER CERTIFY THAT UPON COMPLETION, A LETTER OF LANDSCAPE INSTALLATION, ACCOMPANIED BY AN EXECUTED ONE(1) YEAR GUARANTEE OF PLANT MATERIALS, WILL BE SUBMITTED TO THE DEPARTMENT OF PLANNING AND ZONING.

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING


Chief Development Engineering Division: *ya* DATE: *1/20/08*

Chief, Division of Land Development: *MMB* DATE: *1/20/08*

Director: *Frank P. Lepley* DATE: *2/1/08*


DATE: *1/20/08*

1	REVISE GRADES AND HOUSE ELEVATIONS	4.18.08
NO	REVISION	DATE



PLAN VIEW

SCALE: 1"=20'



HOUSE TEMPLATE

SCALE: 1"=20'

OWNER/ DEVELOPER

MARTIN KOLLAR
8005 PAUL MARTIN
ELKBRIDGE, MARYLAND 21075
443.277.7911

SITE DEVELOPMENT AND LANDSCAPE PLAN

KOLLAR PROPERTY

SINGLE FAMILY DETACHED DWELLING

TAX MAP 35 GRID 24 5TH ELECTION DISTRICT PARCEL 130 HOWARD COUNTY, MARYLAND

Sill · Adcock & Associates · LLC

Engineers · Surveyors · Planners

3300 North Ridge Road, Suite 160
Ellicott City, Maryland 21043
Phone: 443.325.7682 Fax: 443.325.7685
Email: info@saalland.com

DESIGN BY: PS
DRAWN BY: PS
CHECKED BY: PS
SCALE: AS SHOWN
DATE: JANUARY 08, 2008
PROJECT #: 06-064
SHEET #: 1 OF 2

PERMANENT SEEDING NOTES

APPLY TO GRADED OR CLEARED AREAS NOT SUBJECT TO IMMEDIATE FURTHER DISTURBANCE WHERE A PERMANENT LONG-LIVED VEGETATIVE COVER IS NEEDED.

SEEDBED PREPARATION: LOOSEN UPPER THREE INCHES OF SOIL BY RAKING, DISCING OR OTHER ACCEPTABLE MEANS BEFORE SEEDING, IF NOT PREVIOUSLY LOOSENED.

SOIL AMENDMENTS: IN LIEU OF SOIL TEST RECOMMENDATIONS, USE ONE OF THE FOLLOWING SCHEDULES

- 1) PREFERRED - APPLY 2 TONS PER ACRE DOLOMITIC LIMESTONE (92 LBS/1000 SQ.FT.) AND 600 LBS PER ACRE 10-10-10 FERTILIZER (14 LBS/1000 SQ.FT.) BEFORE SEEDING. HARROW OR DISC INTO UPPER THREE INCHES OF SOIL. AT THE TIME OF SEEDING, APPLY 400 LBS PER ACRE 30-0-0 UREAFORM FERTILIZER (9 LBS/1000 SQ.FT.)
- 2) ACCEPTABLE - APPLY 2 TONS PER ACRE DOLOMITIC LIMESTONE (92 LBS/1000 SQ.FT.) AND APPLY 1000 LBS PER ACRE 10-10-10 FERTILIZER (23 LBS/1000 SQ.FT.) BEFORE SEEDING. HARROW OR DISC INTO UPPER THREE INCHES OF SOIL.

SEEDING: FOR THE PERIODS MARCH 1 THRU APRIL 30, AND AUGUST 1 THRU OCTOBER 15, SEED WITH 60 LBS PER ACRE (1.4 LBS/1000 SQ.FT.) OF KENTUCKY 31 TALL FESCUE. FOR THE PERIOD MAY 1 THRU JULY 31, SEED WITH 60 LBS KENTUCKY 31 TALL FESCUE PER ACRE AND 2 LBS PER ACRE (0.05 LBS/1000 SQ.FT.) OF WEEPING LOVEGRASS. DURING THE PERIOD OF OCTOBER 16 THRU FEBRUARY 28, PROTECT SITE BY: OPTION (1) 2 TONS PER ACRE WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING. OPTION (2) USE SOD. OPTION (3) SEED WITH 60 LBS/ACRE KENTUCKY 31 TALL FESCUE AND MULCH WITH 2 TONS/ACRE WELL ANCHORED STRAW.

MULCHING: APPLY 1 1/2 TO 2 TONS PER ACRE (70 TO 90 LBS/1000 SQ.FT.) OF UNROTTED SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. ANCHOR MULCH IMMEDIATELY AFTER APPLICATION USING MULCH ANCHORING TOOL OR 218 GALLONS PER ACRE (5 GAL/1000 SQ.FT.) OF EMULSIFIED ASPHALT ON FLAT AREAS. ON SLOPES 8 FEET OR HIGHER, USE 348 GALLONS PER ACRE (6 GAL/1000 SQ.FT.) FOR ANCHORING.

TEMPORARY SEEDING NOTES

SEEDBED PREPARATION: LOOSEN UPPER THREE INCHES OF SOIL BY RAKING, DISCING OR OTHER ACCEPTABLE MEANS BEFORE SEEDING, IF NOT PREVIOUSLY LOOSENED.

SOIL AMENDMENTS: APPLY 600 LBS PER ACRE 10-10-10 FERTILIZER (14 LBS/1000 SQ.FT.)

SEEDING: FOR PERIODS MARCH 1 THRU APRIL 30 AND FROM AUGUST 15 THRU NOVEMBER 15, SEED WITH 2 1/2 BUSHEL PER ACRE OF ANNUAL RYE (3.2 LBS/1000 SQ.FT.) FOR THE PERIOD MAY 1 THRU JULY 31, SEED WITH 3 LBS PER ACRE OF WEEPING LOVEGRASS (0.07 LBS/1000 SQ.FT.), FOR THE PERIOD NOVEMBER 1 THRU FEBRUARY 28, PROTECT SITE BY APPLYING 2 TONS PER ACRE OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING, OR USE SOD.

MULCHING: APPLY 1 1/2 TO 2 TONS PER ACRE (70 TO 90 LBS/1000 SQ.FT.) OF UNROTTED SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. ANCHOR MULCH IMMEDIATELY AFTER APPLICATION USING MULCH ANCHORING TOOL OR 218 GALLONS PER ACRE (5 GAL/1000 SQ.FT.) OF EMULSIFIED ASPHALT ON FLAT AREAS. ON SLOPES 8 FEET OR HIGHER, USE 348 GALLONS PER ACRE (6 GAL/1000 SQ.FT.) FOR ANCHORING.

REFER TO THE 1984 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL, FOR RATE AND METHODS NOT COVERED.

21.0 STANDARDS AND SPECIFICATIONS FOR TOPSOILS

DEFINITION
I. FOR SITES HAVING DISTURBED AREAS UNDER 5 ACRES:

II. FOR SITES HAVING DISTURBED AREAS OVER 5 ACRES:

III. FOR SITES HAVING DISTURBED AREAS OVER 5 ACRES:

IV. ON SOIL MEETING TOPSOIL SPECIFICATIONS, OBTAIN TEST RESULTS DICTATING FERTILIZER AND LIME AMENDMENTS REQUIRED TO BRING THE SOIL INTO COMPLIANCE WITH THE FOLLOWING:

- A. PH FOR TOPSOIL SHALL BE BETWEEN 6.0 AND 7.5. IF THE TESTED SOIL DEMONSTRATES A PH OF LESS THAN 6.0, SUFFICIENT LIME SHALL BE PRESCRIBED TO RAISE THE PH TO 6.5 OR HIGHER.
- B. ORGANIC CONTENT OF TOPSOIL SHALL BE NOT LESS THAN 1.5 PERCENT BY WEIGHT.
- C. TOPSOIL HAVING SOLUBLE SALT CONTENT GREATER THAN 500 PARTS PER MILLION SHALL NOT BE USED.
- D. NO SOD OR SEED SHALL BE PLACED ON SOIL WHICH HAS BEEN TREATED WITH SOIL STERILANTS OR CHEMICALS USED FOR WEED CONTROL UNTIL SUFFICIENT TIME HAS ELAPSED (14 DAYS MIN.) TO PERMIT DISSIPATION OF PHYTO-TOXIC MATERIALS.

NOTE: TOPSOIL SUBSTITUTES OR AMENDMENTS, AS RECOMMENDED BY A QUALIFIED AGRONOMIST OR SOIL SCIENTIST AND APPROVED BY THE APPROPRIATE APPROVAL AUTHORITY, MAY BE USED IN LIEU OF NATURAL TOPSOIL.

V. TOPSOIL APPLICATION

- WHEN TOPSOILING, MAINTAIN NEEDED EROSION AND SEDIMENT CONTROL PRACTICES SUCH AS DIVERSIONS, GRADE STABILIZATION STRUCTURES, EARTH DIKES, SLOPE SILT FENCE AND SEDIMENT TRAPS AND BASINS.
- GRADES ON THE AREAS TO BE TOPSOILED, WHICH HAVE BEEN PREVIOUSLY ESTABLISHED, SHALL BE MAINTAINED, ALBERT 4"-8" HIGHER IN ELEVATION.
- TOPSOIL SHALL BE UNIFORMLY DISTRIBUTED IN A 4"-8" LAYER OR TO A MINIMUM THICKNESS OF 4". SPREADING SHALL BE PERFORMED IN SUCH A MANNER THAT SODDING OR SEEDING CAN PROCEED WITH A MINIMUM OF ADDITIONAL SOIL PREPARATION AND TILLAGE. ANY IRREGULARITIES IN THE SURFACE RESULTING FROM TOPSOILING OR OTHER OPERATIONS SHALL BE CORRECTED IN ORDER TO PREVENT THE FORMATION OF DEPRESSIONS OR WATER POCKETS.
- TOPSOIL SHALL NOT BE PLACED WHILE THE TOPSOIL OR SUBSOIL IS IN A FROZEN OR MUDDY CONDITION, WHEN THE SUBSOIL IS EXCESSIVELY WET OR IN A CONDITION THAT MAY OTHERWISE BE DETRIMENTAL TO PROPER GRADING AND SEEDBED PREPARATION.

CONSTRUCTION AND MATERIAL SPECIFICATIONS



- TOPSOIL SALVAGED FROM THE EXISTING SITE MAY BE USED PROVIDED THAT IT MEETS THE STANDARDS AS SET FORTH IN THESE SPECIFICATIONS. TYPICALLY, THE DEPTH OF TOPSOIL TO BE SALVAGED FOR A GIVEN SOIL TYPE CAN BE FOUND IN THE REPRESENTATIVE SOIL PROFILE SECTION IN THE SOIL SURVEY PUBLISHED BY USDA. SCs IN COOPERATION WITH MARYLAND AGRICULTURAL EXPERIMENTAL STATION.
- TOPSOIL SPECIFICATIONS - SOIL TO BE USED AS TOPSOIL MUST MEET THE FOLLOWING:
 - TOPSOIL SHALL BE A LOAM, SANDY LOAM, CLAY LOAM, SILT LOAM, SANDY CLAY LOAM, LOAMY SAND. OTHER SOILS MAY BE USED IF RECOMMENDED BY AN AGRONOMIST OR A SOIL SCIENTIST AND APPROVED BY THE APPROPRIATE APPROVAL AUTHORITY. REGARDLESS, TOPSOIL SHALL NOT BE A MIXTURE OF CONTRASTING TEXTURED SUBSOILS AND SHALL CONTAIN LESS THAN 5% BY VOLUME OF CINDERS, STONES, SLAG, COARSE FRAGMENTS, GRAVEL, STONES, ROOTS, TRASH, OR OTHER MATERIAL LARGER THAN 1 AND 1/2" IN DIAMETER.
 - TOPSOIL MUST BE FREE OF PLANTS OR PLANT PARTS SUCH AS BERMUDA GRASS, QUACKGRASS, JOHNSONGRASS, HUTSODGE, POISON IVY, THISTLE, OR OTHERS AS SPECIFIED.
 - WHERE THE SUBSOIL IS EITHER HIGHLY ACIDIC OR COMPOSED OF HEAVY CLAYS, GROUND LIMESTONE SHALL BE SPREAD AT THE RATE OF 4-8 TONS/ACRE (200-400 POUNDS PER 1,000 SQUARE FEET) PRIOR TO THE PLACEMENT OF TOPSOIL. LIME SHALL BE DISTRIBUTED UNIFORMLY OVER DESIGNATED AREAS AND WORKED INTO THE SOIL IN CONJUNCTION WITH TILLAGE OPERATIONS AS DESCRIBED IN THE FOLLOWING PROCEDURES.

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING
 CHIEF, DEVELOPMENT ENGINEERING DIVISION
 DATE: 1/22/08
 DATE: 1/30/08
 DATE: 2/1/08

REVIEWED FOR HOWARD COUNTY AND MEETS TECHNICAL REQUIREMENTS
 U.S. NATURAL RESOURCES CONSERVATION SERVICE
 DATE: 1/17/08
 DATE: 1/17/08

ENGINEER'S CERTIFICATE
 I CERTIFY THAT THIS PLAN FOR SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING.
 SIGNATURE OF ENGINEER: Paul M. Sill, P.E.
 DATE: 01/14/08

DEVELOPER'S CERTIFICATE
 I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN FOR SEDIMENT AND EROSION CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING.
 SIGNATURE OF DEVELOPER: Matt C. Hill
 DATE: 01/09/08



SEDIMENT CONTROL NOTES

1. A minimum of 48 hours notice must be given to the Howard County Department of Inspection, License and Permits Sediment Control Division prior to the start of any construction (410-313-1855).
2. All vegetation and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the 1984 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL, as revised thereon.
3. Following initial soil disturbance or redistribution, permanent or temporary stabilization shall be completed within: (a) 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes, and all slopes greater than 3:1; (b) 14 days after all other disturbed or graded areas on the project site.
4. All sediment traps/basins shown must be fenced and warning signs posted around their perimeter in accordance with Vol. 1, Chapter 7, HOWARD COUNTY DESIGN MANUAL, Storm Drainage.
5. All disturbed areas must be stabilized within the time period specified above in accordance with the 1984 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL, for permanent seeding, sod, temporary seeding, and mulching (Sec. G). Temporary stabilization with mulch alone shall be done when recommended seeding dates do not allow for proper germination and establishment of grasses.
6. All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.
7. Site Analysis:

Total Area:	0.214 Acres
Area to be roofed or paved:	0.105 Acres
Area to be vegetatively stabilized:	0.033 Acres
Total Cut:	1160 CY
Offsite waste/borrow area location:	26 CY

8. Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.

9. Additional sediment controls must be provided, if deemed necessary by the Howard County Sediment Control Inspector.

10. On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the inspection agency is made.

11. Trenches for the construction of utilities is limited to three pipe lengths or that which shall be back-filled and stabilized within one working day, whichever is shorter.



* Earthwork quantities are solely for the purpose of calculating fees. Contractor to verify all quantities prior to the start of construction.

** To be determined by contractor, with pre-approval of the Sediment Control Inspector with an approved and active grading permit.



SEQUENCE OF CONSTRUCTION

1. OBTAIN GRADING PERMIT.
2. NOTIFY HOWARD COUNTY DEPARTMENT OF INSPECTIONS, LICENSE AND PERMITS AT (410) 313-1880 AT LEAST 24 HOURS BEFORE STARTING ANY WORK.
3. INSTALL STABILIZED CONSTRUCTION ENTRANCE AND SILT FENCE. (1 WEEK)
4. ROUGH GRADE SITE AND BEGIN BUILDING CONSTRUCTION. (1 WEEK)
5. FINISH BUILDING CONSTRUCTION AND PAVE DRIVEWAY. (4 MONTHS)
6. FINE GRADE SITE AND INSTALL EROSION CONTROL MATTING. (1 WEEK)
7. UPON STABILIZATION OF ALL DISTURBED AREAS AND WITH THE PERMISSION OF THE SEDIMENT CONTROL INSPECTOR, REMOVE ALL SEDIMENT CONTROL MEASURES AND STABILIZE ANY REMAINING DISTURBED AREA. (1 WEEK)

NOTE: -FOLLOWING INITIAL SOIL DISTURBANCE OR ANY REDISTURBANCES, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN:
 A. 7 CALENDAR DAYS FOR ALL PERIMETER SEDIMENT CONTROL STRUCTURES, DIKES, SWALES AND ALL SLOPES GREATER THAN 3:1.
 B. 14 CALENDAR DAYS FOR ALL OTHER DISTURBED AREAS.
 -DURING GRADING AND AFTER EACH RAINFALL, CONTRACTOR WILL INSPECT AND PROVIDE NECESSARY MAINTENANCE TO THE SEDIMENT CONTROL MEASURES ON THIS PLAN.




SOILS LEGEND		
SYMBOL	NAME / DESCRIPTION	GROUP
GIB2	GLENELG LOAM, 3 TO 8 PERCENT SLOPES, MODERATELY ERODED	B



OWNER/DEVELOPER
 MARTIN KOLLAR
 6005 PAUL MARTIN
 ELK RIDGE, MARYLAND 21075
 443.277.7911

SEDIMENT AND EROSION CONTROL PLAN, NOTES AND DETAILS
 KOLLAR PROPERTY
 SINGLE FAMILY DETACHED DWELLING
 TAX MAP 35 GRID 24
 5TH ELECTION DISTRICT
 PARCEL 130
 HOWARD COUNTY, MARYLAND

Sill · Adcock & Associates · LLC
 Engineers · Surveyors · Planners
 3300 North Ridge Road, Suite 160
 Elkridge City, Maryland 21043
 Phone: 443.325.7682 Fax: 443.325.7685
 Email: info@saadland.com



DESIGN BY: PS
 DRAWN BY: PS
 CHECKED BY: PS
 SCALE: AS SHOWN
 DATE: JANUARY 08, 2008
 PROJECT #: 08-084
 SHEET #: 2 OF 2