


DRAWING SHEET

NO.	NO.	SHEET TITLE
A-01	2.	GENERAL NOTES
A-02	3.	PROJECT LOCATION PLAN
B-01	4.	EXISTING CONDITIONS AND WETLAND DELINEATION SITE PLAN KEY
B-02	5.	EXISTING CONDITIONS AND WETLAND DELINEATION PLAN AREA 01
B-03	6.	EXISTING CONDITIONS AND WETLAND DELINEATION PLAN AREA 02
B-04	7.	EXISTING CONDITIONS AND WETLAND DELINEATION PLAN AREA 03
C-01	8.	PROPOSED SEDIMENT CONTROL AND DREDGING PLAN KEY
C-02	9.	PROPOSED SEDIMENT CONTROL AND DREDGING PLAN AREA 01
C-03	10.	PROPOSED SEDIMENT CONTROL AND DREDGING PLAN AREA 02
C-04	11.	PROPOSED SEDIMENT CONTROL AND DREDGING PLAN AREA 03
C-05	12.	AREA 01 - CROSS-SECTIONS (1 OF 2)
C-06	13.	AREA 01 - CROSS-SECTIONS (2 OF 2)
C-07	14.	AREA 02 - CROSS-SECTIONS
C-08	15.	AREA 03 - CROSS-SECTIONS (1 OF 2)
C-09	16.	AREA 03 - CROSS-SECTIONS (2 OF 2)
D-01	17.	PIPELINE ROUTING
D-02	18.	PIPELINE ROUTING
E-01	19.	STAGING AREA
F-01	20.	WETLAND CREATION AREAS
F-02	21.	WETLAND CREATION AREAS
F-03	22.	PLANTING PLAN
F-04	23.	PLANTING PLAN
F-05	24.	PLANTING DETAILS AND NOTES
G-01	25.	SECTION AND DETAILS
G-02	26.	TYPICAL DETAILS
H-01	27.	ISTHMUS ACCESS ROAD - PLAN & PROFILE
H-02	28.	ISTHMUS ACCESS ROAD - PLAN & PROFILE
H-03	29.	ISTHMUS ACCESS ROAD - PLAN & PROFILE
H-04	30.	ISTHMUS ACCESS ROAD - PLAN & PROFILE
I-01	31.	TEMPORARY EROSION & SEDIMENT CONTROL PLAN - INITIAL PHASE STAGING AREA
I-02	32.	TEMPORARY EROSION & SEDIMENT CONTROL PLAN - FINAL PHASE STAGING AREA
I-03	33.	TEMPORARY EROSION & SEDIMENT CONTROL PLAN - ISTHMUS ACCESS ROAD INITIAL AND FINAL DESIGN
I-04	34.	TEMPORARY EROSION & SEDIMENT CONTROL PLAN - ISTHMUS ACCESS ROAD INITIAL AND FINAL DESIGN
I-05	35.	TEMPORARY EROSION & SEDIMENT CONTROL - DETAILS & NOTES
I-06	36.	TEMPORARY EROSION & SEDIMENT CONTROL - DETAILS & NOTES
I-07	37.	TEMPORARY EROSION & SEDIMENT CONTROL - DETAILS & NOTES

# Lake Kittamaquundi Restoration Project Columbia, Maryland



LOCATION PLAN  
NTS

## Columbia Association Construction Services Project No. 040107DK

J-01	38.	DAM REPAIR - TITLE SHEET
J-02	39.	DAM REPAIR - GENERAL NOTES
J-03	40.	DAM REPAIR - EXISTING CONDITION PLAN
J-04	41.	DAM REPAIR - PROPOSED SITE PLAN
J-05	42.	DAM REPAIR - SECTIONS AND DETAILS
J-06	43.	DAM REPAIR - TEMPORARY EROSION & SEDIMENT CONTROL PLAN - INITIAL PHASE
J-07	44.	DAM REPAIR - TEMPORARY EROSION & SEDIMENT CONTROL PLAN - FINAL PHASE
J-08	45.	DAM REPAIR - TEMPORARY EROSION & SEDIMENT CONTROL - DETAILS & NOTES
J-09	46.	DAM REPAIR - SOIL BORING LOGS

K-01	47.	MULTIUSE TRAIL - COVER SHEET
K-02	48.	MULTIUSE TRAIL - KEY SHEET
K-03	49.	MULTIUSE TRAIL - DESIGN PLANS
K-04	50.	MULTIUSE TRAIL - DESIGN PLANS
K-05	51.	MULTIUSE TRAIL - DESIGN PLANS
K-06	52.	MULTIUSE TRAIL - DESIGN PLANS
K-07	53.	MULTIUSE TRAIL - DESIGN PLANS
K-08	54.	MULTIUSE TRAIL - CROSS SECTIONS & DETAILS
K-09	55.	MULTIUSE TRAIL - BOARDWALK DETAILS
K-10	56.	MULTIUSE TRAIL - BOARDWALK DETAILS
K-11	57.	MULTIUSE TRAIL - EROSION & SEDIMENT CONTROL PLAN
K-12	58.	MULTIUSE TRAIL - EROSION & SEDIMENT CONTROL PLAN
K-13	59.	MULTIUSE TRAIL - EROSION & SEDIMENT CONTROL NOTES & DETAILS

SITE ANALYSIS DATA CHART

a. TOTAL PROJECT AREA				
LAKE	28.3	ACRES	1232748	FT <sup>2</sup>
STAGING AREA	106	ACRES	46153	FT <sup>2</sup>
ISTHMUS	0.66	ACRES	28892	FT <sup>2</sup>
b. AREA OF PLAN SUBMISSION - SEE ITEM a				
c. LIMIT OF DISTURBED AREA				
LAKE	22.3	ACRES	97074	FT <sup>2</sup>
STAGING AREA	193	ACRES	84251	FT <sup>2</sup>
ISTHMUS	17	ACRES	50815	FT <sup>2</sup>
d. PRESENT ZONING NT				
e. NA, TEMPORARY MAINTENANCE EMPLOYEES				

PERMIT INFORMATION CHART

Subdivision Name	Section/Area	SECTION 1	Lot/Parcel No.	LOT 14	
COLUMBIA TOWN CENTER					
Plot # or L/F	Grid #	Zoning	Tax Map No.	Elect. Distr.	Census Tract
PHASE 23 PLAT BOOK 15 FOLD 19 & 20	20/2	NT	30 & 35	AS	6054.02 695692
Water Code	Sewer Code				

REVISIONS

NO.	DATE	ITEM	BY
3	04/21/14	SHEETS 47 TO 59 TO BE ADDED TO PLAN SET TO INCLUDE TRAIL WORK	MB
		SHEET 3 OF 59: PLAN VIEW REVISED TO SHOW PROPOSED CONSTRUCTION ACCESS	
		SHEET 4 OF 59: PLAN VIEW REVISED TO SHOW EXISTING PATHS TO BE PAVED	

REVISIONS

NO.	DATE	ITEM	BY
2	01/16/13	SHEETS 38 TO 46 TO BE ADDED TO PLAN SET TO INCLUDE DAM REPAIR	SB
		SHEET 4 OF 46: PLAN VIEW REVISED TO SHOW DAM SPILLWAY STRUCTURE TO BE REPAIRED	

1 PATH WIDENING REDLINE REVISION IS SUBJECT TO WAIVER OF SUBSECTIONS 16.115(c)(2) and 16.116(a)(2)(iii) APPROVED ON NOVEMBER 8, 2012.

REVISIONS

NO.	DATE	ITEM	BY
1	12/06/12	SHEET 4 OF 37: PLAN VIEW REVISED TO SHOW EXISTING PAVED PATH TO BE WIDENED TO 10 FT WIDE	SB

3 TRAIL PAVING REDLINE REVISION IS SUBJECT TO CONDITIONS OF APPROVAL OF WAIVER PETITION WP-14-079 APPROVED ON FEBRUARY 18, 2014.

APPROVED: DEPARTMENT OF PLANNING AND ZONING

*[Signature]* 12/23/09  
Chief, Development Engineering Division Date

*[Signature]* 1/27/10  
Chief, Division of Land Development Date

*[Signature]* 1/7/10  
Director, DEP Date

Maryland Department of the Environment  
MDE Water Management Administration  
Dam Safety Division

*[Signature]* 11/10/09  
V. P. Dalal  
Regulatory & Compliance Engineer

PROFESSIONAL CERTIFICATION. I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 28997, EXPIRATION DATE: 01-14-2010

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
8700 LAKE WRIGHT DRIVE  
SUITE 500  
NORFOLK, VIRGINIA 23502  
757-222-1800

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.  
11-24-2009

COLUMBIA ASSOCIATION  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947

COLUMBIA ASSOCIATION  
TOWN CENTER

MINOR GRADING IN SUPPORT OF  
LAKE KITTAMAQUUNDI RESTORATION  
ELECTION DISTRICT 5, HOWARD COUNTY MD.  
TAX MAP 30 AND 36

SCALE AS SHOWN  
JUNE 18, 2009

DRAWING SHEET 1 OF 59  
SDP-08-108

**HOWARD COUNTY  
GENERAL NOTES:**

1. All construction shall be in accordance with the latest standards and specifications of Howard County plus MSHA standards and specifications if applicable.
2. The contractor shall notify the Department of Public Works/Bureau of Engineering/Construction Inspection Division at (410) 313-1880 24-hours prior to the start of work.
3. The contractor shall notify "Miss Utility" at 1-800-257-7777 at least 48 hours prior to any excavation work being done.
4. Traffic control devices, markings and signing shall be in accordance with the latest edition of the Manual of Uniform Traffic Control Devices (MUTCD). All street and regulatory signs shall be in place prior to the placement of any asphalt.
5. Street light placement and the type of fixture and pole shall be in accordance with the Howard County Design Manual, Volume III (1993) and as modified by "Guidelines for Street Lights in Residential Developments (June 1993)". A minimum spacing of 20' shall be maintained between any streetlight and any tree.
6. All sign posts used for traffic control signs installed in the County right-of-way shall be mounted on a 2" galvanized steel perforated, square tube post (14 gauge) inserted into a 2-1/2" galvanized steel perforated, square tube sleeve (12 gauge) - 3' long. A galvanized steel pole cap shall be mounted on top of each post.
7. All plan dimensions are to face of curb unless otherwise noted.
8. The existing topography is taken from aerial survey with (maximum two foot) contour intervals prepared by Mercedo Consultants Inc. dated 5-22-06.
9. The coordinates shown hereon are based upon the Howard County Geodetic Control which is based upon the Maryland State Plane Coordinate System. Howard County Monument Nos. A109, 371C and "Harris AZ Mark" were used for this project.
10. No permanent increase in impervious area.
11. Existing utilities are based on GIS mapping.
12. No floodplain study was prepared for this project.
13. Project background information (unless included in title block):
  - Hydraulically dredging the upper half of the lake to its original depths.
  - Pumping the dredged material to a temporary staging area on the South Entrance Road for mechanical dewatering.
  - Trucking dewatered material to an off-site licensed placement facility.
  - Constructing a peninsula and wetlands in the upper portion of the lake to create a Forebay.
  - Install access road on isthmus with turf reinforced matting and placement of riprap at existing overflow areas on the isthmus to prevent further erosion.
  - Providing imbricated riprap for erosion protection at select spots on the right bank of the Little Patuxent River.
  - Restoration of all disturbed areas, including removal of gravel & paving at the staging area.
14. No grading, removal of vegetative cover or trees, paving or new structures shall be permitted outside the limits of disturbance in wetlands, streams, or their associated buffers, forest conservation easements, or 100-year floodplain without DPZ approval.
15. This subject property is zoned NT per the February 2, 2004 Comprehensive Zoning Plan and per the "Comp Life" Zoning Amendments effective July 28, 2006.
16. This project is exempt from the requirements of Section 16J24 of the Howard County Code for Landscaping since disturbance resulting from project activities is temporary and no permanent structures are proposed.
17. This project is exempt from the requirements of Section 16J200 of the Howard County Code for Forest Conservation since it is part of a Planned Unit Development which had preliminary development plan approval and 50% or more of the land was recorded and substantially developed before December 31, 1992.
18. The Contractor shall be responsible for repairs to property damage caused by the Contractor.
19. Project is subject to approval by the U.S. Army Corps of Engineers, Baltimore District, the MDE Nonpoint Wetlands and Waterways Division, and the MDE Dam Safety Division. Copies of the applicable permits or authorizations shall be submitted to the DPZ, Division of Land Development. MDE permit tracking number is 200863535.
20. The Contractor shall comply with all applicable Federal, State and Local Laws and Regulations including project permits. Effluent leaving the site shall not exceed Maryland turbidity limits of 150 NTU at any time or 50 NTU as a monthly average per COMAR 26.08.02.
21. No wetland areas landward of the ordinary high water are disturbed by the project. Wetlands within the lake (mainly nonperennial emergent and lacustrine unconsolidated bottom wetlands) are subject to disturbance from project activity, refer to JPA 2008-63535.M02.
22. WP-17-110 to allow the installation of five Poster Tree art sculptures within Kennedy Gardens adjacent to Lake Kittamaquundi was approved on May 16, 2017, subject to these conditions:
  - All Grading and clearing shall be minimized to the extent required to install five proposed tree sculptures. Any disturbed areas must be returned to the existing grade, and stabilized as appropriate.
  - The petitioner shall obtain state and federal authorization of regulated activities, if applicable.
  - The petitioner shall obtain all required permits from the Howard County Department of Inspections, Licenses and Permits.
  - Include the alternative compliance request number, description, and decision on all associated plans, and permits.

**HOWARD SOIL CONSERVATION DISTRICT  
STANDARD SEDIMENT CONTROL NOTES**

1. A minimum of 24 hours notice must be given to the Howard County Department of Inspection, Licenses and Permits, Sediment Control Division prior to the start of any construction (313-1855).
2. All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the most current MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL and revisions thereto.
3. Following initial soil disturbance or re-disturbance, permanent or temporary stabilization shall be completed within a 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all slopes greater than 3:1. b) 14 days as to all other disturbed or graded areas on the project site.
4. All sediment traps/basins shown must be fenced and warning signs posted around their perimeter in accordance with Vol I, Chapter 12 of the HOWARD COUNTY DESIGN MANUAL, Storm Drainage.
5. All disturbed areas must be stabilized within the time period specified above in accordance with the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for permanent seeding (Sec. 51), sod (Sec. 54), temporary seeding (Sec. 50) and mulching (Sec. 52). Temporary stabilization with mulch alone can only be done when recommended seeding dates do not allow for proper germination and establishment of grasses.
6. All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.
7. Site Analysis: Staging Area
 

Total Area of Site	1.06 Acres
Area Disturbed	1.91 Acres
Area to be roofed or paved	0.00 Acres
Area to be vegetatively stabilized	0.42 Acres
Total Cut	11.09 Cu.Yds.
Total Fill	11.09 Cu.Yds.
Total Dredging Values per 2006 Bathymetric Survey	Cu.Yds.
Offsite waste/borrow area location:	Site with an approved sediment control plan and active permit, as approved by the Inspector and Howard SCD.
8. Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
9. Additional sediment control must be provided, if deemed necessary by the Howard County Sediment Control Inspector.
10. On all sites with disturbed areas in excess of 2 acres, approval of the Inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the Inspection agency is made.
11. Trenches for the construction of utilities is limited to three pipe lengths or that which shall be back-filled and stabilized by the end of each work day, whichever is shorter.

Site Analysis: Isthmus Area

Total Area of Site	0.66 Acres
Area Disturbed	1.91 Acres
Area to be roofed or paved	0.00 Acres
Area to be vegetatively stabilized	0.85 Acres
Total Cut	254 Cu.Yds.
Total Fill	252 Cu.Yds.
Offsite waste/borrow area location:	On Site

**HOWARD SOIL CONSERVATION DISTRICT  
PERMANENT SEEDING NOTES:**

Apply to graded or cleared areas not subject to immediate further disturbance where a permanent long-lived vegetative cover is needed.

Seedbed Preparation: Loosen upper three inches of soil by raking, disk or other acceptable means before seeding, if not previously loosened.

Soil Amendments: In lieu of soil test recommendations, use one of the following schedules:

1. Preferred - Apply 2 tons/acre dolomitic limestone (92 lbs/1000 sq.ft.) and 600 lbs/acre 10-10-10 fertilizer (14 lbs/1000 sq.ft.) before seeding. Harrow or disk into upper three inches of soil. At time of seeding, apply 400 lbs/acre 30-0-0 ureaform fertilizer (9 lbs/1000 sq.ft.)
2. Acceptable - Apply 2 tons/acre dolomitic limestone (92 lbs/1000 sq.ft.) and 1000 lbs/acre 10-10-10 fertilizer (23 lbs/1000 sq.ft.) before seeding. Harrow or disk into upper three inches of soil.

Seeding - For the periods March 1 - April 30, and August 1 - October 15, seed with 60 lbs/acre (1.4 lbs/1000 sq.ft.) of Kentucky 31 Tall Fescue. For the period May 1 - July 31, seed with 60 lbs Kentucky 31 Tall Fescue per acre and 2 lbs/acre (0.5 lbs/1000 sq.ft.) of weeping lovegrass. During the period of October 16 - February 28, protect site by:

Option 1 - Two tons per acre of well anchored straw mulch and seed as soon as possible in the spring.  
Option 2 - Use sod.  
Option 3 - Seed with 60 lbs/acre Kentucky 30 Tall Fescue and mulch with 2 tons/acre well anchored straw.

Mulching - Apply 1-1/2 to 2 tons per acre (70 to 90 lbs/1000 sq.ft.) of unrattled small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gallons per acre (5 gal/1000 sq.ft.) of emulsified asphalt on flat areas. On slope 8 feet or higher, use 348 gallons per acre (8 gal/1000 sq.ft.) for anchoring.

Maintenance - Inspect all seeding areas and make needed repairs, replacements and reseedings.

**TEMPORARY SEEDING NOTES:**

Apply to graded or cleared areas likely to be re-disturbed where a short-term vegetative cover is needed.

Seedbed preparation: - Loosen upper three inches of soil by raking, disk or other acceptable means before seeding, if not previously loosened.


Soil Amendments: - Apply 600 lbs/acre 10-10-10 fertilizer (14 lbs/1000 sq.ft.).

Seeding: - For periods March 1 - April 30 and from August 15 - October 15, seed with 2-1/2 bushel per acre of annual rye (3.2 lbs/1000 sq.ft.). For the period May 1 - August 14, seed with 3 lbs/acre of weeping lovegrass (0.7 lbs/1000 sq.ft.). For the period November 16 - February 28, protect site by applying 2 tons/acre of well anchored straw mulch and seed as soon as possible in the spring, or use sod.

Mulching: - Apply 1-1/2 to 2 tons/acre (70 to 90 lbs/1000 sq.ft.) of unrattled weed-free, small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gal. per acre (5 gal/1000 sq.ft.) of emulsified asphalt on flat areas. On slope 8 ft. or higher, use 348 gal. per acre (8 gal/1000 sq.ft.) for anchoring.

Refer to the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for additional rates and methods not covered.

2/24/17	1	RECONSTRUCTION OF BELL TREE/NEW POSTER TREES
DATE	NO.	REVISION DESCRIPTION



**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]* 12/23/09  
Chief, Development Engineering Division, Date

*[Signature]* 1/01/10  
Chief, Division of Land Development, Date

*[Signature]* 1/7/10  
Director, DEP, Date

Maryland Department of the Environment  
MDE Water Management Administration  
Dam Safety Division

*[Signature]* 12/1/09  
V. P. Dalal  
Regulatory & Compliance Engineer

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.  
11-27-2009


**COLUMBIA ASSOCIATION**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947

**COLUMBIA ASSOCIATION  
TOWN CENTER**

**MINOR GRADING IN SUPPORT OF  
LAKE KITTAMAQUINDI RESTORATION  
ELECTION DISTRICT 5, HOWARD COUNTY MD.  
TAX MAP 30 AND 36**

SCALE AS SHOWN  
JUNE 18, 2009

DRAWING A-01, SHEET 2 OF 59  
SDP-08-108



**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
 Chief, Development Engineering Division  
 Date 12/23/09


*[Signature]*  
 Chief, Division of Land Development  
 Date 1/07/10

*[Signature]*  
 Director, DEP.  
 Date 1/2/10

Maryland Department of the Environment  
 MDE Water Management Administration  
 Dam Safety Division  
*V.P. Dalal* 12/1/09  
 Vistay P. Dalal  
 Regulatory & Compliance Engineer

THIS PLAN SET HAS BEEN PREPARED BY:  
**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 300  
 NORFOLK, VIRGINIA 23502  
 757-222-1600

PLANS HAVE BEEN  
 DESIGNED UNDER MY  
 SUPERVISION  
  
 PIETER DAHMEN, PE  
 HDR ENGINEERING INC.



COLUMBIA ASSOCIATION  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947




**PROJECT LOCATION PLAN**

**COLUMBIA ASSOCIATION  
 TOWN CENTER**

MINOR GRADING IN SUPPORT OF  
 LAKE KITTAMAQUINDI RESTORATION  
 ELECTION DISTRICT #, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36

SCALE AS SHOWN  
 JUNE 18, 2009


DRAWING A-02, SHEET 3 OF 59  
 SDP-08-108



SHEET B-04

SHEET B-03

SHEET B-02



**TYPICAL PATH WIDENING SECTION**  
N.T.S.

**NOTE: STORMWATER MANAGEMENT SHALL BE ADDRESSED WITH DISCONNECTION OF NON-ROOFTOP RUNOFF CREDIT**

RT. 29

**2,150 LF OF EXISTING 8-FT WIDE, PAVED PATH TO BE EXPANDED TO 10-FT WIDE AND REPAVED ACCORDING TO THE TYPICAL PATH WIDENING SECTION THIS SHEET.**

**578 LF OF AN EXISTING GRASS TRAIL & 221 LF OF AN EXISTING GRAVEL TRAIL TO BE PAVED. SEE SHEETS 47-59.**


**220 LF PROPOSED BOARDWALK. SEE SHEETS 47-59.**

**1,571 LF OF AN EXISTING GRAVEL TRAIL TO BE PAVED. SEE SHEETS 47-59.**

**LEGEND:**

- EXISTING CONTOURS
- EXISTING BATHYMETRY
- ← DIRECTION OF WATER FLOW
- EDGE OF WATER
- BATHYMETRIC SURVEY LIMITS
- EXISTING WETLANDS
- STREAM BUFFER
- WETLAND BUFFER
- PARCEL LINE
- 100 YEAR FLOOD PLAIN
- 15% - 25% SLOPES
- SLOPES > 25%

**NOTE:**  
BATHYMETRIC SURVEY OF LAKE BOTTOM, COMPLETED ON 5/22/2006, IS SUBJECT TO CHANGE.



**LAKE KITTAMAQUNDI RESTORATION PROJECT  
EXISTING CONDITIONS AND WETLAND  
DELINEATION SITE PLAN KEY**

**COLUMBIA ASSOCIATION  
TOWN CENTER**

**MINOR GRADING IN SUPPORT OF  
LAKE KITTAMAQUNDI RESTORATION  
ELECTION DISTRICT 5, HOWARD COUNTY MD.  
TAX MAP 30 AND 36**

SCALE AS SHOWN  
JUNE 18, 2009

DRAWING B-01, SHEET 4 OF 59

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
Chief, Development Engineering Division  
Date: 12/23/09

*[Signature]*  
Chief, Division of Land Development  
Date: 1/07/10

*[Signature]*  
Director  
Date: 1/2/10

MDE Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division

*[Signature]*  
V.P. Dalal  
Regulatory & Compliance Engineer

THIS PLAN SET HAS BEEN PREPARED BY:


**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 200  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN  
DESIGNED UNDER MY  
SUPERVISION

*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.

STATE OF MARYLAND  
Professional Engineer  
11-24-2009


**COLUMBIA ASSOCIATION  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947**



**LEGEND:**

- EXISTING CONTOURS
- EXISTING BATHYMETRY
- ← DIRECTION OF WATER FLOW
- EDGE OF WATER
- BATHYMETRIC SURVEY LIMITS
- STREAM BUFFER
- WETLAND BUFFER
- PARCEL LINE
- ▨ EXISTING WETLANDS
- 100 YEAR FLOOD PLAIN
- ▨ 15%-25% SLOPES
- ▨ SLOPES > 25%

**NOTE:**  
 BATHYMETRIC SURVEY OF LAKE BOTTOM, COMPLETED ON 5/22/2006, IS SUBJECT TO CHANGE.



**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

Chief, Development Engineering Division  
 Date: 1/12/10

Chief, Division of Land Development  
 Date: 1/07/10

Director, DEP  
 Date: 1/7/10

Maryland Department of the Environment  
 MDE Water Management Administration  
 Dam Safety Division

V.P. Dalal 12/1/09  
 Visty P. Dalal  
 Regulatory & Compliance Engineer

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**

HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 300  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

PIETER DAHMEN, PE  
 HDR ENGINEERING INC.



**COLUMBIA ASSOCIATION**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947

**LAKE KITTAMAQUNDI RESTORATION PROJECT**  
**EXISTING CONDITIONS AND WETLAND DELINEATION PLAN AREA 01**


**COLUMBIA ASSOCIATION TOWN CENTER**

**MINOR GRADING IN SUPPORT OF LAKE KITTAMAQUNDI RESTORATION**  
**ELECTION DISTRICT 5, HOWARD COUNTY MD.**  
**TAX MAP 30 AND 36**


SCALE AS SHOWN  
 JUNE 18, 2009


DRAWING B-02, SHEET 5 OF 59


C:\w\sdp\p\p\m\080808\KTT.dwg, KTT-0-02, 11/20/09 12:01 PM, emms





**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

  
 Chief, Development Engineering Division  
 Date: 11/2/09

  
 Chief, Division of Land Development  
 Date: 11/07/10



  
 Director, DEP.  
 Date: 11/2/10


 Maryland Department of the Environment  
 Water Management Administration  
 Dam Safety Division  
  
 V.P. Datal  
 Regulatory & Compliance Engineer  
 Date: 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:

  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 300  
 NORFOLK, VIRGINIA 23502  
 757-222-1500


PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

  
 PIETER DAHMEN, PE  
 HDR ENGINEERING INC.  
  
 11-24-2009

COLUMBIA ASSOCIATION  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947

**LAKE KITTAMAQUONDI RESTORATION PROJECT  
EXISTING CONDITIONS AND WETLAND  
DELINEATION PLAN AREA 01**

**COLUMBIA ASSOCIATION  
TOWN CENTER**  
 MINOR GRADING IN SUPPORT OF  
 LAKE KITTAMAQUONDI RESTORATION  
 ELECTION DISTRICT 5, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36  
 SCALE AS SHOWN  
 JUNE 18, 2009  
 DRAWING B-02, SHEET 5 OF 37



**LEGEND:**

- - - - - EXISTING CONTOURS
- - - - - EXISTING BATHYMETRY
- ← DIRECTION OF WATER FLOW
- EDGE OF WATER
- - - - - BATHYMETRIC SURVEY LIMITS
- STREAM BUFFER
- - - - - WETLAND BUFFER
- - - - - PARCEL LINE
- [Cross-hatched] EXISTING WETLANDS
- - - - - 100 YEAR FLOOD PLAIN
- [Stippled] 15% - 25% SLOPES
- [Dotted] SLOPES > 25%

**NOTE:**  
BATHYMETRIC SURVEY OF LAKE BOTTOM, COMPLETED ON 5/22/2006, IS SUBJECT TO CHANGE.

0 50 100  
SCALE IN FEET

**LAKE KITTAMAQUNDI RESTORATION PROJECT  
EXISTING CONDITIONS AND WETLAND  
DELINEATION PLAN AREA 02**

**COLUMBIA ASSOCIATION  
TOWN CENTER**

**MINOR GRADING IN SUPPORT OF  
LAKE KITTAMAQUNDI RESTORATION  
ELECTION DISTRICT #, HOWARD COUNTY MD.  
TAX MAP 30 AND 36**

SCALE AS SHOWN  
JUNE 18, 2009

DRAWING B-03, SHEET 6 OF 59

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
Chief, Development Engineering Division, Date 12/2/09

*[Signature]*  
Chief, Division of Land Development, Date 1/27/10

*[Signature]*  
Director, DEP, Date 1/3/10

Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division

*V.P. Dalal* 12/1/09  
Visty P. Dalal  
Regulatory & Compliance Engineer

THIS PLAN SET HAS BEEN PREPARED BY:


**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN  
DESIGNED UNDER MY  
SUPERVISION

*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC. 11-24-2009

**COLUMBIA ASSOCIATION  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947**

C:\working\pitt\land\sd080308-011T.dwg, 11/2/2009 9:42:49 AM, dmmf



**LEGEND:**

- EXISTING CONTOURS
- EXISTING BATHYMETRY
- ← DIRECTION OF WATER FLOW
- EDGE OF WATER
- BATHYMETRIC SURVEY LIMITS
- STREAM BUFFER
- WETLAND BUFFER
- PARCEL LINE
- ▨ EXISTING WETLANDS
- 100 YEAR FLOOD PLAIN
- 15%-25% SLOPES
- SLOPES > 25%

**NOTE:**  
BATHYMETRIC SURVEY OF LAKE BOTTOM, COMPLETED ON 5/22/2006, IS SUBJECT TO CHANGE.

0 50 100  
SCALE IN FEET

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
Chief, Development Engineering Division  
Date 12/23/09

*[Signature]*  
Chief, Division of Land Development  
Date 1/07/10

*[Signature]*  
Director, DEP.  
Date 1/7/10

Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division


*[Signature]* 12/1/09  
V.P. Dalal  
Regulatory & Compliance Engineer

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 300  
NOFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.



**COLUMBIA ASSOCIATION**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947

**LAKE KITTAMAQUNDI RESTORATION PROJECT  
EXISTING CONDITIONS AND WETLAND  
DELINEATION PLAN AREA 03**

**COLUMBIA ASSOCIATION  
TOWN CENTER**



**MINOR GRADING IN SUPPORT OF  
LAKE KITTAMAQUNDI RESTORATION  
ELECTION DISTRICT #, HOWARD COUNTY MD.  
TAX MAP 30 AND 36**

SCALE AS SHOWN  
JUNE 18, 2009


DRAWING B-04, SHEET 7 OF 59

C:\p\working\PTT\Tamaqundi\KITT.MXD, KITT.B-04, 11/24/2009 9:45:38 AM, Events





DREDGE AREA	NORMAL POOL ELEVATION (FT.)	AVERAGE EXISTING LAKE BOTTOM ELEVATION (FT.)	AVERAGE EXISTING LAKE DEPTH (FT.)	AVERAGE ASSUMED ORIGINAL LAKE BOTTOM ELEVATION (FT.)	AVERAGE ASSUMED ORIGINAL LAKE DEPTH (FT.)	AREA TO BE DREDGED (SQ. FT.)	DREDGE VOLUME TO OBTAIN ASSUMED ORIGINAL LAKE BOTTOM ELEVATION (CU. YD.)
AREA 01	297.7	295.8	1.9	292.0	5.7	265,746	25,699
AREA 02	297.7	294.3	3.4	292.0	5.7	196,852	11,143
AREA 03	297.7	292.7	5.0	292.0	5.7	146,732	3,289
							TOTAL 40,131



**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
 Chief, Development Engineering Division  
 Date: 12/2/09

*[Signature]*  
 Chief, Division of Land Development  
 Date: 1/07/10

*[Signature]*  
 Director, DEP.  
 Date: 1/2/10

Maryland Department of the Environment  
 MDE Water Management Administration  
 Dam Safety Division  
*V.P. Dalal* 12/1/09  
 Visty P. Dalal  
 Regulatory & Compliance Engineer

THIS PLAN SET HAS BEEN PREPARED BY:  
**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 300  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION  
*[Signature]*  
 PIETER DAHMEN, PE  
 HDR ENGINEERING INC.  
 11-27-2009

**COLUMBIA ASSOCIATION**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947

DATE	NO.	REVISION DESCRIPTION
2/24/17	1	RECONSTRUCTION OF BELL TREE/NEW POSTER TREES


**LAKE KITTAMAQUNDI RESTORATION PROJECT  
 PROPOSED SEDIMENT CONTROL AND  
 DREDGING PLAN KEY**

**COLUMBIA ASSOCIATION  
 TOWN CENTER**

MINOR GRADING IN SUPPORT OF  
 LAKE KITTAMAQUNDI RESTORATION  
 ELECTION DISTRICT 5, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36

SCALE AS SHOWN  
 JUNE 18, 2009  
 DRAWING C-01, SHEET 8 OF 59  
 SDP-08-108

C:\Working\PT\Drawings\SDP-08-108.dwg, KITT 2405, 11/24/2009 11:52:59 AM, jhdg




**LEGEND:**

- PROPOSED PENINSULA & EXPANDED ISLAND 2 FT ABOVE LAKE ELEVATION
- EXISTING ISLAND (NOT TO BE DISTURBED)
- PROPOSED RIPRAP
- PROPOSED WETLAND AREA
- PROPOSED IMBRICATED RIPRAP
- PROPOSED PERMANENT ISTHMUS ACCESS ROAD
- PROPOSED DREDGE AREA
- PROPOSED EROSION CONTROL MATTING
- PROPOSED CONTOURS
- EXISTING CONTOURS
- EXISTING BATHYMETRY
- DIRECTION OF WATER FLOW
- EDGE OF WATER
- LIMIT OF DISTURBANCE
- 100 YEAR FLOOD PLAIN
- PARCEL LINE
- 15%-25% SLOPES
- SLOPES > 25%

**NOTES:**

- SIDE SLOPE BASED ON A 3:1 RATIO.
- CROSS SECTION SPACING IS 100 FEET.



DREDGE AREA	NORMAL POOL ELEVATION (FT.)	AVERAGE EXISTING LAKE BOTTOM ELEVATION (FT.)	AVERAGE EXISTING LAKE DEPTH (FT.)	AVERAGE ASSUMED ORIGINAL LAKE BOTTOM ELEVATION (FT.)	AVERAGE ASSUMED ORIGINAL LAKE DEPTH (FT.)	AREA TO BE DREDGED (SQ. FT.)	DREDGE VOLUME TO OBTAIN ASSUMED ORIGINAL LAKE BOTTOM ELEVATION (CU. YD.)
AREA 01	297.7	295.8	1.9	292.0	5.7	265,746	25,699

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
 Chief, Development Engineering Division  
 Date: 12/21/09

*[Signature]*  
 Chief, Division of Land Development  
 Date: 1/2/10

*[Signature]*  
 Director, DEP.  
 Date: 1/7/10

Maryland Department of the Environment  
 Water Management Administration  
 Dam Safety Division

*[Signature]*  
 V.P. Dalal 12/1/09  
 Regulatory & Compliance Engineer

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 300  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
 PIETER DAHMEN, PE  
 HDR ENGINEERING INC.  
 11-27-2009

**COLUMBIA ASSOCIATION**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947



**LAKE KITTAMAQUONDI RESTORATION PROJECT**  
**PROPOSED SEDIMENT CONTROL AND DREDGING PLAN AREA 01**

**COLUMBIA ASSOCIATION TOWN CENTER**

MINOR GRADING IN SUPPORT OF LAKE KITTAMAQUONDI RESTORATION  
 ELECTION DISTRICT 6, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36

SCALE AS SHOWN  
 JUNE 18, 2009

DRAWING C-02, SHEET 9 OF 59



NOTE:  
1. THE 5' MINIMUM BUFFER, VARIES AT PROPOSED WETLAND CREATION AREAS.

**TYPICAL DREDGING SECTION**  
NTS

- LEGEND:**
- PROPOSED PENINSULA & EXPANDED ISLAND 2 FT ABOVE LAKE ELEVATION
  - EXISTING ISLAND (NOT TO BE DISTURBED)
  - PROPOSED RIPRAP
  - PROPOSED WETLAND AREA
  - PROPOSED IMBRICATED RIPRAP
  - PROPOSED PERMANENT ISTHMUS ACCESS ROAD
  - PROPOSED DREDGE AREA
  - PROPOSED EROSION CONTROL MATTING
  - PROPOSED CONTOURS
  - EXISTING CONTOURS
  - EXISTING BATHYMETRY
  - DIRECTION OF WATER FLOW
  - EDGE OF WATER
  - LIMIT OF DISTURBANCE
  - 100 YEAR FLOOD PLAN
  - PARCEL LINE
  - 15%-25% SLOPES
  - SLOPES > 25%

NOTES:  
1. SIDE SLOPE BASED ON A 3:1 RATIO.  
2. CROSS SECTION SPACING IS 100 FEET.

DREDGE AREA	NORMAL POOL ELEVATION (FT.)	AVERAGE EXISTING LAKE BOTTOM ELEVATION (FT.)	AVERAGE EXISTING LAKE DEPTH (FT.)	AVERAGE ASSUMED ORIGINAL LAKE BOTTOM ELEVATION (FT.)	AVERAGE ASSUMED ORIGINAL LAKE DEPTH (FT.)	AREA TO BE DREDGED (SQ. FT.)	DREDGE VOLUME TO OBTAIN ASSUMED ORIGINAL LAKE BOTTOM ELEVATION (CU. YD.)
AREA 02	297.7	294.3	3.4	292.0	5.7	196,852	11,143

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
Chief, Development Engineering Division  
Date: 12/23/09


*[Signature]*  
Chief, Division of Land Development  
Date: 1/01/10

*[Signature]*  
Director, DEP  
Date: 1/2/10

Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division  
**V. P. Dalal**  
Visty P. Dalal  
Regulatory & Compliance Engineer  
Date: 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:  
**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA 23502  
757-222-1500


PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION  
**PIETER DAHMEN, PE**  
HDR ENGINEERING INC.  
Date: 11-24-2009



**COLUMBIA ASSOCIATION**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947

**LAKE KITTAMAQUUNDI RESTORATION PROJECT  
PROPOSED SEDIMENT CONTROL AND  
DREDGING PLAN AREA 02**

**COLUMBIA ASSOCIATION  
TOWN CENTER**  
MINOR GRADING IN SUPPORT OF  
LAKE KITTAMAQUUNDI RESTORATION  
ELECTION DISTRICT #, HOWARD COUNTY MD.  
TAX MAP 30 AND 36  
SCALE AS SHOWN  
JUNE 18, 2009  
DRAWING C-03, SHEET 10 OF 59  
SDP-08-108




**LEGEND:**

- PROPOSED PENINSULA & EXPANDED ISLAND 2 FT ABOVE LAKE ELEVATION
- EXISTING ISLAND (NOT TO BE DISTURBED)
- PROPOSED RIPRAP
- PROPOSED WETLAND AREA
- PROPOSED IMBRICATED RIPRAP
- PROPOSED PERMANENT ISTHMUS ACCESS ROAD
- PROPOSED DREDGE AREA
- PROPOSED EROSION CONTROL MATTING
- PROPOSED CONTOURS
- EXISTING CONTOURS
- EXISTING BATHYMETRY
- DIRECTION OF WATER FLOW
- EDGE OF WATER
- LIMIT OF DISTURBANCE
- PARCEL LINE
- 100 YEAR FLOOD PLAIN
- 15% - 25% SLOPES
- SLOPES > 25%

**NOTES:**

- SIDE SLOPE BASED ON A 3:1 RATIO.
- CROSS SECTION SPACING IS 100 FEET.



NOTE:  
1. THE 5' MINIMUM BUFFER, VARIES AT PROPOSED WETLAND CREATION AREAS.

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*John Deane*  
Chief, Development Engineering Division, 12/23/09  
Date

*Kent Stankovic*  
Chief, Division of Land Development, 1/07/10  
Date

*Dennis E. Antler*  
Director, DEP, 1/2/10  
Date

Maryland Department of the Environment  
MDE Water Management Administration  
Dam Safety Division

*V.P. Dalal*  
Visty P. Dalal  
Regulatory & Compliance Engineer 12/1/09


DREDGE AREA	NORMAL POOL ELEVATION (FT.)	AVERAGE EXISTING LAKE BOTTOM ELEVATION (FT.)	AVERAGE EXISTING LAKE DEPTH (FT.)	AVERAGE ASSUMED ORIGINAL LAKE BOTTOM ELEVATION (FT.)	AVERAGE ASSUMED ORIGINAL LAKE DEPTH (FT.)	AREA TO BE DREDGED (SQ. FT.)	DREDGE VOLUME TO OBTAIN ASSUMED ORIGINAL LAKE BOTTOM ELEVATION (CU. YD.)
AREA 03	297.7	292.7	5.0	292.0	5.7	146,732	3,289

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 500  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*Pieter Dahmen*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC. 11-29-2009



**COLUMBIA ASSOCIATION**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947


**LAKE KITTAMAQUNDI RESTORATION PROJECT  
PROPOSED SEDIMENT CONTROL AND  
DREDGING PLAN AREA 03**

**COLUMBIA ASSOCIATION  
TOWN CENTER**


MINOR GRADING IN SUPPORT OF  
LAKE KITTAMAQUNDI RESTORATION  
ELECTION DISTRICT #, HOWARD COUNTY MD.  
TAX MAP 30 AND 36

SCALE AS SHOWN  
JUNE 18, 2009


DRAWING C-04, SHEET 11 OF 59




CROSS-SECTION A1 A1  
C-02




CROSS-SECTION A2 A2  
C-02




CROSS-SECTION A3 A3  
C-02




CROSS-SECTION A4 A4  
C-02




CROSS-SECTION A5 A5  
C-02




CROSS-SECTION A6 A6  
C-02



CROSS-SECTION A7 A7  
C-02



CROSS-SECTION A8 A8  
C-02



**LEGEND:**  
 --- EXISTING BATHYMETRY  
 ——— PROPOSED BATHYMETRY

**NOTES:**  
 1. SEE SHEET F2 FOR DETAILS REGARDING PROPOSED PENINSULAR WETLAND CREATION AREA AND CONTAINMENT BERM.

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
 Chief, Development Engineering Division 12/20/09  
Date


*[Signature]*  
 Chief, Division of Land Development 1/07/10  
Date

*[Signature]*  
 Director, DEP. 1/7/10  
Date

MDE Maryland Department of the Environment  
 Water Management Administration  
 Dam Safety Division  
*V.P. Dalal*  
 Visty P. Dalal  
 Regulatory & Compliance Engineer 12/11/09

THIS PLAN SET HAS BEEN PREPARED BY:  
**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 300  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION  
 \_\_\_\_\_  
 PIETER DAHMEN, PE  
 HDR ENGINEERING INC. 11-27-2009




**COLUMBIA ASSOCIATION**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947

**LAKE KITTAMAQUNDI RESTORATION PROJECT**  
**AREA 01**  
**CROSS-SECTIONS (1 OF 2)**


**COLUMBIA ASSOCIATION**  
**TOWN CENTER**

**MINOR GRADING IN SUPPORT OF**  
**LAKE KITTAMAQUNDI RESTORATION**  
**ELECTION DISTRICT #, HOWARD COUNTY MD.**  
**TAX MAP 30 AND 36**


SCALE AS SHOWN  
 JUNE 18, 2009  
 DRAWING C-05, SHEET 12 OF 59




CROSS-SECTION A9 A9  
C-02




CROSS-SECTION A10 A10  
C-02



CROSS-SECTION A11 A11  
C-02



CROSS-SECTION A12 A12  
C-02



**LEGEND:**  
 --- EXISTING BATHYMETRY  
 ——— PROPOSED BATHYMETRY

**NOTES:**  
 1. SEE SHEET F2 FOR DETAILS REGARDING PROPOSED PENINSULAS WETLAND CREATION AREA AND CONTAINMENT BERM.

APPROVED: DEPARTMENT OF PLANNING AND ZONING

*[Signature]*  
 Chief, Development Engineering Division

*[Signature]*  
 Chief, Division of Land Development

*[Signature]*  
 Director, DEP.

12/23/09  
 Date

1/27/10  
 Date

1/2/10  
 Date

Maryland Department of the Environment  
 Water Management Administration  
 Dam Safety Division

*[Signature]*  
 V.P. Dalal  
 Regulatory & Compliance Engineer

12/1/09  
 Date


THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 300  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
 PIETER DAHMEN, PE  
 HDR ENGINEERING INC.

11-24-2009



COLUMBIA ASSOCIATION  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947

LAKE KITTAMAQUNDI RESTORATION PROJECT  
 AREA 01  
 CROSS-SECTIONS (2 OF 2)


COLUMBIA ASSOCIATION  
 TOWN CENTER

MINOR GRADING IN SUPPORT OF  
 LAKE KITTAMAQUNDI RESTORATION  
 ELECTION DISTRICT 8, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36


SCALE AS SHOWN  
 JUNE 18, 2009

DRAWING C-06, SHEET 13 OF 37


SDP-08-108




CROSS-SECTION B1 B1  
C-03




CROSS-SECTION B2 B2  
C-03



CROSS-SECTION B3' B3  
C-03



CROSS-SECTION B4 B4  
C-03



**LEGEND:**  
 - - - EXISTING BATHYMETRY  
 ——— PROPOSED BATHYMETRY

**NOTES:**  
 1. SEE SHEET F2 FOR DETAILS REGARDING PROPOSED PENINSULAR WETLAND CREATION AREA AND CONTAINMENT BERM.

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
 Chief, Development Engineering Division, Date 12/23/09

*[Signature]*  
 Chief, Division of Land Development, Date 1/07/10

*[Signature]*  
 Director, DEP, Date 1/2/10

Maryland Department of the Environment  
 Water Management Administration  
 Dam Safety Division  
**V. P. Dalal**  
 Visty P. Dalal  
 Regulatory & Compliance Engineer  
 Date 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 300  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
**PIETER DAHMEN, PE**  
 HDR ENGINEERING INC.  
 11-27-2009

**COLUMBIA ASSOCIATION**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947


**LAKE KITTAMAQUNDI RESTORATION PROJECT**  
**AREA 02**  
**CROSS-SECTIONS**

**COLUMBIA ASSOCIATION**  
**TOWN CENTER**


**MINOR GRADING IN SUPPORT OF**  
**LAKE KITTAMAQUNDI RESTORATION**  
**ELECTION DISTRICT #, HOWARD COUNTY MD.**  
**TAX MAP 30 AND 36**

SCALE AS SHOWN  
 JUNE 18, 2009


DRAWING C-07, SHEET 14 OF 37




CROSS-SECTION C1 C1  
C-04



CROSS-SECTION C2 C2  
C-04



CROSS-SECTION C3' C3  
C-04



CROSS-SECTION C4 C4  
C-04

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
 Chief, Development Engineering Division 12/23/09  
Date

*[Signature]*  
 Chief, Division of Land Development 1/27/10  
Date

*[Signature]*  
 Director, DEP. 1/2/10  
Date

Maryland Department of the Environment  
 Water Management Administration  
 Dam Safety Division  
**V.P. Datal** 12/1/09  
 Vistry P. Datal  
 Regulatory & Compliance Engineer

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 300  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
**PIETER DAHMEN, PE**  
 HDR ENGINEERING INC. 11-24-2009

**COLUMBIA ASSOCIATION**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947

**LAKE KITTAMAQUNDI RESTORATION PROJECT**  
 AREA 03  
 CROSS-SECTIONS (1 OF 2)


**COLUMBIA ASSOCIATION**  
 TOWN CENTER

MINOR GRADING IN SUPPORT OF  
 LAKE KITTAMAQUNDI RESTORATION  
 ELECTION DISTRICT #, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36

SCALE AS SHOWN  
 JUNE 18, 2009


DRAWING C-08, SHEET 15 OF 59






**BELL TREE FENCE**

NOT TO SCALE




**POSTER TREE PLAN**

1" = 40'




**CROSS-SECTION C5**

C5  
C-04





**CROSS-SECTION C6**

C6  
C-04




**BELL TREE ELEVATIONS (FRONT & SIDE)**

NOT TO SCALE




**POSTER TREE DETAIL**

NOT TO SCALE



**BELL TREE PLAN**

NOT TO SCALE



**LEGEND:**  
 --- EXISTING BATHYMETRY  
 --- PROPOSED BATHYMETRY

**NOTES:**  
 1. SEE SHEET F2 FOR DETAILS REGARDING PROPOSED PENINSULA WETLAND CREATION AREA AND CONTAINMENT BERM.

DATE	NO.	REVISION DESCRIPTION
2/24/17	1	RECONSTRUCTION OF BELL TREE / POSTER TREES

**LAKE KITTAMAQUUNDI RESTORATION PROJECT**  
**AREA 03**  
**CROSS-SECTIONS (2 OF 2)**

**COLUMBIA ASSOCIATION TOWN CENTER**  
 MINOR GRADING IN SUPPORT OF LAKE KITTAMAQUUNDI RESTORATION  
 ELECTION DISTRICT 8, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36  
 SCALE AS SHOWN  
 JUNE 18, 2009  
 DRAWING C-09, SHEET 16 OF 59

APPROVED: DEPARTMENT OF PLANNING AND ZONING

*[Signature]*  
 Chief, Development Engineering Division  
 Date: 12/23/09

*[Signature]*  
 Chief, Division of Land Development  
 Date: 1/27/10


*[Signature]*  
 Director, DEP.  
 Date: 1/7/10

Maryland Department of the Environment  
 Water Management Administration  
 Dam Safety Division  
*[Signature]*  
 V. P. Dalal  
 Regulatory & Compliance Engineer  
 Date: 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:  
**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 300  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION  
*[Signature]*  
 PIETER DAHMEN, PE  
 HDR ENGINEERING INC.  
 11-24-2009

**COLUMBIA ASSOCIATION**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947



MATCH LINE SEE SHEET D-02

NOTE:  
 APPROXIMATE PIPELINE LOCATION.  
 ACTUAL LOCATION MAY VARY. LIMITED  
 CLEARING AS REQUIRED FOR PIPELINE  
 INSTALLATION & MAINTENANCE.  
 ALL DISTURBED AREAS TO BE  
 STABILIZED AT THE END OF EACH  
 WORKDAY WITH SEED & MULCH.

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
 Chief, Development Engineering Division, Date 12/23/09

*[Signature]*  
 Chief, Division of Land Development, Date 1/07/10

*[Signature]*  
 Director, DEP, Date 1/7/10

Maryland Department of the Environment  
 Water Management Administration  
 Dam Safety Division

*V.I. Dahl*  
 Visty P. Dalal, Regulatory & Compliance Engineer, Date 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 500  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN  
 DESIGNED UNDER MY  
 SUPERVISION

*[Signature]*  
**PIETER DAHMEN, PE**  
 HDR ENGINEERING INC.  
 11-24-2009

**COLUMBIA ASSOCIATION**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947


**PIPELINE ROUTING**  
 SHEET 1 OF 2

**COLUMBIA ASSOCIATION  
 TOWN CENTER**


**MINOR GRADING IN SUPPORT OF  
 LAKE KITTAMAQUINDI RESTORATION**  
 ELECTION DISTRICT 6, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36

SCALE AS SHOWN  
 JUNE 18, 2009


DRAWING D-01, SHEET 17 OF 37  
 SDP-08-108



MATCH LINE SEE SHEET D-01



NOTE:  
 APPROXIMATE PIPELINE LOCATION.  
 ACTUAL LOCATION MAY VARY. LIMITED  
 CLEARING AS REQUIRED FOR PIPELINE  
 INSTALLATION & MAINTENANCE.  
 ALL DISTURBED AREAS TO BE  
 STABILIZED AT THE END OF EACH  
 WORKDAY WITH SEED & MULCH.



APPROVED: DEPARTMENT OF PLANNING AND ZONING

*[Signature]*  
 Chief, Development Engineering Division  
 Date 12/23/09

*[Signature]*  
 Chief, Division of Land Development  
 Date 1/02/10

*[Signature]*  
 Director, DEP.  
 Date 1/9/10

Maryland Department of the Environment  
 Water Management Administration  
 Dam Safety Division

*V.P. Dalal*  
 V. P. Dalal  
 Regulatory & Compliance Engineer  
 Date 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
 HDR Engineering, Inc.  
 6700 LAKE WRIGHT DRIVE  
 SUITE 300  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN  
 DESIGNED UNDER MY  
 SUPERVISION

*[Signature]*  
 PIETER DAHMEN, PE  
 HDR ENGINEERING INC.  
 11-24-2009

COLUMBIA ASSOCIATION  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947

PIPELINE ROUTING  
 SHEET 2 OF 2



**COLUMBIA ASSOCIATION  
 TOWN CENTER**

MINOR GRADING IN SUPPORT OF  
 LAKE KITTAMAQUONDI RESTORATION  
 ELECTION DISTRICT 5, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36

SCALE AS SHOWN  
 JUNE 18, 2009

DRAWING D-02, SHEET 18 OF 37


SDP-08-108



**LAKE KITTAMAQUONDI EQUIPMENT AREA ACCESS ROAD ALIGNMENT DATA**

	N	E
10+00.00 POT	561,479.3699	1,352,786.5041
11+24.82 PC	561,583.8521	1,352,857.8315
13+94.40 PI	561,809.4510	1,353,005.3928
14+23.56 PT	561,792.4621	1,352,736.3551
15+61.28 POT	561,783.8142	1,352,586.9281

NOTE: R DENOTES PROPERTY LINE





**DEPARTURE SIGHT TRIANGLE**  
SCALE: 1"=100'




**LEGEND**

- SF — SILT FENCE
- SSF — SUPER SILT FENCE
- LOD — LIMITS OF DISTURBANCE
- AL — DIVERSION DIKE
- DSF — DIVERSION SILT FENCE
- - - - - 100 YEAR FLOOD PLAIN

\* - DISTANCES PER SHA STANDARDS NO. MD 104.02-02. EXACT LOCATION OF THE SIGNS WILL BE DETERMINED BY THE CONTRACTOR.



**STAGING AREA**  
 WORK AREA: 5,211 SF  
 EQUIPMENT AREA: 13,444 SF  
 MISC. AREA: 906 SF  
 TRAILER/PARKING AREA: 10,027 SF  
 TOTAL CUT: 1,109 CY  
 TOTAL FILL: 1,109 CY  
 AREA OF DISTURBANCE: 1.91 ac



- (A) 6" - CRUSHER RUN AGGREGATE, CR-6
- (B) 6" - BANK RUN GRAVEL - SUBBASE
- (C) 2" - HOT MIX ASPHALT SUPERPAVE 12.5 mm
- (D) GEOTEXTILE FABRIC

NOTE: 2 SIGNS  
 (1) SIGN ON SOUTH ENTRANCE ROAD  
 (2) SIGN ON THE RAMP

APPROVED: DEPARTMENT OF PLANNING AND ZONING

Chief, Development Engineering Division  
 Chief, Division of Land Development  
 Director, DEP

Date: 12/23/09  
 Date: 1/07/10  
 Date: 1/7/10

Maryland Department of the Environment  
 Water Management Administration  
 Dam Safety Division  
**V. P. Dalal**  
 Regulatory & Compliance Engineer


HDR  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 500  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION  
**PIETER DAHMEN, PE**  
 HDR ENGINEERING INC.

COLUMBIA ASSOCIATION  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947


STAGING AREA

**COLUMBIA ASSOCIATION TOWN CENTER**  
 MINOR GRADING IN SUPPORT OF LAKE KITTAMAQUONDI RESTORATION  
 ELECTION DISTRICT #, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36  
 SCALE AS SHOWN  
 JUNE 18, 2009  
 DRAWING E-01, SHEET 19 OF 27  
 SDP-08-108



**LEGEND**

- PROPOSED PERMANENT ISTHMUS ACCESS ROAD
- DREDGED MATERIAL
- EXISTING ISLAND - AREA NOT TO BE DISTURBED
- PROPOSED WETLAND
- RIPRAP CONTAINMENT BERM



**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
Chief, Development Engineering Division  
Date: 12/23/09

*[Signature]*  
Chief, Division of Land Development  
Date: 1/07/10

*[Signature]*  
Director, DEP.  
Date: 1/7/10

Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division

*[Signature]*  
V.P. Dalal  
Regulatory & Compliance Engineer  
Date: 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN  
DESIGNED UNDER MY  
SUPERVISION

*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.  
11-24-2009



**COLUMBIA ASSOCIATION**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947

**LAKE KITTAMAQUNDI RESTORATION PROJECT**

**WETLAND CREATION AREAS**




**COLUMBIA ASSOCIATION  
TOWN CENTER**

**MINOR GRADING IN SUPPORT OF  
LAKE KITTAMAQUNDI RESTORATION  
ELECTION DISTRICT #5, HOWARD COUNTY MD.  
TAX MAP 30 AND 36**

SCALE AS SHOWN  
JUNE 18, 2009

DRAWING **F-01**, SHEET **20** OF **37**

SDP-08-108



**LEGEND**

- (Dashed line) PROPOSED PERMANENT ISTHMUS ACCESS ROAD
- (Diagonal hatching) DREDGED MATERIAL
- (Cross-hatching) EXISTING ISLAND - AREA NOT TO BE DISTURBED
- (Stippled) PROPOSED WETLAND
- (Hexagonal pattern) RIPRAP CONTAINMENT BERM

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

<i>John...</i>	12/23/09
Chief, Development Engineering Division	Date
<i>Kat...</i>	1/07/10
Chief, Division of Land Development	Date
<i>Thomas...</i>	1/7/10
Director, DEP	Date

Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division

*V.P. Dalal*  
Vista P. Dalal  
Regulatory & Compliance Engineer  
12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA, 23502  
757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*Pieter...*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.

**COLUMBIA ASSOCIATION**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947

**LAKE KITTAMAQUNDI RESTORATION PROJECT**

**WETLAND CREATION AREAS**

**COLUMBIA ASSOCIATION TOWN CENTER**


MINOR GRADING IN SUPPORT OF LAKE KITTAMAQUNDI RESTORATION  
ELECTION DISTRICT #, HOWARD COUNTY MD.  
TAX MAP 30 AND 36

SCALE AS SHOWN  
JUNE 18, 2009

DRAWING F-02, SHEET 21 OF 37

**SDP-08-108**


C:\Program Files\Hatch\Drawings\Projects\08-108\11-10-09\11-10-09.dwg, W:\T\F-02, 11/06/09 11:43:02 AM, cmmh



N 565,500  
E 1,353,500


N 565,500

N 565,250  
E 1,354,000



**LEGEND**

- Sal** Black Willow (*Salix nigra*)
- Aln** Smooth Alder (*Alnus serrulata*)
- WETLAND TREES (GROUPS OF 3):**
- RB** River Birch (*Betula Nigra*)
- SM** Silver Maple (*Acer Saccharinum*)
- RM** Red Maple (*Acer Rubrum*)
- BE** Box Elder (*Acer Negundo*)
- AS** American Sycamore (*Platanus Occidentalis*)
- WETLAND SEED MIX**
- RIPRAP CONTAINMENT BERM**



**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

Chief, Development Engineering Division  
Date: 12/22/09

Chief, Division of Land Development  
Date: 1/27/10

Director, DEP  
Date: 1/7/10

MDE Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division


V. P. Dalal  
Regulatory & Compliance Engineer  
Date: 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
6700 LAKE WRIGHT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

PIETER DAHMEN, PE  
HDR ENGINEERING INC.



COLUMBIA ASSOCIATION  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947

**LAKE KITTAMAQUнди RESTORATION PROJECT**






**PLANTING PLAN**

**COLUMBIA ASSOCIATION TOWN CENTER**

MINOR GRADING IN SUPPORT OF LAKE KITTAMAQUнди RESTORATION  
ELECTION DISTRICT 8, HOWARD COUNTY MD.  
TAX MAP 30 AND 36


SCALE AS SHOWN  
JUNE 18, 2009

DRAWING F-03, SHEET 22 OF 37



**LEGEND**

- Sal** Black Willow (*Salix nigra*)
- Aln** Smooth Alder (*Alnus serrulata*)
- WETLAND TREES (GROUPS OF 3):**
- RB** River Birch (*Betula Nigra*)
- SM** Silver Maple (*Acer Saccharinum*)
- RM** Red Maple (*Acer Rubrum*)
- BE** Box Elder (*Acer Negundo*)
- AS** American Sycamore (*Platanus Occidentalis*)
- WETLAND SEED MIX**
- RIPRAP CONTAINMENT BERM**
- IMBRICATED RIPRAP**



**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
Chief, Development Engineering Division  
Date: 12/23/09

*[Signature]*  
Chief, Division of Land Development  
Date: 1/07/10

*[Signature]*  
Director, DEP.  
Date: 1/2/10

Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division

*[Signature]*  
V. P. Dalal  
Regulatory & Compliance Engineer  
Date: 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.

11-21-2009

COLUMBIA ASSOCIATION  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947

**LAKE KITTAMAQUNDI RESTORATION PROJECT**

**PLANTING PLAN**

**COLUMBIA ASSOCIATION TOWN CENTER**


MINOR GRADING IN SUPPORT OF LAKE KITTAMAQUNDI RESTORATION  
ELECTION DISTRICT #, HOWARD COUNTY MD.  
TAX MAP 30 AND 36

SCALE AS SHOWN  
JUNE 18, 2009


DRAWING F-04, SHEET 23 OF 27



**BALL & BURLAP DETAIL**



**PLANT STAKING DETAIL**



**PLANTING NOTES**

- W-1 Plants and seeds shall be obtained from a commercial supplier. The Contractor shall make arrangements with reliable sources to ensure that an adequate supply of the required plant and seed material is available. A source of supply shall be submitted in writing to the Project Engineer prior to beginning of construction, and shall guarantee that the plant and seed materials are being reserved or grown for the Contractor. If this requirement is not met, the Contractor will be responsible for the additional costs of supplying larger size materials, larger container size, or substitute plants chosen by the Project Engineer.
- W-2 All seed received from commercial suppliers shall be as specified in the plans. All wetland seeding shall be seeded at the specified rate in pounds of Pure Live Seed (PLS) per Acre.
- W-3 In the event that a seed specified is not commercially available, the Contractor may request a substitution in writing. All requests for substitutions shall be made at least 2 months prior to seeding and be approved by the Project Environmental Inspector. Substitute seed must meet the same testing requirements as the original seed specified.
- W-4 All plant material received from commercial suppliers shall conform to the current issue of the American Standard for Nursery Stock, published by the American Association of Nurserymen.
- W-5 Substitutions of plant material will be allowed only under the conditions specified in the Special Provision for Wetland Planting. Requests for plant material substitution must be submitted in writing at least two months prior to planting, and the substitution must be approved by the Project Environmental Inspector.
- W-6 The Contractor is responsible for installing all plant material in the appropriate season for each plant type. Trees and shrubs shall be planted during the period from November 15 through March 15 (outside the growing season). The herbaceous material shall be planted from April 15 to June 30. Any request for variance from these times of year restrictions must be submitted in writing at least two months prior to planting and must be approved by the Project Environmental Inspector.
- W-7 All plant material, unless otherwise specified, shall be uniformly shaped and have a vigorous root system. The plant material shall be healthy, vigorous, and free from defects, decay, abrasions of the bark, plant diseases, insect pest eggs, and all forms of infestations. The plant material must be fresh and free from transplant shock or visible wilt. Unhealthy plant stock and plants from cold storage are unacceptable and will be rejected.
- W-8 All container grown stock shall have been propagated in a container large enough for the roots to have developed sufficiently to hold its soil when removed from the container. Container stock with poorly developed roots is unacceptable and will be rejected.
- W-9 The Contractor shall verify all final grades prior to beginning planting work. If final grades differ from those depicted on the grading plan, the Contractor shall notify the Project Engineer and Project Environmental Inspector prior to planting in the area of concern.
- W-10 After soil preparation and prior to seeding and planting, equipment will not be permitted on the wetland planting zones without prior approval from the Project Engineer.
- W-11 Seeding in wetlands areas will not require lime or fertilizer. No seeding shall occur when the soil is frozen or flooded.
- W-12 The Contractor shall notify the Project Engineer and Project Environmental Inspector a minimum of 48 hours prior to commencing planting or seeding operations.
- W-13 Shrubs (*Alnus serrulata* and *Salix nigra*) shall be planted in cluster arrangements along the western planting area as shown on Planting Plan Sheet 8.
- W-14 - Trees (*Betula nigra*, *Fraxinus pennsylvanica*, *Acer rubrum*, *Acer saccharinum*, and *Platanus occidentalis*) shall be planted as shown on the Planting Plan (Sheets 7 and 8).
- W-15 The final location and orientation of all plant material, as well as the location of all planting zones, will be subject to the approval of the Project Environmental Inspector. The Contractor will be responsible for replanting or reseeded any plant material installed without the approval of the Project Environmental Inspector.
- W-16 Each plant shall be fertilized with 20-10-5 controlled-release tablets. The formulation specified (20-10-5) is a readily available commercial formulation. Formulations vary considerably by manufacturer, and other formulations are acceptable, provided the tablets are not readily water-soluble. The selection of fertilizer and all application specifications shall be approved by the Project Environmental Inspector prior to planting. The tablets shall be buried within the planting pit near the plant's root system. Plant stock shall be fertilized at the following rates:
 

Stock	No. of Tablets
#7 container	3
Ball & Burlap	4

 (Approximate number of tablets equals 249. Cost to be included in other pay items.)
- W-17 During planting the Contractor shall water each plant with the following minimum quantities of water, unless otherwise directed by the Project Engineer:
 

Trees	1 gallon per pit
Shrubs	1 gallon per pit
- W-18 The Contractor shall be required to guarantee and maintain all plant materials for a period of two consecutive years after date of acceptance of finished planting by the Project Engineer.

**FLOOD PLAIN WILDLIFE MIX: ERNMX-154**  
Seed at 15 pounds per acre

Percentage	Scientific Name	Common Name	Quantity
15.0%	<i>Carex vulpinoidea</i>	Fox Sedge	2.75 lbs
15.0%	<i>Elymus virginicus</i>	Virginia Wild Rye	2.75 lbs
11.0%	<i>Elymus canadensis</i>	Canada Wild Rye	2.00 lbs
10.0%	<i>Andropogon gerardii, WI Ecotype</i>	WI Ecotype Big Bluestem	1.75 lbs
7.0%	<i>Verbena hastata</i>	Blue Vervain	1.25 lbs
6.0%	<i>Heliopsis helianthoides</i>	Ox Eye Sunflower	1.00 lbs
5.0%	<i>Panicum clandestinum</i>	Tioga Deer Tongue	1.00 lbs
4.0%	<i>Carex crinita</i>	Fringed (Nodding) Sedge	0.75 lbs
4.0%	<i>Desmodium canadense</i>	Showy Tick Trefoil	0.75 lbs
3.0%	<i>Helenium autumnale</i>	Common Sneezeweed	0.50 lbs
3.0%	<i>Iris versicolor</i>	Blue Flag	0.50 lbs
2.0%	<i>Carex scoparia</i>	Blunt Broom Sedge	0.25 lbs
2.0%	<i>Carex stipata</i>	Awl Sedge	0.25 lbs
2.0%	<i>Carex vesicaria</i>	Inflated Sedge	0.25 lbs
2.0%	<i>Eupatorium perfoliatum</i>	Boneset	0.25 lbs
2.0%	<i>Panicum virgatum, Shelter</i>	Shelter Switch Grass	0.25 lbs
2.0%	<i>Verbesina alternifolia</i>	Wingstem	0.25 lbs
2.0%	<i>Vernonia gigantea</i>	Giant Ironweed	0.25 lbs
1.0%	<i>Carex squarrosa</i>	Squarrose Sedge	0.25 lbs
1.0%	<i>Carex tribuloides</i>	Bristlebract Sedge	0.25 lbs
1.0%	<i>Monarda fistulosa</i>	Wild Bergamot	0.25 lbs

**PLANTING LIST**

Common Name	Scientific Name	Indicator Status	Container Type	Minimum Size	Quantity
Silver Maple	<i>Acer saccharinum</i>	FACW	Ball & Burlap	2-3" caliper	6
Red Maple	<i>Acer rubrum</i>	FAC	Ball & Burlap	2-3" caliper	6
Box Elder	<i>Acer Negundo</i>	FACW	Ball & Burlap or #7 container	1-2" caliper	6
River Birch	<i>Betula nigra</i>	FACW	Ball & Burlap or #7 container	2-3" caliper	6
American Sycamore	<i>Platanus occidentalis</i>	FACW-	Ball & Burlap or #7 container	2-3" caliper	6
Smooth Alder	<i>Alnus serrulata</i>	OBL	#7 container	1-2" caliper	28
Black Willow	<i>Salix nigra</i>	FACW+	#7 container	1-2" caliper	15

APPROVED: DEPARTMENT OF PLANNING AND ZONING

*[Signature]*  
Chief, Development Engineering Division  
Date: 12/23/09

*[Signature]*  
Chief, Division of Land Development  
Date: 1/07/10

*[Signature]*  
Director, DEP  
Date: 1/2/10

Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division

*[Signature]*  
V. I. Dalal  
Regulatory & Compliance Engineer  
Date: 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 500  
NOFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.  
Date: 11-24-2009

COLUMBIA ASSOCIATION  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947

**LAKE KITTAMAQUNDI RESTORATION PROJECT**

**PLANTING DETAILS AND NOTES**


**COLUMBIA ASSOCIATION TOWN CENTER**

MINOR GRADING IN SUPPORT OF LAKE KITTAMAQUNDI RESTORATION ELECTION DISTRICT #, HOWARD COUNTY MD. TAX MAP 30 AND 36

SCALE AS SHOWN  
JUNE 18, 2009

DRAWING F-05, SHEET 24 OF 37


NOTE:  
STONES FOR IMBRICATED RIP RAP SHALL HAVE THE FOLLOWING MIN. DIMENSIONS:  
L - 1'-8"  
H - 9"  
W - 12"



**IMBRICATED RIPRAP ( RIVER BANK PROTECTION ) WALL SECTION**

N.T.S.  
STA. 104+85 to STA. 105+45 Lt.  
STA. 105+95 to STA. 106+82 Lt.  
STA. 108+65 to STA. 108+95 Lt.  
STA. 110+65 to STA. 111+57 Lt.


FOR INSTALLATION & MATERIAL SPECIFICATIONS, SEE **2** **F-01**



**OVERFLOW AREA 1 & 2 RIPRAP PROTECTION SECTION ISTHMUS ACCESS ROAD**


N.T.S.  
STA. 100+90 to STA. 101+50 (Lt. & Rt.)  
STA. 104+75 to STA. 105+25 Lt.  
STA. 104+75 to STA. 105+45 Lt.

NOTE: GEOTEXTILE FABRIC CLASS SE SHALL BE PLACED IN BETWEEN ALL AGGREGATE TOP SOIL AND MD SHA CLASS 3 RIPRAP INTERFACES




**OVERFLOW AREA 4 RIPRAP PROTECTION SECTION ISTHMUS ACCESS ROAD**

N.T.S.  
STA. 107+98 to STA. 108+40 Lt.  
STA. 107+98 to STA. 108+80 Rt.




**OVERFLOW PROTECTION AREA 3 DETAIL SECTION ISTHMUS ACCESS ROAD**

N.T.S.  
STA. 106+34 Lt.  
STA. 106+05 to STA. 106+70 Rt.




**OVERFLOW PROTECTION AREA 5 SECTION ISTHMUS ACCESS ROAD**

N.T.S.  
STA. 110+92 Lt.  
STA. 110+62 to STA. 111+50 Rt.




**IMBRICATED RIPRAP RIVER BANK PROTECTION PLAN VIEW SECTION**

N.T.S.



**OVERFLOW PROTECTION AREA 2 SECTION ISTHMUS ACCESS ROAD**

N.T.S.  
STA. 106+05 to STA. 106+65 Lt.



**OVERFLOW PROTECTION AREA 5 SECTION ISTHMUS ACCESS ROAD**

N.T.S.  
STA. 110+65 to STA. 111+20 Lt.


APPROVED: DEPARTMENT OF PLANNING AND ZONING

Chief, Development Engineering Division: *[Signature]* 12/23/07 Date  
Chief, Division of Land Development: *[Signature]* 1/02/10 Date  
Director, DEP: *[Signature]* 1/7/10 Date

Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division  
*V. P. Dalal*  
Visty P. Dalal  
Regulatory & Compliance Engineer 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:  
**HDR**  
HDR Engineering, Inc.  
8700 LAKE WRIGHT DRIVE  
SUITE 500  
NORFOLK, VIRGINIA 23502  
767-222-1600

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION  
*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.  
12-24-2009




COLUMBIA ASSOCIATION  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947

RIVER BANK PROTECTION SECTIONS  
COLUMBIA ASSOCIATION TOWN CENTER  
MINOR GRADING IN SUPPORT OF LAKE KITTAMAQUNDI RESTORATION  
ELECTION DISTRICT 8, HOWARD COUNTY MD.  
TAX MAP 30 AND 36


SCALE AS SHOWN  
JUNE 18, 2009

DRAWING G-01, SHEET 25 OF 37

SDP-08-108




**WEST PENINSULA (FOREBAY) IN-LAKE RIPRAP CONTAINMENT BERM**  
**SECTION W/O IMBRICATED RIPRAP**  
 SECTION I  
 N.T.S. G-02



**EAST & WEST PENINSULA (FOREBAY) IN-LAKE RIPRAP CONTAINMENT BERM**  
**SECTION WITH IMBRICATED RIPRAP**  
 SECTION J  
 N.T.S. G-02

NOTE:  
 STONES FOR IMBRICATED RIP RAP SHALL HAVE THE FOLLOWING MIN. DIMENSIONS:  
 L = 1'- 8"  
 H = 9"  
 W = 12"



**COIR LOG MATERIAL SPECIFICATIONS AND INSTALLATION GUIDELINES**  
 SECTION K  
 G-02

APPROVED: DEPARTMENT OF PLANNING AND ZONING

*[Signature]*  
 Chief, Development Engineering Division  
 Date: 12/23/09

*[Signature]*  
 Chief, Division of Land Development  
 Date: 1/07/10

*[Signature]*  
 Director, DEP.  
 Date: 1/7/10

Maryland Department of the Environment  
 MDE Water Management Administration  
 Dam Safety Division

*[Signature]*  
 V. P. Dalal  
 Regulatory & Compliance Engineer  
 Date: 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 300  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
 PIETER DAHMEN, PE  
 HDR ENGINEERING INC.  
 11-24-2009

**COLUMBIA ASSOCIATION**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947

**IN-LAKE RIPRAP CONTAINMENT BERM SECTIONS**



**COLUMBIA ASSOCIATION TOWN CENTER**

MINOR GRADING IN SUPPORT OF LAKE KITTAMAQUONDI RESTORATION  
 ELECTION DISTRICT 8, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36

SCALE AS SHOWN  
 JUNE 18, 2009

DRAWING G-02, SHEET 26 OF 37



SDP-08-108



**TYPICAL SECTION**  
NOT TO SCALE

**LEGEND**

- EXISTING CONTOURS
- - - PROPOSED CONTOURS
- · - · - · LIMIT OF CUT SLOPE
- - - - - LIMIT OF FILL SLOPE
- · - · - · LIMIT OF TRANSITION
- TURF REINFORCED MATTING



**ISTHMUS ACCESS ROAD - PLAN & PROFILE**  
STA. 100+00 TO STA. 105+00

**COLUMBIA ASSOCIATION**  
**TOWN CENTER**

MINOR GRADING IN SUPPORT OF  
LAKE KITTAMAQUUNDI RESTORATION  
ELECTION DISTRICT 5, HOWARD COUNTY MD.  
TAX MAP 30 AND 36

SCALE AS SHOWN  
JUNE 18, 2009

DRAWING H-01, SHEET 27 OF 37

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
Chief, Development Engineering Division  
Date: 12/23/09

*[Signature]*  
Chief, Division of Land Development  
Date: 1/07/10

*[Signature]*  
Director, DEP.  
Date: 1/7/10

Maryland Department of the Environment  
MDE Water Management Administration  
Dam Safety Division


*[Signature]*  
V. P. Dalal  
Regulatory & Compliance Engineer  
Date: 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:


**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 500  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN  
DESIGNED UNDER MY  
SUPERVISION



*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.  
Date: 11-24-2009



**COLUMBIA ASSOCIATION**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947



- LEGEND**
- EXISTING CONTOURS
  - PROPOSED CONTOURS
  - - - LIMIT OF CUT SLOPE
  - - - LIMIT OF FILL SLOPE
  - - - LIMIT OF TRANSITION
  - TURF REINFORCED MATTING



**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
 Chief, Development Engineering Division  
 Date: 12/23/09

*[Signature]*  
 Chief, Division of Land Development  
 Date: 1/27/10

*[Signature]*  
 Director, DEP.  
 Date: 1/7/10

Maryland Department of the Environment  
 MDE Water Management Administration  
 Dam Safety Division

*[Signature]*  
**V. P. Dalal**  
 Visty P. Dalal  
 Regulatory & Compliance Engineer  
 Date: 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 500  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
**PIETER DAHMEN, PE**  
 HDR ENGINEERING INC.  
 11-24-2009

**COLUMBIA ASSOCIATION**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947


**ISTHMUS ACCESS ROAD PLAN & PROFILE**  
 STA. 105+00 TO STA. 110+00

**COLUMBIA ASSOCIATION TOWN CENTER**


MINOR GRADING IN SUPPORT OF LAKE KITTAMAQUONDI RESTORATION  
 ELECTION DISTRICT #, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36

SCALE AS SHOWN  
 JUNE 18, 2009

DRAWING H-02, SHEET 28 OF 37  
 SDP-08-108



- LEGEND**
- EXISTING CONTOURS
  - PROPOSED CONTOURS
  - - - LIMIT OF CUT SLOPE
  - - - LIMIT OF FILL SLOPE
  - - - LIMIT OF TRANSITION
  - TURF REINFORCED MATTING



**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*Chris M...*  
Chief, Development Engineering Division  
Date: 12/27/09

*Vest She...*  
Chief, Division of Land Development  
Date: 1/07/10

*Thomas J. Butte*  
Director, DEP  
Date: 1/7/10

Maryland Department of the Environment  
MDE Water Management Administration  
Dam Safety Division

*V. P. Dalal*  
Visty P. Dalal  
Regulatory & Compliance Engineer  
Date: 12/11/09

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*Pieter Dahmen*  
STATE OF MARYLAND PROFESSIONAL ENGINEER

**PIETER DAHMEN, PE**  
HDR ENGINEERING INC.  
11-21-2009

**COLUMBIA ASSOCIATION**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947


**ISTHMUS ACCESS ROAD PLAN & PROFILE**  
STA. 110+00 TO STA. 115+00

**COLUMBIA ASSOCIATION TOWN CENTER**


MINOR GRADING IN SUPPORT OF LAKE KITTAMAQUNDI RESTORATION  
ELECTION DISTRICT 6, HOWARD COUNTY MD.  
TAX MAP 30 AND 36

SCALE AS SHOWN  
JUNE 18, 2009

DRAWING H-03, SHEET 29 OF 37  
SDP-08-108



- LEGEND**
- EXISTING CONTOURS
  - PROPOSED CONTOURS
  - LIMIT OF CUT SLOPE
  - LIMIT OF FILL SLOPE
  - LIMIT OF TRANSITION
  - TURF REINFORCED MATTING



**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
 Chief, Development Engineering Division &  
 Date 12/23/09

*[Signature]*  
 Chief, Division of Land Development  
 Date 1/07/10

*[Signature]*  
 Director, DEP.  
 Date 1/7/10

Maryland Department of the Environment  
 Water Management Administration  
 Dam Safety Division


*[Signature]*  
 V. P. Dalal  
 Regulatory & Compliance Engineer  
 Date 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
 HDR Engineering, Inc.  
 6700 LAKE WRIGHT DRIVE  
 SUITE 500  
 NORFOLK, VIRGINIA 23502  
 757-222-1600

PLANS HAVE BEEN  
 DESIGNED UNDER MY  
 SUPERVISION

*[Signature]*  
 PIETER DAHMEN, PE  
 HDR ENGINEERING INC.  
 11-24-2009



**COLUMBIA ASSOCIATION**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947


**ISTHMUS ACCESS ROAD PLAN & PROFILE**  
 STA. 110+00 TO STA. 115+00

**COLUMBIA ASSOCIATION**  
 TOWN CENTER

MINOR GRADING IN SUPPORT OF  
 LAKE KITTAMAQUNDI RESTORATION  
 ELECTION DISTRICT 8, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36

SCALE AS SHOWN  
 JUNE 18, 2009

DRAWING H-04, SHEET 30 OF 37  
 SDP-08-108






**STAGING AREA**


WORK AREA: 5,211 SF  
 EQUIPMENT AREA: 13,444 SF  
 MISC. AREA: 906 SF  
 TRAILER/PARKING AREA: 10,027 SF

TOTAL CUT: 1,109 CY  
 TOTAL FILL: 1,109 CY  
 AREA OF DISTURBANCE: 1.91 AC


NOTE:  
 USE ROADWAY  
 SECTION DETAIL  
 FOR THE CONSTRUCTION  
 OF THE SCE



**TYPICAL ROADWAY SECTION**



**TYPICAL SECTION WORK AREA**



**TYPICAL SECTION EQUIPMENT AREA TRAILER/PARKING AREA**

- (A) 6" - CRUSHER RUN AGGREGATE, CR-6
- (B) 6" - BANK RUN GRAVEL - SUBBASE
- (C) 2" - HOT MIX ASPHALT SUPERPAVE 12.5 mm
- (D) GEOTEXTILE FABRIC

This development plan is approved for soil erosion and sediment control by the HOWARD SOIL CONSERVATION DISTRICT

*[Signature]*  
 Date: 12/16/09

**ENGINEER'S CERTIFICATE**  
 I certify that this plan for sediment and erosion control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements with the Howard Soil Conservation District.

*[Signature]*  
 Signature of Engineer (print name below signature) Date: 12/17/2009  
**Pieter Dahmen**

**DEVELOPER'S CERTIFICATE**  
 I/We certify that all development and construction will be done according to this plan for sediment and erosion control, and that all responsible personnel involved in the construction project, will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District.

*[Signature]*  
 Signature of Developer (print name below signature) Date: 12/16/09  
**Dennis Matney**

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
 Chief, Development Engineering Division Date: 12/22/09

*[Signature]*  
 Chief, Division of Land Development Date: 1/27/10

*[Signature]*  
 Director, DEP Date: 1/2/10

Maryland Department of the Environment  
 Water Management Administration  
 Dam Safety Division  
*[Signature]*  
 V.P. Dabal  
 Regulatory & Compliance Engineer  
 Date: 12/1/09

THIS PLAN SET HAS BEEN PREPARED BY:  
**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 300  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION  
**PIETER DAHMEN, PE**  
 HDR ENGINEERING INC.  
 11-24-2009

**COLUMBIA ASSOCIATION**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947


**TEMPORARY EROSION AND SEDIMENT CONTROL PLAN**  
 INITIAL PHASE - STAGING AREA

**COLUMBIA ASSOCIATION TOWN CENTER**

**MINOR GRADING IN SUPPORT OF LAKE KITTAMAQUNDI RESTORATION**  
 ELECTION DISTRICT #, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36

SCALE AS SHOWN  
 JUNE 18, 2009

DRAWING I-01, SHEET 31 OF 37  
 SDP-08-108



**LEGEND**

- SF — SILT FENCE
- SSF — SUPER SILT FENCE
- - - LOD - - - LIMITS OF DISTURBANCE
- A1 DIVERSION DIKE
- DSF — DIVERSION SILT FENCE
- EROSION CONTROL MATTING
- 100 YEAR FLOOD PLAIN

NOTE:  
 EXTEND END OF SSF UPHILL FOR A DISTANCE OF 5 FT. UNLESS NOTED.

**Sediment Control**  
 Sequence of Construction  
 for the construction of the Staging Area for Dredging Lake Kittamaqundi


Task	Phase I	Duration (Days)
1	Contractor is to notify the Howard County Department of Inspections Sediment Control Division 24-hours prior to commencing work at (410) 313-1855 and obtain Grading and MDE permits. Reference MDE Tracking Number 200883335.	2
2	Obtain and bring all required E & S materials for construction to the project site	1
3	Clear and grub for stabilized construction entrances (SCE) and access road. Install SCE's for a minimum distance of 50 ft.	2
4	Install diversion dike, diversion silt fence, super silt fence, tree protection fencing and all other controls.	7
5	After receiving permission of the Howard County Sediment Control Inspector, clear and grub within limits of construction of the Staging Area	5
	<b>Total</b>	<b>17</b>

Task	Phase II	Duration (Days)
6	Construct Staging Area Access Road	5
7	Construct Trailer / Parking Area	5
8	Construct Equipment and Working Area	10
9	Mulch, place standard erosion control matting and seed disturbed and exposed areas not to be paved or covered with gravel	2
10	Provide a copy of the approved sediment control plan or other permit authority for the site(s) receiving dewatered dredged material to the Inspector and Howard Soil Conservation District and obtain written permission from Inspector to proceed.	7
11	Install Turbidity Curtain in Lake Kittamaqundi	2
12	Commence dredging. Maintain diversion dike, diversion fence and super silt fence during duration of dredging and dewatering, repair perimeter controls as necessary. The Contractor shall comply with all applicable federal, state, and local laws and regulations, including project permits. Effluent leaving the site shall not exceed Maryland turbidity limits of 150 Ntu at any time or 50 Ntu as a monthly average per COMAR 06.08.02	100
13	Remove access road, gravel surface of equipment area and the paved working area. Restore staging area and temporary access road to original contours, place top soil with erosion control matting and seed.	15
14	Stabilize remaining disturbed areas and remove sediment controls upon approval of Howard County Sediment Control Inspectors.	5
	<b>Total</b>	<b>151</b>
	<b>Total Initial + Final Phase</b>	<b>168</b>


Task	Phase III	Duration (Days)
15	Contractor is to notify the Howard County Department of Inspections Sediment Control Division 24-hours prior to commencing work at (410) 313-1855 and obtain Grading and MDE permits. Reference MDE Tracking Number 200883335.	2
16	Obtain and bring all required E & S materials for construction to the project site	1
17	Clear and grub for stabilized construction entrances (SCE) and access road. Install SCE's for a minimum distance of 50 ft and install access road	2
18	After receiving permission of the Howard County Sediment Control Inspector, clear and grub within limits of construction of the Isthmus Access Road and overflow protection areas	5
	<b>Total</b>	<b>10</b>

Task	Phase IV	Duration (Days)
19	Construct Staging Area Access Road	10
20	Construct Riprap Overflow Area	10
21	Remove debris from channel, construct limbed channel banks stabilization	2
22	Mulch, place standard erosion control matting and seed on disturbed and exposed areas not to be paved or covered with gravel	15
23	Stabilize remaining disturbed areas and remove sediment controls upon approval of Howard County Sediment Control Inspectors.	5
	<b>Total</b>	<b>52</b>
	<b>Total Initial + Final Phase</b>	<b>62</b>







**LEGEND**

— SF —	SILT FENCE
— SSF —	SUPER SILT FENCE
- - - - -	LIMITS OF DISTURBANCE
— A1 —	DIVERSION DIKE
— DSF —	DIVERSION SILT FENCE
▨	EROSION CONTROL MATTING
- - - - -	100 YEAR FLOOD PLAN

NOTE:  
EXTEND END OF SSF UPHILL FOR A DISTANCE OF 5'.

**STAGING AREA**

WORK AREA : 5,211 SF  
EQUIPMENT AREA: 13,444 SF  
MISC. AREA: 905 SF  
TRAILER/PARKING AREA: 10,027 SF

TOTAL CUT: 1,109 CY  
TOTAL FILL: 1,109 CY  
AREA OF DISTURBANCE: 1.51 AC

Curve = CK1  
PI 13+94.40  
D = 126° 47' 50" (LT)  
R = 135.00'  
T = 269.57'  
L = 298.76'

Toby's General Partnership  
C/O Harold D. Orenstein

N 561600

Liberty Property  
Limited Partnership

The Howard Research  
and Development  
Corporation

This development plan is approved for soil erosion and sediment control by the HOWARD SOIL CONSERVATION DISTRICT

*[Signature]* 12/14/09  
Howard SCD Date

**ENGINEER'S CERTIFICATE**  
"I certify that this plan for sediment and erosion control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements with the Howard Soil Conservation District."

*[Signature]* 12/17/2009  
Signature of Engineer (print name below signature) Date  
Pieter Dahmen

**DEVELOPER'S CERTIFICATE**  
"I/We certify that all development and construction will be done according to this plan for sediment and erosion control, and that all responsible personnel involved in the construction project, will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District."

*[Signature]* 12/16/09  
Signature of Developer (print name below signature) Date  
Dennis McKeay

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]* 12/22/09  
Chief, Development Engineering Division &  
Date

*[Signature]* 1/09/10  
Chief, Division of Land Development  
Date

*[Signature]* 1/7/10  
Director, DEP.  
Date

Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division

*[Signature]* 12/1/09  
Regulatory & Compliance Engineer

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
570 LAKE WRIGHT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN  
DESIGNED UNDER MY  
SUPERVISION

*[Signature]* 11-24-2009  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.

**COLUMBIA ASSOCIATION**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947

**TEMPORARY EROSION AND SEDIMENT CONTROL PLAN**  
FINAL PHASE - STAGING AREA

**COLUMBIA ASSOCIATION**  
**TOWN CENTER**


MINOR GRADING IN SUPPORT OF  
LAKE KITTAMAQUONDI RESTORATION  
ELECTION DISTRICT #5, HOWARD COUNTY MD.  
TAX MAP 30 AND 36

SCALE AS SHOWN  
JUNE 18, 2009


DRAWING I-02, SHEET 32 OF 37

SDP-08-108


NOTE:  
AT COMPLETION OF DREDGING REMOVE TEMPORARY  
ACCESS ROAD, GRAVEL SURFACE, PAVED AREAS AND  
RESTORE STAGING AREA TO THE ORIGINAL CONTOURS



TYPICAL ROADWAY SECTION




TYPICAL SECTION WORK AREA



TYPICAL SECTION EQUIPMENT AREA TRAILER/PARKING AREA



- (A) 6" - CRUSHER RUN AGGREGATE, CR-6
- (B) 6" - BANK RUN GRAVEL - SUBBASE
- (C) 2" - HOT MIX ASPHALT SUPERPAVE 12.5 mm
- (D) GEOTEXTILE FABRIC



**LEGEND**

- IMBRICATED RIPRAP
- RIPRAP OVERFLOW PROTECTION
- EROSION CONTROL MATTING
- EXISTING CONTOURS
- PROPOSED CONTOURS
- SF SILT FENCE
- SSF SUPER SILT FENCE
- LOD LIMITS OF DISTURBANCE
- REMOVAL PUMPING STATION

LAKE KITTAMAQUONDI



This development plan is approved for soil erosion and sediment control by the HOWARD SOIL CONSERVATION DISTRICT

*[Signature]* 12/16/09  
 Date

**ENGINEER'S CERTIFICATE**  
 "I certify that this plan for sediment and erosion control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements with the Howard Soil Conservation District."

*[Signature]* 12/17/2009  
 Signature of Engineer (print name below signature) Date  
 Pieter Dahmen

**DEVELOPER'S CERTIFICATE**  
 "We certify that all development and construction will be done according to this plan for sediment and erosion control, and that all responsible personnel involved in the construction project, will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District."

*[Signature]* 12/16/09  
 Signature of Developer (print name below signature) Date  
 Dennis Ketter

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]* 12/23/09  
 Chief, Development Engineering Division Date

*[Signature]* 1/07/10  
 Chief, Division of Land Development Date

*[Signature]* 1/7/10  
 Director, DEP Date

Maryland Department of the Environment  
 MDE Water Management Administration  
 Dam Safety Division


*[Signature]*  
 V. P. Dalal  
 Regulatory & Compliance Engineer 12/11/09

THIS PLAN SET HAS BEEN PREPARED BY:


**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 200  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
 PIETER DAHMEN, PE  
 HDR ENGINEERING INC. 11-24-2009



COLUMBIA ASSOCIATION  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947




**EROSION & SEDIMENT CONTROL PLAN**  
**ISTHMUS ACCESS ROAD**  
**INITIAL AND FINAL DESIGN**

**COLUMBIA ASSOCIATION**  
**TOWN CENTER**


MINOR GRADING IN SUPPORT OF  
 LAKE KITTAMAQUONDI RESTORATION  
 ELECTION DISTRICT 5, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36

SCALE AS SHOWN  
 JUNE 18, 2009

DRAWING I-03, SHEET 33 OF 07



- LEGEND**
- IMBRICATED RIPRAP
  - RIPRAP OVERFLOW PROTECTION
  - EROSION CONTROL MATTING
  - EXISTING CONTOURS
  - PROPOSED CONTOURS
  - SILT FENCE
  - SUPER SILT FENCE
  - LIMITS OF DISTURBANCE
  - REMOVAL PUMPING STATION



NOTE: CONSTRUCT IMBRICATED RIPRAP WALL PRIOR TO PLACING RIPRAP OF OVERFLOW PROTECTION AREA 5

MATCH LINE SEE SHEET I-3

This development plan is approved for soil erosion and sediment control by the HOWARD SOIL CONSERVATION DISTRICT

*[Signature]* 12/16/09  
Howard SCD Date

**ENGINEER'S CERTIFICATE**  
"I certify that this plan for sediment and erosion control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements with the Howard Soil Conservation District."

*Pieter Dahmen* 12/17/2009  
Signature of Engineer (print name below signature) Date  
Pieter Dahmen

**DEVELOPER'S CERTIFICATE**  
"I/we certify that all development and construction will be done according to this plan for sediment and erosion control, and that all responsible personnel involved in the construction project, will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District."

*D. Matley* 12/16/09  
Signature of Developer (print name below signature) Date  
Dennis Matley

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]* 12/22/09  
Chief, Development Engineering Division Date

*[Signature]* 1/07/10  
Chief, Division of Land Development Date

*[Signature]* 1/7/10  
Director, DEP. Date

Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division

*V. P. Dalal*  
Visty P. Dalal 12/1/09  
Regulatory & Compliance Engineer

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.  
11-27-2009

0 25 50  
SCALE IN FEET

**COLUMBIA ASSOCIATION**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947


**EROSION & SEDIMENT CONTROL**  
**ISTHMUS ACCESS ROAD**  
**INITIAL AND FINAL DESIGN**

**COLUMBIA ASSOCIATION**  
**TOWN CENTER**

MINOR GRADING IN SUPPORT OF  
LAKE KITTAMAQUONDI RESTORATION  
ELECTION DISTRICT 8, HOWARD COUNTY MD.  
TAX MAP 30 AND 36

SCALE AS SHOWN  
JUNE 18, 2009

DRAWING I-04 SHEET 34 OF 37



1. Seed and cover with straw mulch.  
 2. Seed and cover with Erosion Control Matting or line with sod.  
 3. 4" - 7" stone or recycled concrete equivalent pressed into the soil 7" minimum
- Construction Specifications**
- All temporary earth dikes shall have uninterrupted positive grade to an outlet. Spot elevations may be necessary for grades less than 1%.
  - Runoff diverted from a disturbed area shall be conveyed to a sediment trapping device.
  - Runoff diverted from an undisturbed area shall outlet directly into an undisturbed, stabilized area at a non-erosive velocity.
  - All trees, brush, stumps, obstructions, and other objectional material shall be removed and disposed of so as not to interfere with the proper functioning of the dike.
  - The dike shall be excavated or shaped to line, grade and cross section as required to meet the criteria specified herein and be free of bank projections or other irregularities which will impede normal flow.
  - Fill shall be compacted by earth moving equipment.
  - All earth removed and not needed for construction shall be placed so that it will not interfere with the functioning of the dike.
  - Inspection and maintenance must be provided periodically and after each rain event.

**EARTH DIKE** 1  
I-05


**Sediment Filter Bag Specifications**

- 1.0 DESCRIPTION**
- 1.1 This work is for furnishing, installing, maintaining, and disposing of a Sediment Filter Bag. The purpose is to control sediment discharge in any dewatering or pumped water application.
- 2.0 MATERIALS**
- 2.1 FB-3 15' x 15' Sediment Filter Bag as manufactured by an approved manufacturer
- 2.2 The geotextile fabric shall be a non-woven fabric with the following properties:

Properties	Test Method	Units	MARV
lb Tensile Strength	ASTM D-4632	lbs.	290
lb Elongation	ASTM D-4632	%	50
pezoid Tear	ASTM D-4533	lbs.	145
cture	ASTM D-4833	lbs.	165
llen Burst	ASTM D-3786	psi	550
mittivity	ASTM D-4491	sec.	0.7
meability	ASTM D-4491	cm/sec	.35
'S	ASTM D-4751	U.S. Sieve	100 (.150 mm)
'Resistance (500hrs.)	ASTM D-4355	%	70
ter Flow Rate	ASTM D-4491	gpm/ft.	110
m Strength	ASTM D-4491	lbs.	250


- 2.3 The Sediment Filter Bag Seams shall be double 401 lock chain stitch seam with a 121 lbs./inch sewn strength, tested in accordance with ASTM D-4884.
- 2.4 The Sediment Filter Bag shall have an adjustable spout large enough to accommodate a six inch (6") diameter discharge hose.
- 3.0 CONSTRUCTION**
- 3.1 Unfold filter bag on a stabilized area over either a bed of straw evenly distributed at a rate of one (1) bale per square feet, or on an aggregate pad constructed of #57 stone at a minimum depth of three inches (3"). Filter bag should not be placed on bare soil.
- 3.2 Insert discharge pump hose into the filter bag spout a minimum of six inches (6") and tightly secure the hose with tie wire or pipe clamp.
- 4.0 MAINTENANCE**

**TEMPORARY SEDIMENT FILTER BAG** 2  
I-05



- Construction Specifications**
- The outer pipe should be 48" dia. or shall, in any case, be at least 4" greater in diameter than the center pipe. The outer pipe shall be wrapped with 1/2" hardware cloth to prevent backfill material from entering the perforations.
  - After installing the outer pipe, backfill around outer pipe with 2" aggregate or clean gravel.
  - The inside stand pipe (center pipe) should be constructed by perforating a corrugated or PVC pipe between 12" and 36" in diameter. The perforations shall be 1/2" x 6" slots or 1" diameter holes 6" on center. The center pipe shall be wrapped with 1/2" hardware cloth first, then wrapped again with Geotextile Class C.
  - The center pipe should extend 12" to 18" above the anticipated water surface elevation or riser crest elevation when dewatering a basin.

**REMOVABLE PUMPING STATION (RPS)** 3  
I-05




- Construction Specifications**
- Fencing shall be 42" in height and constructed in accordance with the latest Maryland State Highway Details for Chain Link Fencing. The specification for a 6' fence shall be used, substituting 42" fabric and 6' length posts.
  - Chain link fence shall be fastened securely to the fence posts with wire ties. The lower tension wire, brace and truss rods, drive anchors and post caps are not required except on the ends of the fence.
  - Filter cloth shall be fastened securely to the chain link fence with ties spaced every 24" at the top and mid section.
  - Filter cloth shall be embedded a minimum of 8" into the ground.
  - When two sections of filter cloth adjoin each other, they shall be overlapped by 6" and folded.
  - Maintenance shall be performed as needed and silt buildups removed when "bulges" develop in the silt fence, or when silt reaches 50% of fence height
  - Filter cloth shall be fastened securely to each fence post with wire ties or staples at top and mid section and shall meet the following requirements for Geotextile Class F:
- |                      |  |                |
|----------------------|--|----------------|
| Tensile Strength     | 50 lbs/in (min.)                       | Test: MSMT 509 |
| Tensile Modulus      | 20 lbs/in (min.)                       | Test: MSMT 509 |
| Flow Rate            | 0.3 gal/ft <sup>2</sup> /minute (max.) | Test: MSMT 322 |
| Filtering Efficiency | 75% (min.)                             | Test: MSMT 322 |


**SUPER SILT FENCE** 4  
I-05

- Construction and Material Specifications**
- I. Topsoil salvaged from the existing site may be used provided that it meets the standards as set forth in these specifications. Typically, the depth of topsoil to be salvaged for a given soil type can be found in the representative soil profile section in the Soil Survey published by USDA-SCS in cooperation with Maryland Agricultural Experimental Station.
- II. Topsoil Specifications - Soil to be used as topsoil must meet the following:
- Topsoil shall be a loam, sandy loam, clay loam, silt loam, sandy clay loam, loamy sand. Other soils may be used if recommended by an agronomist or soil scientist and approved by the appropriate approval authority. Regardless, topsoil shall not be a mixture of contrasting textured subsoils and shall contain less than 5% by volume of cinders, stones, slag, coarse fragments, gravel, sticks, roots, trash, or other materials larger than 1" in diameter.
  - Topsoil must be free of plants or plant parts such as bermuda grass, quackgrass, Johnsongrass, nutsedge, poison ivy, thistle, or others as specified.
  - Where the subsoil is either highly acidic or composed of heavy clays, ground limestone shall be spread at the rate of 48 tons/acre (200-400 square feet) prior to the placement of topsoil. Lime shall be distributed uniformly over designated areas and worked into the soil in conjunction with tillage operations as described in the following procedures.
- III. For sites having disturbed areas under 5 acres:
- Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section I - Vegetative Stabilization Methods and Materials.
- IV. For sites having disturbed areas over 5 acres:
- On soil meeting Topsoil specifications, obtain test results dictating fertilizer and lime amendments required to bring the soil into compliance with the following:
    - pH for topsoil shall be between 6.0 and 7.5, if the tested soil demonstrates a pH of less than 6.0, sufficient lime shall be prescribed to raise the pH to 6.5 or higher.
    - Organic content of topsoil shall be not less than 1.5 percent by weight.
    - Topsoil having soluble soil content greater than 500 parts per million shall not be used.
    - No sod or seed shall be placed on soil which has been treated with soil sterilants or chemicals used for weed control until sufficient time has elapsed (14 days min.) to permit dissipation of phyto-toxic materials.
- Note: Topsoil substitutes or amendments, as recommended by a qualified agronomist or soil scientist and approved by the appropriate approval authority, may be used in lieu of natural topsoil.
- Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section I - Vegetative Stabilization Methods and Materials.
- V. Topsoil Application
- When topsoiling, maintain needed erosion and sediment control practices such as diversions, Grade Stabilization Structures, Earth Dikes, Slope Silt Fence and Sediment Traps and Basins.
  - Grades on the areas to be topsoiled, which have been previously established, shall be maintained, albeit 4" - 8" higher in elevation.
  - Topsoil shall be uniformly distributed in a 4" - 8" layer and lightly compacted to a minimum thickness of 4". Spreading shall be performed in such a manner that sodding or seeding can proceed with a minimum of additional soil preparation and tillage. Any irregularities in the surface resulting from topsoiling or other operations shall be corrected in order to prevent the formation of depressions or water pockets.
  - Topsoil shall not be placed while the topsoil or subsoil is in a frozen or muddy condition, when the subsoil is excessively wet or in a condition that may otherwise be detrimental to proper grading and seedbed preparation.

**TOPSOILING** 5  
I-05



**TOE OF FILL - INSTALLATION OF SILT FENCE** 6  
I-05



**SUPER SILT DIVERSION FENCE (DSF)** 7  
I-05

- CONSTRUCTION SPECIFICATIONS**
- FENCING SHALL BE 42 INCHES IN HEIGHT AND CONSTRUCTED IN ACCORDANCE WITH THE LATEST MARYLAND STATE HIGHWAY DETAILS FOR CHAIN LINK FENCING. THE SPECIFICATION FOR A 6 FOOT FENCE SHALL BE USED, SUBSTITUTING 42-INCH FABRIC AND 6 FOOT LENGTH POSTS.
- THE POLES DO NOT NEED TO SET IN CONCRETE.
  - CHAIN LINK FENCE SHALL BE FASTENED SECURELY TO THE FENCE POSTS WITH WIRE TIES.
  - FABRIC WILL BE DOUBLE 6 MIL MIN. THICKNESS U/V RESISTENT BLACK POLYETHYLENE (IP FABRIC).
  - IP FABRIC SHALL BE FASTENED SECURELY TO THE CHAIN LINK FENCE WITH TIES SPACED EVERY 24" AT THE TOP AND MID SECTION.
  - IP FABRIC SHALL BE EMBEDDED A MINIMUM OF 8" INTO THE GROUND.
  - WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THEY SHALL BE OVERLAPPED BY 6" AND FOLDED.
  - MAINTENANCE SHALL BE PERFORMED AS NEEDED AND SILT BUILDUPS REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE.
- NOTE: IP FABRIC DENOTES IMPERMEABLE GEOTEXTILE FABRIC

**TEMPORARY EROSION AND SEDIMENT CONTROL DETAILS AND NOTES**

APPROVED: DEPARTMENT OF PLANNING AND ZONING

*Michael J. ...*  
 Chief, Development Engineering Division  
 Date: 12/23/09

*Kent ...*  
 Chief, Division of Land Development  
 Date: 1/27/10

*Thomas E. Butler*  
 Director, DEP.  
 Date: 1/2/10

Maryland Department of the Environment  
 MDE Water Management Administration  
 Dam Safety Division  
*V. P. Dalal*  
 Vistay P. Dalal  
 Regulatory & Compliance Engineer  
 Date: 12/1/09


THIS PLAN SET HAS BEEN PREPARED BY:  
**HDR**  
 HDR Engineering, Inc.  
 6700 LAKE WRIGHT DRIVE  
 SUITE 500  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION  
*Pieter Dahmen*  
 PIETER DAHMEN, PE  
 HDR ENGINEERING INC.  
 11-24-2009

COLUMBIA ASSOCIATION  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947

COLUMBIA ASSOCIATION  
 TOWN CENTER  
 MINOR GRADING IN SUPPORT OF  
 LAKE KITTAMAQUONDI RESTORATION  
 ELECTION DISTRICT 5, HOWARD COUNTY MD.  
 TAX MAP 30 AND 36  
 SCALE AS SHOWN  
 JUNE 18, 2009  
 DRAWING I-05, SHEET 35 OF 97

Construction Specifications




1. Key-in the matting by placing the top ends of the matting in a narrow trench, 6' in depth. Backfill the trench and tamp firmly to conform to the channel cross-section. Secure with a row of staples about 4' down slope from the trench. Spacing between staples is 6'.
2. Staple the 4' overlap in the channel center using an 18" spacing between staples.
3. Before stapling the outer edges of the matting, make sure the matting is smooth and in firm contact with the soil.
4. Staples shall be placed 2' apart with 4 rows for each strip, 2 outer rows, and 2 alternating rows down the center.
5. Where one roll of matting ends and another begins, the end of the top strip shall overlap the upper end of the lower strip by 4", shiplap fashion. Reinforce the overlap with a double row of staples spaced 6' apart in a staggered pattern on either side.
6. The discharge end of the matting liner should be similarly secured with 2 double rows of staples.

Note: If flow will enter from the edge of the matting then the area effected by the flow must be keyed-in.


EROSION CONTROL MATTING



TRANSVERSE SECTION VIEW



PLAN VIEW



NOTE:  
DETAIL FROM MDE  
MARYLANDS  
GUIDELINES FOR  
WATERWAY  
CONSTRUCTION  
(DETAIL 1.5)



Material Specifications

Materials for sandbag and stone stream diversions should meet the following requirements:  
1. Riprap: Riprap should be washed and have a minimum diameter of 6 inches (0.15 meters).  
2. Sandbags: Sandbags should consist of materials which are resistant to ultra-violet radiation, tearing, and puncture and should be woven tightly enough to prevent leakage of the fill material (i.e., sand, fine gravel, etc.).  
3. Sheeting: Sheeting should consist of polyethylene or other materials which are impervious and resistant to puncture and tearing.

Installation Guidelines



- All erosion and sediment control devices, including dewatering basins, should be implemented as the first order of business according to a plan approved by the WMA or local authority. Installation should proceed from upstream to downstream during periods of low flow. If necessary, silt fence or straw bales should be installed around the perimeter of the work area.
- Sandbag/stone diversions can be used independently or as components of other stream diversion techniques. Installation of this measure should proceed as follows (refer to Detail 1.5):
1. The diversion structure should be installed from upstream to downstream.
  2. The height of the sandbag/stone diversion should be a function of the duration of the project in the stream reach. For projects with a duration less than 2 weeks, the height of the diversion should be one half the streambank height, measured from the channel bed, plus 1 foot (0.3 meters) or bankfull height, whichever is greater. For projects of longer duration, the top of the sandbag or stone diversion should correspond to bankfull height. For diversion structures utilizing sandbags, the stream bed should be hand prepared prior to placement of the base layer of sandbags in order to ensure water tight fit. Additionally, it may be necessary to prepare the bank in a similar fashion.
  3. All excavated material should be deposited and stabilized in an approved area outside the 100-year floodplain unless otherwise authorized by the WMA.
  4. Sediment-laden water from the construction area should be pumped to a dewatering basin.
  5. Sheeting on the diversion should be positioned such that the upstream portion covers the downstream portion with at least a 18-inch (0.45 meters) overlap.
  6. Sandbag or stone diversions should not obstruct more than 45% of the stream width. Additionally, bank stabilization measures should be placed in the constricted section if accelerated erosion and bank scour are observed during the construction time or if project time is expected to last more than 2 weeks.
  7. Prior to removal of these temporary structures, any accumulated sediment should be removed, deposited and stabilized in an approved area outside the 100-year floodplain unless otherwise authorized by the WMA.
  8. Sediment control devices are to remain in place until all disturbed areas are stabilized in accordance with an approved sediment and erosion control plan and the inspecting authority approves their removal.

SANDBAG / STONE DIVERSION





1. Length - minimum of 50' (x30' for single residence lot).
2. Width - 10' minimum, should be flared at the existing road to provide a turning radius.
3. Geotextile fabric (Filter cloth) shall be placed over the existing ground prior to placing stone. The plan approval authority may not require single family residences to use geotextile.
4. Stone - crushed aggregate (2' to 3") or reclaimed or recycled concrete equivalent shall be placed at least 6" deep over the length and width of the entrance.
5. Surface Water - all surface water flowing to or diverted toward construction entrances shall be piped through the entrance, maintaining positive drainage. Pipe installed through the stabilized construction entrance shall be protected with a mountable berm with 5:1 slopes and a minimum of 6" of stone over the pipe. Pipe has to be sized according to the drainage. When the SCE is located at a high spot and has no drainage to convey a pipe will not be necessary. Pipe should be sized according to the amount of runoff to be conveyed. A 6" minimum will be required.
6. Location - A stabilized construction entrance shall be located at every point where construction traffic enters or leaves a construction site. Vehicles leaving the site must travel over the entire length of the stabilized construction entrance.


STABILIZED CONSTRUCTION ENTRANCE



TREE PROTECTION



SILT FENCE



Construction Specifications

1. Fence posts shall be a minimum of 36' long driven 16" minimum into the ground. Wood posts shall be 1 1/2" x 1 1/2" square (minimum) cut, or 1 3/4" diameter (minimum) round and shall be of sound quality hardwood. Steel posts will be standard T or U section weighting not less than 1.00 pound per linear foot.
  2. Geotextile shall be fastened securely to each fence post with wire ties or staples at top and mid-section and shall meet the following requirements for Geotextile Class F:
- |                      |  |                |
|----------------------|--|----------------|
| Tensile Strength     | 50 lbs/in (min.)                       | Test: MSMT 509 |
| Tensile Modulus      | 20 lbs/in (min.)                       | Test: MSMT 509 |
| Flow Rate            | 0.3 gal ft <sup>2</sup> /minute (max.) | Test: MSMT 322 |
| Filtering Efficiency | 75% (min.)                             | Test: MSMT 322 |
3. Where ends of geotextile fabric come together, they shall be overlapped, folded and stapled to prevent sediment bypass.
  4. Silt Fence shall be inspected after each rainfall event and maintained when bulges occur or when sediment accumulation reached 50% of the fabric height.

Silt Fence Design Criteria

Slope Steepness	(Maximum) Slope Length	(Maximum) Silt Fence Length
Flatter than 50:1	unlimited	unlimited
50:1 to 10:1	125 feet	1,000 feet
10:1 to 5:1	100 feet	750 feet
5:1 to 3:1	60 feet	500 feet
3:1 to 2:1	40 feet	250 feet
2:1 and steeper	20 feet	125 feet

Note: In areas of less than 2% slope and sandy soils (USDA general classification system, soil Class A) maximum slope length and silt fence length will be unlimited. In these areas a silt fence may be the only perimeter control required.

TEMPORARY EROSION AND SEDIMENT CONTROL DETAILS AND NOTES

COLUMBIA ASSOCIATION TOWN CENTER

MINOR GRADING IN SUPPORT OF LAKE KITTAQUONDI RESTORATION ELECTION DISTRICT #, HOWARD COUNTY MD. TAX MAP 30 AND 36

SCALE AS SHOWN  
JUNE 18, 2009

DRAWING I-06, SHEET 36 OF 37

APPROVED: DEPARTMENT OF PLANNING AND ZONING


Chief, Development Engineering Division  
Chief, Division of Land Development  
Director, DEP

12/23/09  
1/07/10  
1/2/10  
Date


Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division  
V. P. Dalal  
Regulatory & Compliance Engineer

HDR Engineering, Inc.  
5700 LAKE WINGHAT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.



COLUMBIA ASSOCIATION  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947




**Material Specifications**

- Fiber logs: Natural fiber logs composed of biodegradable materials such as coir fiber are commercially available in 16 or 18-inch (0.40 or 0.45-meter) diameter rolls.  
 - Plantings: Vegetative plantings should be chosen according to their adaptability to site-specific conditions and objectives by a plant specialist.  
 - Live stakes: Live stakes should be cut from fresh, green, healthy dormant parent plants which are adapted to the site conditions whenever possible.

**Installation Guidelines**

All erosion and sediment control devices, including dewatering basins, should be implemented as the first order of business according to a plan approved by the WMA or local authority. Refer to the 1994 Maryland Standards and Specifications for Soil Erosion and Sediment Control. The recommended construction procedure for natural fiber logs should proceed as follows (refer to Detail 2.6):  
 1. Natural fiber rolls should be installed so that they rest against the bottom of the waterway in ponds or lakes. In streams and rivers, the first row of fiber logs should be placed above any necessary toe stabilization measures. Natural fiber logs should not be used as the primary toe stabilization measure in streams or rivers.  
 2. Plants should be plugged in an alternating pattern along the top of the fiber log in gaps between the coir fiber netting. Appropriate species and a spacing ranging from 6 to 12 inches (0.15 to 0.3 meters) should be selected by a plant specialist according to site characteristics such as soil properties, anticipated post-construction bank slope, water chemistry, amount of available sunlight, and expected duration of inundation during high stream flows. If water levels are too low for the fiber logs to be submerged 3/4 to 2/3 of their diameter, plants should be plugged inside the soil/log interface where they will receive adequate moisture.  
 3. Dead or live stakes should be used to anchor the fiber logs in place. Stakes should be notched approximately 5 inches (13 centimeters) from their tops and pounded partially into the ground on either side of the bundle at a spacing of 3 to 4 feet (0.9 to 1.2 meters). Twine should be tied from the notch in one stake to the notch in the stake directly opposite. The stakes should then be driven so that the twine is secured against the top of the roll. Ideally, the top of the stake should be flush with the top of the roll.  
 4. The ends of adjacent logs should be laced together with twine by making a number of passes in the end netting between the logs and pulling the twine taut. Where a fiber roll does not abut another fiber roll, the end should be bent inward and buried in the bank to prevent water from intruding behind the roll and dislodging it.  
 5. Successive rows of fiber rolls should be offset 3 to 8 inches (8 to 20 centimeters). Additionally, to ensure that roots extend into the soil, plants should be plugged into the sides of the fiber log near the soil. The need to backfill/contour the soil behind the fiber logs and between successive lifts will depend on the specific aesthetic and physical requirements of the project. The re-contoured soil should be seeded and/or plugged with appropriate vegetative species and covered with an erosion control blanket to prevent slope erosion.

**NATURAL FIBER ROLLS**



**Material Specifications**

Materials for imbricated riprap construction and installation should meet the following requirements:  
 - Filters: Synthetic filter fabric may be used cautiously based on the 1994 MD Standards and Specifications for Soil Erosion and Sediment Control. Whenever possible, however, granular filters with a minimum thickness of 6 inches (15 cm) should be used with a gradation as found in Table 2.2.

**Table 2.2: Granular Filter Material Grading Specifications**



Percent Less Than	U.S. Standard Sieve Size
100	2 1/2 in (64 mm)
85 - 100	1 in (25 mm)
60 - 100	1/2 in (13 mm)
35 - 70	No. 10
20 - 50	No. 40
3 - 20	No. 200

- Toe Riprap: The maximum diameter or weight of stone for toe riprap should be based upon the bankfull stream channel velocity as detailed in the MGWC 2.1: Riprap and Figure 2.1.  
 - Imbricated Stones: Imbricated riprap should be angular and blocky in shape such that they are stackable and should be sufficiently large to resist displacement by both the design storm event and the site-specific lateral earth stresses. Therefore, the length of the longest axis of each stone should be the greater of 1/3 the height of the proposed wall and the size necessary to resist the design stream flow according to MGWC 2.1: Riprap. A typical minimum axis length is 24 inches (0.6 meters).

**Installation Guidelines**

All erosion and sediment control devices, including dewatering basins, should be implemented as the first order of business according to a plan approved by the WMA or local authority. The recommended construction procedure for imbricated riprap is as follows (refer to Detail 2.2):  
 1. The stream should be diverted according to a WMA recommended procedure (see Section 1: Temporary Instream Construction Measures, Maryland's Guidelines to Waterway Construction), and the construction area should be dewatered.  
 2. All excavation should be made in reasonably close conformity with the existing stream slope and bed. The slope of the cut face should be in the range of 1H:1V to 2H:1V. Loose material at the toe of the embankment should be excavated until a stable foundation is reached, usually within 2 to 3 feet (0.6 to 0.9 meters) of the surface. The subgrade should be smooth, firm, and free from protruding objects or voids that would effect the proper positioning of the first layer of stones.  
 3. A graded granular filter or filter fabric should be placed on the face of the cut slope to prevent the migration of fine materials through the revetment. If filter fabric is used, it should be carefully and loosely placed on the prepared slope and secured. Adjacent strips should overlap a minimum of 8 inches (0.20 meters). If the filter fabric is torn or damaged, it should be repaired or replaced.  
 4. The rock layers should be neatly stacked with staggered joints so that each stone rests firmly on two stones in the tier below. Additionally, smaller stones should be used to fill voids so that each rock rests solidly on the previous rock layer with minimal opportunity for movement. Upon completion of the first layer of stone, the toe trench should be filled with Class III riprap sized according to MGWC 2.1: Riprap or additional imbricated stone. Two footer stones should be used where high potential for channel incision exists. The height of the imbricated revetment is dictated by the size of the stone used, and the height should not exceed 3 times the length of the longest axis and should not be greater than 10 feet (3 meters).  
 5. Placement of the granular backfill should occur concurrently with the stone placement. The backfill slope angle should be 2H:1V or flatter but should be greater than 0 degrees to facilitate drainage. Once all of the backfill is in place, it should be covered with a filter layer and a layer of topsoil sufficient to support a native vegetative cover.  
 6. The disturbed sections of the channel, including the slopes and stream bed, should be stabilized with methods approved by the WMA.


**IMBRICATED RIPRAP**



**TYPE II**  
Not to Scale

- Type II is designed for use on rivers and streams, large open lakes, bays, and beaches with moderate currents and wind exposure.
- When the curtain is no longer required as determined by the Inspector, the curtain and related components shall be removed so as to minimize turbidity. Remaining sediment shall be removed and the original depth or plan elevations restored. Any spoils must be taken to upland area and stabilized.
- Curtain will be opened as required to accommodate passage of work boats.

**TURBIDITY CURTAIN**



**Turbidity Curtain Specifications**

Flotation consists of a series of expanded polyethylene logs, 6" in diameter and 55" long. The logs are enclosed in 22 oz./sq. yd. PVC coated nylon or polyester having 400 lbs. minimum tensile strength. Curtain is permanently attached to the bottom of the flotation unit and weighed down with 1/2" galvanized chain. The curtain material is monofilament woven polypropylene having 200 lb. or 300 lb. tensile strength.

**Woven Curtain Material Specifications:**

Property	Test Method	Results	Results	Results
Fabric Code		AEF 200W	AEF 300W	AEF 650W
Fabric Structure		Woven	Woven	Woven
Polymer Composition		Polypropylene	Polypropylene	Polypropylene
Weight	ASTM D-4632	4.2 oz/sq. yd	5.8 oz/sq. yd	6.3 oz/sq. yd
Grab Strength	ASTM D-4632	200 lbs.	300 lbs.	390 x 250 lbs.
Trap Tear Strength	ASTM D-4533	90 lbs.	120 lbs.	115 x 65 lbs.
Burst Strength	ASTM D-3786	400 psi	600 psi	495 psi
Puncture	ASTM D-3787	90 lbs.	150 lbs.	130 lbs.
Elongation	ASTM D-4632	20%	20%	30%
U.V. Resistance	ASTM D-4335	70% (500hrs)	70% (500hrs)	70% (500hrs)
E.O.S.	CW-02215	40	40	70

**Maintenance**

Inspect turbidity curtain after each major storm event resulting from 3-inches or more of rainfall within a 24-hour period. Repair or replace damaged materials and remove any debris lodged against the turbidity curtain.

**TEMPORARY EROSION AND SEDIMENT CONTROL  
DETAILS AND NOTES**

**COLUMBIA ASSOCIATION  
TOWN CENTER**

**MINOR GRADING IN SUPPORT OF  
LAKE KITTAMAQUONDI RESTORATION  
ELECTION DISTRICT 5, HOWARD COUNTY MD.  
TAX MAP 30 AND 36**

SCALE AS SHOWN  
JUNE 18, 2009

DRAWING I-07, SHEET 37 OF 37

APPROVED: DEPARTMENT OF PLANNING AND ZONING

*[Signature]*  
Chief, Development Engineering Division  
*[Signature]*  
Chief, Division of Land Development  
*[Signature]*  
Director, DEP


12/22/08  
Date  
 1/07/10  
Date  
 1/9/10  
Date

Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division  
*V.P. Dalal*  
V.P. Dalal  
Regulatory & Compliance Engineer  
12/1/09


THIS PLAN SET HAS BEEN PREPARED BY:  
**HDR**  
 HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN  
DESIGNED UNDER MY  
SUPERVISION

PIETER DAHMEN, PE  
HDR ENGINEERING INC.




COLUMBIA ASSOCIATION  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947



- NOTES**
- DO NOT REMOVE EXISTING ROOTBALL OF REMOVED TREES. GRIND STUMP TO 6-INCH MINIMUM BELOW SURFACE.
  - ALL DISTURBED AREAS SHALL BE TOPSOILED, SEEDED, FERTILIZED, AND MULCHED.

**SEQUENCE OF LAND DISTURBING ACTIVITIES**

- ALL MECHANICAL CONTROLS SHALL BE CONSTRUCTED PRIOR TO STARTING EXCAVATION OPERATIONS. EXCAVATE FOR CONSTRUCTION. REMOVE EXCESS MATERIAL AND CLEARED VEGETATION FROM SITE. STABILIZE DENuded AREAS. AFTER CONSTRUCTION IS COMPLETED, PREPARE SURFACES THAT ARE TO RECEIVE FILL, BACKFILL AND TOPSOIL. COMPLETE EARTHWORK AND ESTABLISH PERMANENT PLANT MATERIAL.
- PHASE I**
- OBTAIN A GRADING PERMIT FROM HOWARD COUNTY, MARYLAND.
  - NOTIFY WATER MANAGEMENT ADMINISTRATION (WMA) AT (410)-537-3510 AT LEAST 7 DAYS BEFORE BEGINNING CONSTRUCTION AND ARRANGE A PRECONSTRUCTION MEETING ON-SITE.
  - INSTALL TREE PROTECTION AS REQUIRED BY CONTRACT AND INSPECTOR.
  - INSTALL SILT FENCE.
  - CLEAR AREA FOR STABILIZED CONSTRUCTION ENTRANCES.
  - INSTALL STABILIZED CONSTRUCTION ENTRANCE.
  - INSTALL SANDBAGS IN FRONT OF THE PRINCIPAL SPILLWAY, 12' ABOVE NORMAL POOL ELEVATION.
  - INSTALL REMOVABLE PUMP STATION.
  - INSTALL ARTICULATED INTERLOCKING CONCRETE BLOCK MATTING ALONG THE FORD CROSSING (50' LONG).
  - CLEAR REMAINING AREAS AS SHOWN.
- PHASE II**
- INSTALL REMAINING ARTICULATED INTERLOCKING CONCRETE BLOCK MATTING & CHANNEL STABILIZATION MEASURES.
  - INSTALL BOULDERS FROM THE RELOCATED AREA.
  - REHABILITATE & PAINT SHEET PILES ALONG PRINCIPAL SPILLWAY.
  - REMOVE SANDBAGS IN FRONT OF THE SPILLWAY.
  - INSTALL TURF REINFORCEMENT MAT, SEED & MULCH ALL DISTURBED AREAS.
  - STABILIZE REMAINING DISTURBED AREAS AND REMOVE SEDIMENT CONTROLS UPON APPROVAL OF WMA SEDIMENT CONTROL INSPECTORS.



This development plan is approved for soil erosion and sediment control by the HOWARD SOIL CONSERVATION DISTRICT

*John P. Robertson* 10/2/12  
 Howard SCD Date


**ENGINEER'S CERTIFICATE**  
 "I certify that this plan for sediment and erosion control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements with the Howard Soil Conservation District."

*Walter Dinicola* 3/8/13  
 Signature of Engineer (print name below signature) Date

**DEVELOPER'S CERTIFICATE**  
 "We certify that all development and construction will be done according to this plan for sediment and erosion control, and that all responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District."

*D. Mott* 3/8/13  
 Signature of Developer (print name below signature) Date

- LEGEND**
- [Hatched Box] LIMITS OF CLEARING
  - [Line with SF] SILT FENCE
  - [Dashed Line] LIMITS OF DISTURBANCE (LOD)



**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]* 3/1/13  
 Chief, Development Engineering Division CE Date

*[Signature]* 3/08/13  
 Chief, Division of Land Development Date

*[Signature]* 3-12-13  
 Director Date

Maryland Department of the Environment  
 Water Management Administration  
 Dam Safety Division

*V.P. Dalal* 10/2/12  
 Sr. Regulatory & Compliance Engineer Date

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 200  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
 PIETER DAHMEN, PE  
 HDR ENGINEERING INC.  
 MAY 7, 2012


**COLUMBIA ASSOCIATION**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947

**EROSION AND SEDIMENT CONTROL PLAN**  
**INITIAL PHASE**


**COLUMBIA ASSOCIATION**  
**TOWN CENTER**

REVISED SITE DEVELOPMENT PLAN  
 LAKE KITTAMAQUNDI DAM REPAIR  
 HOWARD COUNTY, MARYLAND


SCALE AS SHOWN  
 FEBRUARY 2011 J-06 43 59  
 DRAWING E-01, SHEET 6 OF 9  
 SDP-08-103



TYPICAL SECTION




N.T.S.



SECTION A-A


WHEEL STOP




N.T.S.

HEAD-ON PARKING

NOT TO SCALE




DETAIL




REPAIR MEASURES FOR PRINCIPAL SPILLWAY

N.T.S.



TYPICAL SECTION



N.T.S.

NOTE:  
N.T.S. DENOTES NOT TO SCALE

APPROVED: DEPARTMENT OF PLANNING AND ZONING

*[Signature]*  
Chief, Development Engineering Division



3/1/13  
Date

*[Signature]*  
Chief, Division of Land Development

3/28/13  
Date


*[Signature]*  
Director

3-12-13  
Date



PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

PIETER DAHMEN, PE  
HDR ENGINEERING INC.



COLUMBIA ASSOCIATION  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947

SECTIONS AND DETAILS

COLUMBIA ASSOCIATION  
TOWN CENTER

REVISED SITE DEVELOPMENT PLAN  
LAKE KITTAMAQUONDI DAM REPAIR  
HOWARD COUNTY, MARYLAND


SCALE AS SHOWN  
FEBRUARY 2011 J-05





DRAWING D-01, SHEET 5 OF 9


42 59

SDP-08-108





- LEGEND**
-  ARTICULATED INTERLOCKING CONCRETE BLOCK MATTING
  -  MD SHA CLASS 1 RIPRAP & CHANNEL BED BOULDERS
  -  TURF REINFORCEMENT MATTING
  -  SOIL BORING LOCATION



**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
Chief, Development Engineering Division


*[Signature]*  
Chief, Division of Land Development

*[Signature]*  
Director **MARSHA McLAUGHLIN**

Date 3/1/13

Date 3/28/13

Date 3-12-13

  
Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division

*[Signature]*  
V.P. Dalaf  
Sr. Regulatory & Compliance Engineer


Date 10/2/12

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 200  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.



DATE 7.2.07

**COLUMBIA ASSOCIATION**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947

**PROPOSED SITE PLAN**



**COLUMBIA ASSOCIATION TOWN CENTER**

REVISED SITE DEVELOPMENT PLAN  
LAKE KITTAMAQUIDI DAM REPAIR  
HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
FEBRUARY 2011 J-04


DRAWING **G-01**, SHEET **4** OF **9**

41 59  
SDP-08-108



**LEGEND**  
 LK-3 SOIL BORING LOCATION

- NOTES**
1. PRINCIPAL SPILLWAY CONSISTS OF NOTCH IN SHEET PILE.
  2. 100-YEAR FLOOD ELEVATION = 307.29ft. NAVD88 DATUM.



**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
 Chief, Development Engineering Division  
 Date: 3/1/13

*[Signature]*  
 Chief, Division of Land Development  
 Date: 3/8/13

*[Signature]*  
 Director  
 Date: 3-10-13

MDE  
 Maryland Department of the Environment  
 Water Management Administration  
 Dam Safety Division

*[Signature]*  
 V.P. Dalal  
 Sr. Regulatory & Compliance Engineer  
 Date: 10/2/12

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 300  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
 PIETER DAHMEN, PE  
 HDR ENGINEERING INC.  
 May 7, 2012

**COLUMBIA ASSOCIATION**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947

**EXISTING CONDITIONS PLAN**

**COLUMBIA ASSOCIATION TOWN CENTER**

REVISED SITE DEVELOPMENT PLAN  
 LAKE KITTAMAQUNDI DAM REPAIR  
 HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
 FEBRUARY 2011 J-03  
 DRAWING **B0-1**, SHEET **3** OF **9**

40 59  
 SDP-08-108

**HOWARD COUNTY  
GENERAL NOTES:**

- All construction shall be in accordance with the latest standards and specifications of Howard County plus MSHA standards and specifications if applicable.
- The contractor shall notify the Department of Public Works/Bureau of Engineering/Construction Inspection Division at (410) 313-1880 24-hours prior to the start of work.
- The contractor shall notify "Miss Utility" at 1-800-257-7777 at least 48 hours prior to any excavation work being done.
- Traffic control devices, markings and signing shall be in accordance with the latest edition of the Manual of Uniform Traffic Control Devices (MUTCD). All street and regulatory signs shall be in place prior to the placement of any asphalt.
- Street light placement and the type of fixture and pole shall be in accordance with the Howard County Design Manual, Volume III (1993) and as modified by "Guidelines for Street Lights in Residential Developments (June 1993)." A minimum spacing of 20' shall be maintained between any streetlight and any tree.
- All sign posts used for traffic control signs installed in the County right-of-way shall be mounted on a 2" galvanized steel, perforated, square tube post (1/4 gauge) inserted into a 2-1/2" galvanized steel, perforated, square tube sleeve (1/2 gauge) - 3' long. A galvanized steel pole cap shall be mounted on top of each post.
- All plan dimensions are to face of curb unless otherwise noted.
- The existing topography is taken from aerial survey with (maximum two foot) contour intervals prepared by Mercado Consultants Inc. dated 5-22-06.
- The coordinates shown herein are based upon the Howard County Geodetic Control, which is based upon the Maryland State Plane Coordinate System, Howard County Monument Nos. A109, 371C and "Harris AZ Mark" were used for this project.
- No permanent increase in impervious area.
- Existing utilities are based on GIS mapping.
- No floodplain study was prepared for this project.
- Project background information (unless included in title block):
  - Hydraulically dredging the upper half of the lake to its original depths.
  - Pumping the dredged material to a temporary staging area on the South Entrance Road for mechanical dewatering.
  - Trucking dewatered material to an off-site licensed placement facility.
  - Constructing a peninsula and wetlands in the upper portion of the lake to create a Forebay.
  - Install access road on Isthmus with turf reinforced matting and placement of riprap at existing overflow areas on the Isthmus to prevent further erosion.
  - Providing Imbricated riprap for erosion protection at select spots on the right bank of the Little Patuxent River.
  - Restoration of all disturbed areas, including removal of gravel & paving at the staging area.
- No grading, removal of vegetative cover or trees, paving or new structures shall be permitted outside the limits of disturbance in wetlands, streams, or their associated buffers, forest conservation easements, or 100-year floodplain without DPZ approval.
- This subject property is zoned NT per the February 2, 2004 Comprehensive Zoning Plan and per the "Comp Life" Zoning Amendments effective July 28, 2006.
- This project is exempt from the requirements of Section 16J24 of the Howard County Code for Landscaping since disturbance resulting from project activities is temporary and no permanent structures are proposed.
- This project is exempt from the requirements of Section 16J200 of the Howard County Code for Forest Conservation since it is part of a Planned Unit Development which had preliminary development plan approval and 50% or more of the land was recorded and substantially developed before December 31, 1992.
- The Contractor shall be responsible for repairs to property damage caused by the Contractor.
- Project is subject to approval by the U.S. Army Corps of Engineers, Baltimore District, the MDE Nonpoint Waterways and Waterways Division, and the MDE Dam Safety Division. Copies of the applicable permits or authorizations shall be submitted to the DPZ, Division of Land Development. MDE permit tracking number is 200863535.
- The Contractor shall comply with all applicable Federal, State and Local Laws and Regulations including project permits. Effluent leaving the site shall not exceed Maryland turbidity limits of 150 NTU at any time or 50 NTU as a monthly average per COMAR 26.08.02.
- No wetland areas landward of the ordinary high water are disturbed by the project. Wetlands within the lake (mainly nonperennial emergent and lacustrine unconsolidated bottom wetlands) are subject to disturbance from project activity, refer to JPA 2008-63535.M02.

**HOWARD SOIL CONSERVATION DISTRICT  
STANDARD SEDIMENT CONTROL NOTES**

- A minimum of 24 hours notice must be given to the Howard County Department of Inspection, Licenses and Permits, Sediment Control Division prior to the start of any construction (313-1855).
- All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the most current MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL and revisions thereto.
- Following initial soil disturbance or re-disturbance, permanent or temporary stabilization shall be completed within 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all slopes greater than 3:1, b) 14 days as to all other disturbed or graded areas on the project site.
- All sediment traps/basins shown must be fenced and warning signs posted around their perimeter in accordance with Vol. I, Chapter 12 of the HOWARD COUNTY DESIGN MANUAL, Storm Drainage.
- All disturbed areas must be stabilized within the time period specified above in accordance with the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for permanent seeding (Sec. 51), sod (Sec. 54), temporary seeding (Sec. 50) and mulching (Sec. 52). Temporary stabilization with mulch alone can only be done when recommended seeding dates do not allow for proper germination and establishment of grasses.
- All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.
- Site Analysis: Staging Area
 

Total Area of Site	1.06 Acres
Area Disturbed	1.91 Acres
Area to be roofed or paved	0.00 Acres
Area to be vegetatively stabilized	0.42 Acres
Total Cut	11.09 Cu.Yds.
Total Fill	11.09 Cu.Yds.
Total Dredging Values per 2006 Bathymetric Survey	Cu.Yds.

 Offsite waste/borrow area location: Site with an approved sediment control plan and active permit, as approved by the Inspector and Howard SCD.

Site Analysis: Isthmus Area

Total Area of Site	0.66 Acres
Area Disturbed	1.91 Acres
Area to be roofed or paved	0.00 Acres
Area to be vegetatively stabilized	0.85 Acres
Total Cut	254 Cu.Yds.
Total Fill	252 Cu.Yds.

Offsite waste/borrow area location: On Site

- Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
- Additional sediment control must be provided, if deemed necessary by the Howard County Sediment Control Inspector.
- On all sites with disturbed areas in excess of 2 acres, approval of the Inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading Inspection approvals may not be authorized until this initial approval by the Inspection agency is made.
- Trenches for the construction of utilities is limited to three pipe lengths or that which shall be back-filled and stabilized by the end of each work day, whichever is shorter.

**HOWARD SOIL CONSERVATION DISTRICT  
PERMANENT SEEDING NOTES:**

Apply to graded or cleared areas not subject to immediate further disturbance where a permanent long-lived vegetative cover is needed.

Seedbed Preparation: Loosen upper three inches of soil by raking, disking or other acceptable means before seeding, if not previously loosened.

Soil Amendments: In lieu of soil test recommendations, use one of the following schedules:

- Preferred - Apply 2 tons/acre dolomitic limestone (92 lbs/1000 sq.ft.) and 600 lbs/acre 10-10-10 fertilizer (14 lbs/1000 sq.ft.) before seeding. Harrow or disk into upper three inches of soil. At time of seeding, apply 400 lbs/acre 30-0-0 ureaform fertilizer (9 lbs/1000 sq.ft.)
- Acceptable - Apply 2 tons/acre dolomitic limestone (92 lbs/1000 sq.ft.) and 1000 lbs/acre 10-10-10 fertilizer (23 lbs/1000 sq.ft.) before seeding. Harrow or disk into upper three inches of soil.

Seeding - For the periods March 1 - April 30, and August 1 - October 15, seed with 60 lbs/acre (14 lbs/1000 sq.ft.) of Kentucky 31 Tall Fescue. For the period May 1 - July 31, seed with 60 lbs Kentucky 31 Tall Fescue per acre and 2 lbs/acre (.05 lbs/1000 sq.ft.) of weeping lovegrass. During the period of October 16 - February 28, protect site by:

Option 1 - Two tons per acre of well anchored straw mulch and seed as soon as possible in the spring.  
Option 2 - Use sod.  
Option 3 - Seed with 60 lbs/acre Kentucky 30 Tall Fescue and mulch with 2 tons/acre well anchored straw.

Mulching - Apply 1/2 to 2 tons per acre (70 to 90 lbs/1000 sq.ft.) of unrattled small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 2/8 gallons per acre (5 gal/1000 sq.ft.) of emulsified asphalt on flat areas. On slope 8 feet or higher, use 348 gallons per acre (8 gal/1000 sq.ft.) for anchoring.

Maintenance - Inspect all seeding areas and make needed repairs, replacements and reseedings.

**TEMPORARY SEEDING NOTES:**

Apply to graded or cleared areas likely to be re-disturbed where a short-term vegetative cover is needed.

Seedbed preparation: - Loosen upper three inches of soil by raking, disking or other acceptable means before seeding, if not previously loosened.

Soil Amendments: - Apply 600 lbs/acre 10-10-10 fertilizer (14 lbs/1000 sq.ft.).

Seeding: - For periods March 1 - April 30 and from August 15 - October 15, seed with 2-1/2 bushel per acre of annual rye (3.2 lbs/1000 sq.ft.). For the period May 1 - August 14, seed with 3 lbs/acre of weeping lovegrass (.07 lbs/1000 sq.ft.). For the period November 16 - February 28, protect site by applying 2 tons/acre of well anchored straw mulch and seed as soon as possible in the spring, or use sod.

Mulching: - Apply 1/2 to 2 tons/acre (70 to 90 lbs/1000 sq.ft.) of unrattled weed-free, small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 2/8 gal. per acre (5 gal/1000 sq.ft.) of emulsified asphalt on flat areas. On slope 8 ft. or higher, use 348 gal. per acre (8 gal/1000 sq.ft.) for anchoring.

Refer to the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for additional rates and methods not covered.

**22. The Department of Planning and Zoning determined that activities in the floodplain and within 75 feet of the lake and streambank are necessary for completion of the dam repair.**

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

Approved: *John R. Roberts* 10/2/12  
Howard S.C.D. Date



**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
Chief, Development Engineering Division  
Date: 3/1/13

*[Signature]*  
Chief, Division of Land Development  
Date: 3/8/13

*[Signature]*  
Director  
Date: 3-12-13

Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division

*V.P. Dalal* 10/2/12  
Sr. Regulatory & Compliance Engineer Date

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.  
May 7, 2012

**COLUMBIA ASSOCIATION  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947**

**GENERAL NOTES**

**COLUMBIA ASSOCIATION  
TOWN CENTER**  
REVISED SITE DEVELOPMENT PLAN  
**MINOR GRADING IN SUPPORT OF  
LAKE KITTAMAQUONDI RESTORATION  
ELECTION DISTRICT 4, HOWARD COUNTY MD.  
TAX MAP 30 AND 36**

SCALE AS SHOWN  
JUNE 18, 2009 J-02 39 59  
DRAWING A-01, SHEET 2 OF 8


SDP-08-103

DRAWING SHEET NO.	SHEET TITLE
<del>A-04 J-01 2: 39</del>	<del>GENERAL NOTES</del>
<del>B-04 J-03 3: 40</del>	<del>EXISTING CONDITIONS PLAN</del>
<del>C-04 J-04 4: 41</del>	<del>PROPOSED SITE PLAN</del>
<del>D-04 J-05 5: 42</del>	<del>SECTIONS AND DETAILS</del>
<del>E-01 J-06 6: 43</del>	<del>TEMPORARY EROSION &amp; SEDIMENT CONTROL PLAN - INITIAL PHASE</del>
<del>E-02 J-07 7: 44</del>	<del>TEMPORARY EROSION &amp; SEDIMENT CONTROL PLAN - FINAL PHASE</del>
<del>E-03 J-08 8: 45</del>	<del>TEMPORARY EROSION &amp; SEDIMENT CONTROL - DETAILS &amp; NOTES</del>
<del>F-04 J-09 9: 46</del>	<del>SOIL BORING LOGS</del>



J-01	38.	DAM REPAIR - TITLE SHEET
J-02	39.	DAM REPAIR - GENERAL NOTES
J-03	40.	DAM REPAIR - EXISTING CONDITION PLAN
J-04	41.	DAM REPAIR - PROPOSED SITE PLAN
J-05	42.	DAM REPAIR - SECTIONS AND DETAILS
J-06	43.	DAM REPAIR - TEMPORARY EROSION & SEDIMENT CONTROL PLAN - INITIAL PHASE
J-07	44.	DAM REPAIR - TEMPORARY EROSION & SEDIMENT CONTROL PLAN - FINAL PHASE
J-08	45.	DAM REPAIR - TEMPORARY EROSION & SEDIMENT CONTROL - DETAILS & NOTES
J-09	46.	DAM REPAIR - SOIL BORING LOGS

# Lake Kittamaquundi Dam Repair Columbia, Maryland




LOCATION PLAN  
NTS

## Columbia Association Construction Services Project No. 040107DK

SITE ANALYSIS DATA CHART			
a. TOTAL PROJECT AREA			
DAM REPAIR AREA	.039	ACRES	1,710 FT <sup>2</sup>
b. AREA OF PLAN SUBMISSION	- SEE ITEM a		
c. LIMIT OF DISTURBED AREA	.161	ACRES	7,040 FT <sup>2</sup>
d. PRESENT ZONING	NT		
e. NA. TEMPORARY MAINTENANCE EMPLOYEES			

PERMIT INFORMATION CHART					
Subdivision Name COLUMBIA TOWN CENTER		Section/Area SECTION 1		Lot/Parcel No. LOT 14	
Plat # or L/F PHASE 23 PLAT BOOK 16 FOLIO 19 & 20	Grid #	Zoning NT	Tax Map No. 30 & 36	Elect Distr 4	Census Tract 605602
Water Code		Sewer Code			



**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
Chief, Development Engineering Division  
Date: 3/1/13

*[Signature]*  
Chief, Division of Land Development  
Date: 3/8/13

*[Signature]*  
Director  
Date: 3-12-13

MDE  
Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division

*[Signature]*  
V.P. Dalal  
Sr. Regulatory & Compliance Engineer  
Date: 10/2/12


PROFESSIONAL CERTIFICATION. I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 29997, EXPIRATION DATE: 01-14-2014.

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.  
May 7, 2012



COLUMBIA ASSOCIATION  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947


GP-12-018

**COLUMBIA ASSOCIATION TOWN CENTER**

Revised Site Development Plan  
LAKE KITTAMAQUUNDI DAM REPAIR  
HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
FEBRUARY 2011

DRAWING J-01 SHEET 4 OF 9



- Length - minimum of 50', or as shown on plans (30' for single residence lot).
- Width - 10' minimum, should be flared at the existing road to provide a turning radius.
- Geotextile fabric (filter cloth) shall be placed over the existing ground prior to placing stone. The plan approval authority may not require single family residences to use geotextile.
- Stone - crushed aggregate (2" to 3") or reclaimed or recycled concrete equivalent shall be placed at least 6" deep over the length and width of the entrance.
- Surface Water - all surface water flowing to or diverted toward construction entrances shall be piped through the entrance, maintaining positive drainage. Pipe installed through the stabilized construction entrance shall be protected with a mountable berm with 5:1 slopes and a minimum of 6" of stone over the pipe. Pipe has to be sized according to the drainage. When the SCE is located at a high spot and has no drainage to convey a pipe will not be necessary. Pipe should be sized according to the amount of runoff to be conveyed. A 6" minimum will be required.
- Location - A stabilized construction entrance shall be located at every point where construction traffic enters or leaves a construction site. Vehicles leaving the site must travel over the entire length of the stabilized construction entrance.

**STABILIZED CONSTRUCTION ENTRANCE** 1  
E-03

**Construction Specifications**

- Fence posts shall be a minimum of 36" long driven 16" minimum into the ground. Wood posts shall be 1 1/2" x 1 1/2" square (minimum) cut, or 1 3/4" diameter (minimum) round and shall be of sound quality hardwood. Steel posts will be standard T or U section weighting not less than 1.00 pound per linear foot.
- Geotextile shall be fastened securely to each fence post with wire ties or staples at top and mid-section and shall meet the following requirements for Geotextile Class F:





Tensile Strength	50 lbs/in (min.)	Test: MSMT 509
Tensile Modulus	20 lbs/in (min.)	Test: MSMT 509
Flow Rate	0.3 gal ft <sup>2</sup> /minute (max.)	Test: MSMT 322
Filtering Efficiency	75% (min.)	Test: MSMT 322

- Where ends of geotextile fabric come together, they shall be overlapped, folded and stapled to prevent sediment bypass.
- Silt Fence shall be inspected after each rainfall event and maintained when bulges occur or when sediment accumulation reached 50% of the fabric height.


**Silt Fence Design Criteria**

Slope Steepness	Silt Fence Length	
	(Maximum) Slope Length	(Maximum) Silt Fence Length
Flatter than 50:1	unlimited	unlimited
50:1 to 10:1	125 feet	1,000 feet
10:1 to 5:1	100 feet	750 feet
5:1 to 3:1	60 feet	500 feet
3:1 to 2:1	40 feet	250 feet
2:1 and steeper	20 feet	125 feet

Note: In areas of less than 2X slope and sandy soils (USDA general classification system, soil Class A) maximum slope length and silt fence length will be unlimited. In these areas a silt fence may be the only perimeter control required.




**SILT FENCE** 3  
E-03



- Construction Specifications**
- The outer pipe should be 48" dia. or shall, in any case, be at least 4" greater in diameter than the center pipe. The outer pipe shall be wrapped with 1/2" hardware cloth to prevent backfill material from entering the perforations.
  - After installing the outer pipe, backfill around outer pipe with 2" aggregate or clean gravel.
  - The inside stand pipe (center pipe) should be constructed by perforating a corrugated or PVC pipe between 12" and 36" in diameter. The perforations shall be 1/2" x 6" slits or 1" diameter holes 6" on center. The center pipe shall be wrapped with 1/2" hardware cloth first, then wrapped again with Geotextile Class C.
  - The center pipe should extend 12' to 18' above the anticipated water surface elevation or riser crest elevation when dewatering a basin.

**REMOVABLE PUMPING STATION (RPS)** 4  
E-03




**TREE PROTECTION** 5  
E-03

**Construction and Material Specifications**

- Topsoil salvaged from the existing site may be used provided that it meets the standards as set forth in these specifications. Typically, the depth of topsoil to be salvaged for a given soil type can be found in the representative soil profile section in the Soil Survey published by USDA-SCS in cooperation with Maryland Agricultural Experimental Station.
- Topsoil Specifications - Soil to be used as topsoil must meet the following:
  - Topsoil shall be a loam, sandy loam, clay loam, silt loam, sandy clay loam, loamy sand, or other soils may be used if recommended by an agronomist or soil scientist and approved by the appropriate approval authority. Regardless, topsoil shall not be a mixture of contrasting textured subsoils and shall contain less than 5% by volume of cinders, stones, slag, coarse fragments, gravel, sticks, roots, trash, or other materials larger than 1 1/2" in diameter.
  - Topsoil must be free of plants or plant parts such as bermuda grass, quackgrass, Johnsongrass, nutsedge, poison ivy, chistle, or others as specified.
  - Where the subsoil is either highly acidic or composed of heavy clays, ground limestone shall be spread at the rate of 48 tons/acre (200-400 pounds per 1,000 square feet) prior to the placement of topsoil. Lime shall be distributed uniformly over designated areas and worked into the soil in conjunction with tillage operations as described in the following procedures.
- For sites having disturbed areas under 5 acres:
  - Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section I - Vegetative Stabilization Methods and Materials.
- For sites having disturbed areas over 5 acres:
  - On soil meeting topsoil specifications, obtain test results dictating fertilizer and lime amendments required to bring the soil into compliance with the following:
    - pH for topsoil shall be between 6.0 and 7.5. If the tested soil demonstrates a pH of less than 6.0, sufficient lime shall be prescribed to raise the pH to 6.5 or higher.
    - Organic content of topsoil shall be not less than 1.5 percent by weight.
    - Topsoil having soluble salt content greater than 500 parts per million shall not be used.
    - No sod or seed shall be placed on soil which has been treated with soil sterilants or chemicals used for weed control until sufficient time has elapsed (14 days min.) to permit dissipation of phytotoxic materials.
  - Note: Topsoil substitutes or amendments, as recommended by a qualified agronomist or soil scientist and approved by the appropriate approval authority, may be used in lieu of natural topsoil.
  - Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section I - Vegetative Stabilization Methods and Materials.
- Topsoil Application:
  - When topsoiling, maintain needed erosion and sediment control practices such as diversions, Grade Stabilization Structures, Earth Bikes, Slope Silt Fence and Sediment Traps and Basins.
  - Grades on the areas to be topsoiled, which have been previously established, shall be maintained, albeit 4" - 8" higher in elevation.
  - Topsoil shall be uniformly distributed in a 4" - 8" layer and lightly compacted to a minimum thickness of 4". Spreading shall be performed in such a manner that soiling or seeding can proceed with a minimum of soil and soil preparation and tillage. Any irregularities in the surface resulting from topsoiling or other operations shall be corrected in order to prevent the formation of depressions or water pockets.
  - Topsoil shall not be placed while the topsoil or subsoil is in a frozen or muddy condition, when the subsoil is excessively wet or in a condition that may otherwise be detrimental to proper grading and seedbed preparation.

**TOPSOILING** 2  
E-03

- Construction Specifications**
- Key-in the matting by placing the top ends of the matting in a narrow trench, 6" in depth. Backfill the trench and tamp firmly to conform to the channel cross-section. Secure with a row of staples about 4' down slope from the trench. Spacing between staples is 6'.
  - Staple the 4" overlap in the channel center using an 18" spacing between staples.
  - Before stapling the outer edges of the matting, make sure the matting is smooth and in firm contact with the soil.
  - Staples shall be placed 2' apart with 4 rows for each strip, 2 outer rows, and 2 alternating rows down the center.
  - Where one roll of matting ends and another begins, the end of the top strip shall overlap the upper end of the lower strip by 4', shiplap fashion. Reinforce the overlap with a double row of staples spaced 6' apart in a staggered pattern on either side.
  - The discharge end of the matting liner should be similarly secured with 2 double rows of staples.
- Note: If flow will enter from the edge of the matting then the area effected by the flow must be keyed-in.



**EROSION CONTROL MATTING** 6  
E-03

THIS DEVELOPMENT PLAN IS APPROVED FOR EROSION AND SEDIMENT CONTROL BY THE HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

Approved: *[Signature]* Director

**TEMPORARY EROSION AND SEDIMENT CONTROL DETAILS AND NOTES**

**COLUMBIA ASSOCIATION TOWN CENTER**

REVISED SITE DEVELOPMENT PLAN - LAKE KITTAMAQUINDI DAM REPAIR HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
FEBRUARY 2011 J-08 45 59  
DRAWING E-03, SHEET 8 OF 8

APPROVED: DEPARTMENT OF PLANNING AND ZONING

*[Signature]* 3/1/13  
Chief, Development Engineering Division

*[Signature]* 3/08/13  
Chief, Division of Land Development

*[Signature]* 3-12-13  
Director MACHA McLAUGHLIN

MDE  
Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division

*[Signature]* 10/2/12  
V. P. Dalal  
Sr. Regulatory & Compliance Engineer


THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
5700 LAKE WRIGHT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA 23502  
757-222-1500


PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.

COLUMBIA ASSOCIATION  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947



- NOTES**
- DO NOT REMOVE EXISTING ROOTBALL OF REMOVED TREES. GRIND STUMP TO 6-INCH MINIMUM BELOW SURFACE.
  - ALL DISTURBED AREAS SHALL BE TOPSOILED, SEEDED, FERTILIZED, AND MULCHED.



This development plan is approved for soil erosion and sediment control by the HOWARD SOIL CONSERVATION DISTRICT


*John K. Roberts*  
 Howard SOCD Date 4/2/12

ENGINEER'S CERTIFICATE  
 "I certify that this plan for sediment and erosion control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements with the Howard Soil Conservation District."

*Walter Dinicola*  
 Signature of Engineer (print name below signature) Date 3/8/13  
 Walter Dinicola

"We certify that all development and construction will be done according to this plan for sediment and erosion control, and that all responsible personnel involved in the construction project, will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District."

*D. Nash*  
 Signature of Developer (print name below signature) Date 3.8.13



- LEGEND**
- ARTICULATED INTERLOCKING CONCRETE BLOCK MATTING
  - SILT FENCE
  - LIMITS OF DISTURBANCE (LOD)

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*[Signature]*  
 Chief, Development Engineering Division Date 2/1/13

*[Signature]*  
 Chief, Division of Land Development Date 3/08/13

*[Signature]*  
 Director MARINA MCLAUGHLIN Date 3-12-13

Maryland Department of the Environment  
 Water Management Administration  
 Dam Safety Division

*V.P. Datal*  
 Visty P. Datal  
 Sr. Regulatory & Compliance Engineer Date 10/2/12

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
 HDR Engineering, Inc.  
 5700 LAKE WRIGHT DRIVE  
 SUITE 200  
 NORFOLK, VIRGINIA 23502  
 757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
 PIETER DAHMEN, PE  
 HDR ENGINEERING INC.  
 M 47 7, 2012

**COLUMBIA ASSOCIATION**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21044  
 (410)-381-2947

**TEMPORARY EROSION AND SEDIMENT CONTROL PLAN FINAL PHASE**

**COLUMBIA ASSOCIATION TOWN CENTER**

REVISED SITE DEVELOPMENT PLAN  
 LAKE KITTAMAQUNDI DAM REPAIR  
 HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
 FEBRUARY 2011 J-07 44 59  
 DRAWING E-02 SHEET 7 OF 9

SDP-08-103

PROJECT #: 95522 PROJECT: Lake Kittamaqundi STRUCTURE: West End of Dam		LK-1 PAGE 1 OF 1	
LOCATION: OFFSET: LATITUDE: "N LONGITUDE: "W SURFACE ELEVATION: 299.6 ft COORD. DATUM: NAD 83		Date(s) Drilled: 11/5/08 - 11/5/08 Drilling Method(s): Hollow Stem Auger w/SPTs SPT Method: Automatic Hammer Other Test(s): Driller: Andy Bisette/F&R Logger: Sue Young/HDR	
FIELD DATA		LAB DATA	
SOIL		ROCK	
DEPTH (ft)		LIQUID LIMIT	
ELEVATION (ft)		PLASTICITY INDEX	
STANDARD PENETRATION TEST HANMER BLOWS		MOISTURE CONTENT (%)	
% SOIL RECOVERY			
SAMPLE INTERVAL			
Core Recovery			
ROCK QUALITY DESIGNATION			
STRATA			
DIP			
STRATA LEGEND			
GROUND WATER			
- 8 feet at 0 hrs NO LONG TERM MEASUREMENTS TAKEN			
DESCRIPTION OF STRATA			
0.0 / 299.6 Topsoil TOPS			
0.2 / 299.4 Red brown CLAYEY SAND, medium dense, moist, micaceous SC		44 18 15.0	
Same, red brown and gray, moist			
4.8 / 294.8 Dark gray SILT, trace fine sand, very soft to soft, very moist, micaceous MH Lenses of red brown sandy silt below 7.5 feet		0.5	
Trace small well rounded pebbles			
Wet at 9 feet		57 25 52.5 0.75	
10.3 / 289.3 Medium gray, SAND, SILT AND GRAVEL, very dense, wet (saturated) GP-GM		0.25	
12.0 / 287.6 DECOMPOSED GRANITE, recovered as tan to pink silt, and rock fragments GRN			
Auger refusal at 15.5 feet			
REMARKS: RIG TYPE: CME-75 truck mounted rig. Boring tremie grouted upon completion Water entering boring when 0 hr water level taken		PAGE 1 OF 1 LK-1	

PROJECT #: 95522 PROJECT: Lake Kittamaqundi STRUCTURE: Center of Dam		LK-2 PAGE 1 OF 1	
LOCATION: OFFSET: LATITUDE: "N LONGITUDE: "W SURFACE ELEVATION: 298.7 ft COORD. DATUM: NAD 83		Date(s) Drilled: 11/5/08 - 11/5/08 Drilling Method(s): Hollow Stem Auger w/SPTs SPT Method: Automatic Hammer Other Test(s): Driller: Andy Bisette/F&R Logger: Sue Young/HDR	
FIELD DATA		LAB DATA	
SOIL		ROCK	
DEPTH (ft)		LIQUID LIMIT	
ELEVATION (ft)		PLASTICITY INDEX	
STANDARD PENETRATION TEST HANMER BLOWS		MOISTURE CONTENT (%)	
% SOIL RECOVERY			
SAMPLE INTERVAL			
Core Recovery			
ROCK QUALITY DESIGNATION			
STRATA			
DIP			
STRATA LEGEND			
GROUND WATER			
4.7 feet at 0 hrs NO LONG TERM MEASUREMENTS TAKEN			
DESCRIPTION OF STRATA			
0.0 / 298.7 Leaves, roof mat OH			
0.2 / 298.5 Fill, recovered as tan rock fragments, very dense, dry FL		44 21 18.2 2.75	
2.5 / 296.2 Brown fine SANDY CLAY, trace gravel, stiff to medium stiff, moist, micaceous CL		1.75	
4.5 / 294.2 Brown gray CLAY, very soft to medium stiff, moist, micaceous CL		1.25	
Trace fine sand and small gravel lenses, wet below 7.5 feet			
9.2 / 289.5 Gray, tan, and brown GRAVEL, SAND, SILT, medium dense, wet GP-GM		54 15 31.8 0.25	
12.0 / 286.7 DECOMPOSED GRANITE, recovered as gray, tan, and brown sand, silt, and rock fragments GRN			
Auger refusal at 14.0 feet			
REMARKS: RIG TYPE: CME-75 truck mounted rig. Boring tremie grouted upon completion, boring located adjacent to gravel access road		PAGE 1 OF 1 LK-2	

PROJECT #: 95522 PROJECT: Lake Kittamaqundi STRUCTURE: East End of Dam		LK-3 PAGE 1 OF 1	
LOCATION: OFFSET: LATITUDE: "N LONGITUDE: "W SURFACE ELEVATION: 298.5 ft COORD. DATUM: NAD 83		Date(s) Drilled: 11/5/08 - 11/5/08 Drilling Method(s): Hollow Stem Auger w/SPTs SPT Method: Automatic Hammer Other Test(s): Driller: Andy Bisette/F&R Logger: Sue Young/HDR	
FIELD DATA		LAB DATA	
SOIL		ROCK	
DEPTH (ft)		LIQUID LIMIT	
ELEVATION (ft)		PLASTICITY INDEX	
STANDARD PENETRATION TEST HANMER BLOWS		MOISTURE CONTENT (%)	
% SOIL RECOVERY			
SAMPLE INTERVAL			
Core Recovery			
ROCK QUALITY DESIGNATION			
STRATA			
DIP			
STRATA LEGEND			
GROUND WATER			
6.6 feet at 1 hr NO LONG TERM MEASUREMENTS TAKEN			
DESCRIPTION OF STRATA			
0.0 / 298.5 Topsoil TOPS			
0.2 / 298.3 Red brown fine SILTY SAND, some small gravel, medium dense, moist, micaceous ML		2.25	
1.8 / 296.7 Red brown fine CLAYEY SAND, loose to very loose, moist, micaceous SC		46 20 20.8	
5.5 / 293.0 Red brown fine SILTY SAND, very loose, moist, micaceous SM		47 18 28.3	
8.2 / 290.3 Gray fine SANDY SILT, very soft, wet ML			
8.8 / 289.7 Gray and tan GRAVEL, SILT, and SAND, medium dense, wet GP-GM			
10.2 / 288.3 DECOMPOSED GRANITE, recovered as gray, dark gray, and tan, sand, silt, and rock fragments GRN Top of weathered rock at 10.2 feet		0.25	
Auger refusal at 19.3 feet			
REMARKS: RIG TYPE: CME-75 truck mounted rig. Boring tremie grouted upon completion		PAGE 1 OF 1 LK-3	

APPROVED: DEPARTMENT OF PLANNING AND ZONING

*[Signature]*  
Chief, Development Engineering Division  
Date: 3/1/13

*[Signature]*  
Chief, Division of Land Development  
Date: 3/28/13

*[Signature]*  
Director MARSHA MCLAUGHLIN  
Date: 3-12-13

Maryland Department of the Environment  
Water Management Administration  
Dam Safety Division

*[Signature]*  
V.P. Datal  
Sr. Regulatory & Compliance Engineer  
Date: 10/2/12

THIS PLAN SET HAS BEEN PREPARED BY:

**HDR**  
HDR Engineering, Inc.  
6700 LAKE WRIGHT DRIVE  
SUITE 300  
NORFOLK, VIRGINIA 23502  
757-222-1500

PLANS HAVE BEEN DESIGNED UNDER MY SUPERVISION

*[Signature]*  
PIETER DAHMEN, PE  
HDR ENGINEERING INC.  
Date: May 7, 2012

COLUMBIA ASSOCIATION  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21044  
(410)-381-2947

SOIL BORING LOGS

COLUMBIA ASSOCIATION  
TOWN CENTER

REVISED SITE DEVELOPMENT PLAN  
LAKE KITTAMAQUNDI DAM REPAIR  
HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
FEBRUARY 2011 J-09 46 59  
DRAWING F-01, SHEET 9 OF 9  
SDP-08-103

# LAKE KITTAMAQUUNDI MULTIUSE TRAIL CONSTRUCTION DRAWINGS COLUMBIA ASSOCIATION HOWARD COUNTY, MARYLAND


## GENERAL NOTES

- HORIZONTAL AND VERTICAL SURVEY CONTROLS:  
THE COORDINATES SHOWN ON THE DRAWINGS ARE BASED ON MARYLAND STATE REFERENCE SYSTEM NAD 83/91 AS PROJECTED BY HOWARD COUNTY GEODETIC CONTROL STATIONS HOWARD CO. BM 30 BA AND BM 36 EA. ALL VERTICAL CONTROLS ARE BASED NAVD 88. VERTICAL CONTROLS PROVIDED ON THE DRAWINGS ARE BM 30 BA AND BM 36 EA.
- THE EXISTING UTILITIES, GRADES, AND OBSTRUCTIONS SHOWN ARE FROM THE BEST AVAILABLE RECORDS AND SHALL BE VERIFIED BY THE CONTRACTOR TO HIS SATISFACTION PRIOR TO CONSTRUCTION. NECESSARY PRECAUTIONS SHALL BE TAKEN BY THE CONTRACTOR TO PROTECT EXISTING SERVICES AND MAINS AND ANY DAMAGE TO THEM SHALL BE REPAIRED IMMEDIATELY AT HIS OWN EXPENSE.
- CONTOURS SHOWN OUTSIDE OF LIMIT OF WORK ARE BASED ON HOWARD COUNTY 2011 GIS TOPOGRAPHY.
- PROPERTY LINES SHOWN ARE BASED ON HOWARD COUNTY 2012 CADASTRAL DATA.
- WETLAND DELINEATION WAS PERFORMED BY BAYLAND CONSULTANTS & DESIGNERS, INC. ON JUNE 16TH 2013.
- THE MARYLAND DEPARTMENT OF THE ENVIRONMENT PERMIT TRACKING NUMBER IS 201460150.
- FEMA FIRM #24027C01550 EFFECTIVE NOVEMBER 6, 2013 SHOWS THAT THE PROJECT SITE IS LOCATED WITHIN ZONE A.
- RIPRAP SHOWN IN PLAN VIEW AND PROFILE ARE SYMBOLIC AND DO NOT REPRESENT INDIVIDUAL STONES.
- THE SITE IS WITHIN THE LITTLE PATUXENT RIVER WATERSHED.
- FOR DETAILS, MATERIALS, AND CONSTRUCTION METHODS NOT SHOWN ON THE DRAWINGS, THE CONTRACTOR SHALL REFER TO HOWARD COUNTY DESIGN MANUAL, VOLUME IV, STANDARD SPECIFICATIONS AND DETAILS FOR CONSTRUCTION. THE CONTRACTOR SHALL HAVE A COPY VOLUME IV ON SITE AT ALL TIMES.
- THIS PLAN IS EXEMPT FROM FOREST CONSERVATION REQUIREMENTS UNDER SUBSECTION 16.1202(b)(1)(iv) SINCE IT IS PART OF A PLANNED UNIT DEVELOPMENT WHICH HAD PRELIMINARY PLAN APPROVAL AND 50% OR MORE OF THE LAND WAS RECORDED AND SUBSTANTIALLY DEVELOPED BEFORE DECEMBER 31, 1992.
- LANDSCAPING FOR THIS PLAN IS PROVIDED BY ALTERNATIVE COMPLIANCE BASED ON EXISTING SITE CONDITIONS AND VEGETATION.
- THIS PLAN IS SUBJECT TO WAIVER PETITION WP-14-079, APPROVED ON FEBRUARY 18, 2014. WP-14-079 APPROVES A WAIVER TO SUBSECTIONS 16.115(c)(2), 16.116(g)(1), AND 16.116(g)(2)(iii) WHICH IS SUBJECT TO THE FOLLOWING CONDITIONS:
  - HOWARD COUNTY APPROVAL OF REDLINE REVISION NO. 3 TO SDP-08-108
  - STATE AND FEDERAL AUTHORIZATION OF REGULATED ACTIVITIES
  - OBTAIN ALL REQUIRED PERMITS FROM THE HOWARD COUNTY DEPARTMENT OF INSPECTIONS, LICENSES, AND PERMITS.
  - OBTAIN ALL NECESSARY PERMISSION AND AGREEMENTS FROM THE MARYLAND STATE HIGHWAY ADMINISTRATION (SHA) FOR THE PORTIONS OF THE PATHWAY LOOP LOCATED WITHIN THE US ROUTE 29 RIGHT-OF-WAY.

## STORMWATER MANAGEMENT NOTE

STORMWATER MANAGEMENT REQUIREMENTS WILL BE PROVIDED FOR THE PROPOSED PAVED TRAIL AS SHOWN ON THIS PLAN VIA NON-ROOFTOP DISCONNECTION IN ACCORDANCE WITH THE CURRENT HOWARD COUNTY DESIGN MANUAL, VOLUME I: STORM DRAINAGE, CHAPTER 5: STORMWATER MANAGEMENT. A SIMPLIFIED ENVIRONMENTAL CONCEPT PLAN WAS APPROVED ON JANUARY 13, 2014.

APPROVED  
PLANNING BOARD  
of HOWARD COUNTY  
DATE 6/5/2014



HOWARD COUNTY ADC MAP COORDINATES: MAP 15 GRID H-5 MAP COPYRIGHT UNIVERSAL MAP GROUP LLC. PERMITTED USE NUMBER 20911186

## LOCATION MAP

SCALE: 1"=2000'

## LEGEND

TRaverse POINT	△	PROP. PATH	
EX. SPOT SHOT	X ELEV	PROP. BOARDWALK	
EX. BOUNDARY	---	PROP. IMBRICATED ROCK WALL	
EX. MINOR CONTOUR	---	PROP. CONSTRUCTION ACCESS	
EX. MAJOR CONTOUR	---	LIMIT OF DISTURBANCE	LOD
EX. ROAD	---	SILT FENCE	SF
EX. TREELINE	---	TURBIDITY CURTAIN	TC
EX. VEGETATED BUFFER	VB	TEMPORARY ACCESS BRIDGE	TB
EX. WATERS OF THE U.S.	WUS		
EX. 100-YR FEMA FLOODPLAIN	---		
EX. 15' NON-TIDAL WETLAND BUFFER	---		
EX. NON-TIDAL WETLANDS	---		
EX. IMBRICATED RIPRAP WALL	---		

## PROJECT INFORMATION

1. OWNER/DEVELOPER:	COLUMBIA ASSOCIATION CONTACT: DENNIS MATTEY
2. OWNER/DEVELOPER INFORMATION:	9450 GERWIG LANE COLUMBIA, MD 21046 410-381-0591
3. ENGINEER:	BAYLAND CONSULTANTS AND DESIGNERS, INC.
4. ENGINEER INFORMATION:	1321 MERCEDES DRIVE, SUITE A HANOVER, MARYLAND 21076 PH: 410-694-9401
5. TAX MAP:	0036
6. PARCEL:	0210
7. DEED REF:	03324/00191
8. DISTRICT:	15
9. HO. COUNTY TAX ID NO:	15-010657
10. USE:	OPEN SPACE
11. ZONING:	NEW TOWN
12. PROPERTY AREA:	39.8± ACRES
13. WATERSHED:	LITTLE PATUXENT RIVER

## INDEX OF SHEETS

DRAWING NO.	SHEET NO.	SHEET TITLE
K-01	47	MULTIUSE TRAIL - COVER SHEET
K-02	48	MULTIUSE TRAIL - KEY SHEET
K-03	49	MULTIUSE TRAIL - DESIGN PLANS
K-04	50	MULTIUSE TRAIL - DESIGN PLANS
K-05	51	MULTIUSE TRAIL - DESIGN PLANS
K-06	52	MULTIUSE TRAIL - DESIGN PLANS
K-07	53	MULTIUSE TRAIL - DESIGN PLANS
K-08	54	MULTIUSE TRAIL - CROSS SECTIONS & DETAILS
K-09	55	MULTIUSE TRAIL - BOARDWALK DETAILS
K-10	56	MULTIUSE TRAIL - BOARDWALK DETAILS
K-11	57	MULTIUSE TRAIL - EROSION AND SEDIMENT CONTROL PLAN
K-12	58	MULTIUSE TRAIL - EROSION AND SEDIMENT CONTROL PLAN
K-13	59	MULTIUSE TRAIL - EROSION AND SEDIMENT CONTROL NOTES & DETAILS

## SITE ANALYSIS

1. TOTAL DISTURBED AREA:	2.87 ACRES
2. TOTAL AREA TO BE STABILIZED:	2.87 ACRES
2.1. TOTAL EX. IMP. AREA:	0.00 ACRES
2.2. TOTAL PR. IMPERVIOUS AREA:	0.55 ACRES
2.3. TOTAL STABILIZED CONSTRUCTION ACCESS:	0.33 ACRES
2.4. TOTAL TO BE VEGETATIVELY STABILIZED:	1.99 ACRES
3. PROPOSED IMPERVIOUS AREA:	0.88 ACRES
4. ESTIMATED CUT:	620 CY
5. ESTIMATED FILL:	0 CY

NOTE:  
THE EARTHWORK QUANTITIES SHOWN HEREON ARE FOR INFORMATION PURPOSES ONLY. BAYLAND MAKES NO GUARANTEES OF ACCURACY OF QUANTITIES OR BALANCE OF SITE. THE CONTRACTOR SHALL TAKE FULL RESPONSIBILITY OF ACTUAL EARTHWORK QUANTITIES ENCOUNTERED DURING CONSTRUCTION.

## PROFESSIONAL CERTIFICATION

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. 21194, EXPIRATION DATE: 04/20/2016.

## REVISED SITE DEVELOPMENT PLAN

### LAKE KITTAMAQUUNDI MULTIUSE TRAIL COVER SHEET


DATE		BY	REVISIONS	DESCRIPTION	SCALE: AS-SHOWN

## APPROVED: DEPARTMENT OF PLANNING AND ZONING


<u>Chad Clark</u> Chief, Development Engineering Division Asst	5.9.14 Date
<u>Keith Sheehy</u> Chief, Division of Land Development	6-09-14 Date
<u>Mark A. Gyll</u> Director	6/9/14 Date

**Columbia Association**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21046  
(410) 381-2947

**Bayland Consultants & Designers, Inc.**  
"Integrating Engineering and Environment"  
1321 Mercedes Drive, Suite A Phone: (410)694-9401  
Hanover, Maryland 21076 Fax: (410)694-9405  
Email: bayland@baylandinc.com  
Website: http://www.baylandinc.com  
BAYLAND JOB NO. 8\_16202







**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*Chad Elch*  
 Chief, Development Engineering Division *HSP*      Date 5.9.14

*Walter D. ...*  
 Chief, Division of Land Development *WJD*      Date 6.09.14

*Walter D. ...*  
 Director *WJD*      Date 6/9/14

**APPROVED**  
 PLANNING BOARD  
 of HOWARD COUNTY  
 DATE 6/5/2014

**Columbia Association**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21046  
 (410) 381 - 2947

**BayLand Consultants & Designers, Inc.**  
 "Integrating Engineering and Environment"  
 1321 Mercedes Drive, Suite A Phone: (410)694-9401  
 Hanover, Maryland 21076 Fax: (410)694-9405  
 Email: bayland@baylandinc.com  
 Website: http://www.baylandinc.com  
 BAYLAND JOB NO. 8\_16202




**REVISED SITE DEVELOPMENT PLAN**  
**LAKE KITTAMAQUONDI MULTIUSE TRAIL**  
**KEY SHEET**

DATE		BY	REVISIONS	DESCRIPTION

SCALE: 1" = 50'

DRAWN BY: MKB      DATE: 04/21/14  
 CHECKED BY: SB      DATE: 4/21/2014  
 DESIGNED BY: MKB      DATE: 04/21/14  
 DRAWING K-02, SHEET NO. 48 OF 59  
 SDP-08-108


COLUMBIA ASSOCIATION INC.  
L 502 F 5E1  
FB 15 P20  
PARCEL 210  
**LAKE KITTAMAQUONDI**



**PLAN**  
SCALE: 1" = 20'

LINE	LENGTH	DIRECTION	START	END
L1	96.25'	N19°52'58"E	N: 564,302 E: 1,354,109	N: 564,383 E: 1,354,141
L2	64.70'	N18°01'07"E	N: 564,423 E: 1,354,152	N: 564,485 E: 1,354,172
L3	8.16'	N21°10'56"E	N: 564,537 E: 1,354,190	N: 564,544 E: 1,354,193
L4	34.53'	N18°36'14"E	N: 564,555 E: 1,354,197	N: 564,588 E: 1,354,208
L5	29.41'	N10°38'13"E	N: 564,655 E: 1,354,226	N: 564,684 E: 1,354,231
L6	21.08'	N13°06'15"E	N: 564,705 E: 1,354,236	N: 564,726 E: 1,354,240
L7	42.10'	N19°36'21"W	N: 564,762 E: 1,354,238	N: 564,802 E: 1,354,224

CURVE	RADIUS	LENGTH	CHORD DIRECTION	TANGENT	DELTA
C1	1000'	32.54'	N18°57'02"E	16.27'	1°51'51"
C2	1000'	55.22'	N19°36'01"E	27.62'	3°09'49"
C3	250'	11.25'	N19°53'35"E	5.63'	2°34'42"
C4	500'	89.53'	N14°37'13"E	34.82'	7°58'01"
C5	500'	21.53'	N11°52'14"E	10.77'	2°28'03"
C6	65'	37.11'	N3°15'03"W	19.08'	32°42'36"



**PROFILE OF PROPOSED TRAIL STA: 100+00 TO STA: 105+50**

HORIZONTAL: 1" = 20'  
VERTICAL: 1" = 5'


**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

Chief, Development Engineering Division *H&P* Date 5.9.14

Chief, Division of Land Development *EWB* Date 6-09-14


Director *March M. Cayle* Date 6/9/14

**APPROVED**  
PLANNING BOARD  
of HOWARD COUNTY  
DATE 6/5/2014



**Columbia Association**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21046  
(410) 381-2947

**Bayland Consultants & Designers, Inc.**  
"Integrating Engineering and Environment"  
1321 Mercedes Drive, Suite A Phone: (410)694-9401  
Hanover, Maryland 21076 Fax: (410)694-9405  
Email: bayland@baylandinc.com  
Website: http://www.baylandinc.com  
BAYLAND JOB NO. 8\_16202




**REVISED SITE DEVELOPMENT PLAN**  
**LAKE KITTAMAQUONDI MULTIUSE TRAIL DESIGN PLANS**


DATE	BY	REVISIONS DESCRIPTION	SCALE: 1" = 20'

DRAWN BY: MKB DATE: 04/21/14  
CHECKED BY: SB DATE: 4/21/2014  
DESIGNED BY: MKB DATE: 04/21/14  
DRAWING K-03, SHEET NO. 49 OF 59  
SDP-08-108

Z:\03-16202\LAKE\_KITTAMAQUONDI\MULTIUSE TRAIL\CAD Files\Sheet Files\8\_16202\_SDP01



**PLAN**  
SCALE: 1" = 20'




**PROFILE OF PROPOSED TRAIL STA: 105+25 TO STA: 111+50**

**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

Chief, Development Engineering Division *HS* Date 5-9-14  
  
 Chief, Division of Land Development *DS* Date 6-09-14  
  
 Director *M. K. O'Connell* Date 6/9/14


**APPROVED**  
PLANNING BOARD  
OF HOWARD COUNTY  
DATE 6/5/2014



HORIZONTAL : 1" = 20'  
VERTICAL : 1" = 5'

**Columbia Association**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21046  
(410) 381 - 2947

**Bayland Consultants & Designers, Inc.**  
"Integrating Engineering and Environment"  
1321 Mercedes Drive, Suite A Phone: (410)694-9401  
Hanover, Maryland 21076 Fax: (410)694-9405  
Email: bayland@baylandinc.com  
Website: http://www.baylandinc.com  
BAYLAND JOB NO. 8\_16202





**REVISED SITE DEVELOPMENT PLAN**

**LAKE KITTAMAQUUNDI MULTIUSE TRAIL DESIGN PLANS**

REVISIONS		SCALE: 1" = 20'	
DATE	BY	DESCRIPTION	

DRAWN BY: MKB DATE: 04/21/14  
 CHECKED BY: SB DATE: 4/21/2014  
 DESIGNED BY: MKB DATE: 04/21/14  
 DRAWING K-04, SHEET NO. 50 OF 59  
**SDP-08-108**




APPROVED: DEPARTMENT OF PLANNING AND ZONING

Chief, Development Engineering Division *MSR* Date 5-9-14

Chief, Division of Land Development *MSR* Date 6-09-14

Director *Mark A. Gough* Date 6/9/14


APPROVED  
PLANNING BOARD  
of HOWARD COUNTY  
DATE 6/5/2014



HORIZONTAL : 1" = 20'  
VERTICAL : 1" = 5'

**Columbia Association**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21046  
(410) 381 - 2947


**Bayland Consultants & Designers, Inc.**  
"Integrating Engineering and Environment"  
1321 Mercedes Drive, Suite A Phone: (410)694-9401  
Hanover, Maryland 21076 Fax: (410)694-9405  
Email: bayland@baylandinc.com  
Website: http://www.baylandinc.com  
BAYLAND JOB NO. 8\_16202



REVISED SITE DEVELOPMENT PLAN

LAKE KITTAMAQUONDI MULTIUSE TRAIL  
DESIGN PLANS


REVISIONS			SCALE: 1" = 20'	
DATE	BY	DESCRIPTION	DRAWN BY: MKB	DATE: 04/21/14
			CHECKED BY: SB	DATE: 4/21/2014
			DESIGNED BY: MKB	DATE: 04/21/14
			DRAWING K-05, SHEET NO. 51 OF 59	



LINE TABLE				
LINE	LENGTH	DIRECTION	START	END
L8	13.47'	S15°27'27"W	N: 565,859 E: 1,354,045	N: 565,846 E: 1,354,042
L9	17.16'	S27°48'44"W	N: 565,838 E: 1,354,038	N: 565,822 E: 1,354,030
L10	3.75'	S50°24'22"W	N: 565,810 E: 1,354,020	N: 565,808 E: 1,354,018
L11	18.05'	S7°15'41"W	N: 565,776 E: 1,354,000	N: 565,758 E: 1,353,998
L12	6.53'	S12°47'26"W	N: 565,744 E: 1,353,995	N: 565,737 E: 1,353,994
L13	10.18'	S21°11'49"E	N: 565,688 E: 1,353,983	N: 565,679 E: 1,353,987

CURVE TABLE					
CURVE	RADIUS	LENGTH	CHORD DIRECTION	TANGENT	DELTA
C7	55'	24.40'	S28°08'53"W	12.40'	25°18'37"
C8	40'	8.63'	S21°38'06"W	4.33'	12°21'17"
C9	40'	15.77'	S39°06'33"W	7.99'	22°35'38"
C10	50'	37.65'	S28°50'01"W	19.77'	43°08'41"
C11	150'	14.48'	S10°01'33"W	7.24'	5°31'45"
C12	100'	26.03'	S20°14'52"W	13.09'	14°54'52"
C13	30'	25.80'	S3°15'15"W	13.64'	48°54'07"

**PLAN**  
SCALE: 1" = 20'



**PROFILE OF PROPOSED TRAIL STA: 115+25 TO STA: 120+25**

HORIZONTAL : 1" = 20'  
VERTICAL : 1" = 5'


APPROVED: DEPARTMENT OF PLANNING AND ZONING

Chief, Development Engineering Division *HSP* Date 5.9.14

Chief, Division of Land Development *STP* Date 6.09.14


Director *Mark M. Coyle* Date 6/9/14

APPROVED  
PLANNING BOARD  
of HOWARD COUNTY  
DATE 6/5/2014



**Columbia Association**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21046  
(410) 381-2947


**Bayland Consultants & Designers, Inc.**  
"Integrating Engineering and Environment"  
1321 Mercedes Drive, Suite A Phone: (410)694-9401  
Hanover, Maryland 21076 Fax: (410)694-9405  
Email: bayland@baylandinc.com  
Website: http://www.baylandinc.com  
BAYLAND JOB NO. 8\_16202



REVISED SITE DEVELOPMENT PLAN  
**LAKE KITTAMAQUONDI MULTIUSE TRAIL DESIGN PLANS**

DATE		BY	REVISIONS DESCRIPTION	SCALE: 1" = 20'	
				DRAWN BY: MKB	DATE: 04/21/14
				CHECKED BY: SB	DATE: 4/21/2014
				DESIGNED BY: MKB	DATE: 04/21/14
				DRAWING K-06, SHEET NO. 52 OF 59	

SDP-08-108




CURVE	RADIUS	LENGTH	CHORD DIRECTION	TANGENT	DELTA
C14	50'	19.62'	S9°57'19"E	9.94'	22°29'00"
C15	50'	42.36'	S25°33'24"W	22.54'	48°32'27"
C16	50'	33.71'	S30°30'47"W	17.52'	38°37'42"
C17	35'	29.84'	S39°06'04"W	15.89'	48°50'52"
C18	55'	46.53'	S87°45'33"W	24.76'	48°28'06"
C19	50'	34.76'	N87°55'16"W	18.11'	39°49'44"
C20	50'	25.55'	S86°48'13"W	13.06'	29°16'42"
C21	25'	19.93'	S78°36'24"W	10.53'	45°40'21"
C22	50'	15.64'	S62°40'48"W	7.88'	17°55'17"
C23	50'	14.03'	S63°36'06"W	7.06'	16°04'42"
C24	400'	8.66'	S54°54'44"W	4.33'	1°14'25"
C26	250'	25.08'	S41°14'01"W	12.55'	5°44'52"
C25	25'	6.95'	S46°19'33"W	3.50'	15°55'56"
C27	25'	12.91'	S58°54'20"W	6.60'	29°35'46"

LINE	LENGTH	DIRECTION	START	END
L14	12.51'	S11°17'11"W	N: 565,659 E: 1,353,990	N: 565,647 E: 1,353,990
L15	10.82'	S49°49'38"W	N: 565,610 E: 1,353,972	N: 565,603 E: 1,353,964
L16	30.88'	S14°40'38"W	N: 565,574 E: 1,353,947	N: 565,544 E: 1,353,939
L17	2.91'	S63°31'29"W	N: 565,522 E: 1,353,921	N: 565,521 E: 1,353,918
L18	25.00'	N68°00'24"W	N: 565,519 E: 1,353,873	N: 565,528 E: 1,353,850
L19	22.16'	S72°09'52"W	N: 565,529 E: 1,353,816	N: 565,523 E: 1,353,795
L20	2.81'	N78°33'28"W	N: 565,521 E: 1,353,770	N: 565,522 E: 1,353,767

LINE	LENGTH	DIRECTION	START	END
L21	28.93'	S55°46'14"W	N: 565,518 E: 1,353,748	N: 565,502 E: 1,353,724
L22	4.32'	S71°38'26"W	N: 565,495 E: 1,353,710	N: 565,493 E: 1,353,706
L23	4.22'	S55°33'45"W	N: 565,487 E: 1,353,694	N: 565,485 E: 1,353,690
L24	28.14'	S54°17'31"W	N: 565,480 E: 1,353,683	N: 565,463 E: 1,353,660
L25	34.34'	S38°21'35"W	N: 565,458 E: 1,353,655	N: 565,431 E: 1,353,634
L26	24.67'	S44°06'27"W	N: 565,413 E: 1,353,617	N: 565,395 E: 1,353,600
L27	9.86'	S73°42'13"W	N: 565,398 E: 1,353,589	N: 565,386 E: 1,353,580

PLAN  
SCALE: 1" = 20'



PROFILE OF PROPOSED TRAIL STA: 120+00 TO STA: 126+15

APPROVED: DEPARTMENT OF PLANNING AND ZONING

*Chad Chubb*  
Chief, Development Engineering Division #3P  
Date: 5.9.14

*Keith Sheehy*  
Chief, Division of Land Development  
Date: 6.09.14

*Mark J. Long Jr.*  
Director  
Date: 6/9/14


APPROVED  
PLANNING BOARD  
of HOWARD COUNTY  
DATE 6/5/2014

0 10 20 40  
1 Inch = 20 Feet

HORIZONTAL: 1" = 20'  
VERTICAL: 1" = 5'

**Columbia Association**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21046  
(410) 381-2947

**Bayland Consultants & Designers, Inc.**  
"Integrating Engineering and Environment"  
1321 Mercedes Drive, Suite A Phone: (410)694-9401  
Hanover, Maryland 21076 Fax: (410)694-9405  
Email: bayland@baylandinc.com  
Website: http://www.baylandinc.com  
BAYLAND JOB NO. 8\_16202




REVISED SITE DEVELOPMENT PLAN  
LAKE KITTAMAQUONDI MULTIUSE TRAIL  
DESIGN PLANS

DATE	BY	REVISIONS	DESCRIPTION


SCALE: 1" = 20'

DRAWN BY: MKB DATE: 04/21/14  
CHECKED BY: SB DATE: 4/21/2014  
DESIGNED BY: MKB DATE: 04/21/14  
DRAWING K-07, SHEET NO. 53 OF 59  
SDP-08-108


Z:\8\_16202\_LAKE\_KIT\_MULTIUSE\_TRAIL\JOB Files\Sheet Files\8\_16202\_SDP08




**PROP. TRAIL SECTION XS 01 STA 111+25**  
SCALE: 1" = 5'




**PROP. TRAIL SECTION XS 04 STA 112+65**  
SCALE: 1" = 5'




**PROP. TRAIL SECTION XS 02 STA 111+55**  
SCALE: 1" = 5'




**PROP. TRAIL SECTION XS 05 STA 113+00**  
SCALE: 1" = 5'



**PROP. TRAIL SECTION XS 03 STA 111+95**  
SCALE: 1" = 5'



**CONSTRUCTION ACCESS**  
NOT TO SCALE




**IMBRICATED ROCK WALL DETAIL**  
SCALE: NTS


- IMBRICATED ROCK WALL NOTES**
- ALL MATERIALS SHALL BE UNDERLAIN BY MIRAFI FW404 GEOTEXTILE FABRIC OR EQUAL.
  - WHEN BACKFILLING, ALL MATERIAL SHALL BE COMPACTED FIRMLY IN ALL VOIDS TO SECURE STONE. ALL SOIL SHALL BE COMPACTED TO MD-378 STANDARDS.
  - IMBRICATED ROCK WALL SHALL BE CONSTRUCTED SUCH THAT ALL ROCKS SECURELY INTERLOCK AND SHALL NOT ROCK OR ROTATE IN PLACE. ALL ROCKS EXCEPT BOTTOM FOOTER ROCKS SHALL BE SUPPORTED BY A FOOTER ROCK.
  - IMBRICATED ROCK SHALL BE OBLONG AND FLAT IN APPEARANCE WITH TWO PARALLEL FACES, AND SHALL BE STACKABLE.
  - ALL ROCK SHALL BE GRANITE ROCK THAT IS TAN, DARK BROWN, OR DARK GRAY IN COLOR. ROCKS NOT MEETING SPECIFICATIONS SHALL BE REMOVED AND REPLACED AT NO COST TO THE OWNER.

**ROCK SIZE TABLE**

ROCK TYPE	SIZE	% BY WEIGHT
IMBRICATED ROCK	GREATER THAN 16" X 18" X 24"	20
	8" X 9" X 12" TO 16" X 18" X 24"	80




**PLAN**




**SECTION**

**UPSTREAM FLANK DETAIL**  
SCALE: NTS


APPROVED  
PLANNING BOARD  
of HOWARD COUNTY  
DATE: 6/5/2014




STA. 100+15.57 TO STA. 105+00  
STA. 118+07 TO STA. 123+85  
**FULL DEPTH PAVING PATH DETAIL**  
NOT TO SCALE



STA. 123+85 TO STA. 126+06  
**WIDENING & FULL DEPTH PAVING PATH DETAIL**  
NOT TO SCALE



**OVERFLOW PROTECTION DETAIL**  
NOT TO SCALE



STA. 105+00 TO STA. 115+87  
**OVERLAY PAVING PATH DETAIL**  
NOT TO SCALE

APPROVED: DEPARTMENT OF PLANNING AND ZONING

Chief, Development Engineering Division *HSP* Date: 5-9-14

Chief, Division of Land Development *Diana* Date: 6-09-14


Director *Wash* Date: 6/9/14

**UPSTREAM FLANK DETAIL**  
SCALE: NTS

APPROVED  
PLANNING BOARD  
of HOWARD COUNTY  
DATE: 6/5/2014

**Columbia Association**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21046  
(410) 381-2947

**Bayland Consultants & Designers, Inc.**  
"Integrating Engineering and Environment"  
1321 Mercedes Drive, Suite A Phone: (410)694-9401  
Hanover, Maryland 21076 Fax: (410)694-9405  
Email: bayland@baylandinc.com  
Website: http://www.baylandinc.com  
BAYLAND JOB NO. 8\_16202




**LAKE KITTAMAQUONDI MULTIUSE TRAIL CROSS SECTIONS & DETAILS**

REVISIONS

DATE	BY	DESCRIPTION


SCALE: 1" = 5'

DRAWN BY: MKB DATE: 04/21/14  
CHECKED BY: SB DATE: 4/21/2014  
DESIGNED BY: MKB DATE: 04/21/14  
DRAWING K-08, SHEET NO. 54 OF 59




**BOARDWALK SIDE VIEW**

SCALE: 1" = 2'




**BOARDWALK SECTION VIEW**

SCALE: 1" = 2'




**SUPPORT CONNECTION DETAIL**

NOT TO SCALE




**CAPPING DETAIL**

NOT TO SCALE




**BOARDWALK DECKING PLAN**

SCALE: 1" = 2'




**SPLIT CAP DETAIL**

NOT TO SCALE



**STEEL STRAP DETAIL**

NOT TO SCALE




**BUTT BLOCK DETAIL**

NOT TO SCALE

**STAINLESS STEEL CABLE RAILING NOTE**

THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR THE PROPOSED STAINLESS STEEL CABLE RAILING SYSTEM. THE SHOP DRAWINGS MUST BE STAMPED APPROVED BY MARYLAND REGISTERED PROFESSIONAL ENGINEER.

APPROVED  
PLANNING BOARD  
of HOWARD COUNTY  
DATE 6/5/2014




**SIDE VIEW**

**TOP VIEW**

**PILE DETAILS**

SCALE: 1" = 1'



**BOARDWALK TO PAVED TRAIL TRANSITION**

SCALE 1" = 2'

**NOTES:**


- ALL PILES SHALL BE 12" DIA. TIMBER TYPE 'B' AND TREATED W/ 2.5 CCA
- ALL DIMENSIONAL LUMBER SHALL BE NO.1 SYP  
2.1. STRUCTURAL LUMBER SHALL BE TREATED W/ 1.0 CCA  
2.2. DECKING, POSTS, & CAPS SHALL BE TREATED W/ 0.06 CA-C
- ALL HARDWARE SHALL BE HOT DIPPED GALVANIZED (GALV.) OR 305 STAINLESS STEEL (S.S.) AS NOTES ON PLANS
- ALL EXPOSED HARDWARE SHALL BE COUNTERSUNK

APPROVED: DEPARTMENT OF PLANNING AND ZONING

Chief, Development Engineering Division HSP Date 5-9-14  
 Chief, Division of Land Development Date 6-09-14  
 Director Date 6/9/14

**Columbia Association**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21046  
(410) 381-2947

**BayLand Consultants & Designers, Inc.**  
"Integrating Engineering and Environment"  
1321 Mercedes Drive, Suite A Phone: (410)694-9401  
Hanover, Maryland 21076 Fax: (410)694-9405  
Email: bayland@baylandinc.com  
Website: http://www.baylandinc.com





REVISED SITE DEVELOPMENT PLAN


**LAKE KITTAMAQUONDI MULTIUSE TRAIL BOARDWALK DETAILS**

REVISIONS		SCALE: AS-SHOWN	
DATE	BY	DESCRIPTION	
			DRAWN BY: MKB DATE: 04/21/14
			CHECKED BY: SB DATE: 4/21/2014
			DESIGNED BY: MKB DATE: 04/21/14
			DRAWING K-09, SHEET NO. 55 OF 59








**15' O.C. PILES DETAILS**  
THE SPLIT CAP DETAIL, PILE DETAIL, STEEL STRAP DETAIL, SUPPORT CONNECTION DETAIL, AND CAPPING DETAIL FOR THE 15' O.C. PILES ON SHEET 55 SHALL ALSO BE USED FOR THE 15' O.C. PILES. SUBSTITUTING 4"x12" SPLIT CAPS AND STRINGERS DOES NOT CHANGE THE HARDWARE USED TO CONNECT THE BOARDWALK MEMBERS.




**APPROVED**  
PLANNING BOARD  
of HOWARD COUNTY  
DATE 6/5/2014



**BOARDWALK DECKING PLAN (15' O.C. PILES)**  
SCALE: 1" = 2'



**STEEL STRAP DETAIL (50' RADIUS)**  
NOT TO SCALE




**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

Chief, Development Engineering Division  
Date 5.9.14

Chief, Division of Land Development  
Date 6.09.14

Director  
Date 6/9/14




**NOTES:**

- ALL PIPE TO BE STANDARD WEIGHT AS PER AISC MANUAL.
- ALL EXPOSED METAL SURFACES SHALL BE PAINTED WITH GALVANIZED PAINT - ONE COAT METAL PRIMER AND TWO COATS STANDARD SAFETY YELLOW # 4540 METAL ENAMEL.

**Columbia Association**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21046  
(410) 381-2947


**BayLand Consultants & Designers, Inc.**  
"Integrating Engineering and Environment"  
1321 Mercedes Drive, Suite A Phone: (410)694-9401  
Hanover, Maryland 21076 Fax: (410)694-9405  
Email: bayland@baylandinc.com  
Website: http://www.baylandinc.com



**LAKE KITTAMAQUUNDI MULTIUSE TRAIL BOARDWALK DETAILS**

REVISIONS			SCALE: AS-SHOWN	
DATE	BY	DESCRIPTION	DRAWN BY: MKB	DATE: 04/21/14
			CHECKED BY: SB	DATE: 4/21/2014
			DESIGNED BY: MKB	DATE: 04/21/14
			DRAWING K-10, SHEET NO. 56 OF 59	

Z:\9-16202-LAKE\_KITT\_MULTIUSE\_TRAIL\CAD Files\Sheet Files\8-16202\_0102



**NOTES**

1. THE ENTIRE LIMITS OF DISTURBANCE ARE WITHIN THE 100-YEAR FLOODPLAIN AND STOCKPILES ARE NOT PERMITTED WITHIN THE 100-YEAR FLOODPLAIN. THEREFORE, THE CONTRACTOR IS RESPONSIBLE FOR HAULING AWAY ALL EXCAVATED MATERIAL BY THE END OF EACH WORKING DAY. FOR DAILY STOCKPILES, THE CONTRACTOR SHALL PILE EXCAVATED MATERIAL WITHIN THE LIMITS OF DISTURBANCE AND THE STOCKPILE SHALL BE PROTECTED WITH SILT FENCE TO ENSURE SEDIMENT LADEN RUNOFF DOES NOT DISCHARGE FROM THE LIMITS OF DISTURBANCE.
2. THE CONTRACTOR SHALL REPLACE SILT FENCE WITH SUPER SILT FENCE AT THE DIRECTION OF THE SEDIMENT CONTROL INSPECTOR.
3. THE CONTRACTOR MAY SUBSTITUTE SILT FENCE WITH FILTER LOGS IN THE VICINITY OF WETLAND AND/OR TREE AREAS. THE CONTRACTOR SHALL REPLACE SILT FENCE WITH FILTER LOGS AT THE DIRECTION OF THE SEDIMENT CONTROL INSPECTOR.

**SEQUENCE OF CONSTRUCTION**

- PRE-CONSTRUCTION**
1. OBTAIN A GRADING PERMIT FROM HOWARD COUNTY DEPARTMENT OF INSPECTIONS, LICENSES AND PERMITS.
  2. THE CONTRACTOR SHALL NOTIFY THE MARYLAND DEPARTMENT OF THE ENVIRONMENT, SEDIMENT CONTROL INSPECTOR AT (410) 301-4020 AT LEAST 48 HOURS BEFORE COMMENCING WORK. WORK MAY NOT COMMENCE UNTIL THE PERMITTEE OR THE RESPONSIBLE PERSONNEL HAVE MET ON SITE WITH THE SEDIMENT AND EROSION CONTROL INSPECTOR TO REVIEW THE APPROVED PLANS.


- PHASE I: STABILIZED CONSTRUCTION ACCESS**
1. CLEAR AND GRUB FOR THE INSTALLATION OF THE SEDIMENT AND EROSION CONTROL DEVICES.
  2. INSTALL THE STABILIZED CONSTRUCTION ENTRANCE AND SILT FENCE.
  3. BEGIN EXCAVATION AND GRADING FOR THE CONSTRUCTION ACCESS ROAD AND INSTALL THE STONE BASE. THE CONTRACTOR SHALL ONLY EXCAVATE AND GRADE A LENGTH THAT CAN BE STABILIZED AT THE END OF EACH WORKING DAY. THE SILT FENCE IS A PRECAUTIONARY MEASURE TO ENSURE EXCAVATED MATERIALS DO NOT ENTER THE LITTLE PATUXENT RIVER AND WORK IN THIS AREA SHALL BE STABILIZED AT THE END OF EACH WORKING DAY.
  4. AS CONSTRUCTION PROGRESS TOWARD THE EXISTING INTERMITTENT CHANNEL, INSTALL TEMPORARY ACCESS BRIDGE #1 AND CONTINUE EXCAVATION AND STONE BASE INSTALLATION TOWARD LAKE KITTAMAQUONDI.
  5. INSTALL TEMPORARY ACCESS BRIDGE #2.
  6. COMPLETE CONSTRUCTION ACCESS ROAD STONE BASE INSTALLATION AND TIE INTO EXISTING PAVED TRAIL.
  7. WITH SEDIMENT CONTROL INSPECTOR'S APPROVAL, REMOVE THE SILT FENCE AND PERMANENTLY STABILIZE ANY DISTURBED AREAS. THE STABILIZED CONSTRUCTION ENTRANCE AND TEMPORARY ACCESS BRIDGES SHALL REMAIN FOR PHASE II CONSTRUCTION.

**SUMMARY OF ESC QUANTITIES**


PHASE I	
STABILIZED CONSTRUCTION ENTRANCE	1 EA
MOUNTABLE BERM	1 EA
TEMPORARY ACCESS BRIDGE	2 EA
SILT FENCE	300 L.F.

NOTE: THIS SUMMARY OF SEDIMENT CONTROL QUANTITIES IS FOR USE BY THE HOWARD SOIL CONSERVATION DISTRICT ONLY. THIS SUMMARY IS NOT INTENDED TO BE USED BY THE CONTRACTOR FOR ESTIMATING AND BIDDING PURPOSES.

- PHASE II: LAKE KITTAMAQUONDI MULTIUSE TRAIL**
1. CLEAR AND GRUB FOR THE INSTALLATION OF THE SEDIMENT AND EROSION CONTROL DEVICES.
  2. INSTALL THE SILT FENCE AND TEMPORARY ACCESS BRIDGE #3 AS SHOWN ON THE APPROVED CONSTRUCTION DRAWINGS.
  3. INSTALL TURBIDITY CURTAIN AND CONSTRUCT PROPOSED IMBRICATED RIPRAP WALL. FOLLOWING THE CONSTRUCTION AND WITH THE SEDIMENT CONTROL INSPECTOR'S APPROVAL, REMOVE THE TURBIDITY CURTAIN.
  4. INSTALL BOARDWALK PILES AND CONSTRUCT THE BOARDWALK AND ASSOCIATED RAILINGS. CONTRACTOR SHALL TRIM TREE BRANCHES AS NECESSARY FOR ACCESS AND CONSTRUCTION.
  5. BEGIN PAVING OVERLAY AND FULL DEPTH WIDENING FOR THE EXISTING 8' WIDE TO 10' WIDE GRAVEL TRAIL (STA. 123+85 TO STA. 126+00). ALL NECESSARY TRAIL WIDENING SHALL OCCUR SOUTH EAST SIDE OF THE TRAIL WHICH IS THE FAR SIDE FROM THE WETLANDS. THE CONTRACTOR SHALL USE CAUTION IN THIS AREA AS TO NOT DISTURB THE EXISTING NON-TIDAL WETLAND.
  6. BEGIN EXCAVATION FOR THE FULL DEPTH PAVING TRAIL (STA. 100+15.57 TO STA. 105+00 AND STA. 118+07 TO STA. 123+85) AND INSTALL PAVING SECTION.
  7. BEGIN PAVING OVERLAY THE EXISTING GRAVEL TRAIL (STA. 105+00 TO STA. 115+87). THE CONTRACTOR SHALL ONLY DISTURB AN AREA THAT CAN BE STABILIZED AT THE END OF EACH WORKING DAY.
  8. WITH SEDIMENT CONTROL INSPECTOR'S APPROVAL, REMOVE ALL REMAINING SEDIMENT CONTROLS, INCLUDING PHASE I SEDIMENT CONTROLS, AND PERMANENTLY STABILIZE ANY DISTURBED AREAS. THE CONSTRUCTION ACCESS ROAD SHALL REMAIN AND WILL BE PAVED BY OTHERS.



**CONSTRUCTION ACCESS DETAIL**



**ULTIMATE PAVED TRAIL DETAIL (BY OTHERS)**

**ENGINEER'S CERTIFICATION**

I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

*Sepehr Baharlou* 4/21/14  
 SIGNATURE OF ENGINEER DATE  
**SEPEHR BAHARLOU**  
 PRINTED NAME

**DEVELOPER'S CERTIFICATION**

I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT.

*Dennis Matley* 4.24.14  
 SIGNATURE OF DEVELOPER DATE  
**Dennis Matley**  
 PRINTED NAME

**HOWARD SOIL CONSERVATION DISTRICT**

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

*John R. Robertson* 4/29/14  
 SIGNATURE OF DISTRICT ENGINEER DATE  
**HOWARD SOIL CONSERVATION DISTRICT**


**APPROVED: DEPARTMENT OF PLANNING AND ZONING**

*Chad Chubb* 5-9-14  
 Chief, Development Engineering Division HSP Date

*Kate Shalinski* 6-09-14  
 Chief, Division of Land Development Date


*Mark J. Lovell* 6/9/14  
 Director Date

**APPROVED PLANNING BOARD of HOWARD COUNTY**  
 DATE 6/5/2014




**Columbia Association**  
 10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21046  
 (410) 381-2947

**BayLand Consultants & Designers, Inc.**  
 "Integrating Engineering and Environment"  
 1321 Mercedes Drive, Suite A Phone: (410)694-9401  
 Hanover, Maryland 21076 Fax: (410)694-9405  
 Email: bayland@baylandinc.com  
 Website: http://www.baylandinc.com  
 BAYLAND JOB NO. 8-16202



**REVISED SITE DEVELOPMENT PLAN LAKE KITTAMAQUONDI MULTIUSE TRAIL EROSION AND SEDIMENT CONTROL PLAN**

REVISIONS		SCALE: 1" = 50'
DATE	DESCRIPTION	
		DRAWN BY: MKB DATE: 04/21/14
		CHECKED BY: SB DATE: 4/21/2014
		DESIGNED BY: MKB DATE: 04/21/14
		DRAWING K-11, SHEET NO. 57 OF 58



APPROVED  
PLANNING BOARD  
OF HOWARD COUNTY  
DATE 6/5/2014

**SUMMARY OF ESC QUANTITIES**

PHASE II		
SILT FENCE	1,310 LF	
TURBIDITY CURTAIN	200 LF	
TEMPORARY ACCESS BRIDGE	1 EA	

NOTE: THIS SUMMARY OF SEDIMENT CONTROL QUANTITIES IS FOR USE BY THE HOWARD SOIL CONSERVATION DISTRICT ONLY. THIS SUMMARY IS NOT INTENDED TO BE USED BY THE CONTRACTOR FOR ESTIMATING AND BIDDING PURPOSES.

**DEVELOPER'S CERTIFICATION**

I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT

*D. Mathey* 4/24/14  
SIGNATURE OF DEVELOPER DATE  
Dennis Mathey  
PRINTED NAME

**HOWARD SOIL CONSERVATION DISTRICT**

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.


*John R. Pollock* 4/29/14  
SIGNATURE OF DISTRICT ENGINEER DATE  
John R. Pollock  
PRINTED NAME

**ENGINEER'S CERTIFICATION**

I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.


*Sepehr Baharlow* 4/21/14  
SIGNATURE OF ENGINEER DATE  
SEPEHR BAHARLOW  
PRINTED NAME

APPROVED: DEPARTMENT OF PLANNING AND ZONING	
<i>Chad E. Egan</i> Chief, Development Engineering Division HSP	5-9-14 Date
<i>Kate DeRosa</i> Chief, Division of Land Development	6-09-14 Date
<i>Danish A. Long U.</i> Director	6/9/14 Date



**Columbia Association**  
10221 WINCOPIN CIRCLE #100  
COLUMBIA, MD 21046  
(410) 381 - 2947

**BayLand Consultants & Designers, Inc.**  
"Integrating Engineering and Environment"  
1321 Mercedes Drive, Suite A Phone: (410)694-9401  
Hanover, Maryland 21076 Fax: (410)694-9405  
Email: bayland@baylandinc.com  
Website: http://www.baylandinc.com  
BAYLAND JOB NO. 8\_16202



**LAKE KITTAMAQUNDI MULTIUSE TRAIL EROSION AND SEDIMENT CONTROL PLAN**

REVISIONS

DATE	BY	DESCRIPTION

SCALE: 1" = 50'

DRAWN BY: MKB	DATE: 04/21/14
CHECKED BY: SB	DATE: 4/21/2014
DESIGNED BY: MKB	DATE: 04/21/14
DRAWING K-12, SHEET NO. 58 OF 59	

SDP-08-108

# HOWARD SOIL CONSERVATION DISTRICT STANDARD SEDIMENT CONTROL NOTES

- A MINIMUM OF 48 HOURS NOTICE MUST BE GIVEN TO THE HOWARD COUNTY DEPARTMENT OF INSPECTIONS, LICENSES AND PERMITS, SEDIMENT CONTROL DIVISION PRIOR TO THE START OF ANY CONSTRUCTION (313-1855).
- ALL VEGETATIVE AND STRUCTURAL PRACTICES ARE TO BE INSTALLED ACCORDING TO THE PROVISIONS OF THIS PLAN AND ARE TO BE IN CONFORMANCE WITH THE MOST CURRENT MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL AND REVISIONS THERETO.
- FOLLOWING INITIAL SOIL DISTURANCE OR RE-DISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN: A) 3 CALENDAR DAYS FOR ALL PERMETER SEDIMENT CONTROL STRUCTURES, DIKES, PERIMETER SLOPES AND ALL SLOPES GREATER THAN 3:1, B) 7 DAYS AS TO ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE.
- ALL DISTURBED AREAS MUST BE STABILIZED WITHIN THE TIME PERIOD SPECIFIED ABOVE IN ACCORDANCE WITH THE 2011 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL TEMPORARY SEEDING (SEC. B-4-F), TEMPORARY SEEDING (SEC. B-4-A) AND MULCHING (SEC. B-4-C); TEMPORARY STABILIZATION WITH MULCH ALONE CAN ONLY BE USED WHEN RECOMMENDED SEEDING DATES DO NOT ALLOW FOR PROPER GERMINATION AND ESTABLISHMENT OF GRASSES.
- ALL SEDIMENT CONTROL STRUCTURES ARE TO REMAIN IN PLACE AND ARE TO BE MAINTAINED IN OPERATIVE CONDITION UNTIL PERMITS FOR THEIR REMOVAL HAS BEEN OBTAINED FROM THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR.
- SITE ANALYSIS:
 

TOTAL AREA OF SITE AREA DISTURBED	2.87 ACRES
AREA TO BE ROOFED OR PAVED	0.88 ACRES
AREA TO BE VEGETATED / STABILIZED	1.99 ACRES
TOTAL CUT	820 CU. YDS.
TOTAL FILL	0 CU. YDS.
OFFSITE WASTE/BORROW LOCATION	
- ANY SEDIMENT CONTROL PRACTICE THAT IS DISTURBED BY GRADING ACTIVITY FOR PLACEMENT OF UTILITIES MUST BE REPAIRED ON THE SAME DAY OF DISTURBANCE.
- ADDITIONAL SEDIMENT CONTROL MUST BE PROVIDED, IF DEEMED NECESSARY BY THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR.
- ON ALL SITES WITH DISTURBED AREAS IN EXCESS OF 2 ACRES, APPROVAL OF THE INSPECTION AGENCY SHALL BE REQUESTED UPON COMPLETION OF INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS, BUT BEFORE PROCEEDING WITH ANY OTHER EARTH DISTURBANCE OR GRADING, OTHER BUILDING OR GRADING INSPECTION APPROVALS MAY NOT BE AUTHORIZED UNTIL THIS INITIAL APPROVAL BY THE INSPECTION AGENCY IS MADE.
- TRENCHES FOR THE CONSTRUCTION OF UTILITIES IS LIMITED TO THREE PIPE LENGTHS OR THAT WHICH SHALL BE BACK-FILLED AND STABILIZED BY THE END OF EACH WORKDAY, WHICHEVER IS SHORTER.
- ANY CHANGES OR REVISIONS TO THE SEQUENCE OF CONSTRUCTION MUST BE REVIEWED AND APPROVED BY THE PLAN APPROVAL AUTHORITY PRIOR TO PROCEEDING WITH CONSTRUCTION.
- A PROJECT IS TO BE SEQUENCED SO THAT GRADING ACTIVITIES BEGIN ON ONE GRADING UNIT (MAXIMUM ACREAGE OF 20 AC. PER GRADING UNIT) AT A TIME. WORK MAY PROCEED TO A SUBSEQUENT GRADING UNIT WHEN AT LEAST 50 PERCENT OF THE DISTURBED AREA IN THE PRECEDING GRADING UNIT HAS BEEN STABILIZED AND APPROVED BY THE ENFORCEMENT AUTHORITY, UNLESS OTHERWISE SPECIFIED AND APPROVED BY THE APPROVAL AUTHORITY, NO MORE THAN 30 ACRES CUMULATIVELY MAY BE DISTURBED AT A GIVEN TIME.

## TOPSOIL SPECIFICATIONS

- TOPSOIL IS PLACED OVER PREPARED SUBSOIL PRIOR TO ESTABLISHMENT OF PERMANENT VEGETATION. THE PURPOSE IS TO PROVIDE A SUITABLE SOIL MEDIUM FOR VEGETATIVE GROWTH. SOILS OF CONCERN HAVE LOW MOISTURE CONTENT, LOW NUTRIENT LEVELS, LOW PH, MATERIALS TOXIC TO PLANTS, AND/OR UNACCEPTABLE SOIL GRAIN DENSITIES.
- TOPSOIL SALVAGED FROM AN EXISTING SITE MAY BE USED PROVIDED IT MEETS THE STANDARDS AS SET FORTH IN THESE SPECIFICATIONS. TYPICALLY, THE DEPTH OF TOPSOIL TO BE SALVAGED FOR A GIVEN SOIL TYPE CAN BE FOUND IN THE REPRESENTATIVE SOIL PROFILE SECTION IN THE SOIL SURVEY PUBLISHED BY USDA-NRCS.
- TOPSOILING IS LIMITED TO AREAS HAVING 2:1 OR FLATTER SLOPES WHERE:
  - THE TEXTURE OF THE EXPOSED SUBSOIL/PARENT MATERIAL IS NOT ADEQUATE TO PRODUCE VEGETATIVE GROWTH.
  - THE SOIL MATERIAL IS SO SHALLOW THAT THE ROOTING ZONE IS NOT DEEP ENOUGH TO SUPPORT PLANTS OR FURNISH CONTINUING SUPPLIES OF MOISTURE AND PLANT NUTRIENTS.
  - THE ORIGINAL SOIL TO BE VEGETATED CONTAINS MATERIAL TOXIC TO PLANT GROWTH.
  - THE SOIL IS SO ACIDIC THAT TREATMENT WITH LIMESTONE IS NOT FEASIBLE.
- AREAS HAVING SLOPES STEEPER THAN 2:1 REQUIRE SPECIAL CONSIDERATION AND DESIGN.
- TOPSOIL SPECIFICATIONS: SOIL TO BE USED AS TOPSOIL MUST MEET THE FOLLOWING CRITERIA:
  - TOPSOIL MUST BE LOAM, SANDY LOAM, CLAY LOAM, SILT LOAM, SANDY CLAY LOAM, OR LOAMY SAND. OTHER SOILS MAY BE USED IF RECOMMENDED BY AN AGRONOMIST OR SOIL SCIENTIST AND APPROVED BY THE APPROVAL AUTHORITY. TOPSOIL MUST NOT BE A MIXTURE OF CONTRASTING TEXTURED SUBSOILS AND MUST CONTAIN LESS THAN 5 PERCENT BY VOLUME OF CHINDERS, STONES, SLAG, COARSE FRAGMENTS, GRAVEL, STICKS, ROOTS, TRASH, OR OTHER MATERIALS LARGER THAN 1 1/2 INCHES IN DIAMETER.
  - TOPSOIL MUST BE FREE OF NOXIOUS PLANTS OR PLANT PARTS SUCH AS BERMUDA GRASS, QUACK GRASS, JOHNSON GRASS, NUT SEDGE, POISON IVY, THISTLE, OR OTHERS AS SPECIFIED.
  - TOPSOIL SUBSTITUTES OR AMENDMENTS, AS RECOMMENDED BY A QUALIFIED AGRONOMIST OR SOIL SCIENTIST AND APPROVED BY THE APPROPRIATE APPROVAL AUTHORITY, MAY BE USED IN LIEU OF NATURAL TOPSOIL.
- TOPSOIL APPLICATION:
  - EROSION AND SEDIMENT CONTROL PRACTICES MUST BE MAINTAINED WHEN APPLYING TOPSOIL. UNIFORMLY DISTRIBUTE TOPSOIL IN A 5 TO 8 INCH LAYER AND LIGHTLY COMPACT TO A MINIMUM THICKNESS OF 4 INCHES. SPREADING IS TO BE PERFORMED IN SUCH A MANNER THAT SODDING OR SEEDING CAN PROCEED WITH MINIMUM OF ADDITIONAL SOIL PREPARATION AND TILLAGE. ANY IRREGULARITIES IN THE SURFACE RESULTING FROM TOPSOILING OR OTHER OPERATIONS MUST BE CORRECTED IN ORDER TO PREVENT THE FORMATION OF DEPRESSIONS OR WATER POCKETS.
  - TOPSOILING IS NOT TO BE PLACED ON FROZEN OR FROZEN OR MUDDY OR MUDDY CONDITION, WHEN THE SUBSOIL IS EXCESSIVELY WET OR IN A CONDITION THAT MAY OTHERWISE BE DETRIMENTAL TO PROPER GRADING AND SEEDBED PREPARATION.

TEMPORARY SEEDING SUMMARY						FERTILIZER (10-20-20)	LIME RATE
HARDNESS ZONE (FROM FIGURE B.3): 6b		SEED MIXTURE (FROM TABLE B.1)					
NO.	SPECIES	APPLICATION RATE (lb/ac)	SEEDING DATES	SEEDING DEPTHS			
1	ANNUAL RYEGRASS	40 (1lb/1000 sf)	3/1 - 5/15 8/1 - 10/15	0.5"			
2	BARLEY	96 (2.2lb/1000 sf)	3/1 - 5/15 8/1 - 10/15	0.5"	436 lb/ac	2 tons/ac	
3	OATS	72 (1.7lb/1000 sf)	3/1 - 5/15 8/1 - 10/15	0.5"	10 lb/1000 sf	90 lb/1000 sf	
4	RYE	112 (2.8lb/1000 sf)	3/1 - 5/15 8/1 - 10/15	0.5"			
5	FOXTAIL MILLET	30 (0.7lb/1000 sf)	5/16 - 7/31	0.5"			

NOTES:  
 1. SEEDING RATES FOR THE WARM-SEASON GRASSES ARE IN POUNDS OF PURE LIVE SEED (PLS). ACTUAL PLANTING RATES SHALL BE ADJUSTED TO REFLECT PERCENT SEED GERMINATION AND PURITY, AS TESTED. ADJUSTMENTS ARE USUALLY NOT NEEDED FOR THE COOL-SEASON GRASSES. SEEDING RATES LISTED ABOVE ARE FOR TEMPORARY SEEDINGS, WHEN PLANTED ALONE, WHEN PLANTED AS A NURSE CROP WITH PERMANENT SEED MIXES, USE 1/3 OF THE SEEDING RATE LISTED ABOVE FOR BARLEY, OATS, AND WHEAT. FOR SMALLER-SEEDED GRASSES (ANNUAL RYEGRASS, PEARL MILLET, FOXTAIL MILLET), DO NOT EXCEED MORE THAN 5% (BY WEIGHT) OF THE OVERALL PERMANENT SEEDING MIX. CEREAL RYE GENERALLY SHOULD NOT BE USED AS A NURSE CROP, UNLESS PLANTING WILL OCCUR IN VERY LATE FALL BEFORE THE SEEDING DATES FOR OTHER TEMPORARY SEEDINGS. CEREAL RYE HAS ALLELOPATHIC PROPERTIES THAT INHIBIT THE GERMINATION AND GROWTH OF OTHER PLANTS. IF IT MUST BE USED AS A NURSE CROP, SEED AT 1/3 OF THE RATE LISTED ABOVE. OATS ARE THE RECOMMENDED NURSE CROP FOR WARM-SEASON GRASSES.

2. FOR SANDY SOILS, PLANT SEEDS AT TWICE THE DEPTH LISTED ABOVE.

3. THE PLANTING DATES LISTED ARE AVERAGES FOR EACH ZONE AND MAY REQUIRE ADJUSTMENT TO REFLECT LOCAL CONDITIONS, ESPECIALLY NEAR THE BOUNDARIES OF THE ZONE.

APPROVED: DEPARTMENT OF PLANNING AND ZONING

Chief, Department Engineering Division HSP  
 Date: 5/9/14  
 Chief, Division of Land Development  
 Date: 6-09-14  
 Director  
 Date: 6/9/14

# STANDARDS AND SPECIFICATIONS FOR SEEDING AND MULCHING

- SEEDING
  - ALL SEED MUST MEET THE REQUIREMENTS OF THE MARYLAND STATE SEED LAW. ALL SEED MUST BE SUBJECT TO RE-TESTING BY A RECOGNIZED SEED LABORATORY. ALL SEED USED MUST HAVE BEEN TESTED WITHIN THE 6 MONTHS IMMEDIATELY PRECEDING THE DATE OF SOWING SUCH MATERIAL ON ANY PROJECT. REFER TO TABLE B.4 REGARDING THE QUALITY OF SEED. SEED TAGS MUST BE AVAILABLE UPON REQUEST TO THE INSPECTOR TO VERIFY TYPE OF SEED AND SEEDING RATE.
  - MULCH ALONE MAY BE APPLIED BETWEEN THE FALL AND SPRING SEEDING DATES ONLY IF THE GROUND IS FROZEN. THE APPROPRIATE SEEDING MIXTURE MUST BE APPLIED WHEN THE GROUND THAWNS.
  - INOCULANTS: THE INOCULANT FOR TREATING LEGUME SEED IN THE SEED MIXTURES MUST BE A PURE CULTURE OF NITROGEN FIXING BACTERIA PREPARED SPECIFICALLY FOR THE SPECIES. INOCULANTS MUST NOT BE USED LATER THAN THE DATE INDICATED ON THE CONTAINER. ADD FRESH INOCULANTS AS DIRECTED ON THE PACKAGE. USE FOUR TIMES THE RECOMMENDED RATE WHEN HYDROSEEDING. NOTE: IT IS VERY IMPORTANT TO KEEP INOCULANTS AS COOL AS POSSIBLE UNTIL USED. TEMPERATURES ABOVE 75 TO 80 DEGREES FAHRENHEIT CAN WEAKEN BACTERIA AND MAKE THE INOCULANT LESS EFFECTIVE.
  - SOD OR SEED MUST NOT BE PLACED ON SOIL WHICH HAS BEEN TREATED WITH SOIL STERILANTS OR CHEMICALS USED FOR WEED CONTROL UNTIL SUFFICIENT TIME HAS ELAPSED (14 DAYS MIN.) TO PERMIT DISSIPATION OF PHYTO-TOXIC MATERIALS.
- APPLICATION
  - DRY SEEDING: THIS INCLUDES USE OF CONVENTIONAL DROP OR BROADCAST SPREADERS.
  - INCORPORATE SEED INTO THE SUBSOIL AT THE RATES PRESCRIBED ON TEMPORARY SEEDING TABLE B.1, PERMANENT SEEDING TABLE B.3, OR SITE-SPECIFIC SEEDING SUMMARIES.
  - APPLY SEED IN TWO DIRECTIONS, PERPENDICULAR TO EACH OTHER. APPLY HALF THE SEEDING RATE IN EACH DIRECTION. ROLL THE SEEDED AREA WITH A WEIGHTED ROLLER TO PROVIDE GOOD SEED TO SOIL CONTACT.
  - DRILL OR OUTLAPACKER SEEDING: MECHANIZED SEEDERS THAT APPLY AND COVER SEED WITH SOIL.
  - OUTLAPACKER SEEDERS ARE REQUIRED TO BURY THE SEED IN SUCH A FASHION AS TO PROVIDE AT LEAST 1/4 INCH OF SOIL COVERING. SEEDBED MUST BE FIRM AFTER PLANTING.
  - APPLY SEED IN TWO DIRECTIONS, PERPENDICULAR TO EACH OTHER. APPLY HALF THE SEEDING RATE IN EACH DIRECTION.
  - HYDROSEEDING: APPLY SEED UNIFORMLY WITH HYDROSEEDER (SLURRY INCLUDES SEED AND FERTILIZER).
    - IF FERTILIZER IS BEING APPLIED AT THE TIME OF SEEDING, THE APPLICATION RATES SHOULD NOT EXCEED THE FOLLOWING: NITROGEN, 100 POUNDS PER ACRE TOTAL OF SOLUBLE NITROGEN; P205 (PHOSPHORUS), 200 POUNDS PER ACRE; K20 (POTASSIUM), 200 POUNDS PER ACRE.
    - LIME: USE ONLY GROUND AGRICULTURAL LIMESTONE (UP TO 3 TONS PER ACRE MAY BE APPLIED BY HYDROSEEDING). NORMALLY, NOT MORE THAN 2 TONS ARE APPLIED BY HYDROSEEDING AT ANY ONE TIME. DO NOT USE BURNT OR HYDRATED LIME WHEN HYDROSEEDING.
    - MIX SEED AND FERTILIZER ON SITE AND SEED IMMEDIATELY AND WITHOUT INTERRUPTION.
    - WHEN HYDROSEEDING DO NOT INCORPORATE SEED INTO THE SOIL.
- MULCHING
  - MULCH MATERIALS (IN ORDER OF PREFERENCE)
    - STRAW CONSISTING OF THOROUGHLY THRESHED WHEAT, RYE, OAT, OR BARLEY AND REASONABLY BRIGHT IN COLOR. STRAW IS TO BE FREE OF NOXIOUS WEED SEEDS AS SPECIFIED IN THE MARYLAND SEED LAW AND NOT MOLLY, MOULDY, CANKY, DICKY, OR EXCESSIVELY DUSTY. NOTE: USE ONLY STERILE STRAW MULCH IN AREAS WHERE ONE SPECIES OF GRASS IS DESIRED.
    - WOOD CELLULOSE FIBER MULCH (WCFM) CONSISTING OF SPECIALLY PREPARED WOOD CELLULOSE PROCESSED INTO A UNIFORM FIBROUS PHYSICAL STATE.
      - WCFM IS TO BE DYED GREEN OR CONTAIN A GREEN DYE IN THE PACKAGE THAT WILL PROVIDE AN APPROPRIATE COLOR TO FACILITATE VISUAL INSPECTION OF THE UNIFORMLY SPREAD SLURRY.
      - WCFM, INCLUDING DYE, MUST CONTAIN NO GERMINATION OR GROWTH INHIBITING FACTORS.
      - WCFM MATERIALS ARE TO BE MANUFACTURED AND PROCESSED IN SUCH A MANNER THAT THE WOOD CELLULOSE FIBER MULCH WILL REMAIN IN UNIFORM SUSPENSION IN WATER UNDER AGITATION AND WILL BLEND WITH SEED, FERTILIZER AND OTHER ADDITIVES TO FORM A HOMOGENEOUS MIXTURE. THE MULCH MATERIAL MUST FORM A BLOTTER-LIKE GROUND COVER, ON APPLICATION, ALLOWING MOISTURE ABSORPTION AND PERCOLATION PROPERTIES AND MUST COVER AND HOLD GRASS SEED IN CONTACT WITH THE SOIL WITHOUT INHIBITING THE GROWTH OF THE GRASS SEEDLINGS.
      - WCFM MATERIAL MUST NOT CONTAIN ELEMENTS OR COMPOUNDS AT CONCENTRATIONS LEVELS THAT WILL BE PHYTO-TOXIC.
      - WCFM MUST CONFORM TO THE FOLLOWING PHYSICAL REQUIREMENTS: FIBER LENGTH OF APPROXIMATELY 10 MILLIMETERS; DIAMETER APPROXIMATELY 1 MILLIMETER; PH RANGE OF 4.0 TO 8.5, ASH CONTENT OF 1.6 PERCENT MAXIMUM AND WATER HOLDING CAPACITY OF 90 PERCENT MINIMUM.
  - APPLICATION
    - APPLY MULCH TO ALL SEEDED AREAS IMMEDIATELY AFTER SEEDING.
    - WHEN STRAW MULCH IS USED, SPREAD IT OVER ALL SEEDED AREAS AT THE RATE OF 2 TONS PER ACRE TO A UNIFORM LOOSE DEPTH OF 1 TO 2 INCHES. APPLY MULCH TO ACHIEVE A UNIFORM DISTRIBUTION AND DEPTH SO THAT THE SOIL SURFACE IS NOT EXPOSED. WHEN USING A MULCH ANCHORING TOOL, INCREASE THE APPLICATION RATE TO 2.5 TONS PER ACRE.
    - WOOD CELLULOSE FIBER USED AS MULCH MUST BE APPLIED AT A NET DRY WEIGHT OF 1500 POUNDS PER ACRE. MIX THE WOOD CELLULOSE FIBER WITH WATER TO ATTAIN A MIXTURE WITH A MAXIMUM OF 50 POUNDS OF WOOD CELLULOSE FIBER PER 100 GALLONS OF WATER.
  - ANCHORING
    - PERFORM MULCH ANCHORING IMMEDIATELY FOLLOWING APPLICATION OF MULCH TO MINIMIZE LOSS BY WIND OR WATER. THIS MAY BE DONE BY ONE OF THE FOLLOWING METHODS (LISTED BY PREFERENCE), DEPENDING UPON THE SIZE OF THE AREA AND EROSION HAZARD:
      - A MULCH ANCHORING TOOL IS A TRACTOR DRAWN IMPLEMENT DESIGNED TO PUNCH AND ANCHOR MULCH INTO THE SOIL SURFACE A MINIMUM OF 2 INCHES. THIS PRACTICE IS MOST EFFECTIVE ON LARGE AREAS, BUT IS LIMITED TO FLATTER SLOPES WHERE QUIP CAN OPERATE SAFELY. IF USED ON SLOPING LAND, THIS PRACTICE SHOULD FOLLOW THE CONTOUR.
      - WOOD CELLULOSE FIBER MAY BE USED FOR ANCHORING STRAW. APPLY THE FIBER BINDER AT A NET DRY WEIGHT OF 750 POUNDS PER ACRE. MIX THE WOOD CELLULOSE FIBER WITH WATER AT A MAXIMUM OF 50 POUNDS OF WOOD CELLULOSE FIBER PER 100 GALLONS OF WATER.
      - SYNTHETIC BINDERS SUCH AS ACRYLIC DLR (AGRO-TACK), DCA-70, PTEROSET, TERRA TAX II, TERRA TACK, AR, OR OTHER APPROVED EQUAL MAY BE USED. FOLLOW APPLICATION RATES AS SPECIFIED BY THE MANUFACTURER. APPLICATION OF LIQUID BINDERS NEEDS TO BE HEAVIER AT THE EDGES WHERE WIND CATCHES MULCH, SUCH AS IN VALLEYS AND ON CRESTS OF BANKS. USE OF ASPHALT BINDERS IS STRICTLY PROHIBITED.
      - LIGHTWEIGHT PLASTIC NETTING MAY BE STAPLED OVER THE MULCH ACCORDING TO MANUFACTURER RECOMMENDATIONS. NETTING IS USUALLY AVAILABLE IN ROLLS 4 TO 15 FEET WIDE AND 300 TO 3,000 FEET LONG.

PERMANENT SEEDING SUMMARY						FERTILIZER RATE (10-20-20)	LIME RATE
HARDNESS ZONE (FROM FIGURE B.3): 6b		SEED MIXTURE (FROM TABLE B.3)					
NO.	SPECIES	APPLICATI ON RATE (lb/ac)	SEEDING DATES	SEEDING DEPTHS			
1	SWITCHGRASS	10	3/1 -				
	CREeping RED FESCUE BUSH CLOVER	15	5/15 8/1	3" - 3"			
		2	- 10/15				
					45 lb/ac	90 lb/ac	
					(1.0 lb/ 1000 sf)	(2.0 lb/ 1000 sf)	
3	DEERTONGUE SHEEP FESCUE COMMON LESPEDAZA	20	3/1 -				
		20	5/15 8/1	3" - 3"			
		10	- 10/15				
					90 lb/ac	90 lb/ac	
					(2.0 lb/ 1000 sf)	(2.0 lb/ 1000 sf)	

## DEVELOPER'S CERTIFICATION

I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT

*D. Mathey*  
 SIGNATURE OF DEVELOPER  
 DATE: 4.24.14  
*Dennis Mathey*  
 PRINTED NAME

## HOWARD SOIL CONSERVATION DISTRICT

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.  
*John D. ...*  
 DATE: 4/29/14

## BEST MANAGEMENT PRACTICES FOR WORKING IN NON TIDAL WETLANDS, WETLAND BUFFERS, WATERWAYS AND 100 YEAR FLOOD PLAINS

- NO EXCESS FILL, CONSTRUCTION MATERIAL, OR DEBRIS SHALL BE STOCKPILED OR STORED IN NON TIDAL WETLANDS, NON TIDAL WETLAND BUFFERS, WATERWAYS OR THE 100-YEAR FLOODPLAIN.
- PLACE MATERIALS IN A LOCATION AND MANNER WHICH DOES NOT ADVERSELY IMPACT SURFACE OR SUBSURFACE WATER FLOW INTO OR OUT OF NON TIDAL WETLANDS, NON TIDAL WETLAND BUFFERS, WATERWAYS OR THE 100 YEAR FLOODPLAIN.
- DO NOT USE EXCAVATED MATERIAL AS BACK FILL IF IT CONTAINS WASTE METAL PRODUCTS, UNSIGHTLY DEBRIS, TOXIC MATERIAL, OR ANY OTHER DELETERIOUS SUBSTANCE. IF ADDITIONAL BACK FILL IS REQUIRED, USE CLEAN MATERIAL FREE OF WASTE METAL PRODUCTS, UNSIGHTLY DEBRIS, TOXIC MATERIAL, OR ANY OTHER DELETERIOUS SUBSTANCE.
- PLACE HEAVY EQUIPMENT ON MATS OR SUITABLY OPERATE THE EQUIPMENT TO PREVENT DAMAGE TO NON TIDAL WETLANDS, NON TIDAL WETLAND BUFFERS, OR WATERWAYS OR THE 100 YEAR FLOOD PLAN.
- REPAIR AND MAINTAIN ANY SERVICEABLE STRUCTURE OR FILL SO THERE IS NO PERMANENT LOSS OF NON TIDAL WETLANDS, NON TIDAL WETLAND BUFFERS, OR WATERWAYS, OR PERMANENT MODIFICATION OF THE 100 YEAR FLOOD PLAN IN EXCESS OF THAT LOSS UNDER THE ORIGINALLY AUTHORIZED STRUCTURE OR FILL.
- RECTIFY ANY NON TIDAL WETLANDS, WETLAND BUFFERS, WATERWAYS OR 100 YEAR FLOOD PLAN TEMPORARILY IMPACTED BY ANY CONSTRUCTION.
- ALL STABILIZATION IN THE NON TIDAL WETLAND AND NON TIDAL WETLAND BUFFER SHALL CONSIST OF THE FOLLOWING SPECIES: ANNUAL RYEGRASS (LOLUM MULTIFLORUM), MILLET (STARIA ITALICA), BARLEY (HORDEUM SP.), OATS (UNOLA SP.), AND/OR RYE (SECALE CEREALE). THESE SPECIES WILL ALLOW FOR THE STABILIZATION OF THE SITE WHILE ALSO ALLOWING FOR THE VOLUNTARY REVEGETATION OF NATURAL WETLAND SPECIES. OTHER NON PERSISTENT VEGETATION MAY BE ACCEPTABLE, BUT MUST BE APPROVED BY THE NON TIDAL WETLANDS AND WATERWAYS DIVISION. KENTUCKY 31 FESCUE SHALL NOT BE UTILIZED IN WETLAND OR BUFFER AREAS. THE AREA SHOULD BE SEEDED AND MULCHED TO REDUCE EROSION AFTER CONSTRUCTION ACTIVITIES HAVE BEEN COMPLETED.
- IF AFTER INSTALLATION HAS BEEN COMPLETED, MAKE POST CONSTRUCTION GRADES AND ELEVATIONS THE SAME AS THE ORIGINAL GRADES AND ELEVATIONS IN TEMPORARILY IMPACTED AREAS.
- TO PROTECT AQUATIC SPECIES, IN STREAM WORK IS PROHIBITED AS DETERMINED BY THE CLASSIFICATION OF THE STREAM: USE IV WATERS.
- STORMWATER RUNOFF FROM IMPERVIOUS SURFACES SHALL BE CONTROLLED TO PREVENT THE WASHING OF DEBRIS INTO THE WATERWAY.
- CULVERTS SHALL BE CONSTRUCTED AND ANY RIP RAP PLACED SO AS NOT TO OBSTRUCT THE MOVEMENT OF AQUATIC SPECIES, UNLESS THE PURPOSE OF THE ACTIVITY IS TO IMPOUND WATER.

## ENGINEER'S CERTIFICATION

I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.  
*Sepehr Baharloo*  
 SIGNATURE OF ENGINEER  
 DATE: 4/21/14  
 SEPEHR BAHARLOU  
 PRINTED NAME  
 DATE: 6/5/2014

10221 WINCOPIN CIRCLE #100  
 COLUMBIA, MD 21046  
 (410) 381 - 2947

1321 Mercedes Drive, Suite A  
 Hanover, Maryland 21076  
 Phone: (410)694-9401  
 Fax: (410)694-9405  
 Email: bayland@baylandinc.com  
 Website: http://www.baylandinc.com  
 BAYLAND JOB NO. 8-16202

WOVEN CURTAIN MATERIAL SPECIFICATIONS				
PROPERTY	TEST METHOD	RESULTS	RESULTS	RESULTS
FABRIC CODE		AEF 200W	AEF 300W	AEF 650W
FABRIC STRUCTURE		WOVEN	WOVEN	WOVEN
POLYMER COMPOSITION		POLYPROPYLENE	POLYPROPYLENE	POLYPROPYLENE
WEIGHT	ASTM D-4632	4.2 OZ/SQ. YD	5.8 OZ/SQ. YD	6.3 OZ/SQ. YD
GRAB STRENGTH	ASTM D-4632	200 LBS.	300 LBS.	390 X 250 LBS.
TRAP TEAR STRENGTH	ASTM D-4533	90 LBS.	120 LBS.	115 X 65 LBS.
BURST STRENGTH	ASTM D-3786	400 PSI	600 PSI	495 PSI
PUNCTURE	ASTM D-3787	90 LBS.	150 LBS.	130 LBS.
ELONGATION	ASTM D-4632	20%	20%	30%
UV RESISTANCE	ASTM D-4335	70K (500HRS)	70K (500HRS)	70K (500HRS)
E.O.S.		CW-02215	40	70

MAINTENANCE: INSPECT TURBIDITY CURTAIN AFTER EACH MAJOR STORM EVENT RESULTING FROM 3-INCHES OR MORE OF RAINFALL WITHIN A 24-HOUR PERIOD. REPAIR OR REPLACE DAMAGED MATERIALS AND REMOVE ANY DEBRIS LODGED AGAINST THE TURBIDITY CURTAIN.

## FLOATING TURBIDITY BARRIERS

REVISED SITE DEVELOPMENT PLAN  
 LAKE KITTAMAQUUNDI MULTIUSE TRAIL  
 EROSION AND SEDIMENT CONTROL  
 NOTES & DETAILS

REVISIONS				SCALE: AS-SHOWN	
DATE	BY	DESCRIPTION			

DRAWN BY: MKB DATE: 04/21/14  
 CHECKED BY: SB DATE: 4/21/2014  
 DESIGNED BY: MKB DATE: 04/21/14  
 DRAWING K-13, SHEET NO. 59 OF 59