I CERTIFY THAT THE PLAN OF DEVELOPMENT AND THE PLAN FOR CONTROL OF SILT AND EROSION MEETS THE REQUIREMENTS, STANDARDS, & SPECIFICATIONS OF THE HOWARD SOIL CONSERVATION DISTRICT.

H. Byron Gates Jr. 2/3/72

H. BYRON GATES JR. AIA, ARCHITECT DATE:

I CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT AND PLAN OF SILT AND SEDIMENT CONTROL.

C. M. Hale 2-3-72

C.M. HALE CO., CONTRACTOR DATE:

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

REVIEWED James M. Helm 2-11-72

DIST. CONSERVATIONIST DATE

APPROVED Robert W. Zickefoose 2-11-72

HOWARD SOIL CONSERVATION DISTRICT DATE



DRIVEWAY & PARKING LOT SURFACE SPECIFICATION AS FOLLOWS:

BITUMINOUS CONC. SURFACE	1" BAND C-3
BITUMINOUS CONC. BINDER	3" BAND C-2
BALTIMORE GRAVEL BASE	9"

CLEARING & GRADING = ARTICLE C-1
SUBGRADE = ARTICLE C-2
BASE COURSE = ARTICLE C-25
BINDER COURSE = ARTICLE C-31 OR C-33
SURFACE COURSE = ARTICLE C-31

TO BE CONSTRUCTED IN ACCORDANCE WITH THE HOWARD COUNTY ROAD CONSTRUCTION CODE & SPECIFICATIONS THIS TO INCLUDE CONCRETE CURB CHANNELIZED INTERSECTION @ NEW DRIVEWAY & BETHANY LANE.
ALL NOTED WORK; ACCESS APRON, DRIVEWAY & PARKING AREAS TO BE PERFORMED BY THE CONTRACTOR.

GENERAL NOTES:
1. GRADING & PAVING CONSTR. SHALL PERFORM SITE WORK, INCLUDING PAVING, SODDING & SEEDING, IN ONE CONTINUOUS OPERATIONS. IN THE EVENT COMPLETION OF WORK IS DELAYED, PROVIDE SILTATION CONTROL POND IN COMPLIANCE W/HOWARD CO. REQUIREMENTS
2. STABILIZATION OF DISTURBED GROUND SHALL BE DONE AS SOON AFTER CONSTRUCTION IS COMPLETED AS PRACTICABLE.
3. BERMS & LEVEL SPREADERS SHALL NOT BE REMOVED WITHOUT WRITTEN APPROVAL FROM THE HOWARD CO. SOIL CONSERVATION DISTRICT.
4. SLOPE & CRITICAL AREA STABILIZATION SHALL ADHERE TO METHODS OUTLINED IN THE "EROSION & SEDIMENT CONTROL TECHNICAL HANDBOOK", PUBLISHED BY HOWARD CO. SOIL CONSER. DIST.
5. THE CONSTR. SHALL NOTIFY THE HOWARD CO. SOIL CONSER. DIST. 24 HOURS PRIOR TO START OF CONSTRUCTION.





PARKING AREA - SPACE 10'x20'
PARKING REQ'D - 99 SPACES
PARKING PROVIDED - 102 SPACES

NEW PARKING AREA & DT ROLLED & COMPACTED.

SITE

THESE PLANS ARE DRAWN IN ACCORDANCE THE BUILDING CODE OF HOWARD CO., MARY

H. Byron Gates

H. BYRON GATES, JR. MD. REG. NO. 8

SDP 71-105

PROPOSED INTERIM SANCTUARY AND EDUCATIONAL BUILDING
BETHANY LANE BAPTIST CHURCH, ELLICOTT CITY, MARYLAND 21043
REV. MARVIN C. SIMPSON, PASTOR

PREPARED FOR
C. M. HALE ASSOCIATES, INC.
8525 COLESVILLE ROAD
SILVER SPRING MARYLAND 20910
301-588-0658

H. BYRON GATES, JR. A.I.A.
ARCHITECT
8525 COLESVILLE ROAD
SILVER SPRING MARYLAND
301-589-8577