

PERMANENT SEEDING NOTES

Apply to graded or cleared area not subject to immediate further disturbance where a permanent long—lived vegetative cover is needed

Seedbed Preparation: Loosen upper three inches of soil be raking, discing or other acceptable means before seeding. (If not previously loosened)

Soil Amendments: In lieu of soil test recommendations, use on the following

- 1) Preferred Apply 2 tons per acre dolomitic limestone (92 lbs/1000 sf) and 600 lbs per acre 10-10-10 fertilizer (14 lbs/1000 sf) before seeding. Harrow or disc into upper three inches of soil. At time of seeding, apply 400 lbs per acre 30-0-0 ureaform fertilizer (9 lbs/1000 sf)
- 2) Acceptable Apply 2 tons per acre dolomitic limestone (92 lbs/1000 sf) and 1000 lbs per acre 10-10-10 fertilizer (23 lbs/1000 sf) before seeding. Harrow or disc into upper three inches of soil.

Seeding: For the periods March 1 through April 30 and August 1 through October 15, seed with 60 lbs per acre (1.4 lbs/1000 sf) of Kentucky 31 Tall Fescue. For the period May 1 through July 31, seed with 60 lbs Kentucky 31 Tall Fescue per acre and 2 lbs per acre (0.05 lbs/1000 sf) of Weeping Lovegrass. During the period of October 16 through February 28, protect site by: Option 1) 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring Option 2) use sod. Option 3) seed with 60 lbs/acre Kentucky 31 Tall Fescue and mulch with 2 tons/acre well anchored straw.

Mulching: Apply 1-1/12 to 2 tons per acre (70 to 90 lbs/1000 sf) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gallons per acre (5 gal/1000 sf) of emulsified asphalt on flat areas. On slopes 8 feet or higher, use 348 gallons per acre (8 gal/1000 sf) for anchoring.

Maintenance: Inspect all seeded areas and make needed repairs, replacements and reseedings

SEDIMENT CONTROL NOTES

- 1. A minimum of 48 hours notice must be given to the Howard County Department of Inspections and Permits, Sediment Control Division prior to the start of any construction (313-1855)
- 2. All vegetative and structural practices are to be installed accordingly to the provisions of this plan and are to be in conformance with the most current "Maryland Standards and Specifications for Soil Erosion and Sediment Control". and revisions thereto
- 3. Following initial soil disturbances or redisturbance, permanent or temporary stabilization shall be completed within: a) 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all slopes greater than 3:1, b) 14 calendar days as to all other disturbed or graded areas on the project site.
- 4. All sediment traps/basins shown must be fenced and warning signs posted around their perimeter in accordance with Vol. 1, Chapter 12, of the "Howard County Design Manual, Storm Drainage
- 5. All disturbed areas must be stabilized within the time period specified above in accordance with the "1991 Maryland Standards and Specifications for Soil Erosion and Sediment Control" for Permanent Seedings (Sec. 51) Sod (Sec. 54), Temporary Seeding (Sec. 50) and Mulching (Sec. 52). Temporary stabilization with mulch alone can only be done when recommended seeding dates do not allow for proper germination and establishment of grasses.
- 6. All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector

2.38± acres

2.7**4**± acre

0.67± acre

2.07± acre

4660 cy.

7. Site Analysis: Total Area of Site:

Area to be Disturbed Area to be roofed or paved: Area to be vegetatively stabilized:

Total Fill: Offsite Waste/Borrow Area Location : •

- 8. Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance. 9. Additional sediment controls must be provided, if deemed necessary by the Howard County DPW Sediment Control Inspector
- 10. On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the inspection agency is made.
- 11 Trenches for the construction of utilities is limited to three pipe lengths or that which can be back filled and stabilized within one working day, whichever is shorter.
- 12. Quantities and estimates shown are for sediment control purposes only. Contractor shall prepare his/her own quantity estimates to his/her satisfaction. * It is the responsibility of the contractor to identify the spoil/borrow site and notify and gain approval from the sediment control inspector of the site and it's grading permit number at the time of construction.

SEQUENCE OF CONSTRUCTION

Notify Sediment Control Division 48 hours prior to start of construction.

- Obtain grading permit
- 2. Install new sediment and erosion control devices and stabilize. Install tree protection fence as indicated on plan
- 4. Excavate for foundations, rough grade and temporarily stabilize. Except Lots 23-25K, delay construction of these lots until the site is stabilized and the trap is removed with the approval of the Howard County Sediment Control Inspector. Note: silt fence may be required along the perimeter of each house
- 5. Construct house and driveway.
- 6. Final grade and stabilize in accordance with standards and specifications.
- 7. Upon approval of the Howard County sediment control inspector, remove sediment and erosion control devices and stabilize.

TEMPORARY SEEDING NOTES

Apply to graded or cleared areas likely to be redisturbed where a short—term vegetative cover is needed.


Seedbed Preparation: Loosen upper three inches of soil by raking, discing or

other acceptable means before seeding. (If not previously loosened) Soil Amendments: Apply 600 lbs per acre 10-10-10 fertilizer (14 lbs/1000 sf).

Seeding: For periods March 1 through April 30 and from August 15 through November 15, seed with 2-1/2 bushel per acre of annual rye (3.2 lbs/1000 sf). For the period May 1 through August 14, seed with 3 lbs per acre of Weeping Lovegrass (0.07 lbs/1000 sf). For the period November 16 through February 28. protect site by applying 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring, or use sod.

Mulching: Apply 1-1/2 to 2 tons per acre (70 to 90 lbs/1000 sf) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gallons per acre (5 gal/1000 sf) of emulsified asphalt on flat areas. On slopes 8 feet or higher, use 348 gallons per acre (8 gal/1000 sf) for anchoring.


Refer to the 1983 Maryland Standards and Specifications for Soil Erosion and Sediment Control for rate and methods not covered.



- 1. FOREST PROTECTION DEVICE ONLY.
- RETENTION AREA WILL BE SET AS PART OF THE REVIEW PROCESS. 3. BOUNDARIES OF RETENTION AREA SHOULD BE STAKED AND FLAGGED PRIOR TO INSTALLING DEVICES
- 4. AVOID ROOT DAMAGE WHEN PLACING ANCHOR POSTS
- DEVICE SHOULD BE PROPERLY MAINTAINED DURING CONSTRUCTION 6. PROTECTIVE SIGNAGE IS ALSO REQUIRED.

TEMPORARY TREE PROTECTION FENCE

NOT TO SCALE




Days 7-10 ★ TREE PLANTING DETAIL Days 11-81* NOT TO SCALE Days 82-86

DETAIL 1 - EARTH DIKE STANDARD SYMBOL NOT TO SCALE A-2 B-3 *→* -/*→* --EXCAVATE TO PROVIDE RADE LINE-REQUIRED FLOW WIDTH -AT DESIGN FLOW DEPTH CROSS SECTION POSITIVE DRAINAGE - GRADE SUFFICIENT TO DRAIN o-DIKE HEIGHT b-DIKE **W**DTH A A A A A A APLAN VIEW FLOW CHANNEL STABILIZATION Seed and cover with straw mulch. Seed and cover with Erosion Control Matting or line with sod.
 4" - 7" stone or recycled concrete equivalent pressed into the soil 7" minimum. CONSTRUCTION SPECIFICATIONS All temporary earth dikes shall have uninterrupted positive grade to an outlet.

- . Runoff diverted from a disturbed area shall be conveyed to a sediment trapping
- Runoff diverted from an undisturbed area shall outlet directly into an undisturbed, stabilized area at a non-erosive velocity. All trees, brush, stumps, obstructions, and other objectional material shall be removed and disposed of so as not to interfere with the proper functioning of the dice.
- . The dike shall be excavated or shaped to line, grade and cross section as required to meet the criteria specified herein and be free of bank projections or other irregularities which will impede normal flow. 5. Fill shall be compacted by earth moving equipment.
- . All earth removed and not needed for construction shall be placed so that it will 3. Inspection and maintenance must be provided periodically and after each rain event.

PAGE
A - 1 - 6


MARYLAND DEPARTMENT OF ENVIRONMEN
WATER MANAGEMENT ADMINISTRATION U.S. DEPARTMENT OF AGRICULTURE





 Geotextile fabric (filter cloth) shall be placed over the existing ground prior to placing stone. **The plan approval authority may not require single family 4. Stone — crushed aggregate (2" to 3") or reclaimed or recycled concrete equivalent shall be placed at least 6" deep over the length and width of the entrance. Surface Water - all surface water flowing to or diverted toward construction entrances shall be piped through the entrance, maintaining positive drainage. Pipe


installed through the stabilized construction entrance shall be protected with a mountable berm with 5:1 slopes and a minimum of 6" of stone over the pipe. Pipe has to be sized according to the drainage. When the SCE is located at a high spot and has no drainage to convey a pipe will not be necessary. Pipe should be sized according to the amount of runoff to be conveyed. A 6" minimum will be require Location - A stabilized construction entrance shall be located at every point where construction traffic enters or leaves a construction site. Vehicles leaving the site must travel over the entire length of the stabilized construction entrance PAGE F - 17 - 3 WARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE

DETAIL 33 - SUPER SILT FENCE SUPER SILT FENCE CONSTRUCTION SPECIFICATIONS CHAIN LINK FENCE WITH ONE LAYER OF FILTER CLOTH OVER Fencing shall be 42" in height and constructed in accordance with the latest Maryland State Highway Details for Chain Link Fencing. The specification for a 5' fence shall be used, substituting 42" fabric and 6' length posts. 10' MAXIMUM Chain link fence shall be fastened securely to the fence posts with wire ties. The lower tension wire, brace and truss rods, drive anchors and post caps are not required except on the ends of the fence. Filter cloth shall be fastened securely to the chain link fence with ties spaced every 24" at the top and mid section. . Filter cloth shall be embedded a minimum of 8" into the ground. FLOW PERSPECTIVE VIEW _2~1'/'2~" Dig. GALVANIZED OR SSF-CHAIN LINK FENCE --SUPER SILT FENCE DESIGN CRITERIA _2~1'/'2~" Dia. GALVANIZED OR ALUMINUM FENCE POST 16" MIN. 1st LAYER (maximum) FILTER CLOTH FLOW 0 - 10:1 Unlimited 10 - 20% 10:1 - 5:1 200 feet EMBED FILTER CLOTH 100 feet 20 - 33% 5:1 - 3:1 MIN. B" INTO GROUND 33 - 50% 3:1 - 2:1 50 feet











I hereby certify that this plan for erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard County Soil Conservation District.

DEVELOPER'S CERTIFICATE

I/We certify that all development and construction will be done in accordance with this plan of development and plan for erosion and sediment control and that all responsible personnel involved in the construction of this project will have a certificate of attendance at a Department of the Environment approved training program for the control of sediment and erosion before beginning the project. I also authorize periodic onsite inspection by the Howard County Soil Conservation District or their authorized agents, as are deemed necessary.



1-2-96 REV. AS PER CO. COMMENTS NO DATE

TSA GROUP, INC. planning · architecture · engineering · surveying

8480 Baltimore National Pike • Ellicott City, Maryland 21043 • (410) 465-6105

SUBDIVISION NAME NORTH LAUREL PARK OWNER/DEVELOPER BLOCK K, LOTS 17-29 NORTH LAUREL PARK SECT./AREA PARCEL # LIBER & FOLIO PREVIOUS FILE: BLOCK K, LOTS 17-29 L.61 F.470 N/A LOCATION: _ _ _ _ _ 426 CORNERSTONE HOMES TAX MAP 50-PARCEL 426 6571 HUNTSHIRE DRIVE 6th ELECTION DISTRICT HOWARD COUNTY, MARYLAND ELKRIDGE, MARYLAND 21227 PLAT No. BLOCK No. ZONE TAX MAP ELEC. DIST. CENSUS (410)379-0157 61/470 6069.03 R-SC SEDIMENT CONTROL NOTES & DETAILS SEWER COD WATER CODE CO5 7140000 & 7141500 PROJECT NO. 0850 SCALE: DATE: OCT.,1995 NOT TO SCALE DES: MLV/CAM | CHK: CAM | DRN: JMC | SCALE: NOT TO SCALE DRAWING $\underline{3}$ OF $\underline{3}$

PERMIT INFORMATION CHART

HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING

*INDICATES SINGLE HOUSE CONSTRUCTION.

APPROVED:

REVIEWED FOR HOWARD COUNTY SOIL CONSERVATION DISTRICT AND MEETS TECHNICAL REQUIREMENTS.

APPROVED: THIS DEVELOPMENT IS APPROVED FOR EROSION AND

SEDIMENT CONTROL BY THE HOWARD COUNTY SOIL CONSERVATION DISTRICT.