


CENTURY ENGINEERING
 CONSULTING ENGINEERS - PLANNERS
 10710 GILROY ROAD
 HUNT VALLEY, MARYLAND 21031
 PHONE: (443) 589-2400 FAX: (443) 589-2401




DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND
Mark S. Richmond 12/30/19
 CHIEF, STORMWATER MANAGEMENT DIVISION DATE
 I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.
 LICENSE #: 28371 EXPIRES: 01/01/2021

REVISIONS		
NO.	DATE	DESCRIPTION

HOWARD COUNTY
 DEPARTMENT OF PUBLIC WORKS
 D-1158 CHERRYTREE FARM
 STREAM RESTORATION
 FINAL (100%) DESIGN
 SHEET LAYOUT

PROJECT NO:	121104.64
SCALE:	1" = 50'
DATE:	12/28/19
DESIGN:	SH
DRAWN:	JT
CHECK:	CL
DWG NO:	OV-01 of OV-01
SHEET NO:	02 of 22



- PROPOSED FEATURES LEGEND**
- LIMIT OF DISTURBANCE — LOD —
 - 1' MINOR CONTOUR — 305 —
 - 5' MAJOR CONTOUR — 305 —
 - WOODY HABITAT FEATURE (WHF) [Symbol]
 - BOULDER DROP STRUCTURE (BDS) [Symbol]
 - ROCK STEP-POOL STRUCTURE (RSP) [Symbol]
 - ARMORED RIFFLE (R) [Symbol]
 - CLASS 0 RIPRAP CHOKED WITH SILT AND GRAVEL [Symbol]
 - CLAY CHANNEL BLOCK (CCB) [Symbol]
- EXISTING FEATURES LEGEND**
- EX. BUILDING [Symbol]
 - EX. NONTIDAL WETLAND [Symbol]
 - EX. WATERS OF THE U.S. [Symbol]
 - EX. FENCE [Symbol]
 - EX. PROPERTY BOUNDARY [Symbol]
 - EX. EASEMENT [Symbol]
 - EX. EDGE OF PAVEMENT [Symbol]
 - EX. GAS MAIN [Symbol]
 - EX. TREE LINE [Symbol]
 - EX. CONCRETE DEBRIS [Symbol]
 - EX. RIPRAP [Symbol]
 - EX. CONCRETE MONUMENT [Symbol]
 - EX. TREE [Symbol]
 - EX. TRAVERSE POINT [Symbol]
 - EX. STORMDRAIN [Symbol]
 - EX. 1' MINOR CONTOUR [Symbol]
 - EX. 5' MAJOR CONTOUR [Symbol]

CLAY CHANNEL BLOCK (CCB)

CCB #	FROM STATION	OFFSET	TO STATION	OFFSET
1	1+22.61	5.44 R	1+22.77	19.07 R
2	1+55.95	14.59 L	1+56.49	4.47 L
3	1+97.66	8.26 R	1+98.27	21.03 R
4	4+42.65	6.28 R	4+44.03	21.10 R
5	4+72.88	17.05 L	4+73.08	0.46 L

ROCK STEP POOL (RSP)

RSP#	WEIR STATION*	WEIR ELEVATION*	WEIR WIDTH	A**		B**	
				NORTHING	EASTING	NORTHING	EASTING
1	0+51.81	323.54	4.0'	536946.2130	1342942.2886	536936.6808	1342902.3496
2	0+86.94	322.29	4.0'	536901.5754	1342932.3254	536918.0471	1342914.8399
3	1+26.46	321.04	4.0'	536876.5975	1342923.6811	536867.2011	1342901.6965
4	1+60.46	320.04	4.0'	536837.3747	1342930.7476	536844.1989	1342905.3638
5	2+02.98	318.54	4.0'	536805.1205	1342927.0091	536794.9877	1342901.0607
6	2+38.57	317.29	4.0'	536776.9678	1342947.6132	536761.0282	1342917.5642
7	2+82.15	315.79	4.0'	536743.7868	1342966.5835	536726.5689	1342947.1405
8	3+12.71	314.79	4.0'	536714.9101	1342983.4225	536702.3700	1342963.2532
9	3+59.89	313.54	6.0'	536663.3816	1343000.3779	536662.5964	1342968.5693
10	3+88.06	312.54	4.0'	536638.9115	1343004.7758	536632.0192	1342973.9217
11	4+47.85	311.04	6.0'	536582.2213	1343019.9764	536572.6422	1342983.3899
12	4+79.86	309.79	4.0'	536550.0593	1343026.5290	536544.9565	1342996.8604
13	5+18.11	308.54	4.0'	536512.0192	1343030.1396	536506.8535	1342998.4233
14	5+65.63	307.04	4.0'	536470.0162	1343042.2043	536460.0433	1343018.8281
15	5+96.63	305.79	4.0'	536439.0900	1343051.8906	536429.7796	1343025.6610

*STATION AND ELEVATIONS DENOTE THE DOWNSTREAM EDGE OF THE WEIR STONE. REFER TO THE DETAIL SHEET (DE-01) AND PROFILE SHEET (PR-01) FOR ADDITIONAL INFORMATION.

** CONTROL POINTS 'A' AND 'B' ARE ONLY TO DENOTE THE ORIENTATION OF THE ROCK STEP STRUCTURE. REFER TO THE PROFILE SHEET (PR-01) FOR STATIONS AND ELEVATIONS. ACTUAL CUT-OFF SILL LENGTH MAY VARY DUE TO INTERIM STREAM BANK EROSION. SILL MUST KEY INTO EXISTING BANK A MINIMUM OF 3.0'. SEE DETAIL SHEET DE-01.

- NOTES:**
- NOT ALL FURNISHED STONE IS SHOWN IN PLAN VIEW. SEE THE STREAM RESTORATION DETAILS (DE-01 TO 03) AND PROFILE (PR-01) FOR ADDITIONAL INFORMATION.
 - SOIL FABRIC LIFTS SHALL BE USED TO CONSTRUCT ALL FILL SLOPES AS SHOWN ON DETAIL SHEET DE-03.

ORIGINAL SCALE: 1"=20'

ARMORED RIFFLE (R)

R#	STA. FROM	STA. TO
1	3+40.98	3+57.89
2	4+17.75	4+45.65
3	5+43.36	5+63.63

WOODY HABITAT FEATURE (WHF)

WHF #	STA. FROM	STA. TO
1	1+38.38	1+44.34
2	1+73.06	1+79.59
3	3+98.91	4+05.53
4	4+57.63	4+64.30

TRIBUTARY STABILIZATION (CLASS 0 RIPRAP)


STA. FROM	STA. TO
100+02.08	100+05.59
100+09.85	100+20.59
100+25.00	100+33.59
100+36.95	100+47.59
100+51.82	100+65.92

BOULDER DROP STRUCTURE (BDS)

BDS #	WEIR STATION	WEIR ELEVATION
1	100+07.59	319.48
2	100+22.59	317.98
3	100+34.59	316.73
4	100+49.59	315.73

*STATION AND ELEVATIONS DENOTE THE DOWNSTREAM EDGE OF THE WEIR STONE. REFER TO THE DETAIL SHEET (DE-01) AND PROFILE SHEET (PR-01) FOR ADDITIONAL INFORMATION.

MT CENTURY ENGINEERING
 CONSULTING ENGINEERS - PLANNERS
 10710 GILROY ROAD
 HUNT VALLEY, MARYLAND 21031
 PHONE: (443) 589-2400 FAX: (443) 589-2401



DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND
 Chief, Stormwater Management Division
 Mark S. Richmond 12/30/19
 I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.
 LICENSE #: 28371 EXPIRES: 01/01/2021

HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

REVISIONS


NO.	DATE	DESCRIPTION

PROJECT NO: 121104.64
 SCALE: 1"=20' DATE: 12/26/19
 DESIGN: SH DRAWN: JT CHECK: CL
 DWS NO: SR-01 OF SR-02
 SHEET NO: 03 OF 22

D-1158 CHERRYTREE FARM STREAM RESTORATION

FINAL (100%) DESIGN

STREAM RESTORATION PLAN



- PROPOSED FEATURES LEGEND**
- LIMIT OF DISTURBANCE
 - 1" MINOR CONTOUR
 - 5' MAJOR CONTOUR
 - WOODY HABITAT FEATURE (WHF)
 - BOULDER SILL
 - ROCK STEP POOL STRUCTURE (RSP)
 - ARMORED RIFFLE (R)
 - TRIBUTARY STABILIZATION (CLASS I RIPRAP CHOKED WITH SILT AND GRAVEL)
 - CLAY CHANNEL BLOCK (CCB)
- EXISTING FEATURES LEGEND**
- EX. BUILDING
 - EX. NONTIDAL WETLAND
 - EX. WATERS OF THE U.S.
 - EX. FENCE
 - EX. PROPERTY BOUNDARY
 - EX. EASEMENT
 - EX. EDGE OF PAVEMENT
 - EX. GAS MAIN
 - EX. TREETRUNK
 - EX. CONCRETE DEBRIS
 - EX. RIPRAP
 - EX. CONCRETE MONUMENT
 - EX. TREE
 - EX. TRAVERSE POINT
 - EX. STORMDRAIN
 - EX. 1" MINOR CONTOUR
 - EX. 5' MAJOR CONTOUR

BOULDER SILL

STA. FROM	STA. TO
200+19.65	200+21.65

CLAY CHANNEL BLOCK (CCB)

CCB #	FROM STATION	OFFSET	TO STATION	OFFSET
6	7+26.89	16.33 R	7+27.42	1.80 R
7	7+62.85	25.26 L	7+67.99	5.91 L
8	8+84.31	6.31 L	8+86.19	20.37 L
9	9+23.45	4.59 R	9+25.78	27.02 R
10	9+35.14	26.14 L	9+41.72	4.06 L
11	9+71.48	5.15 R	9+71.51	27.13 R

ARMORED RIFFLE (R)

R#	STA. FROM	STA. TO
4	6+99.96	7+31.59
5	8+32.65	8+58.95
6	10+03.34	10+46.95

ROCK STEP POOL (RSP)

RSP #	WEIR STATION*	WEIR ELEVATION*	WEIR WIDTH	A**		B**	
				NORTHING	EASTING	NORTHING	EASTING
16	6+33.48	304.54	4.0'	536401.4133	1343059.7463	536395.3637	1343032.3710
17	6+70.96	303.29	4.0'	536354.9570	1343059.4856	536396.3314	1343030.8654
18	7+31.59	302.04	6.0'	536303.2226	1343026.5160	536313.8211	1342998.5248
19	7+73.64	301.04	4.0'	536263.3398	1343015.6800	536277.5425	1342980.4492
20	8+58.95	298.54	6.0	536213.0952	1343040.1589	536189.2499	1343005.5164
21	8+87.53	297.04	4.0'	536172.7682	1343045.8651	536163.3871	1343006.6658
22	9+16.05	295.54	4.0'	536139.5732	1343047.1981	536143.3430	1343008.7069
23	9+44.98	294.04	4.0'	536112.4696	1343036.7216	536114.1103	1343010.2371
24	9+73.39	292.54	4.0'	536085.3465	1343031.7314	536082.2108	1343007.1954

*STATION AND ELEVATIONS DENOTE THE DOWNSTREAM EDGE OF THE WEIR STONE. REFER TO THE DETAIL SHEET (DE-01) AND PROFILE SHEET (PR-01) FOR ADDITIONAL INFORMATION.

** CONTROL POINTS 'A' AND 'B' ARE ONLY TO DENOTE THE ORIENTATION OF THE ROCK STEP STRUCTURE. REFER TO THE PROFILE SHEET (PR-01) FOR STATIONS AND ELEVATIONS. ACTUAL CUT-OFF SILL LENGTH MAY VARY DUE TO INTERIM STREAM BANK EROSION. SILL MUST KEY INTO EXISTING BANK A MINIMUM OF 3.0'. SEE DETAIL SHEET DE-01.

- NOTES:**
- NOT ALL FURNISHED STONE IS SHOWN IN PLAN VIEW. SEE THE STREAM RESTORATION DETAILS (DE-01 TO 03) AND PROFILE (PR-01) FOR ADDITIONAL INFORMATION.
 - SOIL FABRIC LIFTS SHALL BE USED TO CONSTRUCT ALL FILL SLOPES AS SHOWN ON DETAIL SHEET (DE-01).


TRIBUTARY STABILIZATION (CLASS I RIPRAP)

STA. FROM	STA. TO
200+20.53	200+95.92

WOODY HABITAT FEATURE (WHF)

WHF #	STA. FROM	STA. TO
5	6+79.86	6+87.24
6	8+69.08	8+75.47
7	9+28.28	9+35.57
8	9+54.22	9+60.68

MT CENTURY ENGINEERING
 CONSULTING ENGINEERS - PLANNERS
 10710 GILROY ROAD
 HUNT VALLEY, MARYLAND 21031
 PHONE: (443) 589-2400 FAX: (443) 589-2401



DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND
 Chief, Stormwater Management Division
 DATE: 12/20/19

REVISIONS

NO.	DATE	DESCRIPTION


HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS


D-1158 CHERRYTREE FARM STREAM RESTORATION

FINAL (100%) DESIGN

STREAM RESTORATION PLAN

PROJECT NO: 121104.64
 SCALE: 1" = 20'
 DATE: 12/26/19
 DESIGN: SH
 DRAWN: JT
 CHECK: CL
 DWG NO: SR-02 of SR-02
 SHEET NO: 04 OF 22






ROCK STEP POOL (RSP) SERIES - PLAN VIEW


NOTE: CONTROL POINTS (A) AND (B) REFER TO STRUCTURE TABLES ON SR-01 & SR-02 AND ARE TO DENOTE THE ORIENTATION OF THE ROCK STEP IN PLAN VIEW ONLY. REFER TO THE PROFILE SHEET (PR-01) FOR STATIONS AND ELEVATIONS.

NOT TO SCALE



ROCK STEP POOL (RSP) SERIES - PROFILE VIEW

NOT TO SCALE




ROCK STEP - TYPICAL SECTION A - A'

ROCK STEP STRUCTURE DESIGN PEAK VALUES
 $Q_p = 455.5$ CFS
 $V_p = 10.5$ FT/SEC
 $T_p = 4.3$ lbs/sq ft

NOTE: ROCK STEPS LOCATED IMMEDIATELY DOWNSTREAM OF ARMORED RIFFLES HAVE 6.0' BOTTOM WIDTH. ALL OTHER ROCK STEPS HAVE A 4.0' BOTTOM WIDTH. SEE ROCK-STEP POOL STRUCTURE TABLES ON DWG. NO. SR-01 AND SR-02.


NOT TO SCALE



ROCK STEP-POOL DESIGN PEAK VALUES
 $Q_p = 455.5$ CFS
 $V_p = 4.4$ FT/SEC
 $T_p = 0.6$ lbs/sq ft

POOL - TYPICAL SECTION B - B'


NOT TO SCALE



GLIDE - TYPICAL SECTION C - C'

NOT TO SCALE

CENTURY ENGINEERING
 CONSULTING ENGINEERS - PLANNERS
 10710 GILROY ROAD
 HUNT VALLEY, MARYLAND 21031
 PHONE: (443) 589-2400 FAX: (443) 589-2401



DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND
 Mark A. Schmidt 12/30/19
 CHIEF, STORMWATER MANAGEMENT DIVISION
 I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.
 LICENSE #: 28371 EXPIRES: 01/01/2021

HOWARD COUNTY
 DEPARTMENT OF PUBLIC WORKS

REVISIONS


NO.	DATE	DESCRIPTION

D-1158 CHERRYTREE FARM
 STREAM RESTORATION

FINAL (100%) DESIGN


STREAM RESTORATION DETAIL SHEET

PROJECT NO:	121104.64
SCALE:	N.T.S.
DATE:	12/28/19
DESIGN:	SH
DRAWN:	JT
CHECK:	CL
DWG NO:	DE-01 OF DE-03
SHEET NO:	05 OF 22




BOULDER DROP STRUCTURE (BDS) - PROFILE VIEW (TRIBUTARY 1)

NOT TO SCALE




ARMORED RIFFLE (R) - PROFILE VIEW

NOT TO SCALE




**BOULDER DROP STRUCTURE (BDS) - WEIR / SPLASH STONE SECTION VIEW (TRIBUTARY 1)
BOULDER SILL - SECTION VIEW (TRIBUTARY 2)**

NOT TO SCALE



ARMORED RIFFLE (R) - SECTION VIEW


NOT TO SCALE



BOULDER SILL - PROFILE VIEW (TRIBUTARY 2)

NOT TO SCALE



NOTE: SEE SECTION VIEW ABOVE ON THIS DETAIL SHEET FOR ADDITIONAL INFORMATION.



TYPICAL TRIBUTARY STABILIZATION - SECTION VIEW

NOT TO SCALE

<p>CENTURY ENGINEERING CONSULTING ENGINEERS - PLANNERS 10710 GILROY ROAD HUNT VALLEY, MARYLAND 21031 PHONE: (443) 589-2400 FAX: (443) 589-2401</p>	<p>MARK L. RICHMOND CHIEF, STORMWATER MANAGEMENT DIVISION DATE: 12/30/19</p>	<p>DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND</p>		<p>HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS</p>		<p>PROJECT NO.: 121104.64 SCALE: N.T.S. DATE: 12/28/19 DESIGNER: SH DRAWN: JT CHECK: CL DWG NO.: DE-02 OF DE-03 SHEET NO.: 06 OF 22</p>						
		<p>REVISIONS</p> <table border="1"> <thead> <tr> <th>NO.</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>		NO.	DATE		DESCRIPTION				<p>D-1158 CHERRYTREE FARM STREAM RESTORATION</p>	
		NO.	DATE	DESCRIPTION								
<p>I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.</p>		<p>FINAL (100%) DESIGN</p>										
<p>LICENSE #: 28371 EXPIRES: 01/01/2021</p>		<p>STREAM RESTORATION DETAIL SHEET</p>										



ANCHOR STAKE DETAIL
NOT TO SCALE
NOTE: ANCHOR STAKES SHALL BE TAPERED TWO FOOT LONG WOODEN STAKES CONSISTING OF STANDARD 2" X 4" WOODEN BOARDS CUT DIAGONALLY.

POOL PAVEMENT	
CLASS 0	50%
CLASS I	50%

RIFFLE BED MATERIAL	
CLASS I	40%
CLASS II	60%

NOTE: ALL POOL PAVEMENT AND RIFFLE BED MATERIAL TO BE CHOKED WITH FURNISHED SILT AND GRAVEL TO ENSURE SURFACE FLOW.

ANGULAR BOULDER				
	A AXIS (LONG)	B AXIS (INTERMEDIATE)	C AXIS (SHORT)	WEIGHT
MINIMUM SIZE	2.5 FT.	1.5 FT.	1.0 FT.	600 LBS.
MAXIMUM SIZE	3.5 FT.	2.5 FT.	2.0 FT.	2800 LBS.

MD SHA STANDARD RIPRAP SIZE CLASSES		
MD SHA RIPRAP	D ₅₀	D ₁₀₀
CLASS 0	5.8 in.	8.7 in.
CLASS I	9.5 in.	15 in.
CLASS II	16 in.	24 in.

SILT AND GRAVEL	
% PARTICLE SIZE LESS THAN	PARTICLE DIAMETER PASSING THROUGH SIEVE (IN) OR SIEVE NO.
100	2.5 in.
85	1 in.
50	0.5 in.
30	No. 40
16	No. 200

FURNISHED STONE NOTES:

- STONE MUST MEET THE ABOVE REQUIREMENTS AND BE APPROVED BY THE ENGINEER.
- STONE USED AS CLASS I OR II RIPRAP AND BOULDERS MUST HAVE A MINIMUM DENSITY GREATER THAN 160 LBS/FT³ AND BE BROWN OR GRAY IN COLOR. NO WHITE STONE WILL BE ALLOWED. THE STONE SHALL NOT DISINTEGRATE FROM THE ACTION OF AIR, WATER, OR HANDLING AND PLACING. GRANULAR SEDIMENTARY STONE WILL GENERALLY BE UNACCEPTABLE.
- FURNISHED STONE SHALL BE COMPOSED OF ANGULAR QUARRY STONE. NO ROUND STONE WILL BE PERMITTED.
- CONCRETE WILL NOT BE CONSIDERED AS AN ALTERNATIVE FOR STONE.

STRUCTURE CONSTRUCTION NOTES:

- EXCAVATE THE BED AND BANKS ACCORDING TO THE PLANS TO OBTAIN THE NECESSARY SUBGRADE. PLACE NONWOVEN GEOTEXTILE CLASS SE AS ILLUSTRATED ON THE CONTRACT DOCUMENTS. GEOTEXTILE TORN OR DAMAGED SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE. GEOTEXTILE SHALL BE KEYPED-IN AND TRIMMED TO AVOID EXPOSED EDGES UPON COMPLETION OF CONSTRUCTION.
- RIPPRAP SHALL BE PLACED SO THAT SMALL AND LARGE STONES ARE MIXED TO MINIMIZE VOID SPACE AND PROMOTE INTERLOCKING. SILT AND GRAVEL SHALL BE WASHED INTO THE FURNISHED STONE TO ENSURE ALL INTERSTITIAL VOIDS ARE FILLED AND SURFACE FLOW IS ACHIEVED. DUMPING OF STONE WILL NOT BE PERMITTED.
- PLACED MATERIAL NOT CONFORMING TO THE SPECIFIED LIMITS SHALL BE REMOVED AND REPLACED AS DIRECTED BY THE ENGINEER AT NO ADDITIONAL COST. A DEFINED THALWEG MUST BE ACHIEVED AND APPROVED BY THE ENGINEER.
- IF FOOTER DEPTH CANNOT BE ACHIEVED DUE TO BEDROCK, BOULDERS ARE TO BE PLACED DIRECTLY ON BEDROCK TO MEET PROPOSED GRADE. BEDROCK MUST BE FREE OF DIRT AND GRAVELS PRIOR TO BOULDER PLACEMENT. BOULDERS MUST BE PROPERLY SEATED WITH MINIMAL OPPORTUNITY FOR MOVEMENT.

MATERIAL SPECIFICATIONS

TYPE D SOIL STABILIZATION MATTING

Type D Soil Stabilization Matting: Matting for the bank treatment areas shall consist of a machine produced mat of degradable natural fibers and shall meet the following minimum specifications:

Material:	Woven coir fiber yarn or twine
Thickness:	0.25 in.
Elongation (Dry/Wet):	29%/35%
Weight:	20 oz/SY
Open Area:	50%
Size:	6 ft. wide X 150 ft in length (100 SY per roll)
Flow Velocity:	8 ft./sec.
Life Expectancy:	3 years

COMMON BORROW

COMMON BORROW SHALL BE PER MDOT MSHA 916.01 COMMON BORROW. COMMON BORROW SHALL BE A NATURAL, FRIABLE SUBSURFACE SOIL UNIFORM IN TEXTURE AND FREE FROM ANY PARTS OF NON-NATIVE INVASIVE SPECIES. MATERIAL SHALL BE FREE OF ROOTS, CONCRETE, AND STONES LARGER THAN 3-INCHES. FROZEN MATERIAL WILL NOT BE APPROVED FOR USE AS SUBSOIL.

PLACING, SPREADING, AND COMPACTING COMMON BORROW. COMMON BORROW SHALL BE PLACED, SPREAD, AND COMPACTED IN MAXIMUM LAYERS OF 8 IN. TO PRODUCE A UNIFORM FIRM LAYER OF SUBSOIL. THE COMPLETED WORK SHALL BE IN CONFORMANCE WITH THE THICKNESS, LINES, GRADES, AND ELEVATIONS SPECIFIED IN THE CONTRACT DOCUMENTS. STONES AND OTHER FOREIGN MATERIAL LARGER THAN 4 IN. SHALL BE REMOVED AND DISPOSED BY THE CONTRACTOR. SLOPES 4:1 TO 2:1 SHALL BE TRACKED WITH CLEATED TRACT TYPE EQUIPMENT OPERATING PERPENDICULAR TO THE SLOPE.

TOPSOIL

TOPSOIL SHALL BE PER MDOT SHA 920.01.02 FURNISHED TOPSOIL.

NOTE: ALL REFERENCES TO MDOT SHA REFER TO THE MD SHA STANDARDS AND SPECIFICATIONS FOR CONSTRUCTION MATERIALS, 2017, AND ALL SUBSEQUENT REVISIONS.

CLAY CHANNEL BLOCK


CLAY CHANNEL BLOCK MATERIAL MUST BE UNIFIED SOIL CLASSIFICATION SC OR CL-ML AND SHALL PASS A MINIMUM OF 35% COMPONENTS THROUGH THE #20 SIEVE.

PLACE CLAY CHANNEL BLOCK MATERIAL IN MAXIMUM 8-INCH THICK PRE-COMPACTION LAYERS. EACH LAYER OF FILL SHALL BE COMPACTED WITH CONSTRUCTION EQUIPMENT, ROLLERS, OR HAND TAMPERS TO ENSURE MAXIMUM COMPACTION AND MINIMUM PERMEABILITY AND WILL BE APPROVED BY THE ENGINEER.

GEOTEXTILE


MARYLAND APPLICATION CLASS	TYPE OF GEOTEXTILE	GRAB STRENGTH lb	PUNCTURE STRENGTH lb	PERMITTIVITY sec	APPARENT OPENING SIZE, MAX mm	TRAPEZOID TEAR STRENGTH (MD***) lb	
		D 4632	D 6241	D4491	D 4751	D 4533	
SD	TYPE I	NONWOVEN	160	310	0.50	0.43	55
		WOVEN, MONOFILAMENT	250	495	0.50	0.43	90
	TYPE II	NONWOVEN	160	310	0.20	0.25	55
		WOVEN, MONOFILAMENT	250	495	0.20	0.25	90
PE	TYPE I	NONWOVEN	200	430	0.70	0.43	80
		WOVEN, MONOFILAMENT	250	620	0.70	0.43	90
	TYPE II	NONWOVEN	200	310	0.20	0.25	55
		WOVEN, MONOFILAMENT	250	495	0.20	0.25	90
	TYPE III	NONWOVEN	200	220	0.10	0.22	40
		WOVEN, MONOFILAMENT	250	370	0.10	0.22	70
SE	NONWOVEN	160	310	0.20	0.30	80	
ST	WOVEN	250	495	0.20	0.30	90	
F	WOVEN	300*	600	0.05	0.15**	110	
E	NONWOVEN	200	450	0.05	0.60	75	
	WOVEN, MONOFILAMENT	200	450	1.1	0.21	80	
	WOVEN, MONOFILAMENT	370	900	0.28	0.21	100	

NOTE 1: ALL PROPERTY VALUES IN THE ABOVE TABLE ARE BASED ON MINIMUM AVERAGE ROLL VALUES IN THE WEAKEST PRINCIPLE DIRECTION EXCEPT FOR APPARENT OPENING SIZE.
NOTE 2: THE ULTRAVIOLET STABILITY SHALL BE 50 PERCENT AFTER 500 HRS OF EXPOSURE FOR ALL CLASSES, EXCEPT CLASS F, WHICH SHALL BE 70 PERCENT (D 4355).
*15% ELONGATION FOR SILT FENCE AND MONOFILAMENT WOVEN GEOTEXTILE IN MACHINE DIRECTION
**THIS IS A MINIMUM APPARENT OPENING SIZE, NOT A MAXIMUM.
***MACHINE DIRECTION




SOIL FABRIC LIFTS - TYPICAL SECTION VIEW

- NOT TO SCALE
- SOIL FABRIC LIFT NOTES:
- SOIL FABRIC LIFTS ARE TO BE USED TO CONSTRUCT ALL FILL SLOPES.
 - REFER TO THE PLAN VIEW SHOWN ON SHEETS SR-01 & 02 FOR LOCATIONS OF POOL PAVEMENT, CUT-OFF SILLS, AND RIFFLE BED MATERIAL. REFER TO THE DETAILS SHOWN ON SHEETS DE-01 & 02 FOR INFORMATION REGARDING THE ROCK-STEP POOL SERIES AND ARMORED RIFFLE CONSTRUCTION.
 - REFER TO THE PLAN VIEW SHOWN ON SHEETS SR-01 & 02 AND THE CROSS-SECTIONS SHOWN ON SHEETS CS-01 TO CS-04 FOR PROPOSED GRADING AND TIE-INS.
 - SOIL FABRIC LIFT CONSTRUCTION IS TO BE CONSIDERED INCIDENTAL TO THE UNIT PRICE PER SQUARE YARD OF NEDIA KOIRWRAP 1000 MATTING.




CLAY CHANNEL BLOCK (CCB) - PLAN VIEW

NOTE: SEE CLAY CHANNEL BLOCK CROSS-SECTION DETAILS ON THIS SHEET FOR ADDITIONAL INFORMATION REGARDING SUBGRADE CONSTRUCTION.




CLAY CHANNEL BLOCK (CCB) - CROSS SECTION A-A'

NOT TO SCALE



CLAY CHANNEL BLOCK (CCB) - CROSS SECTION B-B'

NOT TO SCALE




Nedia KoirWrap™ 1000


Nedia KoirWrap™ 1000 is a double layered biodegradable erosion control fabric made up of an outer layer of high strength coir fabric and an inner layer of lightweight jute fabric tied together at regular intervals. Ideal for fabric encapsulated soil lifts; this product effectively replaces the traditional use of a coir fiber matting in combination with a non-woven coir blanket.

Property	Test Method	Typical Value	
		English Units	Metric Units
Thickness	ASTM D 5199	0.35 in	0.90 cm
Mass per unit area	ASTM D 5261	33.3 oz/sq.yd	1130 g/sq.m
Wide Width Tensile Strength MD x TD (Primary Layer)	ASTM D 4595	1008 x 936 lbs/ft	14.7 x 13.7 kNm
Maximum Elongation MD x TD (Primary Layer)	ASTM D 4595	30% x 26%	
Wide Width Tensile Strength MD x TD (Secondary Layer)	ASTM D 4595	612 x 468 lbs/ft	8.94 x 6.83 kNm
Maximum Elongation MD x TD (Secondary Layer)	ASTM D 4595	8% x 9%	
Puncture Strength (Secondary Layer)	GRI GS1	553 lbs	2,461 N
Flexural Rigidity (Stiffness)	ASTM D 1388	0.692 x 0.690 oz-in	49.8 x 49.7 g-cm
Water Absorption	ASTM D 1117	146%	
Shear Stress (Recommended)	Flume Test	4.5 paf	215 Pa
Water Velocity (Recommended)	Flume Test	12 ft./sec	3.7 m/sec
Functional Longevity	Observed	3 to 5 years	
Permittivity	ASTM D 4491	3.07/sec	
Permeability	ASTM D 4491	1.03 in/sec	2.61 cm/sec
Flow Rate	ASTM D 4491	229 gal/min/sq.ft	9.36 cu.m/min/sq.m

Standard Roll Size: 13.1' x 83' (4m x 25m) - 120 syroll



CENTURY ENGINEERING
CONSULTING ENGINEERS - PLANNERS
10710 GILROY ROAD
HUNT VALLEY, MARYLAND 21031
PHONE: (443) 589-2400 FAX: (443) 589-2401



DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND
CHIEF, STORMWATER MANAGEMENT DIVISION
DATE: 12/30/19
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.
LICENSE #: 28371 EXPIRES: 01/01/2021





HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

REVISIONS	
NO.	DATE


D-1158 CHERRYTREE FARM STREAM RESTORATION
FINAL (100%) DESIGN
STREAM RESTORATION DETAIL SHEET

PROJECT NO:	121104.64
SCALE:	N.T.S.
DATE:	12/26/19
DESIGN:	SH
DRAWN:	JT
CHECK:	CL
DWG NO:	DE-03 OF DE-03
SHEET NO:	07 OF 22

CHERRYTREE MAINSTEM












NOTE: NOT ALL STRUCTURES AND MATERIALS ARE SHOWN IN PROFILE VIEW. SEE THE STREAM RESTORATION PLAN SHEETS (SR-01 TO 02), DETAIL SHEETS (DE-01 TO 03), AND CROSS-SECTION SHEETS (CS-01 TO 04) FOR INFORMATION REGARDING CLAY CHANNEL BLOCKS AND WOODY HABITAT FEATURES




<p>CENTURY ENGINEERING CONSULTING ENGINEERS - PLANNERS 10710 GILROY ROAD HUNT VALLEY, MARYLAND 21031 PHONE: (443) 589-2400 FAX: (443) 589-2401</p>		DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND CHIEF, STORMWATER MANAGEMENT DIVISION		REVISIONS		PROJECT NO: 121104.04 SCALE: 1" = 20' DATE: 12/26/19 DESIGN: SH DRAWN: JT CHECK: CL DWG NO: PR-01 of PR-01 SHEET NO: 08 of 22
		DATE: 12/30/19	NO. DATE DESCRIPTION	D-1158 CHERRYTREE FARM STREAM RESTORATION FINAL (100%) DESIGN STREAM RESTORATION PROFILE SHEET		

MAINSTEM



- NOTES
- 1) ONLY FURNISHED STONE IS SHOWN IN CROSS-SECTIONS. REFER TO STREAM RESTORATION PLAN SHEETS AND DETAIL SHEETS FOR INFORMATION REGARDING TOPSOIL, CLAY CHANNEL BLOCK, SOIL FABRIC LIFTS, WOODY HABITAT FEATURES, GEOTEXTILE PLACEMENT AND EXTENTS.
 - 2) SOIL FABRIC LIFTS ARE TO BE USED TO CONSTRUCT ALL FILL SLOPES. REFER TO DE-01 FOR CONSTRUCTION INFORMATION

CENTURY ENGINEERING
 CONSULTING ENGINEERS - PLANNERS
 10710 GILROY ROAD
 HUNT VALLEY, MARYLAND 21031
 PHONE: (443) 589-2400 FAX: (443) 589-2401



DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND
 Mark S. Richmond 12/30/19
 CHIEF, STORMWATER MANAGEMENT DIVISION DATE

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.
 LICENSE #: 28371 EXPIRES: 01/01/2021

HOWARD COUNTY
 DEPARTMENT OF PUBLIC WORKS

REVISIONS		
NO.	DATE	DESCRIPTION












D-1158 CHERRYTREE FARM
 STREAM RESTORATION

FINAL (100%) DESIGN

STREAM RESTORATION
 CROSS-SECTION SHEET

PROJECT NO.: 121104 64
 SCALE: AS NOTED DATE: 12/26/19
 DESIGN: SH DRAWN: JT CHECK: CL
 DWG NO.: CS-01 OF CS-04
 SHEET NO.: 09 OF 22

MAINSTEM



NOTES
 1) ONLY FURNISHED STONE IS SHOWN IN CROSS-SECTIONS. REFER TO STREAM RESTORATION PLAN SHEETS AND DETAIL SHEETS FOR INFORMATION REGARDING TOPSOIL, CLAY CHANNEL BLOCK, SOIL FABRIC LIFTS, WOODY HABITAT FEATURES, GEOTEXTILE PLACEMENT AND EXTENTS.
 2) SOIL FABRIC LIFTS ARE TO BE USED TO CONSTRUCT ALL FILL SLOPES. REFER TO DE-01 FOR CONSTRUCTION INFORMATION

CENTURY ENGINEERS
 CONSULTING ENGINEERS - PLANNERS
 10710 GILROY ROAD
 HUNT VALLEY, MARYLAND 21031
 PHONE: (443) 589-2400 FAX: (443) 589-2401







DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND
 Chief, Stormwater Management Division
 Mark L. Richmond
 12/30/19
 I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.
 LICENSE #: 28371 EXPIRES: 01/01/2021

REVISIONS		
NO.	DATE	DESCRIPTION

PROJECT NO: 121104.64
 SCALE: AS NOTED DATE: 12/28/19
 DESIGNER: SH DRAWN: JT CHECKED: CL
 DWG NO: CS-02 OF CS-04
 SHEET NO: 10 OF 22

HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
D-1158 CHERRYTREE FARM STREAM RESTORATION
FINAL (100%) DESIGN
STREAM RESTORATION CROSS-SECTION SHEET




MAINSTEM







- NOTES
- ONLY FURNISHED STONE IS SHOWN IN CROSS-SECTIONS. REFER TO STREAM RESTORATION PLAN SHEETS AND DETAIL SHEETS FOR INFORMATION REGARDING TOPSOIL, CLAY CHANNEL BLOCK, SOIL FABRIC LIFTS, WOODY HABITAT FEATURES, GEOTEXTILE PLACEMENT AND EXTENTS.
 - SOIL FABRIC LIFTS ARE TO BE USED TO CONSTRUCT ALL FILL SLOPES. REFER TO DE-01 FOR CONSTRUCTION INFORMATION

<p>CENTURY ENGINEERING CONSULTING ENGINEERS - PLANNERS 10710 GILROY ROAD HUNT VALLEY, MARYLAND 21031 PHONE: (443) 589-2400 FAX: (443) 589-2401</p>	<p>12/26/2019</p>	DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND CHIEF, STORMWATER MANAGEMENT DIVISION <i>Mark Richmond</i> 12/30/19 DATE		HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS					
		REVISIONS <table border="1"> <thead> <tr> <th>NO.</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>		NO.	DATE	DESCRIPTION			
NO.	DATE	DESCRIPTION							
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE #: 28371 EXPIRES: 01/01/2021				D-1158 CHERRYTREE FARM STREAM RESTORATION FINAL (100%) DESIGN STREAM RESTORATION CROSS-SECTION SHEET					

TRIBUTARY 1




TRIBUTARY 2



- NOTES
- ONLY FURNISHED STONE IS SHOWN IN CROSS-SECTIONS. REFER TO STREAM RESTORATION PLAN SHEETS AND DETAIL SHEETS FOR INFORMATION REGARDING TOPSOIL, CLAY CHANNEL BLOCK, SOIL FABRIC LIFTS, WOODY HABITAT FEATURES, GEOTEXTILE PLACEMENT AND EXTENTS.
 - SOIL FABRIC LIFTS ARE TO BE USED TO CONSTRUCT ALL FILL SLOPES. REFER TO DE-01 FOR CONSTRUCTION INFORMATION

MT CENTURY
ENGINEERING
CONSULTING ENGINEERS - PLANNERS
10710 GILROY ROAD
HUNT VALLEY, MARYLAND 21031
PHONE: (443) 589-2400 FAX: (443) 589-2401



DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND
Mark Richmond 12/30/19
CHIEF, STORMWATER MANAGEMENT DIVISION DATE
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.
LICENSE #: 28371 EXPIRES: 01/01/2021

HOWARD COUNTY
DEPARTMENT OF PUBLIC WORKS


REVISIONS

NO.	DATE	DESCRIPTION

D-1158 CHERRYTREE FARM
STREAM RESTORATION

FINAL (100%) DESIGN
STREAM RESTORATION
CROSS-SECTION SHEET

PROJECT NO: 121104.64
SCALE: AS NOTED DATE: 12/26/19
DESIGN: SH DRAWN: JT CHECK: CL
DWG NO: CS-04 OF CS-04
SHEET NO: 12 OF 22



PROPOSED FEATURES LEGEND	
1' MINOR CONTOUR	305
5' MAJOR CONTOUR	
WOODY HABITAT FEATURE (WHF)	
BOULDER DROP STRUCTURE (BDS)	
ROCK STEP STRUCTURE (RSS)	
ARMORED RIFFLE (R)	
CLASS 0 RIPRAP CHOKED WITH SILT AND GRAVEL	
CLAY CHANNEL BLOCK (CCB)	

EXISTING FEATURES LEGEND	
EX. BUILDING	
EX. NONTIDAL WETLAND	
EX. WATERS OF THE U.S.	
EX. FENCE	
EX. PROPERTY BOUNDARY	
EX. EASEMENT	
EX. EDGE OF PAVEMENT	
EX. GAS MAIN	
EX. TREE LINE	
EX. CONCRETE DEBRIS	
EX. RIPRAP	
EX. CONCRETE MONUMENT	
EX. TREE	
EX. TRAVERSE POINT	
EX. STORMDRAIN	
EX. 1' MINOR CONTOUR	305
EX. 5' MAJOR CONTOUR	305

EROSION & SEDIMENT CONTROL LEGEND	
LIMIT OF DISTURBANCE	LOD
STREAM BUFFER	SB
WATERS OF THE U.S.	WUS
100 YR FLOODPLAIN	FP
SOIL BOUNDARY	
CLEAN WATER / SEDIMENT DIKE	
DIVERSION HOSE	
OUTLET PROTECTION	
FILTER BAG	FB
PUMP	P
TEMPORARY ACCESS BRIDGE	
TIMBER MAT	
STABILIZED CONSTRUCTION ENTRANCE	
TREE TO BE REMOVED	
PROTECTED EXISTING TREE	
SLOPES > 15%	

STABILIZATION NOTE:
ALL DISTURBED SLOPES GREATER THAN 4:1 AND SENSITIVE AREAS (STREAM BUFFER, FLOODPLAIN, STEEP (>20%) SLOPES, HIGHLY ERODIBLE SOILS) MUST BE PERMANENTLY STABILIZED WITH SOIL STABILIZATION MATTING.


20' 0 20' 40'
ORIGINAL SCALE: 1"=20'

THIS PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

[Signature] 12/20
DATE

- NOTES:
- 1) NOT ALL FURNISHED STONE IS SHOWN IN PLAN VIEW. SEE THE STREAM RESTORATION DETAILS AND PROFILE FOR ADDITIONAL INFORMATION.
 - 2) REMOVE THE TEMPORARY MULCH ACCESS ROAD AS NECESSARY TO COMPLETE GRADING OPERATIONS. THE CONTRACTOR MUST ENSURE POSITIVE DRAINAGE FROM THE PROPOSED CHANNEL TO THE EXISTING CHANNEL AT THE END OF THE WORKING DAY. THIS SHALL BE DONE THROUGH TEMPORARY GRADING AND STABILIZATION WITH CLASS 1 RIPRAP, EXCEPT WHERE EROSION & SEDIMENT CONTROL INSPECTOR ALLOWS THE USE OF TEMPORARY SOIL STABILIZATION MATTING.
 - 3) AT THE END OF EACH WORK DAY THE CONTRACTOR SHALL STABILIZE ANY DISTURBED AREA WITHIN THE LOD NOT DIRECTED TO AN APPROVED SEDIMENT CONTROL DEVICE AND REMOVE SANDBAG DIVERSION AND PUMP AROUND PRACTICE. THE WORK AREA SHALL BE DEWATERED UTILIZING DEWATERING PUMPS AND PORTABLE SEDIMENT TANK/FILTER BAG OR MDE APPROVED SUBSTITUTE.

CENTURY ENGINEERING
CONSULTING ENGINEERS - PLANNERS
10710 GILROY ROAD
HUNT VALLEY, MARYLAND 21031
PHONE: (443) 589-2400 FAX: (443) 589-2401



DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND
Mark S. Kichman 12/30/19
CHIEF, STORMWATER MANAGEMENT DIVISION DATE

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.
LICENSE # 28371 EXPIRES 01/01/2021

HOWARD COUNTY
DEPARTMENT OF PUBLIC WORKS


REVISIONS		
NO.	DATE	DESCRIPTION

D-1158 CHERRYTREE FARM
STREAM RESTORATION


FINAL (100%) DESIGN

EROSION AND SEDIMENT CONTROL PLAN

PROJECT NO: 121104 64
SCALE: 1" = 20' DATE: 12/28/19
DESIGN: SH DRAWN: JT CHECK: CL
DWG NO: SC-01 of SC-05
SHEET NO: 13 OF 22



EROSION & SEDIMENT CONTROL LEGEND		PROPOSED FEATURES LEGEND	
LIMIT OF DISTURBANCE	LOD	1' MINOR CONTOUR	305
STREAM BUFFER	SB	5' MAJOR CONTOUR	305
WATERS OF THE U.S.	WUS	WOODY HABITAT FEATURE (WHF)	
100 YR FLOODPLAIN	FP	BOULDER SILL	
SOIL BOUNDARY		ROCK STEP-POOL STRUCTURE (RSP)	
CLEAN WATER / SEDIMENT DIKE		ARMORED RIFLE (R)	
DIVERSION HOSE		TRIBUTARY STABILIZATION (CLASS I RIPRAP CHOKED WITH SILT AND GRAVEL)	
OUTLET PROTECTION		CLAY CHANNEL BLOCK (CCB)	
FILTER BAG	FB	EXISTING FEATURES LEGEND	
PUMP	P	EX. BUILDING	
TEMPORARY ACCESS BRIDGE		EX. NONTIDAL WETLAND	
TIMBER MAT		EX. FENCE	
STABILIZED CONSTRUCTION ENTRANCE		EX. WATERS OF THE U.S.	
TREE TO BE REMOVED		EX. PROPERTY BOUNDARY	
PROTECTED EXISTING TREE		EX. EASEMENT	
SLOPES > 15%		EX. EDGE OF PAVEMENT	
		EX. GAS MAIN	
		EX. TREETRUNK	
		EX. CONCRETE DEBRIS	
		EX. RIPRAP	
		EX. CONCRETE MONUMENT	
		EX. TREE	
		EX. TRAVERSE POINT	
		EX. STORMDRAIN	
		EX. 1' MINOR CONTOUR	
		EX. 5' MAJOR CONTOUR	



STOCKPILE NOTE: CONTRACTOR TO CONTACT SCOTT MOORE, COLONIAL PIPELINE (443-821-1797) TO MARK LOCATION OF GAS LINE PRIOR TO INSTALLATION OF SEDIMENT CONTROLS FOR STOCKPILE AREA.

INSET SCALE:
1" = 30'


THIS PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

[Signature]
HOWARD SOIL CONSERVATION DISTRICT

1/2/20
DATE

- NOTES:
- NOT ALL FURNISHED STONE IS SHOWN IN PLAN VIEW. SEE THE STREAM RESTORATION DETAILS AND PROFILE FOR ADDITIONAL INFORMATION.
 - REMOVE THE TEMPORARY MULCH ACCESS ROAD AS NECESSARY TO COMPLETE GRADING OPERATIONS.
 - THE CONTRACTOR MUST ENSURE POSITIVE DRAINAGE FROM THE PROPOSED CHANNEL TO THE EXISTING CHANNEL AT THE END OF THE WORKING DAY. THIS SHALL BE DONE THROUGH TEMPORARY GRADING AND STABILIZATION WITH CLASS I RIPRAP, EXCEPT WHERE EROSION & SEDIMENT CONTROL INSPECTOR ALLOWS THE USE OF TEMPORARY SOIL STABILIZATION.
 - AT THE END OF EACH WORK DAY THE CONTRACTOR SHALL STABILIZE ANY DISTURBED AREA WITHIN THE LOD NOT DIRECTED TO AN APPROVED SEDIMENT CONTROL DEVICE AND REMOVE SANDBAG DIVERSION AND PUMP AROUND PRACTICE. THE WORK AREA SHALL BE DEWATERED UTILIZING DEWATERING PUMPS AND PORTABLE SEDIMENT TANK/FILTER BAG OR MDE APPROVED SUBSTITUTE.

CENTURY ENGINEERING
CONSULTING ENGINEERS - PLANNERS
10710 GILROY ROAD
HUNT VALLEY, MARYLAND 21031
PHONE: (443) 589-2400 FAX: (443) 589-2401



DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND

Mark S. Richmond
12/30/19
CHIEF, STORMWATER MANAGEMENT DIVISION

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.

LICENSE # 28371 EXPIRES 01/01/2021


REVISIONS		
NO.	DATE	DESCRIPTION

HOWARD COUNTY
DEPARTMENT OF PUBLIC WORKS


**D-1158 CHERRYTREE FARM
STREAM RESTORATION**

FINAL (100%) DESIGN
EROSION AND SEDIMENT CONTROL PLAN


PROJECT NO: 121104 64
SCALE: 1" = 20'
DATE: 12/26/19
DESIGN: SH DRAWN: JT CHECK: CL
DWG NO: SC-02 OF SC-05
SHEET NO: 14 OF 22



SANDBAG DIVERSION, WITH PUMP AROUND PRACTICE - PLAN VIEW



SANDBAG DIVERSION, WITH PUMP AROUND PRACTICE - TYPICAL CROSS SECTION



OUTLET PROTECTION (OP)

MGWC 1.2: PUMP-AROUND PRACTICE
 DESCRIPTION THE WORK SHALL CONSIST OF INSTALLING A TEMPORARY PUMP AROUND AND SUPPORTING MEASURES TO DIVERT FLOW AROUND INSTREAM CONSTRUCTION SITES.
 IMPLEMENTATION SEQUENCE SEDIMENT CONTROL MEASURES, PUMP-AROUND PRACTICES, AND ASSOCIATED CHANNEL AND BANK CONSTRUCTION SHALL BE COMPLETED IN THE FOLLOWING SEQUENCE (REFER TO DETAIL 1.2):

- CONSTRUCTION ACTIVITIES INCLUDING THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES SHALL NOT BEGIN UNTIL ALL NECESSARY EASEMENTS AND/OR RIGHT-OF-WAYS HAVE BEEN ACQUIRED. ALL EXISTING UTILITIES SHALL BE MARKED IN THE FIELD PRIOR TO CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE TO EXISTING UTILITIES THAT MAY RESULT FROM CONSTRUCTION AND SHALL REPAIR THE DAMAGE AT HIS/HER OWN EXPENSE TO THE COUNTY'S OR UTILITY COMPANY'S SATISFACTION.
- THE CONTRACTOR SHALL NOTIFY THE MARYLAND DEPARTMENT OF THE ENVIRONMENT OR WMA SEDIMENT CONTROL INSPECTOR AT LEAST 5 DAYS BEFORE BEGINNING CONSTRUCTION. ADDITIONALLY, THE CONTRACTOR SHALL INFORM THE LOCAL ENVIRONMENTAL PROTECTION AND RESOURCE MANAGEMENT INSPECTION AND ENFORCEMENT DIVISION AND THE PROVIDER OF LOCAL UTILITIES A MINIMUM OF 48 HOURS BEFORE STARTING CONSTRUCTION.
- THE CONTRACTOR SHALL CONDUCT A PRE-CONSTRUCTION MEETING ON SITE WITH THE WMA SEDIMENT CONTROL INSPECTOR, THE COUNTY PROJECT MANAGER, AND THE ENGINEER TO REVIEW LIMITS OF DISTURBANCE, EROSION AND SEDIMENT CONTROL REQUIREMENTS, AND THE SEQUENCE OF CONSTRUCTION. THE CONTRACTOR SHALL STAKE OUT ALL LIMITS OF DISTURBANCE PRIOR TO THE PRE-CONSTRUCTION MEETING SO THEY MAY BE REVIEWED. THE PARTICIPANTS WILL ALSO DESIGNATE THE CONTRACTOR'S STAGING AREAS AND FLAG ALL TREES WITHIN THE LIMIT OF DISTURBANCE WHICH WILL BE REMOVED FOR CONSTRUCTION ACCESS. TREES SHALL NOT BE REMOVED WITHIN THE LIMIT OF DISTURBANCE WITHOUT APPROVAL FROM THE WMA OR LOCAL AUTHORITY.
- CONSTRUCTION SHALL NOT BEGIN UNTIL ALL SEDIMENT AND EROSION CONTROL MEASURES HAVE BEEN INSTALLED AND APPROVED BY THE ENGINEER AND THE SEDIMENT CONTROL INSPECTOR. THE CONTRACTOR SHALL STAY WITHIN THE LIMITS OF THE DISTURBANCE AS SHOWN ON THE PLANS AND MINIMIZE DISTURBANCE WITHIN THE WORK AREA WHENEVER POSSIBLE.
- UPON INSTALLATION OF ALL SEDIMENT CONTROL MEASURES AND APPROVAL BY THE SEDIMENT CONTROL INSPECTOR AND THE LOCAL ENVIRONMENTAL PROTECTION AND RESOURCE MANAGEMENT INSPECTION AND ENFORCEMENT DIVISION, THE CONTRACTOR SHALL BEGIN WORK AT THE UPSTREAM SECTION AND PROCEED DOWNSTREAM BEGINNING WITH THE ESTABLISHMENT OF STABILIZED CONSTRUCTION ENTRANCES. IN SOME CASES, WORK MAY BEGIN DOWNSTREAM IF APPROPRIATE. THE SEQUENCE OF CONSTRUCTION MUST BE FOLLOWED UNLESS THE CONTRACTOR GETS WRITTEN APPROVAL FOR DEVIATIONS FROM THE WMA OR LOCAL AUTHORITY. THE CONTRACTOR SHALL ONLY BEGIN WORK IN AN AREA WHICH CAN BE COMPLETED BY THE END OF THE DAY INCLUDING GRADING ADJACENT TO THE CHANNEL. AT THE END OF EACH WORK DAY, THE WORK AREA MUST BE STABILIZED AND THE PUMP AROUND REMOVED FROM THE CHANNEL. WORK SHALL NOT BE CONDUCTED IN THE CHANNEL DURING RAIN EVENTS.
- SANDBAG DIKES SHALL BE SITUATED AT THE UPSTREAM AND DOWNSTREAM ENDS OF THE WORK AREA AS SHOWN ON THE PLANS, AND STREAM FLOW SHALL BE PUMPED AROUND THE WORK AREA. THE PUMP SHALL DISCHARGE ONTO A STABLE VELOCITY DISSIPATER MADE OF RIPRAP OR SANDBAGS. TEMPORARY MEASURE FOR DEWATERING INCHANNEL CONSTRUCTION SITES.
- WATER FROM THE WORK AREA SHALL BE PUMPED TO A SEDIMENT FILTERING MEASURE SUCH AS A DEWATERING BASIN, SEDIMENT BAG, OR OTHER APPROVED SOURCE. THE MEASURE SHALL BE LOCATED SUCH THAT THE WATER DRAINS BACK INTO THE CHANNEL BELOW THE DOWNSTREAM SANDBAG DIKE.
- TRAVERSING A CHANNEL REACH WITH EQUIPMENT WITHIN THE WORK AREA WHERE NO WORK IS PROPOSED SHALL BE AVOIDED. IF EQUIPMENT HAS TO TRAVERSE SUCH A REACH FOR ACCESS TO ANOTHER AREA, THEN TIMBER MATS OR SIMILAR MEASURES SHALL BE USED TO MINIMIZE DISTURBANCE TO THE CHANNEL. TEMPORARY STREAM CROSSINGS SHALL BE USED ONLY WHEN NECESSARY AND SHALL BE USED ONLY WHERE NOTED ON THE PLANS OR SPECIFIED. (SEE SECTION 4, STREAM CROSSINGS, MARYLAND GUIDELINES TO WATERWAY CONSTRUCTION).
- ALL STREAM RESTORATION MEASURES SHALL BE INSTALLED AS INDICATED BY THE PLANS AND ALL BANKS GRADED IN ACCORDANCE WITH THE GRADING PLANS AND TYPICAL CROSS-SECTIONS. ALL GRADING MUST BE STABILIZED AT THE END OF EACH DAY WITH SEED AND MULCH OR SEED AND MATTING AS SPECIFIED ON THE PLANS.
- AFTER AN AREA IS COMPLETED AND STABILIZED, THE CLEAN WATER DIKE SHALL BE REMOVED. AFTER THE FIRST SEDIMENT FLUSH, A NEW CLEAN WATER DIKE SHALL BE ESTABLISHED UPSTREAM FROM THE OLD SEDIMENT DIKE. FINALLY, UPON ESTABLISHMENT OF A NEW SEDIMENT DIKE BELOW THE OLD ONE, THE OLD SEDIMENT DIKE SHALL BE REMOVED.
- A PUMP AROUND MUST BE INSTALLED ON ANY TRIBUTARY OR STORM DRAIN OUTFALL WHICH CONTRIBUTES BASEFLOW TO THE WORK AREA. THIS SHALL BE ACCOMPLISHED BY LOCATING A SANDBAG DIKE AT THE DOWNSTREAM END OF THE TRIBUTARY OR STORM DRAIN OUTFALL AND PUMPING THE STREAM FLOW AROUND THE WORK AREA. THIS WATER SHALL DISCHARGE ONTO THE SAME VELOCITY DISSIPATER USED FOR THE MAIN STEM PUMP AROUND.
- IF A TRIBUTARY IS TO BE RESTORED, CONSTRUCTION SHALL TAKE PLACE ON THE TRIBUTARY BEFORE WORK ON THE MAIN STEM REACHES THE TRIBUTARY CONFLUENCE. CONSTRUCTION IN THE TRIBUTARY, INCLUDING PUMP AROUND PRACTICES, SHALL FOLLOW THE SAME SEQUENCE AS FOR THE MAIN STEM OF THE RIVER OR STREAM. WHEN CONSTRUCTION ON THE TRIBUTARY IS COMPLETED, WORK ON THE MAIN STEM SHALL RESUME. WATER FROM THE TRIBUTARY SHALL CONTINUE TO BE PUMPED AROUND THE WORK AREA IN THE MAIN STEM.
- THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING ACCESS TO AND MAINTAINING ALL EROSION AND SEDIMENT CONTROL DEVICES UNTIL THE SEDIMENT CONTROL INSPECTOR APPROVES THEIR REMOVAL.
- AFTER CONSTRUCTION, ALL DISTURBED AREAS SHALL BE REGRADED AND REVEGETATED AS PER THE PLANTING PLAN.
- IF, IN THE JUDGMENT OF THE ENGINEER, INADEQUATE ENERGY DISSIPATION OR CHANNEL BED EROSION IS OCCURRING, THE CONTRACTOR SHALL BE REQUIRED TO INCREASE THE MATERIAL OR PLACEMENT SIZE OF THE OUTFALL PROTECTION AT THE DIRECTION OF THE ENGINEER.
- THE CONDITION OF THE OUTFALL PROTECTION SANDBAGS IS TO BE CHECKED TWICE PER DAY (START OF WORK DAY AND MID-DAY) TO ENSURE THAT SAND IS NOT ESCAPING BAGS. DAMAGED OR LEAKING BAGS ARE TO BE REMOVED AND REPLACED.
- OUTFALL PROTECTION MATERIALS AND GEOTEXTILE SHALL BE REMOVED FROM THE CHANNEL AT THE COMPLETION OF EACH CONSTRUCTION STAGE.

THIS PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

Sheila Salas 1/2/20
 HOWARD SOIL CONSERVATION DISTRICT DATE

<p>CENTURY ENGINEERING CONSULTING ENGINEERS - PLANNERS 10710 GILROY ROAD HUNT VALLEY, MARYLAND 21031 PHONE: (443) 589-2400 FAX: (443) 589-2401</p>		DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND CHIEF, STORMWATER MANAGEMENT DIVISION		12/30/19		PROJECT NO: 121104.64 SCALE: N.T.S. DATE: 12/28/19 DESIGN: SH DRAWN: JT CHECK: CL DWG NO: SC-05 of SC-05 SHEET NO: 17 of 22					
		DEPARTMENT OF PUBLIC WORKS DEPARTMENT OF PUBLIC WORKS		REVISIONS <table border="1"> <thead> <tr> <th>NO.</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>			NO.	DATE	DESCRIPTION		
NO.	DATE	DESCRIPTION									

SURVEYED TREES DATA TABLE
(TREES ≥ 12" DBH)

Tree #	Species	DBH (in.)	Condition
1	Scarlett oak	25.4	Good
2	Sugar maple	15.5	Good
3	Black walnut	14	Good
4	River birch	20	Good
5	River birch	13.2	Good
6	River birch	16.4	Good
7	Black Willow	13.6	Fair
8	Black Willow	17.5	Fair
9	Tulip Poplar	29	Fair
10	Tulip Poplar	13.2	Good
11	Tulip Poplar	21.1	Good
12	Black walnut	15.4	Fair
13	Tulip Poplar	14.1	Good
14	Tulip Poplar	14	Good
15	Tulip Poplar	15	Good
16	Tulip Poplar	12.4	Good
17	Tulip Poplar	15.6	Good
18	Black walnut	14.6	Good
19	Tulip Poplar	16	Good
28	White Pine	13	Good
29	White Pine	18	Good
30	White Pine	15	Good
31	White Pine	19.7	Good
32	White Pine	20.8	Good
33	White Pine	18.3	Good
34	White Pine	16	Good
35	White Pine	20.5	Good
36	White Pine	12.3	Good
37	White Pine	12.7	Good
38	White Pine	15.6	Good
39	White Pine	13.4	Good
40	White Pine	14.1	Good
41	White Pine	15	Good
42	White Pine	13.8	Good
43	White Pine	16.1	Good
44	White Pine	15.7	Good
45	White Pine	22	Good
46	Tulip Poplar	32.9	Good
47	Tulip Poplar	13.8	Good
48	Tulip Poplar	13.1	Good
49	Tulip Poplar	12.5	Good
51	Tulip Poplar	26.1	Good
50	Tulip Poplar	25.9	Good
52	Mockernut hickory	15.2	Good
53	Tulip Poplar	20.7	Good
54	Tulip Poplar	13.9	Good
57	Tulip Poplar	31.8	Fair
58	Red Maple	14.9	Good
59	Tulip Poplar	19	Good
60	Tulip Poplar	19.9	Good
61	Tulip Poplar	16.1	Good
62	Tulip Poplar	15.3	Good


Tree #	Species	DBH (in.)	Condition
63	Tulip Poplar	12	Good
64	Tulip Poplar	13.5	Good
65	Tulip Poplar	15.8	Good
66	Tulip Poplar	20.9	Good
67	Tulip Poplar	13.1	Good
68	Tulip Poplar	18.8	Good
71	Tulip Poplar	24.5	Good
73	Mockernut Hickory	15.8	Good
74	Tulip Poplar	22.8	Good
75	Tulip Poplar	33.9	Good
77	White Oak	27.6	Good
78	Tulip Poplar	36.1	Good
79	Tulip Poplar	33.8	Good
80	Tulip Poplar	35.9	Fair
81	Tulip Poplar	24.2	Good
82	Tulip Poplar	44.4	Fair
83	Tulip Poplar	32	Fair
85	Northern Red Oak	29.6	Good
86	Northern Red Oak	20.8	Good
87	Tulip Poplar	31.8	Good
88	Tulip Poplar	20.5	Good
89	Northern Red Oak	16.6	Good
90	White Oak	17.9	Good
91	Red Maple	13.7	Good
92	Tulip Poplar	21	Fair
93	Tulip Poplar	23.7	Fair
94	Tulip Poplar	21.7	Poor
96	Tulip Poplar	35.5	Fair
97	Tulip Poplar	18.9	Good
98	White Oak	15.1	Fair
99	Northern Red Oak	23.7	Good
100	Black Oak	16.3	Good
101	Northern Red Oak	19.8	Good
102	Tulip Poplar	26.7	Good
103	Tulip Poplar	30.5	Fair
104	Tulip Poplar	15.2	Fair
105	White Oak	21.2	Fair
106	Tulip Poplar	28.8	Good
107	Tulip Poplar	16.1	Good
108	Tulip Poplar	19	Good
109	Tulip Poplar	20.6	Good
110	Tulip Poplar	39.8	Fair
111	White Oak	15.9	Good
112	Red Maple	24	Fair
113	Red Maple	17.5	Fair
114	Red Maple	14.6	Good
115	Tulip Poplar	33	Fair
116	White Oak	17.8	Fair
117	Tulip Poplar	13.2	Poor
118	Tulip Poplar	22.7	Good
119	White Oak	15.7	Good
120	Mockernut Hickory	16	Good

Tree #	Species	DBH (in.)	Condition
121	White Oak	20	Good
122	Northern Red Oak	25	Good
123	Northern Red Oak	25.2	Good
124	Northern Red Oak	19.8	Good
127	White Oak	25.6	Good
128	White Oak	21.4	Good
129	Red Maple	21.3	Fair
130	Tulip Poplar	40.6	Good
131	White Oak	31	Good
132	Tulip Poplar	23.8	Good
133	Black Walnu	19.9	Good
134	Tulip Poplar	29	Good
135	Tulip Poplar	26.3	Good
138	Mockernut Hickory	14.4	Good
139	Tulip Poplar	25.1	Good
140	Northern Red Oak	23.4	Good
141	White Oak	14.6	Good
142	Tulip Poplar	31.1	Good
143	Mockernut Hickory	14.7	Good
144	Mockernut Hickory	13.7	Good
145	Mockernut Hickory	14.1	Good
146	Red Maple	20.4	Good
148	Northern Red Oak	21.9	Poor
149	Tulip Poplar	221	Poor
150	Tulip Poplar	34	Fair
151	Red Maple	12	Poor
152	Red Maple	19	Poor
153	Tulip Poplar	15.9	Good
155	White Oak	31.5	Good
156	Tulip Poplar	23	Fair
157	Red Maple	17.7	Good
158	Tulip Poplar	20.5	Good
159	Tulip Poplar	14.2	Good
160	Tulip Poplar	17.9	Good
161	Tulip Poplar	25.4	Good
162	Tulip Poplar	17.4	Fair
163	Tulip Poplar	15	Fair
164	Red Maple	22.2	Good
165	Tulip Poplar	18.4	Good
166	Red Maple	27.3	Fair
167	Red Maple	16	Fair
168	Black Cherry	14.1	Good
169	Tulip Poplar	14.2	Good
170	Red Maple	18.5	Good
171	Tulip Poplar	18.5	Good
172	Tulip Poplar	15.8	Good
173	Red Maple	20.8	Fair
174	Tulip Poplar	30.1	Fair
176	Red Maple	15.3	Fair
177	Red Maple	25.1	Fair
179	Tulip Poplar	14	Fair
180	Red Maple	19.2	Fair

Tree #	Species	DBH (in.)	Condition
181	Mockernut Hickory	21.2	Fair
182	Tulip Poplar	12.7	Good
185	White Oak	20.3	Fair
186	Tulip Poplar	17.2	Good
187	Tulip Poplar	23.3	Good
188	Tulip Poplar	13.5	Poor
189	Tulip Poplar	244	Good
190	Red Maple	17	Good
191	Red Maple	16.4	Good
192	Red Maple	14	Good
193	Black Cherry	15	Fair
194	Red Maple	20.6	Good
195	Tulip Poplar	21.2	Good
196	Black Cherry	12.2	Good
197	Tulip Poplar	17.3	Good
198	Tulip Poplar	23.2	Good
199	Red Maple	22.8	Good
200	Tulip Poplar	22.2	Fair
201	Tulip Poplar	18.3	Fair
202	Red Maple	13.6	Fair
202	Black gum	16.1	Fair
203	Tulip Poplar	16.5	Good
204	Red Maple	18.6	Good
205	Red Maple	20	Good
206	Tulip Poplar	20.2	Good
207	Tulip Poplar	13.2	Good
209	White Oak	16.8	Good
211	White Oak	26.5	Fair
212	Black gum	16.1	Fair
213	Tulip Poplar	24.8	Good
214	Tulip Poplar	20	Good
215	Tulip Poplar	20.6	Good
216	Tulip Poplar	20.6	Good
217	Tulip Poplar	20.6	Good
218	Tulip Poplar	17	Good
219	Black Walnu	13.6	Fair
221	Tulip Poplar	20.8	Good
222	Tulip Poplar	16.9	Good
223	Tulip Poplar	22.3	Fair
225	Tulip Poplar	13	Good
226	Tulip Poplar	19.7	Good
227	Black walnu	16.1	Fair
228	Tulip Poplar	38.2	Poor
229	Tulip Poplar	18.6	Good
230	Tulip Poplar	14.2	Good
232	Tulip Poplar	18.5	Good
233	Tulip Poplar	18.5	Good
237	Tulip Poplar	14.8	Good
238	Tulip Poplar	14.8	Good
239	Tulip Poplar	15	Good
240	Tulip Poplar	234	Good
241	Tulip Poplar	15.8	Good

Tree #	Species	DBH (in.)	Condition
245	Tulip Poplar	28.8	Good
248	Tulip Poplar	19.2	Good
249	Tulip Poplar	19.1	Good
250	Tulip Poplar	18.1	Good
251	Tulip Poplar	20.5	Good
252	Red Maple	12.5	Good
253	Tulip Poplar	12.7	Good
254	Tulip Poplar	15.5	Good
259	Tulip Poplar	12.2	Good
260	Tulip Poplar	16	Good
261	Tulip Poplar	17.1	Good
262	Tulip Poplar	20.1	Good
263	Tulip Poplar	14.5	Good
264	Tulip Poplar	15.8	Good
265	Tulip Poplar	18.5	Good
266	Tulip Poplar	20.1	Good
268	Tulip Poplar	20.8	Good
269	Tulip Poplar	21.9	Good
270	Tulip Poplar	17.2	Good
271	Tulip Poplar	19.5	Good
272	Tulip Poplar	19.4	Good
273	Tulip Poplar	12.1	Good
274	Tulip Poplar	14.4	Good
275	Tulip Poplar	22	Good
276	Black walnu	17.4	Poor
277	Tulip Poplar	27.8	Good
278	Tulip Poplar	20.4	Good
279	Tulip Poplar	12.3	Good
280	Tulip Poplar	22.9	Good
281	Tulip Poplar	13.8	Good
282	Tulip Poplar	23.6	Good
283	Tulip Poplar	18.1	Good
284	Tulip Poplar	23	Good
285	Red Maple	13.2	Good
286	Red Maple	13.5	Good
287	Tulip Poplar	14.8	Good
288	Tulip Poplar	16.5	Good
291	Tulip Poplar	15.2	Good
292	Tulip Poplar	19.6	Good
293	Tulip Poplar	18.3	Good
295	Northern Red Oak	31	Good

CENTURY ENGINEERING
CONSULTING ENGINEERS - PLANNERS
10710 GILROY ROAD
HUNT VALLEY, MARYLAND 21031
PHONE: (443) 589-2400 FAX: (443) 589-2401



DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND
M. S. Lockman 12/30/19
CHIEF, STORMWATER MANAGEMENT DIVISION
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.
LICENSE # 28371 EXPIRES: 01/01/2021

REVISIONS		
NO.	DATE	DESCRIPTION


HOWARD COUNTY
DEPARTMENT OF PUBLIC WORKS

**D-1158 CHERRYTREE FARM
STREAM RESTORATION**

FINAL (100%) DESIGN

SURVEYED TREE LIST

PROJECT NO:	121104.64
SCALE:	N.T.S.
DATE:	12/30/19
DESIGNER:	SH
DRAWN:	JT
CHECKER:	CL
DWG NO:	TR-01 OF TR-01
SHEET NO:	18 OF 22




- PROPOSED LANDSCAPE LEGEND**
- HERBACEOUS PLUG PLANTINGS:
1,804 SF / 0.04 AC
*EXTEND FROM THE EDGE OF STONE TO THE TOP OF PROPOSED STREAM BANK.
 - FLOODPLAIN BENCH PLANTINGS:
2,526 SF / 0.06 AC
 - RIPARIAN FOREST PLANTINGS:
20,011 SF / 0.46 AC
 - UPLAND MEADOW SEED ESTABLISHMENT:
11,457 SF / 0.26 AC
- PROPOSED FEATURES LEGEND**
- LIMIT OF DISTURBANCE: LOD
 - 1' MINOR CONTOUR: 1' - 305
 - 5' MAJOR CONTOUR: 5' - 305
 - WOODY HABITAT FEATURE (WHF)
 - BOULDER DROP STRUCTURE (BDS)
 - ROCK STEP STRUCTURE (RSS)
 - ARMORED RIFFLE (R)
 - CLASS 0 RIPRAP CHOKED WITH SILT AND GRAVEL
 - CLAY CHANNEL BLOCK (CCB)
- EXISTING FEATURES LEGEND**
- EX. BUILDING
 - EX. NONTIDAL WETLAND
 - EX. WATERS OF THE U.S.
 - EX. FENCE
 - EX. PROPERTY BOUNDARY
 - EX. EASEMENT
 - EX. EDGE OF PAVEMENT
 - EX. GAS MAIN
 - EX. TREELINE
 - EX. CONCRETE DEBRIS
 - EX. RIPRAP
 - EX. CONCRETE MONUMENT
 - EX. TREE
 - EX. TRAVERSE POINT
 - EX. STORMDRAIN
 - EX. 1' MINOR CONTOUR
 - EX. 5' MAJOR CONTOUR

MATCH LINE - SEE SHEET LS-02


ALL TREE AND WOODY PLANTINGS SHALL STRICTLY ADHERE TO THE FOLLOWING PLANTINGS OFFSETS:
 *WATER, SANITARY SEWER, & STORMDRAIN PIPES - 7' PLUS 1/2 PIPE DIAMETER
 *MANHOLES - 10'
 *GAS PIPELINES - 10'
 *BURIED WIRE - 5'
 *RISER PIPES & STRUCTURES - 25'
 *EXISTING TREES - 10' (APPLIES TO TREES ONLY)
 *DAM EMBANKMENTS - 15'
 *ROAD EDGE - 20'
 **NO WOODY VEGETATION IS TO BE PLANTED DIRECTLY OVER ROCK STEP STRUCTURE SILLS.

NOTE:
 NOT ALL FURNISHED STONE IS SHOWN IN PLAN VIEW. SEE THE STREAM RESTORATION DETAILS AND PROFILE FOR ADDITIONAL INFORMATION.



STABILIZATION NOTE:
 ALL DISTURBED SLOPES GREATER THAN 4:1 AND SENSITIVE AREAS (STREAM BUFFER, FLOODPLAIN, STEEP (>20%) SLOPES, HIGHLY ERODIBLE SOILS) MUST BE PERMANENTLY STABILIZED WITH SOIL STABILIZATION MATTING.

CENTURY ENGINEERING
 CONSULTING ENGINEERS - PLANNERS
 10710 GILROY ROAD
 HUNT VALLEY, MARYLAND 21031
 PHONE: (443) 589-2400 FAX: (443) 589-2401



DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND
 Mark S. Richmond 12/30/19
 CHIEF, STORMWATER MANAGEMENT DIVISION
 I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.
 LICENSE # 28371 EXPIRES: 01/01/2021

HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS


REVISIONS		
NO.	DATE	DESCRIPTION

**D-1158 CHERRYTREE FARM
 STREAM RESTORATION**

FINAL (100%) DESIGN

LANDSCAPE SHEET

PROJECT NO:	121104.64
SCALE:	1" = 20'
DATE:	12/30/19
DESIGN:	CR
DRAWN:	JT
CHECK:	EW
DWG NO:	LS-01 of LS-04
SHEET NO:	19 OF 22



- PROPOSED LANDSCAPE LEGEND**
- HERBACEOUS PLUG PLANTINGS: 2,115 SF / 0.05 AC
 - FLOODPLAIN BENCH PLANTINGS: 5,049 SF / 0.12 AC
 - RIPARIAN FOREST PLANTINGS: 10,627 SF / 0.24 AC


- PROPOSED FEATURES LEGEND**
- LIMIT OF DISTURBANCE
 - 1' MINOR CONTOUR
 - 5' MAJOR CONTOUR
 - WOODY HABITAT FEATURE (WHF)
 - BOULDER SILL
 - ROCK STEP-POOL STRUCTURE (RSP)
 - ARMORED RIFLE (R)
 - TRIBUTARY STABILIZATION (CLASS I RIPRAP CHOKED WITH SILT AND GRAVEL)
 - CLAY CHANNEL BLOCK (CCB)

- EXISTING FEATURES LEGEND**
- EX. BUILDING
 - EX. NONTIDAL WETLAND
 - EX. WATERS OF THE U.S.
 - EX. FENCE
 - EX. PROPERTY BOUNDARY
 - EX. EASEMENT
 - EX. EDGE OF PAVEMENT
 - EX. GAS MAIN
 - EX. TREELINE
 - EX. CONCRETE DEBRIS
 - EX. RIPRAP
 - EX. CONCRETE MONUMENT
 - EX. TREE
 - EX. TRAVERSE POINT
 - EX. STORMDRAIN
 - EX. 1' MINOR CONTOUR
 - EX. 5' MAJOR CONTOUR



ALL TREE AND WOODY PLANTINGS SHALL STRICTLY ADHERE TO THE FOLLOWING PLANTINGS OFFSETS:
 *WATER, SANITARY SEWER, & STORMDRAIN PIPES - 7' PLUS 1/2 PIPE DIAMETER
 *MANHOLES - 10'
 *GAS PIPELINES - 10'
 *BURIED WIRE - 5'
 *RISER PIPES & STRUCTURES - 25'
 *EXISTING TREES - 10' (APPLIES TO TREES ONLY)
 *DAM EMBANKMENTS - 15'
 *ROAD EDGE - 20'
 **NO WOODY VEGETATION IS TO BE PLANTED DIRECTLY OVER ROCK STEP STRUCTURE SILLS.

NOTE:
 NOT ALL FURNISHED STONE IS SHOWN IN PLAN VIEW. SEE THE STREAM RESTORATION DETAILS AND PROFILE FOR ADDITIONAL INFORMATION.



SCALE: 1" = 20'


CENTURY ENGINEERING
 CONSULTING ENGINEERS - PLANNERS
 10710 GILROY ROAD
 HUNT VALLEY, MARYLAND 21031
 PHONE: (443) 589-2400 FAX: (443) 589-2401

DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND
Mark A. Richmond 12/30/19
 CHIEF, STORMWATER MANAGEMENT DIVISION DATE
 I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.
 LICENSE # 28371 EXPIRES: 01/01/2021

REVISIONS		
NO.	DATE	DESCRIPTION



HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
 D-1158 CHERRYTREE FARM STREAM RESTORATION
 FINAL (100%) DESIGN
 LANDSCAPE SHEET

PROJECT NO: 121104.64
 SCALE: 1" = 20' DATE: 12/30/19
 DESIGN: CR DRAWN: JT CHECK: EW
 DWG NO: LS-02 OF LS-04
 SHEET NO: 20 OF 22




- NOTES:
 1. FOR CONTAINER SHRUBS, COMPLETELY REMOVE ALL NON-Biodegradable CONTAINERS AND SCARIFY ROOTBALL BY USING A SHARP BLADE AND MAKING 4 TO 5 ONE INCH CUTS THE LENGTH OF THE ROOTBALL.
 2. FOR B&B SHRUBS, CUT AND REMOVE BURLAP FROM TOP 1/3 OF ROOTBALL.

SHRUB PLANTING
Not To Scale





DECIDUOUS TREE PLANTING
Not To Scale




- NOTES:
 1. TO BE USED ON SINGLE STEM TREES.
 2. HEIGHT OF SHELTER TO BE ADJUSTED TO PREVENT CANOPY BREAKAGE.
 3. TREE SHELTERS ARE TO BE CONSIDERED INCIDENTAL TO EACH TREE PLANTING.

TREE SHELTER
Not To Scale



2" PERENNIAL PLUG DETAIL
Not To Scale



CLUSTER SHRUB DEER PROTECTION
Not To Scale

- NOTES:
 1. THIS DETAIL IS TO BE USED FOR INDIVIDUAL SHRUBS AND SHRUB BEDS. IN ADDITION, IT WILL BE USED FOR EVERGREEN TREES OR DECIDUOUS TREES WITH BRANCHES LOWER THAN 4' IN HEIGHT.
 2. HEIGHT OF CAGE SHALL BE 4 FEET MINIMUM WITH A MAXIMUM DIAMETER OF 10 FEET.
 3. CAGE SHALL BE FASTENED TO STAKE WITH 3 (MIN.) TWIST TIE EVENLY SPACED WITH A 6" (MIN.) ABOVE THE GROUND.
 4. CAGE SHALL SURROUND ALL SHRUBS AND TREES WITH A 1 FOOT SPACING FROM THE OUTSIDE OF THE PLANT.
 5. STAKES SHALL BE PLACED AT A MAXIMUM 5 FOOT SPACING.
 6. CAGES TO BE REMOVED AT DIRECTION OF HOWARD COUNTY.
 7. HARDWOOD MULCH SHALL BE PLACED TO 2-3 INCH DEPTH WITHIN FENCING.
 8. CLUSTER SHRUB DEER PROTECTION IS TO BE CONSIDERED INCIDENTAL TO SHRUB PLANTINGS.

LANDSCAPING NOTES:

PLANT MATERIAL SELECTION -

- THE CONTRACTOR SHALL FURNISH PLANT MATERIALS IN SIZES AND QUANTITIES SPECIFIED IN THE PLANT SCHEDULES ON SHEET LS-04.
- NURSERY GROWN PLANT MATERIAL SHOULD MEET OR EXCEED THE REQUIREMENTS OF THE AMERICAN NURSERY & LANDSCAPE ASSOCIATION'S (A.N.L.A.) LATEST EDITION OF "AMERICAN STANDARD NURSERY STOCK" (ANSI Z60.1) SPECIFICATIONS, PARTICULARLY REGARDING THE SIZE, GROWTH, SIZE OF THE ROOT BALL, AND DENSITY OF BRANCH STRUCTURE.
- ALL PLANTING MATERIAL SHALL BE SOURCED FROM WITHIN 100 MILES OF THE SITE.
- NO SUBSTITUTIONS SHALL BE MADE WITHOUT THE WRITTEN CONSENT OF THE OWNER AND/OR LANDSCAPE ARCHITECT.
- THE LANDSCAPE ARCHITECT OR OWNER SHALL HAVE THE RIGHT, AT ANY STAGE OF THE OPERATIONS, TO REJECT ANY AND ALL WORK AND MATERIALS WHICH, IN HIS OR HER OPINION, DO NOT MEET THE REQUIREMENTS OF THESE PLANS AND SPECIFICATIONS. ALL REJECTED MATERIAL SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR.
- SEE PLANT LISTS ON SHEET LS-04 FOR SIZE, TYPE, SPECIES, SPACING, QUANTITIES AND APPLICATION RATES.
- SEED MIXES SHALL HAVE A MINIMUM PURITY OF 98% AND A MINIMUM GERMINATION OF 85% PER PLANTING ZONE. THE SEED MIX IS TO BE ENDOPHYTE-FREE AND CONTAIN LESS THAN 1% INERT MATTER.

PLANT MATERIAL TRANSPORT, APPROVAL, & STORAGE -

- PLANT MATERIAL SHALL BE PROTECTED TO PREVENT SUN SCALD, DESICCATION, AND STRUCTURAL DAMAGE DURING TRANSPORT TO THE SITE. ROOT STOCK OF THE PLANT MATERIAL SHALL BE KEPT MOIST DURING TRANSPORT FROM THE SOURCE TO THE JOB SITE AND UNTIL PLANTED.
- PLANT MATERIAL SHALL BE INSPECTED TO BE FREE OF DISEASE, DAMAGE, INSECT INFESTATION, AND VIGOR UPON DELIVERY TO THE SITE. ALL PLANTS SHOULD BE HEALTHY AND WELL STRUCTURED. NO HELED-COLD STORAGE OR COLLECTED STOCK WILL BE ACCEPTED. PLANTS IN POOR CONDITION SHALL BE REJECTED, REMOVED FROM THE SITE AND REPLACED WITH ACCEPTABLE MATERIALS.
- PLANT MATERIAL SHALL BE STORED IN A COOL, SHADED AREA ON THE SITE AND KEPT MOIST TO PREVENT DESICCATION UNTIL READY FOR PLANTING. PLANTING SHALL BEGIN WITHIN 24 HOURS OF PLANT DELIVERY TO THE SITE. PLANT MATERIAL THAT REMAINS UNPLANTED BEYOND 24 HOURS SHALL BE PROTECTED FROM DIRECT SUN AND WEATHER, AND KEPT MOIST. PLANT MATERIALS SHALL NOT BE LEFT UNPLANTED FOR MORE THAN 2 WEEKS.
- THE CONTRACTOR IS REQUIRED TO OBTAIN CLEAN FRESH WATER FOR USE DURING PLANTING OPERATIONS AND THE SUBSEQUENT MAINTENANCE PERIOD.

SITE PREPARATION -

- THE SITE AND AREAS ABUTTING THE LOD SHALL BE TREATED FOR INVASIVE SPECIES PRIOR TO THE START OF CONSTRUCTION.
- NO CLEARING OR GRADING SHALL BEGIN BEFORE STRESS-REDUCTION MEASURES HAVE BEEN IMPLEMENTED. SUCH MEASURES MAY INCLUDE TREE PROTECTION PLANKING, ROOT PRUNING, CROWN REDUCTION OR PRUNING, ETC. AT THE DISCRETION OF THE PLAN PREPARER, DESIGNATED SPECIALIST, OR AN MDL/TE/ISA CERTIFIED ARBORIST.
- PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITIES, TREE PROTECTION FENCING SHALL BE INSTALLED ALONG ALL SECTIONS OF THE LOD ABUTTING WOODED/FORESTED AREAS AND AROUND ALL 'TREE SAVE' AREAS TO ENSURE PRESERVATION OF THESE AREAS.
- ALL TREE PROTECTION MEASURES MUST BE IN PLACE AT THE TIME OF THE SEDIMENT & EROSION CONTROL INSPECTION. PRIOR TO THE COMMENCEMENT OF DEMOLITION, SITE CLEARING, GRADING, OR CONSTRUCTION, TREE PROTECTION DEVICES SHALL BE MAINTAINED FOR THE DURATION OF CONSTRUCTION. NO EQUIPMENT, TRUCKS, MATERIALS, OR DEBRIS MAY BE STORED WITHIN THE TREE PROTECTION AREAS DURING THE ENTIRE CONSTRUCTION PROJECT.
- ALL TREES TO BE REMOVED MUST BE REMOVED IN A MANNER THAT WILL NOT DAMAGE THE REMAINING TREES. THE CONTRACTOR SHALL DISPOSE OF STUMPS AND MAJOR ROOTS OF ALL PLANTS TO BE REMOVED. ANY DEPRESSIONS CAUSED BY REMOVAL OPERATIONS SHALL BE REFILLED WITH FERTILE, FRIABLE, SOIL PLACED AND COMPACTED SO AS TO REESTABLISH PROPER GRADE FOR NEW PLANTING AND/OR LAWN AREAS.

- ANY TREES THAT ARE TO REMAIN THAT ARE DAMAGED DURING THE CLEARING OPERATION MUST BE REPAIRED OR REMOVED AND REPLACED IN AN APPROVED MANNER BY AN MDL/TE/ISA CERTIFIED ARBORIST, DESIGNATED SPECIALIST, OR HOWARD COUNTY DPW REPRESENTATIVE AS SOON AS FINAL CLEARING HAS BEEN COMPLETED.
- ROOT PRUNING MAY BE NECESSARY WHERE THE CRITICAL ROOT ZONE IS IMPACTED, AS DETERMINED BY THE PLAN PREPARER OR AN MDL/TE/ISA CERTIFIED ARBORIST. PRUNING SHALL BE ALONG THE LOD ADJACENT TO TREE PROTECTION FENCING. A CERTIFIED ARBORIST SHALL SUPERVISE OR CONDUCT ROOT PRUNING.

PLANTING AND SCHEDULE -

- REFER TO THE MDSHA STANDARDS AND SPECIFICATIONS SECTION 710.03.01 PLANTING SEASONS TABLE FOR ACCEPTABLE PLANTING PERIOD. PLANTING SHALL NOT BE COMPLETED IN SUB-FREEZING TEMPERATURES; WHEN THE GROUND IS FROZEN; WHEN WEATHER CONDITIONS WILL ADVERSELY AFFECT PLANT MATERIALS; OR WHEN THE SOIL IS TOO WET OR OTHERWISE IN A CONDITION NOT ACCEPTABLE FOR PLANTING.
- THE CONTRACTOR SHALL STABILIZE, SEED WITH THE DESIGNATED PERMANENT SEED MIX (SEE LANDSCAPE SCHEDULES), AND MULCH THE SITE IMMEDIATELY FOLLOWING THE ESTABLISHMENT OF FINISHED GRADE.
- MOW PLANTING AREA CLOSE TO THE GROUND ONE WEEK (OR LESS) PRIOR TO PLANTING DATE.
- THE CONTRACTOR IS RESPONSIBLE FOR TESTING PROJECT SOILS. THE CONTRACTOR IS TO PROVIDE A CERTIFIED SOILS REPORT TO THE OWNER. THE CONTRACTOR SHALL VERIFY THAT THE SOILS ON SITE ARE ACCEPTABLE FOR THE PROPER GROWTH OF THE PROPOSED PLANT MATERIAL. SHOULD THE CONTRACTOR FIND POOR SOIL CONDITIONS, THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE SOIL AMENDMENTS AS NECESSARY. THESE AMENDMENTS SHALL INCLUDE, BUT NOT BE LIMITED TO FERTILIZERS, LIME, AND TOPSOIL. PROPER PLANTING SOILS MUST BE VERIFIED PRIOR TO WHEN PLANTING MATERIALS ARE INSTALLED.
- PREPARE PLANTING PITS PER MDSHA STANDARDS AND SPECIFICATIONS SECTION 710.03.04.
- NO TREES ARE TO BE PLANTED DIRECTLY OVER UTILITY LINES.
- INSTALL PLANT MATERIALS PER MDSHA STANDARDS AND SPECIFICATIONS 710.03.09.
- MAINTAIN ALL MINIMUM WOODY VEGETATION OFFSETS LISTED ON SHEETS LS-01 AND LS-02.
- UPON COMPLETION OF ALL LANDSCAPING, AN ACCEPTANCE OF THE WORK SHALL BE HELD. THE CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT, DESIGNATED SPECIALIST, OR THE OWNER FOR SCHEDULING OF THE INSPECTION AT LEAST SEVEN (7) DAYS PRIOR TO THE ANTICIPATED INSPECTION DATE.
- AFTER INSTALLATION OF PLANTS, THE CONTRACTOR SHALL MONITOR THE SOIL MOISTURE AND WATER NEEDS OF PLANTS AND SEED AS NECESSARY TO ENSURE SURVIVABILITY. WATERING PLANTING PITS AND SEEDED AREAS SHOULD OCCUR AS SPECIFIED IN MDSHA STANDARDS AND SPECIFICATIONS SECTION 710.03.04(C).

MAINTENANCE -

- UPON COMPLETION OF INSTALLATION, THE PLANTING AREA IS TO BE MAINTAINED FOR A 1 YEAR PERIOD. AN 100% SURVIVAL RATE MUST BE ACHIEVED FROM THE DATE OF ACCEPTANCE TO THE TERMINATION OF THE MAINTENANCE PERIOD. MAINTENANCE SHALL BE AS FOLLOWS:
 - ANY PLANT MATERIAL SHOWING SIGNS OF DISTRESS ARE TO BE REPLACED IMMEDIATELY BY THE CONTRACTOR.
 - NATIVE VOLUNTEER SEEDLINGS SHALL BE REMOVED ONLY IF THEY ARE ADVERSELY IMPACTING THE GROWTH OF THE PLANTED MATERIAL. NON-NATIVE AND INVASIVE SPECIES ARE TO BE REMOVED FROM THE ENTIRE PLANTING AREA THROUGH SELECTED AND APPROVED MEANS.
 - ALL MAN-MADE MATERIALS SHALL BE REMOVED FROM THE SITE WHICH WOULD IMPACT THE ESTABLISHMENT OF THE PLANTED MATERIALS.
 - THOROUGHLY WATER PLANTED MATERIAL ONCE WEEKLY OR AS NEEDED DURING THE GROWING SEASON.
 - PLANTED MATERIAL IS TO BE MONITORED FOR SIGNS OF DAMAGE AND APPROPRIATE ACTIONS SHALL BE TAKEN TO PREVENT FURTHER DAMAGE. THIS MAY INCLUDE, BUT NOT BE LIMITED TO, THE FOLLOWING: PEST DAMAGE OR INFESTATION, DISEASE OR BROWSING; ANY DEAD OR DECIMATED MATERIAL SHALL BE REPLACED WITH THE IDENTICAL SPECIES OR AN APPROVED REPLACEMENT.
 - AT THE END OF THE 1 YEAR MAINTENANCE PERIOD, THE SITE SHALL BE INSPECTED FOR THE 100% SURVIVAL RATE AS REQUIRED BY THE HOWARD COUNTY DPW.

<p>CENTURY ENGINEERING CONSULTING ENGINEERS - PLANNERS 10710 GILROY ROAD HUNT VALLEY, MARYLAND 21031 PHONE: (443) 589-2400 FAX: (443) 589-2401</p>	<p>HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS</p>		<p>D-1158 CHERRYTREE FARM STREAM RESTORATION</p> <p>FINAL (100%) DESIGN</p> <p>LANDSCAPE NOTES & DETAILS</p>	<p>PROJECT NO: 121104.64 SCALE: 1" = 20' DATE: 12/30/19 DESIGN: CR DRAWN: JT CHECK: EW DWG. NO: LS-03 of LS-04 SHEET NO: 21 OF 22</p>												
	<p>DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND Mark Richmond 12/30/19 CHIEF, STORMWATER MANAGEMENT DIVISION DATE</p>	<table border="1"> <thead> <tr> <th colspan="3">REVISIONS</th> </tr> <tr> <th>NO.</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>			REVISIONS			NO.	DATE	DESCRIPTION						
REVISIONS																
NO.	DATE	DESCRIPTION														

HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.
 LICENSE # 28371 EXPIRES: 01/01/2021

Riparian Seed Mix (30,638 SF / 0.70 AC)

Botanical Name	Common Name	Percent of Mix	Application Rate (lbs/AC)	Quantity (lbs)
<i>Andropogon gerardii</i>	Big bluestem	35.00%	14.00	9.80
<i>Panicum virgatum</i>	Switchgrass	28.00%	11.20	7.84
<i>Elymus virginicus</i>	Virginia wildrye	22.00%	8.80	6.16
<i>Sorghastrum nutans</i>	Indiangrass	12.00%	4.80	3.36
<i>Desmodium canadese</i>	Showy ticktrefoil	1.00%	0.40	0.28
<i>Symphotrichum novae-angliae</i>	New England aster	1.00%	0.40	0.28
<i>Aquilegia canadensis</i>	New England aster	1.00%	0.40	0.28
			Total:	28.00

Total Application Rate of 40 lbs/ac. To be applied with 15lbs/ac of perennial ryegrass (*Lolium perenne*) and 60lbs/ac of hard fescue (*Festuca trachyphylla*) during the periods of March 1 to May 15 and August 1 to October 15 or foxtail millet (*Setaria italica*) if during May 16 to July 31.

Riparian Forest Plantings (30,638 SF / 0.70 AC)

Species	Common Name	Layer	Size	Type	Spacing	Quantity
<i>Quercus alba</i>	White oak	Canopy tree	6'-8' Height	Container	18'-20' O.C.	21
<i>Quercus rubra</i>	Northern red oak	Canopy tree	6'-8' Height	Container	18'-20' O.C.	21
<i>Liriodendron tulipifera</i>	Tuliptree	Canopy tree	6'-8' Height	Container	18'-20' O.C.	21
<i>Carya glabra</i>	Pignut hickory	Canopy tree	6'-8' Height	Container	18'-20' O.C.	22
Total:						85
<i>Cornus florida</i>	Flowering dogwood	Understory tree	5' Height	Container	12'-14' O.C.	18
<i>Prunus serotina</i>	Black cherry	Understory tree	5' Height	Container	12'-14' O.C.	18
<i>Ostrya virginiana</i>	Hophornbeam	Understory tree	5' Height	Container	12'-14' O.C.	18
Total:						54

Note: Assume 100% canopy and 30% understory coverage.

Floodplain Seed Mix (Floodplain Bench Plantings, and Herbaceous Plug Plug Plantings TOTAL: 11,494 SF / 0.26 AC)

Botanical Name	Common Name	Percent of Mix	Application Rate (lbs/AC)	Quantity (lbs)
<i>Panicum clandestinum</i>	Deertongue	22.00%	8.80	2.29
<i>Elymus virginicus</i>	Virginia wildrye	21.00%	8.40	2.18
<i>Andropogon gerardii</i>	Big bluestem	17.00%	6.80	1.77
<i>Panicum virgatum</i>	Switchgrass	15.00%	6.00	1.56
<i>Carex vulpinoidea</i>	Fox sedge	11.00%	4.40	1.14
<i>Heliopsis helianthoides</i>	Oxeye sunflower	8.00%	3.20	0.83
<i>Desmodium paniculatum</i>	Panicled-leaf ticktrefoil	3.00%	1.20	0.31
<i>Eupatorium fistulosum</i>	Joe pye weed	2.00%	0.80	0.21
<i>Juncus tenuis</i>	Path rush	1.00%	0.40	0.10
			Total:	10.40

Total Application Rate of 40 lbs/ac. To be applied with 15lbs/ac of perennial ryegrass (*Lolium perenne*) and 60lbs/ac of hard fescue (*Festuca trachyphylla*) during the periods of March 1 to May 15 and August 1 to October 15 or foxtail millet (*Setaria italica*) if during May 16 to July 31.

Floodplain Bench Plantings (7,575 SF / 0.17 AC)

Species	Common Name	Layer	Size	Type	Spacing	Quantity
<i>Cornus amomum</i>	Silky dogwood	Understory tree	5' Height	Container	12'-14' O.C.	7
<i>Carpinus caroliniana</i>	American hornbeam	Understory tree	5' Height	Container	12'-14' O.C.	7
<i>Amelanchier canadensis</i>	Canadian serviceberry	Understory tree	5' Height	Container	12'-14' O.C.	8
Total:						22
<i>Alnus serrulata</i>	Hazel alder	Shrub	2'-3' Height	Container	6-8' O.C.	15
<i>Lindera benzoin</i>	Spicebush	Shrub	2'-3' Height	Container	6-8' O.C.	15
<i>Viburnum dentatum</i>	Southern arrowwood	Shrub	2'-3' Height	Container	6-8' O.C.	16
Total:						46

Note: Assume 50% understory and 30% shrub coverage. Shrubs to be planted in clusters of 5-7.

Upland Meadow Seed Establishment (11,457 SF / 0.26 AC)

Botanical Name	Common Name	Percent of Mix	Application Rate (lbs/AC)	Quantity (lbs)
<i>Andropogon gerardii</i>	Big bluestem	40.00%	16.00	4.16
<i>Elymus virginicus</i>	Virginia wildrye	25.00%	10.00	2.60
<i>Panicum virgatum</i>	Switchgrass	15.00%	6.00	1.56
<i>Sorghastrum nutans</i>	Indiangrass	8.00%	3.20	0.83
<i>Asclepias tuberosa</i>	Butterflyweed	5.00%	2.00	0.52
<i>Asclepias syriaca</i>	Common milkweed	4.00%	1.60	0.42
<i>Rudbeckia hirta</i>	Blackeyed susan	3.00%	1.20	0.31
			Total:	10.40


Total Application Rate of 40 lbs/ac. To be applied with 15lbs/ac of perennial ryegrass (*Lolium perenne*) and 60lbs/ac of hard fescue (*Festuca trachyphylla*) during the periods of March 1 to May 15 and August 1 to October 15 or foxtail millet (*Setaria italica*) if during May 16 to July 31.

Herbaceous Plug Plantings (3,919 SF / 0.09 AC)

Species	Common Name	Size	Root	Spacing	Quantity	Notes
<i>Iris versicolor</i>	Blue flag	2" Plug	5" Depth	3' O.C.	72	Lower on stream bank
<i>Carex crinita</i>	Long hair sedge	2" Plug	5" Depth	3' O.C.	72	Lower on stream bank
<i>Elymus riparius</i>	Riverbank wild-rye	2" Plug	5" Depth	3' O.C.	72	Lower on stream bank
<i>Panicum virgatum</i>	Switchgrass	2" Plug	5" Depth	3' O.C.	73	Higher on stream bank
<i>Elymus hystrix</i>	Bottlebrush grass	2" Plug	5" Depth	3' O.C.	73	Higher on stream bank
<i>Athyrium angustum</i>	Lady fern	2" Plug	5" Depth	3' O.C.	73	Higher on stream bank
					Total:	435

Note: Arrange plug plantings according to listed notes.

THIRD CENTURY ENGINEERING
CONSULTING ENGINEERS - PLANNERS
10710 GILROY ROAD
HUNT VALLEY, MARYLAND 21031
PHONE: (443) 589-2400 FAX: (443) 589-2401



DEPARTMENT OF PUBLIC WORKS, HOWARD COUNTY MARYLAND
Mark S. Richmond 12/30/19
CHIEF, STORMWATER MANAGEMENT DIVISION DATE
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.
LICENSE # 28371 EXPIRES: 01/01/2021

HOWARD COUNTY
DEPARTMENT OF PUBLIC WORKS

REVISIONS

NO.	DATE	DESCRIPTION

D-1158 CHERRYTREE FARM
STREAM RESTORATION

FINAL (100%) DESIGN
LANDSCAPE NOTES &
DETAILS

PROJECT NO: 121104.64
SCALE: 1" = 20' DATE: 12/30/19
DESIGN: CR DRAWN: JT CHECK: EW
DWG NO: LS-04 of LS-04
SHEET NO: 22 OF 22