



**PAVING SYMBOLS**

EXISTING		PROPOSED
	Curb and Gutter	
	Roadway Paving	
	Concrete Sidewalk	



- GENERAL NOTES**
- All work performed under this contract shall be in accordance with "Howard County Road Construction Code and Standard Specifications."
  - For details, see referenced Howard County Standards.

**QUANTITY SCHEDULE**

DESCRIPTION	UNIT	QUANTITY
Removal of Existing Curb and Gutter	L.F.	265
Removal of Existing Pavement	S.Y.	160
Road Excavation	C.Y.	47
Std. Concrete Sidewalk	S.F.	425
Std. 7" Combination Curb and Gutter	L.F.	45
Bituminous Concrete Surface (Band C-3)	TON	6
Bituminous Concrete Binder (Band A-3)	TON	5
Bituminous Concrete Base (Band C-2)	TON	8
7" Crusher Run Base Course	S.Y.	53
Select Backfill	C.Y.	31
Top Soil	C.Y.	7
Sod	S.Y.	125

**DEPARTMENT OF PUBLIC WORKS**  
 HOWARD COUNTY, MARYLAND

Director of Public Works DATE  
 Chief - Bureau of Engineering DATE  
 Chief - Division of Roads DATE  
 Chief - Traffic Division DATE





**PLAN INTERSECTION GEOMETRIC MODIFICATIONS**

**LITTLE PATUXENT PARKWAY / CEDAR LANE**  
 CAPITAL PROJECT NO. T-0-7011  
 ELECTION DISTRICT NO 5  
 HOWARD COUNTY, MARYLAND

DRAWING NO. 1 OF 2	SCALE 1"=30'	D.T.C. R.W.S. K.L.E.
--------------------	--------------	----------------------

C794B201

PHASE AND SEQUENCE DIAGRAM	Traffic Signal Head									Min. Green	Passage Yellow	Red Clear	Max. I	Seconds Per Actuation	Time to Reduce	Time Before Reduction	Minimum Gap	Recall	Memory	
	1	2,3	4,5	6,7,8,9																
	Phase A	G	G	R	R	12	1													
	Phase A Clear	Y,R	G	G	R			4	1											
	Phase B	R	G	G	R	13	5			13	3	5	5	35	Off	On				
	Phase B Clear	R	Y,R	Y,R	R			4	1											
	Phase C	R	R	R	G	14	5			25	1.5	10	10	35	Off	On				
	Phase C Clear	R	R	R	Y,R			4	1											
	Flash	R	R	R	Y															



VICINITY MAP  
SCALE: 1"=2000'

**GENERAL NOTES**

- All highway marking shall be the responsibility of the Division of Traffic Engineering of the Bureau of Engineering, Department of Public Works, of Howard County, Maryland, and is not to be considered a part of this contract.
- The utilities shown on the construction plan are schematic only and are not to be considered complete. The contractor shall be responsible for notifying all utility companies prior to construction so that all utilities can be located in the field. The contractor shall locate existing utilities a minimum of two (2) weeks in advance of the construction operations in the vicinity of the utilities. Any damage incurred by the contractor shall be repaired immediately at the contractor's expense. See Section 4.09 of the General Specifications.
- All materials and workmanship employed under this contract shall conform with the "GENERAL SPECIFICATIONS FOR INSTALLATION OF AND EQUIPMENT FOR TRAFFIC SIGNALS FOR HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS" dated October 7, 1974; revised February 18, 1976.
- All disturbed areas shall be properly restored in accordance with Section 4.20 of the General Specifications.
- The reconstruction of the center median island and the removal of the temporary bituminous concrete curb island shall not be considered a part of this contract.

**CONTROLLER AND ACCESSORIES**

- NEMA three phase modular thumbwheel programmable controller with solid state circuitry and digital timing, equivalent to the Crouse Hinds DM-400 Series Digital Controller unit or approved equal. The controller shall be capable of expansion to four phase operation.
  - Equipped with one (1) vehicular actuated module.
  - Equipped with two (2) vehicular actuated modules with volume density controls.
  - Vehicular actuated phase modules shall be capable of the following functions: Minimum Green, Passage Time, Yellow, All Red Clearance, Dual Maximum, Pedestrian Timing, Recall and Memory.
  - Vehicular actuated phase module with volume density controls shall be capable of the following functions: Minimum Green, Passage Time, Yellow, All Red Clearance, Dual Maximum, Pedestrian Timing, Seconds Per Actuation, Time to Reduce, Time Before Reduction, Minimum Gap, Recall and Memory.
  - Four phase signal overlap capability.
- Conflict Monitor and Solid State load switches.
- Solid State flasher and switch accessible through police door panel.
- Ground mounted traffic controller cabinet large enough to accommodate the above control equipment and detectors. The cabinet shall be furnished with a thermostatically controlled cabinet vent fan.
- Finish of the cabinet shall be all-weather bronze paint.
- Install 3'x4'x5" concrete slab in front of the controller cabinet.
- Meter box shall be installed in vandal proof enclosure provided by the contractor.

**UNDERGROUND WIRING**

- Underground wiring shall be placed in new PVC Conduits under the road surface and in grass areas, as shown on the Contract Drawings.
- The conduit shall be sized to accommodate future wiring for pedestrian (WALK/DON'T WALK) signal heads, and pedestrian push button detectors.
- The contractor shall furnish an "as-built" drawing as per "General Specifications - 4.02b".

**LOOPS AND DETECTORS**

The following new loops shall be installed:

Number	Dimensions	Phase
1	6' x 40'	A
2	6' x 25'	B
3	6' x 18'	B
4,5	6' x 18'	C

\* Loops to be installed with 6'x3' powerhead detection of small vehicles.

- Loop 1 shall be wired to a standard detector.
- Loops 2 and 3 shall be wired in parallel to a standard detector.
- Loops 4 and 5 shall be wired in parallel to a standard detector.
- All wiring shall be in accordance with manufacturer's recommendations for correct operation.
- Loop 1 shall operate in presence mode. Loops 2, 3, 4 and 5 shall operate in pulse mode.
- Standard detectors shall be Sarasota 215B/MS or approved equal.


**SIGNAL HEADS**

- The contractor shall provide the following new signal heads:
 

Signal Number	Description
1	Optically programmed 3-section signal head with green left turn arrow; "3M Model 131" or approved equal
2,3,4,5,6,7,8,9	12" diameter indications
- All signals shall have brown baked enamel finish and shall be vertically mounted with clevis hangers. Signal No. 1 shall be bracket mounted to the signal pole.

**POLES**

- The contractor shall provide the following new signal poles:
- Two (2) twin arm support poles with 90° angle of separation.
  - Style and appearance shall be equivalent to Union Metal Design No. 50700. Finish shall be all weather bronze paint.
- | Pole Number | Description   |
|-------------|---|
| 1           | 32' and 44' arm spread, each supporting two signal heads. |
| 2           | 26' and 38' arm spread, each supporting two signal heads. |



**NOTE 'A'**  
Temporary bituminous concrete curbs and island to be removed and area reconstructed by others.

**NOTE 'B'**  
Harpers Choice - Section 1, Area 4 is presently under construction. Extend detector loop #5 if entrance is completed at time of signal construction.

DEPARTMENT OF PUBLIC WORKS  
HOWARD COUNTY, MARYLAND

PREPARED BY:  
THE WILSON T. BALLARD CO.  
CONSULTING ENGINEERS  
OWINGS MILLS, MARYLAND  
TEL NO. 363-0150

**PLAN**  
**CONSTRUCTION OF TRAFFIC**  
**SIGNAL AND EQUIPMENT LIST**

**LITTLE PATUXENT PARKWAY / CEDAR LANE**

CAPITAL PROJECT NO. T-O-7011  
ELECTION DISTRICT NO. 5  
HOWARD COUNTY, MARYLAND

NO.	DATE	DESCRIPTION OF REVISION	SIGNATURE

DRAWING	SCALE	D.T.C.
NO. 1	1"=30'	DESIGNED BY
OF 1		R.W. DRAFTED BY

C794B202