SHEET INDEX	
SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	ENVIRONMENTAL CONCEPT PLAN

ENVIRONMENTAL CONCEPT PLAN
VILLAGE OF HARPERS CHOICE
SECTION 5, AREA 9, PHASE 2
LOT 11

TAX MAP No. 29 GRID No. 15 PARCEL NO. 370
FIFTEENTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND

LEGEND	
SYMBOL	DESCRIPTION
	EXISTING CONTOUR 2' INTERVAL
	PROPOSED CONTOUR 2' INTERVAL
SF SF	SILT FENCE
SSF SSF	SUPER SILT FENCE
LOD	LIMIT OF DISTURBANCE
	EXISTING FENCE LINE
	EX. LIMIT OF TREES AND FOREST
	PROPOSED LANDSCAPING
	EXISTING TREES
	PROPOSED GRAVEL/RIPRAP/SCE
	15% TO 25% SLOPES
	25% OR GREATER SLOPES
MaC / OcB	SOIL LINES AND TYPES
	EXISTING STREAM BANKS

DESIGN NARRATIVE

Introduction:
This report will demonstrate how the criteria set forth in the Maryland Stormwater Design Manual, Volumes I and II (effective October 2000, revised May 2009) will be satisfied on this project. The goal of creating hydrology similar to that of "Woods in Good Condition" will be accomplished through the use of the practices contained within Chapter 5 of said manual. The achievement of this goal will remove the requirement of providing Channel Protection Volume.

General Site Conditions:
Village of Harpers Choice, Section 5, Area 9, Lot 11 is development on an unimproved single family detached lot that is zoned NT. It is located on Tax Map 29, Grid 15, Parcel No. 370 of the Howard County, Maryland Tax Map Database System. The property is part of a larger subdivision recorded in 1993. This plat consisted of thirteen (13) buildable lots. Existing public water and sewer house connections will be utilized that were built under contract #34-3307-D. The property is located in the Columbia area of Howard County in the watershed of an unnamed tributary of the Middle Patuxent River (02131106). This property is irregularly shaped but somewhat square and runoff on-site is mainly from east to west starting at the right of way of Manorstone Lane with runoff to an existing off-site stream. Site is exempt from Forest Conservation requirements, since the lot is part of a planned unit development, however, the entires site is forested. Also, according to a field inspection conducted by Eco-Science Professionals (ESP) dated February 5, 2014, no wetlands or streams are present on-site, but is subject to a 75 foot stream buffer per a recorded plat. The Web Soil Survey shows soils on the site consist of Manor loam (MgD) and Gladstone loam (GbC), Type "B" soils for the majority of the property, and a small portion of Glenville-Baile silt loams (GnB), Type "C" soils within the stream buffer near the edge of the property. The runoff from the roof of the proposed house is to be directed through roof leaders to a micro-bioretention which will outfall into an existing channel on the property. Runoff from the proposed driveway will flow overland and be treated by non-rooftop disconnection.

I. Natural Resource Protection:
Environmentally sensitive areas do exist on-site (stream buffer), therefore development has been proposed outside of the buffer area in an effort to protect this natural resource on-site.

II. Maintenance of Natural Flow Patterns:
It is the intent of the proposed design to discharge runoff similar to the characteristics and direction of this site prior to any of the proposed improvements.

III. Reduction of impervious areas through better site design, alternative surfaces and Nonstructural Practices
The design of this project utilizes a single driveway. Non-Structural practices as permitted in Chapter 5, one (1) Micro-Bioretention Areas (M-6) and Non-Rooftop Disconnection (N-2) will be used to address ESD to the MEP requirements.

IV. Integration of Erosion and Sediment Controls into Stormwater Strategy:
Since this is a small drainage area (most of site sheet flows from this 1.14 acre site toward the off-site stream), silt fence, super silt fence, and erosion control matting will be utilized for erosion & sediment control. There is no direct discharge of runoff directly to a stream. All site runoff will discharge to the the existing ground or prior to entering the existing off-site stream channel and eventually to the Middle Patuxent River. No drainage easements will be required. It is anticipated that all cut will be utilized on-site for construction at time of Grading Plan.

V. Implementation of ESD Planning Techniques and practices to the Maximum Extent Practicable (MEP)
The full required ESD volume is being provided.

VI. Request for a Design Manual Waiver:
No Waivers related to stormwater management are being requested in this project..


SITE
HO CO #2838003
HO CO #2838002
GUILFORD ROAD
MANORSTONE LANE
GLADSTONE WAY
MANORSTONE DRIVE
MANORSTONE COURT
MANORSTONE PLACE
MANORSTONE CIRCLE
MANOR LANE
HARPERS FARM RD.
WINTER TRACE LN.
LARKSPUR LANE
LARKSPUR COURT
LARKSPUR PLACE
LIGHTHOOFOOT
WOODMOOR CIRCLE
WOODMOOR DRIVE
WOODMOOR COURT
WOODMOOR PLACE
WOODMOOR WAY
WOODMOOR LANE
WOODMOOR ROAD
WOODMOOR CT.
WOODMOOR PL.
WOODMOOR LN.
WOODMOOR RD.
WOODMOOR CIR.
WOODMOOR DR.



SECTION A-A

SECTION B-B

MICRO-BIORETENTION DETAIL (M-6)

NOT TO SCALE



PLAN

NOT TO SCALE

MICRO-BIORETENTION									
BIORETENTION FILTER	A	B	C	D	E	F	G	H	I
1	340.00	340.00	339.00	338.75	336.75	336.42	335.92	334.00	335.75



MICRO-BIORETENTION PLANTING DETAIL

NOT TO SCALE

*MIXED PERENNIALS

NEW YORK OR CINNAMON FERNS (2-3' SP.)
VIRGINIA BLUEBELLS (1.5' SP.)
CARDINAL FLOWER LOBELIA (1.5' SP.)

ARROWWOOD VIBURNUM

*SEE PLANT MATERIAL CHARTS FOR QUANTITIES AND SPACING

NOTE: PLANT MATERIAL MUST COVER AT LEAST 50% OF THE SURFACE AREA OF THE MICRO-BIORETENTION

MICRO-BIORETENTION PLANT MATERIAL		
QUANTITY	NAME	MAXIMUM SPACING (FT.)
58	MIXED PERENNIALS	1.5 TO 3.0 FT.
1	ARROWWOOD VIBURNUM	PLANT AWAY FROM INFLOW LOCATION


STATE NORTH
NAD '27
MARYLAND GRID
OPEN SPACE LOT 32 VILLAGE OF HARPERS CHOICE SECTION 5, AREA 9, PHASE I PLAT NOS. 11247-11249
OPEN SPACE LOT 32 VILLAGE OF HARPERS CHOICE SECTION 5, AREA 9, PHASE I PLAT NOS. 11247-11249
LOT 21 VILLAGE OF HARPERS CHOICE SECTION 5, AREA 9, PHASE II PLAT NOS. 11367-11368
N507200
E826000
N 506800
E 826200
GnB
GbC
GbB
MgD
MaD
352.85 Storm Drain MH @ 346.23 II 18RCP
346.82 10 8PVC
N81°16'35"E 95.15'
N45°12'14"E 266.71'
20' B.R.L.
30' B.R.L.
EX. WATER METER (TO REMAIN)
EX. 8" WATER CLOSE
EX. 8" WATER CLOSE
EX. CURB
EX. 8" WATER CLOSE
DRIVEWAY
1.5"WHC
MANOR STONE LANE
LOCAL PUBLIC ROAD
356.37 10 18RCP
356.75 II 18RCP
357.45 10 8PVC
357.57 II 8PVC
CABLE TV BOX
R=295.00' L=16.28'
R=295.00' L=37.43'
N63°45'06"W 300.31'
17,608 SQ.FT. (OR 0.40ac) LIMIT OF DISTURBANCE
11,357 SQ.FT. (OR 0.26ac) LIMIT OF DISTURBANCE
11,140 SQ.FT.
30' B.R.L.
14,608 SQ.FT.
STREAM BUFFER
PAVED
BASEMENT 381.6 FIRST FLOOR 392.0
GARAGE
382.5
382.4
382.1
382.0
381.9
381.4
381.6
381.5
381.3
381.2
381.1
381.0
380.9
380.8
380.7
380.6
380.5
380.4
380.3
380.2
380.1
380.0
379.9
379.8
379.7
379.6
379.5
379.4
379.3
379.2
379.1
379.0
378.9
378.8
378.7
378.6
378.5
378.4
378.3
378.2
378.1
378.0
377.9
377.8
377.7
377.6
377.5
377.4