


LOCATION PLAN
SCALE: 1" = 400'



VICINITY MAP
SCALE: 1" = 2000'

RECORDED PLAT BOOK 20 FOLIO 296
ON 4/11 1974 AMONG THE LAND RECORDS OF
HOWARD COUNTY, MD.

E.G.U.
SECTION 2 AREA 7

PETITIONER AND OWNER
THE HOWARD RESEARCH AND DEVELOPMENT CORPORATION
COLUMBIA, MARYLAND 21044

COLUMBIA

FINAL DEVELOPMENT PLAN PHASE 154
6TH ELECTION DISTRICT HOWARD COUNTY, MD.
SCALE 1" = 400' January, 1974 SHEET 1 OF 3

PREPARED AS TO SHEETS 1 TO 3
IN ACCORDANCE WITH THE ZONING REGULATIONS
OF HOWARD COUNTY
ADOPTED MAY 16, 1961 AND AS
AMENDED MAY 27, 1965



Guy Della Rocca 8714
LAND SURVEYOR'S SIGNATURE

AMENDED B.C.C. CASE 644 RESOLUTION APPROVED JANUARY 7, 1974
BOARD OF COUNTY COMM. B. C. C. CASE 412
RESOLUTION APPROVED AUGUST 10, 1965
AMENDED B.C.C. CASE 507 RESOLUTION APPROVED NOVEMBER 4, 1968
AMENDED B.C.C. CASE 605 RESOLUTION APPROVED NOVEMBER 22, 1972

HOWARD COUNTY PLANNING BOARD
Thomas A. Harig 4-3-74 H.C.P.B. EXEC. SEC. DATE
E. Marianne Lynch 4/3/74 H.C.P.B. CHAIRMAN DATE

FINAL DEVELOPMENT PLAN CRITERIA

The Area included within this Final Development Plan Phase is applicable to Section 2, Area 7, of E.G.U.

1. PUBLIC STREET AND ROADS - Section 17.031 A (1):
To be shown on subdivision plats, if required by the Howard County Office Of Planning and Zoning.
2. PUBLIC RIGHTS-OF-WAY - Section 17.031 A (2):
2A To be shown on subdivision plats, if required by the Howard County Office of Planning and Zoning.
3. MAJOR UTILITY RIGHTS-OF-WAY - Section 17.031 (3):
To be shown on subdivision plats, if required by the Howard County Office of Planning and Zoning.
4. DRAINAGE FACILITIES - Section 17.031 A (4):
To be shown on subdivision plats, if required by the Howard County Office of Planning and Zoning.
5. RECREATIONAL, SCHOOL, PARK AND OTHER COMMUNITY USES - Section 17.031 B:
To be shown on the Final Development Plan, if required by the Howard County Planning Board.
6. PERMITTED GENERAL LOCATIONS OF BUILDINGS AND STRUCTURES - Section 17.031 D.
The term "structure", as used in this Final Development Plan Phase, shall include but not be limited to:

cornices	porches
eaves	bay windows
roof or building overhangs	privacy walls or screens
chimneys	all parts of any buildings
trellises	dwelling, or accessory buildings

All setback areas shall be clear of any protrusions, extension, or construction of any type, and where any land use is adjacent to a freeway or primary road, no structure shall be located within 50' of the right-of-way line thereof nor within fifty (50) feet of a public road owned and/or maintained by the County or State for any building permitted with T-1, B-1, B-2, S-C, M-R, or M-I use type areas of the New Town District, except, however, that structures may be constructed at any location within such setback areas if such construction is in accordance with a site development plan approved by the Howard County Planning Board after a public hearing in accordance with Section 17.037E(2) of the Howard County Zoning Regulations.

The term "structure" does not include the following upon which no restriction as to location is imposed:

walks	excavations or fill
shrubbery	fencing under 6' in height
trees	retaining walls under 3' in height
ornamental landscaping	similar minor structures

Determination of the specific character of "similar minor structures" and setbacks applicable thereto will be made by the Howard County Office of Planning and Zoning.

Fences or walls, if located within setback areas adjacent to a public street, road, or highway upon which construction of structures is prohibited, shall not exceed 3' in height if solid or closed not 5' in height if open, except in accordance with a site development plan approved by the Howard County Planning Board.

6C-2 EMPLOYMENT CENTER LAND USE AREAS - INDUSTRIAL

No structure shall be located within twenty-five (25) feet of the right-of-way of any public street, road, or highway. Any building or structure exceeding twenty (20) feet in height, measured from the highest adjoining ground elevation along the front of the structure, shall be set back an additional one foot for each additional foot of building height in excess of twenty (20) feet. No parking lot shall be located within twenty-five (25) feet of the right-of-way of any public street, road, or highway. No structure shall be erected within one hundred (100) feet of any boundary line of any residential district. Except as restricted by this Paragraph 6C-2, buildings and other structures may be located at any location within industrial land use areas if such construction is in accordance with a site development plan approved by the Howard County Planning Board and if a structure is located within fifty (50) feet of the right-of-way of any public street, road, or highway, after a public hearing in accordance with Section 17.037E(2) of the Howard County Zoning Regulations. No parking shall be located within ten (10) feet of any lot line except as may be shown on a site development plan approved by the Howard County Planning Board. All structures must be developed in accordance with a site development plan approved by the Howard County Planning Board.

Adequate planting and landscaping must be provided, as required by the Howard County Planning Board at the time a site development plan is submitted for approval, whenever employment center industrial areas are situated within one hundred (100) feet of a residential land use area.

7. PERMITTED USES - Section 17.031 D:

7D EMPLOYMENT CENTER LAND USE - INDUSTRIAL LAND USE AREAS

All uses permitted in industrial districts or industrial land use zones are permitted, including, but not limited to, all uses permitted in M-1 and M-R districts except, however, the uses only permitted in M-2 and T-2 districts are prohibited. Location of commercial uses ancillary to or compatible with permitted industrial uses and planned as an integral part of the pre-dominantly industrial area are permitted as approved by the Howard County Planning Board.

Location of railroad right-of-ways are specifically permitted on all parcels of this final development plan phase.

8. HEIGHT LIMITATIONS - Section 17.031 E:

8D INDUSTRIAL LAND USE AREAS

No structure shall be constructed within the area encompassed by this Final Development Plan Phase exceeding 50 feet in height from the highest adjoining ground elevation along the front of the structure, except, however, that structures may be constructed to any height provided such construction is in accordance with a site development plan approved by the Howard County Planning Board.

9. PARKING REQUIREMENTS - Section 17.031 E:

9D INDUSTRIAL LAND USE AREAS

Parking requirements for uses permitted under this Final Development Plan Criteria shall be as follows:

- a. Five (5) parking spaces shall be provided for each 1,000 square feet of net leasable area devoted to commercial retail sales uses including restaurants.
 - b. Two (2) parking spaces shall be provided for each 1,000 square feet of net leasable area contained within any building or buildings constructed upon land encompassed by this Final Development Plan Phase which are devoted to office uses.
 - c. One parking space for each 1 employees shall be provided for all sites devoted to industrial uses.
10. SETBACK PROVISIONS - Section 17.031 E:
- 10A. GENERALLY:
- a. Setbacks shall conform to the requirements of Section 6 above.
 - b. No other setback restrictions are imposed upon land within this Final Development Plan Phase.

11. MINIMUM LOT SIZES - Section 17.031 E:

As shown on subdivision plat in accordance with minimum lot sizes as may be required by the Howard County Planning Board.

12. COVERAGE REQUIREMENTS - Section 17.031 E:

12D INDUSTRIAL LAND USE AREAS

In no event shall more than 50 percent of the land included within any lot within this Final Development Plan Phase be covered by buildings or other major structures, except in accordance with a site development plan approved by the Howard County Planning Board. No coverage limitation is imposed upon the area used for sidewalks, paved parking areas, trees and shrubbery and similar minor structures.

TABULATION OF LAND USE

LAND USE	ACRES
EMPLOYMENT CENTER INDUSTRIAL	1.528
TOTAL	1.528

RECORDED ✓ PLAT BOOK 20 FOLIO 297
ON 4/11 1974

E.G.U.
SECTION 2 AREA 7

PETITIONER AND OWNER
THE HOWARD RESEARCH AND DEVELOPMENT CORPORATION
COLUMBIA, MARYLAND 21044

COLUMBIA


FINAL DEVELOPMENT PLAN PHASE 154
6TH ELECTION DISTRICT HOWARD COUNTY, MD.

January, 1974 SHEET 2 OF 3

FDP-154

DRWN. BY:
CHKD. BY:

COORDINATE		SCHEDULE
No.	NORTH	EAST
51	488,445.17	848,157.00
52	488,454.48	848,203.41
53	488,204.16	849,344.65
54	488,210.22	849,349.06
57	488,165.77	849,316.67
58	488,171.83	849,321.09
59	488,415.25	848,211.28
60	488,400.46	848,137.55
61	488,039.31	849,583.58
62	487,979.84	849,571.81



RECORDED FLAT BOOK 20 FOLIO 298
ON 9/11 1979 AMONG THE LAND RECORDS OF
HOWARD COUNTY, MD.

E.G.U.
SECTION 2 AREA 7
PETITIONER AND OWNER
THE HOWARD RESEARCH AND DEVELOPMENT CORPORATION
COLUMBIA, MARYLAND 21044

COLUMBIA

FINAL DEVELOPMENT PLAN PHASE 154
6TH ELECTION DISTRICT HOWARD COUNTY, MD.
SCALE 1" = 100' January, 1974 SHEET 3 OF 3

FDP-154 DRWN. BY:
CHKD. BY: