### MARYLAND HISTORICAL TRUST DETERMINATION OF ELIGIBILITY FORM

NR Eligible:	yes	K
	nο	

Property Name: Blandair		Inventory Number:	HO-33	
Address: 6651 Rt. 175	City: Columbia	Zip Cod	e: <u>2104</u>	4
County: Howard	USGS Topographic Map:	Savage		
Owner: Howard County Maryland	Is	the property being evalu	ated a distr	rict?y
Tax Parcel Number: 3 Tax Map N	Jumber: 36 Tax Account ID N	Number: 140 64 25 151		
Project:	Ager	ncy: Howard County De	pt. of Recre	ation and Pa
Site visit by MHT Staff: no	X yes Name: Thomas Reinha		January 4	
Is the property located within a historic dis	<del></del>			,
If the property is within a district	District In	ventory Number:		
NR-listed districtyes Eligible	districtyes District Na	me:		
Preparer's Recommendation: Contribu	ating resourceyesno Non	-contributing but eligible	e in another	r context
If the property is not within a district (or the Preparer's Recommendation: Eligib				
Criteria: XABXCXI	D Considerations:A_	BCDF	EF_	_GN
Documentation on the property/district is p	presented in:			
Description of Property and Eligibility D	etermination: (Use continuation sheet if ne	ecessary and attach map and p	hoto)	
Blandair is a 300-acre farm with about 20 dwelling house, built c. 1858, with an ori near the dwelling house and an agricultur garage (c. 1937) comprise the domestic g stone foundation. The first story has two rooms accessed by separate stairs. The athe mid-20 <sup>th</sup> centuries, including: a grana 1930), a hog house (signed 1939), a hay blandscape has been largely overgrown, but documentary evidence of earlier farm strategies.	ginal two-story wing. Outbuildings ral group. A smokehouse and slave of group. The quarter is notable. It is a rooms that communicate around a c gricultural group is a conglomeration ry, (c. 1844) a springhouse-dairy (c. barn (1942), and several tractor and out two unimproved lanes of early 19 <sup>th</sup>	are arranged in two groupuarter (both 1850's) and double-pen, sawn plank entral double fireplace. In of buildings ranging in 1850), two tenant house equipment sheds (all c. 1 h-cenutry date have surv	ppings, a dod i a partially structure of The second date from to s (1850's), 950). The sived. There	mestic ground collapsed on a raised listory has to the mid-19 <sup>th</sup> a barn (c. historic et is
The property is eligible for the National I agricultural parcel in Columbia, and retai house is an outstanding example of anteb	ns a significant collection of 19th an	d early 20th-century outh	uildings. T	The dwelling
MARYLAND HISTORICAL TRUST	<del></del>			
Eligibility recommended \( \frac{\frac{\chi}{\chi}}{\chi} \) Criteria: \( \frac{\chi}{\chi} \) A \( \frac{\chi}{\chi} \) B \( \frac{\chi}{\chi} \) C \( \frac{\chi}{\chi} \) Comments:	Eligibility not recommendedA	BCDI	EF_	_GNo
<u> </u>				
3kmta_	21	4/04		
Reviewer, Office of Preservat	ion Services	Date	- <del>-</del>	
Reviewer, NR Progr	'am	Date		

## MARYLAND HISTORICAL TRUST NR-ELIBILITY REVIEW FORM

Continuation Sheet No. 1

HO-33

the slaves. The interiors finishes of the house are well preserved, and its materials and design mark a transition from traditional handcrafts to more industrialized building trades. The slave cabin is an almost pristine example of the type having interior whitewash and second-floor board partition wall. The outbuildings chronicle significant trends in local and national agriculture from grain production in the early 19<sup>th</sup> century, to dairying in the late 19<sup>th</sup> century to the implementation of farm machinery and organic fertilizers. This physical history of agriculture can be extended back through the known archaeological resources on the property.

Prepared by:

Date Prepared: 2/4

HO-33 BLANDAIR Private Columbia

circa 18 Century

Blandair is a five bay wide, two bay deep, two and a half story brick (laid in English garden wall brick bond) gabled roof structure with twin chimneys centered into the roof line lying on each side of the central hall which connects identical north and south rectangular, double paneled entrances surmounted by five lite transoms.

An exceptionally fine corbeled brick cornice decorated with a row of header brick dentils is rather unique. A smaller kitchen east wing lies on the east wall of the main house. The interior of the house features random width Georgia pine floors, outstanding marble mantle pieces, and an exceptionally fine staircase which runs all the way to the attic with mahagany bannister and oak spindles.

Assocaited with John C. Weems who later became a member of congress and Mr. Theodoric Bland, Chancellor of Maryland Blandair is presently owned by Mrs. Henry Smith.

#### MARYLAND HISTORICAL TRUST WORKSHEET

#### NOMINATION FORM

for the

NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

	1.	NAME								
	-	COMMON:								
		Blandair								
•		AND/OR HISTORIC:								
	2.	LOCATION								
•	STREET AND NUMBER:									
		MD Route 175, Litt	le Patuxent 1	Parkway		*				
	CITY OR TOWN:									
		STATE		co	OUNTY:					
	F-1177	Maryland			Howard					
•	3.	CLASSIFICATION	<u>,                                      </u>			<u> </u>				
S		CATEGORY (Check One)		OWNERSHIP			ACCESSIBLE TO THE PUBLIC			
Z		☑ District ☐ Building	Public P	Public Acquisition:		○ Occupied	Yes:			
0		Site Structure	☑ Private	☐ In Process	ı	Unoccupied	Ø Restricted			
		☐ Object	☐ Both	☐ Being Con	sidered	Preservation work	☐ Unrestricted			
						in progress	□ No			
U		PRESENT USE (Check One or h	Tore as Appropriate)	t		<del></del>				
$\supset$		🖎 Agricultural 🔲 Ge	evernment [	] Park		Transportation	Comments			
œ		Commercial In	dustrial K	Private Residence						
<b> </b>		☐ Educational ☐ Mi	litory	] Religious		(0,000,000,000,000,000,000,000,000,000,				
S		Entertainment Mu	150um [	Scientific						
z	4.	OWHER OF PROPERTY			- 1500 - <b>X</b> 600					
_	<u> </u>	OWNER'S NAME:		······································	<del></del>	The second of th				
		Mrs. Henry E. S	mith	•						
in		STREET AND NUMBER: Blandair Rout	e 175							
Ш		CITY OR TOWN:	e 1/5		,					
<b>.</b>		Columbia			Maryland 21044					
	5.	LOCATION OF LEGAL DESC	RIPTION							
	-	COURTHOUSE, REGISTRY OF		<del></del>						
		Hall of Records								
		STREET AND NUMBER:								
		Howard County C	ourthouse							
		CITY OR TOWN: Ellicott City			STATE	210/2				
		<u>.                                    </u>	. f. O	5 7 75	Maryland 21043					
	6.	Title Reference of REPRESENTATION IN EXIST	DI CUTTENT			#): See Tax	Map 36			
	<u> </u>	TITLE OF SURVEY:	MO SURVEYS	150/250 p.	. 3	· · · · · · · · · · · · · · · · · · ·				
		Howard County H	istoric Site	s Inventory						
	•	DATE OF SURVEY: 1977 Federal State County Local								
		DEPOSITORY FOR SURVEY RECONDS:								
		Maryland Historical Trust								
		STREET AND NUMBER:								
		21 State Circle								
		CITY ON TOWN!			STATES		· .			
		Annapolis			Maryland 214					

7. DESCRIPTION			1 <u></u>				
				(Check One)	<del>-</del> -		
	Excellent	☐ Good	☐ Fair	☐ Deteriorate	d 🔲 Ruins	Unexposed	
CONDITION		(Check Or	10)		(Che	ick One)	
	☐ Alte	red	XX Uncitered	1	☐ Meved	Original Site	1

DESCRIBE THE PRESENT AND ORIGINAL (If known) PHYSICAL APPEARANCE

Blandair is composed of an east and west brick (laid in English garden wall brick bond) wing, the west wing of which is grander in scale, is five bays wide, two bays deep, two and a half stories high with gabled roof (running east-west) holding two central brick chimneys with corbeled edges. A central hall connects the central north and south rectangular double paneled entrance doors which are surmounted by five lite transoms and flanked by two square columns decorated with a single concave flute between which are held two vertical side lites. This entire door is separated from the five lite transom by a projecting wooden lintel. The north and south entrance doors are identical with the exception of the flat roofed portico over the north door which is held by two square posts and crowned by a cornice, above which is a bannister connected by an east and west post and pilaster. A central second floor french door opens on to this small balacony. Basement windows lie under the two east and two west bays of the north and south elevations.

The east wing holds four first and second floor windows on the north walland a north bay rectangular entrance on the south wall. A rectangular gabled roof nine lite casement dormer window is placed in the center of the roof of the south elevation of the east wing, and decorated with a broken pediment. A square brick chimney lies west of the dormer. A central brick chimney is inset into the east wing flanked by third story six lite casement windows.

The west wing holds a north and south entrance approached by five wooden stairs and flanked by two north and south first floor windows respectively with five north and south second floor windows lying above. Its east and west walls hold two third floor windows in the A line of the gabled roof.

Rectangular double-hung fenestration is vertically alligned and proportionall scaled, with six-over-six lites, decorated with flat arched stretcher brick lintels, projecting stone sills and black shutters. Exceptions are the four jib windows located on the second floor of the south facade which originally opened up to a second floor porch which no longer exists and are presently protected by a black wooden railing on the exterior of the house. The middle second floor window on the south elevation of the west wing holds four-over-four lites.

The building is characterized by exceptionally fine brick decoration. A brick water table runs along the entire perimeter of both wings, as well as a brick belt course shortly below the roof line which is terminated at the roof line by a cornice composed of two rows of corbeled bricks decorated with a row of header brick dentils. This unusual cornice which decorates both the east and west wing is quite unique and noteworthy architectually.

Box wood gardens lie outh-east of the house which is surrounded by a grove of mature trees and shrubbery.

Dependencies lie east of the property. A one story gabled roof (running north-south) simple log house was once used for a smoke house. A stone and frame barn lies south of it, both of which are very close to the east wall of the east wing.

North east of these two buildings lies a gabled roof (running north-south) one and a half story high log house with a central square brick chimney once used as a slave quarters. Its west wall holds two rectangular wooden entrances. The north and south elevations hold a single double-hung rectangular first floor window with six-over-six lites and a four lite second floor square casement window.

Further north-east and a distance from the house lie barns and two old houses with modern additions; 1) a stone house with recent frame addition and 2) a frame building with concrete block addition added some twenty-five years ago. Part of the frame structure was torn down when the addition was put on. The sizes of the lumber were randam and put together with wooden pegs. A granary stands here too put together with logs.

The property has been surrounded by the new town of Columbia and divided by the new route 175. The house and land have been designated as a Critical Area of State Concern suitable for preservation. It is hoped this will prevent any further encroachment to the property.

The interior features original randam width Georgia pine floors, open bible and cross paneled doors and notable marble mantles which feature curvilinear patterns. These mantles were supposedly a wedding gift.

An outstanding staircase runs all the way to the attic and features a black walnut knewel post, oak spindles and mahogany bannister.

TERIOD (Check One or More #s	Appropriate)		•
Pro-Columbian	16th Century	₩ 18th Century	20th Contury
15th Century	17th Century	19th Contury	<u> </u>
PECIFIC DATES (If Applicat	ole and Known)		
PERSON SIGNIFICANCE (Ch	ook One or Hare to Aspeopl	eta)	
Abariginal	■ Education	☐ Political	Urban Planning
Prohista is	Enginearing	Roligion/Phi-	Other (Specity)
Historic'	Industry	losophy	
Agriculture	☐ Invention	Science	*****
Architecture	Landscape	Sculpture	<del></del>
□ Ar	Architecture	Social/Human-	
Commerce	Literature	itarian	•
Communications	Military	Theater	
Conservation	Music	Transportation	

#### STATEMENT OF SIGNIFICANCE

According to Celia Holland, local Howard County Historian, Blandair is located on a tract of land once a part of "Talbott's Resolution Manor" which was surveyed in 1714 by John and Elizabeth Talbott and comprised 1087 acres.

It was later acquired by Nicholas Gassaway, who in his will of 1757 bequeathed to "his three sons, Benjamin, Richard and Robert Gassaway, all my tract called "Talbotts Resolution Manor". Witnesses of this will were John Dorsey (of John) and Caleb Dorsey (of John). These witnesses locate the testator near the old Brick Church.

During the late 1700's Blandair was acquired by John C. Weems and known as LaGrange. He was a 1894 graduate of St. John's College in Annapolis who later became a member of Congress. It was he who sold the property to Theodoric Bland in 1828.

Theodoric Bland had been authorized to survey a canal route connecting Baltimore City with the Susquehana River. Later he became Chancellor for Maryland and also served as Consul to Brazil by his wife, Sarah Glen, widow of Major Jacob Davies of Baltimore. In 1835 Sarah Battaile Fitzhugi Bland, his daughter married Commodore Isaac Mayo, who distinguished himself in the Mexican War. In 1 46 Theodorick Bland, Chancellor of Maryland diel in his 70th year. The lovely marble fireplaces throughout the house were supposedly a wedding gift, perhaps to the Chancellor's daughter, Sarah.


Architecturally Blandair has some unusual and rather unique brick decoration for a Howard County mansion. A double decorative brick course forms a closing for the A on each side of the gabled roof which runs east-west. A corbeled brick cornice lies along the eaves of the roof on the north and south elevation decorated by a row of header brick dentils. Otherwise the entire house is laid in English garden wall brick bond as compared to Howard Lodge's entire use of flemish brick bond.

Blandair is surrounded by many of its original dependencies and sits on a hill commanding a view of the surrounding town of Columbia. This area of some 300 acres has been split in half by Route 175 which passes through the middle of the property. It is the owner's earnest desire that this land be set aside for agricultural use and not development which is the present zoning recommendation. The area has been recommended for inclusion to the State Critical Areas Program and should be considered for inclusion into


the National Register and any future local landmark legislation.

Local groups and individuals interested in farm preservation should also consider Blandair for inclusion into their program as a further aid in its preservation.

9.	MAJOR!	BIBLIOGRAPHICAL F	REFEREN	ICES .	<del></del>			
· T				<del></del>	Co	ounty, Maryland. Un	iversity Park 1975.	<,
	Stein, Charles. <u>Origin and History of Howard County, Maryland</u> . Baltimore, 1973.							
						and Howard Counties	Baltimore,	1972.
			Henry	Smith at Bl	aņ	ndair, February 16,	1977.	
10.		RAPHICAL DATA			7 —	LATITUDE AND LONG	THOS COORDINAT	
		LATITUDE AND LONGI'			OR	DEFINING THE CENTER		
G	CORNER	LATITUDE		ONGITUDE	]~	LATITUDE	LONGITUD	E
		Degrees Minutes Second	s Degree	s Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes	Seconds
	NW NE			· -				-
	SE		,   .	• •		·		
_	SW	9 ,	.   .	o , ,	<u></u>	<u> </u>		
L	APPROXI	IMATE ACREAGE OF N	OMINATED	PROPERTY:				
	Acrea	age Justifica	ation:	:				
<b>∤</b> 1								
1	Pleas	e See Tax Map	36 p.	. 3				
		156/256	299.457	7 acres				
l I								
								•
1								:
}	•	• -						!
	I							•
	• <del>-</del>						•	•
							,	··•
		PREPARED BY	-					
1		ND TITLE: Ta B. Thompson,	Archiv	vic+				
}	ORGANI		AI CIII	VISL		·	DATE	
		ehensive Plann	ing Sec	ction				
Ì		AND NUMBER:						
		Courthouse Dri	ve		<del></del> -			<u> </u>
·	CITY OF				- 1	STATE Maryland		21043
12		cott City				rial y land		
E	Stat	te Liaison O	ficer	: Review:		(Office Use Only)		
	Significance of this property is:							
ļ		National [		Local	-			
	}					<del></del>		,
	Signature							
	Ι ,							



# MAP OF FLOOD-PRONE AREAS





HO-33
BLANDAIK
CNORTH) FEB. 1977

CLEGRA BARNES THOMPSON FLANNING CONSULTANT HISTORICAL SITES SUBJEY