

Fulton House
3926 Old Columbia Pike
HO-628

This 2 1/2 story American Four Square was built in 1930 and sits about 100 feet north of the Old Columbia Pike right of way on 0.83 acres. The house displays many of the characteristics of this early 20th century style including its high hipped roof central dormer and symmetrical shape.

This house is significant as an early example of planned suburban development in Howard County. It is part of an important intact corridor on the outskirts of Ellicott City lined with early 20th century houses.

While several planned developments were built along the B&O Railroad's Washington branch near Laurel in the late 19th century, this development was one of the first of its type in the northern section of the county. Unlike many neighboring counties, Howard County never experienced the housing boom created by the arrival of rail service. This small development along Old Columbia Pike represents some of the few commuter oriented suburban housing built in the county before World War II.

Fulton House
3926 Old Columbia Pike
HO-628

HISTORIC PERIOD CONTEXT:

Region: Piedmont
Period: Modern Period
Theme: Architecture, Landscape Architecture and Community Planning
Resource Type: Residence/rural vernacular
Site Types: Standing structures

**Maryland Historical Trust
State Historic Sites Inventory Form**

**MARYLAND INVENTORY OF
HISTORIC PROPERTIES**

Survey No. HO-628

Magi No.

DOE yes no

1. Name (indicate preferred name) Fulton House

historic

and/or common Fulton House

2. Location

street & number 3926 Old Columbia Pike (MD987) not for publication

city, town Ellicott City vicinity of congressional district Sixth

state Maryland county Howard

3. Classification

Category	Ownership	Status	Present Use
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture <input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial <input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational <input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment <input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government <input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial <input type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input checked="" type="checkbox"/> no	<input type="checkbox"/> military <input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Williams P. and Melissa Fulton

street & number 3926 Old Columbia Pike telephone no.: (410) 465-8367

city, town Ellicott City state and zip code Maryland 21043

5. Location of Legal Description

courthouse, registry of deeds, etc. Howard County liber 1133

street & number 8360 Court Avenue folio 112

city, town Ellicott City state Maryland

6. Representation in Existing Historical Surveys

title

date federal state county local

depository for survey records

city, town state

7. Description

Survey No. HO-628

Condition		Check one	Check one	
<input checked="" type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input checked="" type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site	
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

This 2 1/2 story American Four Square was built in 1930 and sits about 100 feet north of the Old Columbia Pike right-of-way on 0.83 acres. The house displays many of the characteristics of this early 20th century style including its high hipped roof central dormer and symmetrical shape.

The house is three bays wide and two bays deep. The fenestration on the facade is symmetrical with pairs of windows flanking the door and a single window on the second story. A hipped roof gable dormer holds a pair of windows. A two-bay by one bay sun room with a flat roof extends from the west side.

A solid wood door is surmounted by a projecting round arched hood supported by scrolled brackets which covers the brick entry steps. All of the windows are double hung 1/1 sash and, with the exception of the dormer windows, are flanked by panelled shutters. A shed roofed vestibule with a sliding glass door which is not original extends from the east corner of the north side.

There are three other openings on the north side, a pair of windows on the first floor and two evenly spaced windows on the second floor. The window on the westernmost corner of the north side was probably removed.

There is a recently added slender exterior brick chimney on the north end of the west side a door and window flank the chimney. The house rests on a stuccoed cement-covered concrete foundation and has a slate roof.

There is also a two-bay gabled-roof garage and a wood frame gazebo north of the house that are not original. The rear of the property is heavily wooded with mature trees where the hillside drops down to the stream valley.

8. Significance

Survey No. HO-628

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates	Builder/Architect
check: Applicable Criteria: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D and/or	
Applicable Exception: <input type="checkbox"/> A <input type="checkbox"/> B <input checked="" type="checkbox"/> C <input type="checkbox"/> D <input type="checkbox"/> E <input type="checkbox"/> F <input type="checkbox"/> G	
Level of Significance: <input type="checkbox"/> national <input type="checkbox"/> state <input checked="" type="checkbox"/> local	

Prepare both a summary paragraph of significance and a general statement of history and support.

SIGNIFICANCE

Although aluminum siding covers the wood frame, the house retains its overall integrity and is a significant example of vernacular Prairie Box design.

This house is significant as an early example of planned suburban development in Howard County. it is part of an important intact corridor on the outskirts of Ellicott City lined with early 20th century houses.

While several planned developments were built along the B&O Railroad's Washington branch near Laurel in the late 19th century, this development was one of the first of its type in the northern section of the county. Unlike neighboring counties, Howard County never experienced the housing boom created by the arrival of rail service. This small development along Old Columbia Pike represents one of the few built in the county before World War II.

Like many prosperous merchants in downtown Ellicott City, August Stigler, a wholesale flour dealer, moved outside of town to the hillside along Columbia Pike in the early 1920s. After purchasing 20 acres from Caleb Rogers in 1928, Stigler subdivided his land into 12 lots of nearly equal size--roughly 1/3 of an acre. The lots were all 70 feet wide and about 200 feet deep abutting the Cat Rocks Branch stream valley.

According to his son, August Stigler Jr., Stigler capitalized on the success of the street car line which connected Ellicott City with Baltimore. He believed that families would purchase lots and build medium sized homes within walking distance of the Ellicott City station.

Construction on these lots began in 1928, but at least three lots remained empty for many years because of the Depression. Land Records indicate this house was built in 1930. Although no documentation has been found to confirm their origin, Stigler's son believes a number of the houses eventually built were ordered from popular catalogues of the period and their styles suggest that this is a valid theory.

9. Major Bibliographical References

Survey No. HO-628

Howard County Land Records
Interview with August Stigler, Jr.

10. Geographical Data

Acreeage of nominated property .83

Quadrangle name Ellicott City, MD

Quadrangle scale 1:24000

UTM References do NOT complete UTM references

A	<input type="text"/>	<input type="text"/>	<input type="text"/>
	Zone	Easting	Northing

B	<input type="text"/>	<input type="text"/>	<input type="text"/>
	Zone	Easting	Northing

C	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

D	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

E	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

F	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

G	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

H	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

11. Form Prepared By

name/title Amy Worden, Historic Sites Surveyor

organization	<u>Howard County Department of Planning and Zoning</u>	date
--------------	--	------

street & number	<u>3430 Courthouse Drive</u>	telephone	<u>(410) 313-2037</u>
-----------------	------------------------------	-----------	-----------------------

city or town	<u>Ellicott City</u>	state	<u>Maryland</u>
--------------	----------------------	-------	-----------------


The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

MARYLAND HISTORICAL TRUST
DHCP/DHCD
100 COMMUNITY PLACE
CROWNSVILLE, MD 21032-2027
301-514-7600

3926
Old Columbia Pike
Ellicott City Quad
HO-628
HOWARD COUNTY





1

2

3

4

5

6