

HO-802, Stone boundary wall fragment  
Ellicott City vicinity, Howard County  
Date unknown  
Private access

#### CAPSULE SUMMARY

On a piece of property off of Ilchester Road, adjacent to Patapsco State Park, a fragment of an old stone boundary wall is nearly hidden beneath the fallen leaves and branches that litter the forest floor. The wall begins just to the northwest of a gravel driveway that serves several home sites and runs northwest for approximately 150 feet before it turns a 90 degree angle and runs northeast at least another 250 feet along the edge of a ridge. The wall is constructed of native material, probably granite, of a variety of sizes and shapes. Stones range in size from 4" in diameter to 18" or more in some locations. They are both angular and rounded and are not worked at all. The wall was not dry laid or laid with mortar in regular courses but instead simply mounded to form an A-shape in profile. Currently the wall is an average of 18" tall and between three and four feet thick at its base.

This boundary wall fragment is significant under criteria A as an example of a once common landscape feature that has been all but obliterated from the landscape. Such rudimentary walls built entirely of native material were probably common in the county, especially in the area along the Patapsco River where the raw material is extremely plentiful. But the extensive development of the eastern half of the county has transformed the forests, farms and hills into graded townhouse lots and manicured subdivisions and there are no surviving examples of such boundary walls in the area of the county bounded on the west by I-95 and the east by the Patapsco River and the county line.

# Maryland Historical Trust

## Maryland Inventory of Historic Properties Form

Inventory No. HO-802

### 1. Name of Property (indicate preferred name)

historic Stone boundary wall fragment  
 other

### 2. Location

street and number behind 4635 Ilchester Road not for publication  
 city, town Ellicott City X vicinity  
 county Howard

### 3. Owner of Property (give names and mailing addresses of all owners)

name Robert A. Hale  
 street and number 4635 Ilchester Road telephone  
 city, town Ellicott City state MD zip code 21043

### 4. Location of Legal Description

courthouse, registry of deeds, etc. Howard County Courthouse tax map and parcel: Map 31, P 623  
 city, town Ellicott City liber 1267 folio 356

### 5. Primary Location of Additional Data

- Contributing Resource in National Register District
- Contributing Resource in Local Historic District
- Determined Eligible for the National Register/Maryland Register
- Determined Ineligible for the National Register/Maryland Register
- Recorded by HABS/HAER
- Historic Structure Report or Research Report
- Other

### 6. Classification

Category	Ownership	Current Function	Resource Count	
			Contributing	Noncontributing
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> agriculture		
<input type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade		<input type="checkbox"/> 1 buildings
<input checked="" type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense		<input type="checkbox"/> sites
<input type="checkbox"/> site		<input type="checkbox"/> domestic	<input type="checkbox"/> 1	<input type="checkbox"/> structures
<input type="checkbox"/> object		<input type="checkbox"/> education		<input type="checkbox"/> objects
		<input type="checkbox"/> funerary	<input type="checkbox"/> 1	<input type="checkbox"/> Total
		<input type="checkbox"/> government		
		<input type="checkbox"/> health care		
		<input type="checkbox"/> industry		
		<input type="checkbox"/> landscape		
		<input type="checkbox"/> recreation/culture		
		<input type="checkbox"/> religion		
		<input type="checkbox"/> social		
		<input type="checkbox"/> transportation		
		<input type="checkbox"/> work in progress		
		<input type="checkbox"/> unknown		
		<input checked="" type="checkbox"/> vacant/not in use		
		<input type="checkbox"/> other:		
			Number of Contributing Resources previously listed in the Inventory	
			0	

---

## 7. Description

Inventory No. HO-802

---

### Condition

- |  |                                       |
|--|---------------------------------------|
| <input type="checkbox"/> excellent       | <input type="checkbox"/> deteriorated |
| <input type="checkbox"/> good            | <input type="checkbox"/> ruins        |
| <input checked="" type="checkbox"/> fair | <input type="checkbox"/> altered      |
- 

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

On a piece of property off of Ilchester Road, adjacent to Patapsco State Park, a fragment of an old stone boundary wall is nearly hidden beneath the fallen leaves and branches that litter the forest floor. The wall begins just to the northwest of a gravel driveway that serves several homesites and runs northwest for approximately 150 feet before it turns a 90 degree angle and runs northeast at least another 250 feet along the edge of a ridge. To the north of the wall, the topography drops off sharply towards the Patapsco River. The wall was observed to continue on, bending to the east but it was surveyed as a result of a proposed development and the neighbors' hostility prevented the surveyor from following the wall off of the property being developed. The wall runs through a mature hardwood forest and probably meanders onto park land. The existing house on the 5-acre parcel containing the stone wall fragment is not historic.

The wall is constructed of native material, probably granite, of a variety of sizes and shapes. Stones range in size from 4" in diameter to 18" or more in some locations. They are both angular and rounded and are not worked at all. The wall was not dry laid or laid with mortar in regular courses but instead simply mounded to form an A-shape in profile. Currently the wall is an average of 18" tall and between three and four feet thick at its base. The short section running northwest is the portion of the wall that is the most intact at this point. The portion that runs northeast along the edge of the ridge incorporates some very large boulders but some sections of this portion of the wall have tumbled down the hillside. There is also one area directly to the north of and adjacent to the wall where the ground is covered with rocks of the same size and shape as those used in the wall. Though rocks of the type used in the wall litter the ground throughout this forested area, the concentration of stones in this particular spot is unusually high. These stones may have been incorporated into the wall at one point and been intentionally dismantled and spread across the ground for some reason. Someone may have dismantled the wall to reuse stones of a particular size and shape for something else.

## 8. Significance

Inventory No. HO-802

Period	Areas of Significance	Check and justify below			
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts	
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy	
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government	
<input checked="" type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input checked="" type="checkbox"/> landscape architecture	<input type="checkbox"/> religion	
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	<input type="checkbox"/> science	
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	<input type="checkbox"/> social history	
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime industry	<input type="checkbox"/> transportation	
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	<input type="checkbox"/> other:	
<b>Specific dates</b>	unknown	<b>Architect/Builder</b>	unknown		
<b>Construction dates</b>	unknown				

Evaluation for:

National Register

Maryland Register

not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance reports, complete evaluation on a DOE Form - see manual.)

This boundary wall fragment is significant under criteria A as an example of a once common landscape feature that has been all but obliterated from the landscape. Such rudimentary walls built entirely of native material were probably common in the county, especially in the area along the Patapsco River where the raw material is extremely plentiful. But the extensive development of the eastern half of the county has transformed the forests, farms and hills into graded townhouse lots and manicured subdivisions and there are no surviving examples of such boundary walls in the area of the county bounded on the west by I-95 and the east by the Patapsco River and the county line. There are probably (hopefully) other fragments like this one along the northern county line along the river between Ellicott City and Elkridge that remain to be documented, but this region is also being subjected to heavy residential development.

This wall was probably constructed as a boundary wall between two separate parcels or land grants. At this point it is impossible to say when it was constructed, it could be as recent as the early 20th century but it could just as easily be as old as the 18th century. These walls are an important part of the historic landscape and the remaining fragments of them should be preserved. Documenting where they are, or were, on the landscape can inform our understanding of settlement patterns and early land surveying. In such cases where a corner is intact, as with this wall fragment, noting its location on a map can assist with future research on surrounding parcels by potentially providing a known point on the property line to compare to deed records.

---

## 9. Major Bibliographical References

---

Inventory No. HO-802

See continuation sheet.

---

## 10. Geographical Data

---

Acreage of surveyed property 5

Acreage of historical setting unknown

Quadrangle name Savage

Quadrangle scale 1:24000

---

### Verbal boundary description and justification

Tax map 31, parcel 623 was the only parcel surveyed as a result of a proposed development. The existing house on the property is not historic.

---

## 11. Form Prepared By

---

name/title Kristin Hill, Historic Sites Surveyor

organization Howard County Department of Planning and Zoning

date 10/20/03

street and number 3430 Court House Drive

telephone 410-313-4335


city or town Ellicott City

state MD zip code 21043

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust  
DHCD/DHCP  
100 Community Place  
Crownsville MD 21032  
410-514-7600



HO-802

**Locational Map**  
HO-802, Stone boundary wall fragment  
Ellicott City vicinity, Howard County  
USGS Topographic Quadrangle  
Savage, 1:24000, 1957

4345

2.8 MI. TO U.S. 17  
510  
FEET

4343

1.3 MI. TO U.S. 17

1273

4341

ELKRIDGE 2.9 MI.  
BALTIMORE 9.4 MI.



HO-802 Stone boundary wall fragment  
behind 4635 Elchester Rd, Ellicott City vic.

Howard County, MD

49 21-01 NICHAN 021

Kristin Hill, 10/03

Negative at MOSHPO

corner of the wall, looking SW

118



HO-802 Stone boundary wall fragment  
behind 4635 Ilchester Rd, Ellicott City vic.

Howard County, MD

Kristin Hill, 10/03

Negative at MDSHPO

corner of the wall, looking SW

2/8



H0-202 stone boundary wall fragment  
behind 4635 Ilchester Rd, Elliott City. v.c.

Howard County, MD

Kristin Hill, 10/03

Negative at MDSHPD

Looking northeast along the wall

3/8



HO-802 stone boundary wall fragment  
behind 4635 Ilchester Rd, Ellicott City vic.

Howard County, MD

Kristin Hill, 10/03

Negative at MDSHPD

48 21481 NININ 621

Looking northeast along the wall

4/8



HO-802 stone boundary wall fragment  
behind 4635 Ilchester Rd, Ellicott City, vic.

Howard County, MD

45 21 +81 R11111 621

Knstik Hill, 10/03

Negative at MDSTHPD

corner of the wall, looking SW

S/8



HO-802 stone boundary wall fragment

behind 4635 Ilchester Rd, Ellicott City, Md.

Howard County, MD

Kristin Hill, 10/03

Negative at MDSHPD

Looking S-SE across scattered rocks at wall running across  
middle of photo.

6/8



HO-802, stone boundary wall fragment  
behind 4635 Ilchester Rd, Ellicott City, vic

Howard County, MD

43 21+82 NNNNN 621

Knott Hill, 10/03

Negative at MDSHPD

Looking S-SE across scattered rocks at wall running across  
middle of photo.

7/8



HO-802, Stone boundary wall fragment  
behind 4635 Ilchester Rd, Ellicott City, vic.  
Howard County, MD

46 21+01 NNNNN 621

Kristin Hill, 10/03  
Negative at MDSHPO

rocks from the wall (?) scattered beside wall, looking north

8/8