


ROADS, STORM DRAINS & GRADING

THE WESTWOODS OF CHERRY GROVE


HOWARD COUNTY, MARYLAND



Vicinity Map
Scale: 1" = 2000'

SHEET INDEX:

- Title Sheet
- Colton Court - Plan & Profile
- Old Sawmill Road - Plan & Profile
- Grading, Sediment Control & Forest Conservation Plan
- Grading, Sediment Control & Forest Conservation Plan
- Grading, Sediment Control & Forest Conservation Plan
- Grading, Sediment Control & Forest Conservation Plan
- Forest Conservation Notes and Details
- Forest Conservation Plan - OFFSITE RETENTION ON Holtzinger Property
- Landscape Plan
- Stormwater Management Details
- Stormwater Management Details
- Stormwater Management Details
- Stormwater Management Details
- Stormwater Management Details
- Storm Drain Profiles
- Sediment Control Notes and Details
- Proposed SWM/Storm Drain Drainage Area Map



GENERAL NOTES:

- All construction shall be in accordance with the latest standards and specifications of Howard County plus MSHA standards and specifications if applicable.
- The contractor shall notify the Department of Public Works/Bureau of Engineering/Construction Inspection Division at (410) 313-1880 at least five (5) working days prior to the start of work.
- The contractor shall notify "Miss Utility" at 1-800-257-7777 at least 48 hours prior to any excavation work being done.
- Traffic control devices, marking and signing shall be in accordance with the latest edition of the Manual of Uniform Traffic Control Devices (MUTCD). All street and regulatory signs shall be in place prior to the placement of any asphalt.
- The existing topography is taken from aerial survey with two foot contour intervals prepared by Wings Aerial Mapping Co., dated 3/26/98.
- The coordinates shown herein are based on NAD '83/91 Maryland Coordinate System as projected by Howard County Geodetic Control Stations Nos. 13HA & 20B2.
(Meters x 3.280833333 = Feet; Feet x 0.3048006096 = Meters)
No. 13HA N 589965.189 E 128594.906 Elev. 566.35
No. 20B2 N 589346.299 E 1287505.584 Elev. 577.924
- Water is private.
- Sewer is private.
- Stormwater management pond numbers 1 and 2 are extended detention facilities that will be owned by "The Westwoods of Cherry Grove Homeowners Association" (HOA), and jointly maintained by the HOA and Howard County, Maryland. Stormwater management pond number 3 is a detention facility that will be privately owned and jointly maintained by the HOA and Howard County, Maryland.
- The floodplain study for this project was prepared by R.M. Mochi Group, P.C., dated February 1999, and was approved on July 16, 1999.
- The wetlands delineation study for this project was prepared by M.A. Dirks & Co., Inc., dated February 1999 and was approved on July 16, 1999.
- The traffic study for this project was prepared by Lee Cunningham and Associates, Inc., dated December 1998 and was approved on July 16, 1999.
- Unless otherwise noted all BRLs shown are standard for RC zoning district.
- The Contractor shall contact the Construction Inspection Division 24 hours prior to commencement of any work at 410-313-1880.
- The existing gravel driveway to the Bounds property will be maintained in place and open for use until Colton Court is completed and the Bounds property is connected. Particular attention will be paid to assuring minimal disturbance to Bounds' traffic at the point where Colton Court and the gravel driveway intersect.
- Project background information:
a. Zoning: RC-BEO
b. Gross Area of Tract: 63.27 Ac.
c. Net Area of Tract: 62.02 Ac. (63.27 Ac. - 1.25 Ac. (Parcels D&E))
d. Area of Proposed Lots/Parcels: 60.74 Ac.
e. Area of Proposed R/W: 2.53 Ac.
f. Number of Proposed Lots: 30 Buildable Lots, 1 Build. Pres. Parcel, 1 Open Space Lot, 2 Non-Build. Pres. Parcels & 2 Parcels
g. Open Space Required: 3.10 Ac.
Open Space Provided: 3.10 Ac.
- The existing utilities are based on Howard County contract drawings.
- 19.4 AC OF FOREST RETENTION AREA IS PROVIDED ON-SITE. FINANCIAL SURETY FOR THE ON-SITE FOREST RETENTION AREA WILL BE IN THE AMOUNT OF \$84,507
- 10.2 AC. OF FOREST RETENTION AREA IS PROVIDED OFF-SITE ON THE HARRISON PROPERTY SEE SHEET 9 FOR LOCATION OF SITE. FINANCIAL SURETY FOR THE OFF-SITE FOREST RETENTION AREA WILL BE IN THE AMOUNT OF \$44,432. *AKA HOLTZINGER
- FINANCIAL SURETY FOR THE REQUIRED 122 LANDSCAPE TREES, IN THE AMOUNT OF \$23,400 IS PART OF THE DEVELOPER'S AGREEMENT.
- PARCEL D+E ARE FOR FRONTAGE + ACCESS TO PARCEL 109 (SAVAGE PROPERTY). THESE PARCELS WILL BE CONVEYED TO PARCEL 109 AT THE TIME THE WESTWOODS OF CHERRY GROVE WILDLIFE PRES. AREA IS COMPLETED.
- CONTACT THE HOWARD COUNTY TRAFFIC ENGINEERING DIVISION (410) 313-2430 FOR SPECIFIC DIRECTIONS ON STUPEL FOR ROAD CONNECTIONS AT JENNINGS CHAPEL ROAD.

APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Andrew M. Quack 11/3/00
CHIEF, BUREAU OF HIGHWAYS DATE

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Cindy Hamilton 11/3/00
CHIEF, DIVISION OF LAND DEVELOPMENT DATE

Mike Roman 11/6/02
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

OWNER / DEVELOPER
MARSHALL W. NICHOLS
c/o R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD 21774
(301) 865-5858

ENGINEER / SURVEYOR
R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD 21774
(301) 865-5858
Attn: Mr. Robert Mochi, P.E.



The Westwoods of Cherry Grove
Lots 5 through 35
Non-Buildable Preservation Parcels A & C AND F
Buildable Preservation Parcel B
Parcels D & E
Election District No. 4 Howard County, Maryland
Tax Map 13 Grid 15 Part of Parcel 46
Scale: 1" = 200' January 2000
Previous Files: F-92-142 & SP-99-09

project	98006.13	date	12-18-99
illustration	KBM	engineering	PFB
scale	1" = 200'	approval	RM




no.	3	date	10/04/00
description	REVISED PER DPZ COMMENTS/MTLA SUBMITTAL	revision	7/28/99
revision	1	description	1-14-00
revision	0	description	

THE WESTWOODS OF CHERRY GROVE
ELECTION DISTRICT No. 4
HOWARD COUNTY, MARYLAND
TITLE SHEET

R.M. MOCHI GROUP, P.C.
P.O. Box 10
New Market, MD 21774-0010
(301) 865-5858
Fax: (301) 865-5111

THE PAD IS TO BE MAINTAINED BY THE H.O.A. IT SHALL NOT BE COVERED OR ANY WALLS ERECTED SO THAT SIGHT DISTANCE IS NOT AFFECTED.

TEMPORARY TRAFFIC CONTROL SHALL BE MAINTAINED DURING CONSTRUCTION IN ACCORDANCE WITH MSHA STANDARDS FOR HIGHWAYS AND INCIDENTAL STRUCTURES STANDARDS: STD. No. MD 104.04-02 MD 104.31-02








COLTON COURT - ROADSIDE DITCH DATA

BEGIN STATION	END STATION	Q10 (CFS)	V10 (FPS)	SLOPE	ROADSIDE DITCH LINING
0+00	1+45	0.68	2.20	3.96%	ECM #
0+00	1+45	0.13	1.46	3.95%	ECM #
1+45	5+00	1.33	2.46	3.40%	ECM #
1+45	5+00	0.86	2.21	3.40%	ECM #
5+00	6+21	2.71	2.41	2.00%	ECM #
5+00	6+21	1.20	1.97	2.00%	ECM #

COLTON COURT - DRIVEWAY CULVERTS

Lot	Slope (%)	Q10 (cfs)	DW Pipe Size
5	T2VC	0.0	NO PIPE
6	3.20	1.0	STANDARD
7	3.00	1.5	STANDARD
8	3.00	2.1	(H-C STANDARD)
9	3.00	2.1	(H-C STANDARD)
10	1.75	2.0	STANDARD
11	1.00	2.2	STANDARD
12	2.00	1.2	STANDARD
13	2.00	1.1	STANDARD

ALL Q'S HAVE BEEN EXTRAPOLATED FROM THE 10 YR. STORM DRAIN COMPUTATIONS STANDARD 12" CIRCULAR OR 14"x9" ARCH PIPE T2VC = LOCATED NEAR THE TOP OF A VERTICAL CURVE.



APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
 Andrew M. Danaker 11/2/00
 CHIEF, BUREAU OF HIGHWAYS

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
 Cindy Hamden 11/13/00
 CHIEF, DIVISION OF LAND DEVELOPMENT

APPROVED: 11/16/00
 CHIEF, DEVELOPMENT ENGINEERING DIVISION

date	01-12-00
project	98008.13
illustration	KMB
scale	1"=50'
approval	RMM

date	11/06/00
revision	1
description	REVISED PER DPZ COMMENTS / H/LAR SUBMITTAL
revision	2
description	REVISED SUBMITTAL TO HOWARD CO DPZ FOR REVIEW
revision	3
description	REVISED SUBMITTAL TO HOWARD COUNTY FOR REVIEW
revision	4
description	REVISED SUBMITTAL TO HOWARD COUNTY FOR REVIEW

Tax Map 13, Grid 15, Parcel 46 (p/o)
THE WESTWOODS OF CHERRY GROVE
 HOWARD COUNTY, MARYLAND
 ELECTION DISTRICT No. 4
COLTON COURT PLAN AND PROFILE

R.M. MOCHI GROUP, P.C.
 P.O. Box 10
 New Market, MD 21774-0010
 (301) 865-8909
 Fax: (301) 865-8911

OWNER
 MARSHALL W. NICHOLS
 P.O. BOX 10
 NEW MARKET, MD 21774
 (301) 965-5858


ENGINEER/SURVEYOR
 R.M. MOCHI GROUP, P.C.
 P.O. BOX 10
 NEW MARKET, MD 21774
 (301) 965-5858

REVISED PER DPZ COMMENTS / NAYLOR SUBMITTAL 10/14/00
 1 7/22/00
 REVISED SUBMITTAL TO HOWARD CO. DPZ FOR REVIEW 4-28-00
 2
 REVISED SUBMITTAL TO HOWARD COUNTY DPZ FOR REVIEW 01-14-2000
 1
 SUBMITTED TO HOWARD COUNTY DPZ FOR REVIEW

THE WESTWOODS OF CHERRY GROVE
 ELECTION DISTRICT No. 4
 HOWARD COUNTY, MARYLAND

Tax Map 13, Grid 15, Parcel 46 (p/o)
 OLD SAWMILL ROAD PLAN AND PROFILE



R.M. MOCHI GROUP, P.C.
 P.O. Box 10
 New Market, MD 21774-0010
 (301) 965-5859
 Fax: (301) 965-5911



THE PAD IS TO BE MAINTAINED BY THE H.O.A. IT SHALL NOT BE COVERED OR ANY WALLS ERECTED SO THAT SIGHT DISTANCE IS NOT AFFECTED.

TEMPORARY TRAFFIC CONTROL SHALL BE MAINTAINED DURING CONSTRUCTION IN ACCORDANCE WITH MSHA STANDARDS FOR HIGHWAYS AND INCIDENTAL STRUCTURES STANDARDS: STD. No. MD 104.04-02 MD 104.31-02

JENNINGS CHAPEL ROAD & OLD SAWMILL ROAD
 FILLET PROFILES
 1"=10' HORIZ. 1"=2' VERT. SOUTHWEST FILLET



OLD SAWMILL ROAD - ROADSIDE DITCH DATA

BEGIN	END	Q10 (cfs)	V10	SLOPE	ROADSIDE DITCH LINING*
0+00 L	2+56 L	0.80	2.30	3.99%	ECM*
0+00 R	2+56 R				NO DITCH
2+56 L	6+25 L	1.69	2.13	1.96%	ECM*
2+56 R	6+25 R	0.69	2.22	1.96%	ECM*
6+25 L	10+50 L	3.33	4.20	7.65%	ECM*
6+25 R	10+50 R	1.31	3.32	7.65%	ECM*
10+50 L	11+48 L	5.82	3.95	4.50%	ECM*
10+50 R	11+48 R	1.55	2.84	4.50%	ECM*

* ECM TO BE PLACED OVER SEED AND MULCH

OLD SAWMILL ROAD - DRIVEWAY CULVERTS

Lot	Slope(%)	Q10(cfs)	DW Pipe Size
14	3.99	1.0	STANDARD
15	TOVC	0.0	NO PIPE
16	1.96	0.7	STANDARD
17	4.50	1.2	STANDARD
18	7.00	2.0	STANDARD
19	7.65	2.5	STANDARD
20	2.50	4.0	15" CMP
21	-	OPEN SPACE	-
22	1.50	1.0	STANDARD
23	4.00	0.9	STANDARD
24	4.00	0.8	STANDARD
25	5.50	0.7	STANDARD
26	5.75	0.6	STANDARD
27	7.65	0.5	STANDARD
28	3.50	0.4	STANDARD
29	1.96	0.3	STANDARD
30	1.96	0.2	STANDARD
31	1.96	0.2	STANDARD
32	1.96	0.2	STANDARD
33	1.96	0.2	STANDARD
34	No Ditch	-	No Pipe
35	No Ditch	-	No Pipe

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Andrew M. Danaher 1/3/00
 CHIEF, BUREAU OF HIGHWAYS


APPROVED:
 HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Cindy Hamstra 1/13/00
 CHIEF, DIVISION OF LAND DEVELOPMENT

John P. ... 1/16/00
 CHIEF, DEVELOPMENT ENGINEERING DIVISION



J:\98008-13\CD\DATA\PLAN3.DWG

SEE SHEET 5 FOR LEGEND



project	98006.13	date	01-11-00
illustration	KMB	engineering	P.F.B.
scale	1" = 50'	approval	
		R.M.M.	

REVISED PER DPZ COMMENT / M/LK SUBMITTAL	10/04/00	DATE	
REVISION 3	7/26/00	DATE	
REVISION 2	07/14/2000	DATE	
REVISION 1		DATE	

MATCH LINE SEE SHEET 6 OF 18

Tax Map 13, Grid 15, Parcels 46 (P/O)

THE WESTWOODS OF CHERRY GROVE

ELECTION DISTRICT NO. 4

HOWARD COUNTY, MD.

GRADING, SEDIMENT CONTROL AND FOREST CONSERVATION

R.M. MOCHI GROUP, P.C.

P.O. BOX 10
New Market, MD 21774-0010

(301) 865-5858
Fax: (301) 865-5111

MATCH LINE SEE SHEET 5 OF 18

APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

Richard M. Sanchez 11-3-00
CHIEF, BUREAU OF HIGHWAYS

PARKTON WOODLAND SERVICES
17409 EVNA ROAD
PARKTON, MD. 21120
(410) 357-5835

QUALIFIED PROFESSIONAL PER THE
MARYLAND FOREST CONSERVATION ACT

Stephen Paul Masten 4/27/00
Stephen Paul Masten, Reg. No. 2471

OWNER

MARSHALL W. NICHOLS
C/O R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD. 21774
(301) 865-5858

ENGINEER/SURVEYOR:

R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD. 21774
(301) 865-5858

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING

Cindy Stovetter 11/13/00
CHIEF, DIVISION OF LAND DEVELOPMENT

John J. ... 11/16/00
CHIEF, DEVELOPMENT ENGINEERING DIVISION

APPROVED:
THESE PLANS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

John J. ... 10/26/00
HOWARD SOIL CONSERVATION DISTRICT

APPROVED:
THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.

J.G. ... 10/26/00
USDA NATIONAL RESOURCE CONSERVATION SERVICE

DEVELOPER'S CERTIFICATE

I/We certify that all development and construction will be done according to these plans, and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I shall engage a registered professional engineer to supervise pond construction and provide the Howard Soil Conservation District with an "as-built" plan of the pond within 30 days of completion. I also authorize periodic on-site inspections by the Howard Soil Conservation District.


Marshall W. Nichols 4/28/00
Signature of Developer

ENGINEER'S CERTIFICATE

I certify that this plan for pond construction, erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions. This plan was prepared in accordance with the requirements of the Howard Soil Conservation District. I have notified the developer that he/she must engage a registered professional engineer to supervise pond construction and provide the Howard Soil Conservation District with an "as-built" plan of the pond within 30 days of completion.

Robert M. Mochi 4/28/00
Robert M. Mochi, P.E.






LEGEND:

- PERC AREAS
- 25% OR GREATER SLOPES
- 15% - 24.9% SLOPES
- PUBLIC STORMWATER MANAGEMENT DRAINAGE AND UTILITY EASEMENT
- DENOTES LOCATION OF FOREST RETENTION EASEMENT WITH TREE PROTECTION AND SIGNAGE.
- DENOTES TREE SIGNAGE
- DENOTES FENCE
- DENOTES SILT FENCE
- DENOTES SUPER SILT FENCE
- DENOTES SILT FENCE/TREE PROTECTION FENCE COMBINATION
- FOREST CONSERVATION/RETENTION EASEMENT (F.C.E.)
- EARTH DIKE LIMITS OF DISTURBANCE (L.O.D.)

- DESCRIPTION**
- The work shall consist of installing a flow diversion structure when construction activities take place within the stream channel, such as culvert or storm drain construction.
- MATERIAL SPECIFICATIONS**
- Sandbags: Sandbags shall consist of materials which are resistant to ultraviolet radiation, tearing and puncture, and woven tightly enough to prevent leakage of fill material (e.g., sand, fine gravel)
 - Sheeting: sheeting shall consist of polyethylene or other material which is impervious and resistant to puncture and tearing.
- CONSTRUCTION SPECIFICATIONS**
- All sediment and erosion control devices shall be installed as the first order of work.
 - The top width of the sandbag wall shall be from 2 to 4 feet.
 - The height of the diversion structure shall be 1.5 times the diversion pipe diameter.
 - All excavated materials shall be disposed of in an SCD-approved disposal area outside the 100-year floodplain.
 - All de-watering of the construction area shall be pumped from an RPS prior to re-entering the stream.
 - Sheeting shall be overlapped such that the upstream portion covers the downstream portion with a 1" minimum overlap.
 - Sediment control devices are to remain in place until all disturbed areas are stabilized in accordance with an approved Sediment and Erosion Control Plan and the inspecting authority approves the removal.

MATCH LINE SEE SHEET 4 OF 18



WBEI For Pond 3

2 Year Storm	562.45
10 Year Storm	564.64
100 Year Storm	565.46

**PRIVATELY OWNED
JOINTLY MAINTAINED BY HOA
1 HOWARD CO., MD.
SWM POND NO. 3
PUBLIC CLASS A
DETENTION FACILITY
(FOR POND LANDSCAPING SEE SHEET 10)
(FOR RUNOFF SUMMARY TABLE
SEE SHEET 14 OF 18)**

RETENTION AREA NO. 6
(6.5203 Ac.)
6.5203 Ac. TOTAL
6.5203 Ac. TOTAL
NON-BUILDABLE
(Purpose: Forest, Environmental Conservation, & SWM)
367,554 sq. ft.
5,209,272 sq. ft.

PRESERVATION PARCEL 'C'
NON-BUILDABLE
(Purpose: Forest, Environmental Conservation, & SWM)
367,554 sq. ft.
5,209,272 sq. ft.

PRESERVATION PARCEL 'B'
(3.1253 Ac.)
3.1253 Ac. TOTAL
NON-BUILDABLE
(Purpose: Forest, Environmental Conservation, & SWM)
422,736 sq. ft.
6,038,104 sq. ft.

RETENTION AREA NO. 4
(3.1253 Ac.)
3.1253 Ac. TOTAL
NON-BUILDABLE
(Purpose: Forest, Environmental Conservation, & SWM)
422,736 sq. ft.
6,038,104 sq. ft.

APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Andrew M. Danter 11/3/00
CHIEF, BUREAU OF HIGHWAYS

PARKTON WOODLAND SERVICES
17409 EVNA ROAD
PARKTON, MD. 21120
(410) 357-5835

QUALIFIED PROFESSIONAL PER THE
MARYLAND FOREST CONSERVATION ACT
Stephen Paul Masler 10/11/00
Stephen Paul Masler, Reg. No. 971 DATE

OWNER
MARSHALL W. NICHOLS
C/O R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD. 21774
(301) 865-5858

ENGINEER/SURVEYOR:
R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD. 21774
(301) 865-5858

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Cindy Hamble 11/6/00
CHIEF, DIVISION OF LAND DEVELOPMENT

APPROVED:
THESE PLANS FOR SMALL POND CONSTRUCTION, SOIL EROSION
AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE
HOWARD SOIL CONSERVATION DISTRICT.
John M. ... 10/20/00
HOWARD SOIL CONSERVATION DISTRICT

APPROVED:
THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD
SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL
REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL
EROSION AND SEDIMENT CONTROL.
J.G. Campfield 10/20/00
NATIONAL RESOURCES CONSERVATION SERVICE

DEVELOPER'S CERTIFICATE
I/We certify that all development and construction will be done according to these
plans, and that any responsible personnel involved in the construction project will
have a Certificate of Attendance at a Department of the Environment Approved
Training Program for the Control of Sediment and Erosion before beginning the
project. I shall engage a registered professional engineer to supervise pond
construction and provide the Howard Soil Conservation District with an "as-built"
plan of the pond within 30 days of completion. I also authorize periodic
on-site inspections by the Howard Soil Conservation District.
Robert M. Mochi 10/11/00
Signature of Developer DATE

ENGINEER'S CERTIFICATE
I certify that this plan for pond construction, erosion and sediment control represents
a practical and workable plan based on my personal knowledge of the site conditions.
This plan was prepared in accordance with the requirements of the Howard Soil
Conservation District. I have notified the developer that he/she must engage a
registered professional engineer to supervise pond construction and provide the
Howard Soil Conservation District with an "as-built" plan of the pond within 30 days
of completion.
Robert M. Mochi 10/19/00
Robert M. Mochi, P.E. DATE




Project	98008.13	Date	01-11-00
Illustration	KMB	Engineering	P.F.B.
Revision		Approval	R.M.L.
Scale		1" = 60'	

Revised	PER DPZ COMMENTS/NTAR SUBMITTAL	10/04/00
2	REVISED SUBMITTAL TO HOWARD COUNTY DPZ FOR REVIEW	11/06/00
0	REVISED SUBMITTAL TO HOWARD COUNTY DPZ FOR REVIEW	01-11-00
0	REVISED SUBMITTAL TO HO. CO. DPZ FOR REVIEW	01-11-00
0	REVISED SUBMITTAL TO HO. CO. DPZ FOR REVIEW	01-11-00

Tax Map 13, Grid 15, Parcel 46 (p/o)
THE WESTWOODS OF CHERRY GROVE
ELECTION DISTRICT NO. 4
HOWARD COUNTY, MD.
GRADING, SEDIMENT CONTROL AND FOREST CONSERVATION

R.M. MOCHI GROUP, P.C.
P.O. Box 10
New Market, MD 21774-0010
(301) 865-5858
Fax: (301) 865-5711



IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN UNINTERRUPTED ACCESS TO PARCEL 104 (SOUND'S PROPERTY) FROM JENNINGS CHAPEL ROAD DURING CONSTRUCTION. THE EXISTING ACCESS DRIVE SHALL BE KEPT OPEN AND MAINTAINED WHENEVER POSSIBLE. ANY TEMPORARY ACCESS REQUIRED TO AVOID THE ROADWAY CONSTRUCTION SHALL BE A MINIMUM OF 12' WIDE AND SURFACED WITH 6" OF CRUSHED STONE. THE EXISTING AND TEMPORARY ACCESS DRIVES ARE TO BE ABANDONED WHEN COLTON COURT AND THE PROPOSED 12 FOOT DRIVE FROM THE CUL-DE-SAC TO PARCEL 104 ARE PAVED.

APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Andrew M. Danaher 11/3/00
CHIEF, BUREAU OF HIGHWAYS 1/3 DATE

PARKTON WOODLAND SERVICES
17409 EYNA ROAD
PARKTON, MD. 21120
(410) 357-5835

QUALIFIED PROFESSIONAL PER THE MARYLAND FOREST CONSERVATION ACT
Stephen Paul Masten 4/22/00 4/22/00
Stephen Paul Masten, Reg. No. 247 DATE

MATCH LINE SEE SHEET 7 OF 18

OWNER
MARSHALL W. NICHOLS
C/O R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD. 21774
(301) 865-5858

ENGINEER/SURVEYOR:
R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD. 21774
(301) 865-5858

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Cinda Hawton 11/13/00
CHIEF, DIVISION OF LAND DEVELOPMENT 1/3 DATE

APPROVED:
THESE PLANS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.
John A. [Signature] 10/22/00
HOWARD SOIL CONSERVATION DISTRICT DATE

APPROVED:
THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.
J.G. Welfield Les 10/22/00
USDA NATIONAL RESOURCES CONSERVATION SERVICE DATE

DEVELOPER'S CERTIFICATE
I/We certify that all development and construction will be done according to these plans, and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I shall engage a registered professional engineer to supervise pond construction and provide the Howard Soil Conservation District with an "as-built" plan of the pond within 30 days of completion. I also authorize periodic on-site inspections by the Howard Soil Conservation District.
Robert M. Mochi 11/20/00
Signature of Developer DATE


ENGINEER'S CERTIFICATE
I certify that this plan for pond construction, erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions. This plan was prepared in accordance with the requirements of the Howard Soil Conservation District. I have notified the developer that he/she must engage a registered professional engineer to supervise pond construction and provide the Howard Soil Conservation District with an "as-built" plan of the pond within 30 days of completion.
Robert M. Mochi, P.E. 11/20/00
DATE



date	01-11-00
project	99008.13
illustration	KMB
scale	1" = 50'
approval	P.F.B.
approval	R.M.M.

REVISED PER DZ COMMENTS/MYLAR SUBMITTAL	10/06/00
REVISED PER COMMENTS FROM REVIEW	7/26/00
REVISED PER COMMENTS FROM REVIEW	01-14-2000
DESCRIPTION	DATE
NO.	


Tax Map 13, Grid 15, Parcel 46 (p/o)
THE WESTWOODS OF CHERRY GROVE
ELECTION DISTRICT NO. 4
HOWARD COUNTY, MD.
GRADING, SEDIMENT CONTROL AND FOREST CONSERVATION



SEE SHEET 5 FOR LEGEND.

POND #1 SEDIMENT BASIN DATA
 DRAINAGE AREA = 8.76 AC.
 WET STORAGE REQUIRED = 15,768 FT3
 WET STORAGE PROVIDED = 16,427 FT3 @ 551.50
 DRY STORAGE REQUIRED = 15,760 FT3
 DRY STORAGE PROVIDED = 16,546.5 FT3 @ 553.00
 BOTTOM ELEVATION = 547.9
 EMBANKMENT ELEVATION = 556.0
 RISER CREST ELEVATION = 553.0
 CLEAN OUT ELEVATION = 550.29
 DRAIN DOWN ORIFICE INV. = 547.90
 DISTANCE FROM TOP OF RISER TO CLEAN OUT ELEVATION = 4.38'
 SEE SHEET #1 FOR ADDITIONAL SEDIMENT CONTROL DETAILS FOR POND
 TEMP. SWM Q2PRE = 0.8 CFS
 Q2POST = 0.2 CFS, WSEL = 552.84

MATCH LINE SEE SHEET 6 OF 18



WSEL For Pond 1

Extended Detention	550.88
2 Year Storm	551.44
10 Year Storm	552.78
100 Year Storm	553.83

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Andrew M. Casper 11/3/00
 CHIEF, BUREAU OF HIGHWAYS

PARKTON WOODLAND SERVICES
 17409 EVNA ROAD
 PARKTON, MD. 21120
 (410) 357-5835

QUALIFIED PROFESSIONAL PER THE MARYLAND FOREST CONSERVATION ACT
Stephen Paul Maslen 4/27/02
 Stephen Paul Maslen, Reg. No. 247

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Cindy Hamble 11/13/00
 CHIEF, DIVISION OF LAND DEVELOPMENT
Michael... 11/16/00
 CHIEF, DEVELOPMENT ENGINEERING DIVISION

APPROVED:
 THESE PLANS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.
... 10/20/00
 HOWARD SOIL CONSERVATION DISTRICT

APPROVED:
 THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.
J.G. Langford 10/20/00
 U.S. NATIONAL RESOURCES CONSERVATION SERVICE

DEVELOPER'S CERTIFICATE
 I/We certify that all development and construction will be done according to these plans, and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I shall engage a registered professional engineer to supervise pond construction and provide the Howard Soil Conservation District with an "as-built" plan of the pond within 30 days of completion. I also authorize periodic on-site inspections by the Howard Soil Conservation District.
Robert M. Mochi 4/27/00
 Signature of Developer

ENGINEER'S CERTIFICATE
 I certify that this plan for pond construction, erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions. This plan was prepared in accordance with the requirements of the Howard Soil Conservation District. I have notified the developer that he/she must engage a registered professional engineer to supervise pond construction and provide the Howard Soil Conservation District with an "as-built" plan of the pond within 30 days of completion.
Robert M. Mochi 4/27/00
 Robert M. Mochi, P.E.

OWNER
 MARSHALL W. NICHOLS
 C/O R.M. MOCHI GROUP, P.C.
 P.O. BOX 10
 NEW MARKET, MD. 21774
 (301) 865-5858

ENGINEER/SURVEYOR:
 R.M. MOCHI GROUP, P.C.
 P.O. BOX 10
 NEW MARKET, MD. 21774
 (301) 865-5858






Project	98008.13	Date	01-11-00
Illustration	KMB	P.F.B.	approval
Scale	1" = 50'	R.M.M.	

Revised	10/05/00	Comments	FOR DPZ COMMENTS/INTEGRAL SUBMITTAL
Revised	7/26/00	Comments	REVISOR SUBMITTAL TO HOWARD COUNTY DPZ FOR REVIEW
Revised	4-28-00	Comments	1ST SUBMITTAL TO HO. CO. DPZ FOR REVIEW
Revised	01-14-2000	Comments	

Tax Map 13, Grid 15, Parcel 46 (p/o)
THE WESTWOODS OF CHERRY GROVE
 ELECTION DISTRICT NO. 4
 HOWARD COUNTY, MD.
GRADING, SEDIMENT CONTROL AND FOREST CONSERVATION

R.M. MOCHI GROUP, P.C.
 P.O. Box 10
 New Market, MD 21774-0010
 (301) 865-5858
 Fax: (301) 865-5111



Forest Conservation Plan- Additional Documentation

Owner: Marshall Nichols
Project: Westwoods of Cherry Grove

This site contains no particularly high priority areas. While the chestnut oak stand contains more diverse vegetation, the tulip-tree stand is largely stream buffer. Therefore the submission is in general conformity with retention priorities.


Construction Period Practices

Traffic is to be excluded from the retention areas which will be fenced and posted prior to construction. Every effort will be made to avoid disturbance of the primary root zone of trees in the retention area. This means, generally, that the root zone will not be disturbed within the drip line of trees in the retention area. For trees which are to be retained outside the retention area the same care applies. Additionally, these trees will be protected from compaction by construction equipment, from storage of construction materials, and from filling over their root zones within the drip line. Parking of equipment and storage of materials will be directed away from retention areas, streams, and other trees which are to be retained.

Post-Construction Practices

Retention area fencing is to be retained for the required period. Trees on the margins of the retention areas will be checked for signs of decline caused by construction disturbance, and treated appropriately. Any erosion problems will be corrected, particularly those that impact the retention areas. The new homeowners will receive brief instruction about the importance of the retention areas and their own rights and responsibilities with respect to those areas on their property. In general the construction period prohibitions will apply* the new owners will be instructed to minimize use of herbicides and insecticides adjacent to retention areas and they will be encouraged to feature native species in any planting done on the new lots.

Stephen Paul Maslen
MD, Registered Forester #247



FCP GENERAL SITE INFORMATION:

- A. ZONING: RC-DEO
 - B. GROSS AREA OF TRACT: 62.02 Ac.*
 - C. AREA WITHIN 100 YEAR FLOOD PLAIN: 0.79 Ac.
 - D. NET AREA OF TRACT: 61.23 Ac.
 - E. TOTAL FORESTED AREA OF NET TRACT: 55.98 Ac.
 - F. FOREST AREA TO BE DISTURBED: 36.58 Ac.
 - G. FOREST AREA TO BE PRESERVED: 19.4 Ac.
 - H. REFORESTATION REQUIREMENT OF 5.06 AC. WILL BE PROVIDED BY OFF-SITE RETENTION AT 2:1.
 - I. RECONNAISSANCE FOR FSD REVEALED TWO FOREST STAND/TYPES. NO SPECIMEN TREES, AND NO UNIQUE PLANT COMMUNITIES. THEREFORE, THIS PLAN CONSISTS OF THE FOREST CONSERVATION WORKSHEET AND PLANS SHOWING THE ON-SITE + OFF-SITE RETENTION AREAS, ALONG WITH THE FENCING AND FLAGGING DETAILS.
 - J. FOREST RETENTION AREA FENCING WILL BE OF PLASTIC MESH ATTACHED TO 6 FOOT WOODEN STAKES (2X2) DRIVEN 2 FEET IN THE GROUND ON A SPACING 6 FEET IN MANNER SHOWN IN THE FOREST CONSERVATION MANUAL.
- THE WOODEN STAKES WILL BE CROSS-BRACED WITH 12 FT. 2X4'S THE PLASTIC MESH FENCING WILL BE SECURED TO THE GROUND WITH 8\"/>

NOTE: FENCING WILL BE INSTALLED IF DISTURBANCE IS WITHIN 100' OF THE FOREST RETENTION EASEMENT LINE.

* THE GROSS SITE AREA EXCLUDES THE AREA OF PARCELS D & E (1.45 ac). THE FOREST CONSERVATION OBLIGATIONS FOR THESE PARCELS WILL BE ADDRESSED WITH THE FUTURE SUBDIVISION OF PARCEL 109 (SAME PROPERTY)

FOREST CONSERVATION DATA:

BASIC SITE DATA	ACRES
GROSS SITE AREA	62.02 Ac. *
AREA WITHIN 100YR FLOODPLAIN	0.79 Ac.
NET TRACT AREA	61.23 Ac.
LAND USE CATEGORY	RC-DEO

REFORESTATION CALCULATIONS	ACRES
NET TRACT AREA	61.23 Ac.
REFORESTATION THRESHOLD 25%(61.23 Ac.)	15.31 Ac.
EXISTING FOREST ON NET TRACT	55.98 Ac.
FOREST AREAS TO BE CLEARED	36.58 Ac.
FOREST AREAS TO BE RETAINED	19.4 Ac.
FOREST AREA CLEARED ABOVE THRESHOLD	36.58 Ac.
FOREST AREA RETAINED ABOVE THRESHOLD	4.89 Ac.
REFORESTATION FOR CLEARING ABOVE THRESHOLD (36.58 Ac. x 1/4)	9.15 Ac.
CREDIT FOR FOREST AREAS RETAINED ABOVE THRESHOLD	4.09 Ac.
REFORESTATION REQUIRED	5.06 Ac.

REFORESTATION REQUIREMENT WILL BE PROVIDED BY OFF-SITE RETENTION AT 2:1

10.2 AC. OF OFF-SITE RETENTION WILL BE PROVIDED ON THE HARRISON PROPERTY (Tax Map 1, Grid 23, Parcel 7)
SEE SHEET 9 FOR OFF-SITE RETENTION PLAN

OWNER
MARSHALL W. NICHOLS
C/O R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD. 21774
(301) 865-5858

ENGINEER/SURVEYOR:
R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD. 21774
(301) 865-5858

On - Site Forest Conservation Easement Area Tabulation

	Total Area	Credit Area	Non-Credit Area	Type
Forest Conservation Easement Area # 1	4.4461 ac	4.4309 ac	0.0152 ac	Retention
Forest Conservation Easement Area # 2	0.8914 ac	0.8857 ac	0.0057 ac	Retention
Forest Conservation Easement Area # 3	3.9917 ac	3.9632 ac	0.0285 ac	Retention
Forest Conservation Easement Area # 4	3.1253 ac	3.1253 ac	0 ac	Retention
Forest Conservation Easement Area # 5	0.5375 ac	0.5231 ac	0.0144 ac	Retention
Forest Conservation Easement Area # 6	6.5203 ac	6.4924 ac	0.0279 ac	Retention
Total	19.5123 ac	19.4206 ac	0.0917 ac	

PARKTON WOODLAND SERVICES
17409 EVNA ROAD
PARKTON, MD. 21120
(410) 357-5835

QUALIFIED PROFESSIONAL PER THE MARYLAND FOREST CONSERVATION ACT
Stephen Paul Maslen, 10/11/00
Step. Paul Maslen, Reg. No. 247 DATE

APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Andrew M. Casella 11-3-00
CHIEF, BUREAU OF HIGHWAYS DATE

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Cindy Hamstra 11/3/00
CHIEF, DIVISION OF LAND DEVELOPMENT DATE

William D. ... 11/10/00
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

PROJECT: 98008-13
DATE: 01-12-00
ILLUSTRATION: PFB
SCALE: As Shown
APPROVAL: RMM




REVISIONS
DATE: 01-14-2000
DESCRIPTION: REVISIONS

NO. 1: REVISIONS PER PZ COMMENTS (MAY BE SUBMITTED FOR REVIEW) (SEE SHEET 9)
NO. 2: REVISIONS PER PZ COMMENTS (MAY BE SUBMITTED FOR REVIEW) (SEE SHEET 9)
NO. 3: REVISIONS PER PZ COMMENTS (MAY BE SUBMITTED FOR REVIEW) (SEE SHEET 9)

Tax Map 13, Grid 15, Parcel 46 (p/o)
THE WESTWOODS OF CHERRY GROVE
ELECTION DISTRICT NO. 4
HOWARD COUNTY, MD.
FOREST CONSERVATION PLAN

R.M. MOCHI GROUP, P.C.
P.O. Box 10
New Market, MD 21774-0010
(301) 865-5858
Fax: (301) 865-5911

8 OF 18
00-105



Vicinity Map
Scale: 1" = 2000'

Stand Narrative:

Project: Westwoods of Cherry Grove
Offsite Retention Area (Harrison property) (NOW KNOWN AS HOLTEINGER PROPERTY)

The site consists of about 10 acres of a 35 acre woodland on a farm off Long Corner Road. Contiguous portions of the woodland lie along the headwaters of the Patapsco River. The proposed retention area is rectangular in shape, about 1,000 feet long and 400 feet wide and sloping gently to the north.

Stand F1 (24.2 ac)
 This stand includes most of the woodland on the site. It has been actively managed; a selective timber harvest appears to have been done 15-20 years ago. Species composition is unusually diverse. Black oak is the most common tree but there are significant components of Scarlet oak, White oak, Northern red oak, Rock oak, Tulip-tree, Hickory species, Black-gum, White pine, and Virginia pine. The size class is medium to large sawtimber, averaging about 16.5" dbh; stocking is in the optimum range for tree growth (74% relative density). The understory is sparse, except near the crop fields, and is composed mainly of tree regeneration, Smilax species, spicabush, and Virginia creeper. There are no unusual species or specimen trees. Soils are mostly of the Glenelg and Mt. Airy series, with a little bit of Glenville in the lower areas.

The area proposed for retention lies in this stand along the southern boundary of the property. This is a natural woodland which has never been cleared. While it is not undisturbed and the trees are not remarkably large, there is an unusual diversity of species and the location is near the headwaters of the Patapsco River. The proposed retention area is large and broad enough to stand by itself if the woodlands adjoining it were cleared in the future. There is no question that the species composition, size, and stocking meet the FCA definition of a forest and, beyond that, make this woodland a desirable candidate for retention. The easement conditions should not include prohibitions or unreasonable restrictions on timber harvesting. Timber harvesting should be permitted so long as it conforms with best management practices and with a forest stewardship plan (by a registered professional forester) written prior to harvesting.

Stand F2 (1.5 ac)
 This is a hedgerow between fields. It was not inspected in detail.

Stand F3 (7.6 ac)
 This is a floodplain forest located along the Patapsco River. It appears to be dominated by Tulip-tree. Again, it was not inspected in detail because it was unsuitable for offsite retention.

Stephen Paul Maslen
 MD. Registered Forester #247

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Andrew M. Daniels 11-3-00
 CHIEF, BUREAU OF HIGHWAYS 11/2 DATE

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Andy Spitzer 11/2/00
 CHIEF, DIVISION OF LAND DEVELOPMENT JA DATE

Adam Demunier 11/6/00
 CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

TOPOGRAPHY SOURCE
 Howard County Maryland Site Planning GIS Data
 CD Date: October 14, 1999
 Data Date: 1998 Contour Lines (east) with 5' contour intervals

SPATIAL REFERENCE INFORMATION
 Coordinate System Name: Maryland State Plane Coordinate System 1927
 Horizontal Datum Name: North American Datum of 1927 (NAD 27)

Soil Legend

ChA	Chester silt loam, 0 to 3% slopes
Co	Codorus silt loam
CuB	Cornus silt loam, local alluvium, 3 to 8 % slopes
GIB2	Glenelg loam, 3 to 8 % slopes, moderately eroded
GIC2	Glenelg loam, 8 to 15 % slopes, moderately eroded
GIC3	Glenelg loam, 8 to 15% slopes, severely eroded
GnB2	Glenville silt loam, 3 to 8% slopes, moderately eroded
Ha	Hatboro silt loam
MtC2	Mt. Airy channery loam, 8 to 15% slopes, moderately eroded
MtC3	Mt. Airy channery loam, 8 to 15% slopes, severely eroded
MtD2	Mt. Airy channery loam, 15 to 25% slopes, moderately eroded
MTE	Mt. Airy channery loam, 25 to 45% slopes

Plan Legend

<i>MtB2</i>	Soil Type & Limit
	Steep Slopes 15% - 25%
	Steep Slopes 25% & greater
	Existing Tree Line
	Forest Stand Limit & Description
	Forest Retention Easement
	Forest Retention Signage

PARKTON WOODLAND SERVICES
 17409 EVNA ROAD
 PARKTON, MD. 21120
 (410) 357-5835

QUALIFIED PROFESSIONAL PER THE
 MARYLAND FOREST CONSERVATION ACT
Stephen Paul Maslen 1/26/00
 DATE

HARRISON PROPERTY
 Tax Maps #1 & #6, Parcel 7

The Westwoods of Cherry Grove
 HOWARD COUNTY, MARYLAND
 ELECTION DISTRICT No. 4
Forest Conservation Plan - Offsite Retention

RM MOCHI GRAPH P/L
 (301) 885-5858
 (301) 885-5111
 P.O. Box 10
 New Market, MD 21774-0010

project	98006.13	date	7-14-00
illustration	PFB	engineer	PFB
scale	1" = 200'	approval	RMM

1	REMOVED PER DPZ COMMENTS / MYLAR SUBMITTAL	9/25/00	date
0	SUBMITTED TO HOWARD COUNTY DPZ FOR REVIEW	7/26/00	date
			description
			revisions

SCHEDULE D - STORMWATER MANAGEMENT AREA LANDSCAPING

	SWM Pond 1 (Type B)	SWM Pond 2 (Type B)	SWM Pond 3 (Type B)	TOTAL
Linear Feet of Perimeter	1170	1006	1026	3127
Number of Trees Required/Provided	12	13	0	25
Shade Trees	29	17	26	72
Evergreen Trees Provided (1:40')	Yes-578 L.F.	Yes-350 L.F.	Yes-1026 L.F.	
Credit for Existing Veg. (NO, YES and L.F.)	NO	NO	NO	
Credit for Other Landscaping (NO, YES and L.F.)	NO	NO	NO	

CREDIT IS GIVEN FOR SHADE TREES AND EVERGREEN TREES ARE PROVIDED FOR THE TYPE 'B' BUFFER.

SCHEDULE A - PERIMETER LANDSCAPE EDGE

Perimeter	1	2	3	4	5	6	7	8	9	Total
Category*	*	*	*	*	Adj. to Roadways	Adj. to Roadways	*	*	*	
Landscape Type	A	A	A	A	B	B	A	A	A	
Linear Feet of Perimeter	1461	392	828	397	323	295	819	784	1033	6332
Credit for Existing Vegetation (Yes, Linear Feet)	Yes 1411	Yes 392	Yes 828	Yes 340	No 323	Yes 295	Yes 819	Yes 784	Yes 1033	6225
Net Linear Feet to be Planted	50	0	0	57	323	0	0	0	0	430
Number of Plants Required										
Shade Trees	1	0	0	1	7	0	0	0	0	9
Evergreen Trees (1:40')	0	0	0	0	8	0	0	0	0	8
Shrubs	0	0	0	0	0	0	0	0	0	0

* = ADJACENT TO PROPERTIES/PRESERVATION PARCELS UNLESS NOTED OTHERWISE.
 PERIMETER 1: LOTS 5, 8, AND 9. MUST RETAIN A MINIMUM 20-FOOT WIDE LANDSCAPE EDGE ADJACENT TO THE BAILEY, MAYNE AND BROWN PROPERTIES.
 PERIMETER 7: LOTS 31-35 MUST RETAIN A MINIMUM 20-FOOT WIDE LANDSCAPE EDGE ADJACENT TO THE GORDON PROPERTY.

THE DEVELOPER WILL BE RESPONSIBLE FOR STREET TREE INSTALLATION. FINANCIAL SURETY FOR THE 96 PROPOSED STREET TREES, IN THE AMOUNT OF \$ 28,800 IS PART OF THE DEVELOPER'S AGREEMENT.

THIS PLAN HAS BEEN PREPARED IN ACCORDANCE WITH THE PROVISIONS OF SECTION 16.124 OF THE HOWARD COUNTY CODE AND THE LANDSCAPE MANUAL. FINANCIAL SURETY FOR THE REQUIRED 122 LANDSCAPE TREES, IN THE AMOUNT OF \$ 23,400 IS PART OF THE DEVELOPER'S AGREEMENT.

LEGEND

- RS
- OG
- WO
- RO
- LC
- EWP

LANDSCAPE SCHEDULE

KEY	BOTANICAL NAME	COMMON NAME	SIZE	QT.	COMMENTS
RS	Acer rubrum	RED SUNSET	2 1/2-3" CAL	6	B & B
OG	Acer rubrum	OCTOBER GLORY	2 1/2-3" CAL	10	B & B
WO	Quercus phellos	WILLOW OAK	2 1/2-3" CAL	10	B & B
RO	Quercus rubra	RED OAK	2 1/2-3" CAL	8	B & B
LC	Cupressocyparis leyland	LEYLAND CYPRESS	5'-6" HT.	43	B & B
EWP	Pinus strobus	EASTERN WHITE PINE	6'-8" HT.	45	B & B
TOTALS				122	



APPROVED:
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Richard M. Daniels 11-3-00
 CHIEF, BUREAU OF HIGHWAYS

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Cindy Hamilton 11/3/00
 CHIEF, DIVISION OF LAND DEVELOPMENT

OWNER
 MARSHALL W. NICHOLS
 610 R.M. MOCHI GROUP PC
 P.O. BOX 10
 NEW MARKET, MD. 21774
 (301) 665-5555

ENGINEER/SURVEYOR
 R.M. MOCHI GROUP PC
 P.O. BOX 10
 NEW MARKET, MD. 21774
 (301) 665-5555

NOTE: ALL EFFORTS SHALL BE TAKEN TO MINIMIZE THE REMOVAL OF EX. TREES AROUND THE SWM FACILITIES, IT IS NOT THE INTENT OF THIS PLAN THAT EX. TREES ARE TO BE REMOVED IN ORDER TO PLANT THE LANDSCAPING TREES SPECIFIED. PROP. LANDSCAPING AROUND THE PONDS SHALL BE PLACED ALONG THE LIMITS OF DISTURBANCE THAT IS REQUIRED TO GRADE & CONSTRUCT THE SWM FACILITIES. THE 20' NO WOODY VEGETATION ZONE AT THE TOE OF THE FACILITIES AS SHOWN SHALL NOT CONTAIN ANY EX. TREES OR PROPOSED LANDSCAPING.











PROJECT: 98008-04
 DATE: 01-12-00
 ILLUSTRATION: PFB
 APPROVAL: RMM

REVISED PER COMMENTS / MILLER SUBMITTAL
 10/24/00
 7/26/00
 4-28-00
 1-14-2000
 3 REVISED PER COMMENTS / MILLER SUBMITTAL
 2 REVISED SUBMITTAL TO HOWARD COUNTY DPZ FOR REVIEW
 1 SUBMITTED TO HOWARD COUNTY DPZ FOR REVIEW

Tax Map 13, Grid 15, Parcel 46 (p/o)
THE WESTWOODS OF CHERRY GROVE
 ELECTION DISTRICT No. 4
 HOWARD COUNTY, MARYLAND
LANDSCAPE PLAN

R.M. MOCHI GROUP, P.C.
 P.O. BOX 10
 NEW MARKET, MD. 21774-0010
 (301) 665-5555
 Fax: (301) 665-5511



APPROVED:
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
 [Signature] 11/3/00
 CHIEF, BUREAU OF HIGHWAYS

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
 [Signature] 11/16/00
 CHIEF, DIVISION OF LAND DEVELOPMENT

APPROVED:
 [Signature] 11/16/00
 CHIEF, DEVELOPMENT ENGINEERING DIVISION

OWNER
 MARSHALL W. NICHOLS
 C/O R.M. MOCHI GROUP, P.C.
 P.O. BOX 10
 NEW MARKET, MD. 21774
 (301) 865-5858

ENGINEER/SURVEYOR:
 R.M. MOCHI GROUP, P.C.
 P.O. BOX 10
 NEW MARKET, MD. 21774
 (301) 865-5858

APPROVED:
 THESE PLANS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.
 [Signature] 10/20/00
 HOWARD SOIL CONSERVATION DISTRICT


APPROVED:
 THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.
 [Signature] 10/20/00
 NATIONAL RESOURCES CONSERVATION SERVICE

DEVELOPER'S CERTIFICATE
 I/We certify that all development and construction will be done in accordance with this plan of development and plan for erosion and sediment control and that all responsible personnel involved in the construction of this project will have a certificate of attendance at a Department of the Environment approved training program for the control of sediment and erosion before beginning the project. I also authorize periodic onsite inspection by the Howard County Soil Conservation District or their authorized agents, as are deemed necessary.
 [Signature] 10/20/00
 Signature of Developer

ENGINEER'S CERTIFICATE
 I hereby certify that this plan for erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions. This plan was prepared in accordance with the requirements of the Howard Soil Conservation District. I have notified the developer that he/she must engage a registered professional engineer to supervise pond construction and provide the Howard Soil Conservation District with an "as-built" plan of the pond within 30 days of completion.
 [Signature] 10/20/00
 Robert M. Mochi, P.E.


APPROVED:
 [Seal of the State of Maryland Professional Engineer]
 [Signature] 10/20/00
 PROFESSIONAL ENGINEER

Project: 98008-13	Date: 1-10-00	Illustration: JMZ	Engineering: PFB	Approval: RJK	Risk: AS SHOWN
REVISIONS 3 REVISED PER DPZ COMMENTS / MAYLAK SUBMITTAL 10/05/00 2 REVISED SUBMITTAL TO HOWARD COUNTY DPZ FOR REVIEW 7-21-00 1 REVISED SUBMITTAL TO HOWARD COUNTY DPZ FOR REVIEW 4-11-00 0 SUBMITTED TO HOWARD COUNTY DPZ FOR REVIEW 4-1-00		THE WESTWOODS OF CHERRY GROVE ELECTION DISTRICT NO. 4 HOWARD COUNTY, MARYLAND STORMWATER MANAGEMENT DETAILS			




POND 2
PROFILE ALONG CL TOP OF DAM

SCALE: 1" = 50' HORIZ.
1" = 5' VERT.




SEDIMENT BASIN BAFFLE LAYOUT - POND No. 2

NORMAL POOL ELEV. 566.3
A-NORMAL POOL AREA 7434#
D=74'
W₀ = A/D = 7434/74 = 100'
L₀/W₀ ≥ 2. L₀/100 ≥ 2. L₀ ≥ 200'
L₀ = 88' + 70' + 55' + 35' = 248'
SEE SEDIMENT BASIN BAFFLE DETAIL SHEET 14 OF 18



RISER STRUCTURE GENERAL NOTES:

1. PRECAST RISER AND TOP SLAB TO BE MANUFACTURED AND SUPPLIED BY FREEMARK PRECAST CONCRETE, INC. OR APPROVED EQUIVALENT.
2. SHOP DRAWINGS FOR RISER AND TOP SLAB MUST BE REVIEWED BY THE ENGINEER OF RECORD.
3. IF ANY DIMENSIONS ARE CHANGED OR REDUCED, REVERSED ANTI-FLOTATION COMPUTATION MUST BE SUBMITTED WITH THE SHOP DRAWINGS TO HOWARD COUNTY FOR APPROVAL.
4. TRASH RACKS ARE NOT SHOWN IN THIS VIEW FOR CLARITY.
5. THE RISER STRUCTURE SHOWN IS NOT TO SCALE. SEE THIS SHEET FOR ACTUAL DIMENSIONS.
6. PRECASTER SHALL ENSURE THAT RISER STRUCTURE JOINTS ARE WATER-TIGHT (GASKETS SHALL INCLUDE RUBBER CASSETT). RISER JOINTS SHALL BE PROTECTED WITH 1" MIN. THICKNESS OF 1" MIN. CLASS "E" FILTER FABRIC. SEE SHEET 14 FOR GASKET AND FABRIC DETAILS.
7. ALL JOINTS SHALL BE PROTECTED AS SHOWN. SEE SHEET 14.



APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
[Signature] 11-3-00
CHIEF, BUREAU OF HIGHWAYS

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
[Signature] 11/14/00
CHIEF, DIVISION OF LAND DEVELOPMENT

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
[Signature] 11/14/00
CHIEF, DIVISION OF PLANNING & ZONING

APPROVED:
THESE PLANS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.
[Signature] 10/20/00
HOWARD SOIL CONSERVATION DISTRICT


APPROVED:
THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.
[Signature] 10/20/00
NATIONAL RESOURCES CONSERVATION SERVICE

DEVELOPER'S CERTIFICATE
I/We certify that all development and construction will be done in accordance with this plan of development and plan for erosion and sediment control and that all responsible personnel involved in the construction of this project will have a certificate of attendance at a Department of the Environment approved training program for the control of sediment and erosion before beginning the project. I also authorize periodic onsite inspection by the Howard County Soil Conservation District or their authorized agents, as are deemed necessary.

[Signature] 10/20/00
Signature of Developer



ENGINEER'S CERTIFICATE
I hereby certify that this plan for erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions. This plan was prepared in accordance with the requirements of the Howard Soil Conservation District. I have notified the developer that he/she must engage a registered professional engineer to supervise pond construction and provide the Howard Soil Conservation District with an "as-built" plan of the pond within 30 days of completion.




[Signature] 10/20/00
R.M. Mochi, P.E.




PRINCIPAL SPILLWAY PROFILE FOR SWM POND #2

SCALE: 1" = 20' HORIZ.
1" = 2' VERT.







PRINCIPAL SPILLWAY PROFILE FOR POND # 3




- RISER STRUCTURE GENERAL NOTES:**
1. PRECAST RISER AND TOP SLAB TO BE MANUFACTURED AND SUPPLIED BY FREDERICK PRECAST CONCRETE, INC. OR APPROVED EQUIVALENT.
 2. SHOP DRAWINGS FOR RISER AND TOP SLAB MUST BE REVIEWED BY THE ENGINEER OF RECORD.
 3. IF ANY DIMENSIONS ARE CHANGED OR REDUCED, REVISED ANTI-FLOTATION COMPUTATION MUST BE SUBMITTED WITH THE SHOP DRAWINGS TO HOWARD COUNTY FOR APPROVAL.
 4. TRASH RACKS ARE NOT SHOWN IN THIS VIEW FOR CLARITY.
 5. THE RISER STRUCTURE SHOWN IS NOT TO SCALE. SEE THIS SHEET FOR ACTUAL DIMENSIONS.
 6. PRECASTER SHALL ENSURE THAT RISER STRUCTURE JOINTS ARE WATERPROOFED. JOINTS SHALL INCLUDE RUBBER GASKETS. RISER JOINTS THAT WILL BE BURIED SHALL BE WATERPROOFED WITH CLASSIC FILTER FABRIC 1/4\"/>
 - 7. ALL JOINTS SHALL BE TIGHTENED TOGETHER. SEE SHEET #8.



PROFILE ALONG E OF EMBANKMENT POND #3




- NOTES**
1. USE MIX No. 2 CONCRETE.
 2. PROVIDE JOINTS AT 12 FT. INTERVALS. INSTALL JOINTS WITH 1/2\"/>
 - 3. SURFACE TO HAVE SMOOTH FINISH.
 - 4. CONCRETE SHALL BE CURED (MAINTAIN MOISTURE) FOR 2 DAYS MINIMUM AFTER POUR.
 - 5. PLACE 4x4 WELDED WIRE MESH WITH 2\"/>
 - 6. SUBGRADE SHALL BE DRY AND COMPACTED PRIOR TO POUR.
 - 7. CHANNEL SLOPE SHALL BE 1% MINIMUM AT ALL LOCATIONS.





HW-3 HEADWALL DETAIL W/ REMOVABLE TRASH RACK

- REMOVABLE TRASH RACK NOTES**
1. TRASH RACK SHALL BE ENTIRELY COVERED BY 1/2\"/>
 - 2. STEEL TO CONFORM TO ASTM A-36. #5 BARS TO BE SMOOTH. SEE DETAILS FOR SPACING.
 - 3. ALL BENDS TO BE 2\"/>
 - 4. GALVANIZE TRASH RACK AFTER FABRICATION AND PAINT BATTLESHIP GRAY (2 Coats).
 - 5. TRASH RACK SHALL PROTRUDE 1\"/>



TRASH RACK DETAIL



APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Richard M. ... 11/3/00
CHIEF, BUREAU OF HIGHWAYS DATE

OWNER
MARSHALL W. NICHOLS
C/O R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD. 21774
(301) 865-5858

ENGINEER/SURVEYOR:
R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD. 21774
(301) 865-5858

APPROVED:
THESE PLANS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.
John ... 10/26/00
HOWARD SOIL CONSERVATION DISTRICT DATE

APPROVED:
THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.
J.G. ... 10/26/00
USDA NATIONAL RESOURCES CONSERVATION SERVICE DATE

DEVELOPER'S CERTIFICATE
I/We certify that all development and construction will be done in accordance with this plan of development and plan for erosion and sediment control and that all responsible personnel involved in the construction of this project will have a certificate of attendance at a Department of the Environment approved training program for the control of sediment and erosion before beginning the project. I also authorize periodic onsite inspection by the Howard County Soil Conservation District or their authorized agents, as are deemed necessary.
Robert M. Mochi 10/26/00
Signature of Developer DATE

ENGINEER'S CERTIFICATE
I hereby certify that this plan for erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions. This plan was prepared in accordance with the requirements of the Howard Soil Conservation District. I have notified the developer that he/she must engage a registered professional engineer to supervise pond construction and provide the Howard Soil Conservation District with an "as-built" plan of the pond within 30 days of completion.
Robert M. Mochi, P.E. 10/26/00
DATE





Project	88008.13	Date	1-10-00
Illustration	JMZ	Engineering	PFB
Scale	AS SHOWN	Approval	RMA

NO.	3	DATE	10/16/00
DESCRIPTION	REVISED PER DPT COMMENTS / ANYLAR SUBMITTAL	BY	JMZ
REVISIONS	REVISED SUBMITTAL TO HOWARD CO. DPT FOR REVIEW	DATE	7-21-00
	2	DESCRIPTION	REVISED SUBMITTAL TO HOWARD COUNTY DPT FOR REVIEW
	1	DATE	4-28-00
	0	DATE	1-14-00


THE WESTWOODS OF CHERRY GROVE
ELECTION DISTRICT No. 4
HOWARD COUNTY, MARYLAND
STORMWATER MANAGEMENT DETAILS

R.M. MOCHI GROUP, P.C.
P.O. Box 10
New Market, MD 21774-0010
(301) 865-5858
Fax: (301) 865-5711


STORMWATER MANAGEMENT STRUCTURE SCHEDULE						
Pond No.	Structure	Type	Location	In	Out	Elevation
1	S-1	Concrete Riser	N 591469.65 E 1284071.85	547.90	545	554.67
	ES-1	Type "C" Endwall	N 591520.18 E 1284023.88	---	542.00	---
	HW-1	Modified Type "C" Endwall	N 591432.29 E 1284087.91	547.90	---	---
2	S-2	Concrete Riser	N 592122.34 E 1284567.19	564.50	562.00	571.00
	ES-2	Type "C" Endwall	N 592062.31 E 1284572.54	---	560.75	---
	HW-2	Modified Type "C" Endwall	N 592133.96 E 1284566.16	567.50	---	---
3	S-3	Concrete Riser	N 592534.84 E 1283538.48	559.00	558.25	566.67
	ES-3	Type "C" Endwall	N 592484.36 E 1283536.72	---	557.75	---
	HW-3	Modified Type "C" Endwall	N 592546.51 E 1283538.89	559.00	---	---



NOTES:
 1. POUR CONCRETE AGAINST UNDISTURBED EARTH. CONCRETE SHALL BE MSHA MIX NO. 3 (FC=3,500 PSD) BARREL MAY BE PLACED ON PRECAST CONCRETE BLOCKS PRIOR TO CRADLE POUR.
 2. POURING AN ADDITIONAL 4" TO 6" THICK "MUDMAY" MAY BE ACCEPTABLE IF SUBSTITUTIONS ARE MET AND WITH APPROVAL OF GEOTECHNICAL ENGINEER.
 3. IF ALL OF CONCRETE CRADLE CANNOT BE POURED AT ONE TIME, ONE HORIZONTAL JOINT IS ALLOWED. PLACE A MINIMUM OF THREE (3) - 6" LONG #4 REBAR DOVELS TO CONNECT POURS.
 4. IF A CRADLE HORIZONTAL JOINT IS USED, DO NOT LOCATE WITHIN 2' OF PIPE JOINT.



NOTES:
 1. CONCRETE SHALL BE MSHA MIX NO. 3 (FC = 3,500 PSD)




NOTES:
 1. CONCRETE SHALL BE MSHA MIX NO. 3 (FC = 3,500 PSD)

POND NO. 3 CONCRETE CRADLE (SCS TR-46; A-2)

POND NO.	ELEV. "A"	ELEV. "B"	ELEV. "C"	ELEV. "D"
1	548.90	546.40	544.90	547.90
2	565.50	563.00	561.50	564.50

NOTES:
 1. Fasten 1/4" VB to 6" DIP with retainer gland.
 2. See Howard Co. Detail SD-5.21 for reinforcement details not shown.
 3. Chamfer all exposed corners (1"x1").
 4. Use MSHA Mix No. 2 concrete.
 5. Use #4 deformed steel bars. Footing rebar shall extend into vertical wall. Lap bars 1'-6" minimum.
 6. See plan view for wall slew angle.




HW-1 & HW-2 DETAIL (MODIFIED HOWARD COUNTY DETAIL SD-5.21 - 24")

POND NO. 1 & 2 CONCRETE COLLAR (SCS TR-46; A-2)


POND NO.	ELEV. "A"	ELEV. "B"	ELEV. "C"	ELEV. "D"
1	548.90	546.40	544.90	547.90
2	565.50	563.00	561.50	564.50

NOTES:
 1. CONCRETE SHALL BE MSHA MIX NO. 3 (FC = 3,500 PSD)




CONCRETE COLLAR SECTION A-A

POND NO. 1 & 2 CONCRETE COLLAR




CONCRETE ANTI-SEEP COLLAR SECTION A-A




CONCRETE ANTI-SEEP COLLAR SECTION A-A

NOTES:
 1. ANTI-SEEP COLLARS ARE TO BE FIELD LOCATED A MINIMUM OF 2' AWAY FROM ANY PIPE JOINT. SEE PIPE PROFILE FOR APPROX. SPACING.
 2. CONCRETE SHALL BE MSHA MIX NO. 3 (FC=3,500 PSD).
 3. A "ONE POUR" COLLAR DOES NOT REQUIRE A CONSTRUCTION JOINT.
 4. PROVIDE A MINIMUM OF 2" CLEARANCE FROM OUTSIDE OF PIPE OR CONCRETE CRADLE TO OUTSIDE OF ANTI-SEEP COLLAR.
 5. CONCRETE CRADLE IS NOT SHOWN IN SECTION A-A.



GABION FOREBAY DETAIL Elevation




GABION FOREBAY DETAIL SECTION A-A

POND NO.	ELEV. "A"	ELEV. "B"	ELEV. "C"
1	560.0	562.0	561.0
2	568.5	570.5	568.5


GABION FOREBAY DETAIL SECTION A-A

Location of Trash Rack	Qty. Req'd	"A"	"B"	"C"	"D"	"E"	"F"	"G"	Notes:
POND No. 3	1	5'-6"	5'-0"	3'-3"	2'-9"	7 1/2"	6 5/8"	7"	9 Vertical Bars in front, bent top & bottom 6 Horizontal Bars in front, bent around sides 4 Horizontal Bars, 2 along top & bottom 4 Vertical Bars, 2 along each side
POND No. 2	1	5'-9"	5'-3"	4'-1"	3'-7"	7 7/8"	7 1/8"	8"	9 Vertical Bars in front, bent top & bottom 7 Horizontal Bars in front, bent around sides 4 Horizontal Bars, 2 along top & bottom 4 Vertical Bars, 2 along each side
POND No. 1 Sides A & C	2	3'-5"	3'-0"	2'-0"	1'-6"	6"	6"	6"	7 Vertical Bars in front, bent top & bottom 4 Horizontal Bars in front, bent around sides 2 Horizontal Bars, 2 along top & bottom 2 Vertical Bars, 2 along each side
POND No. 1 Side B	1	5'-9"	5'-3"	3'-6"	3'-0"	7 7/8"	6"	7"	9 Vertical Bars in front, bent top & bottom 7 Horizontal Bars in front, bent around sides 4 Horizontal Bars, 2 along top & bottom 4 Vertical Bars, 2 along each side


TRASH RACKS ARE TO BE GALVANIZED AFTER FABRICATION, AND PAINTED WITH 2 COATS OF BATTLESHIP GREY PAINT.



TRASH RACK DETAILS Elevation



TRASH RACK DETAILS SECTION A-A




TRASH RACK DETAILS SECTION A-A

CONCRETE ANTI-SEEP COLLAR SECTION A-A

RUNOFF SUMMARY TABLE - WESTWOODS OF CHERRY GROVE					
STUDY POINT #1 (POND #3)					
DRAINAGE AREA (ACRES)	EXISTING DISCHARGE (CFS)	PROPOSED DISCHARGE (CFS) (ALLOWABLE)	PROPOSED DISCHARGE (CFS) (INFLOW)	PROPOSED DISCHARGE (CFS) (OUTFLOW)	POND ELEV./ STORAGE (FT')
Q2	25.47	18.60 (D.A. 1A) 5.42 (D.A. 1B) 3.07 Total	3.6	7.7 (D.A. 1A)	562.43 / 8,854
Q10				17 (D.A. 1A-POND #3) 12 (D.A. 1B-POND #3) 23 (D.A. 1C)	564.64 / 25,282
Q100				17 (D.A. 1A-POND #3) 14 (D.A. 1B-POND #3) 24 (D.A. 1C)	565.46 / 34,910
STUDY POINT #2 (PONDS #1 and #2)					
DRAINAGE AREA (ACRES)	EXIST. DISCHARGE (CFS)	PROPOSED DISCHARGE (CFS) (ALLOWABLE)	PROPOSED DISCHARGE (CFS) (INFLOW)	PROPOSED DISCHARGE (CFS) (OUTFLOW)	POND #1 ELEV./ STORAGE (FT')
Q2	50.45	15.96 (D.A. 2B) Pond #1 11.28 (D.A. 2A) Pond #2 33.55 (D.A. 2C) Pond #3 53.53 Total	10.7	9.2 (D.A. 2B) Pond #1 9.2 (D.A. 2A) Pond #2	Pond #1 551,447 / 15,945 Pond #2 547,213 / 3,573
Q10			61.8	31.3 (D.A. 2B) Pond #1 29.4 (D.A. 2A) Pond #2 33.5 (D.A. 2C) Pond #3 52.5 (D.A. 2D) Pond #4	Pond #1 552,783 / 1,222 Pond #2 568,762 / 2,203
Q100			N/A	69.9 (D.A. 2B) Pond #1 46.5 (D.A. 2A) Pond #2 27.9 (D.A. 2C) Pond #3 161.9 (D.A. 2D) Pond #4	Pond #1 553,834 / 4,520 Pond #2 569,904 / 1,124 Pond #3 550,881 / 1,641 Pond #4 566,901 / 1,213
Extended Detention			N/A	2.82 (D.A. 2B) Pond #1 3.27 (D.A. 2A) Pond #2	

CONCRETE ANTI-SEEP COLLAR SECTION A-A



DETAIL 15 - RISER BASE DETAIL

US DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE PAGE: 8-9-88 MARSHLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
 [Signature] 11/3/00
 CHIEF, BUREAU OF HIGHWAYS

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
 [Signature] 11/13/00
 CHIEF, DIVISION OF LAND DEVELOPMENT

APPROVED: [Signature] 11/16/00
 CHIEF, DEVELOPMENT ENGINEERING DIVISION

APPROVED: THESE PLANS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.
 [Signature] 10/24/00
 HOWARD SOIL CONSERVATION DISTRICT

APPROVED: THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.
 [Signature] 10/24/00
 USDA NATIONAL RESOURCES CONSERVATION SERVICE

DEVELOPER'S CERTIFICATE
 I/We certify that all development and construction will be done according to these plans, and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I shall engage a registered professional engineer to supervise pond construction and provide the Howard Soil Conservation District with an "as-built" plan of the pond within 30 days of completion. I also authorize periodic on-site inspection by the Howard Soil Conservation District.
 [Signature] 10/24/00
 Signature of Developer

ENGINEER'S CERTIFICATE
 I certify that this plan for pond construction, erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions. This plan was prepared in accordance with the requirements of the Howard Soil Conservation District. I have notified the developer that he/she must engage a registered professional engineer to supervise pond construction and provide the Howard Soil Conservation District with an "as-built" plan of the pond within 30 days of completion.
 [Signature] 10/17/00
 R.M. Mochi, P.E.



date 01-19-00
 project 98006.15
 illustration K.M.B.
 scale as shown
 approval R.M.M.

10/06/00
 REVISED PER DPZ COMMENTS / NYLAR SUBMITTAL TO HOWARD CO. DPZ FOR REVIEW
 7-28-00
 4-28-00
 01-14-2000
 1ST SUBMITTAL TO HOWARD CO. DPZ FOR REVIEW
 no. 3
 description
 revisions

Tax Map 13, Grid 15, Parcel 46 (p/o)
THE WESTWOODS OF CHERRY GROVE
 ELECTION DISTRICT NO. 4
 HOWARD COUNTY, MD.
 STORMWATER MANAGEMENT DETAILS

OWNER
 MARSHALL W. NICHOLS
 C/O R.M. MOCHI GROUP, P.C.
 P.O. BOX 10
 NEW MARKET, MD. 21774
 (301) 865-5858

ENGINEER/SURVEYOR
 R.M. MOCHI GROUP, P.C.
 P.O. BOX 10
 NEW MARKET, MD. 21774
 (301) 865-5858

Construction Considerations

Construction monitoring should be performed during construction of the SWM facilities. If requested, HCEA can perform the required construction monitoring.

Based on the laboratory test results and previous experience at similar sites, the slopes of the embankments should be designed at 2:1 horizontal to 1.0 vertical (2.7H:1.0V) or flatter. If steeper slopes are desired, HCEA can perform direct shear strength tests to verify the soil strength properties for embankment design.

Rock Excavation

We expect that Rock will be encountered during the excavation of the basin and cutoff trench at SWM Basin No. 1 and SWM Basin No. 3. Rock excavation depths of up to 5.5 feet will be required in these areas to excavate the proposed basins. Rock surface elevations are listed above in the Subsurface Conditions section.

The depth to the rock surface encountered in the test pits may not reflect the depth between the pits, or at other portions of the site. Variations in the depth to rock should be expected between the test pits.

The rock encountered at the site is partially weathered, and we expect that much of the rock may be removed by ripping. Localized zones of hard rock may be encountered which require the use of large track hoes with hydraulic hoe rams, or possibly blasting.

The project specifications should include a definition of rock to reduce construction disputes and for budgeting purposes. Rock is defined as any material which cannot be dislodged by a D-8 Caterpillar tractor equipped with a hydraulic ripper, or by a CAT 235 hydraulic excavator. Removal of boulders larger than 1 cubic yard should be considered rock excavation.

We expect that an unclassified rock specification would be appropriate for this project. The unclassified excavation specification pays for any and all excavation in a lump sum contract price, with little record keeping of quantities required. As such, some risk is transferred to the contractor with this specification, and may increase the contingency of the contractor's bids. However, the cost of the project is known up-front and reduces the likelihood of unanticipated costs during construction. However, unclassified rock excavation specifications generally have a higher likelihood for disputes and claims for variations in subsurface conditions.

Considerations to change the site grading plans to reduce the amount of rock excavation should also be discussed.

Embankment and Cut-Off Trench Subgrade

Prior to the placement of compacted fill, the topsoil and any other unsuitable materials should be stripped from the pond embankment area or areas to receive fill. After stripping operations have been completed, the exposed subgrade materials should be profiled with a loaded dump truck, or similar equipment, in the presence of a geotechnical engineer or his representative. The purpose of the profiling is to identify loose or soft soils, and to locally densify the profiled soils. Any soft or loose materials identified by profiling should be excavated to suitable firm soil, and then graded and re-established by backfilling with suitable soil as described in the Compacted Fill section.

Based on the test pits, we expect that the embankment subgrade soils in each of the SWM facility areas will consist of firm natural soils or rock. Groundwater is not expected to be encountered within the proposed excavations, however, water may enter the excavation from precipitation or surface runoff, and may be controlled by sump pits and pumps. Construction traffic should be minimized to reduce the amount of disturbance of the subgrade soils.

We have assumed that a cutoff trench and impermeable core will be required for each of the facilities. The Soil Conservation Service of Maryland, Specification 378 (SCS-378) governs the construction and construction of the storm water management facilities. The SCS-378 document specifies that soil used in cutoff trenches and embankment cores meet USCS Classification CL (low plasticity clay), CH (high plasticity clay), SC (clayey sand), or GC (clayey gravel). Furthermore, HCEA recommends that similar materials be used for backfill adjacent to the cutoff pipe across the entire width of the embankment in order to decrease the potential of seepage and piping along the pipe.

Based on our visual observations and laboratory testing, soils meeting the recommended classifications for cutoff trench construction are readily available on site, and will require to be imported. The on-site soils classified as sandy SILT are considered suitable for use in the exterior portions of the embankments.

Rock fragments resulting from the rock excavation are expected, and may be mixed with on-site soils for use as fill in the exterior portions of the embankments. Rock fragments to be used within the embankment soils should be less than 6 inches in diameter. The rocks and soil must be well mixed prior to placement as compacted fill, with a maximum rock percentage of 50 percent.

All compacted fill should be placed in horizontal layers, maximum 8-inch loose thickness, and compacted to at least 95 percent of the maximum dry density per ASTM D-698. Sheepsfoot rollers should be used for compacting the soils within cutoff and impermeable core. Careful control of fill placement and compaction around the cutoff pipe is recommended to reduce the likelihood of seepage along the pipe. Lift thicknesses for soil compacted with walk behind equipment should be placed in 4-inch lifts (prior to compacting effort).

Moisture contents tests were conducted on 10 soil samples retrieved from our test pits. The moisture contents ranged from 16 to 33 percent as listed in the Records of Subsurface Exploration. We expect that the soils excavated from the basins will have moisture contents up to 10 percent above the optimum content required for compaction, and may require drying prior to use as compacted fill. We expect that the soils near the streams may be wet and soil excavated from higher elevations may have lower moisture contents. Similar, soils excavated below a depth of 2 to 3 feet will likely have lower moisture contents than the near surface soils. Earthwork should be scheduled in the drier months (June to October) to reduce the likelihood of delays and additional construction costs.

STORMWATER MANAGEMENT POND MAINTENANCE SCHEDULE (PONDS #1, 2, 3)

Routine Maintenance

Facility shall be inspected annually and after major storms. Inspections should be performed during wet weather to determine if the pond is functioning properly.

Top and side slopes of the embankment shall be mowed a minimum of two (2) times a year, once in June and once in September. Other side slopes, the bottom of the pond, and maintenance access should be mowed as needed.

Debris and litter next to the outlet structure shall be removed during regular mowing operations and as needed.

Visible signs of erosion in the pond as well as rip-rap outlet area shall be repaired as soon as it is noticed.

Non-Routine Maintenance

Structural components of the pond such as the dam, riser structure and the pipes shall be repaired upon the detection of any damage. The components should be inspected during routine maintenance operations.

Sediment should be removed when its accumulation significantly reduces the design storage, interferes with the function of the riser, when deemed necessary for aesthetic reasons, or when deemed necessary by the Howard County Department of Public Works.

OPERATION, MAINTENANCE AND INSPECTION

Inspection of the pond(s) shown herein shall be performed at least annually, in accordance with the checklist and requirements contained within USDA, SCS "Standards and Specifications for Ponds" (MD-378). The pond owner(s) and any heirs, successors, or assigns shall be responsible for the safety of the pond and the continued operation, surveillance, inspection, and maintenance thereof. The pond owner(s) shall promptly notify the Soil Conservation District of any unusual observations that may be indications of distress such as excessive seepage, turbid seepage, sliding or slumping.

HILLIS - CARNES ENGINEERING ASSOCIATES, INC. RECORD OF SOIL EXPLORATION

Table with 4 columns: ELEV., SOIL DESCRIPTION, DEPTH SCALE, BORDERS & SURPLING NOTES. Contains soil data for Westwood at Cherry Grove.

HILLIS - CARNES ENGINEERING ASSOCIATES, INC. RECORD OF SOIL EXPLORATION

Table with 4 columns: ELEV., SOIL DESCRIPTION, DEPTH SCALE, BORDERS & SURPLING NOTES. Contains soil data for Westwood at Cherry Grove.

HILLIS - CARNES ENGINEERING ASSOCIATES, INC. RECORD OF SOIL EXPLORATION

Table with 4 columns: ELEV., SOIL DESCRIPTION, DEPTH SCALE, BORDERS & SURPLING NOTES. Contains soil data for Westwood at Cherry Grove.

STORMWATER MANAGEMENT CONSTRUCTION SPECIFICATIONS

THESE SPECIFICATIONS ARE APPROPRIATE TO ALL PONDS WITHIN THE SCOPE OF THE STANDARD FOR PRACTICE MD-378. ALL REFERENCES TO ASTM AND AASHTO SPECIFICATIONS APPLY TO THE MOST RECENT VERSION.

I. SITE PREPARATION

AREAS DESIGNATED FOR BORROW AREAS, EMBANKMENT, AND STRUCTURAL WORKS SHALL BE FREE OF ROOTS, STUMPS, WOOD, RUBBER, STONES GREATER THAN 4 INCHES, FENCIBLES, RUBBER AND OTHER OBSTRUCTIONABLE MATERIAL UNLESS OTHERWISE DESIGNATED ON THE PLANS, TREES, BRUSH AND STUMPS SHALL BE CUT APPROXIMATELY 12 FEET WITH THE ORIGINAL SURFACE FOR DRY STORMWATER MANAGEMENT PONDS. A MINIMUM OF A 50 FOOT RADIUS AROUND THE INLET STRUCTURE SHALL BE CLEARED.

II. EARTH FILL

THE FILL MATERIAL SHALL BE TAKEN FROM APPROVED DESIGNATED BORROW AREAS, IT SHALL BE FREE OF ROOTS, STUMPS, WOOD, RUBBER, STONES GREATER THAN 4 INCHES, FENCIBLES, RUBBER AND OTHER OBSTRUCTIONABLE MATERIAL UNLESS OTHERWISE DESIGNATED ON THE PLANS, TREES, BRUSH AND STUMPS SHALL BE CUT APPROXIMATELY 12 FEET WITH THE ORIGINAL SURFACE FOR DRY STORMWATER MANAGEMENT PONDS.

III. STRUCTURE BACKFILL

BACKFILL ADJACENT TO PIPES OR STRUCTURES SHALL BE OF THE TYPE AND QUALITY CONFORMING TO THAT SPECIFIED FOR THE ADJOINING FILL MATERIAL. THE FILL SHALL BE PLACED IN HORIZONTAL LAYERS NOT TO EXCEED FOUR INCHES IN THICKNESS AND COMPACTED BY HAND TAMPORS OR OTHER MANUALLY DIRECTED COMPACTION EQUIPMENT. THE MATERIAL NEEDS TO BE FULLY COMPACTED TO THE UNDER AND AROUND THE PIPE TO THE POINT OF NO INTERFERENCE WITH THE OPERATION OR MAINTENANCE OF THE STRUCTURE. STREAM DIMENSIONS SHALL BE MAINTAINED UNTIL AFTER THE EXCAVATION AND THE FOUNDATION SHALL BE REMOVED FROM THE REQUIRED EXCAVATION AND THE FOUNDATION SHALL BE PUMPED IN MANNER AND TO THE EXTENT THAT WILL MAINTAIN STABILITY OF THE EXCAVATED SCOPES AND BOTTOM OF REQUIRED EXCAVATION.

IV. PIPE CONDUITS

ALL PIPES SHALL BE CIRCULAR IN CROSS SECTION. CORRUGATED METAL PIPE. ALL OF THE FOLLOWING CRITERIA SHALL APPLY FOR CORRUGATED METAL PIPE: 1. MATERIALS (STEEL PIPE). THIS PIPE AND ITS APPURTENANCES SHALL BE GALVANIZED AND FULLY BITUMINOUS COATED AND SHALL CONFORM TO THE REQUIREMENTS OF AASHTO SPECIFICATION M-190 PIPE WITH WATER TIGHT COUPLING BANDS. ANY BITUMINOUS COATING DAMAGED OR OTHERWISE REMOVED SHALL BE REPLACED WITH HOT APPLIED BITUMINOUS COATING COMPOUND. STEEL PIPES WITH POLYMERIC COATINGS SHALL HAVE A MINIMUM COATING THICKNESS OF 0.01 INCH (1 MIL) ON BOTH SIDES OF THE PIPE. THE FOLLOWING COATINGS OR AN APPROVED EQUAL MAY BE USED: NEXON, PLASTI-COTE, BLACK-MAX, AND BETH-CL-LOV-PC. COATED CORRUGATED STEEL PIPE SHALL MEET THE REQUIREMENTS OF AASHTO M-245 AND M-246.

CONNECTIONS

CONNECTIONS WITH PIPES MUST BE COMPLETELY WATER TIGHT. THE DRAIN PIPE OR BARREL CONNECTION TO THE RISER SHALL BE WELDED ALL AROUND WHEN THE PIPE AND RISER ARE METAL. ANTI-SEEP COLLARS SHALL BE CONNECTED TO THE PIPE IN SUCH A MANNER AS TO BE COMPLETELY WATER TIGHT. DWIPLE BANDS ARE NOT CONSIDERED TO BE WATER TIGHT. ALL CONNECTIONS SHALL USE A RUBBER OR NEOPRENE GASKET WHEN JOINING PIPE SECTIONS. THE END OF EACH PIPE SHALL BE PROVIDED AN ACCEPTABLE NUMBER OF CORRUGATIONS TO ACCOMMODATE THE BAND WIDTH. THE FOLLOWING TYPE CORRUGATIONS ARE ACCEPTABLE FOR PIPES LESS THAN 24 IN. IN DIAMETER: 12 IN. WIDE BY 3/8" THICK CLOSED CELL CIRCULAR NEOPRENE GASKET. AND A 12" WIDE BY 3/8" THICK CLOSED CELL CIRCULAR NEOPRENE GASKET. A MINIMUM DIAMETER OF 1/2" GREATER THAN THE CORRUGATION DEPTH. PIPES 24" IN DIAMETER AND LARGER SHALL BE CONNECTED BY A 24" LONG ANNUAL CORRUGATED BAND USING RODS AND LUGS. A 12" WIDE BY 3/8" THICK CLOSED CELL CIRCULAR NEOPRENE GASKET WILL BE INSTALLED ON THE END OF EACH PIPE FOR A TOTAL OF 24".

HILLIS - CARNES ENGINEERING ASSOCIATES, INC. RECORD OF SOIL EXPLORATION

Table with 4 columns: ELEV., SOIL DESCRIPTION, DEPTH SCALE, BORDERS & SURPLING NOTES. Contains soil data for Westwood at Cherry Grove.

HILLIS - CARNES ENGINEERING ASSOCIATES, INC. RECORD OF SOIL EXPLORATION

Table with 4 columns: ELEV., SOIL DESCRIPTION, DEPTH SCALE, BORDERS & SURPLING NOTES. Contains soil data for Westwood at Cherry Grove.

HILLIS - CARNES ENGINEERING ASSOCIATES, INC. RECORD OF SOIL EXPLORATION

Table with 4 columns: ELEV., SOIL DESCRIPTION, DEPTH SCALE, BORDERS & SURPLING NOTES. Contains soil data for Westwood at Cherry Grove.

HILLIS - CARNES ENGINEERING ASSOCIATES, INC. RECORD OF SOIL EXPLORATION

Table with 4 columns: ELEV., SOIL DESCRIPTION, DEPTH SCALE, BORDERS & SURPLING NOTES. Contains soil data for Westwood at Cherry Grove.

HILLIS - CARNES ENGINEERING ASSOCIATES, INC. RECORD OF SOIL EXPLORATION

Table with 4 columns: ELEV., SOIL DESCRIPTION, DEPTH SCALE, BORDERS & SURPLING NOTES. Contains soil data for Westwood at Cherry Grove.

HILLIS - CARNES ENGINEERING ASSOCIATES, INC. RECORD OF SOIL EXPLORATION

Table with 4 columns: ELEV., SOIL DESCRIPTION, DEPTH SCALE, BORDERS & SURPLING NOTES. Contains soil data for Westwood at Cherry Grove.

OWNER ENGINEER/SURVEYOR:

MARSHALL W. NICHOLS C/O R.M. MOCHI GROUP, P.C. PO BOX 10 NEW MARKET, MD. 21774 (301) 865-5858

R.M. MOCHI GROUP, P.C. PO BOX 10 NEW MARKET, MD 21774 (301) 865-5858



APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

APPROVED: THESE PLANS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

APPROVED: THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL.

DEVELOPER'S CERTIFICATE I/We certify that all development and construction will be done according to these plans, and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I shall engage a registered professional engineer to supervise pond construction and provide the Howard Soil Conservation District with an "as-built" plan of the pond within 30 days of completion. I also authorize periodic on-site inspections by the Howard Soil Conservation District.

ENGINEER'S CERTIFICATE I certify that this plan for pond construction, erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions. This plan was prepared in accordance with the requirements of the Howard Soil Conservation District. I have notified the developer that he/she must engage a registered professional engineer to supervise pond construction and provide the Howard Soil Conservation District with an "as-built" plan of the pond within 30 days of completion.

Signature: Cindy Hamler, Chief, Division of Land Development, 4/14/10

Signature: Andrew M. Ducker, Chief, Bureau of Highways, 4/16/10

Signature: Mark A. [unclear], Howard Soil Conservation District, 10/20/10






Signature: J. C. [unclear], USDA - Natural Resources Conservation Service, 10/20/10

Signature: [unclear], Date: 10/20/10

Signature: R.M. Mochi, Date: 10/20/10

PROFILES ALONG CL STORM DRAIN


SCALE: 1" = 50' HORIZ.
1" = 5' VERT.



CULVERT AT ENTRANCE TO COLTON COURT

SCALE: 1" = 20' HORIZ.
1" = 2' VERT.

Type	Total Length
18" HDPE	1341'
24" HDPE	149'
15" RCP CLASS IV	28'



STORM DRAIN DRAINAGE AREAS						
Subarea	Zoning	Area (ac)	Area (sq mi)	"C" Factor	% Impervious	Tc (hr)
(B)	(Z)	(A)	(A)	(C)	(P)	
A	RC-DEO	4.22	0.0066	0.31	27	0.20
B	RC-DEO	7.14	0.0110	0.27	17	0.33
C	RC-DEO	0.35	0.0005	0.52	49	0.17
D	RC-DEO	1.55	0.0024	0.32	26	0.25

STORM DRAIN STRUCTURE SCHEDULE					
No.	Type	Location	Location	Remarks	
I-1	Precast Open End Grate	N	591709.76	E	1284795.88 SD 4.36
I-2	Precast Open End Grate (Double Opening)	STA	2+24.08	O/S	7.50 (Lin. Prof) SD 4.36
I-3	Precast Open End Grate (Double Opening)	STA	1+58.40	O/S	7.50 (Lin. Prof) SD 4.36
I-4	Precast Open End Grate (Double Opening)	STA	1+59.84	O/S	7.50 (Lin. Prof) SD 4.36
M-1	40" Precast Manhole	N	591325.78	E	1284359.92 GS.12
M-2	40" Precast Manhole	N	591569.32	E	1284432.23 GS.12
M-3	40" Precast Manhole	N	591685.84	E	1284609.74 GS.12
M-4	40" Precast Manhole	N	591244.63	E	1284563.85 GS.12
M-5	40" Precast Manhole	N	592071.15	E	1284449.80 GS.12
ES-4	Type "C" Endwall Circular Pipe	N	591364.97	E	1284233.72 SD 5.21
ES-5	Type "C" Endwall Circular Pipe	N	592093.58	E	1284487.20 SD 5.21
ES-6	Concrete End Section	STA	0+40	O/S	14.00 R SD 5.52
ES-7	Concrete End Section	STA	0+40	O/S	14.00 L SD 5.52

* All precast open end grates to be used with the standard type "K" inlet grate (SD 4.13)

OWNER
MARSHALL W. NICHOLS
C/O R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD. 21774
(301) 865-5858

ENGINEER/SURVEYOR:
R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD. 21774
(301) 865-5858

APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Andrew M. Donelle 11-5-00
CHIEF, BUREAU OF HIGHWAYS

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Cindy Amodeo 11/13/0
CHIEF, DIVISION OF LAND DEVELOPMENT

APPROVED:
John Danner 11/16/00
CHIEF, DEVELOPMENT ENGINEERING DIVISION








DATE	DESCRIPTION	BY
04-17-00	engineering	RAM
08008-13	illustration	JMZ
	scale	As Shown
	approval	RAM

NO.	DESCRIPTION	DATE
3	REVISED PER DPZ COMMENTS / M.V.L.R. SUBMITTAL 10/14/00	10/14/00
2	REVISED SUBMITTAL TO HOWARD COUNTY DPZ FOR REVIEW 7-21-00	7-21-00
1	REVISED SUBMITTAL TO HOWARD COUNTY DPZ FOR REVIEW 04-28-2000	04-28-2000
0	SUBMITTED TO HOWARD CO. DPZ FOR REVIEW 01-14-2000	01-14-2000

Tax Map 13, Grid 15, Parcel 46 (p/o)
THE WESTWOODS OF CHERRY GROVE
HOWARD COUNTY, MD
ELECTION DISTRICT NO. 4
STORM DRAIN PROFILES

R.M. MOCHI GROUP, P.C.
P.O. Box 10
New Market, MD 21774-0010
(301) 865-5858
Fax: (301) 865-3711

F.00.105



PERMANENT SEEDING NOTES

Apply to graded or cleared area not subject to immediate further disturbance with a permanent long-lived vegetative cover is needed.

Soil Amendments: In lieu of soil test recommendations, use on the following conditions:

- Preferred - Apply 2 tons per acre dolomitic limestone (92 lbs/1000 sf) and 600 lbs per acre 10-10-10 fertilizer (14 lbs/1000 sf) before seeding. Harrow or disc into upper three inches of soil. At time of seeding, apply 400 lbs per acre 30-0-0 urea-form fertilizer (9 lbs/1000 sf).
- Acceptable - Apply 2 tons per acre dolomitic limestone (92 lbs/1000 sf) and 1000 lbs per acre 10-10-10 fertilizer (23 lbs/1000 sf) before seeding. Harrow or disc into upper three inches of soil.

Seeding: For the periods March 1 through April 30 and August 1 through October 15, seed with 60 lbs per acre (1.4 lbs/1000 sf) of Kentucky 31 Tall Fescue. For the period May 1 through July 31, seed with 60 lbs Kentucky 31 Tall Fescue per acre and 2 lbs per acre (0.05 lbs/1000 sf) of Weeping Lovegrass. During the period of October 16 through February 28, protect site by Option 1) 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring. Option 2) use seed. Option 3) seed with 60 lbs/acre Kentucky 31 Tall Fescue and mulch with 2 tons/acre well anchored straw.

Mulching: Apply 1-1/2 to 2 tons per acre (70 to 90 lbs/1000 sf) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gallons per acre (5 gal/1000 sf) of emulsified asphalt on flat areas. On slopes 8 feet or higher, use 348 gallons per acre (8 gal/1000 sf) for anchoring.

Maintenance: Inspect all seeded areas and make needed repairs, replacements and reseedings.

TEMPORARY SEEDING NOTES

Apply to graded or cleared areas likely to be restituted where a short-term vegetative cover is needed.

Soil Amendments: Apply 600 lbs per acre (1.4 lbs/1000 sf) of Kentucky 31 Tall Fescue.





Seeding: For periods March 1 through April 30 and from August 15 through November 15, seed with 2-1/2 bushel per acre of annual ryegrass (3.2 lbs/1000 sf). For the period May 1 through August 14, seed with 3 lbs per acre of Weeping Lovegrass (0.07 lbs/1000 sf). For the period November 16 through February 28, protect site by applying 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring, or use seed.

Mulching: Apply 1-1/2 to 2 tons per acre (70 to 90 lbs/1000 sf) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gallons per acre (5 gal/1000 sf) of emulsified asphalt on flat areas. On slopes 8 feet or higher, use 348 gallons per acre (8 gal/1000 sf) for anchoring.

Refer to the 1994 Maryland Standards and Specifications for Soil Erosion and Sediment Control for rate and methods not covered.

SEDIMENT CONTROL NOTES

- A minimum of 48 hours notice must be given to the Howard County Department of Inspections, Licenses and Permits, Sediment Control Division prior to the start of any construction (10-21-2003).
- All vegetative and structural practices are to be installed according to the provisions of this plan and in accordance with the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL (10-21-2003).
- Following installation of practices or re-disturbance, permanent or temporary stabilization shall be completed within 72 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and/or ground surface. For the period November 16 through February 28, protect site by applying 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring, or use seed.
- All sediment control structures are to remain in place and are to be maintained in operative condition until removal has been obtained from the Howard County Sediment Control Inspector.
- Site Area: 63,326 Ac. Total Area to be Disturbed: 7.7 Ac. Area to be seeded or planted: 6.1 Ac. Total FFC: 10,400 c.y. Off Site Sediment/Borrow Area: N/A
- Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
- Additional sediment controls must be installed, if deemed necessary by the Howard County Sediment Control Inspector.
- On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of installation of perimeter erosion and sediment control structures and before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the inspection agency is made.
- On all sites with disturbed areas, the construction of utilities is limited to three pipe lengths or that which shall be back-filled and stabilized within one working day, whichever is shorter. Quantities and estimates shown are for sediment control purposes only. Contractor shall prepare his own quantity estimates to his/her satisfaction.
- Any excess material shall be transported to a suitable spoil site with appropriate sediment control measures as required by this plan.



SEQUENCE OF CONSTRUCTION

- Obtain all required permits, approvals and licenses from appropriate agencies. 2 weeks.
- Notify Howard County Construction Inspection Division (410-313-1880) at least five (5) working days prior to starting work. 1 day.
- Install temporary traffic control measures. 2 days.
- Install stabilized construction entrances. Install line conservation signs and tree protection fences as required (See Signs & Fence Detail on Sheet B).
- Construct SWM Ponds. 2 days.
- Install silt fence below SWM ponds. Install clean water diversion dikes for Pond #2 to divert clean water away from pond construction area. 2 weeks.
- Clear and grub area for SWM ponds.
- Complete embankment fills and diversion pipes for Pond #1.
- Install temporary seeding and cover for SWM ponds as verified by a Professional Engineer.
- Upon obtaining proper inspections and certifications, backfill principal spillway.
- Complete embankment fills and excavate for pond volumes per approved construction. Delay construction of forestry, construction of temporary sediment control vertical draw-down dikes and brick walls per details on Sheets (H) and (I).
- Secure permission from Inspector before proceeding. 1 week.
- Clear and grub remainder of site. Mass grade site. (Note: The existing gravel driveway to the Bounded property will be maintained in place and open for use until Colton Court is completed and the Bounded property is connected. Particular attention will be paid to assuring minimum disturbance to Bounded traffic at the point where Colton Court and the gravel driveway intersect.)
- Construct storm drains. Upon installation of 14" brick stub and bypass flows from site. 3 weeks.
- Remove temporary seeding and cover for SWM ponds. 3 weeks.
- Upon stabilization of all disturbed areas, clean and flush storm drainage. Ponds and sediment control structures, convert sediment basins to final SWM Ponds and stabilize construction. 1 week.
- Notify Howard County Office of Inspection and Permits for final inspection of completed project. 1 week.

Placement of Topsoil over prepared subsoil prior to establishment of permanent vegetation.

Purpose: To provide a suitable soil medium for vegetation growth. Soils of concern have low moisture content, low nutrient levels, low pH, materials toxic to plants, and/or unacceptable soil profile.

Conditions Where Practice Applies:

- This practice is limited to areas having 2:1 or flatter slopes where:
 - The texture of the exposed subsoil/parent material is not adequate to produce vegetative growth.
 - The soil material is so shallow that the zone material is not deep enough to support plants or furnish continuing supplies of moisture and plant nutrients.
 - The original soil to be vegetated contains material toxic to plant growth.
 - The soil is so acidic that treatment with limestone is not feasible.
- For the purpose of these standards and specifications, areas having slopes steeper than 2:1 require special consideration and design for adequate stabilization. Areas having slopes steeper than 2:1 shall have the appropriate stabilization shown on plans.

Construction and Material Specifications:

- Topsoil salvaged from the existing site may be used provided that it meets the standards set forth in these specifications. Typically, the depth of the topsoil to be salvaged for a given soil class can be found in the representative soil profile section in the Soil Survey published by USDA-NRCS in cooperation with Maryland Agricultural Experiment Station.
- Topsoil Specifications - Soil to be used as topsoil must meet the following:
 - Topsoil shall be a loam, sandy loam, clay loam, silt loam, sandy clay loam, loamy sand. Other soils may be used if recommended by an agronomist or soil scientist and approved by the appropriate approval authority. Topsoil shall not be a mixture of contrasting textured subsoils and shall contain less than 5% by volume of cinders, stones, slag, coarse fragments, and other materials. For the period November 16 through February 28, protect site by applying 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring, or use seed.
 - Topsoil must be free of plants or plant parts such as Bermuda grass, quack grass, Johnsongrass, nutgrass, poison ivy, thistle, or others as specified.
 - Where the subsoil is highly acidic or composed of materials 20:1 clay (100:1 clay) the topsoil shall be applied at a rate of 4-8 tons/acre (200-400 pounds per 1,000 square feet) prior to the placement of topsoil. Line shall be distributed uniformly over disturbed areas and worked into the soil in conjunction with tillage operations as described in the following procedures.
 - Topsoil shall be applied at a rate of 4-8 tons/acre (200-400 pounds per 1,000 square feet) prior to the placement of topsoil. Line shall be distributed uniformly over disturbed areas and worked into the soil in conjunction with tillage operations as described in the following procedures.
 - Topsoil shall be applied at a rate of 4-8 tons/acre (200-400 pounds per 1,000 square feet) prior to the placement of topsoil. Line shall be distributed uniformly over disturbed areas and worked into the soil in conjunction with tillage operations as described in the following procedures.
 - For sites having disturbed areas over 5 acres:
 - Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section 1 - Vegetative Stabilization Methods and Materials.
 - On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of installation of perimeter erosion and sediment control structures and before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the inspection agency is made.
 - On all sites with disturbed areas, the construction of utilities is limited to three pipe lengths or that which shall be back-filled and stabilized within one working day, whichever is shorter. Quantities and estimates shown are for sediment control purposes only. Contractor shall prepare his own quantity estimates to his/her satisfaction.
 - Any excess material shall be transported to a suitable spoil site with appropriate sediment control measures as required by this plan.
 - No soil or seed shall be placed on soil which has been previously established, shall be maintained, about 4" - 8" higher in elevation.
 - Alternative for Permanent Seeding - Instead of applying the full amounts of lime and commercial fertilizer, composted sludge and amendments may be applied as specified below.
 - Composted Sludge Material for use as a soil conditioner for sites having disturbed areas over 5 acres shall be tested to prescribed amendments and for sites having disturbed areas under 5 acres shall conform to the following requirements:
 - Composted sludge shall be applied by, or originate from, a person or persons who are registered or licensed in the regulation of the compost by the Maryland Department of the Environment under COMAR 26.04.06.
 - Composted sludge shall contain at least 1 percent nitrogen, 1.5 percent phosphorus, and 0.2 percent potassium and have a Ph of 7.0 to 8.0. If compost does not meet these requirements, the appropriate constituents must be added to meet the requirements prior to use.
 - Composted sludge shall be applied at a rate of 1 ton / 1,000 square feet.
 - Composted sludge shall be amended with a potassium fertilizer applied at the rate of 4 lb. / 1,000 square feet, and 1/3 the normal lime application rate.

TABLE 2.0 MATERIALS SPECIFICATIONS

CLASS	APPROXIMATE OPENING SIZE (IN. MAX.)	GRAIN TENSILE STRENGTH (LB. MAX.)	BURST STRENGTH (PSI. MIN.)
A	0.30	250	300
B	0.60	300	320
C	0.30	200	330
D	0.60	90	145
E	0.30	90	145
F	0.60/0.90	90	150

The properties shall be determined in accordance with the following procedures:

Apparent opening size: MSHT 523

Grab tensile strength: ASTM D 1682; 48" squares, 12" strips, 12" wide, ends one in each perpendicular direction of tensile fabric.




Burst strength: ASTM D 5786

The fabric shall be tested to determine tensile strength and hydrostatic, and will be set and allow release. It shall be constructed from fibers consisting of long chain polypropylene, and composed of a minimum of 85% by weight of polypropylene, polyethylene, or polybutene. The geotextile fabric shall demonstrate three straight edges.

In addition, Class A through E shall have a 0.01 mm. minimum permeability when tested in accordance with MSHT 507, and an apparent modulus of at least 20 percent (20%) when tested in accordance with the burst strength requirements listed above.

Class F geotextile fabric for all uses shall have a 50 lb/in. ultimate tensile strength and a 20 lb/in. ultimate modulus when tested in accordance with MSHT 509. The fabric shall also have a 0.3 gal/100 sq ft/min. flow rate and a maximum flow rate of 0.3 gal/100 sq ft/min. when tested in accordance with MSHT 502.

Geotextile fabric shall be the construction of all fabric shall conform to the following specifications. The fabric shall conform to the following specifications: 10% of expected ultimate construction life at a temperature range of 0 to 120 degrees F.



OWNER

MARSHALL W. NICHOLS
C/O R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD. 21774
(301) 865-5858

ENGINEER/SURVEYOR

R.M. MOCHI GROUP, P.C.
P.O. BOX 10
NEW MARKET, MD. 21774
(301) 865-5858

STONE FOR GABION BASINS

NUMBER	SIZE RANGE	D ₁₅	D ₅₀	CLASSIFICATION	WEIGHT
1	3/4" - 1 1/2"	1/2"	1 1/2"	M-43	N/A
2	1 1/2" - 2"	1"	2"	M-43	N/A
3	2" - 3"	1 1/2"	3"	N/A	N/A
4	3" - 4"	2"	4"	N/A	N/A
5	4" - 5"	3"	5"	N/A	N/A
6	5" - 6"	4"	6"	N/A	N/A
7	6" - 8"	5"	8"	N/A	N/A
8	8" - 12"	6"	12"	N/A	N/A
9	12" - 18"	8"	18"	N/A	N/A
10	18" - 24"	10"	24"	N/A	N/A
11	24" - 36"	12"	36"	N/A	N/A
12	36" - 48"	15"	48"	N/A	N/A
13	48" - 60"	18"	60"	N/A	N/A
14	60" - 72"	21"	72"	N/A	N/A
15	72" - 84"	24"	84"	N/A	N/A
16	84" - 96"	27"	96"	N/A	N/A
17	96" - 108"	30"	108"	N/A	N/A
18	108" - 120"	33"	120"	N/A	N/A
19	120" - 132"	36"	132"	N/A	N/A
20	132" - 144"	39"	144"	N/A	N/A
21	144" - 156"	42"	156"	N/A	N/A
22	156" - 168"	45"	168"	N/A	N/A
23	168" - 180"	48"	180"	N/A	N/A
24	180" - 192"	51"	192"	N/A	N/A
25	192" - 204"	54"	204"	N/A	N/A
26	204" - 216"	57"	216"	N/A	N/A
27	216" - 228"	60"	228"	N/A	N/A
28	228" - 240"	63"	240"	N/A	N/A
29	240" - 252"	66"	252"	N/A	N/A
30	252" - 264"	69"	264"	N/A	N/A
31	264" - 276"	72"	276"	N/A	N/A
32	276" - 288"	75"	288"	N/A	N/A
33	288" - 300"	78"	300"	N/A	N/A
34	300" - 312"	81"	312"	N/A	N/A
35	312" - 324"	84"	324"	N/A	N/A
36	324" - 336"	87"	336"	N/A	N/A
37	336" - 348"	90"	348"	N/A	N/A
38	348" - 360"	93"	360"	N/A	N/A
39	360" - 372"	96"	372"	N/A	N/A
40	372" - 384"	99"	384"	N/A	N/A
41	384" - 396"	102"	396"	N/A	N/A
42	396" - 408"	105"	408"	N/A	N/A
43	408" - 420"	108"	420"	N/A	N/A
44	420" - 432"	111"	432"	N/A	N/A
45	432" - 444"	114"	444"	N/A	N/A
46	444" - 456"	117"	456"	N/A	N/A
47	456" - 468"	120"	468"	N/A	N/A
48	468" - 480"	123"	480"	N/A	N/A
49	480" - 492"	126"	492"	N/A	N/A
50	492" - 504"	129"	504"	N/A	N/A
51	504" - 516"	132"	516"	N/A	N/A
52	516" - 528"	135"	528"	N/A	N/A
53	528" - 540"	138"	540"	N/A	N/A
54	540" - 552"	141"	552"	N/A	N/A
55	552" - 564"	144"	564"	N/A	N/A
56	564" - 576"	147"	576"	N/A	N/A
57	576" - 588"	150"			



SOIL LEGEND		
SYMBOL	NAME	GROUP
ChA	Chester silt loam, 0 to 3% slopes	B
ChB2	Chester silt loam, 3 to 8% slopes, moderately eroded	B
ChC2	Chester silt loam, 8 to 15% slopes, moderately eroded	B
ChD2	Chester silt loam, 15 to 25% slopes, moderately eroded	B
G1B2	Glenelg loam, 3 to 8% slopes, moderately eroded	B
G1C3	Glenelg loam, 8 to 15% slopes, severely eroded	B
GnB2	Glenville silt loam, 3 to 8% slopes, moderately eroded	C
MID2	Manor loam, 15 to 25% slopes, moderately eroded	B
MI2	Mt. Airy channery loam, 8 to 15% slopes, moderately eroded	B
GnB2 *	Glenville silt loam, 3 to 8% slopes, moderately eroded	C

* Soils with hydric inclusions

OWNER	ENGINEER/SURVEYOR
MARSHALL W. NICHOLS C/O R.M. MOCHI GROUP, P.C. P.O. BOX 10 NEW MARKET, MD. 21774 (301) 865-5858	R.M. MOCHI GROUP, P.C. P.O. BOX 16 NEW MARKET, MD. 21774 (301) 865-5858

project	98008.13	date	01-13-00
illustration	KMB	engineering	PFB
scale	1"=100'	approval	RAM

1	REVISED PER DZ COMMENTS / ANY OF SUBMITTAL	DATE	11/24/00
2	REVISED SUBMITTAL TO HOWARD COUNTY DEPT. OF PUBLIC WORKS	DATE	7/25/01
3	SUBMITTED TO HOWARD COUNTY DEPT. FOR REVIEW	DATE	01-14-2000
4		DESCRIPTION	REVISIONS

Tax Map 13, Grid 15, Parcel 46 (p/o)
THE WESTWOODS OF CHERRY GROVE
 ELECTION DISTRICT NO. 4
 HOWARD COUNTY, MD
PROPOSED SWM/STORM DRAIN DRAINAGE AREA MAP

R.M. MOCHI GROUP, P.C.
 P.O. Box 10
 New Market, MD 21774-0010
 (301) 865-5858
 Fax: (301) 865-5111

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

 CHIEF, BUREAU OF HIGHWAYS
 DATE: 11-3-00

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING

 CHIEF, DIVISION OF LAND DEVELOPMENT
 DATE: 11/16/00

LEGEND:
 - - - - - PROPOSED S.W.M. DRAINAGE AREAS
 - - - - - PROPOSED STORM DRAIN DRAINAGE AREAS
 - - - - - Tc PATHS

(B) X FLOODPLAIN STUDY PT.
 S.W.M. SUBAREAS
 (A) FOR DETAILS SEE APPROPRIATE STUDY SHEET

STORMWATER MANAGEMENT DRAINAGE AREAS						
Subarea (B)	Zoning (Z)	Area (ac) (A)	Area (sq mi) (A)	CN (C)	% Impervious (P)	Tc (hr)
1A	RC-DEO	18.60	0.0281	63	12	0.32
1B	RC-DEO	4.47	0.0070	61	5	0.24
2A	RC-DEO	13.50	0.0211	66	16	0.23
2B	RC-DEO	15.90	0.0248	65	12	0.26
2C	RC-DEO	23.95	0.0374	61	5	0.29
3A	RC-DEO	15.20	0.0238	62	9	0.45

STORM DRAIN DRAINAGE AREAS						
Subarea (B)	Zoning (Z)	Area (ac) (A)	Area (sq mi) (A)	"C" Factor (C)	% Impervious (P)	Tc (hr)
A	RC-DEO	4.22	0.0068	0.31	27	0.24
B	RC-DEO	7.14	0.0110	0.27	17	0.33
C	RC-DEO	0.35	0.0005	0.52	49	0.17
D	RC-DEO	1.55	0.0024	0.32	26	0.25

NOTE: THIS SHEET TO BE USED FOR DRAINAGE AREAS ONLY.