

## MANAGEMENT NOTES FOR FOREST RETENTION AREAS

1. All proposed activities shall adhere to the conditions, schedules and terms of an approved sediment control and erosion plan.

2. After the boundaries of the retention area have been staked and flagged and before any disturbance has taken place on-site, a preconstruction meeting at the construction site shall take place. The developer, contractor or project manager, and appropriate County inspectors shall attend.

3. Prior to grading, the contractor shall arrange to meet with the forester to determine adequate protection measures for Specimen Trees located on buildable

4. Tree protection for all retained areas:

a. All retention areas within 50 feet of proposed construction activities shall be protected by highly visible, well anchored temporary protection devices (silt fence or blaze orange plastic mesh).

b. All protection devices shall be in place prior to any grading or land

c. All protection devices shall be properly maintained and shall remain in place until construction has ceased.

d. Attachment of signs, fencing or other objects to trees is prohibited. e. No equipment, machinery, vehicles, materials or excessive pedestrian traffic shall be allowed within protected areas.

5. If the critical root zone (see detail) is affected by construction activities such as grade change, digging for foundations and roads or utility installation

a. Prune roots with a clean cut using proper pruning equipment (see root pruning detail)

b. Water and fertilize as needed.

6. Buring construction phase, monitor and correct condition of retained trees for soil compaction, root injury, flood conditions, drought conditions and other stress signs.

7. Post-Construction Phase

a. Inspect existing trees around the perimeter of disturbed limits for evidence of soil compaction, root injury, limb injury, or other stress signs and correct with proper management techniques such as root or limb prunir soil aeration, fertilization, crown reduction or watering. Inspection and evaluation shall be performed by a licensed arborist.

b. Inspect for dead or dying trees or limbs which may pose safety hazard and remove.


c. No burial of discarded materials will occur onsite within the conservation

d. No burning within 100 feet of wooded area.


e. All temporary forest protection structures will be removed after


f. Following completion of construction, prior to use, the County inspector shall inspect the entire area.

THE FOREST CONSERVATION EASEMENTS WILL BE ESTABLISHED TO FULFILL THE REQUIREMENTS OF SECTION 16.1200 OF THE HOWARD COUNTY CODE. NO CLEARING, GRADING, OR CONSTRUCTION IS PERMITTED WITHIN THE FOREST CONSERVATION EASEMENTS, HOWEVER, FOREST MANAGEMENT PRACTICES AS DEFINED IN THE DEED OF FOREST CONSERVATION EASEMENT ARE ALLOWED.














TREE PROTECTION DETAIL













COMBINED FOREST STAND DELINEATION AND FOREST CONSERVATION PLAN BLACKSTONE MANOR LOTS 1, 2, AND O.S. LOT 3

> TAX MAP: 37 PARCEL: 351 BLOCK NO. 12 FIRST ELECTION DISTRICT HOWARD COUNTY, MARYLAND SCALE: 1"=30' DATE: NOV. 15, 2001 SHEET 2 OF 2

F02-76