

# FINAL PLAN STORMWATER MANAGEMENT FACILITIES DRAINAGE AREA B

## THE JOHNS HOPKINS UNIVERSITY APPLIED PHYSICS LABORATORY LOCATED SOUTHEAST INTERSECTION OFF ROUTE 29 & 32 IN HOWARD COUNTY, MD

### INDEX OF DRAWINGS

- C1. COVER SHEET
- C2. OVERALL DRAINAGE AREA--APL
- C3. DRAINAGE AREA "B"
- C4. DRAINAGE AREA "B"
- C5. SITE, LAYOUT
- C6. POND GRADING/DRAINAGE PLAN
- C7. PIPE PROFILE
- C8. EMBANKMENT PROFILE AND PIPE PROFILES
- C9. SWM DETAILS
- C10. SWM2 DETAILS
- C11. DETAILS
- C12. STORMCEPTOR DETAILS
- C13. POND SPECS
- C14. BORING LOCATIONS AND DATA

- ES-1. EROSION AND SEDIMENT CONTROL PLAN
- ES-2. EROSION AND SEDIMENT CONTROL NOTES & DETAILS
- ES-3. EROSION AND SEDIMENT CONTROL NOTES & DETAILS
- ES-4. EROSION AND SEDIMENT CONTROL NOTES & DETAILS
- L-1. LANDSCAPE PLAN
- L-2. LANDSCAPE NOTES & DETAILS PLAN

### GENERAL NOTES


1. THE TOPOGRAPHIC AND UTILITY INFORMATION SHOWN IN THIS DEVELOPMENT PLAN WERE OBTAINED FROM FIELD SURVEYS PERFORMED BY WHITMAN, REQUARDT, AND ASSOCIATES (TOPOGRAPHY), APPLIED PHYSICS LABORATORY (UTILITIES) CONSULTANTS IN NOVEMBER 1998, AND FROM REPORTS PROVIDED BY JOHNS HOPKINS UNIVERSITY APPLIED PHYSICS LAB (APL). SINCE NOT ALL INFORMATION SHOWN MAY REFLECT CURRENT CONDITIONS, IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY CURRENT TOPOGRAPHIC AND UTILITY INFORMATION TO HIS OWN SATISFACTION.
2. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE HOWARD COUNTY AND MSHA SPECIFICATIONS AND DETAILS FOR CONSTRUCTION, UNLESS OTHERWISE NOTED.
3. ELEVATIONS SHOWN ARE BASED ON AN ASSUMED DATUM PROVIDED BY WHITMAN, REQUARDT, AND ASSOCIATES.
4. APPROXIMATE LOCATIONS OF EXISTING UTILITIES ARE SHOWN. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PROTECT EXISTING UTILITIES AND MAINTAIN UNINTERRUPTED SERVICE. ANY DAMAGE CAUSED BY THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED IMMEDIATELY BY THE CONTRACTOR AT NO COST TO THE OWNER.
5. ACCESS TO THE CONSTRUCTION AREA THROUGH THE SECURED AREA OF THE APPLIED PHYSICS LABORATORY (WITHIN THE FENCED ENCLOSURE) MUST BE ARRANGED IN ADVANCE BY CONTACTING THE PLANT ENGINEERING OFFICE (443) 778-5134.
6. SECURITY MUST BE MAINTAINED WITHIN THE CONSTRUCTION AREA. THE CONTRACTOR SHALL COORDINATE ANY REQUIRED FENCE CONSTRUCTION AND RELOCATION WITH APL-JHU, WITH NOTIFICATIONS OF ALL SCHEDULES AND REQUIREMENTS.
7. THE CONTRACTOR SHALL CONTACT MR. JIM LOESCH (PLANT ENGINEER 443.778.5134) AT LEAST FIVE DAYS BEFORE STARTING WORK OR DISRUPTION OF ANY UTILITIES.
8. ALL "TIE-INS" TO EXISTING UTILITIES MAY ONLY BE DONE AFTER NORMAL WORKING HOURS AT JHU-APL. WORK MUST BE SCHEDULED ACCORDINGLY THRU JHU-APL. NORMAL WORKING HOURS ARE 8:30 A.M. TO 5:00 P.M., MONDAY THROUGH FRIDAY.
9. THE CONTRACTOR OR DEVELOPER SHALL CONTACT THE HOWARD COUNTY CONSTRUCTION INSPECTION DIVISION 24 HOURS IN ADVANCE OF COMMENCING WORK AT 410.313.1880.
10. ALL UTILITIES SHALL HAVE A MINIMUM CLEARANCE OF 6". ALL POLES AND FOUNDATIONS SHALL HAVE A MINIMUM CLEARANCE OF 2'-0", OR TUNNEL AS REQUIRED.
11. THE CONTRACTOR SHALL NOT OPERATE ANY WATER MAIN VALVES ON THE EXISTING WATER SYSTEMS. COORDINATE WITH THE OWNER FOR OPERATING WATER MAIN VALVES.
12. THE CONTRACTOR SHALL PROVIDE A JOINT IN ALL STORM DRAINS WITHIN 2'-0" OF EXTERIOR MANHOLE WALL.
13. THE CONTRACTOR SHALL PERMANENTLY SEED AND STABILIZE ALL DISTURBED AREAS THAT ARE NOT TO BE PAVED.
14. ALL DRIVEWAYS ARE PRIVATELY OWNED AND MAINTAINED.
15. THE AREA SHOWN IS LOCATED ON TAX MAP #41.
16. THE INFORMATION CONCERNING UNDERGROUND UTILITIES WAS OBTAINED FROM AVAILABLE RECORDS, BUT THE CONTRACTOR MUST DETERMINE THE EXACT LOCATION BY DIGGING TEST PITS BY HAND AT ALL CROSSINGS WELL IN ADVANCE OF CONSTRUCTION.
17. ALL SITE UTILITIES ARE THE PROPERTY OF APL-JHU WHO WILL HORIZONTALLY LOCATE ALL ACTIVE UTILITIES FOR THE CONTRACTOR.
18. EXISTING PAVEMENT, (ROADWAY SIDEWALKS ETC.) TO BE REMOVED AND REPLACED BY NEW PAVEMENT SHALL BE REPLACED "IN-KIND", TRAFFIC SHALL BE MAINTAINED BY THE CONTRACTOR ALONG EXISTING ROADWAYS DURING PROPOSED WORK AT ALL TIMES.
19. SEE DETAIL SHEETS FOR OTHER ITEMS THAT APPLY TO THIS PROJECT.
20. THE CONTRACTOR SHALL TAKE PROPER PRECAUTIONS TO AVOID DAMAGE TO EXISTING ADJACENT FACILITIES AND STRUCTURES. THE CONTRACTOR SHALL RESTORE ALL DISTURBED AREAS TO THEIR ORIGINAL CONDITION OR BETTER UNLESS NOTED OTHERWISE.
21. DUE TO THE PROXIMITY OF LIVE UNDERGROUND UTILITIES, THE OWNER AND A. MORTON THOMAS AND ASSOCIATES, INC. ARE NOT RESPONSIBLE FOR ANY DAMAGE OR INJURY SUSTAINED DURING CONSTRUCTION BY ANY PERSON, VEHICLES, OR EQUIPMENT USED ON OR ADJACENT TO THE SITE.
22. ACCESS TO ALL EXISTING FACILITIES SHALL BE MAINTAINED AT ALL TIMES.
23. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO NOTIFY THE OWNER OF ANY DEVIATION FROM THESE PLANS PRIOR TO ANY CHANGE BEING MADE. ANY DEVIATION FROM THESE PLANS WITHOUT WRITTEN AUTHORIZATION BY THE OWNER WILL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR THUS RELIEVING RESPONSIBILITY FROM THE OWNER, A. MORTON THOMAS & ASSOC., HOWARD COUNTY DPZ, & SCD.
24. SURFACED STREETS AND PARKING AREAS SHALL BE MAINTAINED IN A CLEAN CONDITION, MUD AND DUST FREE AT ALL TIMES. ADEQUATE MEANS SHALL BE PROVIDED TO CLEAN TRUCKS AND OTHER EQUIPMENT USING EXISTING SURFACED STREETS AND PARKING AREAS.
25. THE CONTRACTOR SHALL MAKE EVERY ATTEMPT TO MINIMIZE DAMAGE TO EXISTING TREES DURING CONSTRUCTION.
26. ALL EROSION AND SEDIMENT CONTROL DEVICES SHALL MEET CURRENT HOWARD COUNTY DEPARTMENT OF PERMITTING SERVICES STANDARDS AND DIRECTIVES.
27. EXISTING SIGNS, GUARDRAILS, AND OTHER MINOR SITE FEATURES IN THE WAY OF PROPOSED CONSTRUCTION, WHETHER OR NOT SHOWN ON THESE PLANS, SHALL BE REMOVED AND REPLACED AT NO ADDITIONAL COST TO THE OWNER.
28. CONTRACTOR SHALL CONTACT JHU-APPLIED PHYSICS LAB PLANT FACILITIES OFFICE (240) 228-5134 AND "MISS UTILITY" AT 1-800-257-7777, 48 HOURS PRIOR START OF THE EXCAVATION AND MUST NOTIFY ALL PUBLIC UTILITY COMPANIES AND THE OWNER OF UNDERGROUND FACILITIES IN THE AREA OF PROPOSED EXCAVATION AND HAVE THOSE FACILITIES LOCATED BY THE UTILITY COMPANIES PRIOR TO COMMENCING EXCAVATION.
29. THE SUBJECT PROPERTY IS ZONED PEC PER THE OCTOBER 1993 COMPREHENSIVE ZONING PLAN.
30. NO CLEARING, GRADING, OR CONSTRUCTION ARE PERMITTED WITHIN THE REQUIRED WETLANDS, STREAMS, OR THEIR BUFFERS WHERE NOT PERMITTED BY MDE, U.S. ARMY CORPS OF ENGINEERS, AND HOWARD COUNTY; AND WITHIN THE FOREST CONSERVATION AREAS.
31. THE FOREST CONSERVATION EASEMENT HAS BEEN ESTABLISHED TO FULFILL THE REQUIREMENTS OF SECTION 16.1200 OF THE HOWARD COUNTY CONSERVATION ACT. NO CLEARING, GRADING, OR CONSTRUCTION ARE PERMITTED WITHIN THE FOREST CONSERVATION EASEMENT. THE FOREST CONSERVATION OBLIGATION HAS BEEN ADDRESSED WITH F-02-40, JHU-APL SWM BASIN A.
32. THE EXISTING TOPOGRAPHY IS TAKEN FROM AERIAL SURVEY WITH ONE FOOT CONTOUR INTERVALS PREPARED AS DESCRIBED IN GENERAL NOTE #1.
33. WATER IS PUBLIC (HOWARD COUNTY)
34. SEWER IS PUBLIC (HOWARD COUNTY)
35. THE FLOODPLAIN LIMITS FOR THIS PROJECT WAS TAKEN FROM HOWARD COUNTY STUDY.
36. DIMENSION TO NEW STRUCTURES ARE PERPENDICULAR TO PROPERTY LINE.
37. THE FINAL PLAN AREA AND THE LOD OF THE JOHNS HOPKINS UNIVERSITY APPLIED PHYSICS LABORATORY ARE NOT LOCATED IN THE 100 YEAR FLOOD PLAIN.
38. ALL EXISTING UTILITIES WITHIN THE FOOTPRINT OF NEW PARKING FACILITIES WILL BE RELOCATED OUTSIDE THE AREA AS SHOWN.
39. SOIL MAP USED SHEET NO. 29, SOIL SURVEY JULY 1968 HOWARD COUNTY, MARYLAND, USDA.
40. THE STORMWATER MANAGEMENT POND WILL BE PRIVATELY OWNED AND MAINTAINED. FINANCIAL SURETY FOR THE REQUIRED LANDSCAPING HAS BEEN POSTED AS PART OF THE DPW DEVELOPER'S AGREEMENT IN THE AMOUNT OF \$12,150.00: FOR 25 SHADE TREES, 31 EVERGREEN TREES, AND 0 SHRUBS.

HOWARD COUNTY RELATED FILE NUMBERS FOR ADJOINING PROJECTS AT JHU-APL AREAS FOLLOWS AND ARE LISTED ON SHEET C-2


SDP NO.	DESCRIPTION	DATE
S-01-12		
F-02-40	JHU-APL SWM	12/01
Wp-01-80	BASIN A	
82-118	BUILDINGS 23 LOT NO. F	4/82
87-07	LOT NO. F-1	
90-218*	ARRAY TEST FACILITY BUILDING NO. 49	12/90

\* RED LINE REVISION

### KEY LEGEND



SCALE: NTS



SCALE: 1"=2000'

### SITE ANALYSIS TOTAL APL PROPERTY:

#### PROPERTY NOTES

1. COURSES AND COORDINATES ARE BASED ON THE MARYLAND STATE COORDINATE SYSTEM (NAD 83) AND ARE DERIVED FROM THE FOLLOWING JOHNS HOPKINS UNIVERSITY CONTROL STATIONS:
 

STATION	NORTH	EAST
HOPKINS	544836.5300	1340825.3542
G12	550256.5002	1342325.2642
G7	548107.0328	1341025.0830
G8	549478.7005	1341170.4345
- A. AREA OF PARCEL/LOT = 358 ACRES
- B. PRESENT ZONING = PEC
- C. PARKING TABULATION: EXISTING PARKING SPACES = 3,780  
PROPOSED PARKING SPACES = 398 (NET)  
TOTAL SPACES PROVIDED = 4,178
- D. EXISTING BUILDING COVERAGE = 36.2 ACRES GROSS FLOOR AREA COVERAGE = 18.1 ACRES, 5% OF TOTAL LOT AREA  
PROPOSED BUILDING COVERAGE = 6.5 ACRES GROSS FLOOR AREA COVERAGE = 1.6 ACRES, 0.45% OF TOTAL LOT AREA
- F. TOTAL PROPOSED BUILDING COVERAGE = 19.7 ACRES, 5.45% OF TOTAL LOT AREA
- G. PROPOSED BUILDINGS DISTURBED AREA = 2.4 ACRES
- H. PROPOSED USE = EDUCATION/RESEARCH
- I. FLOOR SPACE USE = EDUCATION/RESEARCH
- J. MAXIMUM NUMBER OF EMPLOYEES = 3,900
- K. NO LOT SUBDIVISION IS ANTICIPATED.
- L. CASE NUMBERS APPLICABLE: WAIVER PRELIMINARY PLAN, #WP-01-80
- M. SANITARY SEWER / WATER SERVICE SEE GENERAL NOTES.
- N. EXISTING OPEN SPACE AREA (LOT AREA MINUS PARKING AND BUILDINGS) = 305 ACRES, 85.2% OF TOTAL LOT AREA.
- O. PROPOSED OPEN SPACE AREA = 300 ACRES, 83.8% OF TOTAL LOT (PROPOSED BUILDINGS AND PARKING = 5 ACRES)

#### BASIN B AREA DRAINAGE NOTES

- A. DRAINAGE AREA TO BASIN B = 28.8 ACRES.
- B. DESIGN IMPERVIOUS SURFACES:  
EXISTING 16% IMPERVIOUS SURFACES 4.6 ACRES  
FUTURE BASIN DESIGN 89.2% IMPERVIOUS SURFACES 25.7 ACRES.
- C. HYDRAULIC CALCULATION CAN BE FOUND IN THE MDE APPROVED "STORMWATER MANAGEMENT FINAL PLAN AREA B REPORT" (AUGUST 2002).

#### SEDIMENT CONTROL

(X) BY THE DEVELOPER:  
I CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Signature of Developer: *James E. Loesch* Date: *10/24/02*

( ) BY THE ENGINEER:  
I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

Signature of Engineer: *Robert A. Warner* Date: *10/24/02*

( ) THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

Signature: *Jan Meyer* Date: *10/24/02*

( ) THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

Signature: *John O'Connell* Date: *10/24/02*

CONTACT PERSON FOR OWNER: JEFF ANDERSON  
TELEPHONE: 443.778.5960 FAX: 443.778.5960

### ADDRESS CHART

LOT/PARCEL #	STREET ADDRESS
P # 123/129	11100 JOHNS HOPKINS ROAD LAUREL, MD 20723 CONTACT: MR. JEFF ANDERSON

### PERMIT INFORMATION CHART

SUBDIVISION NAME		SECTION / AREA		LOT/PARCEL NO	
JHU APPLIED PHYSICS LAB		N/A		1	
PLOT# OR L/F	GRID#	ZONING	TAX MAP NO.	ELEC. DISTRICT	CENSUS TRACT
15429-15433	16	PEC	41	5	6051
WATER CODE E-21		SEWER CODE 6480000			

Review for HOWARD SCD and meets Technical Requirements.

USDA - Natural Resources Conservation Service Date: \_\_\_\_\_

This development plan is approved for soil erosion and sediment control by the HOWARD SOIL CONSERVATION DISTRICT.

Howard SCD Date: \_\_\_\_\_

APPROVED: DEPARTMENT OF PUBLIC WORKS

*N/A No Public Facilities.*

CHIEF, BUREAU OF HIGHWAYS Date: \_\_\_\_\_

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

*Chief, Development Engineering Division MK* Date: *11/15/02*

*Chief, Division of Land Development* Date: *11/21/02*

1) BY THE ENGINEER:  
I certify that the plan for pond construction, erosion and sediment plan represents a practical and workable plan based on my personal knowledge of the site conditions. This plan was prepared in accordance with the requirements of the Howard Soil Conservation District. I have notified the developer that he/she must engage a registered professional engineer to supervise pond construction and provide the Howard Soil Conservation District with an "As-Built" plan of the pond within 30 days of completion.

Design Engineer Signature: *Robert A. Warner* Date: *10/23/02*

Printed Name: *Robert A. Warner* Registration Number: *13403*

12750 TWINBROOK PARKWAY  
ROCKVILLE, MARYLAND 20852  
301.881.2545

DEVELOPER & ENGINEER CERTIFICATES

2) BY THE DEVELOPER:  
I/We certify that all development and/or construction will be done according to these plans, and that any responsible personal involved in the construction project will have a certificate of attendance at a department of the environment approved training program for the control of sediment and erosion before beginning the project. I shall engage a registered professional engineer to supervise pond construction and provide the Howard Soil Conservation District with an "As-Built" plan of the pond within 30 days of completion. I also authorize periodic on-site inspections by the Howard Soil Conservation District.

Signature of developer: *James E. Loesch, PE, CFM* Date: *9/18/02*



3) CERTIFICATION BY PROFESSIONAL:  
There are no wetlands on the site that will be disturbed. Therefore, the requirement of 401 and 404 wetlands permits from the State of Maryland, and Corps of Engineers are not needed.

Professional's Signature: *Robert A. Warner* Date: *10/16/02*

Print Name: *Robert A. Warner*



MODE SUBMISSION



DES:	DRN:	CHK:	DATE:	DATE:	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK	APP
B. WARNER	P. FRIAS	S. ITANI	08/23/02						

PROPERTY OWNER: JOHNS HOPKINS UNIVERSITY APPLIED PHYSICS LABORATORY  
11100 JOHNS HOPKINS ROAD  
LAUREL, MD 20723  
CONTACT: MR. JEFFREY ANDERSON  
443.778.5960

APPLIED PHYSICS LABORATORY  
THE JOHNS HOPKINS UNIVERSITY - POND B  
PARCEL 1  
COVER SHEET - AREA B

TAX MAP 41 PARCEL 123  
ELECTION DISTRICT NO. 5  
HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
SHEET C1  
SHEET 1 OF 20

F-02-77

**SEDIMENT CONTROL**

( ) BY THE DEVELOPER:  
 "I CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT."

Signature: *[Signature]* Date: 11/15/02  
 Signature of Developer: *[Signature]* Date: 10/15/02

( ) BY THE ENGINEER:  
 "I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT."

Signature of Engineer: *[Signature]* Date: *[Date]*

USDA-NATURAL RESOURCES CONSERVATION SERVICE: *[Signature]* Date: *[Date]*

( ) THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

HOWARD SOIL CONSERVATION DISTRICT: \_\_\_\_\_ Date: \_\_\_\_\_





SE OF CEDAR  
 RESIDENTIAL  
 DEVELOPMENT

RIVERSIDE ESTATES  
 RESIDENTIAL  
 DEVELOPMENT




DOES NOT APPEAR ON THIS SHEET  
 SEE INFORMATION ON  
 SHEET # C3 AND #C4

- LEGEND**
- - - EXISTING CONTOUR
  - - - FOREST STAND
  - - - DRAINAGE AREA
  - - - 100 YEAR FLOODPLAIN
  - - - STREAM VALLEY BUFFER
  - - - STREAM SYSTEM
  - - - WETLANDS
  - - - 20' WETLAND BUFFER
  - - - SOIL CLASSIFICATION
  - - - PROPERTY LINE
  - - - ADJACENT PROPERTY LINE
  - - - 8" SAN. EXISTING SANITARY SEWER
  - - - 12" W. EXISTING WATER
  - - - 18" SD. EXISTING STORM DRAIN
  - - - 18" SD. PROPOSED STORM DRAIN
  - - - EXISTING WATER TO BE REMOVED
  - - - EXISTING SANITARY SEWER TO BE REMOVED
  - - - EXISTING SANITARY SEWER TO BE READVANCED
  - - - 30" DBM TREE
  - - - SOILS CLASSIFICATION
  - - - PROPOSED INFILTRATION TRENCH
  - - - CATCH BASIN
  - - - EXISTING MANHOLE
  - - - PROPOSED MANHOLE
  - - - SANITARY SEWER MANHOLE
  - - - PROPOSED STORM DRAIN
  - - - EXISTING FIRE HYDRANT
  - - - EXISTING CLEANOUT
  - - - PROPOSED STORM DRAIN CATCH BASIN
  - - - WETLANDS
  - - - SLOPES >25%
  - - - SLOPES 15% - 25%
  - - - EXISTING BUILDING
  - - - PROPOSED BUILDING
  - - - PARKING LOT
  - - - EDGE OF ROAD
  - - - FLOOD PLAN AREA



APPROVED: DEPARTMENT OF PLANNING AND ZONING  
 Signature: *[Signature]* Date: 11/15/02  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION MK  
 Signature: *[Signature]* Date: 11/21/02  
 CHIEF, DIVISION OF LAND DEVELOPMENT






DES.	DRN.	CHK.	DATE	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK	APP
B. WARNER	P. FRIAS	S. ITANI	06/21/02						

APPLIED PHYSICS LABORATORY  
 THE JOHN'S HOPKINS UNIVERSITY  
 PARCEL 1  
**OVERALL DRAINAGE AREA**  
 TAX MAP 41 PARCEL 123  
 ELECTION DISTRICT NO. 5  
 HOWARD COUNTY, MARYLAND

SCALE AS  
 SHEET C2  
 SHEET 2 OF 20

**F-02-77**



- LEGEND**
- EXISTING CONTOUR
  - TREELINE
  - FOREST STAND
  - DRAINAGE AREA
  - 100 YEAR FLOODPLAIN
  - STREAM VALLEY BUFFER
  - STREAM SYSTEM
  - WETLANDS
  - 25' WETLAND BUFFER
  - SOIL CLASSIFICATION
  - BOUNDARY
  - STREAMS
  - DD --- DRAINAGE DITCH
  - PROPERTY LINE
  - ADJACENT PROPERTY LINE
  - 8" SAN. --- EXISTING SANITARY SEWER
  - 8" SAN. --- PROPOSED SANITARY SEWER
  - 12" W --- EXISTING WATER
  - 12" W --- PROPOSED WATER
  - 18" DRAIN --- EXISTING STORM DRAIN
  - 18" SD --- PROPOSED STORM DRAIN
  - 18" DRAIN --- EXISTING STORM DRAIN TO BE REMOVED
  - 12" W --- EXISTING WATER TO BE REMOVED
  - 8" SAN. --- EXISTING SANITARY SEWER TO BE REMOVED
  - 8" SAN. --- EXISTING SANITARY SEWER TO BE ABANDONED
  - WETLANDS
  - SLOPES >25%
  - SLOPES 15% - 25%
  - EXISTING BUILDING
  - PROPOSED BUILDING
  - PARKING LOT
  - EDGE OF ROAD
- ⊙ OA-1 OBSERVATION AREA
  - ⊙ A1 30" DBH TREE
  - ⊙ A1B2 SOILS CLASSIFICATION
  - ⊙ PROPOSED INFILTRATION TRENCH
  - ⊙ CATCH BASIN
  - ⊙ C.B. C.B.
  - ⊙ EXISTING MANHOLE
  - ⊙ SANITARY SEWER MANHOLE
  - ⊙ PROPOSED MANHOLE
  - ⊙ EXISTING POST INDICATOR VALVE
  - ⊙ EXISTING WATER VALVE
  - ⊙ EXISTING FIRE HYDRANT
  - ⊙ EXISTING CLEANOUT
  - ⊙ PROPOSED STORM DRAIN CATCH BASIN



**SEDIMENT CONTROL**

( ) BY THE DEVELOPER:  
 I HEREBY CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT.  
 I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Signature: [Signature] DATE: 11/15/02  
 SIGNATURE OF DEVELOPER PRINT NAME BELOW SIGNATURE

( ) BY THE ENGINEER:  
 I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

Signature: [Signature] DATE: 11/21/02  
 SIGNATURE OF ENGINEER PRINT NAME BELOW SIGNATURE

( ) THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

USDA-NATURAL RESOURCES CONSERVATION SERVICE DATE: [Signature]


( ) THESE PLANS FOR EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

HOWARD SOIL CONSERVATION DISTRICT DATE: [Signature]

APPROVED: DEPARTMENT OF PLANNING AND ZONING  
 Chief, Development Engineering Division MK DATE: 11/15/02  
 Chief, Division of Land Development WB DATE: 11/21/02



**OWNER/DEVELOPER**  
 APPLIED PHYSICS LABORATORY—  
 THE JOHNS HOPKINS UNIVERSITY  
 11100 JOHNS HOPKINS ROAD  
 LAUREL, MARYLAND 20707

**SURVEYOR**  
 WHITMAN, REQUART AND ASSOCIATES  
 2315 SAINT PAUL STREET  
 BALTIMORE, MARYLAND 21218




		DES: B. WARNER								APPLIED PHYSICS LABORATORY THE JOHNS HOPKINS UNIVERSITY PARCEL 1 <b>DRAINAGE AREA "B"</b> TAX MAP 41 PARCEL 123 ELECTION DISTRICT NO. 5 HOWARD COUNTY, MARYLAND	SCALE AS SHOWN
		DRN: P. FRIAS									SHEET C3
		CHK: S. ITANI									SHEET 3 OF 20
		DATE: 06/21/02	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK	APP			

F-02-77



- LEGEND**
- EXISTING CONTOUR
  - TREELINE
  - FOREST STAND
  - DRAINAGE AREA
  - 100 YEAR FLOODPLAIN
  - STREAM VALLEY BUFFER
  - STREAM SYSTEM
  - WETLANDS
  - 25' WETLAND BUFFER
  - SOIL CLASSIFICATION BOUNDARY
  - STREAMS
  - DRAINAGE DITCH
  - PROPERTY LINE
  - ADJACENT PROPERTY LINE
  - 8" SAN. EXISTING SANITARY SEWER
  - 8" SAN. PROPOSED SANITARY SEWER
  - 12" W. EXISTING WATER
  - 12" W. PROPOSED WATER
  - 18" DRAIN EXISTING STORM DRAIN
  - 18" SD PROPOSED STORM DRAIN
  - 18" DRAIN EXISTING STORM DRAIN TO BE REMOVED
  - 12" W EXISTING WATER TO BE REMOVED
  - 8" SAN. EXISTING SANITARY SEWER TO BE REMOVED
  - 8" SAN. EXISTING SANITARY SEWER TO BE ABANDONED
  - EXISTING STORM WATER MANAGEMENT POND
  - WETLANDS
  - SLOPES >25%
  - SLOPES 15% - 25%
  - EXISTING BUILDING
  - PROPOSED BUILDING
  - PARKING LOT
  - EDGE OF ROAD
- OAM1 OBSERVATION AREA
  - A1 30" DBH TREE
  - ABR2 SOILS CLASSIFICATION
  - PROPOSED INFILTRATION TRENCH
  - CATCH BASIN C.B. C.B.
  - EXISTING MANHOLE
  - SANITARY SEWER MANHOLE
  - PROPOSED MANHOLE
  - PROPOSED STORMCEPTOR
  - EXISTING POST INDICATOR VALVE
  - EXISTING WATER VALVE
  - EXISTING FIRE HYDRANT
  - EXISTING CLEANOUT
  - PROPOSED STORM DRAIN CATCH BASIN

SURFACE PARKING:  
 NORTH LOT= 217 SPACES  
 SOUTH LOT= 237 SPACES  
 DEMO= 56 SPACES  
 TOTAL = 398 SPACES



**SEDIMENT CONTROL**

( ) BY THE DEVELOPER:  
 I CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT.  
 I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

( ) BY THE ENGINEER:  
 I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

USDA-NATURAL RESOURCES CONSERVATION SERVICE DATE

( ) THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

HOWARD SOIL CONSERVATION DISTRICT DATE

APPROVED: DEPARTMENT OF PLANNING AND ZONING  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION MK  
 CHIEF, DIVISION OF LAND DEVELOPMENT


OWNER/DEVELOPER  
 APPLIED PHYSICS LABORATORY--  
 THE JOHNS HOPKINS UNIVERSITY  
 11100 JOHNS HOPKINS ROAD  
 LAUREL, MARYLAND 20707

SURVEYOR  
 WHITMAN, REQUART AND ASSOCIATES  
 2315 SAINT PAUL STREET  
 BALTIMORE, MARYLAND 21218

**AMT**  
 A. MORTON THOMAS AND ASSOCIATES, INC.  
 CONSULTING ENGINEERS  
 12750 TWINBROOK PARKWAY, SUITE 200, ROCKVILLE MD 20852  
 TEL: (301) 981-2500 FAX: (301) 981-0814  
 AMT FILE # 98-133


**Einhorn Yaffee Prescott**

DES: B. WARNER					
DRN: P. FRIAS					
CHK: S. ITANI					
DATE: 06/21/02	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK APP



APPLIED PHYSICS LABORATORY  
 THE JOHNS HOPKINS UNIVERSITY  
 PARCEL 1  
**DRAINAGE AREA "B"**  
 TAX MAP 41 PARCEL 123  
 ELECTION DISTRICT NO. 5  
 HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
 SHEET C4  
 SHEET 4 OF 20



**KEY NOTES:**

- 1. EXISTING ROADWAY ASPHALT PAVEMENT
- 2. NEW RIP-RAP TRAPEZOIDAL, TYPE CHANNEL (SEE DETAIL)
- 3. NEW BASIN CONCRETE OUTLET STRUCTURE (SEE DETAIL).
- 4. NEW CONCRETE HEADWALL MD SHA STD. #B-48" MD 352.01 MODIFIED FOR TWO PIPES WITH CL. #2 RIP-RAP (SEE PROFILE AND DETAIL SECTION).
- 5. EXISTING 24" CMP CULVERT IN RIP-RAP INLET PROTECTION TO REMAIN.
- 6. EXISTING RIP-RAP LINED DRAINAGE DITCH, NEW RIP-RAP MEETING EXISTING FLUSH.
- 7. EXISTING TRAFFIC BARRIER TO REMAIN.
- 8. EXISTING PIPE CAPPED
- 9. EXISTING TREES TO BE REMOVED
- 10. EXISTING 10' HIGH X 28' LONG X 8' THICK REINFORCED CONC. WALL WITH 4' DEEP CONC. FOUNDATION TO BE REMOVED
- 11. EXISTING 6" THICK ASPHALT PAVEMENT TO BE REMOVED
- 12. EXISTING 10' HIGH X 930' LONG CHAIN LINK FENCE WITH CONC. FOUNDATIONS AT THE POSTS TO BE REMOVED
- 13. EXISTING CLAY/SAND TENNIS COURT COMPOSITION MATERIAL 12" THICK, REMOVE AS REQUIRED TO INSTALL NEW STORM DRAIN, BACKFILL WITH FILL SOIL, TOP SOIL, AND SEED.
- 14. EXISTING 2" WATER PIPE DISCONNECT AND CAP AT VALVE BOX AT TENNIS COURTS AS DIRECTED BY APL. REMOVE ANY EXISTING PIPE IN THE WAY OF STORM DRAIN PIPE CONSTRUCTION.
- 15. REMOVE EXISTING 24" SD LOCATED BENEATH PROPOSED 36" SD
- 16. CONNECT EXISTING 18" SD PIPE TO NEW MANHOLE
- 17. LIMIT OF INITIAL WORK - STUB UP PIPE FOR FUTURE CONNECTION

APPROVED: DEPARTMENT OF PLANNING AND ZONING  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION MK DATE 11/15/02  
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE 11/21/02

**SEDIMENT CONTROL**

( ) BY THE DEVELOPER:  
 I CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Signature of Developer: [Signature] DATE: 11/15/02  
 Signature of Engineer: [Signature] DATE: 11/21/02

( ) THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

( ) THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

Signature: [Signature] DATE: 10/24/02

GRAPHIC SCALE  
 1 inch = 80 ft.

NORTH

NTS

SCALE: NTS


**AMT**  
 A. MORTON THOMAS AND ASSOCIATES, INC.  
 CONSULTING ENGINEERS  
 12750 TWINBROOK PARKWAY, SUITE 200, ROCKVILLE MD 20852  
 TEL (301) 981-5500 FAX (301) 981-9814  
 AMT FILE # 98-153

Einhorn  
 Yaffee  
 Prescott

DES: B. WARNER					
DRN: S. ITANI					
CHK: B. WARNER					
DATE: 06/21/02	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK APP



APPLIED PHYSICS LABORATORY  
 THE JOHNS HOPKINS UNIVERSITY  
 PARCEL 1  
**SITE LAYOUT**  
 TAX MAP 41 PARCEL 123  
 ELECTION DISTRICT NO. 5  
 HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
 SHEET C5  
 SHEET 5 OF 20



APPROVED: DEPARTMENT OF PLANNING AND ZONING  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION MK  
 CHIEF, DIVISION OF LAND DEVELOPMENT WB

4/15/02  
 11/21/02



**SEDIMENT CONTROL**  
 ( ) BY THE DEVELOPER:  
 I CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT.  
 I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Signature of Developer: [Signature]  
 DATE: 4/15/02

( ) BY THE ENGINEER:  
 I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

Signature of Engineer: [Signature]  
 DATE: 4/15/02

( ) THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

Signature: [Signature]  
 DATE: 4/15/02

( ) THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS FOR THE HOWARD SOIL CONSERVATION DISTRICT.

Signature: [Signature]  
 DATE: 4/15/02

**AMT**  
 A. MORTON THOMAS AND ASSOCIATES, INC.  
 CONSULTING ENGINEERS  
 12750 TWINBROOK PARKWAY, SUITE 200, ROCKVILLE MD 20852  
 TEL: (301) 581-2547 FAX: (301) 581-0514  
 AMT FILE # 98-153



Einhorn  
 Yaffee  
 Prescott

DES: B. WARNER									
DRN: S. ITANI									
CHK: B. WARNER									
DATE: 06/21/02	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK	APP			

APPLIED PHYSICS LABORATORY  
 THE JOHNS HOPKINS UNIVERSITY  
 PARCEL 1  
**POND GRADING AND DRAINAGE PLAN**  
 TAX MAP 41 PARCEL 123  
 ELECTION DISTRICT NO. 5  
 HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
 SHEET C6  
 SHEET 6 OF 20

F-02-77



**SEDIMENT CONTROL**

( ) BY THE DEVELOPER:  
 "I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT."

Signature of Developer: *[Signature]* DATE: 11/21/02

( ) BY THE ENGINEER:  
 "I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT."

Signature of Engineer: *[Signature]* DATE: 11/21/02

( ) THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

USDA-NATURAL RESOURCES CONSERVATION SERVICE DATE: *[Signature]*


( ) THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

HOWARD SOIL CONSERVATION DISTRICT DATE: *[Signature]*



1 PIPE PROFILE THRU 36" RCP  
 SCALE: HORIZ. 1"=50'  
 VERT. 1"=5'

APPROVED: DEPARTMENT OF PLANNING AND ZONING  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION MK DATE 11/15/02  
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE 11/21/02




DES: B. WARNER					
DRN: P. FRIAS					
CHK: S. ITANI					
DATE: 06/21/02	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK APP


APPLIED PHYSICS LABORATORY  
 THE JOHNS HOPKINS UNIVERSITY  
 PARCEL 1  
**PIPE PROFILE**  
 TAX MAP 41 PARCEL 123  
 ELECTION DISTRICT NO. 5  
 HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
 SHEET C7  
 SHEET 7 OF 20


F-86-77




1 PROFILE THRU EMBANKMENT  
SCALE: HORIZ. 1"=50'  
VERT. 1"=5'



3 PIPE PROFILE THRU TWIN 48" RCP / OUTLET STRUCTURE  
SCALE: HORIZ. 1"=50'  
VERT. 1"=5'



2 PROFILE ALONG TOP OF EMBANKMENT B  
SCALE: HORIZ. 1"=50'  
VERT. 1"=5'



STORM DRAIN PIPE SCHEDULE

FROM	TO	SIZE (INCH)	LENGTH (FEET)	SLOPE %	FLOW CAP (cfs)	10-YRS Q (cfs)	VELOCITY (ft/s)	PIPE TYPE
EW-1	MH-2	36	60	1%	61.93	13.97	8.76	RCP
MH-2	MH-3	36	260	1%	61.93	13.97	8.76	RCP
MH-3	MH-4	36	198	6.5%	157.90	13.97	22.34	RCP
MH-4	MH-5	36	48	6.5%	157.90	13.97	22.34	RCP
MH-5	MH-6	36	91	1%	61.93	13.97	8.76	RCP
MH-6	SC-7	18	17	3%	16.89	13.97	9.96	RCP
HW-4	OS-3	18	5	17%	133.40	105.87	10.62	RCP
OS-3	HW-2	48	68	0.5%	55.58	5.52	5.52	RCP

STORM DRAIN STRUCTURE SCHEDULE

STRUC. No	TYPE	STANDARD No.	TOP ELEVATION	SIZE (ft)	INV. IN	INV. OUT	COMMENT
EW-1	EW	SHA # MD-354.01	374.50	-	-	370.00	TYPE C ENDWALL
MH-2	MH	SHA # MD-384.05	376.81	-	370.80	370.60	MANHOLE PRECAST
MH-3	MH	SHA # MD-384.05	385.31	-	380.15	373.40	MANHOLE PRECAST
MH-4	MH	SHA # MD-384.03	398.94	-	393.24	396.24	MANHOLE PRECAST
MH-5	MH	SHA # MD-384.03	408.83	-	402.92	396.24	MANHOLE PRECAST
MH-6	MH	SHA # MD-384.03	409.05	-	405.33	403.83	MANHOLE PRECAST
SC-7	SC	STC 3600	409.00	-	406.00	405.85	PRECAST CONCRETE SC
HW-2	HW	SHA # MD-354.01	372.53	-	389.76	384.99	MANHOLE PRECAST
OS-3	OS	-	383.50	-	405.68	391.25	MANHOLE PRECAST
HW-4	HW	SHA # MD-354.01	371.70	-	406.00	405.85	PRECAST CONCRETE SC



NOTES:  
ALL RCP PIPES SHALL HAVE RUBBER GASKETS

**SEDIMENT CONTROL**

( ) BY THE DEVELOPER:  
I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT.  
I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

( ) BY THE ENGINEER:  
I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

USDA-NATURAL RESOURCES CONSERVATION SERVICE

HOWARD SOIL CONSERVATION DISTRICT


STORM DRAIN COMPUTATION SHEET

COMPUTED BY: PCF DATE: 11/01 PROJECT: APL-JHU  
CHECKED BY: RAW DATE: 11/01 STORM FREQUENCY: 10-YEAR

MANNING'S "N" (RCP) = 0.013

PIPE STRUCTURE	DRAINAGE AREA (AC)	RUN-OFF COEFF.	"AREA"x"CO"	TIME OF CONC. (MIN)	TIME OF RAINFALL INTENSITY (IN/HR)	RUNOFF "Q" (CFS)	PIPE DIAMETER (IN)	PIPE LENGTH (FT)	MIN. PIPE SLOPE (1/1)	ACTUAL PIPE SLOPE (1/1)	VELOCITY (FPS)	TIME IN PIPE (MIN)	PIPE "Q" CAPAC. (CFS)	
SC-7	MH8	1.73	.95	1.64	5	8.90	13.97	18	17	0.001	0.010	5.52	0.05	8.75
MH8	MH5	1.73	.95	1.64	5	8.90	13.97	36	91	0.001	0.010	8.76	0.17	81.83
MH5	MH4	1.73	.95	1.64	5	8.90	13.97	36	48	0.001	0.065	22.34	0.04	157.90
MH4	MH3	1.73	.95	1.64	5	8.90	13.97	36	198	0.001	0.085	22.34	0.15	157.90
MH3	MH2	1.73	.95	1.64	5	8.90	13.97	36	260	0.001	0.010	8.76	0.49	61.93
MH2	EW1	1.73	.95	1.64	5	8.90	13.97	36	60	0.001	0.010	8.76	0.11	61.83
HW4	OS3	32	.75	24	5	8.90	204	18	60	4.391	0.010	5.52	0.18	8.75
OS3	HW2	32	.75	24	5	8.90	204	48	60	0.024	0.010	10.62	0.09	133.40

APPROVED: DEPARTMENT OF PLANNING AND ZONING  
CHIEF, DEVELOPMENT ENGINEERING DIVISION MK DATE: 11/15/02  
CHIEF, DIVISION OF LAND DEVELOPMENT DATE: 11/21/02




DES: B. WARNER  
DRN: P. FRIAS  
CHK: S. ITANI  
DATE: 06/21/02

DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK	APP


APPLIED PHYSICS LABORATORY  
THE JOHNS HOPKINS UNIVERSITY  
PARCEL 1  
EMBANKMENT B PROFILE AND  
PIPE PROFILE  
TAX MAP 41 PARCEL 123  
ELECTION DISTRICT NO. 5  
HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
SHEET C8  
SHEET 8 OF 20







1 SECTION A-A  
SCALE: 1"=2'




2 SECTION B-B  
SCALE: 1"=2'



3 RISER-PLAN VIEW  
SCALE: 1"=2'




CONCRETE CRADLE EXTENDING A MIN. OF 9 INCHES BELOW PIPE OUTSIDE AND 9 INCHES BEYOND SIDES OF PIPE (36" / 0.25) = 9"




CONCRETE CRADLE EXTENDING A MIN. OF 12 INCHES BELOW PIPE OUTSIDE AND 12 INCHES BEYOND SIDES OF PIPE (48" / 0.25) = 12"


4 CONCRETE CRADLE DETAILS  
SCALE: NTS




5 SECTION E-E  
SCALE: NTS



6 ELEVATION ANTI-SEEP COLLAR  
SCALE: NTS




7 SECTION D-D  
SCALE: NTS



8 TOP VIEW  
SCALE: NTS

APPROVED: DEPARTMENT OF PLANNING AND ZONING  
CHIEF, DEVELOPMENT ENGINEERING DIVISION MK DATE 11/15/02  
CHIEF, DIVISION OF LAND DEVELOPMENT DATE 11/21/02




DES: B. WARNER									
DRN:									
CHK: B. WARNER									
DATE: 06/21/02	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK	APP			


APPLIED PHYSICS LABORATORY  
THE JOHNS HOPKINS UNIVERSITY - POND B  
PARCEL 1  
SWM DETAILS  
TAX MAP 41 PARCEL 123  
ELECTION DISTRICT NO. 5  
HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
SHEET C9  
SHEET 9 OF 20


F-02-77



**BAR TO BAR**  
NOT TO SCALE





**BAR TO SIDE, TOP AND BOTTOM SUPPORTS**  
NOT TO SCALE



**3 DEBRIS RACK BOLT DETAIL**  
USE TOP CONNECTION WHERE APPLICABLE  
NOT TO SCALE

**1 DEBRIS RACK WELD DETAIL**  
NOT TO SCALE

- NOTES:**
- TRASH RACK TO BE CENTERED OVER ORIFICE
  - ALL SURFACES TO BE COATED WITH 2 COATS OF ZRC COLD GALVANIZING COMPONENT AFTER WELDING, COATED WITH SHOP APPLIED PRIME COAT AND 2-COATS OF EPOXY PAINT (9 MIL, MIN THICKNESS)





**FRONT VIEW**

**SIDE VIEW**

- NOTES:**
- GRATE UNDER-FLOW OR FEED-FROM-TRASHRACK BOTTOM: WEIR AREA: FRONT 34 SQ. FT. SIDE 24 SQ. FT. TRASHRACK BOTTOM AREA: FRONT BOTTOM AREA 34 SQ. FT. (15'-4")-(3' FOR 36" PIPE) = 12'-4" OF LENGTH SIDE BOTTOM AREA 25.3 SQ. FT.

**2 TOP TRASH RACK DETAIL**  
NOT TO SCALE




**CONC. SLAB PLAN**  
SCALE: NTS


**ISOMETRIC VIEW**  
SCALE: NTS

NOTE: STEEL TO CONFORM TO A.S.T.M. SPECIFICATION A-36 McNICHOLS Co. OR EQUAL.

- NOTES:**
- TRASH RACK TO BE CENTERED OVER OPENING
  - ALL SURFACES TO BE COATED WITH 2 COATS OF ZRC COLD GALVANIZING COMPONENT AFTER WELDING
  - TRASH RACK TO BE CONNECTED TO HEADWALL WITH 1/2" STAINLESS STEEL ANCHOR EXPANSION BOLTS.




LWD (inches)	LWO (inches)	SWD (inches)	SWO (inches)
8.00	4.00	1.33	0.81



- NOTE:**
- GRATE SIDE-FLOW AS FEED-FROM-TRASHRACK BOTTOM: 36" OPENING=7.1 SQ.FT.; SIDE AREA AT 34 SQ. FT./SIDE

**4 LOW FLOW EXPANDED METAL TRASH RACK**  
SCALE: NTS

APPROVED: DEPARTMENT OF PLANNING AND ZONING  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION MK DATE 11/15/12  
 CHIEF, DIVISION OF LAND DEVELOPMENT WD DATE 11/21/12



DES:	DRN:	CHK:	DATE:	NO.	BY	CK	APP
B. WARNER	P. FRIAS	S. ITANI	06/21/02				

DATE	REVISIONS AND RECORD OF ISSUE


APPLIED PHYSICS LABORATORY - POND B  
 THE JOHNS HOPKINS UNIVERSITY  
 PARCEL 1  
**SWM2 DETAILS**  
 TAX MAP 41 PARCEL 123  
 ELECTION DISTRICT NO. 5  
 HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
 SHEET C10  
 SHEET 10 OF 20




2:1 SLOPE ON FACE OF HEADWALL TOP OF CL RIP-RAP(TYP.)

F-02-77




1 HEADWALL ELEVATION 36" PIPE  
SCALE: NTS




NOTES:  
1. HYDRAULICS: Q(CAP.)=334.32 CFS  
V=23.88 FPS  
S= 1.3%  
DEPTH = 1'  
Q(100)=138.53 CFS

2 RIPRAP SWALE AT OUTFALL 2-48" SD PIPES  
SCALE: NTS




3 HEADWALL SECTION B-B  
SCALE: NTS



NOTES:  
1. HYDRAULICS: Q(CAP.)=86.9 CFS  
V=10.86 FPS  
S= 0.5%  
DEPTH = 1'  
Q(100)= 66.06 CFS

4 RIPRAP SWALE AT 36" OUTFALL  
SCALE: NTS



APPROVED: DEPARTMENT OF PLANNING AND ZONING  
11/16/02  
CHIEF, DEVELOPMENT ENGINEERING DIVISION MK  
11/21/02  
CHIEF, DIVISION OF LAND DEVELOPMENT

SEDIMENT CONTROL  
( ) BY THE DEVELOPER:  
I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT.  
I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.  
Signature of Developer: [Signature] DATE: 11/16/02  
Signature of Engineer: [Signature] DATE: 11/21/02  
( ) BY THE ENGINEER:  
I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.  
( ) THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.  
USDA-NATURAL RESOURCES CONSERVATION SERVICE DATE: [Signature]  
( ) THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.  
HOWARD SOIL CONSERVATION DISTRICT DATE:

**AMT**  
A. MORTON THOMAS AND ASSOCIATES, INC.  
CONSULTING ENGINEERS  
11250 TWINBROOK PARKWAY, SUITE 200, ROCKVILLE MD 20852  
TEL (301) 981-2565 FAX (301) 981-4814  
AMT FILE # 98-153

**Einhorn Yaffee Prescott**


DES: B. WARNER									
DRN: P. FRIAS									
CHK: B. WARNER									
DATE: 06/21/02	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK	APP			

--	--	--	--	--	--	--	--	--	--

APPLIED PHYSICS LABORATORY  
THE JOHNS HOPKINS UNIVERSITY - POND B  
PARCEL 1  
**DETAILS**  
TAX MAP 41 PARCEL 123  
ELECTION DISTRICT NO. 5  
HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
SHEET C11  
SHEET 11 OF 20

F-02-77




PIPING AND INSERT DIMENSIONS					
STRUCTURE No.	PIPE DIAM. (in)	PIPE MATERIAL	HIN (in)	H (in)	L (in)
SC-7	18"	HDCPP	22	42	95

**DROP PIPE INSTALLATION**

- The drop pipe and the riser pipe MUST NOT be attached to Stormceptor couplings until the BY-PASS CHAMBER section has been connected to the installed TRANSITION SLAB.
- Install the drop pipe and riser pipe while inside the Storage Chamber via a ladder placed down the Stormceptor access hole.
- The drop pipe with the T-section MUST be connected to the INLET gasketed coupling using the supplied PVC lubricant. Make certain that the orientation of the tee is correct (see diagrams).
- The riser pipe MUST be connected to the OUTLET gasketed coupling using the supplied PVC pipe lubricant.

**1 STC PIPE INSTALLATION PROCEDURE**  
NOT TO SCALE



**Design Specifications:**

- ASTM C 478

- NOTES:
- NON-SMOOTH OUTSIDE WALL PIPE TO BE GROUTED IN PLACE (NO KOR-N-SEAL BOOTS).
  - RISER SECTION ABOVE THE INSERT TO BE 72" O FOR A MINIMUM OF 60" OR TO THE GRADE (WHICHEVER IS LESSER).
  - COVER TO BE LOCATED ADJACENT TO INLET INSPECTION PORT.
  - PROVIDE TWO OPEN PICK HOLES ON STORMCEPTOR COVER OFFSET 6" FROM THE STRUCTURE EDGE.
  - NO JOINT SHALL BE PERMITTED AT FLOOR AND WALL.

**2 PRECAST CONCRETE STORMCEPTOR (STC 3600)**  
NOT TO SCALE

CONCRETE STORMCEPTOR DATA - STRUCTURE No. 1					
DRAINAGE AREA (ACRES)	TOP ELEVATION	PIPE SIZE & TYPE	INVERT IN	INVERT OUT	MATERIAL/ MODEL NO.
1.73	409.00	18" HDCPP	406.00	405.85	CCRC/STC3600

**CONTRACTOR INSTALLATION INSTRUCTIONS**  
PRECAST CONCRETE STORMCEPTOR

- STAKE-OUT THE LOCATION OF THE STORMCEPTOR AND EXCAVATE HOLE. EXCAVATE ADEQUATE SPACE TO CONNECT INLET AND OUTLET PIPES TO UNIT. INSTALL A 12" DEEP (OR AS REQUIRED) LAYER OF COMPACTED AGGREGATE SUBBASE AT BOTTOM OF EXCAVATION. INSTALL MULE OR SHORING, AS NEEDED.
- CHECK ELEVATION OF UNIT BY MEASURING ITS SECTIONS FROM BASE OF THE STORAGE CHAMBER (BOTTOM OF UNIT'S SLAB) TO THE INVERT OF STORMCEPTOR BYPASS CHAMBER INLET ELEVATION (FIBERGLASS INSERT). SUBTRACT THIS DISTANCE FROM DESIGN INVERT ELEVATION TO DETERMINE TOP OF SUBBASE ELEVATION. CHECK ELEVATION OF INSTALLED SUBBASE AND ADJUST AS NEEDED.
- SECURE INSPECTOR APPROVAL OF SUBGRADE AND SUBBASE.
- INSTALL STORAGE CHAMBER. INSTALL SCREW INSERTS INTO BASE OF STORAGE CHAMBER. ATTACH CABLES OR CHAINS TO ALL 3 LIFTING LUGS ON THE BASE SLAB USING LARGE EQUIPMENT OR CRANE LIFT. PLACE THE BASE SECTION OF THE STORAGE CHAMBER IN THE EXCAVATED HOLE ON THE SUBBASE. MAKE SURE THAT THE BASE IS LEVEL. SPECIFIC ALIGNMENT OF THIS PART IS NOT REQUIRED. INSTALL RUBBER GASKET ON BASE UNIT AND COAT WITH LUBRICATING GREASE (PROVIDED IN SHIPMENT). IF NOT PRELUBRICATED, INSTALL ADDITIONAL STORAGE CHAMBER SECTIONS, AS REQUIRED (PROCEDURE IS SAME AS STEP 6).
- INSTALL REDUCING SLAB (STORMCEPTOR MODELS STC-2400, STC-3600, STC-4800, STC-6000 AND STC-7200) CHECK THAT SECTION IS SET FLUSH, LEVEL, AND IS AT THE PROPER ELEVATION. INSTALL RUBBER GASKET ON THE TRANSITION SLAB SPIGOT AND COAT WITH LUBRICATING GREASE (PROVIDED IN SHIPMENT).
- INSTALL BYPASS CHAMBER OF STORMCEPTOR WITH FACTORY INSTALLED STORMCEPTOR INSERT. LIFT BYPASS SECTION AND INSTALL, WHILE CHECKING ALIGNMENT AND GRADE OF INLET AND OUTLET DRAINAGE PIPES. CHECK TO MAKE SURE THE BYPASS CHAMBER IS SET FLUSH, LEVEL AND IS AT THE PROPER ELEVATION. THE BYPASS CHAMBER MUST BE SET FLUSH WITH THE TOP OF THE STORAGE CHAMBER. INSTALL RUBBER GASKETS ON INSIDE WEIRS (INSIDE INSERT). INSTALL RUBBER GASKET ON TOP OF BYPASS SECTION AND COAT WITH LUBRICATING GREASE, IF NOT LUBRICATED.
- INSTALL STORMCEPTOR DROP PIPES ACCORDING TO STC PIPE INSTALLATION PROCEDURE AS SHOWN ON THIS SHEET.
- INSTALL RISER SECTION. LIFT RISER SECTION AND INSTALL, WHILE CHECKING THAT SECTION IS SET FLUSH AND IS AT PROPER ELEVATION AND THAT UNIT IS LEVEL. SPECIFIC ALIGNMENT OF THIS PART IS REQUIRED IF STEPS ARE INCLUDED. ALIGN STEPS ABOVE INLET INSPECTION PORT. NOTE, FOR SHALLOW INSTALLATIONS THIS SECTION MAY NOT BE REQUIRED.
- INSTALL TOP CAP WITH OPENING FOR STORMCEPTOR COVER. IF OPENING IS OFFSET (NOT CENTERED), THE TOP CAP OPENING SHOULD BE ORIENTED ABOVE THE STORMCEPTOR INLET INSPECTION PORT/PLUG.
- BACKFILL STORMCEPTOR WITH APPROVED BACKFILL MATERIAL (NO ORGANIC OR TOPSOIL IS TO BE USED FOR BACKFILL). BACKFILL AND COMPACT IN 8" LIFTS. BACKFILL SHOULD BE COMPACTED TO LOCAL/STATE REQUIREMENTS.
- INSTALL AND SET GRADE ADJUSTING RINGS AS NEEDED.
- INSTALL AND SET STORMCEPTOR FRAME AND COVER.
- INSTALL INLET AND OUTLET STORM DRAIN PIPES. CONNECT INLET AND OUTLET STORM DRAIN PIPES WITH FLEXIBLE BOOT (WHEN PROVIDED) AND WITH NON-SHRINK GROUT WHEN NO FLEXIBLE BOOTS ARE PROVIDED. THE INVERT OF THE INLET AND OUTLET PIPE IS TO MATCH WITH THE INVERT OF THE STORMCEPTOR INSERT. FLEXIBLE BOOT INSTALLATION PROCEDURES: CENTER THE PIPE IN THE BOOT OPENING, LUBRICATE THE OUTSIDE OF THE PIPE AND/OR THE INSIDE OF THE BOOT IF THE PIPE OUTSIDE DIAMETER IS THE SAME AS THE INSIDE DIAMETER OF THE BOOT. POSITION THE PIPE CLAMP IN THE GROOVE OF THE BOOT WITH THE SCREW AT THE TOP. TIGHTEN THE PIPE CLAMP SCREW TO 60 INCH POUNDS. IF THE PIPE IS MUCH SMALLER THAN THE BOOT LIFT THE BOOT SUCH THAT IT CONTACTS THE BOTTOM OF THE PIPE WHILE TIGHTENING THE CLAMP TO ENSURE EVEN CONTRACTION OF THE RUBBER. MOVE THE PIPE HORIZONTALLY AND/OR VERTICALLY TO BRING IT TO GRADE.
- THE STORMCEPTOR SHOULD BE PUMPED OUT WHEN THE SEDIMENT CONTROL MEASURES ARE REMOVED (SITE PERMANENTLY STABILIZED).
- FINAL INSPECTION

FOR TECHNICAL INFORMATION CALL STORMCEPTOR AT 1-800-762-4703

AS MANUFACTURED BY CSR-HYDRO CONDUIT AND STORMCEPTOR CORPORATION, MODEL STC-3600, PRECAST CONCRETE. FOR TECHNICAL INFORMATION CALL STORMCEPTOR AT 301-762-8361. TO ORDER CONTACT CSR-HYDRO CONDUIT, VIRGINIA PRECAST AT 1-800-999-2278 AT LEAST 3 WEEKS PRIOR TO NEEDED DELIVERY.

**NOTES:**

- THE STORMCEPTOR IS PROTECTED BY U.S. PATENT NO. 4,985,148.
- CAST IRON FRAME & COVER TO BE APPROVED BY STORMCEPTOR CORPORATION. "STORMCEPTOR" TO BE EMBOSSED ON COVER.
- BEDDING, BACKFILL AND GENERAL INSTALLATION REQUIREMENTS SHALL BE IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE MANUFACTURER AND A PROFESSIONAL ENGINEER BASED ON SITE SPECIFIC SOILS CONDITIONS, SUBJECT TO THE APPROVAL OF THE REGULATORY AGENCIES.
- SIZING OF THE STORMCEPTOR SHALL BE IN ACCORDANCE WITH THE GUIDELINES PROVIDED BY STORMCEPTOR CORPORATION, SUBJECT TO THE APPROVAL OF THE REGULATORY AGENCIES.
- THE STORMCEPTOR SHOULD BE MAINTAINED ANNUALLY AND/OR IMMEDIATELY FOLLOWING ANY KNOWN SPILLS.
- THE STORMCEPTOR CONFORMS TO ASTM C 478 DESIGN SPECIFICATIONS / STANDARDS.
- A MINIMUM OF 1 STEP IS TO BE USED IN THE ACCESS WAY.
- COVER TO BE OFFSET 6" FROM ACCESS WALL ADJACENT TO INLET INSPECTION PORT.
- NON-SMOOTH WALL O.D. PIPE TO BE GROUTED IN PLACE
- FURTHER TECHNICAL INFORMATION IS AVAILABLE FROM STORMCEPTOR CORPORATION 1 (800) 762-4703.

**CONSTRUCTION NOTES**

- SILT AND DEBRIS SHALL NOT BE ALLOWED TO ENTER THE STORMCEPTOR UNTIL THE CONTRIBUTING DRAINAGE AREAS HAVE BEEN PERMANENTLY STABILIZED. SILT MAY BE ALLOWED TO ENTER STORMCEPTOR IF IT IS BEING USED AS A FINAL SEDIMENT CONTROL FILTERING DEVICE.
- ALL OPENINGS TO STRUCTURES SHALL BE PROTECTED WITH THE APPROPRIATE SEDIMENT CONTROL MEASURES.
- THE STORMCEPTOR MUST BE PUMPED OUT AND CLEANED AT THE END OF THE CONSTRUCTION OF THE PROJECT.

**FLOW AND CAPACITIES\***

MODEL	MAX. TREATED FLOW RATE (gpm)**	SEDIMENT CAPACITY (ft <sup>3</sup> )	OIL CAPACITY (US gal)	TOTAL CAPACITY (US gal)
STC 3600	475	345	880	3750

\* APPROXIMATE  
\*\* WITHOUT BY-PASSING

**INSPECTION NOTES: PRECAST CONCRETE STORMCEPTOR**

- PRIOR TO THE START OF INSTALLING THE STORMCEPTOR, THE INSPECTOR MUST BE CALLED 48 HOURS IN ADVANCE (PRE-CONSTRUCTION MEETING).
- THE APL INSPECTOR MUST BE NOTIFIED AT EACH OF THE FOLLOWING STAGES:
  - APPROVAL OF SUBGRADE; PREPARE A COMPACTED GRAVEL BED AT THE BOTTOM OF THE EXCAVATION. ENSURE COMPACTION TO 95% DENSITY.
  - PLACE STORMCEPTOR IN EXCAVATION AT CORRECT ELEVATION AND AT CORRECT ALIGNMENT AND GRADE FOR INLET AND OUTLET STORM DRAINS. LEVEL UNIT INSTALL BASE AND LOWER TANK, MIDDLE SECTION WITH STORMCEPTOR INSERT, RISER SECTION, TOP SLAB WITH PERSONWAY, LEVELING RINGS AND MANHOLE FRAME AND COVER.
  - BACKFILL STORMCEPTOR WITH SUITABLE NATIVE SOIL (NO ORGANIC OR TOPSOIL IS TO BE USED FOR BACKFILL). BACKFILL AND COMPACT IN 8" LIFTS. BACKFILL SHOULD BE AT 95% OF DENSITY.
  - WHEN SITE IS PERMANENTLY STABILIZED AND SEDIMENT CONTROL MEASURES HAVE BEEN REMOVED AND STABILIZED, THEN THE STORMCEPTOR WILL BE PUMPED OUT AND CLEANED AND PLACED IN STORMWATER MANAGEMENT OPERATION.
  - FINAL INSPECTION
- ALL GEOTECHNICAL REPORTS, SOIL COMPACTION, BEARING CAPACITY, AND CONCRETE TESTING DATA & RESULTS SHALL BE PROVIDED TO THE INSPECTOR AND COPIED TO THE OWNER.

**MAINTENANCE NOTES: WATER QUALITY STRUCTURE**

- WATER QUALITY STRUCTURES WILL REQUIRE PERIODIC CLEANING. OWNERS OF THESE FACILITIES WILL HAVE TO CLEAN THEM AS NEEDED.
- MAINTENANCE OF THESE FACILITIES WILL CONSIST OF CLEANING OUT THE STORMCEPTOR AND DISPOSAL OF THE WASTE AND REPAIR OF THE FACILITY AS NEEDED. PERIODIC INSPECTIONS OF THESE FACILITIES WILL BE MADE BY THE OWNER.
- THE DISPOSAL OF THE LIQUID AND SOLID MATTER SHALL BE AS FOLLOWS:
  - ALL LIQUID MATERIAL IN THE STORMCEPTOR SHALL BE PUMPED INTO A SUITABLE TANK TRUCK AND DISPOSED OF AT AN APPROVED SANITARY DISTRICT DISCHARGE MANHOLE OR TO BE TAKEN TO AN APPROVED SEWAGE TREATMENT PLANT FOR RECHARGE.
  - THE SOLID MATERIAL SHALL BE LANDFILLED IN AN APPROVED SANITARY LANDFILL.
- THE INLET PIPES AND STRUCTURAL PARTS SHALL BE REPAIRED AS NEEDED.
- STORMCEPTOR INLET AND OUTLET ASSEMBLY SHALL BE PERIODICALLY INSPECTED. BLOCKAGES SHALL BE REMOVED AND DISPOSED OF AS REQUIRED IN 3B ABOVE.



Concrete Stormceptor® Order Request Form

**Contractor Information**  
NAME: \_\_\_\_\_  
ADDRESS: \_\_\_\_\_  
CITY: \_\_\_\_\_ STATE: \_\_\_\_\_ ZIP CODE: \_\_\_\_\_  
CONTACT: \_\_\_\_\_ PHONE: \_\_\_\_\_ FAX: \_\_\_\_\_

**Owner Information**  
NAME: \_\_\_\_\_ PHONE: \_\_\_\_\_ FAX: \_\_\_\_\_

**Stormceptor Model**  
900  3600   
1200  4800   
1800  6000   
2400  7200

**Insert Size**  
22"  32"  44"  Custom

**Manhole Number**  
Top Elevation (ft) \_\_\_\_\_  
Inlet Pipe Invert (ft) \_\_\_\_\_  
Outlet Pipe Invert (ft) \_\_\_\_\_  
Pipe Type: \_\_\_\_\_  
Pipe Inside Diameter (in) (ID) \_\_\_\_\_  
Pipe Outside Diameter (in) (OD) \_\_\_\_\_

**Project Name** \_\_\_\_\_  
Approximate time frame until required delivery (weeks) \_\_\_\_\_  
Delivery Address: Street \_\_\_\_\_ City \_\_\_\_\_ State \_\_\_\_\_ Zip Code \_\_\_\_\_  
Designer Company \_\_\_\_\_ Phone \_\_\_\_\_ Fax \_\_\_\_\_  
Designer Contact \_\_\_\_\_

Please Fax this sheet back to Hydro Conduit/Virginia Precast at (804) 798-3426 Attn: Dave Brinsler / Ed D'Malley (Phone: 1-800-999-2278)

For credit information/applications contact Carole Broodas at (804) 798-6088 For Technical Assistance Please Call Stormceptor Corporation at (301) 762-8361 or toll free at 1 (800) 762-4703

\*TO BE INCLUDED ON SWM PLAN BY DESIGNER 11/23/95

**NOTE:**

- THE STORMCEPTOR SHOWN RELATES TO THE DEVELOPMENT OF BUILDING P, WHICH HAS NOT BEEN DESIGNED. THIS IS INTENDED AS AN EXAMPLE OF THE SIZE AND TYPE OF STORMCEPTOR THAT WILL BE USED AT THIS BUILDING AND ALL FUTURE BUILDINGS IN AREA 'A'.

**SEDIMENT CONTROL**

( ) BY THE DEVELOPER:  
I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT.  
I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Signature of Developer: \_\_\_\_\_ DATE: 11/21/02

( ) BY THE ENGINEER:  
I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

Signature of Engineer: \_\_\_\_\_ DATE: 11/21/02

USDA-NATURAL RESOURCES CONSERVATION SERVICE


THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

Signature: \_\_\_\_\_ DATE: \_\_\_\_\_


HOWARD SOIL CONSERVATION DISTRICT

APPROVED: DEPARTMENT OF PLANNING AND ZONING  
CHIEF, DEVELOPMENT ENGINEERING DIVISION MK 11/15/02  
CHIEF, DIVISION OF LAND DEVELOPMENT 11/21/02

\* CONTRACTOR SHALL FIELD VERIFY ALIGNMENT AND ELEVATION DATA PRIOR TO ORDERING STORMCEPTOR.



Einhorn Yaffee Prescott



DES:	DRN:	CHK:	DATE:	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK	APP
B. WARNER	S. ITANI	B. WARNER	06/21/02						

APPLIED PHYSICS LABORATORY  
THE JOHNS HOPKINS UNIVERSITY - POND B  
PARCEL 1  
**STORMCEPTOR DETAILS**  
TAX MAP 41 PARCEL 123  
ELECTION DISTRICT NO. 5  
HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
SHEET C12  
SHEET 12 OF 20

**Plastic Pipe-** The following criteria shall apply for plastic pipe:

1. Materials - PVC pipe shall be PVC-1120 or PVC-1220 conforming to ASTM D-1785 or ASTM D-2241. Corrugated High Density Polyethylene (HDPE) pipe, couplings and fittings shall conform to the following: 4' - 10' inch pipe shall meet the requirements of AASHTO M252 Type S, and 12' through 24' shall meet the requirements of AASHTO M294 Type S.
2. Joints and connections to anti-seep collars shall be completely watertight.
3. Bedding - The pipe shall be firmly and uniformly bedded throughout its entire length. Where rock or soft, spongy or other unstable soil is encountered, all such material shall be removed and replaced with suitable earth compacted to provide adequate support.
4. Backfilling shall conform to "Structure Backfill".
5. Other details (anti-seep collars, valves, etc.) shall be as shown on the drawings.

**Drainage Diaphragms** when a drainage diaphragm is used, a registered professional engineer will supervise the design and construction inspection.

**Concrete**

Concrete shall meet the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 414, Mix No. 3.

**Rock Riprap**

Rock riprap shall meet the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, section 921.09, Class C.

**Care of Water during Construction**

All work on permanent structures shall be carried out in areas free from water. The Contractor shall construct and maintain all temporary dikes, levees, cofferdams, drainage channels, and stream diversions necessary to protect the areas to be occupied by the permanent works. The contractor shall also furnish, install, operate, and maintain all necessary pumping and other equipment required for removal of water from various parts of the work and for maintaining the excavations, foundation, and other parts of the work free from water as required or directed by the engineer for constructing each part of the work. After having served their purpose all temporary protective works shall be removed or leveled and graded to the extent required to prevent obstruction in any degree whatsoever of the flow of water to the spillway or outlet works and so as not to interfere in any way with the operation or maintenance of the structure. Stream diversions shall be maintained until the full flow can be passed through the permanent works. The removal of water from the required excavation and the foundation shall be accomplished in a manner and to the extent that will maintain stability of the excavated slopes and bottom required excavations and will allow satisfactory performance of all construction operations. During the placing and compacting of material in required excavations, the water level at the locations being refilled shall be maintained below the bottom of the excavation at such locations which may require drainage the water sumps from which the water shall be pumped.

**Stabilization**

All borrow areas shall be graded to provide proper drainage and left in a slightly condition. All exposed surfaces of the embankment, spillway, spoil and borrow areas, and berms shall be stabilized by seeding, liming, fertilizing and mulching in accordance with the Natural Resources Conservation Service Standards and specifications for critical area planting (MD-342) or as shown on the accompanying drawings.

**Erosion and Sediment Control**

Construction operations will be carried out in such a manner that erosion will be controlled and water and air pollution minimized. State and local laws concerning pollution abatement will be followed. Construction plans shall detail erosion and sediment control measures.

NRCS - MARYLAND

JANUARY 2000

**CONSTRUCTION SPECIFICATIONS**

These specifications are appropriate to all ponds within the scope of the Standard for practice MD-378. All references to ASTM and AASHTO specifications apply to the most recent version.

**Site Preparation**

Areas designated for borrow areas, embankment, and structural works shall be cleared, grubbed and stripped of topsoil. All trees, vegetation, roots, and other objectionable material shall be removed. Channel banks and sharp breaks shall be sloped to no steeper than 1:1. All trees shall be cleared and grubbed within 15 feet of the toe of the embankment.

Areas to be covered by the reservoir will be cleared of all trees, brush, and stumps shall be cut approximately level with the ground surface. For dry stormwater management ponds, a minimum of a 25-foot radius around the inlet structure shall be cleared.

All cleared and grubbed material shall be disposed of outside and below the limits of the dam and reservoir as directed by the owner or his representative. When specified, a sufficient quantity of topsoil will be stockpiled in a suitable location for use on the embankment and other designated areas.

**Earth Fill**

**Material** - The fill material shall be taken from approved designated borrow areas. It shall be free of roots, stumps, and wood. Rubbish, stones greater than 6", frozen or other objectionable materials. Fill material for the center of the embankment, and cut off trench shall conform to Unified Soil Classification GC, SC, CH, or CL and must have at least 3% passing the #200 sieve. Consideration may be given to use of other materials in the embankment if designed by a geotechnical engineer. Such special designs must have construction supervised by a geotechnical engineer.

Materials used in the outer shell of the embankment must have the capability to support vegetation of the quality required to prevent erosion of the embankment.

**Placement** - Areas on which fill is to be placed shall be scarified prior to placement of fill. Fill materials shall be placed in maximum 8-inch thick (before compaction) layers which are to be continuous over the entire length of the fill. The most permeable borrow material shall be placed in the downstream portions of the embankment. The principal spillway must be installed concurrently with the fill placement and not excavated into the embankment.

**Compaction** - The movement of the hauling and spreading equipment over the fill shall be controlled so that the entire surface of each lift shall be traversed by not less than one tread track of heavy equipment or compaction shall be achieved by a minimum of four complete passes of a sheepfoot, rubber tired or vibratory roller. Fill material shall contain sufficient moisture such that the required degree of compaction will be obtained with the equipment used. The fill material shall contain sufficient moisture so that if formed into a ball it will not crumble, yet not be so wet that water can be squeezed out.

When required by the reviewing agency the minimum required density shall not be less than 85% maximum dry density with a moisture content within  $\pm 2\%$  of the optimum. Each layer of fill shall be compacted as necessary to obtain that density, and is to be certified by the Engineer at the time of construction. All compaction is to be determined by AASHTO Method T-99 (Standard Proctor).

**Cut Off Trench** - The cutoff trench shall be excavated into impervious material along or parallel to centerline of the embankment as shown on the plans. The bottom width of the trench shall be governed by the equipment used for excavation, with the minimum width being four feet. The depth shall be at least four feet below existing grade or as shown on the plans. The side slopes of the trench shall be 1 to 1 or flatter. The backfill shall be compacted with construction equipment, rollers, or hand tampers to assure maximum density and minimum permeability.

**Embankment core** - The core shall be parallel to the centerline of the embankment as shown on the plans. The top width of the core shall be a minimum of four feet. The height shall extend up to at least the 10-year water elevation or as shown on the plans. The side slopes shall be 1 to 1 or flatter. The core shall be compacted with construction equipment, rollers, or hand tampers to assure maximum density and minimum permeability. In addition the core shall be placed concurrently with the outer shell of the embankment.

**Structure Backfill**

Backfill adjacent to pipes or structures shall be of the type and quality conforming to that specified for the adjoining fill material. The fill shall be placed in horizontal layers not to exceed four inches in thickness and compacted by hand tampers or other manually directed compaction equipment. The material needs to fill completely all spaces under and adjacent to the pipe. At no time during the backfilling operation shall driven equipment be allowed to operate closer than four feet, measured horizontally, to any part of a concrete structure or pipe unless there is a compacted fill of 24" or greater over the structure or pipe.

Structure backfill may be flowable fill meeting the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 313 as modified. The mixture shall have a 100-200 psi, 28 day unconfined compressive strength. The flowable fill shall have a minimum pH of 4.0 and a minimum resistivity of 2,000 ohm-cm. Materials shall be placed such that a minimum of 6" (measured perpendicular to the outside of the pipe) of flowable fill shall be under (bedding), over and on the sides of the pipe. It only needs to extend up to the spring line for rigid conduits. Average slump of the fill shall be 7" to assure flowability if the material. Adequate measures shall be taken (sand bags, etc.) to prevent floating the pipe. When using flowable fill, all metal pipe shall be bituminous coated. Any adjoining soil fill shall be placed in horizontal layers not to exceed four inches in thickness and compacted by hand tampers or other manually directed compaction equipment. The material shall completely fill all voids adjacent to the flowable fill zone. At no time during the backfilling operation shall driven equipment be allowed to operate closer than four feet, measured horizontally, to any part of a structure. Under no circumstance shall equipment be driven over any part of a structure of pipe unless there is a compacted fill of 24" or greater over the structure or pipe. Backfill material outside the structural backfill (flowable fill) zone shall be of the type and quality conforming to that specified for the core of the embankment materials.

**Pipe Conduits**


All pipes shall be circular in cross section.

**Reinforced Concrete Pipe-** All of the following criteria shall apply for reinforced concrete pipe:

1. Materials - Reinforced concrete pipe shall have a bell and spigot joints with rubber gaskets and shall equal or exceed ASTM C-361.
2. Bedding - Reinforced concrete pipe conduit shall be laid in a concrete bedding/cradle for their entire length. This bedding/cradle shall consist of high slump concrete placed under the pipe and up the sides of the pipe at least 3/4 of its outside diameter with its outside diameter with a minimum thickness of 6 inches. Where a concrete cradle is not needed for structural reasons, flowable fill may be used as described in the "Structure Backfill" section of this standard. Gravel bedding is not permitted.
3. Laying Pipe - Bell and spigot pipe shall be placed with the bell end upstream. Joints shall be made in accordance with recommendations of the manufacturer of the material. After the joints are sealed for the entire line, the bedding shall be placed so that all the spaces under the pipe are filled. Care shall be exercised to prevent any deviation from the original line and grade of the pipe. The first joint must be located within 4 feet from the riser.
4. Backfilling shall conform to "Structure Backfill".
5. Other details (anti-seep collars, valves, etc.) shall be as shown on the drawings.

NRCS - MARYLAND

JANUARY 2000



APPROVED: DEPARTMENT OF PLANNING AND ZONING  
 [Signature] DATE 11/15/00  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION MK  
 [Signature] DATE 11/15/00  
 CHIEF, DIVISION OF LAND DEVELOPMENT





DES: B. WARNER									
DRN: S. ITANI									
CHK: B. WARNER									
DATE: 06/21/02	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK	APP			

APPLIED PHYSICS LABORATORY  
 THE JOHNS HOPKINS UNIVERSITY - POND B  
 PARCEL 1  
**POND SPECS**  
 TAX MAP 41 PARCEL 123  
 ELECTION DISTRICT NO. 5  
 HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
 SHEET C13  
 SHEET 13 OF 20

F-02-77



1 PLAN VIEW SCALE: 1"=30'

**SEDIMENT CONTROL**

( ) BY THE DEVELOPER:  
 I, THE DEVELOPER, CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT.  
 I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Signature of Developer: *[Signature]* DATE: 11/15/02

Signature of Engineer: *[Signature]* DATE: 11/21/02

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

USDA-NATURAL RESOURCES CONSERVATION SERVICE DATE: \_\_\_\_\_

( ) THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

HOWARD SOIL CONSERVATION DISTRICT DATE: \_\_\_\_\_

APPROVED: DEPARTMENT OF PLANNING AND ZONING  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION MK DATE: 11/15/02  
 CHIEF, DIVISION OF LAND DEVELOPMENT RW DATE: 11/21/02

**Schnabel Engineering, Inc. TEST LOG** Project: John Hopkins Applied Physics Lab Storm Water Management Basin - B Laurel, Maryland

Boring Contractor: Connelly and Associates, Inc.  
 Boring Foreman: Eric Deazo  
 Drilling Method: 2-1/2" I.D. Hollow Stem Auger  
 Drilling Equipment: Truck-Mounted  
 SEA Representative: Eric Hemminger  
 Date Started: 11/01/01 Finished: 11/01/01  
 Location: See Boring Location Plan

Ground Surface Elevation: 551.05 (ave)

DEPTH (ft)	STRATA DESCRIPTION	CLASS.	BLK. (ft)	NET (ft)	DEPTH (ft)	Groundwater Observations			
						Date	Time	Depth	Quality
0.4	loose sandy SILT, trace mica, nodal, brown	SL	300.0		11-01-01				
					11-02-01				
					11-27-01				
14.0	DISINTEGRATED ROCK, trace mica, nodal, whitish-grey	SR	307.0		11-27-02				
16.7	BOTTOM OF BORING @ 16.7 FT.		302.3		600.1*				

**Schnabel Engineering, Inc. TEST LOG** Project: John Hopkins Applied Physics Lab Storm Water Management Basin - B Laurel, Maryland

Boring Contractor: Connelly and Associates, Inc.  
 Boring Foreman: Eric Deazo  
 Drilling Method: 2-1/2" I.D. Hollow Stem Auger  
 Drilling Equipment: Truck-Mounted  
 SEA Representative: Eric Hemminger  
 Date Started: 11/01/01 Finished: 11/01/01  
 Location: See Boring Location Plan

Ground Surface Elevation: 301.04 (ave)

DEPTH (ft)	STRATA DESCRIPTION	CLASS.	BLK. (ft)	NET (ft)	DEPTH (ft)	Groundwater Observations			
						Date	Time	Depth	Quality
0.4	loose SILT with fine sand, trace mica, nodal, yellowish-brown	SL	300.0		11-01-01				
					11-02-01				
					11-27-01				
14.0	DISINTEGRATED ROCK, trace mica, nodal, whitish-grey	SR	307.0		11-27-02				
16.7	BOTTOM OF BORING @ 16.7 FT.		302.3		600.1*				


**Schnabel Engineering, Inc. TEST LOG** Project: John Hopkins Applied Physics Lab Storm Water Management Basin - B Laurel, Maryland

Boring Contractor: Connelly and Associates, Inc.  
 Boring Foreman: Eric Deazo  
 Drilling Method: 2-1/2" I.D. Hollow Stem Auger  
 Drilling Equipment: Truck-Mounted  
 SEA Representative: Eric Hemminger  
 Date Started: 11/01/01 Finished: 11/01/01  
 Location: See Boring Location Plan


Ground Surface Elevation: 374.06 (ave)

DEPTH (ft)	STRATA DESCRIPTION	CLASS.	BLK. (ft)	NET (ft)	DEPTH (ft)	Groundwater Observations			
						Date	Time	Depth	Quality
0.4	loose sandy SILT, trace mica, nodal, brown	SL	373.0		11-01-01				
					11-02-01				
					11-27-01				
10.0	trace rock fragments @ 8.5 feet		364.0		610-10				
10.0	BOTTOM OF BORING @ 10.0 FT.		364.0		610-10				

2 BORING DATA



Einhorn Yaffee Prescott




DES: B. WARNER					
DRN: P. FRIAS					
CHK: B. WARNER					
DATE: 06/21/02	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK APP

APPLIED PHYSICS LABORATORY  
 THE JOHNS HOPKINS UNIVERSITY - POND B  
 PARCEL 1  
 BORING LOCATION & DATA

TAX MAP 41 PARCEL 123  
 ELECTION DISTRICT NO. 5  
 HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
 SHEET C14  
 SHEET 14 OF 20



PROFILE THRU EMBANKMENT  
SEE SHEET C-8 DETAIL 1

2-YR ELEV. 376.08  
10-YR ELEV. 380.23  
100-YR ELEV. 381.32

EMBANKMENT CL PROFILE  
LAYOUT SEE SHEET C-8

NEW JHU APL PROPERTY LINE  
TRANSFERRED TO HOWARD COUNTY

EDGE OF PAVEMENT

EX. TRAFFIC BARRIER


SANNER ROAD

OLD PROPERTY CORNER

FORMER APL PROPERTY LINE  
TRANSFERRED TO HOWARD COUNTY

NOTES:

- INSTALL SANDBAGS/STONE DIVERSION AROUND STORMWATER MANAGEMENT STRUCTURE OUTLET. AFTER EACH RAINSTORM DEWATER BASIN BY BY MEANS OF A MECHANICAL PUMP THROUGH A "PST" WHICH DISCHARGE TO THE "SP" STRUCTURE
- VERTICAL DRAW-DOWN DEVICE (SEE DETAIL ON SHEET ES-3)



APPROVED: DEPARTMENT OF PLANNING AND ZONING  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION MK DATE 11/15/12  
 CHIEF, DIVISION OF LAND DEVELOPMENT HP DATE 11/21/12

FOR EROSION AND SEDIMENT CONTROL ONLY

SEDIMENT CONTROL

( ) BY THE DEVELOPER: I CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Signature of Developer: [Signature] DATE: 10/7/12

( ) BY THE ENGINEER: I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.



Signature of Engineer: [Signature] DATE: 10/29/12

( ) THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

Signature of Natural Resources Conservation Service: [Signature] DATE: 10/29/12

( ) THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

Signature of Howard Soil Conservation District: [Signature] DATE: 10/29/12





DES: B. WARNER							
DRN: S. ITANI							
CHK: B. WARNER							
DATE: 06/21/02	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK	APP	

APPLIED PHYSICS LABORATORY  
 THE JOHNS HOPKINS UNIVERSITY  
 PARCEL 1  
**EROSION & SEDIMENT CONTROL PLAN**  
 TAX MAP 41 PARCEL 123  
 ELECTION DISTRICT NO. 5  
 HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
 SHEET ES-1  
 SHEET 15 OF 20

F-02-77

DETAIL 21 - PORTABLE SEDIMENT TANK




STANDARD SYMBOL  
PST

Construction Specifications

- The following formula should be used in determining the storage volume of the sediment tank: 1 cubic foot of storage for each gallon per minute of pump discharge capacity.
- An example of a typical sediment tank is shown above. Other container designs can be used if the storage volume is adequate and approval is obtained from the local approving agency.
- Tanks may be connected in series.

U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE PAGE 0-14-2 MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION

DETAIL 20B - SUMP PIT




STANDARD SYMBOL  
SP

Construction Specifications

- Pit dimensions are variable, with the minimum diameter being 2 times the standpipe diameter.
- The standpipe should be constructed by perforating a 12" to 24" diameter corrugated or PVC pipe. Then wrapping with 1/2" hardware cloth and Geotextile Class E. The perforations shall be 1/2" x 6" slits or 1" diameter holes.
- A base of filter material consisting of clean gravel or #57 stone should be placed in the pit to a depth of 12". After installing the standpipe, the pit surrounding the standpipe should then be backfilled with the same filter material.
- The standpipe should extend 12" to 18" above the lip of the pit or the riser crest elevation (basin dewatering only) and the filter material should extend 3" minimum above the anticipated standing water elevation.

U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE PAGE 0-13-2 MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION

DETAIL 33 - SUPER SILT FENCE



STANDARD SYMBOL  
SSF

NOTE: FENCE POST SPACING SHALL NOT EXCEED 10' CENTER TO CENTER

- Fencing shall be 42" in height and constructed in accordance with the latest Maryland State Highway Details for Chain Link Fencing. The specification for a 6' fence shall be used, substituting 42" fabric and 6' length posts.
- Chain link fence shall be fastened securely to the fence posts with wire ties. The lower tension wire, brace and truss rods, drive anchors and post caps are not required except on the ends of the fence.
- Filter cloth shall be fastened securely to the chain link fence with ties spaced every 24" at the top and mid section.
- Filter cloth shall be embedded a minimum of 8" into the ground.
- When two sections of filter cloth adjoin each other, they shall be overlapped by 6" and folded.
- Maintenance shall be performed as needed and silt buildups removed when "bulges" develop in the silt fence, or when silt reaches 50% of fence height.
- Filter cloth shall be fastened securely to each fence post with wire ties or staples at top and mid section and shall meet the following requirements for Geotextile Class F:  
Tensile Strength 50 lbs/in (min.) Test: MSMT 509  
Tensile Modulus 20 lbs/in (min.) Test: MSMT 509  
Flow Rate 0.3 gal/ft<sup>2</sup>/minute (max.) Test: MSMT 322  
Filtering Efficiency 75% (min.) Test: MSMT 322

U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE PAGE H-28-3 MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION

EROSION CONTROL LEGEND

- SCE STABILIZED CONSTRUCTION ENTRANCE
- SSF SUPER SILT FENCE
- LOD LIMIT OF DISTURBANCE
- TP TREE PROTECTION
- SP SUMP PIT
- PST PORTABLE SEDIMENT TANK
- TEMPORARY SANDBAG DIVERSION
- RIPRAP

SEDIMENT CONTROL

( ) BY THE DEVELOPER:  
I CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT.  
I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Signature: [Signature] DATE: 11/15/02

( ) BY THE ENGINEER:  
I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A RATIONAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.


Signature: [Signature] DATE: 11/15/02

( ) THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

Signature: [Signature] DATE: 11/27/02

Signature: [Signature] DATE: 11/27/02

DETAIL 24 - STABILIZED CONSTRUCTION ENTRANCE



STANDARD SYMBOL  
SCE

Construction Specification

- Length - minimum of 50' (\*30' for single residence lot).
- Width - 10' minimum, should be flared at the existing road to provide a turning radius.
- Geotextile fabric (filter cloth) shall be placed over the existing ground prior to placing stone. \*\*The plan approval authority may not require single family residences to use geotextile.
- Stone - crushed aggregate (2" to 3") or reclaimed or recycled concrete equivalent shall be placed at least 6" deep over the length and width of the entrance.
- Surface Water - all surface water flowing to or diverted toward construction entrances shall be piped through the entrance, maintaining positive drainage. Pipe installed through the stabilized construction entrance shall be protected with a mountable berm with 5:1 slopes and a minimum of 6" of stone over the pipe. Pipe has to be sized according to the drainage. When the SCE is located at a high spot and has no drainage to convey a pipe will not be necessary. Pipe should be sized according to the amount of runoff to be conveyed. A 6" minimum will be required.
- Location - A stabilized construction entrance shall be located at every point where construction traffic enters or leaves a construction site. Vehicles leaving the site must travel over the entire length of the stabilized construction entrance.

U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE PAGE F-17-3 MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION


SILT FENCE

Silt Fence Design Criteria

Slope Steepness	(Maximum) Slope Length	(Maximum) Silt Fence Length
Flatter than 50:1	unlimited	unlimited
50:1 to 10:1	125 feet	1,000 feet
10:1 to 5:1	100 feet	750 feet
5:1 to 3:1	60 feet	500 feet
3:1 to 2:1	40 feet	250 feet
2:1 and steeper	20 feet	125 feet

Note: In areas of less than 2% slope and sandy soils (USDA general classification system, soil Class A) maximum slope length and silt fence length will be unlimited. In these areas a silt fence may be the only perimeter control required.

U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE PAGE E-15-3A MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION



MAINTENANCE

- INSPECT SILT FENCES IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY.
- PAY CLOSE ATTENTION TO THE REPAIR OF DAMAGED SILT FENCE RESULTING FROM END RUNS AND UNDERCUTTING.
- SHOULD THE FABRIC ON A SILT FENCE DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL BE NECESSARY, REPLACE THE FABRIC PROMPTLY.
- REMOVE SEDIMENT DEPOSITS AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER.
- AFTER THE SILT FENCE IS NO LONGER REQUIRED, DRESS ANY SEDIMENT DEPOSITS THAT REMAIN IN PLACE TO CONFORM WITH THE EXISTING GRADE. PREPARE AND SEED THESE SEDIMENT DEPOSITS.

CONSTRUCTION OF A SILT FENCE (WITH WIRE SUPPORT) INSTALLATION

INSTALLATION

- THE HEIGHT OF A SILT FENCE SHALL BE A MINIMUM OF 16 INCHES ABOVE THE ORIGINAL GROUND SURFACE AND SHALL NOT EXCEED 34 INCHES ABOVE GROUND ELEVATION.
- THE FILTER FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID THE USE OF JOINTS. WHEN JOINTS ARE UNAVOIDABLE, FILTER CLOTH SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST WITH A MINIMUM 6-INCH OVERLAP, AND SECURELY SEALED.
- A TRENCH SHALL BE EXCAVATED APPROXIMATELY 4-INCHES WIDE AND 4-INCHES DEEP ON THE UPSLOPE SIDE OF THE PROPOSED LOCATION OF THE MEASURE.
- WHEN WIRE SUPPORT IS USED, STANDARD-STRENGTH FILTER CLOTH MAY BE USED. POSTS FOR THIS TYPE OF INSTALLATION SHALL BE PLACED A MAXIMUM OF 10- FEET APART. THE WIRE MESH FENCE MUST BE FASTENED SECURELY TO THE UPSLOPE SIDE OF THE POSTS USING HEAVY DUTY WIRE STAPLES AT LEAST ONE INCH LONG, TIE WIRES, OR HOG RINGS. THE WIRE SHALL EXTEND INTO THE TRENCH A MINIMUM OF TWO INCHES AND SHALL NOT EXTEND MORE THAN 34 INCHES ABOVE THE ORIGINAL GROUND SURFACE. THE STANDARD STRENGTH FABRIC SHALL BE STAPLED OR WIRED TO THE WIRE FENCE, AND 8 INCHES OF THE FABRIC SHALL BE EXTENDED INTO THE TRENCH. THE FABRIC SHALL NOT BE STAPLED TO EXISTING TREES.
- WHEN WIRE SUPPORT IS NOT USED, EXTRA-STRENGTH FILTER CLOTH SHALL BE USED. POSTS FOR THIS TYPE OF FABRIC SHALL BE PLACED A MAXIMUM OF 6- FEET APART. THE FILTER FABRIC SHALL BE FASTENED SECURELY TO THE UPSLOPE SIDE OF THE POSTS USING ONE INCH LONG (MINIMUM) HEAVY-DUTY WIRE STAPLES OR TIE WIRES AND 8-INCHES OF THE FABRIC SHALL BE EXTENDED INTO THE TRENCH. THE FABRIC SHALL NOT BE STAPLED TO EXISTING TREES.
- IF A SILT FENCE IS TO BE CONSTRUCTED ACROSS A DITCH LINE OR SWALE, THE MEASURE MUST BE OF SUFFICIENT LENGTH TO ELIMINATE ENDFLOW. THE CONFIGURATION FLOW SHALL RESEMBLE AN ARC OR HORSESHOE WITH THE ENDS ORIENTED UPSLOPE. EXTRA-STRENGTH FILTER FABRIC SHALL BE USED FOR THIS APPLICATION WITH A MAXIMUM 3-FOOT SPACING OF POSTS. ALL OTHER REQUIREMENTS OF NOTE #5 APPLY.
- THE 4-INCH BY 4-INCH TRENCH SHALL BE BACKFILLED WITH THE SOIL COMPACTED OVER THE FILTER FABRIC.
- SILT FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY STABILIZED.

APPROVED: DEPARTMENT OF PLANNING AND ZONING  
 [Signature] DATE: 11/15/02  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION MK  
 [Signature] DATE: 11/27/02  
 CHIEF, DIVISION OF LAND DEVELOPMENT

FOR EROSION AND SEDIMENT CONTROL ONLY



**AMT**  
 A. MORTON THOMAS AND ASSOCIATES, INC.  
 CONSULTING ENGINEERS  
 112750 TWINBROOK PARKWAY, SUITE 200, ROCKVILLE MD 20852  
 TEL: (301) 981-2546 FAX: (301) 981-0914  
 AMT FILE # 98-153

Einhorn  
 Yaffee  
 Prescott

DES: B. WARNER					
DRN: S. ITANI					
CHK: B. WARNER					
DATE: 06/21/02	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK APP


APPLIED PHYSICS LABORATORY  
 THE JOHNS HOPKINS UNIVERSITY - POND B  
 PARCEL 1  
**EROSION & SEDIMENT  
 NOTES AND DETAILS**  
 TAX MAP 41 PARCEL 123  
 ELECTION DISTRICT NO. 5  
 HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
 SHEET ES-2  
 SHEET 16 OF 20



Figure 2 Temporary Sediment Basin Design Data Sheet

Computed by: RF Date: 06-21-02 Checked by: \_\_\_\_\_ Date: \_\_\_\_\_  
 Project name: APPLIED PHYSICS LAB BASIN #1  
 Location: 11100 JOHN HOPKINS ROAD LAUREL, MARYLAND 20723  
 Total area draining to basin: 0.67 acres (ac)

Design Elevations

- 23. Riser Crest = 399.5 ft.
- 24. Design High Water (dHW) = 390.23 ft.
- 25. Emergency Spillway Crest = 399.5 ft.
- 26. Min. settled top of dam = 388.50 ft.
- 27. Permanent pool = 391.0 ft.
- 28. Bottom of Basin = 378.0 ft.
- 29. Draw-down orifice invert = 378.0 ft.

Surface Area Design

- 30. Min. basin surface area; SA ≥ 0.0035 x Q<sub>0</sub> = 0.0035 x 57 cfs ≤ 0.2 ac. 8712 ft<sup>2</sup>

Draw-down Device


- 31. Draw-down device orifice diameter = \_\_\_\_\_ in. (From Table 11)
- 32. A<sub>i</sub> = Total area of perforations ≥ 4A<sub>o</sub>  
 A<sub>o</sub> = (# of perforation/foot)(perforation area ft<sup>2</sup>)(perforated section length ft.)  
 A<sub>o</sub> = 6.87 ft<sup>2</sup>  
 A<sub>i</sub> = Internal orifice area (from Table 11 or computed)

Basin Volume Design

- Note: 1. Also see Surface Area Design #30, this form.  
 2. To convert ft<sup>2</sup> to yd<sup>2</sup>, divide ft<sup>2</sup> by 9.

- 1. Min. required vol. = 3600 ft<sup>3</sup>/ac x 0.67 ac. drainage = 2412 ft<sup>3</sup>
- 2. Actual Volume of basin = 25410 ft<sup>3</sup>
- 3. Excavate \_\_\_\_\_ ft<sup>3</sup> (\_\_\_\_\_ yd<sup>3</sup>) to obtain required capacity.
- 4. Vol. at dewatering elev. = 1800 ft<sup>3</sup>/ac x 0.67 ac. = 1206 ft<sup>3</sup>
- 5. Vol. of basin at cleanout = 900 ft<sup>3</sup>/ac x 0.67 ac. = 603 ft<sup>3</sup>
- 6. Elevation corresponding to min. required volume of basin (riser crest elevation) 399.5 ft.
- 7. Permanent pool elevation 391.0 ft.
- 8. Distance from riser crest elevation to permanent pool elevation 9.5 ft.
- 9. Basin cleanout elevation 388.50 ft.
- 10. Distance from riser crest elevation to cleanout elevation 11.0 ft.

MECHANICAL PUMP THROUGH "PST".  
 SANDBAG/STONE DIVERSION TO BE INSTALLED TO BLOCK INLET  
 OF BASIN OUTLET STRUCTURE. BASIN TO BE DEWATERED BY



Description

The work shall consist of installing flow diversions for the purpose of erosion control when construction activities take place within the stream channel such as bank stabilization or bridge abutment construction.


Material Specifications

- 1. Sandbags: Sandbags shall consist of materials which are resistant to ultra-violet radiation, tearing and puncture and woven tightly enough to prevent leakage of fill material (i.e., sand, fine gravel, etc.).
- 2. Stone: Stone shall be washed and have a minimum diameter of 6 inches.
- Sheeting: Sheeting shall consist of polyethylene or other material which is impervious and resistant to puncture and tearing.

Construction Requirements

- 1. All erosion and sediment control devices shall be installed as the first order of work.
- 2. The diversion structure shall be installed from upstream to downstream.
- 3. The height of the diversion structure shall be one half the distance from stream bed to stream bank plus one foot, as indicated on the cross-section view.
- 4. All excavated materials shall be disposed of in a SCD approved disposal area outside the 100-year floodplain unless otherwise approved on the plans by the WRA.
- 5. All dewatering of the construction area shall be pumped to a dewatering basin prior to re-entering the stream.
- 6. Sheeting shall be overlapped such that the upstream portion covers the downstream portion with at least an 18-inch overlap.
- 7. Sediment control devices are to remain in place until all disturbed areas are stabilized in accordance with an approved sediment and erosion control plan and the inspecting authority approves their removal.

WATER RESOURCES ADMINISTRATION	Sandbag/Stone Diversion	Approved On <u>11/15/02</u> <u>Chiefl, Waterway Permits</u>	WPD 23
--------------------------------	-------------------------	----------------------------------------------------------------	--------



NOTES:

- 1. Forest protection device only.
- 2. Retention Area will be set as part of the review process.
- 3. Boundaries of retention Area should be staked and flagged prior to installation device.
- 4. Root damage should be avoided.
- 5. Protective signage is required.
- 6. Device should be maintained throughout construction

TREE PROTECTION DEVICE  
 NOT TO SCALE

SEDIMENT CONTROL

( ) BY THE DEVELOPER:  
 I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT.  
 I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Signature of Developer: [Signature] DATE: 10/15/02


( ) BY THE ENGINEER:  
 I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

Signature of Engineer: [Signature] DATE: \_\_\_\_\_

( ) THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

Signature of Reviewer: [Signature] DATE: 10/24/02

Signature of Reviewer: [Signature] DATE: 10/24/02




- Construction Specifications
- 1. Perforations in the draw-down device may not extend into the wet storage.
  - 2. The total area of the perforations must be greater than 2 times the area of the internal orifice.
  - 3. The perforated portion of the draw-down device shall be wrapped with 1/2" hardware cloth and geotextile fabric. The geotextile fabric shall meet the specifications for Geotextile Class E.
  - 4. Provide support of draw-down device to prevent sagging and flotation. An acceptable preventative measure is to stake both sides of draw-down device with 1" steel angle, or 1" by 4" square or 2" round wooden posts set 3' minimum into the ground then joining them to the device by wrapping with 12 gauge minimum wire.

U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE	PAGE C - 10 - 30	MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION
-------------------------------------------------------------	---------------------	-----------------------------------------------------------------------

APPROVED: DEPARTMENT OF PLANNING AND ZONING  
[Signature] DATE: 11/15/02  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION MK  
[Signature] DATE: 11/21/02  
 CHIEF, DIVISION OF LAND DEVELOPMENT VB

FOR EROSION AND SEDIMENT CONTROL ONLY



DES: B. WARNER					
DRN: S. ITANI					
CHK: B. WARNER					
DATE: 06/21/02	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK APP

APPLIED PHYSICS LABORATORY  
 THE JOHNS HOPKINS UNIVERSITY - POND B  
 PARCEL 1  
**EROSION & SEDIMENT  
 DETAILS AND NOTES**  
 TAX MAP 41 PARCEL 123  
 ELECTION DISTRICT NO. 5  
 HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
 SHEET ES-3  
 SHEET 17 OF 20

F-02-77

**SEDIMENT CONTROL**

( ) BY THE DEVELOPER:  
I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT.  
I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Signature of Developer: *[Signature]* Date: *10/24/02*

( ) BY THE ENGINEER:  
I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

Signature of Engineer: *[Signature]* Date: *10/24/02*

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

Signature: *[Signature]* Date: *10/24/02*

THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

Signature: *[Signature]* Date: *10/24/02*

- ADDITIONAL SEDIMENT CONTROLS MUST BE PROVIDED, IF DEEMED NECESSARY BY THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR.
- ON ALL SITES WITH DISTURBED AREAS IN EXCESS OF 2 ACRES, APPROVAL OF THE INSPECTION AGENCY SHALL BE REQUESTED UPON COMPLETION OF INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS, BUT BEFORE PROCEEDING WITH ANY OTHER EARTH DISTURBANCE OR GRADING. OTHER BUILDING OR GRADING INSPECTION APPROVALS MAY NOT BE AUTHORIZED UNTIL THIS INITIAL APPROVAL BY THE INSPECTION AGENCY IS MADE.
- TRENCHES FOR THE CONSTRUCTION OF UTILITIES IS LIMITED TO THREE PIPE LENGTHS OR THAT WHICH SHALL BE BACK-FILLED AND STABILIZED WITHIN ONE WORKING DAY, WHICHEVER IS SHORTER.
- EXCAVATION AND FILL QUANTITIES SHOWN ARE FOR THE USE OF THE SEDIMENT AND EROSION CONTROL REVIEW ONLY. THE CONTRACTOR SHALL NOT ESTIMATE ESTIMATE THEIR CONSTRUCTION COSTS BASED ON THESE QUANTITIES AS THEY ARE APPROXIMATE AND ARE SUBJECT TO UNKNOWN SITE CONDITIONS.

**MAINTENANCE:**

INSPECT ALL SEEDED AREAS AND MAKE NEEDED REPAIRS, REPLACEMENTS AND RESEEDINGS.  
FOR PUBLIC PONDS SUBSTITUTE CHEMUNG CROWN VETCH AT 15 LBS/ACRE AND KENTUCKY 31 TALL FESCUE AT 40 LBS/ACRE AS THE SEEDING REQUIREMENT.  
OPTIMUM SEEDING DATE FOR THIS MISTURE IS MARCH 1 TO APRIL 30.

**TEMPORARY SEEDING NOTES:**

APPLY TO GRADED OR CLEARED AREAS LIKELY TO BE REDISTURBED WHERE A SHORT-TERM VEGETATIVE COVER IS NEEDED.

**SEEDED PREPARATION:**

LOOSEN UPPER THREE INCHES OF SOIL BY RAKING DISCING OR OTHER ACCEPTABLE MEANS BEFORE SEEDING, IF NOT PREVIOUSLY LOOSENED.

**SOIL AMENDMENTS:**

APPLY 600 LBS. PER ACRE 10-10-10 FERTILIZER (14 LBS./1000 SQ. FT.) ACCEPTABLE MEANS BEFORE SEEDING, IF NOT PREVIOUSLY LOOSENED.

**SEEDING:**

FOR THE PERIOD MARCH 1 THROUGH APRIL 30, AND AUGUST 15 THROUGH NOVEMBER 15, SEED WITH 1-1/2 BUSHEL PER ANNUAL RYE (3.2 LBS./1,000 SQ. FT.) FOR THE PERIOD MAY 1 THRU AUGUST 14, SEED WITH 3 LBS./ACRE OF WEEPING LOVE GRASS (0.07 LBS./1000 SQ. FT.). FOR THE PERIOD NOVEMBER 16 THRU FEBRUARY 28. PROTECT SITE BY APPLYING 2 TONS PER ACRE OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING OR USE SOD.

**MULCHING:**

APPLY 1-1/2 TO 2 TONS PER ACRE (70 TO 90 LBS./1,000 SQ.FT) OR UNROTTED SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. ANCHOR MULCH IMMEDIATELY AFTER APPLICATION USING MULCH ANCHORING TOOL OR 218 GALLONS PER ACRE (5 GAL/1,000 SQ.FT) OF EMULSIFIED ASPHALT ON FLAT ACRES. ON SLOPES 8 FEET OR HIGHER, USE 348 GALLONS PER ACRE (8 GAL/1,000 SQ.FT.) FOR ANCHORING.

REFER TO THE 1988 MARYLAND STANDARDS AND SPECIFICATION FOR SOIL EROSION AND SEDIMENT CONTROL FOR RATE AND METHODS NOT COVERED.

**PERMANENT SEEDING NOTES:**

ALL DISTURBED AREAS SHALL BE STABILIZED AS FOLLOWS:

**SEEDBED PREPARATION:**

LOOSEN UPPER THREE INCHES OF SOIL BY RAKING, DISCING OR OTHER ACCEPTABLE MEANS BEFORE SEEDING.

**SOIL AMENDMENTS:**

APPLY TWO TONS PER ACRE DOLOMITIC LIME STONE (92 LBS./1,000 SQ.FT) AND 600 LBS PER ACRE 0-20-20 FERTILIZER (14 LBS./1,000 SQ.FT) BEFORE SEEDING HARROW OR DISCING. INTO UPPER THREE INCHES OF SOIL. AT TIME OF SEEDING, APPLY 400 LNS PER ACRE 38-0-0 UREAFORM FERTILIZER (9 LBS./1,000 SQ. FT.) AND 500 LBS PER ACRE (11.5 LBS./1,000 SQ. FT.) OF 10-20-20 FERTILIZER.

**SOIL AMENDMENTS:**

FOR THE PERIODS MARCH 1 THROUGH APRIL 30, AND AUGUST 1 THROUGH OCTOBER 15, SEED WITH 100 LBS PER ACRE (2.3 LBS./1,000 SQ.FT.) OF KENTUCKY 31 TALL FESCUE, FOR THE PERIOD MAY 1 THROUGH JULY 21, SEED WITH 60 LBS/ACRE (1.4 LBS./1,000 SQ.FT.) KENTUCKY 31 TALL FESCUE AND 2 LBS PER ACRE (0.05 LBS./1,000 SQ.FT.) OF WEEPING LOVEGRASS. DURING THE PERIOD OF OCTOBER 16 THROUGH FEBRUARY 28. PROJECT SITE BY: OPTION (1) - TWO TONS PER ACRE OF WELL ANCHORED STRW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRINGS OPTION (2) - USE 500, OPTION (3) - SEED WITH 100 LBS/ACRE KENTUCKY 21 TALL FESCUE AND MULCH WITH TWO TONS/ACRE WELL ANCHORED STAW. ALL SLOPES SHOULD BE HYDROSEEDED.

**MULCHING:**

APPLY 1-1/2 TO 2 TONS PER ACRE (10 TO 90 LBS./1,000 SQ.FT.) OF UNROTTED SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. ANCHOR MULCH IMMEDIATELY AFTER APPLICATION USING 200 GALLONS PER ACRE (5 GAL./1,000 SQ.FT.) OF EMISIFIED ASPHALT ON FLAT ACRES. ON SLOPES 8 FEET OR HIGHER USE 348 GALLONS PER ACRE (8 GAL./1,000 SQ.FT.) FOR ANCHORING.

**SEQUENCE OF CONSTRUCTION:**

- CONTRACTOR SHALL OBTAIN A GRADING PERMIT.
- NOTIFY APL AND COUNTY SEDIMENT CONTROL INSPECTOR AT LEAST 14 DAYS PRIOR TO BEGINNING WORK TO ARRANGE FOR A PRE-CONSTRUCTION MEETING.
- PERFORM CLEARING ONLY AS NECESSARY TO INSTALL TREE PROTECTION, STABILIZED CONSTRUCTION ENTRANCE, SILT FENCE AND ALL OTHER SEDIMENT CONTROL FACILITIES WITHIN THE PROJECT LIMIT.
- ESTABLISH STAGING AREA FOR CONSTRUCTION.
- ROUGH GRADE SITE AND EXCAVATE TRENCH FOR CONSTRUCTION OF EMBANKMENT CORE TRENCH.
- INSTALL BACKFILL AND COMPACT EMBANKMENT AND CORE TRENCH TO THE TOP ELEVATION OF THE OUTLET PIPE. INSTALL INLET PROTECTION ON NEW STRUCTURE.
- EXCAVATE THE TRENCH TO ALLOW FOR THE INSTALLATION OF THE BASIN OUTLET PIPE AND ANTISEEP COLLAR AND INSTALL SAME.
- INSTALL BACKFILL AND COMPACT REMAINDER OF EMBANKMENT AND CORE TRENCH.
- PROVIDE AND INSTALL REMAINDER OF CONSTRUCTION AS SHOWN.
- PERFORM FINE GRADING AND PERMANENT STABILIZATION OF THE SITE INCLUDING RIP-RAP AND VEGETATIVE STABILIZATION.
- REQUEST FINAL INSPECTION FROM COUNTY SEDIMENT CONTROL INSPECTOR.
- WITH COUNTY SEDIMENT CONTROL INSPECTOR'S APPROVAL OF SITE CONDITIONS REMOVE SEDIMENT CONTROL FACILITIES AND ESTABLISH VEGETATION ON ALL DEWATERED AREAS.

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION & SEDIMENT CONTROL.

Signature: *[Signature]* Date: *10/24/02*

USDA NATURAL RESOURCES CONSERVATION SERVICE

THESE PLANS FOR SOIL EROSION & SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD COUNTY SOIL CONSERVATION DISTRICT.

Signature: *[Signature]* Date: *10/24/02*

HOWARD SOIL CONSERVATION DISTRICT

**SEDIMENT CONTROL NOTES**

- A MINIMUM OF 48 HOURS NOTICE MUST BE GIVEN TO THE HOWARD COUNTY DEPARTMENT OF INSPECTIONS, LICENSES AND PERMITS, SEDIMENT CONTROL DIVISION PRIOR TO THE START OF ANY CONSTRUCTION (313-1855).
- ALL VEGETATIVE AND STRUCTURAL PRACTICES AE TO BE INSTALLED ACCORDING TO THE PROVISIONS OF THIS PLAN AND ARE TO BE IN CONFORMANCE WITH THE MOST CURRENT MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL AND REVISIONS THERE TO.
- FOLLOWING INITIAL SOIL DISTURBANCE OR RE-DISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN: A) 7 CALENDAR DAYS FOR ALL PERIMETER SEDIMENT CONTROL STRUCTURES, DIKES, PERIMETER SLOPES AND ALL SLOPES STEEPER THAN 3:1. B) 14 DAYS AS TO ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE.
- ALL SEDIMENT TRAPS/BASINS SHOWN MUST BE FENCED AND WARNING SIGNS POSTED AROUND THEIR PERIMETER IN ACCORDANCE WITH VOL. 1, CHAPTER 12, OF THE HOWARD COUNTY DESIGN MANUAL, STORM DRAINAGE.
- ALL DISTURBED AREAS MUST BE STABILIZED WITHIN THE TIME PERIOD SPECIFIED ABOVE IN ACCORDANCE WITH THE 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR PERMANENT SEEDING (SEC. 51), SOD (SEC. 54), TEMPORARY SEEDING (SEC. 50) AND MULCHING (SEC. 52). TEMPORARY STABILIZATION WITH MULCH ALONE CAN ONLY BE DONE WHEN RECOMMENDED SEEDING DATES DO NOT ALLOW FOR PROPER GERMINATION AND ESTABLISHMENT OF GRASSES.
- ALL SEDIMENT CONTROL STRUCTURES ARE TO REMAIN IN PLACE AND ARE TO BE MAINTAINED IN OPERATIVE CONDITION UNTIL PERMISSION FOR THEIR REMOVAL HAS BEEN OBTAINED FROM THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR.
- SITE ANALYSIS:
 

TOTAL AREA OF SITE	28.8	ACRES
AREA DISTURBED	2.0	ACRES
AREA TO BE ROOFED OR PAVED	0.0	ACRES
AREA TO BE VEGETATIVELY STABILIZED	28.8	ACRES
TOTAL CUT	3,540	CU.YDS.
TOTAL FILL	2,020	CU.YDS.
OFF SITE WASTE/BORROW AREA LOCATION	6,520	CU. YDS.
- ANY SEDIMENT CONTROL PRACTICE WHICH ID DISTURBED BY GRADING ACTIVITY FOR PLACEMENT OF UTILITIES MUST BE PREPARED ON THE SAME DAY OF DISTURBANCE.

FOR EROSION AND SEDIMENT CONTROL ONLY


APPROVED: DEPARTMENT OF PLANNING AND ZONING

Signature: *[Signature]* Date: *11/15/02*

CHIEF, DEVELOPMENT ENGINEERING DIVISION MK

Signature: *[Signature]* Date: *11/21/02*

CHIEF, DIVISION OF LAND DEVELOPMENT



**AMT**  
A. MORTON THOMAS AND ASSOCIATES, INC.  
CONSULTING ENGINEERS  
12759 TWINBROOK PARKWAY, SUITE 200, ROCKVILLE MD 20852  
TEL: (301) 981-5545 FAX: (301) 981-6034  
AMT FILE # 98-153


Einhorn  
Yaffee  
Prescott

DES: B. WARNER									
DRN: S. ITANI									
CHK: B. WARNER									
DATE: 06/21/02	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK	APP			


APPLIED PHYSICS LABORATORY  
THE JOHNS HOPKINS UNIVERSITY - POND B  
PARCEL 1  
**EROSION & SEDIMENT NOTES AND DETAILS**  
TAX MAP 41 PARCEL 123  
ELECTION DISTRICT NO. 5  
HOWARD COUNTY, MARYLAND

SCALE AS SHOWN
SHEET ES-4
SHEET 18 OF 20

F-02-77



**SEDIMENT CONTROL**

( ) BY THE DEVELOPER:  
 I CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT.  
 I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

*[Signature]* *[Signature]* *[Signature]*  
 SIGNATURE OF DEVELOPER SIGNATURE OF DEVELOPER SIGNATURE OF DEVELOPER  
 PRINT NAME BELOW SIGNATURE DATE DATE DATE

( ) BY THE ENGINEER:  
 I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

*[Signature]* *[Signature]*  
 SIGNATURE OF ENGINEER SIGNATURE OF ENGINEER  
 DATE DATE

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

USDA-NATURAL RESOURCES CONSERVATION SERVICE DATE *[Signature]*

THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

HOWARD SOIL CONSERVATION DISTRICT DATE

**LEGEND**

- NON-PLANTABLE AREA
- LIMITS OF SWM AREA
- PROP. SOD AREA
- PROP. SHADED TREE
- PROP. EVERGREEN TREE

**GRAPHIC SCALE**

( IN FEET )  
 1 inch = 30 ft.

**NORTH**

APPROVED: DEPARTMENT OF PLANNING AND ZONING

*[Signature]* *[Signature]*  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION MK DATE 11/15/02  
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE 11/21/02



<b>A. MORTON THOMAS AND ASSOCIATES, INC.</b> CONSULTING ENGINEERS 12750 TWENBROOK PARKWAY, SUITE 200, ROCKVILLE MD 20852 TEL (301) 581-2545 FAX (301) 581-0814 AMT FILE # 98-153		DES: N. HAINES								APPLIED PHYSICS LABORATORY THE JOHNS HOPKINS UNIVERSITY PARCEL 1 <b>LANDSCAPE PLAN</b> TAX MAP 41 PARCEL 123 ELECTION DISTRICT NO. 5 HOWARD COUNTY, MARYLAND	SCALE AS SHOWN
		DRN: M. NORTON									SHEET L-1
		CHK: N. HAINES									SHEET 19 OF 20
		DATE: 06/21/02	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK	APP			

LANDSCAPING NOTES



- This plan is for landscaping measures only.
- All contractors performing work on this site shall notify "Miss Utility" 48 hours prior to any construction or grading by calling 1-800-257-7777 for the location of all utilities.
- The contractors performing work on the site are responsible for protecting existing plantings during construction.
- The landscape contractor shall perform work and the plantings shall conform with the "Landscape Specification Guidelines For The Baltimore-Washington Metropolitan Areas", latest edition.
- The landscape contractor is to verify all plant quantities and availability and notify landscape architect or owner if there are any problems prior to bidding.
- Sod or seed areas as directed by owner for all disturbed areas to be stabilized that are not landscaped or covered.
- For tree pruning and care methods please refer to the National Arborist Standards, latest edition.
- The owner, A. Morton Thomas & Associates, Howard Co. DPZ, and Howard Co. SCD are not responsible for any consequences resulting from any deviations or substitutions to these plans.
- Financial surety for the required landscaping has been posted as part of the DPW developer's agreement in the amount of \$12,150.00 for 25 shade trees, 31 evergreen trees, and 0 shrubs.

SEQUENCE OF CONSTRUCTION FOR LANDSCAPING

- Flag limits of construction and stake out sediment control measures.
- Arrange pre-construction meeting with the owner, Inspector, and landscape architect at (301)881-2545.
- Call "Miss Utility" at 1-800-257-7777 prior to any work for the location of all utilities.
- Adjust existing sediment control measures for landscape construction as required.
- After site construction has been completed implement site landscaping as shown on plan.
- FINANCIAL SURETY FOR THE REQUIRED LANDSCAPING HAS BEEN POSTED AS PART OF THE DPW DEVELOPER'S AGREEMENT IN THE AMOUNT OF \$12,150.00 FOR 25 SHADE TREES, 31 EVERGREEN TREES, AND 0 SHRUBS.
- After site has been stabilized and all construction has been completed, remove sediment control measures upon inspectors approval.

PROPOSED PLANT MATERIALS

KEY	BOTANICAL NAME	COMMON NAME	SIZE	FORM	SPACING	QUANTITY
<b>SHADE TREES</b>						
AR	ACER RUBRUM	RED MAPLE	2.5" CAL.	B&B	SHOWN	6
FG	FAGUS GRANDIFOLIA	AMERICAN BEECH	2.5" CAL.	B&B	SHOWN	5
FP	FRAXINUS PENNSYLVANICA	GREEN ASH	2.5" CAL.	B&B	SHOWN	5
LS	LIQUIDAMBER STYRACIFLUA	SWEETGUM	2.5" CAL.	B&B	SHOWN	4
QR	QUERCUS RUBRA	RED OAK	2.5" CAL.	B&B	SHOWN	5
<b>EVERGREEN TREES</b>						
IO	ILEX OPACA	AMERICAN HOLLY	7' HGT.	B&B	SHOWN	9
PA	PICEA ABIES	NORWAY SPRUCE	7' HGT.	B&B	SHOWN	4
PP	PICEA PUNGENS	COLORADO SPRUCE	7' HGT.	B&B	SHOWN	6
PS	PINUS STROBUS	WHITE PINE	2" CAL.	B&B	SHOWN	12
<b>STABILIZATION</b>						
SEED		MDSHA CERTIFIED K31 SEED	-	40LBS./ACRE	SHOWN	104
SOD		MDSHA CERTIFIED SOD	-	SY	SHOWN	2,165



SCHEDULE D  
STORMWATER MANAGEMENT AREA LANDSCAPING

LINEAR FEET OF PERIMETER	1,210
NUMBER OF TREES REQUIRED	
SHADE TREES	25
EVERGREEN TREES	31
CREDIT FOR EXISTING VEGETATION (NO, YES AND %)	NO
CREDIT FOR OTHER LANDSCAPING (NO, YES AND %)	NO
NUMBER OF TREES PROVIDED	
SHADE TREES	25
EVERGREEN TREES	31
OTHER TREES (2:1 SUBSTITUTION)	0

**SEDIMENT CONTROL**

( ) BY THE DEVELOPER:  
I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Signature of Developer: *[Signature]* Date: *8/6/02*

Signature of Engineer: *[Signature]* Date: *8/6/02*

( ) THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

USDA-NATURAL RESOURCES CONSERVATION SERVICE DATE: *[Signature]*

( ) THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

HOWARD SOIL CONSERVATION DISTRICT DATE: *[Signature]*

APPROVED: DEPARTMENT OF PLANNING AND ZONING

*[Signature]* DATE: *11/15/02*


CHIEF, DEVELOPMENT ENGINEERING DIVISION MK

*[Signature]* DATE: *11/21/02*

CHIEF, DIVISION OF LAND DEVELOPMENT



DES: N. HAINES									
DRN: M. NORTON									
CHK: N. HAINES									
DATE: 06/21/02	DATE	REVISIONS AND RECORD OF ISSUE	NO.	BY	CK	APP			



APPLIED PHYSICS LABORATORY  
THE JOHNS HOPKINS UNIVERSITY  
PARCEL 1  
**LANDSCAPE NOTES  
& DETAILS PLAN**  
TAX MAP 41 PARCEL 123  
ELECTION DISTRICT NO. 5  
HOWARD COUNTY, MARYLAND

SCALE AS SHOWN  
SHEET L-2  
SHEET 20 OF 20