

GENERAL NOTES:

- All construction shall be in accordance with the latest standards and specifications of Howard County plus MSHA standards and specifications.
- The contractor shall notify the Department of Public Works/Bureau of Engineering Construction Inspection Division at (410) 313-1880 at least (5) working days prior to the start of work.
- The contractor shall notify "Miss Utility" at 1-800-257-7777 at least 48 hours prior to any excavation work being done.
- Traffic control devices, markings and signing shall be in accordance with the latest edition of the Manual of Uniform Traffic Control Devices (MUTCD). All street and regulatory signs shall be in place prior to the placement of any asphalt.
- Street light placement and the type of fixture and pole shall be in accordance with the Howard County Design Manual, Volume III (1993) and as modified by "Guidelines for Street Lights in Residential Developments (June 1993)."

NOTE: A minimum spacing of 20' shall be maintained between any street light and any tree.
- The existing topography is taken from field run survey with two foot contour intervals prepared by CLSI, Inc., dated December 1999.
- The coordinates shown herein are based upon the Howard County Geodetic Control, which is based upon the Maryland State Plane Coordinate System. Howard County Monument Nos. 16 1A and 16 1B were used for this project.
- Water is public, Contract No. 24-3847-D and the drainage area is Little Patuxent.
- Sewer is public, Contract No. 24-3847-D and the drainage area is LPN GMC.
- The stormwater management facility will be an extended detention pond to be owned and maintained by the H.O.A.
- Existing utilities are based on Howard County contract drawings, Nos. 24-1541-D.
- There is no floodplain on this site.
- The wetlands delineation study for this project was prepared by CLSI, Inc., dated October 30, 1998 and was approved on May 25, 2000.
- The traffic study for this project was prepared by Lee Cunningham and Associates, Inc., dated January, 1999 and was approved on February 6, 2001.
- Project background information:
 - Zoning: R-20
 - Gross Area of Tract: 13.31 Ac
 - Net Area of Tract: 13.31 Ac
 - Area of Proposed Lots/Parcels: 7.59 Ac
 - Area of Proposed R/W: 1.29 AC
 - Number of Proposed Lots: 22 Buildable Lots, 3 Open Spaces, 1 SWM Parcel A
 - Open Space Required: 3.96 Ac
 - Open Space Provided: 4.41 Ac
 - Preliminary/Equivalency Sketch Plan #SP-00-06
- This plan assumes that stormwater management for adjacent properties draining to this site will be provided on adjacent properties at the time of development. This plan provides for conveyance only of offsite stormwater flows.
- This plan is not subject to the Zoning Regulations, as amended by Council Bill 90-2001.
- The developer will be required to construct the 4' wide pathway within the open space lot 24 and continue the construction through the adjacent open space lot 163 to connect to the existing pathway. Fee simple transfer of lot 24 to Howard County will be provided.
- The developer will be responsible for the construction to connect the new pathway to the existing pathway within open space lot 163.
- The developer must enter into a Right-of-Entry agreement for the construction of the pathway within open space lot 163.
- The Landscape Surety is \$24000.00
- See note this sheet for Forest Conservation Obligation
- 95% compaction in fill areas required per AASHTO T 180.

FINAL ROAD CONSTRUCTION, GRADING AND STORMWATER MANAGEMENT PLANS

CARLEE MANOR


LOTS 1 THRU 26 AND NON-BUILDABLE PARCEL 'A'
ZONED R-20

TAX MAP NO. 16 PARCEL NO. 123

2ND ELECTION DISTRICT * HOWARD COUNTY, MD.

OWNER
TRUST U/A CARLEE JONES
BRANCH BANKING
4 TRUST CO., TRUSTEE
C/O WILLIAM J. GERING
P.O. BOX 1100
WESTMINSTER, MD 21158
(410) 857-3430

DEVELOPER
C.J. PROPERTY LLC
10753 BIRMINGHAM WAY
WOODSTOCK, MD. 21163
(410) 750-1200




LOCATION PLAN

SCALE: 1" = 200'

FOREST CONSERVATION NOTE

THE FOREST CONSERVATION REQUIREMENT FOR THIS PROJECT WILL REQUIRE 2.00 ACRES OF NEW FOREST PLANTINGS (AFFORESTATION). THIS REQUIREMENT WILL BE PROVIDED ON-SITE AS SHOWN ON THE FOREST CONSERVATION PLAN (SHEETS 21 & 22). SURETY WILL BE PROVIDED TO HOWARD COUNTY IN THE FORM OF AN APPROPRIATE BOND AS PART OF THE PUBLIC WORKS AGREEMENT IN THE AMOUNT OF \$0.50 PER SQUARE FOOT FOR A TOTAL OF \$43560.00.



BENCHMARK LOCATION

SCALE: 1" = 600'

HOWARD COUNTY SURVEY CONTROL

- 16 1A- ELEV. 463.67'
HOWARD COUNTY MONUMENT @ SURFACE APPROXIMATELY 11' SOUTH OF EDGE OF WESTBOUND LANE (WBL) IN MEDIAN OPPOSITE EXISTING RESIDENCE ON NORTH SIDE OF WBL. APPROXIMATELY 135' WEST OF EXISTING "CEMETERY LAND" SIGN ON NORTH EDGE OF E.B.L.
- 16 1B- ELEV. 470.58'
HOWARD COUNTY MONUMENT @ SURFACE APPROXIMATELY 11.5' SOUTH OF EDGE OF WESTBOUND LANE (WBL) IN MEDIAN OPPOSITE EXISTING GUARDRAIL ON NORTH SIDE OF WBL. APPROXIMATELY 0.8 MI EAST OF MARRIOTTVILLE ROAD.

BENCHMARKS:

B.M.#1 - REBAR & CAP #6
N 589049.7820, E 134843.245
EL. = 488.21

B.M.#2 - REBAR & CAP #8
N 589211.5754, E 1349364.4132
EL. = 452.54



Carroll Land Services
Incorporated

Engineers * Surveyors
Land Development Consultants
Landscape Architects * Environmental Specialists
439 East Main Street Westminster, MD 21157-5539
(410) 876-2017 FAX (410) 876-0009

STREET LIGHT SCHEDULE

DWG. NO.	STREET NAME	STATION	OFFSET	FIXTURE/POLE TYPE	COMMENTS
2 OF 22	CARLEE RUN COURT	0+20	25'RT	100 WATT HPS VAPOR PREMIER	
2 OF 22	CARLEE RUN COURT	2+50	15'RT	COLONIAL POST TOP FIXTURE	
2 OF 22	CARLEE RUN COURT	4+23	15'RT	MOUNTED ON A 14' BLACK FIBERGLASS POLE	
3 OF 22	CARLEE RUN COURT	7+45	15'RT		
3 OF 22	CARLEE RUN COURT	L.P. 2+75	3'LT		

LIST OF DRAWINGS


- TITLE SHEET
- ROAD PLAN AND PROFILE: CARLEE RUN CT. STA. 0+00.00 TO 5+75
- ROAD PLAN AND PROFILE: CARLEE RUN CT. STA. 5+75 TO 12+23.87
- GRADING PLAN
- SEDIMENT CONTROL PLAN
- SEDIMENT BASIN/TEMPORARY SWM PLAN
- SEDIMENT BASIN/TEMPORARY SWM PROFILES AND NOTES
- SEDIMENT BASIN/TEMPORARY SWM DETAILS
- SEDIMENT CONTROL NOTES AND DETAILS
- SEDIMENT CONTROL NOTES AND DETAILS
- STORM DRAIN DRAINAGE AREA MAP
- STORM DRAIN PROFILES
- STORM DRAIN PROFILES
- STORMWATER MANAGEMENT PLAN
- STORMWATER MANAGEMENT PROFILES AND NOTES
- STORMWATER MANAGEMENT PROFILES AND NOTES
- STORMWATER MANAGEMENT DETAILS
- SWM DRAINAGE AREA MAP EXISTING CONDITIONS
- SWM DRAINAGE AREA MAP PROPOSED CONDITIONS.
- STREET TREE AND LANDSCAPE PLAN
- FINAL FOREST CONSERVATION PLAN
- FINAL FOREST CONSERVATION NOTES
- RETAINING WALL DETAILS
- RETAINING WALL DETAILS

APPROVED
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Andrew M. Danke
CHIEF, BUREAU OF HIGHWAYS #3
DATE: 2-25-03

APPROVED
HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING
Cindy Hamilton
CHIEF, DIVISION OF LAND DEVELOPMENT #8
DATE: 3/4/03
Alfred Hamard
CHIEF, DEVELOPMENT ENGINEERING DIVISION #10
DATE: 2/28/03


FINAL ROAD CONSTRUCTION, GRADING AND STORMWATER MANAGEMENT PLANS

CARLEE MANOR
LOTS 1 THRU 26 AND NON-BUILDABLE PARCEL 'A'
ZONED: R-20
TAX MAP NO. 16, PARCEL NO. 123
2ND ELECTION DISTRICT * HOWARD COUNTY, MD.




OWNER
TRUST U/A CARLEE JONES
BRANCH BANKING
4 TRUST CO., TRUSTEE
C/O WILLIAM J. GERING
P.O. BOX 1100
WESTMINSTER, MD 21158
410-857-3430
DEVELOPER
C.J. PROPERTY LLC
10753 BIRMINGHAM WAY
WOODSTOCK, MD. 21163
410-750-1200

DATE	REVISIONS	DATE: JAN, 2003
		FILE NO: F--02-91
		JOB NO: 91230A
		SHEET: 1 OF 24




CENTERLINE CURVE DATA


Ref #	RADIUS	ARC	DELTA	TAN	CHORD BEARING	CHORD LENGTH
C1	150.00	221.00	86°42'21"	141.62	S 94°45'02" E	209.95



TYPICAL SECTION NTS
CARLEE RUN COURT
STA. 0+42.50 TO STA. 1+44.40
 PUBLIC ACCESS STREET
 DESIGN SPEED - 25 MPH



CONCRETE CURB AND GUTTER TRANSITION
 (PER STANDARD DETAIL R3-02 DMV IV)
 NOT TO SCALE



PAVING SECTION P-2



FOR STREET TREE LAYOUT AND DETAILS, SEE THE STREET TREE AND LANDSCAPE PLAN, SHEET 20.

NOTE: PROVIDE A 4' TRANSITION FROM INLET TO MODIFIED CURB AND GUTTER ON EITHER SIDE OF INLET PER STANDARD DETAIL R3-02 DMV IV. SEE DETAIL THIS SHEET

PLAN
 SCALE: 1" = 50'

- LEGEND**
- * STREET LIGHTS
 - △ STREET SIGN
 - STREET SIGN TYPE

NOTE: UTILITY BOXES MAY NOT BE LOCATED WITHIN THE OPEN SPACE ACCESS STRIP.




FILLET DETAILS

SCALE:
 HORIZ. 1" = 20'
 VERT. 1" = 2'

OWNER
 TRUST U/A CARLEE JONES
 BRANCH BANKING
 & TRUST CO., TRUSTEE
 C/O WILLIAM J. GERING
 P.O. BOX 1100
 WESTMINSTER, MD 21158
 410-857-3430

DEVELOPER
 C.J. PROPERTY L.L.C.
 10753 BIRMINGHAM WAY
 WOODSTOCK, MD. 21163
 410-750-1200



CARLEE RUN COURT
 PUBLIC ACCESS STREET
 DESIGN SPEED = 25 M.P.H.

PROFILE
 SCALE:
 HORIZ. 1" = 50'
 VERT. 1" = 5'

- LEGEND**
- - - EX GROUND AT MBL LEFT
 - - - EX GROUND AT MBL RIGHT

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Andrew M. Quaker
 CHIEF, BUREAU OF HIGHWAYS
 DATE: 2-25-03

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Andy Henth
 CHIEF, DIVISION OF LAND DEVELOPMENT
 DATE: 3/4/03

Chris Damann
 CHIEF, DEVELOPMENT ENGINEERING DIVISION
 DATE: 2/18/03


ROAD PLAN & PROFILE
CARLEE RUN COURT
 & STA. 0+00.00 TO STA. 5+15
CARLEE MANOR
 LOTS 1 THROUGH 26 AND
 NON-BUILDABLE PARCEL "A"
 TAX MAP 17, GRID 19, PARCEL 129
 2 nd. ELECTION DISTRICT HOWARD COUNTY, MARYLAND



Date	Revisions	Drawn By: BM
		Designed By: A.JD/LSD
		Reviewed By: A.JD/ALH
		Date: JAN, 2003
		Scale: 1"=50'
		Job No: 91230A
		Sheet: 2 OF 24

CAD Drawing File Name: g:\17230\dm\const\resdplans\02\carlee1.dgn


02-15-11 8:02:11 LP: HD 2018101301000000



CENTERLINE CURVE DATA

Ref #	RADIUS	ARC	DELTA	TAN	CHORD BEARING	CHORD LENGTH
C2	106.37	69.92	37°34'44"	36.28	S 59°16'24" E	66.67

CURVE DESIGNATED THIS: CXX



CUL-DE-SAC CURVE DATA

Ref #	RADIUS	ARC	DELTA	TAN	CHORD BEARING	CHORD LENGTH
C1	40.00	178.28	255°14'24"	-	S 44°33'28" W	63.33
C2	35.00	46.01	75°14'24"	27.01	N 40°26'31" W	42.77


CURVE DESIGNATED THIS: CXX

PLAN
SCALE: 1"=50'

- LEGEND
- * STREET LIGHTS
 - △ STREET SIGN
 - STREET SIGN TYPE

NOTE: UTILITY BOXES MAY NOT BE LOCATED WITHIN THE OPEN SPACE ACCESS STRIP.

CARLEE RUN COURT CUL-DE-SAC DETAIL
SCALE: 1"=30'



TYPICAL SECTION NTS

CARLEE RUN COURT
STA. 0+42.50 TO STA. 11+44.40

PAVING SECTION P-2



OWNER
TRUST W/A CARLEE JONES
BRANCH BANKING
& TRUST CO., TRUSTEE
C/O WILLIAM J. GERING
P.O. BOX 1100
WESTMINSTER, MD 21158
410-857-3430

DEVELOPER
C.J. PROPERTY L.L.C.
10753 BIRMINGHAM WAY
WOODSTOCK, MD 21163
410-750-1200

FOR STREET TREE LAYOUT AND DETAILS, SEE THE STREET TREE AND LANDSCAPE PLAN, SHEET 20.

NOTE: PROVIDE A 4' TRANSITION FROM INLET TO MODIFIED CURB & GUTTER ON EITHER SIDE OF INLET. SEE DETAIL SHEET 2

NOTE: UTILITY BOXES MAY NOT BE LOCATED WITHIN THE OPEN SPACE ACCESS STRIP



APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
William M. Donk
CHIEF, BUREAU OF HIGHWAYS
2-25-03 DATE

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
David Hamilton
CHIEF, DIVISION OF LAND DEVELOPMENT
3/4/03 DATE


John D. ...
CHIEF, DEVELOPMENT ENGINEERING DIVISION
2/20/10 DATE

ROAD PLAN & PROFILE
CARLEE RUN COURT
STA. 5+75.00 TO STA. 12+23.87
CARLEE MANOR
LOTS 1 THROUGH 26 AND
NON-BUILDABLE PARCEL "A"
TAX MAP 17, GRID 19, PARCEL 123
2 nd. ELECTION DISTRICT HOWARD COUNTY, MARYLAND



Date	Revisions	Drawn By: BM pct
		Designed By: A.JD/LGD
		Reviewed By: A.JD/ALH
		Date: JAN, 2003
		Scale: 1"=50'
		Job No: 91230A
		Sheet: 3 OF 24

CAD Drawing File Name: g:\17230\dwg\const\resdplans\3\carlee.dgn



OWNER
 TRUST U/A CARLEE JONES
 BRANCH BANKING
 & TRUST CO., TRUSTEE
 C/O WILLIAM J. GERING
 P.O. BOX 1100
 WESTMINSTER, MD 21153
 410-857-3430

DEVELOPER
 C.J. PROPERTY LLC.
 10753 BIRMINGHAM WAY
 WOODSTOCK, MD. 21163
 410-750-1200

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Andrew M. Powell
 CHIEF, BUREAU OF HIGHWAYS 2-25-09 DATE

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Andy Hamrick
 CHIEF, DIVISION OF LAND DEVELOPMENT 3/4/09 DATE

John P. ...
 CHIEF, DEVELOPMENT ENGINEERING DIVISION 2/16/09 DATE

GRADING PLAN
CARLEE MANOR
 LOTS 1 THROUGH 26 AND
 NON-BUILDABLE PARCEL "A"
 TAX MAP 16, PARCEL 123
 2 nd. ELECTION DISTRICT HOWARD COUNTY, MARYLAND

CLSI
 Carroll Land Services
 Incorporated
 Engineers • Surveyors • Land Development Consultants
 Landscape Architects • Environmental Specialists
 439 East Main Street Westminster, MD 21157-5539
 (410) 876-2017 FAX (410) 876-0009

Date	Revisions	Drawn By: BM/SNC
2/16/09		Designed By: AJD/AR
		Reviewed By: AJD/ALH
		Date: JAN, 2009
		Scale: 1"=50'
		Job No. 17230A
		Sheet: 4 OF 24

NOTE:
 ALL ONSITE EXISTING
 STRUCTURES ARE TO BE
 RAZED AND REMOVED

DEVELOPER'S CERTIFICATE
 I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT AND EROSION CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. (ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.)

Alfred L. Mansard
 DATE: 1/16/09

ENGINEER'S CERTIFICATE
 I HEREBY CERTIFY THAT THIS PLAN FOR SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.


Alfred L. Mansard
 DATE: 1/16/09
 PROFESSIONAL ENGINEER REG. NO. 28446

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.



USDA - NATURAL RESOURCES CONSERVATION SERVICE
Myra L...
 DATE: 2/16/09

THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEETS THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

John P. ...
 DATE: 2/16/09
 HOWARD SOIL CONSERVATION DISTRICT



CAD Drawing File Name: g:\17230\dwg\const\resdplans\04\grade.dgn



SEQUENCE OF CONSTRUCTION

1. OBTAIN A GRADING PERMIT (1 DAY)
2. INSTALL ALL SEDIMENT CONTROLS AS SHOWN ON PLAN IN ACCORDANCE WITH DETAILS. CONSTRUCT SEDIMENT BASIN IN ACCORDANCE WITH STORMWATER MANAGEMENT POND SEQUENCE OF CONSTRUCTION SHEET 15 OF 24 AND PLANS AND MODIFY PER SEDIMENT BASIN PLANS. NOTE THAT SUPER SILT FENCE IS TO BE INSTALLED BELOW BASIN/POND PRIOR TO CONSTRUCTION (3 WEEKS)
3. WITH PRIOR PERMISSION OF THE SEDIMENT CONTROL INSPECTOR MASS GRADE SITE. STABILIZE NON-ROAD AREAS PER SEEDING NOTES. ALL AREAS OF CONCENTRATED FLOW (DOWNSPOUTS, SHALES, DITCHES ETC. SHALL RECEIVE EROSION CONTROL MATTING (1 MONTH)
4. GRADE FOR ROAD INSTALLATION (1 WEEK)
5. INSTALL UTILITIES. INSTALL INLET PROTECTION TO REDUCE SEDIMENT BUILD-UP IN STORM DRAIN SYSTEM (3 WEEKS)
6. INSTALL CURB AND GUTTER (3 DAYS)
7. INSTALL ROAD SUB-BASE (3 DAYS)
8. ONCE THE SITE IS PERMANENTLY STABILIZED AND PERMISSION IS GRANTED BY THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR, CONVERT SEDIMENT BASIN TO SWM POND. REMOVE ALL REMAINING SEDIMENT CONTROLS. FILL GRADE AND STABILIZE THOSE AREAS. PAVE ALL ROAD SURFACES (2 WEEKS)

NOTE:
BUILDING CONSTRUCTION MAY BEGIN AFTER STEP 8 WITH PERMISSION OF THE SEDIMENT CONTROL INSPECTOR. LOTS NOT SOLD OR CONSTRUCTED PRIOR TO REMOVAL OF SEDIMENT CONTROLS MUST PROVIDE THEIR OWN SEDIMENT CONTROLS ON A LOT-BY-LOT BASIS.

OWNER
TRUST U/A CARLEE JONES
BRANCH BANKING
& TRUST CO., TRUSTEE
C/O WILLIAM J. GERING
P.O. BOX 1100
WESTMINSTER, MD 21153
410-857-3430

DEVELOPER
C.J. PROPERTY L.L.C.
10753 BIRMINGHAM WAY
WOODSTOCK, MD. 21163
410-750-1200

APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Andrew M. Doyle
CHIEF, BUREAU OF HIGHWAYS
2-15-08 DATE

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Chris Korman
CHIEF, DIVISION OF LAND DEVELOPMENT
3/4/08 DATE

John P. ...
CHIEF, DEVELOPMENT ENGINEERING DIVISION
2/20/08 DATE

SEDIMENT CONTROL PLAN
CARLEE MANOR
LOTS 1 THROUGH 26 AND
NON-BUILDABLE PARCEL 'A'
TAX MAP 16, PARCEL 123
2 nd. ELECTION DISTRICT HOWARD COUNTY, MARYLAND

Date	Revisions	Drawn By: BM/SNC
		Designed By: AJD
		Reviewed By: AJD/ALH
		Date: JAN, 2003
		Scale: 1"=50'
		Job No. 47230A
		Sheet: 5 OF 24

LEGEND

	PROPOSED D.A. TO BASIN (9.09 AC)
	EXISTING D.A. TO BASIN (9.62 AC)
	SUPER SILT FENCE
	SILT FENCE
	EARTH DIKE
	MOUNTABLE BERM
	PIPE SLOPE DRAIN
	TEMPORARY SHALE
	GATION INFLOW PROTECTION
	LIMIT OF DISTURBANCE
	EXISTING ONSITE D.A. A-1 (7.48 AC) TO PROPERTY LINE FOR TEMP. STORM WATER MANAGEMENT
	INLET PROTECTION
	REMOVABLE PUMPING STATION

NOTE:
INSTALL PIPE SLOPE DRAIN UNTIL STORM DRAIN IS INSTALLED FROM I-10 TO E-2

NOTE:
WITH PERMISSION OF THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR SOME OR ALL INLET PROTECTION MAY BE DELETED.

DEVELOPER'S CERTIFICATE
I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT AND EROSION CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I/ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

John P. ...
DATE: 1/16/08

ENGINEER'S CERTIFICATE
I HEREBY CERTIFY THAT THIS PLAN FOR SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

Alfred L. Hensard
DATE: 1/16/08
PROFESSIONAL ENGINEER REG. NO. 23446

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.




USDA - NATURAL RESOURCES CONSERVATION SERVICE
John P. ...
DATE: 2/10/08

THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEETS THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

John P. ...
DATE: 2/10/08
HOWARD SOIL CONSERVATION DISTRICT

CAD Drawing File Name: g:\17290\dmn\const\resplans\0515cplan.dgn

CAD Drawing File Name: g:\17230\dwg\const\resplans\06\jascp\ind.dwg



EMBANKMENT CENTERLINE DATA

Ref #	Bearing	Distance
L1	S 28°36'48" W	180.50

OWNER
 TRUST U/A CARLEE JONES
 BRANCH BANKING
 & TRUST CO., TRUSTEE
 C/O WILLIAM J. GERING
 P.O. BOX 1100
 WESTMINSTER, MD 21158
 410-857-3430


DEVELOPER
 C.J. PROPERTY LLC
 10753 BIRMINGHAM WAY
 WOODSTOCK, MD 21163
 410-750-1200

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Richard M. Dwyer
 CHIEF, BUREAU OF HIGHWAYS
 2-25-03 DATE

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
David Hamrick
 CHIEF, DIVISION OF LAND DEVELOPMENT
 3/4/03 DATE

John Dammann
 CHIEF, DEVELOPMENT ENGINEERING DIVISION
 2/20/03 DATE

BASIN SCHEDULE:
 BASIN NUMBER : ONE
 EXISTING DRAINAGE AREA : 7.48 ACRES
 PROPOSED DRAINAGE AREA : 9.89 ACRES
 STORAGE REQUIRED : 35,604 FT³
 STORAGE PROVIDED : 62,852 FT³
 EMBANKMENT ELEVATION : 445.0
 WEIR CREST : (1 ST STAGE) 442.25'
 OUTLET ELEVATION : 439.0
 CLEANOUT ELEVATION : 439.0
 BOTTOM ELEVATION : 440.0
 BOTTOM DIMENSION : 180' x 130'
 Q_{EXIST}/Q_{PROP} : 3.9 cfs/ 2.7 cfs



NOTE:
 CONTRACTOR TO REFER TO STORMWATER MANAGEMENT CONSTRUCTION DRAWINGS FOR SEQUENCE OF CONSTRUCTION FOR SWM POND/SEDIMENT BASIN

DEVELOPER'S CERTIFICATE
 I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT AND EROSION CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN ON THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.
 ALFRED L. HENDERSON
 1/16/03 DATE
 PROFESSIONAL ENGINEER REG. NO. 29446

ENGINEER'S CERTIFICATE
 I HEREBY CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION.
 ALFRED L. HENDERSON
 1/16/03 DATE
 PROFESSIONAL ENGINEER REG. NO. 29446


THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEETS THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.
 USDA - NATURAL RESOURCES CONSERVATION SERVICE
 2/11/03 DATE
 THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.
 HOWARD SOIL CONSERVATION DISTRICT
 2/11/03 DATE

SEDIMENT BASIN AND TEMPORARY STORMWATER MANAGEMENT PLAN
CARLEE MANOR
 LOTS 1 THROUGH 26 AND NON-BUILDABLE PARCEL "A"
 TAX MAP 17, GRID 19, PARCEL 123
 2 nd. ELECTION DISTRICT HOWARD COUNTY, MARYLAND

CLSI
 Carroll Land Services Incorporated
 Engineers • Surveyors • Land Development Consultants
 Landscape Architects • Environmental Specialists
 439 East Main Street Westminster, MD 21157-5539
 (410) 876-2017 FAX (410) 876-0009

Professional Engineer Registration No. 29446


Date	Revisions	Drawn By: BM/SWC
		Designed By: A.JD/LSD
		Reviewed By: A.JD/ALH
		Date: JAN, 2003
		Scale: 1"=30'
		Job No: 47250A
		Sheet: 6 OF 24




NOTE:
CUTOFF & CORE MATERIAL
TO BE APPROVED BY
GEOTECHNICAL ENGINEER.

NOTE:
CORE AND CUT-OFF TRENCH
MATERIAL SHALL CONSIST OF
UNIFIED SOIL CLASSIFICATION
GC, SC, CH, OR CL AND BE
APPROVED BY THE GEOTECHNICAL
ENGINEER AND HOWARD COUNTY.


CUT-OFF TRENCH
NOT TO SCALE



**TYPICAL EMBANKMENT SECTION
SECTION 'B-B'**
SCALE: HORIZ. : 1" = 30'
VERT. : 1" = 5'



**PROFILE ALONG CENTERLINE
OF EMBANKMENT**
SCALE: HORIZ. : 1" = 30'
VERT. : 1" = 5'



PROFILE ALONG & OF WEIR WALL SPILLWAY
SCALE: HORIZ. : 1" = 30'
VERT. : 1" = 5'

OWNER
TRUST U/A CARLEE JONES
BRANCH BANKING
& TRUST CO., TRUSTEE
C/O WILLIAM J. GERING
P.O. BOX 1100
WESTMINSTER, MD 21158
410-857-3430

DEVELOPER
C.J. PROPERTY LLC
10753 BIRMINGHAM WAY
WOODSTOCK, MD 21163
410-750-1200

APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Andrew M. ... 2-25-03
CHIEF, BUREAU OF HIGHWAYS DATE


APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Chris ... 3/4/03
CHIEF, DIVISION OF LAND DEVELOPMENT DATE

John ... 2/18/03
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

**SEDIMENT BASIN AND TEMPORARY STORMWATER
MANAGEMENT PROFILES AND NOTES**

CARLEE MANOR

LOTS 1 THROUGH 26 AND
NON-BUILDABLE PARCEL "A"
TAX MAP 17, GRID 19, PARCEL 123
2 nd. ELECTION DISTRICT HOWARD COUNTY, MARYLAND



Carroll Land Services
INCORPORATED
Engineers • Surveyors • Land Development Consultants
Landscape Architects • Environmental Specialists
439 East Main Street Westminster, MD 21157-5539
(410) 876-2017 FAX (410) 876-0009

AS-BUILT CERTIFICATION

I HEREBY CERTIFY THAT THE FACILITY SHOWN ON THIS PLAN WAS CONSTRUCTED AS SHOWN ON THE "AS-BUILT" PLANS AND MEETS THE APPROVED PLANS AND SPECIFICATIONS.

SIGNATURE DATE

CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ON-SITE INSPECTIONS AND MATERIAL TESTS ARE THOSE INSPECTIONS AND TESTS DEEMED SUFFICIENT AN APPROPRIATE COMMONLY ACCEPTED ENGINEERING STANDARDS. CERTIFY DOES NOT MEAN OR IMPLY A GUARANTEE BY THE ENGINEER NOR DOES AN ENGINEER'S CERTIFICATION RELIEVE ANOTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING COMMONLY ACCEPTED INDUSTRY PRACTICES.

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEETS THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

USDA - NATURAL RESOURCES CONSERVATION SERVICE

THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE FOND WITHIN 30 DAYS OF COMPLETION.

HOWARD SOIL CONSERVATION DISTRICT

DEVELOPER'S CERTIFICATE
I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT AND EROSION CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE FOND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN ON THE FOND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

... 1/16/03
DATE

ENGINEER'S CERTIFICATE
I HEREBY CERTIFY THAT THIS PLAN FOR FOND CONSTRUCTION, SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE FOND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE FOND WITHIN 30 DAYS OF COMPLETION.

Alfred J. Hansard 1/16/03
ALFRED J. HANSARD, PROFESSIONAL ENGINEER REG. NO. 23446 DATE

DATE: 2/18/03
DATE: 3/4/03

Date	Revisions	Drawn By	JJM
		Designed By	AJD
		Reviewed By	AJD/ALH
		Date:	JAN, 2003
		Scale:	As Shown
		Job No.:	91230A
		Sheet:	7 OF 24

CAD Drawing File Name: g:\17290\dwg\const\resplans\07\accbasimpro.dwg

**HOWARD SOIL CONSERVATION DISTRICT
STANDARD SEDIMENT CONTROL NOTES**

- A minimum of 48 hours notice must be given to the Howard County Department of Inspections, Licenses and Permits, Sediment Control Division prior to the start of any construction (13-10555).
- All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the most current MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL and revisions thereto.
- Following initial soil disturbance or re-disturbance, permanent or temporary stabilization shall be completed within a 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all slopes greater than 3:1. 1/4 days as to all other disturbed or graded areas on the project site.
- All sediment traps/basins shown must be fenced and warning signs posted around their perimeter in accordance with Vol. 1, Chapter 12 of the HOWARD COUNTY DESIGN MANUAL, Storm Drainage.
- All disturbed areas must be stabilized within the time period specified above in accordance with the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL, for permanent seeding (Sec. 5.1), sod (Sec. 5.4), temporary seeding (Sec. 5.0) and mulching (Sec. 5.2). Temporary stabilization with mulch alone can only be done when recommended seeding dates do not allow for proper germination and establishment of grasses.
- All sediment control structures are to remain in place and be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.
- Site Analysis:
Total Area: 19.3 Acres
Area Disturbed: 11.30 Acres
Area to be roofed or paved: 2.54 Acres
Area to be vegetatively stabilized: 8.76 Acres
Total Cut: 42,800 Cu Yds.
Total Fill: 42,800 Cu Yds.
Offsite waste/borrow area location will be to a site with an approved sediment control plan and an approved open grading permit.
- Any sediment control practice, which is disturbed by grading activity for placement of utilities, must be repaired on the same day of disturbance.
- Additional sediment control must be provided, if deemed necessary by the Howard County Sediment Control Inspector.
- On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the inspection agency is made.
- Trenches for the construction of utilities is limited to three pipe lengths or that which shall be back-filled and stabilized by the end of each workday, whichever is shorter.

Rev. 9/99

Topsoil Notes
Construction and Material Specifications.
I. Topsoil salvaged from the existing site may be used provided that it meets the standards as set forth in these specifications. Typically, the depth of topsoil to be salvaged for a given soil type can be found in the representative soil profile section in the soil survey published by USDA-SCS in cooperation with Maryland Agricultural Experimental Station.

- Topsoil Specifications - Soil to be used as topsoil must meet the following:
I. Topsoil shall be a loam, sandy loam, silty loam, sandy clay loam, or loamy sand. Other soils may be used if recommended by an agronomist or soil scientist and approved by the appropriate approval authority. Regardless, topsoil shall not be a mixture of contrasting textured subsols and shall contain less than 5% by volume of cinders, stones, slag, coarse fragments, gravel, sticks, roots, trash, or other materials larger than 1" in diameter.
II. Topsoil must be free of plants or plant parts such as Bermuda grass, quack grass, Johnson grass, nutgrass, poison ivy, thistle, or others as specified.
III. Where the subsol is either highly acidic or composed of heavy clays, ground limestone shall be spread at the rate of 4-8 tons/acre (200-400 pounds per 1,000 square feet) prior to the placement of topsoil. Lime shall be distributed uniformly over designated areas and worked into the soil in conjunction with tillage operations as described in the following procedures.

II. For sites having disturbed areas under 5 acres:
I. Place topsoil (if required) and apply soil amendments as specified in 2.00 Vegetative Stabilization - Section I - Vegetative Stabilization Methods and Materials.

- For sites having disturbed areas over 5 acres:
I. On soil meeting Topsoil specifications, obtain test results dictating fertilizer and lime amendments required to bring the soil into compliance with the following:
Page 2
Topsoil Notes
a) pH for topsoil shall be between 6.0 and 7.5. If the tested soil demonstrates a pH of less than 6.0, sufficient lime shall be prescribed to raise the pH to 6.5 or higher.
b) Organic content of topsoil shall be not less than 1.5 percent by weight.
c) Topsoil having soluble salt content greater than 500 parts per million shall not be used.
d) No sod or seed shall be placed on soil which has been treated with soil sterilants or chemicals used for weed control until sufficient time has elapsed (1-4 days min) to permit dissipation of phytotoxic materials.
Note: Topsoil substitutes or amendments, as recommended by a qualified agronomist or soil scientist and approved by the appropriate approval authority, may be used in lieu of natural topsoil.

II. Place topsoil (if required) and apply soil amendments as specified in 2.00 Vegetative Stabilization - Section I - Vegetative Stabilization Methods and Materials.

V. Topsoil Application
I. When topsoiling, maintain needed erosion and sediment control practices such as diversions, grade stabilization structures, earth dikes, slope silt fence and sediment traps and basins.
II. Grades on the areas to be topsoiled, which have been previously established, shall be maintained, albeit 4"-8" higher in elevation.
III. Topsoil shall be uniformly distributed in a 4"-8" layer and lightly compacted to a minimum thickness of 4". Spreading shall be performed in such a manner that sodding or seeding can proceed with a minimum of additional soil.
IV. preparation and tillage. Any irregularities in the surface resulting from topsoiling or other operations shall be corrected in order to prevent the formation of depressions or water pockets.

Page 3
Topsoil Notes
V. Topsoil shall not be placed while the topsoil or subsol is in a frozen or muddy condition, when the subsol is excessively wet or in a condition that may otherwise be detrimental to proper grading and seeded preparation.
VI. Alternative for Permanent Seeding - Instead of applying the full amounts of lime and commercial fertilizer, composted sludge and amendments may be applied as specified below:
I. Composted Sludge Material for use as a soil conditioner for sites having disturbed areas over 5 acres shall be tested to prescribe amendments and for sites having disturbed areas under 5 acres shall conform to the following requirements:

- Composted sludge shall be supplied by, or originate from, a person or persons that are permitted (at the time of acquisition of the compost) by the Maryland Department of the Environment under COMAR 26.04.06.
- Composted sludge shall contain at least 1 percent nitrogen, 1.5 percent phosphorus, and 0.2 percent potassium and have a pH of 7.0 to 8.0. If compost does not meet these requirements, the appropriate constituents must be added to meet the requirements prior to use.
- Composted sludge shall be applied at a rate of 1 ton/1,000 square feet.
- Composted sludge shall be amended with a potassium fertilizer applied at the rate of 4 lb/1,000 square feet, and 1/3 the normal lime application rate.

STABILIZATION SPECIFICATIONS

TEMPORARY SEEDING NOTES

Scope: Planting short term (no more than 1 year) vegetation to temporarily stabilize any areas where soil disturbance has occurred, until the area can be permanently stabilized with vegetative or non-vegetative practices.

Standards: The following notes shall conform to the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL, published jointly by the Maryland Department of Environment - Water Management Administration, the National Resource Conservation Service, and the State Soil Conservation Committee.

- The seed bed shall be prepared by loosening the soil to a depth of 3 to 5 inches and incorporating the lime and fertilizer into this loosened layer of soil. See 6-20 Sec. 1-C.
- Fertilizer shall consist of a mixture of 10-10-10 and be applied at a rate of 600 lb per acre (15 lb per 1000 sq. ft.) and will meet the requirements in 6-20 Sec. 1-B.
- Lime shall be applied at a rate of 2 tons per acre (100 lb per 1000 sq. ft.) and shall meet the requirements in 6-20 Sec. 1-B.
- Seed tags shall be made available to the inspector to verify the type and rate of seed used. The seed must meet the requirements in 6-20 Sec. 1-C.
- Mulching will be applied immediately after seeding and will need to meet the requirements in 6-20 Sec. 1-F, G and H.
- Seeding mixtures shall be selected from or will be equal to those on Table 26.
- The following is one option, approved equals may be used.

Temporary Seeding Summary

No.	Species	Rate (lb/ac)	Seeding Dates	Seeding Depths
N/A	Kentucky-91	80	3/1 to 11/15	1"
	Annual Rye	20	3/1 to 11/15	1/4" - 1/2"

PERMANENT SEEDING NOTES

Scope: Planting permanent, long lived vegetative cover on graded and/or cleared areas and areas that have been in temporary vegetation for more than 1 year.

Standards: The following notes shall conform to the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL, published jointly by the Maryland Department of Environment - Water Management Administration, the National Resource Conservation Service, and the State Soil Conservation Committee.

- The seed bed shall be prepared by loosening the soil to a depth of 3 to 5 inches and incorporating the lime and fertilizer into this loosened layer of soil. See 6-20 Sec. 1-C.
- For sites over 5 ac, soil tests will be performed to determine the exact mixture and application rates for both lime and fertilizer. Soil tests will be prepared by the University of Maryland or a recognized commercial laboratory. If the existing soil does not meet the minimum conditions as stated in 6-20 Sec. 1-C-II, then topsoil will need to be obtained that meets these conditions and applied so as to meet the requirements in 6-21.
- For sites of 5 ac. or less of disturbance, the following fertilizer and lime rates shall apply:
4. Fertilizer shall consist of a mixture of 10-20-20 and be applied at the following rates:
N=40 lb per acre (2 lb per 1000 sq. ft.) P2O5=175 lb per acre (4 lb per 1000 sq. ft.) K2O=175 lb per acre (4 lb per 1000 sq. ft.) Fertilizer shall meet the requirements in 6-20 Sec. 1-B.
- Lime shall be applied at a rate of 2 tons per acre (100 lb per 1000 sq. ft.) and shall meet the requirements in 6-20 Sec. 1-B.
- Seed tags shall be made available to the inspector to verify the type and rate of seed used. The seed must meet the requirements in 6-20 Sec. 1-C.
- Mulching will be applied immediately after seeding and will need to meet the requirements in 6-20 Sec. 1-F, G & H.
- Refer to 6-20 Sec. 1-E for Methods of Seeding specifications.
- Refer to 6-20 Sec. 4 for Sod specifications.
- Refer to 6-20 Sec. 5 for Turfgrass Establishment specifications.
- Seeding mixtures shall be selected from or will be equal to those on Table 25.
- The following is one option, approved equals may be used.

Permanent Seeding Summary

N 10	P2O5 10	K2O 10	Lime	
Lime application rate - 2 tons/acre (100 lbs/1000 sq. ft.)				
Seed Mixture Hardness Zone 6B/7A (6-20 Figure 5)				
No.	Species	Rate (lb/ac)	Seeding Dates	Seeding Depths
N/A	Triple Fine Fescue	160	3/1 to 10/30	1"-2"
	Perennial Rye	40	3/1 to 10/30	1"-2"

Tracking notes

On areas where the slope is 3:1 or steeper and the height is 8' or greater, contractor shall track the slope using cleared dozer prior to placing asphalt binder. Dozer shall run up-and-down so that clear marks are horizontal. Where tracking is required, it shall be done from existing grade level to finished grade level within the limits established by the 8' height criteria.

UTILITY CONSTRUCTION NOTES



- Place all excavated material on the high side of the trench.
- Only do as much work as can be done in one day so backfilling, final grading, and permanent stabilization can occur.
- Any sediment control measures disturbed by the utility construction will be repaired the same day.

STOCKPILE/TOPSOIL NOTES

- Stockpiling will not be allowed on any impervious area.
- All stockpiles left at the end of the day will need to be temporarily stabilized until they are again disturbed, unless they are within existing perimeter sediment controls.
- All stockpile areas shall be confined within perimeter controls. In the event that stockpile areas must be located outside disturbed areas, the location shall be as directed by the inspector in the field.

NOTE:
ALL SEDIMENT CONTROL MEASURES SHOWN HEREON ARE TEMPORARY UNLESS OTHERWISE NOTED.




BASIN DRAINDOWN SCHEMATION VERTICAL DRAIN-DOWN DEVICE



CONSTRUCTION SPECIFICATIONS

- PERFORATIONS IN THE DRAIN-DOWN DEVICE MAY NOT EXTEND INTO THE NET STORAGE.
- THE TOTAL AREA OF THE PERFORATIONS MUST BE GREATER THAN 2 TIMES THE AREA OF THE INTERNAL ORIFICE.
- THE PERFORATED PORTION OF THE DRAIN-DOWN DEVICE SHALL BE WRAPPED WITH 1/2" HARDWARE CLOTH AND GEOTEXTILE FABRIC. THE GEOTEXTILE FABRIC SHALL MEET THE SPECIFICATIONS FOR GEOTEXTILE CLASS E.
- PROVIDE SUPPORT OF DRAIN-DOWN DEVICE TO PREVENT SAGGING AND FLOATION. AN ACCEPTABLE PREVENTATIVE MEASURE IS TO STAKE BOTH SIDES OF DRAIN-DOWN DEVICE WITH 1" STEEL ANGLE OR 2" BY 2" SQUARE OR 2" ROUND WOODEN POSTS SET 9" MINIMUM INTO THE GROUND THEN JOINING THEM TO THE DEVICE BY WRAPPING WITH 12 GAUGE MINIMUM WIRE.

DETAIL 27 - ROCK OUTLET PROTECTION III



CONSTRUCTION SPECIFICATIONS

- THE SUBGRADE FOR THE FILTER, RIP-RAP OR GABION SHALL BE PREPARED TO THE REQUIRED LINES AND GRADES. ANY FILL REQUIRED IN THE SUBGRADE SHALL BE COMPACTED TO A DENSITY OF APPROXIMATELY THAT OF THE SURROUNDING UNDISTURBED MATERIAL.
- THE ROCK OR GRAVEL SHALL CONFORM TO THE SPECIFIED GRADING LIMITS WHEN INSTALLED RESPECTIVELY IN THE RIP-RAP OR FILTER.
- GEOTEXTILE SHALL BE PROTECTED FROM PUNCHING, CUTTING, OR TEARING. ANY DAMAGE OTHER THAN AN OCCASIONAL SMALL HOLE SHALL BE REPAIRED BY PLACING ANOTHER PIECE OF GEOTEXTILE OVER THE DAMAGED PART OR BY COMPLETELY REPLACING THE GEOTEXTILE. ALL OVERLAPS WHETHER FOR REPAIRS OR FOR JOINING TWO PIECES OF GEOTEXTILE SHALL BE A MINIMUM OF ONE FOOT.
- STONE FOR THE RIP-RAP OR GABION OUTLETS MAY BE PLACED BY EQUIPMENT. THEY SHALL BE CONSTRUCTED TO THE FULL COURSE THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO AVOID DISPLACEMENT OF UNDERLYING MATERIALS. THE STONE FOR RIP-RAP OR GABION OUTLETS SHALL BE DELIVERED AND PLACED IN A MANNER THAT WILL ENSURE THAT IT IS REASONABLY HOMOGENEOUS WITH THE SMALLER STONES AND SPALLS FILLING THE VOIDS BETWEEN THE LARGER STONES. RIP-RAP SHALL BE PLACED IN A MANNER TO PREVENT DAMAGE TO THE FILTER BLANKET OR GEOTEXTILE. HAND PLACEMENT WILL BE REQUIRED TO THE EXTENT NECESSARY TO PREVENT DAMAGE TO THE PERMANENT WORK.
- THE STONE SHALL BE PLACED SO THAT IT BLENDS IN WITH THE EXISTING GROUND. IF THE STONE IS PLACED TOO HIGH THEN THE FLOW WILL BE FORCED OUT OF THE CHANNEL AND SCOUR ADJACENT TO THE STONE WILL OCCUR.

DEVELOPER'S CERTIFICATE

I HEREBY CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT AND EROSION CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.


DATE: 11/6/03

ENGINEER'S CERTIFICATE

I HEREBY CERTIFY THAT THIS PLAN FOR SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

DATE: 11/6/03

DETAIL 23C - CURB INLET PROTECTION DETAIL




CONSTRUCTION SPECIFICATIONS

- MATERIALS**
1. WOODEN FRAME IS TO BE CONSTRUCTED OF 2" X 4" CONSTRUCTION GRADE LUMBER.
2. WIRE MESH MUST BE OF SUFFICIENT STRENGTH TO SUPPORT FILTER FABRIC AND STONE FOR CURB INLETS WITH WATER FULLY IMPOUNDED AGAINST IT.
3. FILTER CLOTH MUST BE OF A TYPE APPROVED FOR THIS PURPOSE, RESISTANT TO ULTRAVIOLET LIGHT WITH AN AVERAGE TENSILE STRENGTH SIZE 40 - 80 SEIVE, TO ALLOW SUFFICIENT PASSAGE OF WATER AND REMOVAL OF SEDIMENT.
4. WASHED STONE 3/4" TO 1 1/2" IN SIZE IS TO BE USED.

PROCEDURE

- ATTACH A CONTINUOUS PIECE OF WIRE MESH (30" MIN. WIDTH BY THROAT LENGTH PLUS 4") TO THE 2" X 4" WEIR (MEASURING THROAT LENGTH PLUS 2") AS SHOWN ON THE STANDARD DRAWINGS.
- PLACE A CONTINUOUS PIECE OF GEOTEXTILE CLASS E THE SAME DIMENSIONS AS THE WIRE MESH OVER THE WIRE MESH AND SECURELY ATTACH IT TO THE 2" X 4" WEIR.
- SECURELY NAIL THE 2" X 4" WEIR TO 4" LONG VERTICAL SPACERS TO BE LOCATED BETWEEN THE WEIR AND THE INLET FACE (MAX. 4' APART).
- PLACE THE ASSEMBLY AGAINST THE INLET THROAT AND NAIL (MINIMUM 2" LENGTHS OF 2" X 4" TO THE TOP OF THE WEIR AT SPACER LOCATIONS). THESE 2" X 4" ANCHORS SHALL EXTEND ACROSS THE INLET TOP AND BE HELD IN PLACE BY SANDBAGS OR ALTERNATE WEIGHT.
- THE ASSEMBLY SHALL BE PLACED SO THAT THE END SPACERS ARE A MINIMUM 1' BEYOND BOTH ENDS OF THE THROAT OPENING.
- FOR THE 1/2" X 1/2" WIRE MESH AND THE GEOTEXTILE FABRIC TO THE CONCRETE GUTTER AND AGAINST THE FACE OF THE CURB ON BOTH SIDES OF THE INLET. PLACE CLEAN 3/4" X 1 1/2" STONE OVER THE WIRE MESH AND GEOTEXTILE IN SUCH A MANNER TO PREVENT WATER FROM ENTERING THE INLET UNDER OR AROUND THE GEOTEXTILE.
- THIS TYPE OF PROTECTION MUST BE INSPECTED FREQUENTLY AND THE FILTER CLOTH AND STONE REPLACED WHEN CLOGGED WITH SEDIMENT.
- ASSURE THAT STORM FLOW DOES NOT BYPASS THE INLET BY INSTALLING A TEMPORARY EARTH OR ASPHALT DIKE TO DIRECT THE FLOW TO THE INLET.

DETAIL 20A - REMOVABLE PUMPING STATION



CONSTRUCTION SPECIFICATIONS


- THE OUTER PIPE SHOULD BE 48" DIA. OR SHALL, IN ANY CASE, BE AT LEAST 4" GREATER IN DIAMETER THAN THE OUTER PERFORATED PIPE. THE OUTER PERFORATED PIPE SHOULD BE WRAPPED WITH 1/2" HARDWARE CLOTH TO PREVENT BACKFILL MATERIAL FROM ENTERING THE PERFORATIONS.
- AFTER INSTALLING THE OUTER PIPE, BACKFILL AROUND OUTER PIPE WITH 2" AGGREGATE OR CLEAN GRAVEL.
- THE INSIDE STAND PIPE (CENTER PIPE) SHOULD BE CONSTRUCTED BY PERFORATING A CORRUGATED OR PVC PIPE BETWEEN 1 1/2" AND 3/8" IN DIAMETER. THE PERFORATIONS SHALL BE 1/2" X 1/2" SLOTS OR 1/2" DIA. HOLES. THE CENTER PIPE SHALL BE WRAPPED WITH 1/2" HARDWARE CLOTH FIRST, THEN WRAPPED AGAIN WITH GEOTEXTILE CLASS E.
- THE CENTER PIPE SHOULD EXTEND 12" TO 18" ABOVE THE ANTICIPATED WATER SURFACE ELEVATION OR RISER GREST ELEVATION WHEN DENATURING A BASIN.

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

USDA - NATURAL RESOURCE CONSERVATION SERVICE

DATE: 2/4/02

DETAIL 18 - SEDIMENT BASIN BAFFLES



BAFFLE DETAIL

- ATTACH A CONTINUOUS PIECE OF WIRE MESH (30" MIN. WIDTH BY THROAT LENGTH PLUS 4") TO THE 2" X 4" WEIR (MEASURING THROAT LENGTH PLUS 2") AS SHOWN ON THE STANDARD DRAWINGS.
- PLACE A CONTINUOUS PIECE OF GEOTEXTILE CLASS E THE SAME DIMENSIONS AS THE WIRE MESH OVER THE WIRE MESH AND SECURELY ATTACH IT TO THE 2" X 4" WEIR.
- SECURELY NAIL THE 2" X 4" WEIR TO 4" LONG VERTICAL SPACERS TO BE LOCATED BETWEEN THE WEIR AND THE INLET FACE (MAX. 4' APART).
- PLACE THE ASSEMBLY AGAINST THE INLET THROAT AND NAIL (MINIMUM 2" LENGTHS OF 2" X 4" TO THE TOP OF THE WEIR AT SPACER LOCATIONS). THESE 2" X 4" ANCHORS SHALL EXTEND ACROSS THE INLET TOP AND BE HELD IN PLACE BY SANDBAGS OR ALTERNATE WEIGHT.
- THE ASSEMBLY SHALL BE PLACED SO THAT THE END SPACERS ARE A MINIMUM 1' BEYOND BOTH ENDS OF THE THROAT OPENING.
- FOR THE 1/2" X 1/2" WIRE MESH AND THE GEOTEXTILE FABRIC TO THE CONCRETE GUTTER AND AGAINST THE FACE OF THE CURB ON BOTH SIDES OF THE INLET. PLACE CLEAN 3/4" X 1 1/2" STONE OVER THE WIRE MESH AND GEOTEXTILE IN SUCH A MANNER TO PREVENT WATER FROM ENTERING THE INLET UNDER OR AROUND THE GEOTEXTILE.
- THIS TYPE OF PROTECTION MUST BE INSPECTED FREQUENTLY AND THE FILTER CLOTH AND STONE REPLACED WHEN CLOGGED WITH SEDIMENT.
- ASSURE THAT STORM FLOW DOES NOT BYPASS THE INLET BY INSTALLING A TEMPORARY EARTH OR ASPHALT DIKE TO DIRECT THE FLOW TO THE INLET.

OWNER
TRUST U/A CARLEE JONES
BRANCH BANKING
& TRUST CO., TRUSTEE
C/O WILLIAM J. GERING
P.O. BOX 1100
WESTMINSTER, MD 21158
410-857-3430

DEVELOPER
C.J. PROPERTY LLC.
10753 BIRMINGHAM WAY
WOODSTOCK, MD. 21163
410-750-1200

APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Richard M. Douker
CHIEF, BUREAU OF HIGHWAYS
DATE: 2-25-02

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Cindy Herms
CHIEF, DIVISION OF LAND DEVELOPMENT
DATE: 2/4/02

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
John P. ...
CHIEF, DEVELOPMENT ENGINEERING DIVISION
DATE: 2/26/02


SEDIMENT CONTROL NOTES & DETAILS

CARLEE MANOR
LOTS 1 THROUGH 26 AND
NON-BUILDABLE PARCEL 'A'
TAX MAP 16, PARCEL 123
2 nd. ELECTION DISTRICT HOWARD COUNTY, MARYLAND



Date	Revisions	Drawn By: BM/SWC
2/4/02		Designed By: AJD
		Reviewed By: AJD/ALH
		Date: JAN, 2003
		Scale: N/A
		Job No: 91230A
		Sheet: 4 OF 24

CAD Drawing File Name: g:\1230\drain\cons\std\sediments\01\SCDD.DWG



TEMPORARY SWALE
NOT TO SCALE

CROSS SECTION

PLAN VIEW


FLOW CHANNEL STABILIZATION

GRADE 0.5% MIN. 1.0% MAX.

CONSTRUCTION SPECIFICATIONS

- SEED AND COVER WITH STRAW MULCH.
- SEED AND COVER WITH EROSION CONTROL MATTING OR LINE WITH 500.
- 4" - 1" STONE OR RECYCLED CONCRETE EQUIVALENT PRESSED INTO SOIL IN A MINIMUM 7" LAYER.

- ALL TEMPORARY SWALES SHALL HAVE UNINTERRUPTED POSITIVE GRADE TO AN OUTLET. SPOT ELEVATIONS MAY BE NECESSARY FOR GRADES LESS THAN 1%.
- RUNOFF DIVERTED FROM A DISTURBED AREA SHALL BE CONVEYED TO A SEDIMENT TRAPPING DEVICE.
- RUNOFF DIVERTED FROM AN UNDISTURBED AREA SHALL OUTLET DIRECTLY INTO AN UNDISTURBED STABILIZED AREA AT A NON-EROSIVE VELOCITY.
- ALL TREES, BRUSH, STUMPS, OBSTRUCTIONS, AND OTHER OBJECTIONAL MATERIAL SHALL BE REMOVED AND DISPOSED OF SO AS NOT TO INTERFERE WITH THE PROPER FUNCTIONING OF THE SWALE.
- THE SWALE SHALL BE EXCAVATED OR SHAPED TO LINE, GRADE AND CROSS SECTION AS REQUIRED TO MEET THE CRITERIA SPECIFIED HEREIN AND BE FREE OF BANK PROJECTIONS OR OTHER IRREGULARITIES WHICH WILL IMPED NORMAL FLOW.
- FILL, IF NECESSARY, SHALL BE COMPACTED BY EARTH MOVING EQUIPMENT.
- ALL EARTH REMOVED AND NOT NEEDED FOR CONSTRUCTION SHALL BE PLACED SO THAT IT WILL NOT INTERFERE WITH THE FUNCTIONING OF THE SWALE.
- INSPECTION AND MAINTENANCE MUST BE PROVIDED PERIODICALLY AND AFTER EACH RAIN EVENT.



DETAIL 33 - SUPER SILT FENCE


CONSTRUCTION SPECIFICATIONS

FENCING SHALL BE 42" IN HEIGHT AND CONSTRUCTED IN ACCORDANCE WITH THE LATEST MARYLAND STATE HIGHWAY DETAILS FOR CHAIN LINK FENCING. THE SPECIFICATION FOR A 6" FENCE SHALL BE USED, SUBSTITUTING 42" FABRIC AND 6" LENGTH POSTS.

- THE POLES DO NOT NEED TO SET IN CONCRETE.
- CHAIN LINK FENCE SHALL BE FASTENED SECURELY TO THE FENCE POSTS WITH WIRE TIES. THE LOWER TENSION WIRE, BRACE AND TRUSS RODS, DRIVE ANCHORS AND POST CAPS ARE NOT REQUIRED EXCEPT ON THE ENDS OF THE FENCE.
- FILTER CLOTH SHALL BE FASTENED SECURELY TO THE CHAIN LINK FENCE WITH TIES SPACED EVERY 24" AT THE TOP AND MID SECTION.
- FILTER CLOTH SHALL BE EMBEDDED A MINIMUM OF 6" INTO THE GROUND.
- WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THEY SHALL BE OVERLAPPED BY 6" AND FOLDED.
- MAINTENANCE SHALL BE PERFORMED AS NEEDED AND SILT BUILDUPS REMOVED WHEN 'BULGES' DEVELOP IN THE SILT FENCE, OR WHEN SILT REACHES 50% OF FENCE HEIGHT.
- FILTER CLOTH SHALL BE FASTENED SECURELY TO EACH FENCE POST WITH WIRE TIES OR STAPLES AT TOP AND MID SECTION AND SHALL MEET THE FOLLOWING REQUIREMENTS FOR GEOTEXTILE CLASS F:

DESIGN CRITERIA


TENSILE STRENGTH	50 LBS/(IN) (MIN)	TEST: MSMT 504
TENSILE MODULUS	20 LBS/(IN) (MIN)	TEST: MSMT 504
FLOW RATE	0.3 GAL/FT ² MINUTE (MAX)	TEST: MSMT 322
FILTERING EFFICIENCY	75% (MIN)	TEST: MSMT 322



DETAIL 24 - STABILIZED CONSTRUCTION ENTRANCE

CONSTRUCTION SPECIFICATIONS


- LENGTH - MINIMUM OF 50' (90' FOR SINGLE RESIDENCE LOT).
- WIDTH - 10' MINIMUM, SHOULD BE FLARED AT THE EXISTING ROAD TO PROVIDE A TURNING RADIUS.
- GEOTEXTILE FABRIC (FILTER CLOTH) SHALL BE PLACED OVER THE EXISTING GROUND PRIOR TO PLACING STONE. *THE PLAN APPROVAL AUTHORITY MAY NOT REQUIRE SINGLE FAMILY RESIDENCES TO USE GEOTEXTILE.
- STONE - CRUSHED AGGREGATE (2" TO 3") OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT SHALL BE PLACED AT LEAST 6" DEEP OVER THE LENGTH AND WIDTH OF THE ENTRANCE.
- SURFACE WATER - ALL SURFACE WATER FLOWING TO OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED THROUGH THE ENTRANCE, MAINTAINING POSITIVE DRAINAGE. PIPE INSTALLED THROUGH THE STABILIZED CONSTRUCTION ENTRANCE SHALL BE PROTECTED WITH A MOUNTABLE BERM WITH 5:1 SLOPES AND A MINIMUM OF 6" OF STONE OVER THE PIPE. PIPE HAS TO BE SIZED ACCORDING TO THE DRAINAGE. WHEN THE SCE IS LOCATED AT A HIGH SPOT AND HAS NO DRAINAGE TO CONVEY A PIPE WILL NOT BE NECESSARY. PIPE SHOULD BE SIZED ACCORDING TO THE AMOUNT OF RUNOFF TO BE CONVEYED. A 6" MINIMUM WILL BE REQUIRED.
- LOCATION - A STABILIZED CONSTRUCTION ENTRANCE SHALL BE LOCATED AT EVERY POINT WHERE CONSTRUCTION TRAFFIC ENTERS OR LEAVES A CONSTRUCTION SITE. VEHICLES LEAVING THE SITE MUST TRAVEL OVER THE ENTIRE LENGTH OF THE STABILIZED CONSTRUCTION ENTRANCE.



DETAIL 23A - STANDARD INLET PROTECTION

CONSTRUCTION SPECIFICATIONS

- EXCAVATE COMPLETELY AROUND THE INLET TO A DEPTH OF 18" BELOW THE NOTCH ELEVATION.
- DRIVE THE 2" X 4" CONSTRUCTION GRADE LUMBER POSTS 1" INTO THE GROUND AT EACH CORNER OF THE INLET. PLACE NAIL STRIPS BETWEEN THE POSTS ON THE ENDS OF THE INLET. ASSEMBLE THE TOP PORTION OF THE 2" X 4" FRAME USING THE OVERLAP JOINT SHOWN ON DETAIL 23A. THE TOP OF THE FRAME (MEAS) MUST BE 6" BELOW ADJACENT ROADWAYS WHERE FLOODING AND SAFETY ISSUES MAY ARISE.
- STRETCH THE 1/2" X 1/2" WIRE MESH TIGHTLY AROUND THE FRAME AND FASTEN SECURELY. THE ENDS MUST MEET AND OVERLAP AT A POST.
- STRETCH THE GEOTEXTILE CLASS E TIGHTLY OVER THE WIRE MESH WITH THE GEOTEXTILE EXTENDING FROM THE TOP OF THE FRAME TO 18" BELOW THE INLET NOTCH ELEVATION. FASTEN THE GEOTEXTILE FIRMLY TO THE FRAME. THE ENDS OF THE GEOTEXTILE MUST MEET AT A POST, BE OVERLAPPED AND FOLDED, THEN FASTENED DOWN.
- BACKFILL AROUND THE INLET IN COMPACTED 6" LAYERS UNTIL THE LAYER OF EARTH IS LEVEL WITH THE NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES.
- IF THE INLET IS NOT IN A SWAMP, CONSTRUCT A COMPACTED EARTH DIKE ACROSS THE DITCH LINE DIRECTLY BELOW IT. THE TOP OF THE EARTH DIKE SHOULD BE AT LEAST 6" HIGHER THAN THE TOP OF THE FRAME.
- THE STRUCTURE MUST BE INSPECTED PERIODICALLY AND AFTER EACH RAIN AND THE GEOTEXTILE REPLACED WHEN IT BECOMES CLOGGED.




PIPE SLOPE DRAIN
NOT TO SCALE

CONSTRUCTION SPECIFICATIONS

- THE PIPE SLOPE DRAIN (PSD) SHALL HAVE A SLOPE OF 3 PERCENT OR STEEPER.
- THE TOP OF THE EARTH DIKE OVER THE INLET PIPE SHALL BE AT LEAST 2 TIMES THE PIPE DIAMETER MEASURED AT THE INVERT OF THE PIPE.
- FLUXIBLE TUBING IS PREFERRED. HOWEVER, CORRUGATED METAL PIPE OR EQUIVALENT PVC PIPE CAN BE USED. ALL CONNECTIONS SHALL BE WATER-TIGHT.
- A FLARED END SECTION SHALL BE ATTACHED TO THE INLET END OF PIPE WITH A WATER-TIGHT CONNECTION. FILTER CLOTH SHALL BE PLACED ABOVE THE INLET OF THE PIPE SLOPE DRAIN AND SHALL EXTEND OUT 9" FROM THE INLET. THE FILTER CLOTH SHALL BE TIED TO ALL SIDES.
- THE PIPE SLOPE DRAIN SHALL BE SECURELY ANCHORED TO THE SLOPE BY STAPLES AT THE SPOKETS PROVIDED. SPACING FOR ANCHORS SHALL BE AS PROVIDED BY MANUFACTURERS SPECIFICATION. IN NO CASE SHALL BE LESS THAN TWO (2) ANCHORS BE PROVIDED ALONG THE LENGTH OF PIPE. THESE DETAILS SHOULD BE PROVIDED BY PIPE SUPPLIER.
- THE SOIL AROUND AND UNDER THE PIPE AND END SECTION SHALL BE HAND TAMPED IN 4 INCH LIFTS TO THE TOP OF THE EARTH DIKE.
- ALL PIPE CONNECTIONS SHALL BE WATER-TIGHT.
- WHENEVER POSSIBLE WHERE A PSD DRAINS AN UNSTABILIZED AREA, IT SHALL OUTLET INTO A SEDIMENT TRAP OR BASIN. IF THIS IS NOT POSSIBLE THEN THE SLOPE DRAIN SHALL DISCHARGE INTO A TRAP OR BASIN THE PIPE SHALL DISCHARGE AT THE SAME ELEVATION AS THE TRAP POOL ELEVATION. THE DRAINAGE FROM THE PSD MUST BE AS FAR AWAY FROM THE SEDIMENT CONTROL OUTLET AS POSSIBLE.
- WHEN THE DRAINAGE AREA IS STABILIZED, THE PSD SHALL DISCHARGE INTO A STABILIZED AREA AT A NON-EROSIVE VELOCITY.
- INSPECTION AND MAINTENANCE SHALL BE PERFORMED PERIODICALLY AND AFTER EACH RAIN EVENT.
- THE INLET MUST BE KEPT OPEN AT ALL TIMES.

TABLE 6- DESIGN CRITERIA FOR PIPE SLOPE DRAIN

PIPE SIZE	PIPE DIAMETER (IN)	AREA (ACRES)
PSD-12	12	0.5
PSD-18	18	1.5
PSD-21	21	2.5
PSD-24	24	3.5
PSD-30	30	9.0



DETAIL 22 - SILT FENCE

CONSTRUCTION SPECIFICATIONS

- FENCE POSTS SHALL BE A MINIMUM OF 36" LONG DRIVEN 16" MINIMUM INTO THE GROUND. WOOD POSTS SHALL BE 1 1/2" X 1 1/2" SQUARE (MINIMUM) CUT, OR 1 3/4" DIAMETER (MINIMUM) ROUND AND SHALL BE OF SOUND QUALITY HARDWOOD. STEEL POSTS WILL BE STANDARD T OR U SECTION LIGHTING NOT LESS THAN 1.00 POUND PER LINEAR FOOT.
- GEOTEXTILE SHALL BE FASTENED SECURELY TO EACH FENCE POST WITH WIRE TIES OR STAPLES AT TOP AND MID-SECTION AND SHALL MEET THE FOLLOWING REQUIREMENTS FOR GEOTEXTILE CLASS F:


DESIGN CRITERIA

TENSILE STRENGTH	50 LBS/(IN) (MIN)	TEST: MSMT 504
TENSILE MODULUS	20 LBS/(IN) (MIN)	TEST: MSMT 504
FLOW RATE	0.3 GAL/FT ² MINUTE (MAX)	TEST: MSMT 322
FILTERING EFFICIENCY	75% (MIN)	TEST: MSMT 322

- WHERE ENDS OF GEOTEXTILE FABRIC COME TOGETHER, THEY SHALL BE OVERLAPPED, FOLDED AND STAPLED TO PREVENT SEDIMENT BYPASS.
- SILT FENCE SHALL BE INSPECTED AFTER EACH RAINFALL EVENT AND MAINTAINED WHEN BULGES OCCUR OR WHEN SEDIMENT ACCUMULATION REACHED 50% OF THE FABRIC HEIGHT.

DESIGN CRITERIA


SLOPE	SLOPE STEEPNESS	SLOPE LENGTH (MAXIMUM)	SILT FENCE LENGTH (MAXIMUM)
0 - 10%	0 - 10:1	UNLIMITED	UNLIMITED
10 - 20%	10:1 - 5:1	200 FEET	1,500 FEET
20 - 33%	5:1 - 3:1	100 FEET	1,000 FEET
33 - 50%	3:1 - 2:1	100 FEET	500 FEET
50% +	2:1 +	50 FEET	250 FEET



DETAIL 6 - GABION INFLOW PROTECTION

CONSTRUCTION SPECIFICATIONS

- GABION INFLOW PROTECTION SHALL BE CONSTRUCTED OF 4" X 3" X 4" GABION BASKETS FORMING A TRAPEZOIDAL CROSS SECTION 1' DEEP, WITH 2:1 SIDE SLOPES, AND A 3' BOTTOM WIDTH.
- GEOTEXTILE CLASS C SHALL BE INSTALLED UNDER ALL GABION BASKETS.
- THE STONE USED TO FILL THE GABION BASKETS SHALL BE 4" - 7".
- GABIONS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.
- GABION INFLOW PROTECTION SHALL BE USED WHERE CONCENTRATED FLOW IS PRESENT ON SLOPES STEEPER THAN 4:1.



DETAIL 1 - EARTH DIKE

CONSTRUCTION SPECIFICATIONS

- SEED AND COVER WITH STRAW MULCH.
- SEED AND COVER WITH EROSION CONTROL MATTING OR LINE WITH 500.
- 4" - 1" STONE OR RECYCLED CONCRETE EQUIVALENT PRESSED INTO THE SOIL 1" MINIMUM.

FLOW CHANNEL STABILIZATION

GRADE 0.5% MIN. 1.0% MAX.

CONSTRUCTION SPECIFICATIONS

- ALL TEMPORARY EARTH DIKES SHALL HAVE UNINTERRUPTED POSITIVE GRADE TO AN OUTLET. SPOT ELEVATIONS MAY BE NECESSARY FOR GRADES LESS THAN 1%.
- RUNOFF DIVERTED FROM A DISTURBED AREA SHALL BE CONVEYED TO A SEDIMENT TRAPPING DEVICE.
- RUNOFF DIVERTED FROM AN UNDISTURBED AREA SHALL OUTLET DIRECTLY INTO AN UNDISTURBED, STABILIZED AREA AT A NON-EROSIVE VELOCITY.
- ALL TREES, BRUSH, STUMPS, OBSTRUCTIONS, AND OTHER OBJECTIONAL MATERIAL SHALL BE REMOVED AND DISPOSED OF SO AS NOT TO INTERFERE WITH THE PROPER FUNCTIONING OF THE DIKE.
- THE DIKE SHALL BE EXCAVATED OR SHAPED TO LINE, GRADE AND CROSS SECTION AS REQUIRED TO MEET THE CRITERIA SPECIFIED HEREIN AND BE FREE OF BANK PROJECTIONS OR OTHER IRREGULARITIES WHICH WILL IMPED NORMAL FLOW.
- FILL SHALL BE COMPACTED BY EARTH MOVING EQUIPMENT.
- ALL EARTH REMOVED AND NOT NEEDED FOR CONSTRUCTION SHALL BE PLACED SO THAT IT WILL NOT INTERFERE WITH THE FUNCTIONING OF THE DIKE.
- INSPECTION AND MAINTENANCE MUST BE PROVIDED PERIODICALLY AND AFTER EACH RAIN EVENT.

OWNER
TRUST U/A CARLEE JONES
BRANCH BANKING
& TRUST CO., TRUSTEE
C/O WILLIAM J. GERING
P.O. BOX 1100
WESTMINSTER, MD 21158
410-857-3430

DEVELOPER
C.J. PROPERTY LLC.
10753 BIRMINGHAM WAY
WOODSTOCK, MD. 21163
410-750-1200

APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

Richard M. Quirk
CHIEF, BUREAU OF HIGHWAYS
2-25-03
DATE

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING

Andy Hancock
CHIEF, DIVISION OF LAND DEVELOPMENT
3/4/03
DATE

Alfred L. Howard
CHIEF, DEVELOPMENT ENGINEERING DIVISION
3/10/03
DATE

SEDIMENT CONTROL NOTES & DETAILS

CARLEE MANOR

LOTS 1 THROUGH 26 AND
NON-BUILDABLE PARCEL "A"
TAX MAP 16, PARCEL 123

2 nd. ELECTION DISTRICT HOWARD COUNTY, MARYLAND

CLSI
Carroll Land Services
Incorporated
Engineers * Surveyors * Land Development Consultants
Landscape Architects * Environmental Specialists
439 East Main Street Westminster, MD 21157-3539
(410) 876-2017 FAX (410) 876-0009

Professional Engineer Registration No. 25446

Date	Revisions	Drawn By
		BM
		Designed By: AJD
		Reviewed By: AJD/ALH
		Date: JAN, 2003
		Scale: N/A
		Job No. 91230A
		Sheet: 10 OF 24

Silt Fence Design Criteria

Slope Steepness	(Maximum) Slope Length	(Maximum) Silt Fence Length
Flatter than 50:1	unlimited	unlimited
50:1 to 10:1	125 feet	1,000 feet
10:1 to 5:1	100 feet	750 feet
5:1 to 3:1	60 feet	500 feet
3:1 to 2:1	40 feet	250 feet
2:1 and steeper	20 feet	125 feet

NOTE: IN AREAS OF LESS THAN 2% SLOPE AND SANDY SOILS (USDA GENERAL CLASSIFICATION SYSTEM, SOIL CLASS A) MAXIMUM SLOPE LENGTH AND SILT FENCE LENGTH WILL BE UNLIMITED. IN THESE AREAS A SILT FENCE MAY BE THE ONLY PERIMETER CONTROL REQUIRED.

NOTE:
ALL SEDIMENT CONTROL MEASURES SHOWN HEREON ARE TEMPORARY UNLESS OTHERWISE NOTED.

DEVELOPER'S CERTIFICATE

I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT AND EROSION CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Alfred L. Howard
1/16/03
DATE

ENGINEER'S CERTIFICATE

I HEREBY CERTIFY THAT THIS PLAN FOR SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

Alfred L. Howard
1/16/03
DATE

ALFRED L. HOWARD
PROFESSIONAL ENGINEER REG. NO. 25446

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

John Agnew
2/16/03
DATE

USDA - NATURAL RESOURCES CONSERVATION SERVICE



THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEETS THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

Alfred L. Howard
1/16/03
DATE

HOWARD SOIL CONSERVATION DISTRICT

CAD Drawing File Name: g:\17230\dwg\conserv\sedplans\1050cd1.dwg

CAD Drawing File Name: g:\17230\cadd\const\resdplans\1105DDAM.DGN



OWNER
 TRUST U/A CARLEE JONES
 BRANCH BANKING
 & TRUST CO., TRUSTEE
 C/O WILLIAM J. GERING
 P.O. BOX 1100
 WESTMINSTER, MD 21158
 410-857-3430

DEVELOPER
 C.J. PROPERTY LLC
 10753 BIRMINGHAM WAY
 WOODSTOCK, MD, 21163
 410-750-1200

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Richard M. Daulton
 CHIEF, BUREAU OF HIGHWAYS 2-25-03 DATE

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Wanda Hamilton 3/4/02 DATE
 CHIEF, DIVISION OF LAND DEVELOPMENT
John D. ... 2/28/02 DATE
 CHIEF, DEVELOPMENT ENGINEERING DIVISION

**STORM DRAIN
 DRAINAGE AREA MAP
 CARLEE MANOR**
 LOTS 1 THROUGH 26 AND
 NON-BUILDABLE PARCEL 'A'
 TAX MAP 17, GRID 19, PARCEL 123
 2 nd. ELECTION DISTRICT HOWARD COUNTY, MARYLAND

CLSI
 Carroll Land Services
 Incorporated
 Engineers • Surveyors • Land Development Consultants
 Landscape Architects • Environmental Specialists
 439 East Main Street Westminster, MD 21157-3539
 (410) 876-2017 FAX (410) 876-0009

Date	Revisions	Drawn By: BM/SNC
		Designed By: AJD
		Reviewed By: AJD/ALH
		Date: JAN, 2003
		Scale: 1"=50'
		Job No: 91290A
		Sheet: 11 OF 24


LEGEND

— DRAINAGE AREA LIMITS

AREA ID ZONING DRAINAGE AREA
 'C' % IMPERVIOUS INFORMATION





22-58-51_002_01.dwg

CAD Drawing File Name: g:\1230\dwg\const\y45dplans\1235DPRO.DWG



NOTE: WATER & SEWER SHOWN FOR REFERENCE PURPOSES ONLY

NOTE: S_f = FRICTION SLOPE
 V_p = PARTIAL FLOW VELOCITY FOR Q_{10}



OWNER
TRUST W/A CARLEE JONES
BRANCH BANKING
& TRUST CO., TRUSTEE
C/O WILLIAM J. GERING
P.O. BOX 1100
WESTMINSTER, MD 21158
410-851-3430

DEVELOPER
C.J. PROPERTY L.L.C.
10753 BIRMINGHAM WAY
WOODSTOCK, MD 21163
410-750-1200


PROFILE
SCALE:
HORIZ. 1" = 50'
VERT. 1" = 5'

APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Richard M. Daulton
CHIEF, BUREAU OF HIGHWAYS
DATE: 2-25-03

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Chris Hamrick
CHIEF, DIVISION OF LAND DEVELOPMENT
DATE: 2/4/02


Alfred L. Howard
CHIEF, DEVELOPMENT ENGINEERING DIVISION
DATE: 2/28/02

STORM DRAIN PROFILES
CARLEE MANOR
LOTS 1 THROUGH 26 AND
NON-BUILDABLE PARCEL "A"
TAX MAP 17, GRID 19, PARCEL 123
2 nd. ELECTION DISTRICT HOWARD COUNTY, MARYLAND



CLSI
Carroll Land Services
Incorporated
Engineers * Surveyors * Land Development Consultants
Landscape Architects * Environmental Specialists
439 East Main Street Westminster, MD 21157-5539
(410) 876-2017 FAX (410) 876-0009


Date	Revisions	Drawn By
		JM
		Designed By: AJD
		Reviewed By: AJD/ALH
		Date: JAN, 2003
		Scale: As Shown
		Job No: 41230A
		Sheet: 12 OF 24



NOTE: CUTOFF & CORE MATERIAL TO BE APPROVED BY GEOTECHNICAL ENGINEER


NOTE: CORE AND CUT-OFF TRENCH MATERIAL SHALL CONSIST OF UNIFIED SOIL CLASSIFICATION GC, SC, CH, OR CL AND BE APPROVED BY THE GEOTECHNICAL ENGINEER AND HOWARD COUNTY.

CUT-OFF TRENCH
NOT TO SCALE




NOTE: CORE AND CUT-OFF TRENCH MATERIAL SHALL CONSIST OF UNIFIED SOIL CLASSIFICATION GC, SC, CH, OR CL AND BE APPROVED BY THE GEOTECHNICAL ENGINEER AND HOWARD COUNTY.

TYPICAL EMBANKMENT SECTION SECTION 'A-A'
SCALE: HORIZ.: 1" = 30'
VERT.: 1" = 5'




NOTE: CORE AND CUT-OFF TRENCH MATERIAL SHALL CONSIST OF UNIFIED SOIL CLASSIFICATION GC, SC, CH, OR CL AND BE APPROVED BY THE GEOTECHNICAL ENGINEER AND HOWARD COUNTY.

PROFILE ALONG CENTERLINE OF EMBANKMENT
SCALE: HORIZ.: 1" = 30'
VERT.: 1" = 5'




CONCRETE ANCHOR DETAIL
NOT TO SCALE



$Q_2 = 1.09 \text{ cfs}$, $V_2 = 2.1 \text{ fps}$
 $Q_{100} = 30.43 \text{ cfs}$, $V_{100} = 2.5 \text{ fps}$
 $Q_{10} = 42.73 \text{ cfs}$, $V_{10} = 3.3 \text{ fps}$
 $Q_{1000} = 45.21 \text{ cfs}$, $V_{1000} = 3.5 \text{ fps}$

PROFILE ALONG & OF WEIR WALL SPILLWAY
SCALE: HORIZ.: 1" = 30'
VERT.: 1" = 5'



GEOTECHNICAL ENGINEER EVALUATIONS AND RECOMMENDATIONS

Based on the shallow depth to rock and groundwater, infiltration is not recommended at this site. The site should be stripped of topsoil and any other unsuitable materials from the embankment or structure area in accordance with Soil Conservation guidelines. After stripping operations have been completed, the exposed subgrade materials should be proofrolled with a loaded scraper or similar equipment in the presence of a geotechnical engineer or his representative. For areas that are not accessible to a scraper, the exposed materials should be observed and tested by a geotechnical engineer or his representative utilizing a Dynamic Cone Penetrometer and hand auger. Any excessively soft or loose materials identified by proofrolling or penetrometer testing should be excavated to suitably firm soil, and then grades re-established by backfilling with suitable soil.

Some groundwater may be encountered within core trench excavations and some degree of dewatering will be required. Core trench dimensions should be the minimum required by MD 37B and extended up to the ten-year water level in the embankment.

A representative of the Geotechnical Engineer should be present to monitor placement and compaction of fill for the embankment and cut off trench, in accordance with Maryland Soil Conservation Specification 37B soils considered suitable for the center of embankment and cut off trench shall conform to Unified Soil Classification GC, SC, CH, or CL. Although some soils meeting these classifications were encountered in the borings, it is our professional opinion that an off site source will be required to obtain the required quantity of material.

CONCRETE RISER AND STRUCTURE CONSTRUCTION

Based on the foundation construction for the riser, principal spillway, endwalls, and other structures below the top two feet of the existing grades, we recommend that the concrete riser structure foundation be designed for a maximum net allowable bearing pressure of 2,000 lbs. per square foot (psf). Water should not be allowed to pond or collect within the foundation excavations, as this can cause a reduction in the bearing capacity of the soils. A geotechnical engineer or his representative should observe foundation excavations and conduct dynamic cone penetrometer testing (DCPT) of the bearing surfaces to depths of three feet. Settlements of the embankment are not anticipated to exceed 1 inch.

DEVELOPER'S CERTIFICATE

I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT AND EROSION CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN ON THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Alfred L. Harwood
1/16/03
DATE

ENGINEER'S CERTIFICATE

I HEREBY CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION.

Alfred L. Harwood
1/16/03
DATE

AS-BUILT CERTIFICATION

I HEREBY CERTIFY THAT THE FACILITY SHOWN ON THIS PLAN WAS CONSTRUCTED AS SHOWN ON THE "AS-BUILT" PLANS AND MEETS THE APPROVED PLANS AND SPECIFICATIONS.

SIGNATURE: *Alfred L. Harwood* DATE: 1/16/03

CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ON-SITE INSPECTIONS AND MATERIAL TESTS ARE THOSE ACCEPTED ENGINEERING STANDARDS. CERTIFY DOES NOT MEAN OR IMPLY A GUARANTEE BY THE ENGINEER NOR DOES AN ENGINEER'S CERTIFICATION RELIEVE AN OTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING COMMONLY ACCEPTED INDUSTRY PRACTICES.

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEETS THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

USDA - NATURAL RESOURCES CONSERVATION SERVICE DATE: 2/4/03

THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

HOWARD SOIL CONSERVATION DISTRICT DATE: 2/4/03

APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Richard M. Ronecke
CHIEF, BUREAU OF HIGHWAYS
2-25-03
DATE

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Chris Harvath
CHIEF, DIVISION OF LAND DEVELOPMENT
3/4/03
DATE

Alfred L. Harwood
CHIEF, DEVELOPMENT ENGINEERING DIVISION
2/10/03
DATE

STORMWATER MANAGEMENT PROFILES AND NOTES

CARLEE MANOR

LOTS 1 THROUGH 26 AND NON-BUILDABLE PARCEL "A"

TAX MAP 17, GRID 14, PARCEL 123

2 nd. ELECTION DISTRICT HOWARD COUNTY, MARYLAND

CLSI
Carroll Land Services Incorporated
Engineers • Surveyors • Land Development Consultants
Landscape Architects • Environmental Specialists
439 East Main Street Westminster, MD 21157-5539
(410) 876-2017 FAX (410) 876-0009

Professional Engineer Registration No. 23446

Date	Revisions	Drawn By:
		JN
		Designed By: AJD
		Reviewed By: AJD/ALH
		Date: JAN, 2003
		Scale: As Shown
		Job No. 41250A
		Sheet: 15 OF 24

CAD Drawing File Name: g:\1729\dwg\cons\resd\plans\15\swmp\prcd.dgn

HILLIS - CARNES ENGINEERING ASSOCIATES, INC. RECORD OF SOIL EXPLORATION

Project Name Carlee Jones Location Howard County Job Number 22798A Boring Number B-1 Page 1 of 1

Table with columns: ELEV, SOIL DESCRIPTION, STRA. DEPTH, DEPTH SCALE, COR, SAMPLE NO., BLOWN FT., NO., REC., BORING & SAMPLING NOTES. Includes soil profile data for boring B-1.

Table with columns: SAMPLE TYPE, SAMPLE CONDITION, BORING METHOD, CHRONOLOGICAL RECORDING. Includes data for boring B-1.

STANDARD PENETRATION TEST-DRIVING 2" O.D. SAMPLER WITH 140# HAMMER FALLING 30" COUNT MADE AT 6" INTERVALS

GENERAL. UNLESS OTHERWISE NOTED, ALL MATERIALS AND CONSTRUCTION PRACTICES SHALL CONFORM TO THE FOLLOWING:

- 1. HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS STANDARDS SPECIFICATIONS AND DETAILS FOR CONSTRUCTION... 2. NATURAL RESOURCE CONSERVATION SERVICE STANDARDS AND SPECIFICATIONS... 3. MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION... 4. TYPICAL WATER MANAGEMENT POND DESIGN MANUAL... 5. REINFORCED CONCRETE PIPE... 6. BACKFILLING SHALL CONFORM TO 'STRUCTURE BACKFILL'... 7. OTHER DETAILS (ANTI-SEEP COLLARS, VALVES, ETC.) SHALL BE AS SHOWN ON THE DRAWINGS.

REINFORCED CONCRETE PIPE - ALL OF THE FOLLOWING CRITERIA SHALL APPLY FOR REINFORCED CONCRETE PIPE... 1. MATERIALS - REINFORCED CONCRETE PIPE SHALL HAVE BELL AND SPIGOT JOINTS WITH RUBBER GASKETS AND SMALL EQUAL OR EXCEED ASTM DESIGNATION C-39.1... 2. BEDDING - ALL REINFORCED CONCRETE PIPE CONDUITS SHALL BE LAID IN A CONCRETE BEDDING FOR THEIR ENTIRE LENGTH...

PLASTIC PIPE - THE FOLLOWING CRITERIA SHALL APPLY FOR PLASTIC PIPE: 1. MATERIALS - PVC PIPE SHALL BE PVC-1120 OR PVC-1220 CONFORMING TO ASTM D-1785 OR ASTM D-2241... 2. JOINTS AND CONNECTIONS TO ANTI-SEEP COLLARS SHALL BE COMPLETELY WATER-TIGHT...

CONCRETE CONCRETE SHALL MEET THE REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION 414, MK NO. 3.

REINFORCEMENT REINFORCEMENT SHALL MEET THE MINIMUM REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION 610 (REINFORCEMENT FOR CONCRETE STRUCTURES)... SECTION 411 (REINFORCING STEEL GRADE 60)... SECTION 412 (REINFORCING STEEL GRADE 80)... SECTION 413 (REINFORCING STEEL GRADE 100)...

SOIL BACKFILL BACKFILL ADJACENT TO PIPES OR STRUCTURES SHALL BE OF THE TYPE AND QUALITY CONFORMING TO THAT SPECIFIED FOR THE ADJOINING FILL MATERIAL... THE FILL SHALL BE PLACED IN HORIZONTAL LAYERS NOT TO EXCEED FOUR INCHES IN THICKNESS AND COMPACTED BY HAND TAMPERS OR OTHER MANUALLY DIRECTED COMPACTION EQUIPMENT...

STABILIZATION STABILIZATION SHALL MEET THE REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION 315 AS MODIFIED... THE MIXTURE SHALL HAVE A 100-200 PLS 20 DAY UNCOMPACTED COMPRESSIVE STRENGTH... THE FLOWABLE FILL SHALL HAVE A MINIMUM PERCENTAGE OF 40% FINE MATERIAL... THE FILL SHALL BE PLACED SUCH THAT A MINIMUM OF 6" OF UNCOMPACTED FILL SHALL BE UNDER (BEDDING) COVER AND ON THE SIDES OF THE PIPE... IT ONLY NEEDS TO EXTEND UP TO THE SPRING LINE FOR RIGID CONDUITS...

FEED CONDUITS ALL FEED CONDUITS SHALL BE CIRCULAR IN CROSS SECTION. CORRUGATED METAL PIPE - ALL OF THE FOLLOWING CRITERIA SHALL APPLY FOR CORRUGATED METAL PIPE: 1. MATERIALS - POLYMER COATED STEEL PIPE - STEEL PIPES WITH POLYMERIC COATINGS SHALL HAVE A MINIMUM COATING THICKNESS OF 0.01 INCH (0.10 MIL) ON BOTH SIDES OF THE PIPE... 2. COUPLING BANDS - ANTI-SEEP COLLARS, END SECTIONS ETC., MUST BE COMPOSED OF THE SAME MATERIAL AND COATING AS THE PIPE METALS... 3. CONNECTIONS - ALL CONNECTIONS WITH PIPES MUST BE COMPLETELY WATER-TIGHT... THE DRAIN PIPE OR BARREL CONNECTION TO THE RISER SHALL BE WELDED ALL AROUND WHEN THE PIPE AND BARREL CONNECTIONS ARE TO BE COMPLETED... THE PIPE SHALL BE PLACED IN SUCH A MANNER AS TO BE COMPLETELY WATER-TIGHT... DOUBLE ENDS ARE NOT CONSIDERED TO BE WATER-TIGHT.

TEMPERATURE SEEDING SUMMARY Seed Mixture Hardness Zone 60 (6-20 Figure 5)

Table with columns: No. Species, Rate (lb/ac), Dates, Depths. Includes data for RYE PLUS FOXTAIL MILLET.

DEVELOPER'S CERTIFICATE I/VE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT AND EROSION CONTROL... AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING PROJECT...

ENGINEER'S CERTIFICATE I HEREBY CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT... I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN 'AS-BUILT' PLAN OF THE POND WITHIN 90 DAYS OF COMPLETION...

Signature and Date of Engineer: [Signature] 2/4/03 DATE

HILLIS - CARNES ENGINEERING ASSOCIATES, INC. RECORD OF SOIL EXPLORATION

Project Name Carlee Jones Location Howard County Job Number 22798A Boring Number B-3 Page 1 of 1

Table with columns: ELEV, SOIL DESCRIPTION, STRA. DEPTH, DEPTH SCALE, COR, SAMPLE NO., BLOWN FT., NO., REC., BORING & SAMPLING NOTES. Includes soil profile data for boring B-3.

Table with columns: SAMPLE TYPE, SAMPLE CONDITION, BORING METHOD, CHRONOLOGICAL RECORDING. Includes data for boring B-3.

STANDARD PENETRATION TEST-DRIVING 2" O.D. SAMPLER WITH 140# HAMMER FALLING 30" COUNT MADE AT 6" INTERVALS

CONCRETE CONCRETE SHALL MEET THE REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION 414, MK NO. 3.

REINFORCEMENT REINFORCEMENT SHALL MEET THE MINIMUM REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION 610 (REINFORCEMENT FOR CONCRETE STRUCTURES)... SECTION 411 (REINFORCING STEEL GRADE 60)... SECTION 412 (REINFORCING STEEL GRADE 80)... SECTION 413 (REINFORCING STEEL GRADE 100)...

SOIL BACKFILL BACKFILL ADJACENT TO PIPES OR STRUCTURES SHALL BE OF THE TYPE AND QUALITY CONFORMING TO THAT SPECIFIED FOR THE ADJOINING FILL MATERIAL... THE FILL SHALL BE PLACED IN HORIZONTAL LAYERS NOT TO EXCEED FOUR INCHES IN THICKNESS AND COMPACTED BY HAND TAMPERS OR OTHER MANUALLY DIRECTED COMPACTION EQUIPMENT...

STABILIZATION STABILIZATION SHALL MEET THE REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION 315 AS MODIFIED... THE MIXTURE SHALL HAVE A 100-200 PLS 20 DAY UNCOMPACTED COMPRESSIVE STRENGTH... THE FLOWABLE FILL SHALL HAVE A MINIMUM PERCENTAGE OF 40% FINE MATERIAL... THE FILL SHALL BE PLACED SUCH THAT A MINIMUM OF 6" OF UNCOMPACTED FILL SHALL BE UNDER (BEDDING) COVER AND ON THE SIDES OF THE PIPE... IT ONLY NEEDS TO EXTEND UP TO THE SPRING LINE FOR RIGID CONDUITS...

Table with columns: SPECIES, APPLICATION RATE (lb/ac), SEEDING DATES. Includes data for TALL FESCUE, PERENNIAL RYEGRASS, and KENTUCKY BLUEGRASS.

DEVELOPER'S CERTIFICATE I/VE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT AND EROSION CONTROL... AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING PROJECT...

ENGINEER'S CERTIFICATE I HEREBY CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT... I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN 'AS-BUILT' PLAN OF THE POND WITHIN 90 DAYS OF COMPLETION...

Signature and Date of Engineer: [Signature] 2/4/03 DATE

HILLIS - CARNES ENGINEERING ASSOCIATES, INC. RECORD OF SOIL EXPLORATION

Project Name Carlee Jones Location Howard County Job Number 22798A Boring Number B-4 Page 1 of 1

Table with columns: ELEV, SOIL DESCRIPTION, STRA. DEPTH, DEPTH SCALE, COR, SAMPLE NO., BLOWN FT., NO., REC., BORING & SAMPLING NOTES. Includes soil profile data for boring B-4.

Table with columns: SAMPLE TYPE, SAMPLE CONDITION, BORING METHOD, CHRONOLOGICAL RECORDING. Includes data for boring B-4.

STANDARD PENETRATION TEST-DRIVING 2" O.D. SAMPLER WITH 140# HAMMER FALLING 30" COUNT MADE AT 6" INTERVALS

CONCRETE CONCRETE SHALL MEET THE REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION 414, MK NO. 3.

REINFORCEMENT REINFORCEMENT SHALL MEET THE MINIMUM REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION 610 (REINFORCEMENT FOR CONCRETE STRUCTURES)... SECTION 411 (REINFORCING STEEL GRADE 60)... SECTION 412 (REINFORCING STEEL GRADE 80)... SECTION 413 (REINFORCING STEEL GRADE 100)...

SOIL BACKFILL BACKFILL ADJACENT TO PIPES OR STRUCTURES SHALL BE OF THE TYPE AND QUALITY CONFORMING TO THAT SPECIFIED FOR THE ADJOINING FILL MATERIAL... THE FILL SHALL BE PLACED IN HORIZONTAL LAYERS NOT TO EXCEED FOUR INCHES IN THICKNESS AND COMPACTED BY HAND TAMPERS OR OTHER MANUALLY DIRECTED COMPACTION EQUIPMENT...

STABILIZATION STABILIZATION SHALL MEET THE REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION 315 AS MODIFIED... THE MIXTURE SHALL HAVE A 100-200 PLS 20 DAY UNCOMPACTED COMPRESSIVE STRENGTH... THE FLOWABLE FILL SHALL HAVE A MINIMUM PERCENTAGE OF 40% FINE MATERIAL... THE FILL SHALL BE PLACED SUCH THAT A MINIMUM OF 6" OF UNCOMPACTED FILL SHALL BE UNDER (BEDDING) COVER AND ON THE SIDES OF THE PIPE... IT ONLY NEEDS TO EXTEND UP TO THE SPRING LINE FOR RIGID CONDUITS...

Table with columns: SPECIES, APPLICATION RATE (lb/ac), SEEDING DATES. Includes data for TALL FESCUE, PERENNIAL RYEGRASS, and KENTUCKY BLUEGRASS.

DEVELOPER'S CERTIFICATE I/VE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT AND EROSION CONTROL... AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING PROJECT...

ENGINEER'S CERTIFICATE I HEREBY CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT... I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN 'AS-BUILT' PLAN OF THE POND WITHIN 90 DAYS OF COMPLETION...

Signature and Date of Engineer: [Signature] 2/4/03 DATE

STORMWATER MANAGEMENT PROFILES AND NOTES

CARLEE MANOR AS-BUILT CERTIFICATION

I HEREBY CERTIFY THAT THE FACILITY SHOWN ON THIS PLAN WAS CONSTRUCTED AS SHOWN ON THE 'AS-BUILT' PLANS AND MEETS THE APPROVED PLANS AND SPECIFICATIONS.


SIGNATURE DATE

CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ON-SITE INSPECTIONS AND MATERIAL TESTS ARE THESE INSPECTIONS AND TESTS DEEMED SUFFICIENT AN APPROPRIATE COMMONLY ACCEPTED ENGINEERING STANDARD. CERTIFY DOES NOT MEAN OR IMPLY A GUARANTEE BY THE ENGINEER NOR DOES AN ENGINEER'S CERTIFICATE RELIEVE AN OTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING COMMONLY ACCEPTED INDUSTRY PRACTICES.

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL. USDA - NATURAL RESOURCES CONSERVATION SERVICE 2/4/03 DATE

THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. HOWARD SOIL CONSERVATION DISTRICT 2/4/03 DATE


Signature and Date of Engineer: [Signature] 2/4/03 DATE



S-1 WEIR WALL ELEVATION OF DOWNSTREAM FACE
SCALE: 3/8" = 1'-0"

NOTE:
THE WEIR WALL IS TO BE CAST AGAINST UNDISTURBED EARTH.

NOTE:
ALL EXPOSED WEIR WALL EDGES ARE TO BE CHAMFERED A MINIMUM OF 1" X 1".



WEIR WALL SECTION A-A
SCALE: 3/8" = 1'-0"


NOTE 'A'
PLACE CONCRETE AGAINST UNDISTURBED EARTH

NOTE:
2000 psf BEARINGS TO BE VERIFIED BY A GEOTECHNICAL ENGINEER

APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Richard M. Gendle
CHIEF, BUREAU OF HIGHWAYS *RG* 2-25-03 DATE

APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Carolee H. Hensley
CHIEF, DIVISION OF LAND DEVELOPMENT *CH* 7/4/02 DATE

William J. Gering
CHIEF, DEVELOPMENT ENGINEERING DIVISION 2/28/03 DATE



STRUCTURAL DESIGN BY
HILLIS-CARNES ENGINEERING ASSOCIATES INC.
P.O. BOX 647
NEW MARKET, MARYLAND 21774
(301)-631-3960

OWNER
TRUST U/A CARLEE JONES
BRANCH BANKING
& TRUST CO., TRUSTEE
C/O WILLIAM J. GERING
P.O. BOX 1100
WESTMINSTER, MD 21158
410-851-3430

DEVELOPER
C.J. PROPERTY L.L.C.
10753 BIRMINGHAM WAY
WOODSTOCK, MD. 21163
410-750-1200

STORMWATER MANAGEMENT DETAILS
CARLEE MANOR
LOTS 1 THROUGH 26 AND
NON-BUILDABLE PARCEL 'A'
TAX MAP 17, GRID 19, PARCEL 123
2 nd. ELECTION DISTRICT HOWARD COUNTY, MARYLAND

CLSI
Carroll Land Services
Incorporated
Engineers * Surveyors * Land Development Consultants
Landscape Architects * Environmental Specialists
439 East Main Street Westminster, MD 21157-3539
(410) 876-2017 FAX (410) 876-0009

AS-BUILT CERTIFICATION
I HEREBY CERTIFY THAT THE FACILITY SHOWN ON THIS PLAN WAS CONSTRUCTED AS SHOWN ON THE "AS-BUILT" PLANS AND MEETS THE APPROVED PLANS AND SPECIFICATIONS.

SIGNATURE _____ DATE _____
CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ON-SITE INSPECTIONS AND MATERIAL TESTS ARE THOSE ACCEPTED ENGINEERING STANDARDS. CERTIFY DOES NOT MEAN OR IMPLY A GUARANTEE BY THE ENGINEER NOR DOES AN ENGINEER'S CERTIFICATION RELIEVE ANY OTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING COMMONLY ACCEPTED INDUSTRY PRACTICES.



DEVELOPER'S CERTIFICATE
I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT AND EROSION CONTROL AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN ON THE POND WITHIN 90 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.
William J. Gering
DATE 1/16/03

ENGINEER'S CERTIFICATE
I HEREBY CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 90 DAYS OF COMPLETION.
Alfred L. Hansard
DATE 1/16/03
PROFESSIONAL ENGINEER REG. NO. 28446

THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.
Alfred L. Hansard 2/4/03 DATE
USDA - NATURAL RESOURCES CONSERVATION SERVICE
THESE PLANS FOR SOIL EROSION AND SEDIMENT CONTROL, MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.
Alfred L. Hansard 2/4/03 DATE
HOWARD SOIL CONSERVATION DISTRICT

Date	Revisions	Drawn By	JJK
		Designed By	AJD
		Reviewed By	AJD/ALH
		Date:	JAN 2003
		Scale:	As Shown
		Job No.:	97250A
		Sheet:	17 OF 24

CAD Drawing File Name: g:\17230\dwg\const\yrf\plans\18\EXS\NMD\MDEN



FOR OFFSITE AREA SEE 1" = 200' SCALE MAP THIS SHEET

OWNER
 TRUST U/A CARLEE JONES
 BRANCH BANKING
 & TRUST CO., TRUSTEE
 C/O WILLIAM J. GERING
 P.O. BOX 1100
 WESTMINSTER, MD 21158
 410-857-3430

DEVELOPER
 C.J. PROPERTY LLC
 10753 BIRMINGHAM WAY
 WOODSTOCK, MD 21163
 410-750-1200

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
David M. Daniels 2/25/07
 CHIEF, BUREAU OF HIGHWAYS DATE

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Wendy Hamilton 3/4/08
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE

APPROVED:
John Dammann 2/20/08
 CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

**SWM DRAINAGE AREA MAP
 EXISTING CONDITIONS
 CARLEE MANOR**

LOTS 1 THROUGH 26 AND
 NON-BUILDABLE PARCEL "A"

TAX MAP 17, GRID 19, PARCEL 123
 2 nd. ELECTION DISTRICT HOWARD COUNTY, MARYLAND

CLSI

Carroll Land Services
 Incorporated
 Engineers • Surveyors • Land Development Consultants
 Landscape Architects • Environmental Specialists
 439 East Main Street Westminster, MD 21157-5339
 (410) 876-2017 FAX (410) 876-0009

Date	Revisions	Drawn By: JWB/CNC
		Designed By: AJD
		Reviewed By: AJD/ALH
		Date: JAN, 2003
		Scale: 1"=50'
		Job No: 97290A
		Sheet: 10 OF 24

LEGEND

(A) DRAINAGE AREA DESIGNATOR

— DRAINAGE AREA LIMIT

— SOIL LIMIT

MIC3 (B) SOIL SERIES (HSG)

A — B — Tc PATH

DEVELOPER'S CERTIFICATE
 I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN FOR POND CONSTRUCTION, SEDIMENT AND EROSION CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN ON THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.

Alfred L. Hansard
 1/16/03
 DATE

ENGINEER'S CERTIFICATE
 I HEREBY CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION.

Alfred L. Hansard
 1/16/03
 DATE

AS-BUILT CERTIFICATION

I HEREBY CERTIFY THAT THE FACILITY SHOWN ON THIS PLAN WAS CONSTRUCTED AS SHOWN ON THE "AS-BUILT" PLANS AND MEETS THE APPROVED PLANS AND SPECIFICATIONS.

SIGNATURE _____ DATE _____


CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ON-SITE INSPECTIONS AND MATERIAL TESTS ARE THOSE INSPECTIONS AND TESTS DEEMED SUFFICIENT AN APPROPRIATE COMMONLY ACCEPTED ENGINEERING STANDARDS. CERTIFY DOES NOT MEAN OR IMPLY A GUARANTEE BY THE ENGINEER NOR DOES AN ENGINEER'S CERTIFICATION RELIEVE ANY OTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING COMMONLY ACCEPTED INDUSTRY PRACTICES.




THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENT CONTROL.

USDA - NATURAL RESOURCES CONSERVATION SERVICE

DATE: 2/16/07

DATE: 2/16/07





OWNER
 TRUST U/A CARLEE JONES
 BRANCH BANKING
 & TRUST CO., TRUSTEE
 C/O WILLIAM J. GERING
 P.O. BOX 1100
 WESTMINSTER, MD 21158
 410-851-3430

DEVELOPER
 C.J. PROPERTY LLC
 10153 BIRMINGHAM WAY
 WOODSTOCK, MD 21163
 410-750-1200

**SCHEDULE D
 STORMWATER MANAGEMENT
 AREA LANDSCAPING**

Linear Feet of Edge	845
Number of Trees Required Shade Trees 1:50 L.F. Evergreen Trees 1:40 L.F. =	17 22
Credit for Existing Vegetation (No, Yes and %)	NO
Credit for Other Landscaping (No, Yes and %)	NO
Number of Trees Provided Shade Trees Evergreen Trees Other Trees (2:1 substitution)	8 40

* 18 EVERGREEN TREES WERE
 SUBSTITUTED FOR 9 SHADE TREES

PLANTING SCHEDULE

SYMBOL	QTY.	COMMON NAME	BOTANICAL NAME	SIZE	SPACING	COMMENTS
Large Deciduous Trees						
AS	10	ASH	Fraxinus americana 'Autumn Purple'	2.5' CAL.	30'-40' o.c.	B4B
RM	13	RED MAPLE	Acer rubrum 'October Glory'	2.5' CAL.	30'-40' o.c.	B4B
HL	9	HONEYLOCUST	Gleditsia triacanthos 'Shademaster'	2.5' CAL.	30'-40' o.c.	B4B
SG	3	SWEETGUM	Liquidambar styraciflua	2.5' CAL.		B4B
LP	7	LONDON PLANE	Platanus x acerifolia 'Bloodgood'	2.5' CAL.		B4B
PO	11	PIN OAK	Quercus palustris	2.5' CAL.		B4B
SO	3	SANTOOTH OAK	Quercus acutissima	2.5' CAL.		B4B
Medium Deciduous Trees						
GH	34	FLOWERING CHERRY	Prunus sargentii	2' CAL.	30'-40' o.c.	B4B
CP	11	CHANTICLEER PEAR	Pyrus calleryana 'Chanticleer'	2' CAL.	30'-40' o.c.	B4B
Evergreen Trees						
LC	37	LEYLAND CYPRESS	Cupressocyparis leylandii	5'-6'	10'-15' o.c.	Cont.
WP	49	WHITE PINE	Pinus strobus	6'-8'	15'-20' o.c.	B4B
AH	12	AMERICAN HOLLY	Ilex opaca	5'-6'	10'-15' o.c.	B4B
Street Trees						

**SCHEDULE A
 PERIMETER LANDSCAPE EDGE**

Category	Adjacent to Perimeter Properties	Perimeter Number:									LANDSCAPE TYPE 'B'	1	2
		1	2	3	4	5	7	8	9				
Linear Feet of Perimeter	3042	65'	860'	240'	559'	310'	350'	366'	342'	340	170	170	
Credit for Existing Vegetation (Yes, No Linear Feet) (Describe below if needed)	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	
Credit for Wall, Fence or Berm (Yes, No Linear Feet) (Describe below if needed)	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	
Number of Plants Required Shade Trees 1:60 L.F. Evergreen Trees 1:40 L.F. Shrubs 0	52	1.1	14.3	4.0	4.3	5.2	5.8	6.1	5.7	6.8	3.4	3.4	
Number of Plants Provided	Shade Trees: 25 Evergreen Trees: 54*	0	6	0	7	5	4	2	1	7	4	3	
(Describe plant substitution credits below if needed)		2	17	8	4	0	7	10	6	4	4	5	

SURETY NOTE:
 1 per 40 L.F. street frontage
 2450 L.F. divided by 40 = 61.25 required
 62.0 proposed
 The street trees will be planted in 10 ft. wide tree maintenance easement.

THIS PLAN HAS BEEN PREPARED IN ACCORDANCE WITH THE PROVISIONS OF SECTION 16.124 OF THE HOWARD COUNTY CODE AND THE LANDSCAPE MANUAL. FINANCIAL SURETY BASED ON REQUIRED PLANTINGS (61 SHADE TREES @ \$300.00 EA. AND 22 EVERGREENS @ \$150.00 EA.) HAS BEEN FOR THE REQUIRED 204 LANDSCAPE TREES HAS BEEN POSTED AS PART OF THE DEVELOPER'S AGREEMENT IN THE AMOUNT OF \$24,000.

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Richard M. Daniels
 CHIEF, BUREAU OF HIGHWAYS
 2/25/07 DATE

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Leidy Houston
 CHIEF, DIVISION OF LAND DEVELOPMENT
 2/24/07 DATE
Chad Damann
 CHIEF, DEVELOPMENT ENGINEERING DIVISION
 2/28/07 DATE

**STREET TREE AND LANDSCAPE
 PLAN
 CARLEE MANOR**
 LOTS 1 THROUGH 26 AND
 NON-BUILDABLE PARCEL 'A'
 TAX MAP 17, GRID 19, PARCEL 123
 2 nd. ELECTION DISTRICT HOWARD COUNTY, MARYLAND



CLSI
 Carroll Land Services
 INCORPORATED
 Engineers • Surveyors • Land Development Consultants
 Landscape Architects • Environmental Specialists
 439 East Main Street Westminster, MD 21157-5339
 (410) 876-2017 FAX (410) 876-0009

Registered Landscape Architect No. 930 MD

Date	Revisions	Drawn By: SMC
		Designed By: PLM
		Reviewed By: AJD/ALH
		Date: JAN, 2003
		Scale: 1"=50'
		Job No: 47230A
		Sheet: 20 OF 24

CAD Drawing File Name: g:\1230\dgn\const\resplans\20\LAND.DGN

CAD Drawing File Name: g:\1230\dgn\const\forestry\011for\plan.dgn



SOILS CHART

SERIES	ERODIBLE (FACTOR 0-25)	HYDRIC
BAILE	+	+
BRANDYWINE	-	-
COMUS	-	-
ELIOAK	-	-
GLENVILLE	+	-
GLENELG	+	-
MANOR	-	-

- LEGEND**
- VEGETATIVE LINE
 - EXISTING CONTOURS
 - X- FENCE
 - EKB2 EXISTING SOILS
 - EXISTING BOUNDARY
 - TREE LINE
 - STREAM BUFFER
 - Ⓠ PROPOSED LOT NUMBERS
 - T/L OPEN FIELD OR PASTURE
 - W WETLANDS
 - H HEDGEROW

NET TRACT CALCULATION

TOTAL AREA: 13.3 ACRES +/-
FLOODPLAIN: 0.0 ACRES
NET TRACT AREA: 13.3 ACRES +/-

F.S.D. Written Narrative

A Forest Stand Delineation was performed in October, 1998 by CLSI, Inc. No forest communities exist on site. Environmental features of concern on site include a springhead, stream with partially eroded banks and nontidal wetlands located in the southeastern corner of the property. Slopes greater than 15% do not exist on site. 6 trees 30" or greater were located and are noted on plan. The site consist of 2 existing residential dwellings and outbuildings surrounded by Tree/Lawn areas in the center of the property. The western portion of the property consists of a mowed Open Field while the eastern portion is fenced in Open Field/pasture and Wetland where livestock is contained. The priority planting area on site is the riparian area in the southeast corner that will be contiguous to the existing forest on the the adjoining property.

FOREST STAND ANALYSIS TABLE

APPLICANT: PROJECT NAME: SUBMISSION NO.

KEY	A. TYPE OF COMMUNITY	B. AREA	C. SOIL INFORMATION		D. EXISTING VEGETATION	E. STAND CHARACTERISTICS			F. FOREST AREA IN SENSITIVE ENVIRONMENTS	G. HABITAT VALUE
			1. Soil Types	2. Typical Forest cover for soil type		1. Size (Plan)	2. Age	3. General Conditions		
H1	Hedgerow	N/A	Glenelg	Oak, Mixed upland hardwoods	4000 - 50	4000 - 50			OPEN	
H2	Hedgerow	N/A	Brandwynne	Oak, Mixed upland hardwoods	4000 - 41	4000 - 41			OPEN	
H3	Hedgerow	N/A	Brandwynne	Oak, Mixed upland hardwoods	4000 - 30	4000 - 45			OPEN	
OP1	Open Field	5.3	Glenelg	Oak, Mixed upland hardwoods	4000 - 50	4000 - 50			OPEN	
OP2	Open Pasture	5.7	Glenelg	Oak, Mixed upland hardwoods	4000 - 50	4000 - 50			OPEN	
T/L1	Tree/Lawn Area	0.9	Glenelg	Oak, Mixed upland hardwoods	4000 - 50	4000 - 50			OPEN	
T/L2	Tree/Lawn Area	1.1	Glenelg	Oak, Mixed upland hardwoods	4000 - 50	4000 - 50			OPEN	
W1	Wetlands	0.3	Glenelg	Wetland	4000 - 12	4000 - 12			WETLAND	

NOTE: NO FOREST EXIST ON-SITE.

TREES 30" AND GREATER

T#	D.B.H.	Common/Scientific Name	Condition	Retention
1	4 1/2"	Silver Maple/Acer saccharinum	Good	No
2	3 0"	White Ash/Praxinus americana	Fair	No
3	4 5"	Black Locust/Robinia Pseudo-Acacia	Poor	No
4	3 0"	Red Maple/Acer rubrum	Poor	Yes
5	3 0"	White Ash/Praxinus americana	Good	No
6	3 0"	Sugar Maple/Acer saccharum	Poor	No

OWNER
TRUST U/A CARLEE JONES
BRANCH BANKING
& TRUST CO., TRUSTEE
C/O WILLIAM J. GERING
P.O. BOX 1100
WESTMINSTER, MD 21158
410-857-3430

DEVELOPER
C.J. PROPERTY LLC.
10753 BIRMINGHAM WAY
WOODSTOCK, MD. 21168
410-750-1200

APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Richard M. Gault 2-25-03 DATE
CHIEF, BUREAU OF HIGHWAYS

HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Cindy Hancock 3/4/03 DATE
CHIEF, DIVISION OF LAND DEVELOPMENT

John D. ... 8/20/03 DATE
CHIEF, DEVELOPMENT ENGINEERING DIVISION

FINAL FOREST CONSERVATION PLAN

CARLEE MANOR
LOTS 1 THROUGH 26 AND
NON-BUILDABLE PARCEL "A"

TAX MAP 17, GRID 19, PARCEL 123
ELECTION DISTRICT HOWARD COUNTY, MARYLAND

CLSI
Carroll Land Services
Incorporated
Engineers * Surveyors * Land Development Consultants
Landscape Architects * Environmental Specialists
439 East Main Street Westminster, MD 21157-5539
(410) 876-2017 FAX (410) 876-0009

HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
REGISTERED PROFESSIONAL FORESTER NO. 142

Date	Revisions	Drawn By
		KB/SNC
		Designed By:
		Reviewed By:
		Date: JAN, 2003
		Scale: 1" = 50'
		Job No: 91290A
		Sheet: 21 OF 24

FOREST CONSERVATION WORKSHEET

Basic Site DATA
 Gross Site Area 13.31 Acres
 Area within 100 Yr. Flood Plain 0
 Area within Agricuilt. Pres. Par. 0
 Net Tract Area 13.31 Acres
 Land Use Category HDR (High Density Res.)

Information for Calculations
 A. Total Net Tract Area: 13.31 Acres
 B. Reforestation Threshold: 20% = 2.66 Acres
 C. Afforestation Minimum: 15% = 2.00 Acres
 D. Existing Forested Area: 0 Acres
 E. Forest area to be cleared 0 Acres
 F. Forest area to be retained 0 Acres

Afforestation required: 2.00 Acres
RETENTION AREAS AND PRIORITY RATINGS

No Forest on site
 REFORESTATION: 0 ACRES
 There are six specimen trees on site, five of these trees will be removed due to grading.

SPECIMEN TREES WITHIN DISTURBANCE AREAS

NO.	COMMON NAME/SCIENTIFIC NAME	DBH	CONDITION	REMOVE
1	Silver Maple/Acer saccharinum	4.1"	Good	Yes
2	White Ash/Fraxinus americana	3.0"	Fair	Yes
3	Locust/Robinia Pseudo-Acacia	4.5"	Poor	Yes
4	Red Maple/Acer rubrum	3.0"	Poor	No
5	White Ash/Fraxinus americana	3.0"	Good	Yes
6	Sugar Maple/Acer saccharum	3.0"	Poor	Yes

FOREST CONSERVATION PLAN NARRATIVE

When applying the Forest Stand Delineation to this project, no forest exists on site, environmental features of concern are a springhead, stream and nontidal wetlands. All specimen trees with the exception of specimen tree No.4, will be removed, due to grading.

FOREST PROTECTION PLAN
 The specimen tree (#4) is within the afforestation area, this area will be protected from impact during grading to the north and grading of 5NM Pond to the west of the stream buffer area. The initial limit of disturbance (L.O.D.) for construction will be marked by the contractor, 15' from the L.O.D. shown on the Forest Conservation Map. The forest buffer line is shown on plan. For specimen tree # 4, the Soil Compaction Zone or CRZ (Critical Root Zone) is 45'. Once the CRZ is established, the L.O.D. will be re-adjusted to conform with the field flagging. At this time the contractor will install the following protection devices (see detail).

The temporary forest protection device, will be well anchored, two-three strand smooth wire fence along with Afforestation Signs posted every 100 feet and two specimen tree signs. This fence will be installed once the CRZ has been established and the L.O.D. located, as mentioned previously. This protection device will be installed prior to any construction activity. Grading will occur near areas designated for retention, making it even more important that the protection device be easily seen. The fence stakes will be installed 2' into the ground just outside the CRZ. Signs are not to be put on trees!!

No construction equipment, machinery, vehicle, materials or excessive pedestrian traffic will be allowed in the afforestation area. Therefore, no openings through the fence will be allowed. Entrance to the area will be allowed for planting and inspection purposes only. This protective tree device will remain in place and will be maintained throughout the life of the construction project. To help reduce the possibility of disturbance within an identified afforestation protection area, a pre-construction meeting will take place after the boundaries of the L.O.D. have been staked and forest protection devices have been installed. The employees of the construction crew will be informed of the importance of the trees slated for retention. Each foreman shall read "Every Builder Should Know", (detail on this plan sheet). During the pre-construction meeting the temporary parking location, stockpile area, staging and fueling area will be shown to all personnel.
NOTE: Wash-Out Area is designated in driveways, or will be taken off site. Cement spills are a main cause of soil pH change.

WHAT EVERY BUILDER SHOULD KNOW
 The Wisconsin Arborist/September-October 1990

- The roots are the most important part of a tree.
- Tree roots must have oxygen, in order to function. Covering roots with soil, paving, or water can deprive roots of vital oxygen supplies.
- The main absorbing roots of trees are in the top 6-12 inches of soil. The myth of "deep rooted trees" is just that a myth.
- Even side transport roots form the short "tap roots" of an oak slant upward to get oxygen and rain water. The majority of roots grow upward toward the surface, not downward.
- The absorbing roots of trees are mostly in a large, shallow disc that is 2-4 times the area covered by the crown, in other words, tree roots extend far beyond the branches!
- Grading dirt over the absorbing roots of trees anywhere under their branches (and often beyond) suffocates the absorbing roots and kills all or most of the crown in 1-3 years.
- Grading soil away from the root zone of trees removes their absorbing roots and does great injury to the crown within 1-3 years. It kills the nearly invisible hair roots.
- If you can see roots of a tree which you have cut, you have already done considerable damage to the tree.
- Compaction of soil under trees (especially by bulldozers working in an area, and by repeated parking of vehicles, by construction people) is almost as deadly to trees as covering their roots with soil. The compaction deprives the roots of oxygen.
- Building a "Tree Well" (e.g. a stone wall) around the trunk of a tree, while covering the surrounding area with soil is a fools project. It does no good at all.
- Trenching to install utilities severs tree roots. Remember, it is the roots of a tree, not its top, which are most important.
- Changing grades so that temporary or permanent ponding of water occurs usually results in suffocation of all roots in the pond due to lack of oxygen, and the tree dies.
- Wounding oak trunks and branches any time from early spring to late summer in areas where oak wilt disease exists, usually results in oak wilt infecting the tree. Damaging any tree trunk is detrimental to the health of the tree as it allows entry of disease and insect infestations.
- Bulldozers and "Bobcats" easily create tree wounds.

FOREST CONSERVATION NOTES

- Plan prepared by MAR-LEN FORESTRY 275 Barnhart Rd Westminster, MD 21158. 410-857-2322
- Concrete wash-off is designated on plan or shall be taken off site.
- Afforestation Area will be posted with "Reforestation Project" Signs every 100 feet and this area will be placed in a Forest Conservation Easement in perpetuity.
- Specimen tree No. 1, 2, 3, 5, and 6 will be removed due to grading

FOREST PROTECTION MEASURES

- All retention areas and isolated specimen trees shall be protected by highly visible, well anchored temporary protection devices as shown.
- All protection devices shall be in place prior to any grading or land clearing.
- All protection devices shall remain in place until all construction has ceased in immediate area.
- Devices shall be maintained throughout construction.
- Attachment of signs or any other object, to trees is prohibited.
- No equipment, machinery, vehicles, materials or excessive pedestrian traffic shall be allowed within protected areas.
- Pre Construction meeting: After the boundaries have been staked and flagged and before any disturbance, the developer, contractor or project manager and local inspector shall attend. Temporary parking, stockpile, staging and fueling area will be shown to all personnel.
- Any changes made to the Forest Conservation Plan due to On-Site conditions shall be made in consultation with a representative of the Department of Planning and Zoning (410) 313-2350.
- No burial of discarded materials will occur on-site within the conservation area.
- No open burning within 100 feet of a wooded area.
- All temporary Forest Protection structures will be removed after construction.
- Field edge determination will be performed along forested areas affected by construction.

Afforestation Plan

Afforestation required: 2.00
 Afforestation on-site: 2.00 Acres

Planting site overview
 The planting will enhance the stream buffer and buffer the nontidal wetlands. The site is currently dominated by forbs and grasses with a sparse population of woody shrubs. The dominant soils consist of Brandwine loam (BrD3) and Glenville silt loam (GnB2), both soils are well drained and moderately deep to bedrock, these soils have a slight rating when it comes to mortality for seedlings. Within the planting site is a small section of Balie silt loam (Ba), confined to the nontidal wetlands.

Planting material will conform to the current issue of "The American Standards for Nursery Stock", published by the "American Association of Nurserymen".
 The planting stock will be bare root seedlings on a 6" x 6" spacing, random distribution of stock.

Planting Area (2.00 acres)
 This area will require 1350 trees.

QUANTITY	SPECIE	SPACING
276	BLACK OAK/QUERCUS VELUTINA	8' x 8'
276	BLACK GUM/NYSSA SYLVATICA	8' x 8'
276	RED MAPLE/ACER RUBRUM	8' x 8'
276	WHITE DOGWOOD/CORNUS FLORIDA	8' x 8'
276	REDBUD/GERCIS CANADENSIS	8' x 8'

SITE PREP:
 Now entire area prior to planting if needed.
 Prepare holes, dibble bar, hand or machine planting and backfill with native soil, water and mulch trees using 2-4 inches to cover in and around the one foot square. The mulch will help retain moisture and reduce weed competition.
PLANTING SCHEDULE:
 Spring is the optimal time to plant, March-April.
CLEAN UP:
 All debris created from the afforestation activities shall be removed from the site within seven days of completion of planting.
PROTECTION DEVICES:
 The Planting site or afforestation area shall be protected with appropriate signs and fencing.

POST-CONSTRUCTION PHASE
 The following measures shall be taken when appropriate:
 1. Corrective measures if damages were incurred due to negligence:
 a. Stress reduction
 b. Removal of dead or dying trees: this may be done only if trees pose an immediate safety hazard.
 2. Removal of temporary structures: the following minimum standards shall be observed during the removal of temporary structures.
 a. No burial of discarded materials will occur on-site within the conservation area.
 b. No open burning within 100 feet of a wooded area.
 c. All temporary forest protection structures will be removed after construction.
 d. Follow procedures in Maintenance and Management agreement.

GENERAL GUIDANCE FOR MAINTENANCE OF PLANTED AREAS
 a. Watering: A watering plan should only be implemented to compensate for deficient rainfall patterns. Trees can die from too much water as well as too little. Newly planted trees may need water as much as once a week for the entire first growing season. The next two years, in contrast, may require watering only a few times a year (once a month during July and August). After that, trees should only need water in severe droughts. Bare root transplants, if sufficiently watered during planting, may not need water for almost 2-4 weeks after growth begins. Balled and burlap material may require more frequent watering.

Soil and Watering: Soil texture influences the downward flow of water. Soils with more clay tend to retain more water and can be watered less often; soils with more sand drain more quickly and need to be watered more often. For examples of on-site evaluation recommendations, if the soil was well prepared before planting, there should be few drainage problems. Restricted downward penetration indicates the soil may have been compacted during construction and not aerated before planting, or there may be a clay hardpan.

How to Water: The best way to water is deeply and slowly using a regular hose, a soaker hose, or drip irrigation. For larger trees, start by watering the root ball thoroughly. The watered area shall be enlarged to include the whole root zone as the tree becomes more established. Mulching around the base of newly transplanted trees prevents roots from drying too quickly while providing air movement to the roots.

b. Fertilizing: Fertilizing is the chemical modification of soils to correct for a specific nutrient deficiency. These deficiencies are most effectively identified in a laboratory soils analysis. Nothing should be added to the soil without first testing to determine any nutrient needs.
 What Nutrients to Apply: Trees depend on three major nutrients, nitrogen, phosphorous and potassium and a host of other minor ones (or micro-nutrients) such as calcium, magnesium and iron. In most soils, most of the micro-nutrients are available in abundance. Of the major nutrients, nitrogen is usually the limiting one.
 When to Fertilize: Even when soils are deficient in nitrogen, fertilizing within the first growing season after planting is not recommended. Too much nitrogen may cause a spurt of canopy growth which the roots cannot support. It is therefore, best to wait until after the end of the first growing season, either in the late fall or early spring.
 What Type of Fertilizer: Organic fertilizers are preferred to synthetic fertilizers. Bone meal or seaweed based products are available commercially. Organic fertilizers have a slow-release effect that can supply nutrients to the plant as needed while minimizing the risk of excessive nutrients entering the forest system and water supply.

c. Control of Competing Vegetation: Unfortunately, good sites for reforestation and afforestation are generally good sites for unwanted vegetation as well. Unwanted vegetation growing near newly planted trees can take over the site. The need to control this problem depends on the ability of the plant material to withstand the intrusion. Smaller trees may need more care, although some seedlings survive with the overgrowth and will shade it out as the trees grow. As a preventative measure, consider the potential for growth of invasive species.


d. Protection: Pests, Disease and Mechanical Injury: Integrated pest management (IPM) is one of the most effective and safest approaches for maintaining a healthy forest. IPM basics include proper species selection for the site, good pruning, mulching and fertilizing practices, regular monitoring, and proper timing of necessary sprays. Good cultural practices will minimize the amount of spraying. Professional IPM programs have reduced pesticide use by 90%. Some aspects of a full IPM program include:

- Elimination of some low vegetation before planting to help control the rodent population which thrives in brushy environment.
- Use of tree shelters to protect the trunks of seedlings or whips from animal damage. The shelters act as mini-greenhouses to speed growth. These trees need more water than those planted without tree shelters.
- Mulching around the trees to minimize trunk damage from mowers. Mounds provide an entryway for pests.
- Pruning dead and disease branches to prevent establishment or spreading of disease.

INSPECTION CHECKLIST
 ___ Pest or disease infestations
 ___ Inhibited or stunted growth
 ___ Binding or restriction due to stakes or ties
 ___ Broken, dead, or diseased branches
 ___ Wilted, curled, or distorted leaves or dried out buds
 ___ Leaf color abnormalities (spots, yellowing, or brown margins);
 ___ Cracks in bark from sunburn
 ___ Sucker growth at the base or on side of the tree's trunk
 ___ Holes or substances oozing from the trunk
 ___ Dead or dying trees nearby, which may infect surrounding vegetation
 ___ Severe erosion, sunken holes in the root-ball area, or an inadequate watering basin that threatens the young tree's water supply
 ___ Flooding or poor drainage
 ___ Surface roots beginning to grow
 ___ Algae or mosses around tree base, indicating excess watering
 ___ A layer of soot or particulate matter from air pollution
 ___ Invasive plant growth threatening viability of planting
 ___ Improper use or intrusions into forest conservation areas
 ___ Missing or damaged protective measures (fences, signs, etc.)
 ___ Unauthorized clearing or other removal of forest vegetation

PLANTING INSPECTION FORM
 SITE NAME: _____
 INSPECTED BY: _____
 IS REINFORCEMENT PLANTING NEEDED? _____ % SURVIVAL _____ %
 CAUSE OF MORTALITY: _____

 COMMENTS: _____



MAINTENANCE SCHEDULE and Management agreement-Post Construction
 1. Plant material will be planted in rows 8 feet apart and have a spacing of feet, as specified.
 2. The intent is to plant 1350 trees- 75% survival- 1035 plants, at the end of two growing seasons.
 3. Plant material source: KIR-MAR TREE COMPANY
 3410 Kirby Country Dr.
 Taneytown, Md 21157
 410-876-8133
 4. Contact Person for site visit: Catonsville Builders
 4025 Chevrolet Drive
 Ellicott City, Md 21042

Maintenance and Management Agreement
 A. For a period of two growing seasons, from the time of planting, landowner/developer will ensure 75% survival rate of total number of trees planted (1035). Within that period any trees dying or in a severely weakened condition will be replaced in the first available planting window.
 B. Watering and fertilizing will be performed on an as needed basis and be carried out by the contractor/developer to insure survival of at least 75%.
 C. Control of competing vegetation will be carried out at least twice annually, during this 24 month or two growing seasons, maintenance agreement.
 D. Pest, disease and mechanical injury will be addressed in the following manner. Mulching the trees will help protect the trees from mechanical damage as it provides some guidance to the person mowing. Pest and disease inspections will be performed annually throughout the maintenance agreement.

INSPECTIONS: Certification of Completion
 A. Within one month of the completed planting, a qualified professional, designated by the developer, will perform an initial inspection, inspecting the status of all forest retention, reforestation and afforestation areas, to certify that the planting is completed and all forest protection measures have been installed as required by the Forest Conservation Plan. Planting must occur before June 30th to be credited toward the current growing season. A certification document will be sent to Department of Planning and Zoning upon review of the certification document for completeness and accuracy the Department will notify the developer of the beginning of the Post-Construction Management period.
 B. At the end of the first growing season, the qualified professional will make another inspection to check survival rate. If the planting survival rate is below 90%, landowner/developer will re-enforce the planting to a minimum of 90% of planting (996 trees), at the beginning of second growing season.
 C. Planting inspections will be carried out for the entire two growing seasons, during each growing season and continue until the final inspection, upon which time a 75% survival rate will be insured. If at the end of the second growing season, survival rate drops below 75%, such material as needed to guarantee a 75% survival rate by the end of the third season, shall be installed.
 D. The occupants of a new development, must avoid activities that destroy or degrade protected forest resources, a plan must be shown to all new owners, exhibiting the afforestation area, so they are aware of the protected area, along with a description of permitted and prohibited activities within the area.
 E. Final Inspection and Release of Obligation
 At the end of the post-construction management and protection period, the designated responsible party shall convey to the Department of Planning and Zoning certification that all forest conservation areas have remained intact or have been restored to the appropriate condition, that the stipulated survival rates have been achieved, and that any permanent protection measures required by the plan are in place. Upon review of the final certification document, the county will notify the developer of release of surety and all future obligations. The developer's last official responsibility will be to transmit a copy of this notification to the owner(s) of the property(ies). Such transmittal will serve as official notice to owners of their assumption of full responsibility for all future forest conservation obligations.

FOREST RETENTION AREA
 MACHINERY, DUMPING OR STORAGE OF ANY MATERIALS IS PROHIBITED
 VIOLATORS ARE SUBJECT TO FINES AS IMPOSED BY THE MARYLAND FOREST CONSERVATION ACT OF 1991
 PLACED APPROXIMATELY EVERY 100 FT.


SPECIMEN TREE DO NOT REMOVE
 MACHINERY, DUMPING OR STORAGE OF ANY MATERIALS IS PROHIBITED
 VIOLATORS ARE SUBJECT TO FINES AS IMPOSED BY THE MARYLAND FOREST CONSERVATION ACT OF 1991
 TWO PER TREE

Forest Conservation Area
REFORESTATION PROJECT
 Trees for Your Future
 PLACED APPROXIMATELY EVERY 100 FT.

REFORESTATION AND AFFORESTATION AREA PROTECTION SIGN DETAILS

BARE ROOT PLANTING TECHNIQUES

PLANTING WITH DIBBLE BAR



APPROVED:
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
 Howard M. Daniels
 CHIEF, BUREAU OF HIGHWAYS
 2-25-07
 DATE

APPROVED:
 HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
 Cindy Hromek
 CHIEF, DIVISION OF LAND DEVELOPMENT
 3/4/08
 DATE
 Chief, Development Engineering Division
 2/28/07
 DATE











FINAL FOREST CONSERVATION PLAN NOTES
CARLEE MANOR
 LOTS 1 THROUGH 26 AND NON-BUILDABLE PARCEL "A"
 TAX MAP 17, GRID 14, PARCEL 123
 SECTION DISTRICT, HOWARD COUNTY, MARYLAND

CLSI
 Carroll Land Services
 INCORPORATED
 Engineers * Surveyors * Land Development Consultants
 Landscape Architects * Environmental Specialists
 439 East Main Street Westminster, MD 21157-5539
 (410) 876-2017 FAX (410) 876-0009

LEONARD H. WHEEL
 MD REG. PROFESSIONAL FORESTER NO.192

Date	Revisions	Drawn By: LGS/SJG
		Designed By: GE
		Reviewed By: GE
		Date: JAN, 2009
		Scale: AS SHOWN
		Job No: 41250A
		Sheet: 22 OF 24

CAD Drawing File Name: d:\17230\adm\conserv\forestry\02\Forestnotes 1.dwg



OWNER
TRUST U/A CARLEE JONES
BRANCH BANKING
& TRUST CO., TRUSTEE
C/O WILLIAM J. GERING
P.O. BOX 1100
WESTMINSTER, MD 21158
410-857-3430

DEVELOPER
C.J. PROPERTY L.L.C.
10753 BIRMINGHAM WAY
WOODSTOCK, MD. 21163
410-750-1200

APPROVED:
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Richard M. Daniels
CHIEF, BUREAU OF HIGHWAYS 148
2-25-03 DATE


APPROVED:
HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING
Chris Hamilton
CHIEF, DIVISION OF LAND DEVELOPMENT 148
2/1/03 DATE

Chris Hamilton
CHIEF, DEVELOPMENT ENGINEERING DIVISION 96
2/20/03 DATE

RETAINING WALL DETAILS
CARLEE MANOR
LOTS 1 THROUGH 26 AND
NON-BUILDABLE PARCEL 'A'
TAX MAP 17, GRID 19, PARCEL 123
2 nd. ELECTION DISTRICT HOWARD COUNTY, MARYLAND

CLSI
Carroll Land Services
INCORPORATED
Engineers • Surveyors • Land Development Consultants
Landscape Architects • Environmental Specialists
439 East Main Street Westminster, MD 21157-5539
(410) 876-2017 FAX (410) 876-0009

Date	Revisions	Drawn By: BM
		Designed By: AJD/LGD
		Reviewed By: AJD/ALH
		Date: JAN. 2003
		Scale:
		Job No. 91280A
		Sheet: 24 of 24



WALL DESIGN PROVIDED BY
HLLB-GARNES ASSOCIATES
OF FREDERICK, INC.

CAD Drawing File Name: g:\17290\dm\const\stdplans\