

SHEET No


1 of 5


3 of 5


4 of 5


5 of 5

F-02-109









MARYLAND FOREST

ONSERVATION ACT OF 1991

10" DEH TREE 10" RADIUS CRZ

30" DBH TREE 45' RADIUS CRZ

MARYLAND FOREST

CONSERVATION ACT OF 1991

BLAZE ORANGE PLASTIC MESH CAL TREE PROTECTION FENCE DETAIL

This Forest Conservation Plan has been developed in accordance with the Howard County Forest Conservation Manual and the 1991 Forest Conservation Act.

The existing site consists of 1.90 acres. The site has 0.69 acres of existing forest within the net tract area. 0.33 acres of existing forest will be cleared. Retention areas have been prioritized to provide protection to the largest area of forest possible. 0.36 acres of woodland will be retained under easement in these areas. A fee-in-lieu is requested to fulfill the reforestation obligations of 0.12 ac (5227 sq ft).

THE FOREST CONSERVATION EASEMENTS WILL BE ESTABLISHED TO FULFILL THE REQUIREMENTS OF SECTION 16,1200 OF THE HOWARD COUNTY CODE. NO CLEARING, GRADING, OR CONSTRUCTION IS PERMITTED WITHIN THE FOREST CONSERVATION EASEMENTS, HOWEVER, FOREST MANAGEMENT PRACTICES AS DEFINED IN THE DEED OF FOREST CONSERVATION EASEMENT ARE ALLOWED.

Surety in the amount of \$3,136.32 (15,681.6 s.f. X \$0.20/s.f.) will be posted as part of the developers agreement.

# FOREST CONSERVATION WORKSHEET

(1/100 ac.) A. Total Tract Area B. Area Within 100 Year Floodpla C. Other deductions Land Use Category: High Density Residential E. Afforestation Minimum (15% x D) F. Conservation Threshold (20% x D) Existing Forest Cover G. Existing Forest on Net Tract Area H. Forest Area Above Conservation Threshold I. Forest Retention Mitigation J. Clearing Permitted without Mitigation Proposed Forest Clearing

#### Planting Requirements

M. Reforestation for Clearing Above Threshold N. Reforestation for Clearing Below the Threshold P. Credit for Retention Above Conservation Threshold 0 Q. Total Reforestation Required R. Total Afforestation Required

FOREST CONSERVATION EASEMENT TABLE Easement #1 0.36 ac

Surety in the amount of \$3,136.32 will be posted as part of the Developers Agreement.

#### ROOT PRUNING

Retention areas shall be set prior to construction 2. Boundaries of retention areas shall be flagged, and location of trench shall be specified by ERI Qualified Professional. 3. Roots shall be cut cleanly with root pruning equipment. Where roots >1" are found, trenching shall be done by air spade or hand tools. Roots >1" shall be cut with a hand saw. 4. Trench shall be immediately backfilled with soil removed or high

organic content soil.

5. Any other techniques shall be approved by the ERI Qualified Professional before implementation. — Tree Protection Fence -6"-12" from trench to fence -12"± from LOD minimum depth 6" maximum width CRITICAL ROOT ZONE

EXPLORATION RESEARCH, INC

#### MANAGEMENT NOTES FOR FOREST RETENTION AREAS

I. All proposed activities shall adhere to the conditions, schedules and terms of an approved sediment control and erosion plan.

2. After the boundaries of the retention area have been staked and flagged and before any disturbance has taken place on-site, a preconstruction meeting at the construction site shall take place. The developer, contractor or project manager, and appropriate County inspectors shall attend.

3. Prior to grading, the contractor shall arrange to meet with the forester to determine adequate protection measures for Specimen Trees located on buildable lots.

4. Tree protection for all retained areas:

a. All retention areas within 50 feet of proposed construction activities shall be protected by highly visible, well anchored temporary protection devices (silt fence or biaze orange plastic mesh).

b. All protection devices shall be in place prior to any grading or land clearing.

c. All protection devices shall be properly maintained and shall remain in place until construction has ceased.

d. Attachment of signs, fencing or other objects to trees is prohibited. e. No equipment, machinery, vehicles, materials or excessive pedestrian traffic

shall be allowed within protected areas. 5. If the critical root zone (see detail) is affected by construction activities such as

grade change, digging for foundations and roads or utility installation: a. Prune roots with a clean cut using proper pruning equipment (see root pruning

b. Water and fertilize as needed.

6. During construction phase, monitor and correct condition of retained trees for: soil compaction, root injury, flood conditions, drought conditions and other stress signs.

a. Inspect existing trees around the perimeter of disturbed limits for evidence of soil compaction, root injury, limb injury, or other stress signs and correct with proper management techniques such as root or limb pruning, soil aeration, fertilization, crown reduction or watering. Inspection and evaluation shall be performed by a licensed

b. Inspect for dead or dying trees or limbs which may pose safety hazard and

c. No burial of discarded materials will occur onsite within the conservation areas.

d. No burning within 100 feet of wooded area.

e. All temporary forest protection structures will be removed after construction. Replace any temporary signage with permanent signage around easements.

f. Following completion of construction, prior to use, the County inspector shall inspect the entire area.

### Soil Protection Zone Notes

7. Post-Construction Phase

1. The Soil Protection Zone shall include all areas contained inside the Limit of Disturbance. 2. Where possible, the Soil Protection Zone shall extend to the drip line of specimen trees. For other groups of trees, the zone shall be the drip line or 40% of the height of the tree, whichever is greater. 3. No construction activity is permitted within the Soil Protection Zone. 4. If soil has been compacted or grading has taken place in the vicinity of the Soil Protection Zone, root pruning shall be implemented per Root Pruning detail, shown on this plan. 5. Root pruning shall occur prior to the beginning of construction. 6. Where the Soil Protection Zone must encroach inside the Critical Root

Zone of a tree, soil disturbance shall be mitigated with vertical mulching, radial trenching, or another method approved by the ERI Forest Conservation Professional. '. Prior to contruction, the Limits of Disturbance shall be marked and the ERI Professional shall determine which trees will need preventative

treatment or removal. 8. Tree maintenance and removal shall be undertaken by a qualified MD Tree Expert to ensure damage to surrounding trees is minimized. 9. Brush and limbs removed for construction shall be chipped and spread at the edge of the Soil Protection Zone to a depth of 6 inches. This shall occur outside the Soil Protection Zone where compaction could impact otherwise unprotected Critical Root Zone.

#### OWNER/DEVELOPER

CORNERSTONE HOLDINGS LLC 9691 NORFOLK AVENUE LAUREL, MD 20723

## FOREST CONSERVATION PLAN ARBOR OVERLOOK

LOTS 1 THRU 7 AND OPEN SPACE LOT 8

TAX MAP 37 GRID 20 3rd ELECTION DISTRICT

PARCEL 148 HOWARD COUNTY, MARYLAND



# Engineers Planners Surveyors 8318 Forrest Street Ellicott City, MD 21043 Tel:410-750-2251 Fax: 410-750-7350

DESIGN BY: \_\_\_MLT DRAWN BY: \_\_RAB CHECKED BY: SLH SCALE: 1"=30" DATE: Oct 23, 2002 E-mail: FSHAssociates@cs.com W.O. No.: \_\_\_\_3021\_

SHEET No. \_5\_OF\_5

CHIEF, DIVISION OF LAND DEVELOPMENT

mut Engineering Division

DATE