

There is no floodplain on the Sowers Property.

0.08 AC Ba

Hardwood

Hardwood

VICINITY MAP

ON OF LAND DEVELOPMENT

Offsite Mixed

Key	Name	Scientific Name	Size	Condition
ST-I	Tulip Poplar	Liriodendron tulipifera	32"	Good
ST-2	Red Maple	Acer rubrum	30"	Good

Hardwood

Hardwood

Wetland Hardwood

Upland Hardwood

GIC3 Oaks and

SPECIMEN TREES

CIC3 Oaks and

CmB2 Upland

Easement 1 Retention 0.41 Ac. Forest Retention Area Specimen Tree

SPECIMEN

TREE

55-64 pines


75-84 pines

65-74 oaks

75-84 oaks

Fair

Good



Austrian 5%

Black

Gum Black

Cherry Red Maple

same as

8-14 in

10% 4-6 in.

15% 4-8 in.

20% 18-24 in.

same as 100± Good

**FOREST** 

RETENTION

AREA

OR STORAGE OF

ANY MATERIALS IS

PROHIBITED

VIOLATORS ARE SUBJECT TO FINES AS IMPOSED BY THE MARYLAND FOREST CONSERVATION ACT OF 1991

SCALE: 1"=2000' APPROVED: HOWARD\_COUNTY DEPARTMENT OF PLANNING AND ZONING

VIOLATORS ARE SUBJECT TO FINES AS IMPOSED BY THE MARYLAND FOREST CONSERVATION ACT OF 1991 Surety in the amount of \$3,571.92 will be posted with the Developers Agreement. (0.41 ac/17,859.6 sf @ EXPLORATION RESEARCH, INC. \$0.20/sf) NVIRONMENTAL CONSULTANTS LANDSCAPE ARCHITECTS

8318 FORREST STREET ELLICOTT CITY, MARYLAND 21043 (410) 750-1150 FAE (410) 750-7360

Forest Conservation Easement Table

streams,

and steep

0.41 Ac.

stream buffers,


For isolated specimen trees: I' DBH = 1.5 ' radius of the critical root zone

6" DBH TREE 8' RADIUS CRZ 30" DBH TREE 45' RADIUS CRZ 10' RADIUS CRZ

-2' minimum depth 6" maximum width CRITICAL ROOT ZONE

		(1/100 )
	Net Tract Area	(1/100 ac.)
I. Retention areas shall be set prior to construction	A. Total Tract Area	1.72
2. Boundaries of retention areas shall be flagged, and location of	B. Area Within 100 Year Floodplain	0
trench shall be specified by ERI Qualified Professional.	C. Other deductions	0
3. Roots shall be cut cleanly with root pruning equipment. Where roots >1" are found, trenching shall be done by air spade or hand tools. Roots >1" shall be cut with a hand saw.	D. Net Tract Area	1.72
	Land Use Category Residential -Suburban	
4. Trench shall be immediately backfilled with soil removed or high organic content soil.	E. Afforestation Minimum (15 % x D)	0.26
5. Any other techniques shall be approved by the ERI Qualified	F. Conservation Threshold (20 % x D)	0.34
Professional before implementation.	Existing Forest Cover	
Tree Protection Fence	G. Existing Forest on Net Tract Area	0.85
/-6"-12" from trench to fence	H. Forest Area Above Conservation Threshold	0.51
50 ) // -12"± from LOD	Breakeven Point	
{	1. Forest Retention for no Mitigation	0.45
\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	J. Clearing Permitted without Mitigation	0.40
{	Proposed Forest Clearing	
	K. Forest Areas to be Cleared	0.44
4   g	L. Forest Areas to be Retained	0.41
) (       +   =	Planting Requirements	
	M. Reforestation for Clearing Above Threshold	0.11
	N. Reforestation for Clearing Below the Threshold	0
	P. Credit for Retention Above Conservation Thresho	ld 0.07
	Q. Total Reforestation Required	0.04
2' minimum depth	R. Total Afforestation Required	0
6" maximum width	S Total Reforestation and Afforestation Requirement	t 0.04
' CRITICAL ROOT ZONE '		

BLAZE ORANGE PLASTIC MESH



TREE PROTECTION DETAIL

with vertical mulching, radial trenching, or another method approved by the ERI Forest Conservation Professional. 7. Prior to contruction, the Limits of Disturbance shall be marked and the ERI Professional shall determine which trees will need preventative treatment or removal. 8. Tree maintenance and removal shall be undertaken by a qualified MD Tree Expert to ensure damage to surrounding trees is NOTES:

1. The Soil Protection Zone shall include all areas contained inside

2. Where possible, the Soil Protection Zone shall extend to the

drip line of specimen trees. For other groups of trees, the zone

3. No construction activity is permitted within the Soil Protection

4. If soil has been compacted or grading has taken place in the

5. Root pruning shall occur prior to the beginning of construction.

Critical Root Zone of a tree, soil disturbance shall be mitigated

6. Where the Soil Protection Zone must encroach inside the

vicinity of the Soil Protection Zone, root pruning shall be

implemented per Root Pruning detail, shown on this plan.

shall be the drip line or 40% of the height of the tree, whichever

Soil Protection Zone Notes

the Limit of Disturbance.

is greater.

9 Brush and limbs removed for construction shall be chipped and spread at the edge of the Soil Protection Zone to a depth of 6 inches. This shall occur outside the Soil Protection Zone where compaction could impact otherwise unprotected Critical Root Zone.

Forest Conservation Narrative

This Forest Conservation Plan has been developed in accordance with the Howard USE 2" × 4" County Forest Conservation Manual and the CROSS BACKING 1991 Forest Conservation Act.

> The existing site consists of 1.72 acres. The site has 0.85 acres of existing forest within the net tract area. An easement will be established to retain 0.41 ac. Specimen trees will be protected where possible. Due to the small size of the site no on-site forest mitigation is possible. We are requesting a fee-in-lieu payment of \$871.20 for the remaining 0.04 ac. (1742.4 sf) of required mitigation.

> > OWNER Christine N. Harris and Daniel S. Kessler 10475 Scaggsville Road Laurel, Maryland 20723

DEVELOPER Scaggsville Road Investment, LLP c/o Brian D. Boy 9691 Norfolk Avenue

Laurel, Maryland 20723

Tel.: (410)792-2565 Fax: (410)792-2567

COMBINED FOREST STAND DELINEATION AND FOREST CONSERVATION PLAN

## THE HILLSIDE AT ROCKY GORGE III

LOTS 1, 2 AND OPEN SPACE LOT 3 A RESUBDIVISION OF LOT 2, KVESETH ADDITION

TO TOWER ACRES PLAT NO. 3818 TAX MAP 46, GRID 18

**FSH Associates** Engineers Planners Surveyors 8318 Forrest Street Ellicott City, MD 21043 Tel:410-750-2251 Fax: 410-750-7350 E-mail: FSHAssociates@cs.com

PARCEL 326 HOWARD COUNTY, MARYLAND

F-03-29

c. No burial of discarded materials will occur onsite within the

crown reduction or watering. Inspection and evaluation shall be performed by a licensed arborist.

LEGEND

Existing Contour

Proposed Contour · Spot Elevation

Direction of Flow

Prop. Shade Tree Per Plan F-

Prop. Dwelling

15% to 24.9% slopes

MANAGEMENT NOTES FOR FOREST RETENTION AREAS

and terms of an approved sediment control and erosion plan.

activities shall be protected by highly visible, well anchored

temporary protection devices (silt fence or blaze orange plastic

County inspectors shall attend.

or land clearing.

utility installation:

3. Tree protection for all retained areas:

remain in place until construction has ceased.

equipment (see root pruning detail)

6. Post-Construction Phase

safety hazard and remove.

b. Water and fertilize as needed.

drought conditions and other stress signs.

flagged and before any disturbance has taken place on-site, a preconstruction meeting at the construction site shall take place. The developer, contractor or project manager, and appropriate

1. All proposed activities shall adhere to the conditions, schedules

2. After the boundaries of the retention area have been staked and

a. All retention areas within 50 feet of proposed construction

b. All protection devices shall be in place prior to any grading

c. All protection devices shall be properly maintained and shall

d. Attachment of signs, fencing or other objects to trees is

e. No equipment, machinery, vehicles, materials or excessive

4. If the critical root zone (see detail) is affected by construction activities such as grade change, digging for foundations and roads or

pedestrian traffic shall be allowed within protected areas.

a. Prune roots with a clean cut using proper pruning

5. During construction phase, monitor and correct condition of

a. Inspect existing trees around the perimeter of disturbed

b. Inspect for dead or dying trees or limbs which may pose

limb pruning, soil aeration, fertilization,

limits for evidence of soil compaction, root injury, limb injury, or other stress signs and correct with proper management techniques

slopes of 25% or greater

 $\sim$ 

d. No burning within 100 feet of wooded area.

e. All temporary forest protection structures will be removed after construction. Permanent signage will be installed in

f. Following completion of construction, prior to use, the County inspector shall inspect the entire area.

Forest Stand Narrative

FI This 0.85 Acre forest is well developed on the interior and young near the edges. The overstory contains tulip poplar, red maple, black cherry as well as small quantities of Austrian Pine, Black Gum and red and white oak. The middle-story contains tulip poplar, American holly, black gum, black cherry, and sassafras. In the understory, raspberry, pokeweed, yucca, Virginia creeper, multiflora rose, Japanese honeysuckle, black cherry, and tulip poplar are found. The stand is in good health without significant invasive infestation.

LI The remainder of the site, 0.87 Ac., is lawn with scattered individual trees.

6TH ELECTION DISTRICT

DESIGN BY: PS/KO DRAWN BY: AB CHECKED BY: \_\_SLH\_ SCALE: 1"=50' DATE: <u>Mar. 11, 2003</u> W.O. No.: 3050 SHEET No. \_ 1 OF \_ 1