


THERMOPLASTIC PAVEMENT MARKING LEGEND

(SDY)	5" YELLOW COUBLE SOLID LINE
(SW)	5" WHITE SOLID LINE
(24W)	24" PREFORMED THERMOPLASTIC WHITE (STOPLINE)


NOTES:
 1. ALL PAVEMENT MARKINGS NOT DETAILED ARE EXISTING AND SHALL REMAIN.




THE SWMF TO BE OWNED BY MDSHA, AND MAINTAINED BY HOA L. F.

LEGEND:

(---)	EXISTING CONTOUR
(---)	PROPOSED CONTOUR
(---)	PROPOSED SPOT ELEVATION
(---)	EXISTING SPOT ELEVATION
(---)	EXISTING CURB AND GUTTER
(---)	EXISTING UTILITY POLE
(---)	EXISTING LIGHT POLE
(---)	EXISTING MAILBOX
(---)	EXISTING SIGN
(---)	EXISTING SANITARY MANHOLE
(---)	EXISTING SANITARY LINE
(---)	EXISTING CLEANOUT
(---)	EXISTING FIRE HYDRANT
(---)	EXISTING WATER LINE
(---)	EXISTING FENCE
(---)	PROPERTY LINE
(---)	RIGHT-OF-WAY LINE
(---)	SOILS BOUNDARY
(---)	PROPOSED STORM DRAIN
(---)	PROPOSED STORM DRAIN INLET
(---)	PROPOSED SIDEWALK
(---)	PROPOSED STREET LIGHT



MD. TYPE 'A' CONCRETE COMBINATION CURB AND GUTTER
 MD. NO. 620.02
 NOT TO SCALE




NOTE: REFER TO DETAIL 7 ON THIS SHEET FOR VERTICAL CURB DETAIL.

PARCEL A
 17.70 AC.
 ZONED CAC
 USE: RESIDENTIAL

ROAD PLAN
 SCALE: 1"=50'

CURVE TABLE

CURVE	RADIUS	LENGTH	DELTA ANGLE	TANGENT	CHORD DIRECTION	CHORD LENGTH
C1	300.00	422.81	80°45'01"	303.54	N15°47'53"E	388.67
C2	288.00	368.08	75°51'40"	216.65	N18°14'34"E	341.78
C3	322.00	345.65	61°31'14"	191.59	N25°25'16"E	329.29



NOTE: ALL STREET LIGHTS WILL BE 250-WALL HPS VAPOR PENDANT FIXTURE (SAG) MOUNTED AT 30' ON BRONZE FIBERGLASS POLE USING 12' ARM.

ROAD CLASSIFICATION

STREET NAME	CLASSIFICATION	DESIGN SPEED	LIMITS
SELNICK DRIVE	LOCAL ROAD	30 MPH	15
RED CLAY FORGE	LOCAL ROAD	30 MPH	15
U.S. ROUTE 1	INTERMEDIATE ARTERIAL	50 MPH	15


APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
W. F. Mohr 10-19-06
 CHIEF, BUREAU OF HIGHWAYS DATE

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING
Chris Home 10/23/06
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE

NO.	REVISION	DATE



FINAL ROAD CONSTRUCTION PLANS
ROAD PLAN & PAVEMENT MARKING
BELMONT STATION
 PARCELS 'A', 'B' & 'C' & OPEN SPACE LOT 1
 REF: WP-04-152, WP-06-79, S-04-10, P-05-17, F-06-169
 TAX MAP 37, BLOCK 18, 1ST ELECTION DISTRICT
 PARCEL 198, 188, 189
 HOWARD COUNTY, MARYLAND

ROBERT H. VOGEL ENGINEERING, INC.
 ENGINEERS • SURVEYORS • PLANNERS
 8407 MAIN STREET
 ELLICOTT CITY, MD 21043
 TEL: 410.461.7666
 FAX: 410.461.8961




DESIGN BY: WJZ
 DRAWN BY: DZ
 CHECKED BY: _____
 DATE: OCTOBER 2006
 SCALE: 1"=50'
 W.O. NO.: 04-08


2 SHEET OF 14




ROAD PROFILE
SCALE: HOR. 1"=50'
VERT. 1"=5'




CURB FILLET PROFILE
SOUTH OF INTERSECTION OF SELNICK DRIVE AND RED CLAY FORGE
SCALE: HOR. 1"=20'
VERT. 1"=2'



DRIVEWAY PROFILE
SCALE: HOR. 1"=50'
VERT. 1"=5'



ROAD PROFILE
SCALE: HOR. 1"=50'
VERT. 1"=5'




CURB FILLET PROFILE
INTERSECTION OF SELNICK DRIVE AND SANTA BARBARA
SCALE: HOR. 1"=20'
VERT. 1"=2'


OWNER/DEVELOPER
ELKRIDGE DEVELOPMENT, LLC
301 TRANSYLVANIA AVENUE
RALEIGH, NC 27609
(919) 789-9289
ELKRIDGE DEVELOPMENT NO.2, LLC
301 TRANSYLVANIA AVENUE
RALEIGH, NC 27609
(919) 789-9289

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Willie F. Mable 10-19-06
CHIEF, BUREAU OF HIGHWAYS DATE


APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING
Cheryl Hantz 10/23/06
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE
Candice Hantz 10/24/06
CHIEF, DIVISION OF LAND DEVELOPMENT DATE



CURB FILLET PROFILE
NORTH OF INTERSECTION OF SELNICK DRIVE AND RED CLAY FORGE
SCALE: HOR. 1"=20'
VERT. 1"=2'



TYPICAL ROADWAY SECTION
SELNICK DRIVE EXTENSION
LIMITS OF CONSTRUCTION:
E STA. 720+29 TO E STA. 729+10
(SECTION NOT TO SCALE)
SUPERELEVATION (MAX. E=0.04)
BEGINS AT STATION 723+65 & ENDS BEYOND THE LIMITS OF THIS CONTRACT
DESIGN SPEED: 30 MPH
ROAD CLASSIFICATION: LOCAL ROAD



TYPICAL ROADWAY SECTION
RED CLAY FORGE
LIMITS OF CONSTRUCTION:
E STA. 0+009 TO E STA. 1+21.89
DESIGN SPEED: 30 MPH
ROAD CLASSIFICATION: LOCAL ROAD

NO.	REVISION	DATE


FINAL ROAD CONSTRUCTION PLANS
ROAD PROFILE
SELNICK DRIVE AND RED CLAY FORGE
BELMONT STATION
PARCELS 'A', 'B' & 'C' & OPEN SPACE LOT 1
REF: WP-04-152, WP-06-79, S-04-10, P-05-17, F-06-169
TAX MAP 37 BLOCK 18 PARCEL 196, 198, 199
1ST ELECTION DISTRICT HOWARD COUNTY, MARYLAND

ROBERT H. VOGEL ENGINEERING, INC.
ENGINEERS • SURVEYORS • PLANNERS
8407 MAIN STREET TEL: 410.461.7666
ELLCOTT CITY, MD 21043 FAX: 410.461.8961

DESIGN BY: WJZ
DRAWN BY: DZ
CHECKED BY: _____
DATE: OCTOBER 2006
SCALE: AS SHOWN
W.O. NO.: 04-08

3 SHEET OF 14

BALTIMORE WASHINGTON BOULEVARD (U.S. ROUTE 1)
 VARIABLE WIDTH RIGHT-OF-WAY
 INTERMEDIATE ARTERIAL
 SRC PLATS NOS. 5549 AND 51905, PLAT 11810 HOWARD COUNTY, MARYLAND LAND RECORDS



STORMWATER MANAGEMENT REQUIREMENTS (SP#2)

AREA	REQUIREMENT	VOLUME/CFS WITHOUT CREDITS	CREDITS	VOLUME REQUIREMENT WITH CREDITS	NOTES
0.83	WATER QUALITY VOLUME (WQv)	SEE NOTE	---	SEE NOTE	THIS IS PROVIDED FOR IN BMP#1 AND ANALYSIS AT SP#1 DUE TO NECESSARY VERTICAL ALIGNMENT OF ROAD AND LIMITED R-0-W
1	DEVELOPED AREAS	---	---	---	---
2	RECHARGE VOLUME (REV)	0.06 AC. FT. OR 0.50 AC. FT. (TOTAL SELNICK DRIVE DEVELOPMENT)	0.04 AC. FT.	0.00 AC. FT.	GRASS CHANNEL ALONG SELNICK DRIVE, SP#1 PROVIDES 0.04 OF CREDIT FOR REMAINDER OF REV CREDIT, 0.54 PROVIDED BY ANALYSIS OF SP#1
3	CHANNEL PROTECTION VOLUME* (CPV)	N/A	---	N/A	TYR PEAK FLOODING OCCURS IN CHANNELS LESS THAN REQUIRED 2' SEE FOR CIP
4	OVERHEAD FLOOD PROTECTION* (OF)	REQUIRED	---	PROVIDED	---
5	EXTREME FLOOD VOLUME* (EFV)	3.79 CFS	0.61 CFS (FROM TR-20, BYPASS+UNMANAGED)	2.99 CFS UNMANAGED	0.61 CFS BYPASS 2.99 CFS UNMANAGED
6	EXISTING PROVIDED	6.80 CFS	1.16 CFS (FROM TR-20, BYPASS+UNMANAGED)	5.10 CFS UNMANAGED	1.16 CFS BYPASS 5.10 CFS UNMANAGED

WQV FOR DEVELOPMENT OF SELNICK DRIVE TO SP#2 IS PROVIDED AT BMP#1. REV (PERCENT AREA METHOD) IS PROVIDED IN GRASS CHANNELS ALONG SELNICK DRIVE, (0.04 AC. TO SP#2 AND 0.54 AC. TO SP#1). CIP IS NOT REQUIRED AT SP#2 SINCE THE TYR PEAK DEVELOPMENT Q OF 0.13 CFS IS LESS THAN 2 CFS. THE POST DEVELOPMENT DISCHARGES OF Q1 AND Q2 ARE LESS THAN THE EXISTING DISCHARGES, THEREFORE NO MANAGEMENT IS PROPOSED.

STORMWATER MANAGEMENT REQUIREMENTS, FACILITY (SP#1)

AREA	REQUIREMENT	VOLUME/CFS WITHOUT CREDITS	CREDITS	VOLUME REQUIREMENT WITH CREDITS	NOTES
6.45 AC.	WATER QUALITY VOLUME (WQv)	0.24 AC. FT.	---	0.24 AC. FT.	0.17 IS PROVIDED BELOW CIP
1	DEVELOPED AREAS	---	---	---	---
2	RECHARGE VOLUME (REV)	0.056 AC. FT. OR 0.50 AC. FT. (TOTAL SELNICK DRIVE DEVELOPMENT)	0.58 AC. FT.	0.00 AC. FT.	GRASS CHANNEL ALONG SELNICK DRIVE, SP#1 PROVIDES 0.04 OF CREDIT FOR REMAINDER OF REV CREDIT, 0.54 PROVIDED BY ANALYSIS OF SP#1
3	CHANNEL PROTECTION VOLUME* (CPV)	0.30 AC. FT.	---	0.30 AC. FT.	CIP PROVIDED IN BMP #1 TO ELEV. 125.90
4	OVERHEAD FLOOD PROTECTION* (OF)	REQUIRED	---	PROVIDED	---
5	EXTREME FLOOD VOLUME* (EFV)	40.21 CFS	27.51 CFS TOTAL	20.97 CFS BYPASS 3.13 CFS UNMANAGED 12.35 CFS TO POND	20.97 CFS BYPASS 3.13 CFS UNMANAGED 12.35 CFS TO POND
6	EXISTING PROVIDED	69.72 CFS	59.83 CFS TOTAL	35.29 CFS BYPASS 5.57 CFS UNMANAGED 24.46 CFS TO POND	35.29 CFS BYPASS 5.57 CFS UNMANAGED 24.46 CFS TO POND

SWM WQV, CIP, OF, AND EFV PROVIDED BY POCKET POND, P.S. WITH CLAY LINER * THE REQUIRED AND ALLOWABLE RUNOFF (CIP, OF, EFV, 01000) INCLUDES THE DRAINAGE FROM ON-SITE BYPASS AND UNMANAGED AREAS SHOWN ON THESE DRAINAGE AREA MAPS.

STREET TREE CALCULATIONS

STREET NAME	LINEAR FEET	REQUIRED	PROVIDED
SELNICK DRIVE	1787	45	45
RED CLAY FORGE	144	4	4
U.S. ROUTE 1*	860	22	25

*STREET TREES ALONG U.S. ROUTE 1 WILL BE PROVIDED WITH SUBSEQUENT SITE DEVELOPMENT PLANS FOR THE BULK PARCEL 'B'

THE SWMF TO BE OWNED BY MDSHA, AND MAINTAINED BY HOA L. F.

OWNER/DEVELOPER
 ELKRIDGE DEVELOPMENT, LLC ELKRIDGE DEVELOPMENT NO.2, LLC
 301 TRANSYLVANIA AVENUE 301 TRANSYLVANIA AVENUE
 RALEIGH, NC 27609 RALEIGH, NC 27609
 (919) 789-9289 (919) 789-9289

FINAL ROAD CONSTRUCTION PLANS
GRADING AND SEDIMENT CONTROL PLAN
BELMONT STATION
 PARCELS 'A', 'B' & 'C' & OPEN SPACE LOT 1
 REF: WP-04-152, WP-06-79, S-04-10, P-05-17, F-06-169
 TAX MAP 37, BLOCK 24, PARCEL 195, 196, 198, 199
 1ST ELECTION DISTRICT HOWARD COUNTY, MARYLAND

ROBERT H. VOGEL ENGINEERING, INC.
 ENGINEERS • SURVEYORS • PLANNERS
 8407 MAIN STREET TEL: 410.461.7666
 ELLICOTT CITY, MD 21043 FAX: 410.461.8961

DESIGN BY: WJZ
 DRAWN BY: DZ
 CHECKED BY: [Signature]
 DATE: OCTOBER 2006
 SCALE: 1"=50'
 W.D. NO.: 04-08

4 SHEET OF 14

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
 [Signature] 10-19-06
 CHIEF, BUREAU OF HIGHWAYS DATE

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING
 [Signature] 10/22/06
 CHIEF, DEVELOPMENT ENGINEERING DIVISION 4 DATE

[Signature] 10/24/06
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE


THESE PLANS HAVE BEEN REVIEWED FOR HOWARD SOIL CONSERVATION DISTRICT AND MEETS THE TECHNICAL REQUIREMENTS.
 [Signature] 10/12/06
 USDA-NATURAL RESOURCES CONSERVATION SERVICE DATE









THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD COUNTY CONSERVATION DISTRICT.
 [Signature] 10/12/06
 HOWARD COUNTY CONSERVATION DISTRICT DATE

ENGINEER'S CERTIFICATE:
 I HEREBY CERTIFY THAT THIS PLAN FOR SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD COUNTY CONSERVATION DISTRICT.
 [Signature] 10/16/06
 SIGNATURE OF ENGINEER WALTER G. ZAWISLAK, PE DATE

DEVELOPER'S CERTIFICATE:
 I HEREBY CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE IN ACCORDANCE TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT CONTROL AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD COUNTY CONSERVATION DISTRICT.
 [Signature] 10/16/06
 SIGNATURE OF DEVELOPER PETER G. VOELKEL DATE

LEGEND:





PERMANENT SEEDING NOTES

APPLY TO GRADED OR CLEARED AREAS NOT SUBJECT TO IMMEDIATE FURTHER DISTURBANCE WHERE A PERMANENT LONG-LIVED VEGETATION SEEDBED PREPARATION: Loosen upper three inches of soil by raking, grading or other acceptable means before seeding, if not previously SOIL AMENDMENTS: In lieu of soil test recommendations, use one of the following:

1. Preferred—Apply 2 tons per acre dolomitic limestone (82 lbs./1000 sq ft.) and 600 lbs per acre 10-10-10 fertilizer (14 lbs./1000 sq ft.) before seeding. Harrow or disc into upper three inches of soil at the time of seeding, apply 400 lbs per acre 30-0-0 ureaform fertilizer (9 lbs./1000 sq ft.).
2. Acceptable—Apply 2 tons per acre dolomitic limestone (82 lbs./1000 sq ft.) and 1000 lbs per acre 10-10-10 fertilizer (14 lbs./1000 sq ft.) before seeding. Harrow or disc into upper three inches of soil at the time of seeding, apply 400 lbs per acre 30-0-0 ureaform fertilizer (9 lbs./1000 sq ft.).

SEEDING: For periods March 1 thru April 30, and August 1 thru October 15, seed with 1/2 bushel per acre of annual ryegrass (3.2 lbs./1000 sq ft.) and 1/2 bushel per acre of annual ryegrass (3.2 lbs./1000 sq ft.) and 1/2 bushel per acre of annual ryegrass (3.2 lbs./1000 sq ft.). For the period May 1 thru August 14, seed with 3 lbs. per acre of weeping lovegrass (.07 lbs./1000 sq ft.). For the period November 1 thru February 28, pretest site by applying 2 tons per acre of well-rotted straw mulch and seed as soon as possible.

MULCHING: Apply 1 1/2 to 2 tons per acre (70 to 90 lbs./1000 sq ft.) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gallons per acre (5 gal/1000 sq ft.) of emulsified asphalt on flat areas. On slopes 5 feet or higher, use 340 gallons per acre of emulsified asphalt.

MAINTENANCE: Inspect all seeded areas and make needed repairs.

TEMPORARY SEEDING NOTES

SEEDBED PREPARATION: Loosen upper three inches of soil by raking, grading or other acceptable means before seeding, if not previously SOIL AMENDMENTS: Apply 600 lbs. per acre 10-10-10 fertilizer.

SEEDING: For periods March 1 thru April 30 and from August 15 thru November 15, seed with 1 1/2 bushel per acre of annual ryegrass (3.2 lbs./1000 sq ft.) and 1/2 bushel per acre of annual ryegrass (3.2 lbs./1000 sq ft.). For the period May 1 thru August 14, seed with 3 lbs. per acre of weeping lovegrass (.07 lbs./1000 sq ft.). For the period November 1 thru February 28, pretest site by applying 2 tons per acre of well-rotted straw mulch and seed as soon as possible.

MULCHING: Apply 1 1/2 to 2 tons per acre (70 to 90 lbs./1000 sq ft.) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gallons per acre (5 gal/1000 sq ft.) of emulsified asphalt on flat areas. On slopes 5 feet or higher, use 340 gallons per acre of emulsified asphalt.

REF. 1 - 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR RATE AND METHODS NOT

21.0 STANDARDS AND SPECIFICATIONS FOR TOPSOIL

Placement of topsoil over a prepared subsoil prior to seeding. To provide a suitable soil medium for vegetable growth. Soils of concern have low moisture content, low nutrient levels, low pH, moderate toxic to plants, and/or

Conditions Where Practice Applies

- i. This practice is limited to areas having 2:1 or flatter slopes.
- ii. The texture of the exposed subsoil/parent material is such that the soil material is so shallow that the rooting zone is not deep enough to support plants or furnish continuous supply of moisture and plant nutrients.
- iii. The original soil to be vegetated contains a. The soil is so acidic that treatment with b. For the purpose of these Standards and Specifications, areas having slopes steeper than 2:1 require special consideration and design for adequate stabilization. Areas having slopes steeper than 2:1 shall have the appropriate

Construction and Material Specifications

- i. Topsoil salvaged from the existing site may be used provided that it meets the standards set forth in these specifications. Typically, the depth of topsoil to be salvaged for a given soil type can be found in the representative soil profile section in the Soil Survey published by USDA-SCS in cooperation with Maryland Department of Agriculture.
- ii. Topsoil Specifications - Soil to be used as topsoil a. Topsoil shall be a loam, sandy loam, clay loam, silt loam, sandy clay loam, loamy sand. Other soils may be used if recommended by an agronomist or a soil scientist and approved by the appropriate approval authority, regardless of the soil type. Topsoil shall not be a mixture of contrasting textures and shall contain less than 5% by volume of cinders, stones, slag, coarse fragments, or other materials larger than 1 and 1/2" in diameter.
- iii. Topsoil must be free of plants or plant parts such as Bermuda grass, quackgrass, johnsongrass, nutgrass, poison ivy, or other highly acidic or composed of heavy clays, ground limestone shall be spread at the rate of 4-8 tons/acre (200-400 pounds per 1,000 square feet) prior to the placement of topsoil. Lime shall be distributed uniformly over designated areas and worked into the soil in conjunction with tillage operations as described in Section I - Vegetative Stabilization Methods and Materials.
- iv. For sites having disturbed areas over 5 acres: 1. On soil meeting topsoil specifications, obtain test results including fertilizer and lime amendments required to bring the soil into compliance with the following: a. pH for topsoil shall be between 6.0 and 7.5. If the tested soil demonstrates a pH of less than 6.0, sufficient lime shall be prescribed to bring the pH to 6.5 or higher. b. Organic content of topsoil shall be not less than 1.5 percent by weight. c. Topsoil having soluble salt content greater than 200 parts per million shall not be used. d. No nod or seed shall be placed on soil which has been treated with soil sterilants or herbicides used for weed control until sufficient time has elapsed (14 days min.) to permit dissipation of phytotoxic materials. e. Topsoil substitutes or amendments, as recommended by a qualified agronomist or soil scientist and approved by the appropriate approval authority, may be used in lieu of natural topsoil.
- v. Topsoil Application 1. When topsoiling, maintain needed erosion and sediment control practices. 2. Grade Stabilization Structures, Earth Dikes, Slope Silt Fence and Sediment Traps and Basins. 3. Grades on the area to be topsoiled, which have been previously established, shall be maintained, about 4" - 8" higher in elevation. 4. Topsoil shall be uniformly distributed in a 4" - 8" layer and lightly compacted to a minimum thickness of 4". Spreading shall be performed in such a manner that seedling preparation and tillage. Any irregularities in the surface resulting from topsoiling or other operations shall be corrected in order to prevent the formation of depressions or water pockets. 5. Topsoil shall not be placed while the topsoil or subsoil is in a frozen or muddy condition, when the subsoil is excessively wet or in a condition that may be detrimental to proper grading and seeded preparation.

Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section I - Vegetative Stabilization Methods and Materials.

20.0 VEGETATIVE STABILIZATION - SECTION I - VEGETATIVE STABILIZATION METHODS AND MATERIALS

1. OBTAIN HONORARY COUNTY PERMIT AND MDE PERMIT (WEEK 1)

2. NOTIFY HOWARD COUNTY AT LEAST 48 HOURS PRIOR TO START OF CONSTRUCTION. (WEEK 1)

3. CONDUCT A PRE-CONSTRUCTION MEETING WITH THE SEDIMENT CONTROL INSPECTOR PRIOR TO ANY LAND DISTURBANCE. (WEEK 1)

4. WITH APPROVAL OF SEDIMENT CONTROL INSPECTOR, CLEAR AND GRUB FOR SEDIMENT CONTROL MEASURES ONLY. INSTALL SUPER SILT FENCE, AND EARTH DIKES AND MOUNTABLE BERMS FOR HAIL ROAD AND TEMPORARY STOCKPILES. (WEEK 2)

5. CONSTRUCT RETAINING WALL AND INITIAL ALL REMAINING SEDIMENT CONTROL MEASURES, INCLUDING BASIN (WITHOUT FORBAYS), EARTH DIKES, AND STORM DRAIN FROM EW-2 TO HW-1. (WEEK 3)

6. UPON RECEIVING WRITTEN PERMISSION FROM INSPECTOR, BEGIN GRADING. (WEEK 3)

7. BEGIN UTILITY INSTALLATION, AND BLOCK INLETS AS WORK PROGRESSES. (WEEK 3)

8. INSTALL ON-SITE PAVING BASE COURSE. (WEEK 6)

9. COMPLETE ALL UTILITY CONSTRUCTION. (WEEK 10)

10. COMPLETE ALL PAVING CONSTRUCTION. (WEEK 10)

11. INSTALL SIDEWALK. (WEEK 11)

12. FINE GRADE AND STABILIZE ALL AREAS OF PARCEL INCLUDING ANY EXPOSED EARTH AREAS OUTSIDE THE LOD. REMOVE ALL TRASH JUNK AND DEBRIS FROM ENTIRE PARCEL, INCLUDING FLOORPLAN. UPON STABILIZATION OF DRAINAGE AREA TO BASIN #1, INCLUDING REMOVAL OF PARCEL A (200-40-23A), CONVERT BASIN TO PERMANENT SWIM FACILITY. AFTER RECEIVING APPROVAL FROM SEDIMENT CONTROL INSPECTOR. (WEEK 13)

13. INSTALL LANDSCAPING. (WEEK 13)

14. REMOVE ALL SEDIMENT CONTROL MEASURES AFTER RECEIVING APPROVAL FROM THE SEDIMENT CONTROL INSPECTOR. (WEEK 14)

NOTES:

1. DURING GRADING AND AFTER EACH RAINFALL, CONTRACTOR WILL INSPECT AND PROVIDE NECESSARY MAINTENANCE TO THE SEDIMENT CONTROL MEASURES ON THIS PLAN.
2. FOLLOWING INITIAL SOIL DISTURBANCES OR REDISTURBANCE PERMANENT SEDIMENT CONTROL MEASURES SHALL BE COMPLETED WITHIN: a. 7 CALENDAR DAYS FOR ALL PERMETER SEDIMENT CONTROL STRUCTURES, DIKES, SHIELDS AND ALL SLOPES GREATER THAN 3:1. b. 14 CALENDAR DAYS FOR ALL OTHER DISTURBED AREAS.

* To be determined by contractor, with pre-approval of the Sediment Control Inspector to a site with an approved and active grading permit.

20.0 VEGETATIVE STABILIZATION - SECTION II - VEGETATIVE STABILIZATION METHODS AND MATERIALS

1. OBTAIN HONORARY COUNTY PERMIT AND MDE PERMIT (WEEK 1)

2. NOTIFY HOWARD COUNTY AT LEAST 48 HOURS PRIOR TO START OF CONSTRUCTION. (WEEK 1)

3. CONDUCT A PRE-CONSTRUCTION MEETING WITH THE SEDIMENT CONTROL INSPECTOR PRIOR TO ANY LAND DISTURBANCE. (WEEK 1)

4. WITH APPROVAL OF SEDIMENT CONTROL INSPECTOR, CLEAR AND GRUB FOR SEDIMENT CONTROL MEASURES ONLY. INSTALL SUPER SILT FENCE, AND EARTH DIKES AND MOUNTABLE BERMS FOR HAIL ROAD AND TEMPORARY STOCKPILES. (WEEK 2)

5. CONSTRUCT RETAINING WALL AND INITIAL ALL REMAINING SEDIMENT CONTROL MEASURES, INCLUDING BASIN (WITHOUT FORBAYS), EARTH DIKES, AND STORM DRAIN FROM EW-2 TO HW-1. (WEEK 3)

6. UPON RECEIVING WRITTEN PERMISSION FROM INSPECTOR, BEGIN GRADING. (WEEK 3)

7. BEGIN UTILITY INSTALLATION, AND BLOCK INLETS AS WORK PROGRESSES. (WEEK 3)

8. INSTALL ON-SITE PAVING BASE COURSE. (WEEK 6)

9. COMPLETE ALL UTILITY CONSTRUCTION. (WEEK 10)

10. COMPLETE ALL PAVING CONSTRUCTION. (WEEK 10)

11. INSTALL SIDEWALK. (WEEK 11)

12. FINE GRADE AND STABILIZE ALL AREAS OF PARCEL INCLUDING ANY EXPOSED EARTH AREAS OUTSIDE THE LOD. REMOVE ALL TRASH JUNK AND DEBRIS FROM ENTIRE PARCEL, INCLUDING FLOORPLAN. UPON STABILIZATION OF DRAINAGE AREA TO BASIN #1, INCLUDING REMOVAL OF PARCEL A (200-40-23A), CONVERT BASIN TO PERMANENT SWIM FACILITY. AFTER RECEIVING APPROVAL FROM SEDIMENT CONTROL INSPECTOR. (WEEK 13)

13. INSTALL LANDSCAPING. (WEEK 13)

14. REMOVE ALL SEDIMENT CONTROL MEASURES AFTER RECEIVING APPROVAL FROM THE SEDIMENT CONTROL INSPECTOR. (WEEK 14)

NOTES:

1. DURING GRADING AND AFTER EACH RAINFALL, CONTRACTOR WILL INSPECT AND PROVIDE NECESSARY MAINTENANCE TO THE SEDIMENT CONTROL MEASURES ON THIS PLAN.
2. FOLLOWING INITIAL SOIL DISTURBANCES OR REDISTURBANCE PERMANENT SEDIMENT CONTROL MEASURES SHALL BE COMPLETED WITHIN: a. 7 CALENDAR DAYS FOR ALL PERMETER SEDIMENT CONTROL STRUCTURES, DIKES, SHIELDS AND ALL SLOPES GREATER THAN 3:1. b. 14 CALENDAR DAYS FOR ALL OTHER DISTURBED AREAS.

* To be determined by contractor, with pre-approval of the Sediment Control Inspector to a site with an approved and active grading permit.

SEDIMENT CONTROL NOTES

1. A minimum of 48 hours notice must be given to the Howard County Department of Inspection, License and Permit's Sediment Control Division prior to the start of any construction (313-1855).

2. All vegetation and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL.

3. Following initial soil disturbances or redisturbances, permanent or temporary stabilization shall be completed within (a) 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes, and all slopes greater than 3:1, (b) 14 days as to all other disturbed or graded areas on the project site.

4. All sediment traps/basins shown must be fenced and warning signs posted around their perimeter in accordance with Vol. 1, Chapter 7, HOWARD COUNTY DESIGN MANUAL, Storm Drainage, i.e. all sediment traps and basins in residential areas or in residential developments expected to have occupants before their removal shall be fenced if the maximum depth for the sediment volume exceeds 18 inches. Fencing shall be equivalent to snow fencing in height, ability to be seen and ability to restrict individual passage.

5. All disturbed areas must be stabilized within the time period specified above in accordance with the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for permanent seeding, soil, temporary seeding, and mulching (Sec. C). Temporary stabilization with mulch alone shall be done when recommended seeding dates do not allow for proper germination and establishment of grasses.

6. All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.

7. Site Analysis:

Total Area	19.9 Acres
Area Disturbed	5.88 Acres
Area to be seeded or paved	5.88 Acres
Area to be vegetatively stabilized	12.000 CF
Total CF	12,000 CF




WASTE/BORROW LOCATION: ON-SITE

Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.

8. Additional sediment controls must be provided, if deemed necessary by the Howard County Sediment Control Inspector.

9. On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other grading or grading inspection approvals must be authorized until this initial approval by the inspection agency is made.

10. Trenches for the construction of utilities are limited to three pipe lengths or that which shall be back-filled and stabilized within one working day, whichever is shorter.



SEDIMENT BASIN #1

D.A. = 7.32 AC.
STORAGE REQUIRED (SEDIMENT) = 26,352 CF.
STORAGE PROVIDED (SEDIMENT) = 64,148 CF.
TOP OF DAM = 130.76
TOP OF RISER = 129.43
WEIR CREST EL. = 126.8
BOTTOM EL. = 121.75
C/O EL. = 122.88
SIDE SLOPES = 3:5
WEIR WIDTH = 3.5'
WET VOLUME REQUIRED = 13176
WET VOLUME PROVIDED = 13176
NET STORAGE EL. = 123.69
DRY VOLUME REQUIRED = 13176
DRY STORAGE PROVIDED = 50970
DRY STORAGE EL. = 128.74
Q₁ (TSWM) = 0.69 CFS.
Q₁₀ (TSWM) = 18.37 CFS.
Q₁₀₀ (TSWM) = 32.90 CFS.
Q₁ (EX) = 9.81 CFS.

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

Walter G. Zawislak 10/19/06
CHIEF, BUREAU OF HIGHWAYS DATE

DEPTH	SOIL TYPE	REMARKS
0-10"	Topsoil Depth 0"	
10-15"	Sandy Silty CLAY, Trace Fine Green, Orange Brown, Mids, (Color Shift to Very Brn)	
15-20"	Fine Silty SAND, Trace Fine Green, Orange Brown, Mids, (Color Shift to Very Brn)	
20-30"	Fine Silty SAND, Trace Fine Green, Orange Brown, Mids, (Color Shift to Very Brn)	
30-40"	Decomposed ROCK, Dark Greenish Gray, Mids, Very Heavy to Extremely Heavy, (D)	
40-50"	Auger Refusal @ 9.5'	
50-60"	Auger Refusal @ 14.5'	
60-70"	Auger Refusal @ 16.0'	

DEPTH	SOIL TYPE	REMARKS
0-10"	Topsoil Depth 0"	
10-15"	Sandy Silty CLAY, Trace Fine Green, Orange Brown, Mids, (Color Shift to Very Brn)	
15-20"	Fine Silty SAND, Trace Fine Green, Orange Brown, Mids, (Color Shift to Very Brn)	
20-30"	Fine Silty SAND, Trace Fine Green, Orange Brown, Mids, (Color Shift to Very Brn)	
30-40"	Decomposed ROCK, Dark Greenish Gray, Mids, Very Heavy to Extremely Heavy, (D)	
40-50"	Auger Refusal @ 9.5'	
50-60"	Auger Refusal @ 14.5'	
60-70"	Auger Refusal @ 16.0'	

DEPTH	SOIL TYPE	REMARKS
0-10"	Topsoil Depth 0"	
10-15"	Sandy Silty CLAY, Trace Fine Green, Orange Brown, Mids, (Color Shift to Very Brn)	
15-20"	Fine Silty SAND, Trace Fine Green, Orange Brown, Mids, (Color Shift to Very Brn)	
20-30"	Fine Silty SAND, Trace Fine Green, Orange Brown, Mids, (Color Shift to Very Brn)	
30-40"	Decomposed ROCK, Dark Greenish Gray, Mids, Very Heavy to Extremely Heavy, (D)	
40-50"	Auger Refusal @ 9.5'	
50-60"	Auger Refusal @ 14.5'	
60-70"	Auger Refusal @ 16.0'	

DEPTH	SOIL TYPE	REMARKS
0-10"	Topsoil Depth 0"	
10-15"	Sandy Silty CLAY, Trace Fine Green, Orange Brown, Mids, (Color Shift to Very Brn)	
15-20"	Fine Silty SAND, Trace Fine Green, Orange Brown, Mids, (Color Shift to Very Brn)	
20-30"	Fine Silty SAND, Trace Fine Green, Orange Brown, Mids, (Color Shift to Very Brn)	
30-40"	Decomposed ROCK, Dark Greenish Gray, Mids, Very Heavy to Extremely Heavy, (D)	
40-50"	Auger Refusal @ 9.5'	
50-60"	Auger Refusal @ 14.5'	
60-70"	Auger Refusal @ 16.0'	

DEPTH	SOIL TYPE	REMARKS
0-10"	Topsoil Depth 0"	
10-15"	Sandy Silty CLAY, Trace Fine Green, Orange Brown, Mids, (Color Shift to Very Brn)	
15-20"	Fine Silty SAND, Trace Fine Green, Orange Brown, Mids, (Color Shift to Very Brn)	
20-30"	Fine Silty SAND, Trace Fine Green, Orange Brown, Mids, (Color Shift to Very Brn)	
30-40"	Decomposed ROCK, Dark Greenish Gray, Mids, Very Heavy to Extremely Heavy, (D)	
40-50"	Auger Refusal @ 9.5'	
50-60"	Auger Refusal @ 14.5'	
60-70"	Auger Refusal @ 16.0'	

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

Walter G. Zawislak 10/23/06
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

Walter G. Zawislak 10/23/06
CHIEF, DIVISION OF LAND DEVELOPMENT DATE

THESE PLANS HAVE BEEN REVIEWED FOR HOWARD COUNTY SOIL CONSERVATION DISTRICT AND MEETS THE TECHNICAL REQUIREMENTS.

Walter G. Zawislak 10/12/06
USDA-NATURAL RESOURCES CONSERVATION SERVICE DATE

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD COUNTY SOIL CONSERVATION DISTRICT.

Walter G. Zawislak 10/12/06
HOWARD S.C.D. DATE

ENGINEER'S CERTIFICATE:

I HEREBY CERTIFY THAT THIS PLAN FOR SEDIMENT AND EROSION CONTROL REPRESENTS A TECHNICAL WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD COUNTY SOIL CONSERVATION DISTRICT.

Walter G. Zawislak 10/12/06
SIGNATURE OF ENGINEER
WALTER G. ZAWISLAK DATE

DEVELOPER'S CERTIFICATE:

I HEREBY CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE IN ACCORDANCE TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT CONTROL AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD COUNTY SOIL CONSERVATION DISTRICT.

Peter G. Voelkel 10/16/06
SIGNATURE OF DEVELOPER
PETER G. VOELKEL DATE

SOILS LEGEND

SYMBOL	GROUP	NAME	DESCRIPTION
BeB2	C	BELTSVILLE SILT LOAM	1%-5% SLOPES, MODERATELY ERODED
BeC3	C	BELTSVILLE SILT LOAM	5%-10% SLOPES, SEVERELY ERODED
Ho	D	HATBORO SILT LOAM	POORLY DRAINED
KeB2	D	KELLY SILT LOAM	3%-8% SLOPES, MODERATELY ERODED
KcE3	D	KELLY CLAY LOAM	15%-30% SLOPES, SEVERELY ERODED
ScD	C	SANDY & CLAYEY LOAM	MODERATELY SLOPING
SfC2	B	SASSAFRAS GRAVELLY SANDY LOAM	5%-10% SLOPES, MODERATELY ERODED
SiC2	B	SASSAFRAS LOAM	5%-10% SLOPES, MODERATELY ERODED
SeE	B	SASSAFRAS LOAM	15%-40% SLOPES

OWNER/DEVELOPER

ELKRIDGE DEVELOPMENT, LLC ELKRIDGE DEVELOPMENT NO.2, LLC
301 TRANSVALYA AVENUE 301 TRANSVALYA AVENUE
RALEIGH, NC 27609 RALEIGH, NC 27609
(919) 789-9289 (919) 789-9289

REVISE SEQUENCE OF CONSTRUCTION

NO.	REVISION	DATE
1	REVISE SEQUENCE OF CONSTRUCTION	4-20-07

FINAL ROAD CONSTRUCTION PLANS

SEDIMENT AND EROSION CONTROL NOTES AND DETAILS

BELMONT STATION


PARCELS 'A', 'B' & 'C' & OPEN SPACE LOT 1
REF: WP-04-152, WP-06-79, S-04-10, P-05-17, F-06-169
TAX MAP 37 BLOCK 18 PARCEL 196, 198, 199
1ST ELECTION DISTRICT HOWARD COUNTY, MARYLAND

ROBERT H. VOGEL ENGINEERING, INC.

ENGINEERS • SURVEYORS • PLANNERS
8407 MAIN STREET TEL: 410.461.7666
ELLCOTT CITY, MD 21043 FAX: 410.461.8961

DESIGN BY: WJZ
DRAWN BY: DZ
CHECKED BY:
DATE: OCTOBER 2006
SCALE: AS SHOWN
W.O. NO.: 04-08

5 SHEET OF 14



LEGEND:

- EXISTING CONTOUR
- PROPOSED CONTOUR
- PROPOSED SPOT ELEVATION
- EXISTING SPOT ELEVATION
- EXISTING CURB AND GUTTER
- PROPOSED CURB AND GUTTER
- EXISTING UTILITY POLE
- EXISTING LIGHT POLE
- EXISTING MAILBOX
- EXISTING SIGN
- EXISTING SANITARY MANHOLE
- EXISTING SANITARY LINE
- EXISTING FIRE HYDRANT
- EXISTING WATER LINE
- EXISTING FENCE
- PROPERTY LINE
- RIGHT-OF-WAY LINE
- SOILS BOUNDARY
- PROPOSED STORM DRAIN
- PROPOSED STORM DRAIN INLET
- PROPOSED SIDEWALK

HOWARD COUNTY DEEP RUN STUDY CAPITAL PROJ. D-1094		BELMONT STATION FLOODPLAIN STUDY	
**SECTION	WSEL	SECTION	WSEL
TRIB D-6 360	111.48	TRIB 3+77	108.79
TRIB D-6 280	110.21	TRIB 2+53	106.21
---	---	TRIB 1+30	106.81
TRIB D 11100	122.57	18+53	120.30
TRIB D 10870	122.36	16+64	118.62
TRIB D 10650	119.67	14+64	116.32
---	---	13+08	113.82
---	---	12+63	111.71
TRIB D 10320	116.93	11+49	110.66
TRIB D 10100	113.44	8+84	109.54
TRIB D 9800	108.39	7+01	105.10
---	---	4+79	105.01
---	---	3+18	105.59
TRIB D 9500	106.12	2+85	104.27
TRIB D 9410	105.51	2+05	104.37
TRIB D 9200	104.27	0+00	104.27*

**APPROXIMATE CORRELATION BETWEEN STUDIES * HOWARD COUNTY DEEP RUN WATERSHED STUDY D-1094 CROSS SECTION 92+00

A FLOODPLAIN ANALYSIS WAS PERFORMED BY ROBERT H. VOGEL ENGINEERING, JULY 2005 TO SUPPLEMENT THE DEEP RUN WATERSHED STUDY D-1094. THE RESULTING 100-YEAR WATER SURFACE ELEVATIONS ARE LOWER THAN THE HOWARD COUNTY STUDY. THEREFORE THE COUNTY'S ELEVATIONS ARE UTILIZED TO DETERMINE THE FLOODPLAIN LIMITS.

OWNER/DEVELOPER
 ELKRIDGE DEVELOPMENT, LLC ELKRIDGE DEVELOPMENT NO.2, LLC
 301 TRANSYLVANIA AVENUE 301 TRANSYLVANIA AVENUE
 RALEIGH, NC 27609 RALEIGH, NC 27609
 (919) 789-9289 (919) 789-9289

PLAN VIEW
 SCALE: 1"=100'

FLOODPLAIN LINE TABLE

L1	N70°48'03"E	35.40	L40	S86°10'05"E	65.00
L2	N87°48'35"E	20.00	L41	N56°37'59"E	140.00
L3	N67°04'44"E	25.00	L42	N69°47'31"E	50.00
L4	S82°18'21"E	19.25	L43	S75°15'20"E	40.00
L5	N89°59'09"E	32.85	L44	N45°07'05"E	110.00
L6	N49°37'27"E	23.10	L45	N36°22'09"E	70.00
L7	N84°59'54"E	10.00	L46	N12°23'48"W	35.00
L8	N56°50'14"E	45.00	L47	N50°23'16"E	55.00
L9	N24°21'24"E	55.00	L48	N58°19'04"E	45.00
L10	N14°28'06"E	35.00	L49	N58°15'56"E	20.00
L11	N21°02'06"E	13.86	L50	N48°59'25"E	20.00
L12	N27°02'18"E	26.18	L51	N76°22'58"E	10.00
L13	N46°34'09"E	25.00	L52	S69°59'14"E	15.00
L14	N39°23'19"E	38.97	L53	S34°43'03"E	45.00
L15	N45°01'13"E	9.38	L54	S14°11'43"E	50.00
L16	N60°19'51"E	24.84	L55	S63°58'02"E	45.00
L17	N89°22'39"E	20.39	L56	S65°57'20"E	29.54
L18	N70°37'29"E	30.00	L57	S87°44'25"E	67.41
L19	N56°13'24"E	20.00	L58	N67°54'12"E	54.43
L20	N77°09'20"E	43.35	L59	S88°30'45"E	79.81
L21	N72°84'23"E	61.58	L60	N85°33'20"E	48.56
L22	N64°46'33"E	59.82	L61	N72°06'59"E	39.59
L23	S89°47'04"E	50.03	L62	N05°55'10"E	27.33
L24	S54°26'27"E	40.98	L63	N13°24'47"W	40.00
L25	S68°14'18"E	48.66	L64	N28°25'28"E	90.00
L26	N85°40'28"E	47.30	L65	N25°44'38"W	35.00
L27	S80°41'39"E	48.94	L66	N48°16'40"W	75.00
L28	N72°38'28"E	41.36	L67	S80°54'41"W	25.00
L29	N85°18'58"E	34.48	L68	N15°06'17"W	17.00
L30	N74°48'00"E	42.58	L69	N34°06'11"E	64.96
L31	S89°54'12"E	53.96			
L32	S80°05'52"E	61.99			
L33	N85°00'24"E	35.47			
L34	N88°37'46"E	32.03			
L35	N82°48'51"E	33.82			

STORM DRAIN SUMMARY

DA LABEL	AREA (AC.)	'C'	% IMPERVIOUS
1	0.26	0.59	47
2	0.37	0.65	53
3	0.32	0.31	0
4	0.84	0.27	3
5	0.65	0.60	60
6	0.79	0.54	34
7	0.59	0.61	54
A	2.31	0.82	88

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
Walter G. Zawislak 10-19-06
 CHIEF, BUREAU OF HIGHWAYS DATE

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING
Walter G. Zawislak 10/20/06
 CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE
Cindy K. Khan 10/19/06
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE

THESE PLANS HAVE BEEN REVIEWED FOR HOWARD SOIL CONSERVATION DISTRICT AND MEETS THE TECHNICAL REQUIREMENTS.
 USDA-NATURAL RESOURCES CONSERVATION SERVICE DATE
 THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT. CONSERVATION DISTRICT. HOWARD S.C.D. DATE

ENGINEER'S CERTIFICATE:
 I HEREBY CERTIFY THAT THIS PLAN FOR SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.
Walter G. Zawislak 10/20/06
 SIGNATURE OF ENGINEER DATE
 WALTER G. ZAWISLAK, PE

DEVELOPER'S CERTIFICATE:
 I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE IN ACCORDANCE TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT.
Peter G. Voelkel 10/16/06
 SIGNATURE OF DEVELOPER DATE
 PETER G. VOELKEL

FINAL ROAD CONSTRUCTION PLANS
STORM DRAIN DRAINAGE AREA MAP
 BELMONT STATION
 PARCELS 'A', 'B' & 'C' & OPEN SPACE LOT 1
 REF: WP-04-152, WP-06-79, S-04-10, P-05-17, F-06-169
 TAX MAP 37, BLOCK 18, PARCEL 196, 198, 199
 1ST ELECTION DISTRICT HOWARD COUNTY, MARYLAND

ROBERT H. VOGEL ENGINEERING, INC.
 ENGINEERS • SURVEYORS • PLANNERS
 8407 MAIN STREET TEL: 410.461.7666
 ELLICOTT CITY, MD 21043 FAX: 410.461.8961

DESIGN BY: *WJZ*
 DRAWN BY: *DZ*
 CHECKED BY: _____
 DATE: OCTOBER 2006
 SCALE: 1"=100'
 W.O. NO.: 04-08

6 SHEET OF 14

QUANTITIES FOR ESTIMATING PURPOSES ONLY

ITEM	DESCRIPTION	QUANTITY	UNIT
1	15" RCP (IV)	163	LF
2	18" RCP (IV)	518	LF
3	21" RCP (IV)	178	LF
4	24" RCP (IV)	116	LF
5	30" RCP (IV)	120	LF
6	42" RCP (IV)	39	LF
7	48" RCP (IV)	165	LF








SECTION A-A

GENERAL NOTES

DISPOSITION OF BARS DETAIL

STANDARD TYPE ENDWALL METAL OR CONCRETE ROUND PIPE

STANDARD NO. MD 356.01



STRUCTURE SCHEDULE

NO.	TYPE	Q. STATION, OFFSET	TOP ELEV.	THROAT ELEV.	INV. IN	INV. OUT	COMMENTS
I-1	COS-10	729+03.1, 31.53' LT	135.90	135.23	129.65	129.40	MD374.61
I-2	TYPE "K" INLET, 2 OPENING	728+77.3, 36.18' LT	135.80	135.80	130.80	130.80	MD378.05
I-3	TYPE "K" INLET, 2 OPENINGS	728+15.3, 47.11' RT	140.88	135.63	135.53	135.53	MD378.05
I-4	TYPE "K" INLET, 1 OPENING	726+07.6, 36.92' RT	158.71	153.46	153.46	153.46	MD378.05
I-5	TYPE "K" INLET, 1 OPENING	727+14.4, 36.71' LT	148.07	142.82	142.82	142.82	MD378.05
I-6	TYPE "K" INLET, 1 OPENING	720+93.7, 36.13' LT	169.08	164.79	164.69	164.69	MD378.05
I-7	TYPE "K" INLET, 2 OPENING	723+23.1, 40.48' RT	170.75	167.75	167.75	167.75	MD378.05
MH-1	STANDARD MANHOLE	727+19.1, 36.92' RT	150.20	141.15	140.90	140.90	MD384.01
MH-2	STANDARD MANHOLE	728+24.7, 40.32' RT	142.52	136.30	135.80	135.80	MD384.01
MH-3	STANDARD MANHOLE	722+99.7, 53.00' LT	172.00	164.12	164.02	164.02	MD384.03
MH-4	STANDARD MANHOLE	722+99.8, 28.00' LT	172.90	164.26	164.16	164.16	MD384.03
MH-4A	STANDARD MANHOLE	722+18.6, 23.25' LT	173.40	164.87	164.77	164.77	MD384.03
MH-5	STANDARD MANHOLE	722+60.1, 26.20' LT	132.80	123.71	123.71	123.71	MD384.03
MH-6	STANDARD MANHOLE	720+93.8, 22.36' LT	171.40	164.87	164.77	164.77	MD384.03
MH-7	STANDARD MANHOLE	729+83.5, 50.06' RT	130.00	125.80	125.70	125.70	MD384.01
MH-8	STANDARD MANHOLE	729+81.5, 96.31' RT	128.00	124.33	123.63	123.63	MD384.01
MH-9	STANDARD MANHOLE	729+58.1, 160.54' RT	125.00	121.50	120.15	120.15	MD384.05
MH-10	STANDARD MANHOLE	729+39.2, 269.85' RT	128.00	120.75	120.75	120.75	MD384.05
ES-1	STANDARD CONCRETE END SECTION - 18"	729+03.4, 68.11' RT	---	---	123.25	136.68	03
ES-2	STANDARD CONCRETE END SECTION - 18"	728+89.2, 72.10' RT	---	---	123.25	136.68	03
ES-4	STANDARD CONCRETE END SECTION - 30"	722+85.5, 52.93' RT	---	---	163.94	136.68	03
ES-5	STANDARD CONCRETE END SECTION - 24"	729+18.5, 185.44' RT	---	---	123.25	136.68	03
HW-1	STANDARD TYPE "C" HEADWALL - 48" (DETAIL, THIS SHEET)	729+41.2, 286.41' RT	123.30	---	118.30	135.61	(MODIFIED)
EW-2	STANDARD TYPE "E" ENDWALL - 18"	728+15.3, 105.43' RT	---	---	149.00	135.61	01
EW-3	STANDARD TYPE "C" ENDWALL - 15"	729+27.1, 149.20' RT	---	---	---	135.61	01
CS-1	CONTROL STRUCTURE, SEE SHEET 9	729+31.6, 149.15' RT	128.00	---	---	---	01

PIPE SCHEDULE

SIZE	TYPE	LENGTH
15"	RCP (IV)	163 LF
18"	RCP (IV)	518 LF
21"	RCP (IV)	178 LF
24"	RCP (IV)	116 LF
30"	RCP (IV)	120 LF
42"	RCP (IV)	39 LF
48"	RCP (IV)	165 LF

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

Walter F. ... 10-19-06
CHIEF, BUREAU OF HIGHWAYS

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

... 10/23/06
CHIEF, DEVELOPMENT ENGINEERING DIVISION

... 10/24/06
CHIEF, DIVISION OF LAND DEVELOPMENT

THESE PLANS HAVE BEEN REVIEWED FOR HOWARD COUNTY CONSERVATION DISTRICT AND MEETS THE TECHNICAL REQUIREMENTS.

... 10/17/06
USDA-NATURAL RESOURCES CONSERVATION SERVICE

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD COUNTY CONSERVATION DISTRICT.

... 10/17/06
HOWARD COUNTY

ENGINEER'S CERTIFICATE:



I HEREBY CERTIFY THAT THIS PLAN FOR SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD COUNTY CONSERVATION DISTRICT.

Walter G. Zawislak 10/16/06
SIGNATURE OF ENGINEER
WALTER G. ZAWISLAK, PE

DEVELOPER'S CERTIFICATE:

I HEREBY CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE IN ACCORDANCE TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD COUNTY CONSERVATION DISTRICT.

Peter G. Voelkel 10/16/06
SIGNATURE OF DEVELOPER
PETER G. VOELKEL



OWNER/DEVELOPER

ELKRIDGE DEVELOPMENT, LLC ELKRIDGE DEVELOPMENT NO.2, LLC
301 TRANSYLVANIA AVENUE 301 TRANSYLVANIA AVENUE
RALEIGH, NC 27609 RALEIGH, NC 27609
(919) 789-9289 (919) 789-9289

FINAL ROAD CONSTRUCTION PLANS

STORM DRAIN PROFILES

BELMONT STATION

PARCELS 'A', 'B' & 'C' & OPEN SPACE LOT 1
REF: WP-04-152, WP-06-79, S-04-10, P-05-17, F-06-169
TAX MAP 37 BLOCK 18 PARCEL 196, 198, 199
1ST ELECTION DISTRICT HOWARD COUNTY, MARYLAND

ROBERT H. VOGEL ENGINEERING, INC.

ENGINEERS • SURVEYORS • PLANNERS

8407 MAIN STREET TEL: 410.461.7666
ELLCOTT CITY, MD 21043 FAX: 410.461.8961

DESIGN BY: *WJZ*
DRAWN BY: *DZ*
CHECKED BY:
DATE: OCTOBER 2006
SCALE: AS SHOWN
W.O. NO.: 04-08

7 SHEET OF 14

**MARYLAND 378
STORMWATER MANAGEMENT POND CONSTRUCTION SPECIFICATIONS**

CONSTRUCTION SPECIFICATIONS
These specifications are appropriate to ponds within the scope of the Standard for practice MD-378. All references to ASIM and ASHSTO specifications apply to the most recent version.

Site Preparation
Areas designated for borrow areas, embankment, and structural works shall be cleared, grubbed and stripped of topsoil. All trees, vegetation, roots and other objectionable material shall be removed. Channel banks and shop berms shall be sloped to no steeper than 1:1. All fill material shall be cleared and grubbed within 15 feet of the top of the embankment.

Areas to be covered by the reservoir will be cleared of all trees, brush, logs, stumps, rubbish and other objectionable material unless otherwise designated on the plans. Trees, brush, and stumps shall be cut approximately level with the ground surface. For dry stormwater management ponds, a minimum of a 25-foot radius around the silt structure shall be cleared.

All cleared and grubbed material shall be disposed of outside and below the limits of the dam and reservoir as directed by the owner or his representative. When specified, a sufficient quantity of topsoil will be stockpiled in a suitable location for use on the embankment and other designated areas.

Earth Fill
Material - The fill material shall be taken from approved designated borrow areas. It shall be free of roots, stumps, wood, rubbish, stones greater than 6" diameter or other objectionable materials. Fill material for the center of the embankment and cut fill trench shall conform to Unified Soil Classification (U.S.C.) CL or CL and must have at least 30% passing the #200 sieve. Consideration may be given to the use of other materials in the embankment if designed by a geotechnical engineer. Such special designs must have construction supervised by a geotechnical engineer. Materials used in the outer shell of the embankment must have the capability to support vegetation of the quality required to prevent erosion of the embankment.

Placement - Areas on which fill is to be placed shall be scarified prior to placement of fill. Fill materials shall be placed in maximum 8 inch thick (before compaction) layers which are to be continuous over the entire length of the embankment. The most permeable material shall be placed in the downstream portion of the embankment. The principal spillway shall be installed concurrently with fill placement and not excavated into the embankment.

Compaction - The movement of the hauling and spreading equipment over the fill shall be controlled so that the entire surface of each lift shall be traversed by not less than one tread truck of heavy equipment or compaction shall be achieved by a minimum of four complete passes of a sheepsfoot, rubber tired or vibratory roller. Fill material shall contain sufficient moisture such that the required degree of compaction will be obtained with the equipment. The fill material shall contain sufficient moisture so that if formed into a ball it will not crumble, yet not be so wet that water can be squeezed out.

When required by the reviewing agency the optimum minimum density shall not be less than 95% of maximum dry density with a moisture content within +/- 2% of the optimum. Each layer of fill shall be compacted as necessary to obtain that density, and is to be certified by the Engineer at the time of construction. All compaction is to be determined by ASTM Method 1-99 (Standard Proctor).

Cut Off Trench - The cutoff trench shall be excavated into impervious material along or parallel to the centerline of the embankment as shown on the plans. The bottom width of the trench shall be governed by the equipment used for excavation, with the minimum width being four feet. The depth shall be at least four feet below existing grade or as shown on the plans. The side slopes of the trench shall be 1 to 1 or flatter. The backfill shall be compacted with construction equipment, rollers, or hand tamping to assure maximum density and minimum permeability. In addition, the core shall be placed concurrently with the outer shell of the embankment.

Embankment Core - The core shall be parallel to the centerline of the embankment as shown on the plans. The top width of the core shall be a minimum of four feet. The height shall extend up to at least the 10 year water elevation or as shown on the plans. The side slopes shall be 1 to 1 or flatter. The core shall be compacted with construction equipment, rollers or hand tamping to assure maximum density and minimum permeability. In addition, the core shall be placed concurrently with the outer shell of the embankment.

Structure Backfill
Backfill adjacent to pipes or structures shall be of the type and quality conforming to that specified for the adjoining fill material. The fill shall be placed in horizontal layers not to exceed four inches in thickness and compacted by hand tampers or other manually directed compaction equipment. The material needs to be completely all spaced around and adjacent to the pipe. At no time during the backfilling operation shall driven equipment be allowed to operate closer than four feet, measured horizontally, to any part of a structure. Under no circumstances shall equipment be driven over any part of a concrete structure or pipe, unless there is a compacted fill of 24" or greater over the structure or pipe.

Structure backfill may be flowable fill meeting the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 313 as modified. The mixture shall have a 100-200 psi, 28 day unconfined compressive strength. The flowable fill shall have a minimum density of 4.0 g/cm³ minimum dry density of 2.00 g/cm³. Material shall be placed in layers that maintain a 6" (measured perpendicular to the outside of the pipe) of flowable fill shall be placed over (bedding), and over, on the sides of the pipe. This bedding shall extend to the top of the pipe and shall be compacted to a minimum density of 95% of maximum dry density. Adequate measures shall be taken (sand logs, etc.) to prevent floating the pipe. When using flowable fill, all metal pipe shall be bituminous coated. Any adjoining silt or fill shall be placed in horizontal layers not to exceed four inches in thickness and compacted by hand tampers or other manually directed compaction equipment. The material shall completely fill all voids adjacent to the flowable fill zone. All no time during the backfilling operation shall driven equipment be allowed to operate closer than four feet, measured horizontally, to any part of the structure. Under no circumstances shall equipment be driven over any part of a structure or pipe unless there is a compacted fill of 24" or greater over the structure or pipe. Backfill (flowable fill) zones shall be of the type and quality conforming to that specified for the core of the embankment or other embankment materials.

Pipe Conduits
All pipes shall be circular in cross section.
Corrugated Metal Pipe - All of the following criteria shall apply for corrugated metal pipe:
1. Materials - (Polymer Coated Steel Pipe) - Steel pipes with polymeric coating shall have a minimum coating thickness of 0.01 inch (10 mil) on both sides of the pipe. This pipe and its appurtenances shall conform to the requirements of ASHSTO Specifications M-245 & M-246 with water tight coating bands or flanges.
Materials - (Aluminum Coated Steel Pipe) - This pipe and its appurtenances shall conform to the requirements of ASHSTO Specification M-274 with water tight coating bands or flanges. Aluminum Coated Steel Pipe, when used with flowable fill or when soil and/or water conditions warrant the need for increased durability, shall be fully bituminous coated per requirements of ASHSTO Specification M-199. A. Aluminum surfaces that are to be in contact with concrete shall be painted with one coat of zinc chromate primer or two coats of asphalt. Otherwise removed shall be replaced with cold applied bituminous coating compound. Aluminum surfaces that are to be in contact with concrete shall be painted with one coat of zinc chromate primer or two coats of asphalt.

POND BOTTOM SOIL CONDITIONS
If broken rock fragments are encountered at finished pond bottom, under cut a minimum of 12" below basin grade and to a horizontal distance of at least 18" beyond each edge of the broken rock and backfill with fine-grained ML or CL soils compacted to a firm condition. This procedure should be performed under the supervision of the project Geotechnical Engineer.

In order to lower the infiltration rate into the sands with gravel, it is recommended that the sands with gravel be undercut and replaced with a minimum of 12 inches of soils classified as SM per ASTM D-2487 or Sandy Loam per USDA classification. The fill soil should be compacted to at least 95 percent of its maximum dry density per ASTM D-698.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

OPERATION MAINTENANCE AND INSPECTION
INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, NRCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND ANY HEIRS, SUCCESSORS, OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVIVAL, PROTECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

Materials - (Aluminum Pipe) - This pipe and its appurtenances shall conform to the requirements of ASHSTO Specification M-196 or M-211 with water tight coating bands or flanges. Aluminum Pipe, when used with flowable fill or when soil and/or water conditions warrant the need for increased durability, shall be fully bituminous coated per requirements of ASHSTO Specification M-199. A. Aluminum surfaces that are to be in contact with concrete shall be painted with one coat of zinc chromate primer or two coats of asphalt. Hot dip galvanized bolts may be used for connections. The areas the surrounding soils shall be protected with a bituminous coating compound.

2. Coupling bands, anti-seep collars, and sections, etc., must be composed of the same material and coatings as the pipe. Metals must be insulated from dissimilar materials with use of rubber or plastic insulating materials of least 24 mils in thickness.

3. Connections - All connections with pipes must be completely watertight. The drain pipe or barrel connection to the riser shall be welded all around when the pipe and riser are metal. Anti-seep collars shall be connected to the pipe such as manner as to be completely watertight. Dimple bands are not considered to be watertight.

All connections shall use a rubber or neoprene gasket when joining pipe sections. The end of each pipe shall be reinforced with adequate number of corrugations to accommodate the bandwidth. The following type connections are acceptable for pipes less than 24 inches diameter: flanges on both ends of the pipe with a circular 3/8 inch thick closed end circular neoprene gasket; and a 12-inch wide hugger type bond with 1/2-inch gaskets having a minimum diameter of 1/2 inch greater than the corrugation depth. Flanges 24 inches in diameter and larger shall be connected by a 24 inch long annular corrugated bonded using a minimum of 4 (four) rods and nuts, 2 on each connecting pipe end. A 24-inch wide by 3/8-inch thick closed end circular neoprene gasket will be installed with flanges on the end of each pipe. Flanged joints with 3/8-inch closed end gaskets the full width of the flange is also acceptable.

Helically corrugated pipe shall have either continuously welded seams or have lock seams with internal caulking or a neoprene bead.

4. Bedding - The pipe shall be firmly and uniformly bedded throughout its entire length. Where rock or soft, spongy or other unstable soil is encountered, all foundation excavations must be backfilled with suitable earth compacted to provide adequate support.

5. Backfilling shall conform to "Structure Backfill".
6. Other details (anti-seep collars, valves, etc.) shall be as shown on the drawings.

Reinforced Concrete Pipe - All of the following criteria shall apply for reinforced concrete pipe:
1. Materials - Reinforced concrete pipe shall have bell and spigot joints with rubber gaskets and shall equal or exceed ASTM C-361.
2. Bedding - Reinforced concrete pipe conduits shall be laid in a concrete bedding for their entire length. The bedding shall be placed in a trench that is at least 24 inches in diameter and larger shall be connected by a 24 inch long annular corrugated bonded using a minimum of 4 (four) rods and nuts, 2 on each connecting pipe end. A 24-inch wide by 3/8-inch thick closed end circular neoprene gasket will be installed with flanges on the end of each pipe. Flanged joints with 3/8-inch closed end gaskets the full width of the flange is also acceptable.

3. Laying pipe - Bell and spigot pipe shall be placed with the bell end upstream. Joints shall be made in accordance with recommendations of the manufacturer of the material. After the joints are sealed for the entire line, the bedding shall be placed and the pipe shall be filled. Care shall be exercised to prevent any deviation from the original line and grade of the pipe. The first joint must be located within 4 feet from the riser.
4. Backfilling shall conform to "Structure Backfill".
5. Other details (anti-seep collars, valves, etc.) shall be as shown on the drawings.

Plastic Pipe - The following criteria shall apply for plastic pipe:
1. Materials - PVC pipe shall be PVC 1120 or PVC 1240 conforming to ASTM D-1785 or ASTM D-2241. Corrugated High Density Polyethylene (HDPE) pipe, couplings and fittings shall conform to the following: 4" - 10" inch pipe shall meet the requirements of ASHSTO M252 Type S, and 12" through 24" inch shall meet the requirements of ASHSTO M294 Type S.
2. Joints and connections to anti-seep collars shall be completely watertight.
3. Bedding - The pipe shall be firmly and uniformly bedded throughout its entire length. Where rock or soft, spongy or other unstable soil is encountered, all foundation excavations must be backfilled with suitable earth compacted to provide adequate support.
4. Backfilling shall conform to "Structure Backfill".
5. Other details (anti-seep collars, valves, etc.) shall be as shown on the drawings.

Drainage Diaphragms - When a drainage diaphragm is used, a registered professional engineer will supervise the design and construction inspection.
Concrete
Concrete shall meet the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 414, Mix No. 3.
Rock Riprap
Rock riprap shall meet the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction Materials, Section 311.
Geotextile shall be placed under all riprap and shall meet requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 521.03, Class C.
Care of all during Construction
All work on permanent structures shall be carried out in areas free from water. The Contractor shall construct and maintain all temporary dikes, levees, cofferdams, drainage channels, and stream diversions necessary to protect to be excavated areas from the permanent works. The Contractor shall also furnish, install, operate, and maintain all necessary pumping and other equipment required for removal of water from various parts of the work and for maintaining the excavations, foundation, and other parts of the work free from water as required or directed by the engineer for protecting each part of the work. After having served their purpose, all temporary protective works shall be removed or leveled and graded to the extent required to prevent obstruction in any degree whatsoever of the flow of water to the spillway or outlet works and so as not to interfere in any way with the operation or maintenance of the structure. Stream diversions shall be maintained until the full flow can be passed through the permanent works. The removal of water from the required excavation on the foundation shall be accomplished in a manner and to the extent that will maintain stability of the excavated slopes and bottom required excavation and will allow satisfactory performance of all construction operations. During the placing and compacting of material in required excavations, the water level at the locations being refilled shall be maintained below the bottom of excavation at such locations which may require draining the water pumps from which the water shall be pumped.



Stabilization
All borrow areas shall be graded to provide proper drainage and left 1 to 2% cross slope. All exposed surfaces of the embankment, spillway, spoil and borrow areas, and berms shall be stabilized by seeding, liming, fertilizing and mulching in accordance with the Natural Resources Conservation Service Standards and Specifications for Onsite Area Planting (MD-342) or as shown on the accompanying drawings.

Erosion and Sediment Control
Construction operations will be carried out in such a manner that erosion will be controlled and water and air pollution minimized. State and local laws concerning pollution abatement will be followed. Construction plans shall detail erosion and sediment control measures.

OPERATION AND MAINTENANCE SCHEDULE FOR STORMWATER MANAGEMENT EXTENDED DETENTION FACILITY
STORMWATER MANAGEMENT FACILITY
ROUTINE MAINTENANCE
1. FACILITY WILL BE INSPECTED ANNUALLY AND AFTER MAJOR STORMS.
INSPECTIONS SHOULD BE PERFORMED DURING WEATHER TO DETERMINE 5.5 FUNCTIONING PROPERLY.
2. TOP AND SIDE SLOPES OF THE EMBANKMENT SHALL BE MOWED A MINIMUM OF TWICE (2) TIMES A YEAR, ONCE IN JUNE AND ONCE IN SEPTEMBER.
OTHER SIDE SLOPES AND MAINTENANCE ACCESS SHOULD BE MOWED AS NEEDED.
3. DEBRIS AND LITTER NEXT TO THE OUTLET STRUCTURE SHALL BE REMOVED DURING REGULAR MOWING OPERATIONS AND AS NEEDED.
4. VISIBLE SIGNS OF EROSION IN THE POND AS WELL AS RIPRAP OUTLET AREAS SHALL BE REPAIRED AS SOON AS IT IS NOTICED.
NON-ROUTINE MAINTENANCE
1. STRUCTURAL COMPONENTS OF THE POND SUCH AS THE DAM, THE RISER, AND THE PIPES SHALL BE REPAIRED UPON DETECTION OF ANY DAMAGE. THE COMPONENTS SHOULD BE INSPECTED DURING ROUTINE MAINTENANCE OPERATIONS.
2. SEDIMENT SHOULD BE REMOVED WHEN ITS ACCUMULATION SIGNIFICANTLY REDUCES THE DESIGN STORAGE, INTERFERE WITH THE FUNCTION OF THE STRUCTURE WHEN DEEMED NECESSARY FOR AESTHETIC REASONS, OR WHEN DEEMED NECESSARY BY THE HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS.

OPERATION AND MAINTENANCE SCHEDULE FOR STORMWATER MANAGEMENT EXTENDED DETENTION FACILITY
STORMWATER MANAGEMENT FACILITY
ROUTINE MAINTENANCE
1. FACILITY WILL BE INSPECTED ANNUALLY AND AFTER MAJOR STORMS.
INSPECTIONS SHOULD BE PERFORMED DURING WEATHER TO DETERMINE 5.5 FUNCTIONING PROPERLY.
2. TOP AND SIDE SLOPES OF THE EMBANKMENT SHALL BE MOWED A MINIMUM OF TWICE (2) TIMES A YEAR, ONCE IN JUNE AND ONCE IN SEPTEMBER.
OTHER SIDE SLOPES AND MAINTENANCE ACCESS SHOULD BE MOWED AS NEEDED.
3. DEBRIS AND LITTER NEXT TO THE OUTLET STRUCTURE SHALL BE REMOVED DURING REGULAR MOWING OPERATIONS AND AS NEEDED.
4. VISIBLE SIGNS OF EROSION IN THE POND AS WELL AS RIPRAP OUTLET AREAS SHALL BE REPAIRED AS SOON AS IT IS NOTICED.
NON-ROUTINE MAINTENANCE
1. STRUCTURAL COMPONENTS OF THE POND SUCH AS THE DAM, THE RISER, AND THE PIPES SHALL BE REPAIRED UPON DETECTION OF ANY DAMAGE. THE COMPONENTS SHOULD BE INSPECTED DURING ROUTINE MAINTENANCE OPERATIONS.
2. SEDIMENT SHOULD BE REMOVED WHEN ITS ACCUMULATION SIGNIFICANTLY REDUCES THE DESIGN STORAGE, INTERFERE WITH THE FUNCTION OF THE STRUCTURE WHEN DEEMED NECESSARY FOR AESTHETIC REASONS, OR WHEN DEEMED NECESSARY BY THE HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS.



OPERATION AND MAINTENANCE SCHEDULE FOR STORMWATER MANAGEMENT EXTENDED DETENTION FACILITY
STORMWATER MANAGEMENT FACILITY
ROUTINE MAINTENANCE
1. FACILITY WILL BE INSPECTED ANNUALLY AND AFTER MAJOR STORMS.
INSPECTIONS SHOULD BE PERFORMED DURING WEATHER TO DETERMINE 5.5 FUNCTIONING PROPERLY.
2. TOP AND SIDE SLOPES OF THE EMBANKMENT SHALL BE MOWED A MINIMUM OF TWICE (2) TIMES A YEAR, ONCE IN JUNE AND ONCE IN SEPTEMBER.
OTHER SIDE SLOPES AND MAINTENANCE ACCESS SHOULD BE MOWED AS NEEDED.
3. DEBRIS AND LITTER NEXT TO THE OUTLET STRUCTURE SHALL BE REMOVED DURING REGULAR MOWING OPERATIONS AND AS NEEDED.
4. VISIBLE SIGNS OF EROSION IN THE POND AS WELL AS RIPRAP OUTLET AREAS SHALL BE REPAIRED AS SOON AS IT IS NOTICED.
NON-ROUTINE MAINTENANCE
1. STRUCTURAL COMPONENTS OF THE POND SUCH AS THE DAM, THE RISER, AND THE PIPES SHALL BE REPAIRED UPON DETECTION OF ANY DAMAGE. THE COMPONENTS SHOULD BE INSPECTED DURING ROUTINE MAINTENANCE OPERATIONS.
2. SED




NOTES APPLICABLE TO ALL TYPE B TERMINALS

- 6:1 MAX GRADING IS ALLOWABLE WHEN THE BARRIER IS LOCATED 12 FT. OR MORE FROM THE OUTSIDE EDGE OF SHOULDER.
- ADD DELINEATION ON END OF TREATMENT AS DIRECTED BY THE OFFICE OF TRAFFIC AND SAFETY.
- 4' FLARE REQUIRED.
- TYPE B TERMINAL SHALL ONLY BE USED WHEN THE GRADING AS SHOWN AND THE REQUIRED LENGTH OF NEED IS PROVIDED.



MDSHA-605.02



CAST-IN-PLACE STRUCTURE (CS-1) DETAIL
SCALE: 1/2"=1'




MGWC 1.5: SANDBAG/STONE DIVERSION



NOTES

- ALL POSTS SHALL BE 6' IN LENGTH. POSTS 1 AND 2 SHALL BE 4'-0" IN LENGTH.
- THE SLOPE BACK FILL MATERIAL SHALL BE COMPACTED FIRMLY TO THE ESTABLISHED SLOPE AND STABILIZED AS DIRECTED BY THE ENGINEER.
- THE CONTRACTOR HAS THE OPTION TO CONSTRUCT THE END ANCHORAGE TERMINAL USING ONE OF THE TWO OPTIONS. OPTION 1 - 4" STEEL POSTS (SEE STD. MD 605.01-02). OPTION 2 - CONCRETE ANCHOR BLOCK (SEE STD. MD 605.01-03).
- LOW SPEED INSTALLATIONS REQUIRE 50 FEET (MINIMUM) USING A 9:1 FLARE RATE.
- PAID FOR PER LINEAR FOOT OF "TRAFFIC BARRIER W BEAM USING 6 FOOT POST." THE "END ANCHORAGE TERMINAL FOR TYPE A END TREATMENT EITHER OPTION," PAID FOR PER EACH.
- FOR ALTERNATIVE OFFSET BLOCKS SEE STD. MD 605.01 NOTE 4.


MDSHA-605.01




NOTES

- NOTES ON STD. MD 605.10 APPLY TO OPTION 2 & 3.
- IF THE FOUNDATION TUBE AND SOIL PLATE (OPTION 2) ARE DRIVEN INTO THE SOIL, PROPER CARE SHOULD BE TAKEN TO ENSURE THAT THE SOIL PLATE FASTENERS ARE NOT BROKEN DURING THE DRIVING PROCESS.
- SECURE BEARING PLATE WITH 16 PENNY GALVANIZED NAIL TO PREVENT ROTATION OF PLATE.
- SAME AS MD 605.01 NOTE 6.

MDSHA-605.10.01




MGWC 1.5: SANDBAG/STONE CHANNEL DIVERSION
Temporary measure for dewatering in channel construction sites



DESCRIPTION
The work should consist of installing sandbag or stone flow diversion for the purpose of erosion control when construction activities occur within the stream channel.

INSTALLATION GUIDELINES

- All erosion and sediment control devices, including diverting basins, should be implemented as the first order of business according to a plan approved by the WMA or local authority. Installation should proceed from the upstream to the downstream during periods of low flow. If necessary, silt fence or stow around the perimeter of the work area. Sand bag/stone diversions can be used independently or as component of other stream diversion techniques. Installation of these measures should proceed as follows (refer to Detail 1.5):
- The diversion structure should be installed from upstream to downstream.
- The height of the sandbag/stone diversion should be a function of the duration of the project in the stream height, measured from the channel bed, plus 1 foot (0.3 meters) or bankfull height, whichever is greater. For projects of longer duration, the top of the sandbag or stone diversion should correspond to bankfull height. For diversion structures utilizing sandbags, the stream bed should be hand prepared prior to placement of the base layer of sandbags in order to ensure a water tight fit. Additionally, it may be necessary to prepare the bank in a similar fashion.
- All excavated material should be deposited and stabilized in an approved area outside 100-year floodplain unless otherwise authorized by the WMA.
- Sediment-laden water from the construction area should be pumped to a dewatering basin.
- Sheeting on the diversion should be positioned such that the upstream portion covers the downstream portion with at least a 18-inch (0.45 meters) overlap.
- Sandbag or stone diversions should not obstruct more than 40% of the stream width. Additionally, bank stabilization measures should be placed in the constructed section if accelerated erosion and bank scour are observed during the construction time or if the project time is expected to last more than 2 weeks.
- Prior to removal of these temporary structures, any accumulated sediment should be removed, deposited and stabilized in an approved area outside the 100-year floodplain unless authorized by the WMA.
- Sediment control devices, including perimeter erosion controls, are to remain in place until all disturbed areas are stabilized in accordance with an approved sediment and erosion control plan and the inspection authority approves their removal.



OWNER/DEVELOPER
ELKRIDGE DEVELOPMENT, LLC
301 TRANSYLVANIA AVENUE
RALEIGH, NC 27609
(919) 789-9289

ELKRIDGE DEVELOPMENT NO.2, LLC
301 TRANSYLVANIA AVENUE
RALEIGH, NC 27609
(919) 789-9289

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

10-19-06
DATE

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

10/22/06
DATE

10/20/06
DATE

THESE PLANS HAVE BEEN REVIEWED FOR HOWARD SOIL CONSERVATION DISTRICT AND MEETS THE TECHNICAL REQUIREMENTS.

10/17/06
DATE

10/17/06
DATE

ENGINEER'S CERTIFICATE:

10/16/06
DATE

10/16/06
DATE

DEVELOPER'S CERTIFICATE:

10/16/06
DATE

10/16/06
DATE

THE SWMF TO BE OWNED BY MDSA, AND MAINTAINED BY HOA L. F.


ADD MGWC 1.5 DETAILS	4-20-07
NO.	REVISION

FINAL ROAD CONSTRUCTION PLANS



STORMWATER MANAGEMENT DETAILS, AND STORM DRAIN PROFILES BELMONT STATION

PARCELS 'A', 'B' & 'C' & OPEN SPACE LOT 1
REF: WP-04-152, WP-06-79, S-04-10, P-05-17, F-06-169
TAX MAP 37 BLOCK 18
1ST ELECTION DISTRICT

ROBERT H. VOGEL ENGINEERING, INC.
ENGINEERS • SURVEYORS • PLANNERS
8407 MAIN STREET
ELICOTT CITY, MD 21043
TEL: 410.461.7666
FAX: 410.461.8961



DESIGN BY: WLZ
DRAWN BY: DZ
CHECKED BY:
DATE: OCTOBER 2006
SCALE: AS SHOWN
W.O. NO.: 04-08



VICINITY MAP
SCALE: 1"=2000'

LEGEND

- EX. CONTOUR
- PROP. CONTOUR
- EX. SPOT ELEVATION
- EX. SPOT ELEVATION
- EX. CURB AND GUTTER
- EX. CURB AND GUTTER
- EX. UTILITY POLE
- EX. LIGHT POLE
- EX. MAILBOX
- EX. SIGN
- EX. SANITARY MANHOLE
- EX. SANITARY LINE
- EX. CLEANOUT
- EX. FIRE HYDRANT
- EX. WATER LINE
- PROP. STORM DRAIN
- PROP. STORM DRAIN INLET
- EX. TREES (FIELD LOCATED)
- EX. TREES (FIELD LOCATED)
- EX. VEGETATION (APPROXIMATE LOCATION)
- EX. FENCE
- PROPERTY LINE
- RIGHT-OF-WAY LINE
- SOILS BOUNDARY
- FOREST CONSERVATION SIGNS
- EX. FOREST CONSERVATION EASEMENT (RETENTION)
- EX. FOREST CONSERVATION EASEMENT (REFORESTATION)
- PROP. FOREST CONSERVATION EASEMENT (REFORESTATION)
- EX. PRIVATE NOISE BERM AND ENTRANCE FEATURE EASEMENT
- LIMIT OF EX. WETLANDS AND WETLANDS BUFFER
- EX. 100 YR FLOODPLAIN BOUNDARY AND UTILITY EASEMENT
- STREAM
- STREAM BUFFER
- EX. MODERATE SLOPES (15-24.99%)
- EX. STEEP SLOPES (25% OR GREATER)
- EX. SEPTIC AREA
- 20' PUBLIC DRAINAGE & UTILITY EASEMENT PLAT# 15648 & 17057

FOREST CONSERVATION EASEMENT TABLE

EASEMENT	REFORESTATION
ESMT A	2.52
ESMT B-1	0.05
ESMT B-2	1.05
ESMT C-1	0.45
ESMT C-2	0.23
ESMT D	3.98
ESMT E	0.78
TOTAL	9.07

SOILS LEGEND

SYMBOL	NAME / DESCRIPTION	TYPE
Ba	BAILE SILT LOAM	D
CgB2	CHESTER GRAVELLY SILT LOAM, 3 TO 8 PERCENT SLOPES, MODERATELY ERODED.	B
CgC2	CHESTER SILTY SILT LOAM, 8 TO 15 PERCENT SLOPES, MODERATELY ERODED.	B
ChB2	CHESTER SILT LOAM, 3 TO 8 PERCENT SLOPES, MODERATELY ERODED.	B
ChC2	CHESTER SILTY LOAM, 8 TO 15 PERCENT SLOPES, MODERATELY ERODED.	B
Ce	COMUS SILT LOAM	B
GIB2	GLENELG LOAM, 3 TO 8 PERCENT SLOPES, MODERATELY ERODED.	B
GIC2	GLENELG LOAM, 8 TO 15 PERCENT SLOPES, MODERATELY ERODED.	B
GID2	GLENELG LOAM, 15 TO 25 PERCENT SLOPES, MODERATELY ERODED.	B
GR2	GLENVILLE SILT LOAM, 3 TO 8 PERCENT SLOPES, MODERATELY ERODED.	B
MID2	MANOR LOAM, 15 TO 25 PERCENT SLOPES, MODERATELY ERODED.	B
MIE	MANOR LOAM, 25 TO 45 PERCENT SLOPES.	B
MgB2	MANOR GRAVELLY LOAM, 3 TO 8 PERCENT SLOPES, MODERATELY ERODED.	B

NOTE: --HOWARD SOIL SURVEY, MAP NUMBER 8

PLAN VIEW
SCALE: 1"=100'

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
W. De. T. ... 10-19-06
CHIEF, BUREAU OF HIGHWAYS DATE

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING
... 10/20/06
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

DEVELOPER'S/BUILDER'S CERTIFICATE
I/WE CERTIFY THAT THE LANDSCAPING WORK ON THIS PLAN WILL BE DONE ACCORDING TO THE PLAN, SECTION 16.124 OF THE HOWARD COUNTY CODE AND THE HOWARD COUNTY LANDSCAPE MANUAL. I/WE FURTHER CERTIFY THAT UPON COMPLETION, A CERTIFICATION OF LANDSCAPE INSTALLATION, ACCOMPANIED BY AN EXECUTED ONE (1) YEAR GUARANTEE OF PLANT MATERIALS, WILL BE SUBMITTED TO THE DEPARTMENT OF PLANNING AND ZONING.
Peter D. Volk 10/6/06
SIGNATURE OF DEVELOPER DATE

OWNER/DEVELOPER
BELMONT STATION
(PARCELS A, B, C AND OPEN SPACE LOT 1)
ELKRIDGE DEVELOPMENT, LLC
301 TRANSYLVANIA AVENUE
RALEIGH, NC 27609
(919) 789-9289
ELKRIDGE DEVELOPMENT NO.2, LLC
301 TRANSYLVANIA AVENUE
RALEIGH, NC 27609
(919) 789-9289


OWNER - BUILDABLE
FOX CREEK
PRESERVATION PARCELS 'A' & 'D'
RICHARD W. TENNANT
MARY L. TENNANT (DECEASED)
12256 FREDERICK ROAD
ELLCOTT CITY, MARYLAND
21042

FOX CREEK
PARCEL A AND PARCEL D
FOX CREEK SUBDIVISION RECORDED AS PLAT 17293-17296
DPZ FILE NUMBERS-S-00-03, F-01-163, F-01-163, F-01-163, P-01-01,
RE-01-02, WP-01-02, F-02-44, PLAT NO. 15646-15649, F-05-119
ZONED RR-DEO
TAX MAP 15, BLOCK 12 & 18
TAX MAP 15, BLOCK 12 & 18
3RD ELECTION DISTRICT
PARCEL '183'
HOWARD COUNTY, MARYLAND

3	REVISE FOR AREAS B-1 & B-2, PARCEL A'	6-10-06
NO.	REVISION	DATE

FINAL ROAD CONSTRUCTION PLANS
FOREST CONSERVATION PLAN
BELMONT STATION
PARCELS 'A', 'B' & 'C' AND OPEN SPACE LOT 1
REF: WP-04-152, WP-06-79, S-04-10, P-05-17, F-06-169, F-07-093
TAX MAP 37, BLOCK 18
1ST ELECTION DISTRICT
HOWARD COUNTY, MARYLAND

ROBERT H. VOGEL
ENGINEERS • SURVEYORS • PLANNERS
8407 MAIN STREET
ELLCOTT CITY, MD 21043
TEL: 410.461.7666
FAX: 410.461.8961



DESIGN BY: WJZ
DRAWN BY: DZ
CHECKED BY: WJZ
DATE: OCTOBER 2006
SCALE: AS SHOWN
W.O. NO.: 04-08
11 SHEET OF 14

LONG TERM FOREST MANAGEMENT

PLANTED AREAS MAY BE MANAGED FOR AESTHETICS, WILDLIFE, TIMBER PRODUCTS AND WATERSHED PROTECTION IN ACCORDANCE WITH SOUND FOREST MANAGEMENT PRACTICES. CONTROL OF INVASIVES SUCH AS MULTIFLORA ROSE AND HONEYSUCKLE WILL BE CRUCIAL DURING THE ESTABLISHMENT YEARS. A FOREST MANAGEMENT PLAN SHOULD BE DEVELOPED BY A MARYLAND REGISTERED FORESTER FOR RECOMMENDATIONS BEYOND THE INITIAL 5-YEAR ESTABLISHMENT PERIOD.

REFORESTATION MONITORING NOTES

- MONTHLY VISITS DURING THE FIRST GROWING SEASON ARE TO ASSESS THE SUCCESS OF THE PLANTINGS AND TO DETERMINE IF SUPPLEMENTAL WATERING, PEST CONTROL OR OTHER ACTIONS ARE NECESSARY. EARLY SPRING VISITS WILL DOCUMENT WINTER KILL AND AUTUMN VISITS WILL DOCUMENT SUMMER KILL.
- THE MINIMUM SURVIVAL RATE SHALL BE 75% OF THE TOTAL NUMBER OF TREES PLANTED PER ACRE AT THE END OF THE TWO YEAR MAINTENANCE PERIOD. WILD TREE SEEDLINGS FROM NATURAL REGENERATION ON THE PLANTING SITE MAY BE COUNTY UP TO 50% TOWARD THE TOTAL SURVIVAL NUMBER IF THEY ARE HEALTHY NATIVE SPECIES AT LEAST 12 INCHES TALL.
- SURVIVAL WILL BE DETERMINED BY A STRATIFIED RANDOM SAMPLE OF THE PLANTINGS. THE SPECIES COMPOSITION OF THE SAMPLE POPULATION SHOULD BE PROPORTIONATE TO THE AMOUNT OF EACH SPECIES IN THE ENTIRE PLANTING TO BE SAMPLED.
- EFFECTIVE MONITORING WILL ASSESS PLANT SURVIVABILITY DURING THE FIRST GROWING SEASON AND MAKE RECOMMENDATIONS FOR REINFORCEMENT PLANTING IF REQUIRED AT THE TIME.

REFORESTATION AREA PLANTING NOTES

- INITIAL PLANTING INSPECTION AND CERTIFICATION REQUIRED.
- REFORESTATION AREAS MAY BE PLANTED AS SOON AS REASONABLE TO DO SO LATE WINTER - EARLY SPRING PLANTINGS ARE PREFERRED. EARLIEST PLANTING DATES WILL VARY FROM YEAR TO YEAR BUT PLANTING MAY GENERALLY BEGIN AS SOON AS THE GROUND IS NO LONGER FROZEN. ALTERNATE PLANTING DATES MAY BE CONSIDERED AS CONDITIONS WARRANT.
- SOIL AMENDMENTS AND FERTILIZATION RECOMMENDATIONS WILL BE MADE BASED UPON THE RESULTS OF SOIL ANALYSIS FOR NITROGEN, PHOSPHORUS, POTASSIUM, ORGANIC MATTER CONTENT AND PH. IF REQUIRED, FERTILIZER WILL BE PROVIDED USING A SLOW RELEASE, SOLUBLE 16-8-16 ANALYSIS DESIGNED TO LAST 5-8 YEARS CONTAINED IN POLYETHYLENE PERFORATED BAGS SUCH AS MANUFACTURED BY ADCO WORKS, P.O. BOX 310 HOLLIS, NY 11423 OR APPROVED EQUAL.
- PLANT MATERIALS SHALL BE PLANTED IN ACCORDANCE WITH THE PLANTING DIAGRAM, PLANTING DETAILS AND PLANTING SCHEDULE.
- PLANT STOCK MUST BE PROTECTED FROM DESICCATION AT ALL TIMES PRIOR TO PLANTING. MATERIALS HELD FOR PLANTING SHALL BE MOISTENED AND PLACED IN COOL SHADED AREAS UNTIL READY FOR PLACEMENT.
- PLANTING MATERIALS SHALL BE NURSERY GROWN AND INSPECTED PRIOR TO PLANTING. PLANTS NOT CONFORMING TO THE AMERICAN STANDARDS FOR NURSERY STOCK SPECIFICATIONS FOR SIZE, FORM, VIGOR, OR ROOTS, OR DUE TO TRUNK WOUNDS, BREAKAGE, DESICCATION, INSECT OR DISEASE MUST BE REPLACED.
- ALL STOCK TO BE CONTAINER GROWN WITH DEER REPELLENT TABLETS IN GROWING MEDIUM SUCH AS "REPELLEX."
- NEWLY PLANTED TREES MAY REQUIRE WATERING AT LEAST ONCE PER WEEK DURING THE FIRST GROWING SEASON DEPENDING ON RAINFALL IN ORDER TO GET ESTABLISHED. THE INITIAL PLANTING OPERATION SHOULD ALLOW FOR WATERING DURING INSTALLATION TO COMPLETELY SOAK BACKFILL MATERIALS.
- MULCH SHALL BE APPLIED IN ACCORDANCE WITH THE DIAGRAM PROVIDED AND SHALL CONSIST OF COMPOSTED, SHREDDED HARDWOOD BARK MULCH, FREE OF WOOD ALCOHOL.
- PLANTING HOLES SHOULD BE EXCAVATED TO A MINIMUM DIAMETER OF 2.5 TO 3 TIMES THE DIAMETER OF THE ROOT BALL OR CONTAINER. MECHANICAL AUGURING IS PREFERRED WITH SCARIFICATION OF THE SIDES OF EACH HOLE.

PLANT SELECTION AND DENSITY SPACING REQUIREMENTS

PLANTING MATERIAL SIZE AND DENSITY SPACING:
PLANTING SIZE AND DENSITY MAY VARY WITH A COMBINATION OF PLANTING STOCK WHICH WILL BE DETERMINED AT THE TIME OF PLANTING. PLANTING QUANTITY AND SPACING ARE BASED ON SQUARE FOOTAGE CREDIT, WHICH VARIES BY MATERIAL SIZE. A TOTAL OF 43,560 SF OF PLANTING CREDIT MUST BE FULFILLED FOR EACH ACRE PLANTED. THIS CREDIT CAN BE FULFILLED WITH ANY COMBINATION OF MATERIAL SIZE IN ACCORDANCE WITH THE FOLLOWING CHART.

PLANT MATERIAL SIZE TABLE

MATERIAL SIZE	SPACING	TPA	SF CREDIT PER PLANT	COMMENTS
2" CALIPER TREES	20' X 20'	100	435.6	B & B
1" CALIPER TREES	15' X 15'	200	217.8	B & B
SEEDLINGS OR WHIPS	11' X 11'	350	125	CONTAINER 1-3 GAL. W/ TREE SHELTERS
SEEDLINGS	8' X 8'	700	62	BARE ROOT OR CONTAINER GROWN

EASEMENT	REFORESTATION
ESMT A	2.52
ESMT B-1	0.05
ESMT B-2	1.85
ESMT C-1	0.45
ESMT C-2	2.23
ESMT D	3.96
ESMTE	0.79
TOTAL	9.87



APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

William T. ... 10-19-06
CHIEF, BUREAU OF HIGHWAYS DATE

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

... 10/20/06
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

... 10/20/06
CHIEF, DIVISION OF LAND DEVELOPMENT DATE



PROPOSED FOREST CONSERVATION EASEMENTS A-E 9.88 AC

QTY	BOTANICAL NAME	COMMON NAME	MIN. SIZE	SPACING	NOTES
EASEMENT A: 2.52 AC (200 TPA) = 504					
72	ACER RUBRUM	RED MAPLE	1" CAL.	15' O.C.	1" CAL. BALLED AND BURLAPED
72	LIQUIDAMBAR STYRACIFLUA	SWEETGUM	1" CAL.	15' O.C.	
72	PLATANUS OCCIDENTALIS	SYCAMORE	1" CAL.	15' O.C.	
72	QUERCUS PALUSTRIS	PIN OAK	1" CAL.	15' O.C.	
72	CERCIS CANADENSIS	REDBUD	1" CAL.	15' O.C.	
72	CARPINUS CAROLINIANA	AMERICAN HORNBEEAM	1" CAL.	15' O.C.	
72	PINUS TAEDA	LOBLOLLY PINE	1" CAL.	15' O.C.	
EASEMENT B-1 & B-2: 1.90 AC (200 TPA) = 380					
55	ACER RUBRUM	RED MAPLE	1" CAL.	15' O.C.	1" CAL. BALLED AND BURLAPED
55	LIQUIDAMBAR STYRACIFLUA	SWEETGUM	1" CAL.	15' O.C.	
54	PLATANUS OCCIDENTALIS	SYCAMORE	1" CAL.	15' O.C.	
54	QUERCUS PALUSTRIS	PIN OAK	1" CAL.	15' O.C.	
54	CERCIS CANADENSIS	REDBUD	1" CAL.	15' O.C.	
54	CARPINUS CAROLINIANA	AMERICAN HORNBEEAM	1" CAL.	15' O.C.	
54	PINUS TAEDA	LOBLOLLY PINE	1" CAL.	15' O.C.	
EASEMENT C1: 0.45 AC (200 TPA) = 90					
14	ACER RUBRUM	RED MAPLE	1" CAL.	15' O.C.	1" CAL. BALLED AND BURLAPED
14	LIQUIDAMBAR STYRACIFLUA	SWEETGUM	1" CAL.	15' O.C.	
14	PLATANUS OCCIDENTALIS	SYCAMORE	1" CAL.	15' O.C.	
12	QUERCUS PALUSTRIS	PIN OAK	1" CAL.	15' O.C.	
12	CERCIS CANADENSIS	REDBUD	1" CAL.	15' O.C.	
12	CARPINUS CAROLINIANA	AMERICAN HORNBEEAM	1" CAL.	15' O.C.	
12	PINUS TAEDA	LOBLOLLY PINE	1" CAL.	15' O.C.	
EASEMENT C2: 0.23 AC (200 TPA) = 46					
7	ACER RUBRUM	RED MAPLE	1" CAL.	15' O.C.	1" CAL. BALLED AND BURLAPED
6	LIQUIDAMBAR STYRACIFLUA	SWEETGUM	1" CAL.	15' O.C.	
6	PLATANUS OCCIDENTALIS	SYCAMORE	1" CAL.	15' O.C.	
6	QUERCUS PALUSTRIS	PIN OAK	1" CAL.	15' O.C.	
6	CERCIS CANADENSIS	REDBUD	1" CAL.	15' O.C.	
6	CARPINUS CAROLINIANA	AMERICAN HORNBEEAM	1" CAL.	15' O.C.	
6	PINUS TAEDA	LOBLOLLY PINE	1" CAL.	15' O.C.	
EASEMENT D: 3.98 AC (200 TPA) = 796					
115	ACER RUBRUM	RED MAPLE	1" CAL.	15' O.C.	1" CAL. BALLED AND BURLAPED
115	LIQUIDAMBAR STYRACIFLUA	SWEETGUM	1" CAL.	15' O.C.	
114	PLATANUS OCCIDENTALIS	SYCAMORE	1" CAL.	15' O.C.	
114	QUERCUS PALUSTRIS	PIN OAK	1" CAL.	15' O.C.	
114	CERCIS CANADENSIS	REDBUD	1" CAL.	15' O.C.	
114	CARPINUS CAROLINIANA	AMERICAN HORNBEEAM	1" CAL.	15' O.C.	
114	PINUS TAEDA	LOBLOLLY PINE	1" CAL.	15' O.C.	
EASEMENT E: 0.79 AC (200 TPA) = 158					
24	ACER RUBRUM	RED MAPLE	1" CAL.	15' O.C.	1" CAL. BALLED AND BURLAPED
24	LIQUIDAMBAR STYRACIFLUA	SWEETGUM	1" CAL.	15' O.C.	
22	PLATANUS OCCIDENTALIS	SYCAMORE	1" CAL.	15' O.C.	
22	QUERCUS PALUSTRIS	PIN OAK	1" CAL.	15' O.C.	
22	CERCIS CANADENSIS	REDBUD	1" CAL.	15' O.C.	
22	CARPINUS CAROLINIANA	AMERICAN HORNBEEAM	1" CAL.	15' O.C.	
22	PINUS TAEDA	LOBLOLLY PINE	1" CAL.	15' O.C.	
1980	TOTAL PLANTINGS				


FOREST CONSERVATION NARRATIVE

THIS FOREST CONSERVATION PLAN WAS PREPARED IN ACCORDANCE WITH THE HOWARD COUNTY FOREST CONSERVATION MANUAL.


THIS PLAN PROVIDES OFF-SITE PLANTING FOR BELMONT STATION. THE REQUIRED REFORESTATION OBLIGATION FOR THIS SUBDIVISION IS 9.83 ACRES AND WILL BE FULFILLED BY PLANTING 9.87 ACRES WITHINSEVEN FOREST CONSERVATION EASEMENTS LOCATED ON THE FOX CREEK SUBDIVISION, PRESERVATION PARCELS A & D, TAX MAP 15, F-01-013, FOX CREEK PRESERVATION PARCELS A, PLAT NO. 18712-18715.

PLANTINGS SHALL OCCUR USING THE STOCK SIZE SHOWN ON THE PLANTING SCHEDULE. HOWEVER IF DUE TO SEASONAL VARIABILITY THE PRESCRIBED SIZE OR SPECIES ARE NOT AVAILABLE, SUBSTITUTIONS MAY BE MADE IF APPROVED BY HOWARD COUNTY PRIOR TO INSTALLATION.


THE FOREST CONSERVATION OBLIGATION OF 9.83 ACRES OF REFORESTATION FOR THIS SUBDIVISION WILL BE MET BY PROVIDING 9.87 ACRES OF REFORESTATION FOREST CONSERVATION EASEMENTS (FCE A-E) OFFSITE ON BUILDABLE PRESERVATION PARCELS A & D, FOX CREEK. FOREST CONSERVATION SURETY IN THE AMOUNT OF \$214,968.60 WILL BE POSTED AS PART OF THE DEVELOPER'S AGREEMENT.



NOTE:
1. BOTTOM OF SIGNS TO BE HIGHER THAN TOP OF TREE PROTECTION FENCE.
2. SIGNS TO BE PLACED APPROXIMATELY 50-100 FEET APART. CONDITIONS ON SITE AFFECTING VISIBILITY MAY WARRANT PLACING SIGNS CLOSER OR FARTHER APART.
3. ATTACHMENT OF SIGNS TO TREES IS PROHIBITED.



NOTE:
1. THE SIGNS NOTIFY CONSTRUCTION WORKERS AND FUTURE RESIDENTS OF THE NEWLY PLANTED MATERIAL, IMPROVING THE TREES' SURVIVAL RATES.
2. SIGNS MAY BE ADAPTED BY RESIDENTS FOR IDENTIFICATION OF FOREST RETENTION AREAS IN LONG TERM.



NOTES:
1. Forest protection device only.
2. Retention area will be set as part of the review process.
3. Boundaries of retention area should be staked and flagged prior to installing device.
4. Foot damage should be avoided.
5. Protection signage should be used.
6. Device should be maintained throughout construction.

BLAZE ORANGE PLASTIC MESH
TYPICAL TREE PROTECTION FENCE DETAIL
NO SCALE

FOREST CONSERVATION WORKSHEET

NET TRACT AREA:	
A. TOTAL TRACT AREA	27.80 AC
B. AREA WITHIN 100 YEAR FLOODPLAIN	7.06 AC
C. AREA TO REMAIN IN AGRICULTURAL PRODUCTION	0.00 AC
D. NET TRACT AREA	20.80 AC

LAND USE CATEGORY (FROM TABLE 3.2.1, PAGE 40, MANUAL)

INPUT THE NUMBER "1" UNDER THE APPROPRIATE LAND USE ZONING, AND LIMIT TO ONLY ONE ENTRY.

ARA	MOR	IDA	HDR	MPD	CIA
0	0	0	1	0	0

E. AFFOREST THRESHOLD 15% X C = 3.12 AC
F. CONSERVATION THRESHOLD 20% X C = 4.16 AC

EXISTING FOREST COVER:
G. EXISTING FOREST COVER (EXCLUDING FLOODPLAIN) = 10.20 AC
H. AREA OF FOREST ABOVE AFFORESTATION THRESHOLD = 8.32 AC
I. AREA OF FOREST ABOVE CONSERVATION THRESHOLD = 6.04 AC

BREAK EVEN POINT:
H. FOREST RETENTION ABOVE THRESHOLD WITH NO MITIGATION = 5.37 AC
I. CLEARING PERMITTED WITHOUT MITIGATION = 4.83 AC

PROPOSED FOREST CLEARING:
J. TOTAL AREA OF FOREST TO BE CLEARED = 10.20 AC
K. TOTAL AREA OF FOREST TO BE RETAINED = 0.00 AC

PLANTING REQUIREMENTS:
L. REFORESTATION FOR CLEARING ABOVE CONSERVATION THRESHOLD = 1.51 AC
M. REFORESTATION FOR CLEARING BELOW CONSERVATION THRESHOLD = 8.32 AC
N. CREDIT FOR RETENTION ABOVE CONSERVATION THRESHOLD = 0.00 AC
O. TOTAL REFORESTATION REQUIRED = 9.83 AC
P. TOTAL AFFORESTATION REQUIRED = 0.00 AC
R. TOTAL REFORESTATION AND AFFORESTATION REQUIRED = 9.83 AC

THE FOREST CONSERVATION OBLIGATIONS OF 9.83 ACRES OF REFORESTATION FOR SUBDIVISION WILL BE MET BY PROVIDING 9.87 ACRES OF REFORESTATION FOREST CONSERVATION EASEMENTS (FCE A-E) OFFSITE ON BUILDABLE PRESERVATION PARCELS A & D, FOX CREEK. FOREST CONSERVATION SURETY IN THE AMOUNT OF \$214,968.60 WILL BE POSTED AS PART OF THE DEVELOPER'S AGREEMENT.

LARRY A. THOMPSON 10.6.06
DNR QUALIFIED PROFESSIONAL


OWNER - BUILDABLE FOX CREEK PRESERVATION PARCELS 'A' & 'D'

RICHARD W. TENNANT
MARY L. TENNANT (DECEASED)
12256 FREDERICK ROAD
ELLICOTT CITY, MARYLAND
21042


FOX CREEK PARCEL A AND PARCEL D
FOX CREEK SUBDIVISION RECORDED AS PLAT 17293-17296
DPZ FILE NUMBERS-S-00-03, F-01-163, F-01-52, P-01-01,
RE-01-02, WP-01-02, F-02-44, PLAT NO. 15646-15649, F-05-119
ZONED RR-DEO

TAX MAP 15, BLOCK 12 & 18
TAX MAP 15, BLOCK 12 & 18
3RD ELECTION DISTRICT

PARCEL '183'
HOWARD COUNTY, MARYLAND



NOTE:
1. PLANT MIX TO BE 1/3 PIONEER & 2/3 MID TO LATE SUCCESSIONAL SPECIES
2. PLANT LARGER STOCK AND EVERGREENS AROUND PERIMETER TO PROTECT INTERIOR SMALLER STOCK.
3. WHEN SHRUBS ARE SPECIFIED, PLANT THEM IN CLUSTERS.
4. DO NOT PLANT TREES IN A GRID PATTERN.



DENSITY CHART

SIZE	QTY. PER ACRE	AVERAGE SPACING
2" CALIPER	100	20'x20'
1" CALIPER	200	15'x15'
WHIPS	350	11'x11'
SEEDLINGS	700	8'x8'

NO.	REVISION	DATE
3	REVISE FCE AREAS B-1 & B-2, PARCEL A	6/10/06

FINAL ROAD CONSTRUCTION PLANS

FOREST CONSERVATION PLAN

BELMONT STATION
PARCELS 'A', 'B' & 'C' & OPEN SPACE LOT 1
REF: WP-04-152, WP-06-79, S-04-10, P-05-17, F-06-169, F-01-093
TAX MAP 37 BLOCK 18 PARCEL 196, 198, 199
1ST ELECTION DISTRICT HOWARD COUNTY, MARYLAND

ROBERT H. VOGEL ENGINEERING, INC.
ENGINEERS • SURVEYORS • PLANNERS
8407 MAIN STREET ELLICOTT CITY, MD 21043 TEL: 410.461.7666 FAX: 410.461.8961

DESIGN BY: WJZ
DRAWN BY: DZ
CHECKED BY: WJZ
DATE: OCTOBER 2006
SCALE: AS SHOWN
W.O. NO.: 04-08


12 SHEET OF 14

Retaining Wall Specifications and Guidelines

- Part 1: General**
- 1.01 Description**
- A. Retaining walls must be constructed under the supervision of a Maryland Registered Professional Engineer.
 - B. Work includes preparation of foundation soils, furnishing all materials, and installing all materials to the lines and grades shown on the construction drawings.
- 1.02 Codes and Standards**
- A. International Building Code - 2003, International Code Council, Inc.
 - B. ACI Manual of Concrete Practice - Parts 1 Through 5 - 2001
 - C. "Manual of Standard Practice" - Concrete Steel Reinforcing Institute
 - D. "American Society for Testing and Materials"
- 1.03 Damage, Storage, and Handling**
- A. The Contractor shall check the materials upon delivery to assure that the proper materials have been received.
 - B. The Contractor shall properly handle and store the materials to prevent damage to the materials. Damaged materials shall not be incorporated into the wall.
- 1.04 Quality Assurance**
- A. The Owner shall engage a qualified testing agency to provide observation and testing services as described below.
 - B. Concrete Placement
 - 1. The agency shall inspect the formwork and reinforcing steel placement for compliance with the contract documents. Reinforcing steel should be inspected for correct size, quantity, and spacing.
 - 2. Fresh concrete shall be sampled in accordance with ASTM C 172, and tested for slump, air entrainment, and temperature.
 - 3. Test cylinders shall be molded in accordance with ASTM C 31. Four test cylinders shall be molded for each day's pour, or for every 100 cubic yards of concrete placed, whichever is greater.
 - C. Fill Placement
 - 1. All soil fills shall be tested in accordance with ASTM D 2922.
 - 2. A minimum of one compaction test per lift should be made per 2,500 square feet of fill lift area, but not fewer than two tests per lift should be made.
 - 3. The elevations and locations of the field density tests should be clearly identified at the time of fill placement and compaction.


- Part 2: Materials**
- 2.01 Concrete**
- A. Concrete shall conform to Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 414
 - B. Concrete shall have a minimum 28-day compressive strength of 5,000 psi.
 - C. Concrete shall have a maximum slump of 6 inches and shall be air entrained to 6% (+/- 1%) by volume. Concrete for foundations does not require air entrainment.
 - D. Concrete shall have a minimum density of 145 pcf and a maximum water-to-cement ratio of 0.50
- 2.02 Steel Reinforcement**
- A. Steel reinforcing shall conform to ASTM A-615, Grade 60.
 - B. Submit shop drawings at least 15 business days before date reviewed submittals will be needed. Shop drawings shall bear the contractor's stamp of approval which shall constitute that he has verified all field measurements, construction criteria, materials, and similar data, and has checked each drawing for completeness, coordination, and compliance with contract documents.
- 2.03 Soil Backfill**
- A. Material should consist of soil classified as SM, SC, or more granular, in accordance with ASTM D 2427.
 - B. Material should have no particle larger than 2.5 inches and shall contain at least 30 percent, by weight, retained on the U.S. No. 200 sieve.
 - C. Materials should have a Liquid Limit less than 45, and a Plasticity Index less than 20.
 - D. Material should have a minimum friction angle of 28 degrees and a minimum dry unit weight of 120 pcf.
 - E. The Contractor should submit samples of the proposed backfill soils to the Geotechnical Engineer of Record for approval prior to their use.
- 2.04 Drainage Board**
- A. Drainage board used behind the walls shall consist of Miradrain 9900, or an approved equivalent.

- Part 3: Construction**
- 3.01 General**
- A. All existing underground utilities shall be properly marked, and relocated if necessary, prior to construction.
 - B. All proposed underground utilities or structures in the general wall area shall be completely installed prior to the construction of the wall.
 - C. Protect all existing and/or new structures from damage by construction equipment. Immediately repair any damage that may occur.
- 3.02 Foundation**
- A. The wall foundation shall be excavated to the grades and lines as shown on the construction drawings. Contractor should take care not to disturb foundation soils beyond the lines and grades shown.
 - B. The foundation shall bear on the minimum embedment depths indicated, as measured from the final grade at the front of the wall.
 - C. The foundation subgrade soils shall be tested by a qualified representative of the geotechnical Engineer to verify the availability of the design bearing pressure of 3,000 pcf.
 - D. If unsuitable soils are encountered at design foundation levels, the unsuitable soils shall be removed and the over-excavated areas shall be replaced with compacted structural fill.
- 3.03 Steel Reinforcement**
- A. All steel reinforcing shall have a minimum clear cover of 3 inches unless otherwise noted on the contract documents.
 - B. Where applicable, splices for reinforcing steel shall be made by contact tension lap splices.
 - C. Welding and field-bending of reinforcing steel is not permitted.
 - D. Furnish all accessories, chairs, space bars, supports, etc. necessary to secure reinforcing.
- 3.04 Cast-in-Place Concrete**
- A. Footing Concrete
 - 1. The vertical faces of the footing and key excavation may be used as forms for placement of foundation concrete.
 - 2. Foundation concrete, or protective mud mats, shall be placed the same day that the foundation subgrade is approved.
 - 3. Provide concrete protection against freezing during placement and for 5 days thereafter.
 - B. Wall Concrete
 - 1. Furnish and erect concrete forms to the lines and grades shown on the construction drawings.
 - 2. Locate construction joints as to not impair the strength of the structure, but not more than 60 feet in any direction. Provide continuous bentonite strip waterstrip at all construction joints.
 - 3. Make stops in concrete pours using vertical bulkheads.
 - 4. All reinforcing shall be continuous through joints and bulkheads.
 - 5. Chamfer exposed concrete corners 3/4" by 3/4" minimum.
 - 6. Provide 4" diameter weep holes every 8 feet along the bottom of the wall and at wall ends. The weep holes should be formed in place prior to concrete placement by using PVC pipe. Weep hole locations must not interfere with steel reinforcing, and shall be no greater than 4 inches above final grade at the front of the wall.
 - 7. Where a fence is required, it is recommended that the fence posts be installed during wall concrete placement. The fence posts shall have a minimum of 24 inches of embedment into the wall, and be located along the center of the wall. Alternatively, provide 4 inch diameter by 24 inch deep post holes at the designated fence post locations along the centerline of the wall. The post holes should be formed in place prior to concrete placement by using PVC pipe.
- 3.05 Backfilling**
- A. All soil backfill shall conform to the material requirements of section 2.03.
 - B. Backfill shall be moisture conditioned to within 2 percentage points of the optimum moisture content, as determined in accordance with ASTM D-698.
 - C. Backfill shall be placed in loose lifts, not exceeding 8 inches in thickness, and then compacted to at least 95 percent of the maximum dry density, as determined in accordance with ASTM D-698.
 - D. Backfilling shall not occur against the wall until the wall concrete has attained at least 75 percent of the 28-day design strength, and no earlier than 3 days after placement.
 - E. Where feasible, maintain equal grades on each side of the wall during backfilling to prevent overturning and lateral movements. When the grade differential at the wall exceeds 12 inches, only hand-operated compaction equipment shall be allowed.
 - F. Drainage boards shall be placed against the wall, extending from the weep hole up within 12 inches of final grade at the top of the wall.
- 3.06 Finish**
- A. Refer to Architectural drawings and specifications for detailed information regarding wall finish and wall cap (if any).
 - B. Final grades at the wall shall be established by the Contractor in accordance with the most recent site grading plans.
 - C. Final grades shall be stabilized and seeded per the approved civil plans unless noted otherwise on the site grading plans.
 - D. Install fence at the top of the wall in accordance with project documents. If fence posts are installed subsequent to wall construction, the fence posts shall be grouted into the PVC post holes using 3,000 psi non-shrink grout.
 - E. See Architectural or Landscape plans and specifications for additional fence details.




PLAN VIEW

SCALE 1"=30'




FOOTING STEP NTS


WALL #1 REINFORCEMENT	
A	#9 @ 16" O.C.
B	#5 @ 12" O.C.
C	#9 @ 16" O.C.
D	#7 @ 16" O.C.



WALL #1 TYPICAL SECTION NTS



CONSTRUCTION JOINT NTS



WALL #1 PROFILE

SCALE
VERTICAL SCALE 1"=4'
HORIZONTAL SCALE 1"=10'
FOR CLARITY, FENCE NOT SHOWN ON ELEVATION VIEW

OWNER/DEVELOPER
ELKRIDGE DEVELOPMENT, LLC ELKRIDGE DEVELOPMENT NO.2, LLC
301 TRANSYLVANIA AVENUE 301 TRANSYLVANIA AVENUE
RALEIGH, NC 27609 RALEIGH, NC 27609
(919) 789-9289 (919) 789-9289


NO.	REVISIONS	DATE

BELMONT STATION
PARCELS 'A', 'B' & 'C' & OPEN SPACE LOT 1
REF: WP-04-152, WP-06-79, S-04-10, P-05-17, F-06-169
TAX MAP 37 BLOCK 18 PARCEL 196, 198, 199'
1ST ELECTION DISTRICT HOWARD COUNTY, MARYLAND

FINAL ROAD CONSTRUCTION PLANS

DSH	KRM	10/06/06	3417-H	13 of 14
-----	-----	----------	--------	----------

ECS MID-ATLANTIC, LLC
1340 CHARWOOD ROAD, SUITE P
HANOVER, MARYLAND 21076





APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

Willa T. Mahesh 10-19-06
CHIEF, BUREAU OF HIGHWAYS DATE

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

Michael E. Leifer 10/24/06
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE
Cindy Hunt 10/24/06
CHIEF, DIVISION OF LAND DEVELOPMENT DATE



- LEGEND:**
- EXISTING TREELINE (FIELD LOCATED)
 - EXISTING VEGETATION (APPROXIMATE LOCATION)
 - EXISTING FENCE
 - PROPERTY LINE
 - RIGHT-OF-WAY LINE
 - EXISTING CONTOUR
 - SILT FENCE
 - SUPER SILT FENCE
 - LIMIT OF DISTURBANCE
 - CURB INLET PROTECTION
 - AT GRADE INLET PROTECTION
 - MOUNTABLE BERM
 - LOCATION TO CURB SUPER SILT FENCE
 - EROSION CONTROL MATTING

OWNER/DEVELOPER
 ELKRIDGE DEVELOPMENT, LLC ELKRIDGE DEVELOPMENT NO 2, LLC
 301 TRANSYLVANIA AVENUE 301 TRANSYLVANIA AVENUE
 RALEIGH, NC 27809 RALEIGH, NC 27809
 (919) 789-9289 (919) 789-9289

2	REVISE TEMPORARY STOCKPILE #2	4-30-07
1	ADD SILT FENCE TO STREAM/SEWER CONNECTION	3-20-07

FINAL ROAD CONSTRUCTION PLANS
HAUL ROAD AND TEMPORARY STOCKPILE
BELMONT STATION
 PARCELS 'A', 'B' & 'C' & OPEN SPACE LOT 1
 REF: WP-04-152, WP-06-79, S-04-10, P-05-17, F-03-169
 TAX MAP 37 BLOCK 18 PARCEL 196, 198, 199
 1ST ELECTION DISTRICT HOWARD COUNTY, MARYLAND

ROBERT H. VOGEL ENGINEERS, INC.
 ENGINEERS • SURVEYORS • PLANNERS
 8407 MAIN STREET ELICOTT CITY, MD 21043 TEL: 410.461.7566 FAX: 410.461.8961

DESIGN BY: wjz
 DRAWN BY: dz
 CHECKED BY: [Signature]
 DATE: 10 OCTOBER 2006
 SCALE: AS SHOWN
 W.O. NO.: 04-09

14 SHEET OF 14

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

Walter J. Zausky 10-19-06
 CHIEF, BUREAU OF HIGHWAYS DATE

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

Chris DeMunnich 10/2/06
 CHIEF, DEVELOPMENT ENGINEERING DATE

Candy Hanna 10/2/06
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE

THESE PLANS HAVE BEEN REVIEWED FOR HOWARD SOIL CONSERVATION DISTRICT AND MEETS THE TECHNICAL REQUIREMENTS.

John M. ... 10/1/06
 USDA-NATURAL RESOURCES CONSERVATION SERVICE DATE

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

William W. Schmitz 10/1/06
 HOWARD S.C.D. DATE

ENGINEER'S CERTIFICATE:
 "I HEREBY CERTIFY THAT THIS PLAN FOR SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT."

Walter J. Zausky 10/1/06
 SIGNATURE OF ENGINEER WALTER J. ZAUSKY, PE DATE

DEVELOPER'S CERTIFICATE:
 "I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE IN ACCORDANCE TO THIS PLAN OF DEVELOPMENT FOR SEDIMENT CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT."

Peter G. Voelkel 10/6/06
 SIGNATURE OF DEVELOPER PETER G. VOELKEL DATE

PLAN VIEW
 SCALE: 1"=60'