

- GENERAL NOTES**
- All storm drainage if paving shall be in accordance with the latest details and specs. for Howard County & M.D.S.A.
 - Types of storm drain structures refer to the standard Details of Ho. Co. & M.D.S.A.
 - Trench compaction for storm drains within Road or Street Rights-of-Way limits shall be in accordance with Ho. Co. Design Manual Vol. II, (Class "C" Trench Bedding to be used for all storm drain unless otherwise noted).
 - Information concerning underground utilities was obtained from available records; but, the Contractor must determine the exact location and elevation of the mains by digging test pits, by hand, at all utility crossings, well in advance of construction.
 - All utility companies shall be notified 24 hrs. in advance of construction.
 - All traffic control services, parking, and signing to be done in accordance with the "Manual of Uniform Traffic Control Devices," 1978 Edition.
 - Sag & Crest Vertical Curves were designed in accordance with "Howard County Design Manual, Vol. III.
 - Design Speed: see det. sht. 3. Zoning: R (Rural)
 - The Contractor or developer shall contact the Construction Inspection Survey Division 24 hrs. in advance of commencement of work @ 792-7272.

NO.	REVISION	DATE
4	Removed 18" CMP @ entrance to Lot 2.	10-18-87
3	Added 18" CMP at entrance to Lot 2.	6-13-86
2	Revised street grade on McGee Way.	3-11-86
1	Added note regarding Homewood Road plan; revised title box.	2-4-86

DEVELOPER'S/BUILDER'S CERTIFICATE

"I/We certify that all development and construction will be done according to this plan of development and plan for erosion and sediment control and that all responsible personnel involved in the construction project will have a Certificate of Attendance at a Dept. of Natural Resources Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District or their authorized agents, as deemed necessary."

Robert Woodier
 Signature of Developer/Builder

9-25-85
 Date

ENGINEER'S CERTIFICATE

I hereby certify that this plan for Erosion and Sediment Control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District.

d.h.e. Clark
 G. Nelson Clark

9-25-85
 Date

STATE OF MARYLAND
 REGISTERED PROFESSIONAL ENGINEER
 NO. 7199

CLARK · FINEROCK & SACKETT
 ENGINEERS · PLANNERS · SURVEYORS

11315 LOCKWOOD DRIVE SILVER SPRING MARYLAND 20904 (301) 593-3400

ROAD CONSTRUCTION PLANS
 MCGEE WAY
 AND WIDENING ALONG HOMEWOOD ROAD
 POINT OF
HOMWOOD
 3RD ELECTION DISTRICT
 HOWARD COUNTY, MARYLAND


FOR: R.C. GOODIER BUILDERS, INC. (OWNER)
 233 Deep Dale Drive
 Timonium, Md. 21093

DESIGNED: GLB
 DRAWN: K/W
 CHECKED: GLB
 DATE: 9-25-85


SCALE: As Shown
 DRAWING: 10F5
 JOB NO.: 85-027
 FILE NO.: 85-027-D

Reviewed for Howard County S.C.D. Name and meets Technical Requirements
Donald B. Sackett
 Signature Date 12-10-85
 U.S. Soil Conservation Service
 THIS SOIL EROSION AND SEDIMENT CONTROL PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD COUNTY CONSERVATION DISTRICT.
Robert J. Zuhm
 Approved Date 12/10/85

PLAN
 SCALE: 1"=50'



#1163



TRAP #2 (SWALE SED. TRAP) (ST. IV)
 DA = 1.0 Acre
 Storage Required = 1.0(100) = 100 CF
 Storage Provided = 100 CF
 Depth = 3'
 Dimensions = 7'x8'
 Outlet Elev. = 432.0
 Clean Out Elev. = 430.5
 Bottom Elev. = 429.0

ROAD
 TRAFFIC (1 SWALE SED. TRAP) (ST. IV)
 DA = 0.5 Acre
 Storage Required = 0.5(100) = 50 CF
 Storage Provided = 50 CF
 Depth = 2'
 Dimensions = 6'x7.5'
 Outlet Elev. = 430.0
 Clean Out Elev. = 429.0
 Bottom Elev. = 428.0

Reviewed for Howard S.C.D.
 Name
 and meets Technical Requirements
 Signature: Robert W. Ziehm
 Date: 12-10-85
 U.S. Soil Conservation Service

THIS DEVELOPMENT PLAN IS APPROVED
 FOR SOIL EROSION AND SEDIMENT
 CONTROL BY THE HOWARD SOIL
 CONSERVATION DISTRICT.



DEVELOPER'S/BUILDER'S CERTIFICATE
 "I/We certify that all development and construction will be done according to this plan of development and plan for erosion and sediment control and that all responsible personnel involved in the construction project will have a Certificate of Attendance at a Dept. of Natural Resources Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District or their authorized agents, as deemed necessary."
 Signature: Robert Woodley
 Date: 9-25-85

ENGINEER'S CERTIFICATE
 I hereby certify that this plan for Erosion and Sediment Control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District.
 Signature: G. Nelson Clark
 Date: 9-25-85

APPROVED: DEPARTMENT OF PUBLIC WORKS
 Chief, Bureau of Engineering
 APPROVED: HOWARD COUNTY OFFICE OF PLANNING & ZONING
 Chief, Division of Land Development & Zoning Administration
 12-11-85
CLARK · FINEFROCK & SACKETT
 ENGINEERS · PLANNERS · SURVEYORS
 11315 LOCKWOOD DRIVE · SILVER SPRING MARYLAND 20904 · (301) 593-3400

DESIGNED GLB	ROAD CONSTRUCTION PLANS WIDENING ALONG HOMEWOOD ROAD POINT OF HOMWOOD 3RD ELECTION DISTRICT HOWARD COUNTY, MARYLAND FOR: R.C. GOODIER BUILDERS, INC. (OWNER) 233 Deep Dale Drive Timonium, Md. 21093	SCALE As Shown DRAWING 2 OF 5 JOB NO. 85-027 FILE NO. 85-027-D
DRAWN KIW		
CHECKED GLB		
DATE 9-25-85		

N.O.	REVISION	DATE
3	Revised ex swale at Sta. 6+80± to meet Prop. ditch.	4-13-87
2	Revised edge of paving profile for McGee Way.	3-11-86
1	Added note regarding Homewood Rd. revised title box.	2-4-86



#1163

PERMANENT SEEDING NOTES

Apply to graded or cleared areas not subject to immediate further disturbance where a permanent long-lived vegetative cover is needed.

Seedbed Preparation: Loosen upper three inches of soil by raking, discing or other acceptable means before seeding.

Soil Amendments: In lieu of soil test recommendations, use one of the following schedules

- 1) Preferred - Apply 2 tons per acre dolomitic limestone (92 lbs/1000 sq ft) and 600 lbs per acre 10-10-10 fertilizer (14 lbs/1000 sq ft) before seeding. Harrow or disc into upper three inches of soil. At time of seeding, apply 400 lbs per acre 30-0-0 ureaform fertilizer (9 lbs/1000 sq ft).
- 2) Acceptable - Apply 2 tons per acre dolomitic limestone (92 lbs/1000 sq ft) and 1000 lbs per acre 10-10-10 fertilizer (23 lbs/1000 sq ft) before seeding. Harrow or disc into upper three inches of soil.

Seeding - For the periods March 1 thru April 30, and August 1 thru October 15, seed with 60 lbs per acre (1.4 lbs/1000 sq ft) of Kentucky 31 Tall Fescue. For the period May 1 thru July 31, seed with 60 lbs Kentucky 31 Tall Fescue per acre and 2 lbs per acre (.05 lbs/1000 sq ft) of weeping lovegrass. During the period of October 16 thru February 28, protect site by: Option (1) 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring. Option (2) Use sod. Option (3) Seed with 60 lbs/acre Kentucky 31 Tall Fescue and mulch with 2 tons/acre well anchored straw.

Mulching - Apply 1 1/2 to 2 tons per acre (70 to 90 lbs/1000 sq ft) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gallons per acre (5 gal/1000 sq ft) of emulsified asphalt on flat areas. On slopes 8 feet or higher, use 348 gallons per acre (8 gal/1000 sq ft) for anchoring.

Maintenance - Inspect all seeded areas and make needed repairs, replacements and reseeding.

TEMPORARY SEEDING NOTES

Apply to graded or cleared areas likely to be redisturbed where a short-term vegetative cover is needed.

Seedbed Preparation: Loosen upper three inches of soil by raking, discing or other acceptable means before seeding.

Soil Amendments: Apply 600 lbs per acre 10-10-10 fertilizer (14 lbs/1000 sq ft)

Seeding - For periods March 1 thru April 30 and August 15 thru November 15, seed with 2 1/2 bushel per acre of annual rye (3.2 lbs/1000 sq ft). For the period May 1 thru August 14, seed with 3 lbs per acre of weeping lovegrass (.07 lbs/1000 sq ft). For the period November 16 thru February 28, protect site by applying 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring, or use sod.


Mulching: Apply 1 1/2 to 2 tons per acre (70 to 90 lbs/1000 sq ft) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gal per acre (5 gal/1000 sq ft) of emulsified asphalt on flat areas. On slopes, 8 ft or higher, use 348 gal per acre (8 gal/1000 sq ft) for anchoring.

Refer to the 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for rate and methods not covered.

SEDIMENT CONTROL NOTES

- 1) A minimum of 24 hours notice must be given to the Howard County Office of Inspection and Permits prior to the start of any construction. (992-2437)
- 2) All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL.
- 3) Following initial soil disturbance or redisturbance, permanent or temporary stabilization shall be completed within: a) 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all slopes greater than 3:1, b) 14 days as to all other disturbed or graded areas on the project site.
- 4) All sediment traps/basins shown must be fenced and warning signs posted around their perimeter in accordance with Vol. 1, Chapter 12, of the HOWARD COUNTY DESIGN MANUAL, Storm Drainage.
- 5) All disturbed areas must be stabilized within the time period specified above in accordance with the 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for permanent seedings (Sec. 51) and (Sec. 52). Temporary stabilization with mulch alone can only be done when recommended seeding dates do not allow for proper germination and establishment of grasses.
- 6) All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.
- 7) Site Analysis:

Total Area of Site	33.140 Acres
Area Disturbed	2.105 Acres
Area to be roofed or paved	0.912 Acres
Area to be vegetatively stabilized	0.684 Acres
Total Cut	7970 Cu. yds
Total Fill	7495 Cu. yds
Offsite waste/borrow area location	N/A
- 8) Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
- 9) Additional sediment control must be provided, if deemed necessary by the Howard County DFW sediment control inspector.
- 10) On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the inspection agency is made.
- 11) If houses are to be constructed on an "As-Sold" basis, at random, Single Lot Sediment Control as shown below shall be implemented. N/A
- 12) All pipes to be blocked at the end of each day (see detail below). N/A
- 13) The total amount of straw bale dikes/silt fence equals 205 L.F.




- CONSTRUCTION SPECIFICATIONS:**
1. All dikes shall be constructed by earth-moving equipment.
 2. All dikes shall have positive drainage to an outlet.
 3. Top width may be wider and side slopes may be flatter if desired, to facilitate crossing by construction traffic.
 4. Field location should be adjusted as needed to utilize a stabilized safe outlet.
 5. Earth dikes shall have an outlet that functions with a minimum of erosion. Runoff shall be conveyed to a sediment trapping device such as a sediment trap or erosion basin where either the dike channel or the drainage area above the dike are not adequately stabilized.
 6. Stabilization shall be: (A) In accordance with standard specifications for seed and straw mulch or straw mulch if not in seeding season, (B) flow channel as per chart below.

TYPE OF TREATMENT	CHANNEL GRADE	DIKE A	DIKE B
1	0.5 - 3.0%	Seed or Straw Mulch	Seed or Straw Mulch
2	3.1 - 5.0%	Seed or Straw Mulch	Seed or Straw Mulch
3	5.1 - 8.0%	Seed or Straw Mulch	Seed or Straw Mulch
4	8.1 - 20.0%	Lined Rip Rap 4"-8" Stone Engineering Design	Lined Rip Rap 4"-8" Stone Engineering Design


A. Stone to be 2" Stone, or recycled concrete equivalent, in a layer at least 3" thick and be pressed into soil with construction equipment.
 B. Rip Rap to be 4"-8" in a layer at least 8" thick, pressed into soil.
 C. Approved equivalents can be substituted for any of the above materials.

EARTH DIKE DETAIL (E.D.)
NO SCALE




- CONSTRUCTION SPECIFICATIONS:**
1. Area under embankment shall be cleared, grubbed and stripped of any vegetation and root mat. The soil shall be 6" compacted.
 2. The fill material for the embankment shall be free of roots and other objectionable material. The embankment shall be compacted by traversing with equipment while it is being constructed.
 3. All cut and fill slopes shall be 2:1 or flatter.
 4. The stone used in the outlet shall be small rip rap 4"-8" with 1" thickness of 2" aggregate placed on the up-grade side on the small rip rap or embedded filter cloth in the rip rap.
 5. Sediment shall be removed and trap restored to its original dimensions when the sediment has accumulated to 1/2 the design depth of the trap.
 6. The structure shall be inspected after each rain and repairs made as needed.
 7. Construction operations shall be carried out in such a manner that erosion and water pollution is minimized.
 8. The structure shall be removed and the area stabilized when the drainage area has been properly stabilized.

STONE OUTLET SEDIMENT TRAP (S.O.S.T.) ST.V.
NO SCALE




- CONSTRUCTION SPECIFICATIONS:**
1. Woven wire fence to be fastened securely to fence posts with wire ties or staples.
 2. Filter cloth to be fastened securely to woven wire fence with ties spaced every 24" at top and mid section.
 3. When 2 sections of filter cloth adjoin each other they shall be overlapped by 6" and fastened.
 4. Maintenance shall be performed as needed and material removed when "bulges" develop in silt fence.
- POSTS:** Steel, either T or U Type or 2" Min. dia. wood.
FENCE: Woven Wire, 1/4" Gauge, 6" Max. Mesh Opening.
FILTER CLOTH: Filter Cloth, Min. 100% Stabilized, 1/4" or approx. equal.
PREFABRICATED UNIT: Geotext, Envirofence, or approx. equal.

SILT FENCE DETAIL (S)
NO SCALE




- CONSTRUCTION SPECIFICATIONS:**
1. Bales shall be placed at the top of a slope or on the contour and in a row with ends tightly abutting the adjacent bales.
 2. Each bale shall be embedded in the soil a min. of 4" and placed so the bindings are horizontal.
 3. Bales shall be securely anchored in place by either 2 stakes or re bars driven thru the bale. The 1st stake in each bale shall be driven through the previously laid bale at an angle to force the bales together. Stakes shall be driven flush with the bale.
 4. Inspection shall be frequent and repair/replacement shall be made promptly as needed.
 5. Bales shall be removed when they have served their usefulness so as not to block or impede storm flow or drainage.

STRAW BALE DIKE DETAIL (SBD)
NO SCALE



- CONSTRUCTION SPECIFICATION FOR ST-IV**
1. The swale sediment trap shall be constructed in accordance with the dimensions provided on the design drawings or sized to provide the minimum storage necessary 1800 cubic feet of storage for each acre of drainage area.
 2. Sediment shall be removed and trap restored to its original dimensions when the sediment has accumulated to 1/2 the design depth of the trap. Removed sediment shall be deposited in a suitable area and in such a manner that it will not erode.
 3. The structure shall be inspected after each rain and repairs made as needed.
 4. Construction operations shall be carried out in such a manner that erosion and water pollution shall be minimized.
 5. The sediment trap shall be removed and area stabilized when the contributory drainage area has been properly stabilized.
 6. The swale sediment trap will be properly backfilled and the swale or ditch reconstructed.

SWALE SEDIMENT TRAP (ST-IV)
NO SCALE



- CONSTRUCTION SPECIFICATION FOR ST-IV**
1. The swale sediment trap shall be constructed in accordance with the dimensions provided on the design drawings or sized to provide the minimum storage necessary 1800 cubic feet of storage for each acre of drainage area.
 2. Sediment shall be removed and trap restored to its original dimensions when the sediment has accumulated to 1/2 the design depth of the trap. Removed sediment shall be deposited in a suitable area and in such a manner that it will not erode.
 3. The structure shall be inspected after each rain and repairs made as needed.
 4. Construction operations shall be carried out in such a manner that erosion and water pollution shall be minimized.
 5. The sediment trap shall be removed and area stabilized when the contributory drainage area has been properly stabilized.
 6. The swale sediment trap will be properly backfilled and the swale or ditch reconstructed.

SWALE SEDIMENT TRAP (ST-IV)
NO SCALE

- CONSTRUCTION SPECIFICATION FOR ST-IV**
1. The swale sediment trap shall be constructed in accordance with the dimensions provided on the design drawings or sized to provide the minimum storage necessary 1800 cubic feet of storage for each acre of drainage area.
 2. Sediment shall be removed and trap restored to its original dimensions when the sediment has accumulated to 1/2 the design depth of the trap. Removed sediment shall be deposited in a suitable area and in such a manner that it will not erode.
 3. The structure shall be inspected after each rain and repairs made as needed.
 4. Construction operations shall be carried out in such a manner that erosion and water pollution shall be minimized.
 5. The sediment trap shall be removed and area stabilized when the contributory drainage area has been properly stabilized.
 6. The swale sediment trap will be properly backfilled and the swale or ditch reconstructed.

SWALE SEDIMENT TRAP (ST-IV)
NO SCALE

ENGINEER'S CERTIFICATE

I hereby certify that this plan for Erosion and Sediment Control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District.

John W. Murchison
12-11-85
Date

Reviewed for Howard S.C.D. Name and meets Technical Requirements
Robert Ziehm
Signature Date
 U.S. Soil Conservation Service


THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

Robert Ziehm
Approved 12/10/85
Date

DEVELOPER'S/BUILDER'S CERTIFICATE

"I/we certify that all development and construction will be done according to this plan of development and plan for erosion and sediment control and that all responsible personnel involved in the construction project will have a Certificate of Attendance at a Dept. of Natural Resources Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District or their authorized agents, as are deemed necessary."

Robert Ziehm
Signature of Developer/Builder 9-25-85
Date



- CONSTRUCTION SPECIFICATIONS:**
1. Stone size - Use 2" stone, or reclaimed or recycled concrete equivalent.
 2. Length - As required, but not less than 50 feet (except on a single residence lot where a 30 foot minimum length would apply).
 3. Thickness - Not less than six (6) inches.
 4. Width - Ten (10) feet minimum, but not less than the full width at points where ingress or egress occurs.
 5. Filter Cloth - Will be placed over the entire area prior to placing of stone. Filter will not be required on a single family residence lot.
 6. Surface Water - All surface water flowing or diverted toward construction entrances shall be piped across the entrance. If piping is impractical, a mountable berm with 5:1 slopes will be permitted.
 7. Maintenance - The entrance shall be maintained in a condition which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair and/or cleanup of any measures used to trap sediment. All sediment spilled, dropped, washed or tracked onto public rights-of-way must be removed immediately.
 8. Washing - Wheels shall be cleaned to remove sediment prior to entrance onto public rights-of-way. When washing is required, it shall be done on an area stabilized with stone and which drains into an approved sediment trapping device.
 9. Periodic inspection and needed maintenance shall be provided after each rain.

STABILIZED CONSTRUCTION ENTRANCE (SCE)
NO SCALE

Temporary Access Culvert Notes:

1. Provide 15" dia. CMP. Invert elevation of culvert shall be installed on natural stream bed grade.
2. Length of culvert adjustable, but in no case shall exceed 40'.
3. Filter cloth shall be placed on stream bed & stream banks prior to placement of culvert and aggregate.
4. Temporary access culvert shall conform to the 1983 Maryland Standards & Specifications for Soil Erosion and Sediment Control, Section 19.

TEMPORARY ACCESS CULVERT DETAIL
NO SCALE

1	Revised title box	2-4-86
NB	REVISION	DATE
APPROVED: DEPARTMENT OF PUBLIC WORKS		
<i>John W. Murchison</i> 12-16-85 Chief, Bureau of Engineering		
APPROVED: HOWARD COUNTY OFFICE OF PLANNING & ZONING		
<i>John W. Murchison</i> 12-11-85 Chief, Division of Land Development & Zoning Administration		

CLARK · FINEFROCK & SACKETT
ENGINEERS · PLANNERS · SURVEYORS
1315 LOCKWOOD DRIVE SILVER SPRING MARYLAND 20904 (301) 593-3400

DESIGNED	GLB	SCALE	AS SHOWN
DRAWN	KIW	DRAWING	5-055
CHECKED	GLB	JOB NO.	85-027
DATE	9-25-85	FILE NO.	85-027 D

ROAD CONSTRUCTION PLANS
 SEDIMENT & EROSION CONTROL
 DETAILS
 POINT OF
 HOMEWOOD
 3RD ELECTION DISTRICT
 HOWARD COUNTY, MARYLAND
 FOR: RC GORRIEK BUILDERS, INC. (OWNER)
 233 Deep Dale Drive
 Timonium, Md. 21093