


STRUCTURE SCHEDULE				
No.	TYPE	TOP ELEVATION UPPER OPENING	INV. ELEVATION IN	REMARKS
S1	STD END SECTION		691.90	SD 3.51
MH2	STD. MANHOLE	699.90	691.9	G 3.03 or G 12
I21	TYPE "D" INLET	718.78	714.28	SD 4.11
I22	TYPE "D" INLET	724.78	722.28	SD 4.11
S21	STD END SECTION		694.28	SD 3.51

STRUCTURE SCHEDULE (CONT.)					
No.	TYPE	TOP ELEVATION UPPER OPENING	INV. ELEVATION IN	OUT	REMARKS
I3	STD "D" INLET	697.6	692.42	692.32	SD 4.11
I4	STD "D" INLET	696.8	696.1	693.0	SD 4.11

PIPE SCHEDULE		
TYPE	SIZE	LENGTH
PCU 1/2"	24"	123'
ALUMINUM	18"	90'
ALUMINUM	18"	120'




Following initial soil disturbance or redistribution, permanent or temporary stabilization shall be completed within 11 seven (7) calendar days for all perimeter sediment control structures, ditches, swales, ditches, perimeter slopes and all slopes greater than 1:1 fourteen (14) days for all other disturbed or graded areas on project site.

NOTE: The contractor or developer shall contact the construction inspection (survey division) 24 hours in advance of commencement of work at 792-7272.

DEVELOPER'S CERTIFICATION:  
I/We certify that all development and construction will be done according to this plan, and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspections by the Howard County Conservation District.


*Neil Schwartz* 11/14/95  
Date



**CURVE DATA**  
 E-1000.00  
 TO 5+10.70  
 R=450.00  
 A=108.80'  
 T=95.80'  
 Δ=24°02'18"  
 CHORD BEARING=85°53'00" S 28° E  
 CHORD=187.42'

**CURVE DATA**  
 E-1100.00  
 TO 13+11.61  
 R=1000.00  
 A=150°10'  
 T=68.30'  
 Δ=101°00'00"  
 CHORD BEARING=85°04'00" S 64° E  
 CHORD=152.26'

**CURVE DATA**  
 E-1200.00  
 TO 17+12.84  
 R=230.00  
 A=188.90'  
 T=82.58'  
 Δ=97°20'00"  
 CHORD BEARING=84°51'00" S 61° E  
 CHORD=199.44'



ENGINEER'S CERTIFICATION:  
 I certify that this plan for erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard County Conservation District.


*Neil Schwartz* 11/14/95  
Date

Approved: Howard County Department of Public Works  
*John D. Jones* 7/2/90  
 Chief, Land Development Division  
 Date

*Priscilla W. Weiland* 7/24/90  
 Chief, Bureau of Highway  
 Date

*John A. ...* 11-2-90  
 Chief, Bureau of Engineering  
 Date

Approved: Howard County Department of Planning and Zoning  
*David J. ...* 11/14/95  
 Chief, Division of Community  
 Planning and Land Development  
 Date



Owner/Developer:  
 PLEASANT HILLS LTD PARTNERSHIP  
 10324 B BALTIMORE NAT'L PKWY  
 CENTENNIAL SQUARE  
 ELLICOTT CITY MD 21043  
 (301)461-6777

NO.	REVISIONS	DATE

**DEVELOPMENT CONSULTANTS GROUP, INC.**  
 17904 GEORGIA AVENUE # 102  
 OLNEY, MARYLAND 20832  
 301-924-4570


STREET GRADE, STORM DRAIN, AND FINISH PLAN  
**PLEASANT HILLS**  
 4<sup>th</sup> ELECTION DISTRICT  
 HOWARD COUNTY, MARYLAND  
 TAX MAP 642C PARCEL 5

DATE: JUN 19 00  
 DRAWN: PCH  
 CHECKED: NS  
 SCALE: AS SHOWN

Sheet 1 of 9  
 PROJECT NO. 154-05

16091

F-90-65



**ZONING DISTRICTS**


ZONING DISTRICTS	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z
RESIDENTIAL SINGLE-FAMILY AREA																										

**OPEN SECTION (RURAL) ("A" ZONING DISTRICT)**

**ROADWAY CROSS SECTION**

**RESIDENTIAL ZONES**

SECTION NUMBER	ROAD AND STREET CLASSIFICATION	PAVING SECTIONS
P-2	LOCAL, CUL-DE-SAC, SIDE ALLEYS AND PRIVATE ROADS SERVING RESIDENTIAL TRAVELERS, APARTMENTS AND COMMERCIAL-INDUSTRIAL ZONES WITH NO MORE THAN 10 HEAVY TRUCKS PER DAY	F-2




**STRUCTURE SCHEDULE**

NO	TYPE	TOP ELEVATION	INVERT ELEVATION	REMARKS
1	12" ACMP WHP SECTION	101.12	101.12	87 5.11
2	12" ACMP	101.12	101.12	88 SHEET 5 OF 9-CUSTOM
3	12" TYPE 'P' INLET GRATE	102.95	102.95	87 4.11
4	12" ACMP	102.95	102.95	87 5.11
5	12" ACMP	102.95	102.95	87 5.12
6	12" TYPE 'P' INLET GRATE	104.00	104.00	87 5.12
7	12" ACMP	104.00	104.00	87 4.12
8	12" TYPE 'P' INLET GRATE	104.75	104.75	87 4.11
9	12" TYPE 'P' INLET GRATE	104.75	104.75	87 4.11

**PIPE SCHEDULE**

TYPE	SIZE	LENGTH
ACMP III	18"	72'
CMF	18"	32'
ACMP III	18"	100'
ACMP IV	18"	74'
ACMP	15"	15'
ACMP	18"	550'
ACMP	24"	25.75'
ACMP	24"	4.5'



Following initial soil disturbance or redistribution, permanent or temporary stabilization shall be completed within: 1) seven (7) calendar days for all perimeter sediment control structures, ditches, swales, ditches, perimeter slopes and all slopes greater than 3:1 2) fourteen (14) days for all other disturbed or graded areas on project site.

**DEVELOPER'S CERTIFICATE:**  
 I certify that all development and construction will be done according to this plan, and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspections by the Howard Soil Conservation District.

**ENGINEER'S CERTIFICATE:**  
 I certify that this plan for erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District.

**APPROVED:**  
 Chief, Land Development Division  
 Chief, Bureau of Highway  
 Chief, Bureau of Engineering  
 Chief, Division of Community Planning and Land Development

**Owner/Developer:**  
 PLEASANT HILLS LTD PARTNERSHIP  
 10224 B BALTIMORE NATL FIRE  
 CENTENNIAL SQUARE  
 ELLIOTT CITY MD 21043  
 (301) 461-6777

**NO.**

**REVISIONS**

**DATE**

**DEVELOPMENT CONSULTANTS GROUP, INC.**  
 17904 GEORGIA AVENUE # 102  
 OLNEY, MARYLAND 20832  
 301-924-4570

**STREET GRADE, STORM DRAIN, AND PAVING PLAN**  
**PLEASANT HILLS**  
 4th ELECTION DISTRICT  
 HOWARD COUNTY, MARYLAND  
 TAX MAP 6412 PARCEL 5

**DATE:** 11/27/90  
**DRAWN:** JCH  
**CHECKED:** NS  
**SCALE:** AS SHOWN

**Sheet 2 of 9**  
**PROJECT NO. 154-05**

16091

F-90-65

SECTION NUMBER	ROAD AND STREET CLASSIFICATION	PAVEMENT MATERIALS	
		FULL DEPTH BIT. CONC. ALTERNATE	GRANULAR BASE ALTERNATES
P-3	RESIDENTIAL ZONES MEDICAL AND MAJOR COLLECTORS COMMERCIAL INDUSTRIAL ZONES LOCAL AND COLLECTOR STREETS TRAVELWAYS INDUSTRIAL ZONES WITH LOW DAILY TRAFFIC VOLUME	1 1/2" BIT. CONC. SURFACE 4 1/2" BIT. CONC. BASE 4" BIT. CONC. BASE	1 1/2" P.S. CONC. SURFACE 4 1/2" BIT. CONC. BASE 4" BIT. CONC. BASE
P-7	STABILIZED SHOULDER FOR ALL ZONES AND ROAD CLASSIFICATIONS	2" CRUSHED STONE SURFACE TREATMENT OF GRAVEL OR SAND COURSE OR 4 1/2" BIT. GRADED STABILIZED GRANULAR BASE COURSE	2" CRUSHED STONE SURFACE TREATMENT OF GRAVEL OR SAND COURSE OR 4 1/2" BIT. GRADED STABILIZED GRANULAR BASE COURSE

TRAVELWAYS ARE DEFINED AS THOSE WITH A WHEEL OR MORE INCLUDING GARBAGE TRUCKS

HOWARD COUNTY, MARYLAND  
DEPARTMENT OF PUBLIC WORKS  
APPROVED: [Signature] DATE: [Date]

PAVING SECTIONS  
LONG CORNER  
ROAD


F.4  
PROFFITT  
L.1087 F.247  
(DOWNS TO E  
LONG CORNER  
ROAD)

NOTE: THESE FINAL SPACES  
IN TRAP AREA  
TO BE ESTABLISHED AFTER  
REMOVAL OF  
SEDIMENT TRAP AS  
SHOWN ON SHEET  
4 OF 9. X

TEMPORARY  
GRADING &  
SLOPE EGMT.  
\* MAINTAIN POSITIVE DRAINAGE  
TO I-3 & I-4

SEE SHEET 1 OF 9 FOR  
TYPICAL SECTION ON  
WATKINS WAY &  
STATION 0+00 TO  
7+64.25

NOTE: ALL UPLAND AREAS ARE TO BE  
PERMANENTLY STABILIZED  
BEFORE CONSTRUCTION OF  
INFILTRATION TRENCHES  
IS TO OCCUR.




PLAN SCALE 1"=50'

NOTE: NO DISTURBANCE OVER 50,000 \$  
ON ANY ADJACENT LOTS IS TO OCCUR  
WITHOUT AN APPROVED CUSTOMER  
EROSION CONTROL PLAN AND A  
COPY OF THE LAND ANALYSIS AT THE  
TIME THE PLAN IS SUBMITTED.

NOTE: ALL DRIVEWAYS ON LONG CORNER  
ROAD AND WATKINS WAY TO BE  
BUILT AS PER H.C. S.P. 50.00 WITH  
CULVERT. LOT 4 DOES NOT REQUIRE  
CULVERT AT POINT OF VERTICAL CURVE  
ALL CULVERTS TO BE 18" X 12" EXCEPT LOT  
4 TO BE 24" X 18". DRIVEWAY CULVERTS TO BE  
PER FORMS QUALITY OF PROPERTY  
OWNERS.

NOTE: S.C.E. TO BE USED  
FOR CONTRACT TO PROPERTY  
RUPING CONSTRUCTION.  
CONNECT S.C.E. TO EX  
ENTERANCE ROAD



Owner/Developer:  
PLEASANT HILLS LTD. PARTNERSHIP  
1032A B BALTIMORE NAT'L PIKE  
CENTENNIAL SQUARE  
ELLCOTT CITY MD 21043  
(301)444-6777

NO.	REVISIONS	DATE

**DEVELOPMENT CONSULTANTS GROUP, INC.**


17904 GEORGIA AVENUE # 102  
OLNEY, MARYLAND 20832  
301-924-4570

PLANNING AND SEWERAGE CONTROL PLAN

PLEASANT HILLS  
4th ELECTION DISTRICT  
HOWARD COUNTY MARYLAND  
TAX MAP 6412 PARCEL 3

DATE: JUN 00  
DRAWN: PCH  
CHECKED: [Signature]  
SCALE: AS SHOWN

Sheet 3 of 9  
PROJECT NO. 154-03



HOWARD COUNTY, MARYLAND  
DEPARTMENT OF PUBLIC WORKS  
APPROVED: [Signature] DATE: [Date]

Following initial soil disturbance or redistribution, permanent temporary stabilization shall be completed within: 1) seven (7) calendar days for all perimeter sediment control structures, ditches, swales, ditches, perimeter slopes and all slopes greater than 3:1 2) fourteen (14) days for all other disturbed or graded areas on project site. NOTE: The contractor or developer shall contact the construction inspection (survey division) 24 hours in advance of commencement of work at 792-7272.

**DEVELOPER'S CERTIFICATE:**  
I/We certify that all development and construction will be done according to this plan, and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspections by the Howard Soil Conservation District.

[Signature] Date: 06/21/90

**ENGINEER'S CERTIFICATE:**  
I certify that this plan for erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District.

[Signature] Date: 06/21/90

Reviewed for HOWARD S.C.D. and meets technical requirements.

[Signature] Date: 07/20

This development plan is approved for SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

[Signature] Date: 07/20




Approved: Howard County Department of Public Works  
[Signature] Date: 7/24/90  
Chief, Bureau of Highway

[Signature] Date: 7/24/90  
Chief, Bureau of Engineering

Approved: Howard County Department of Planning and Zoning  
[Signature] Date: 7/24/90  
Chief, Division of Community Planning and Land Development

160M

F-90-65



Following initial soil disturbance or redistribution, permanent or temporary stabilization shall be completed within: 1) seven (7) calendar days for all perimeter sediment control structures, dikes, swales, ditches, perimeter slopes and all slopes greater than 3:1; 2) fourteen (14) days for all other disturbed or graded areas on project site.

**NOTE:** The contractor or developer shall contact the construction inspection (survey division) 24 hours in advance of commencement of work at 792-7272.

**DEVELOPER'S CERTIFICATE:**  
 "I/We certify that all development and construction will be done according to this plan, and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspections by the Howard Soil Conservation District."  
 Paul R. Harrop 7/1/90  
 Date

**ENGINEER'S CERTIFICATE:**  
 "I certify that this plan for erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District."  
 Neil Schwartz 8/18/90  
 Date  
 Neil Schwartz #1149  
 Reviewed for HOWARD S.C.D. and meets technical requirements.  
 James M. Zelnick 7/5/90  
 Soil Conservation Services, GS, Date  
 THIS DEVELOPMENT PLAN IS APPROVED FOR SITE POSITION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.  
 Jeff Zelnick 7/5/90  
 Date  
 Approved: Howard County Department of Public Works  
 Chief, Land Development Division Date  
 [Signature] 7/5/90  
 Chief, Bureau of Highway Date  
 [Signature] 11-2-90  
 Chief, Bureau of Engineering Date  
 Approved: Howard County Department of Planning and Zoning  
 [Signature] 7/14/90  
 Chief, Division of Community Planning and Land Development Date

NO.	REVISIONS	DATE



**DEVELOPMENT CONSULTANTS GROUP, INC.**  
 17904 GEORGIA AVENUE # 102  
 OLNEY, MARYLAND 20832  
 301-924-4570

DATE	BY	CHECKED	SCALE	PROJECT NO.
JUL 1, 1990	WJH	BCH	1"=30'	15A-05
FEB 1, 1990	WJH	BCH	1"=30'	15A-05
FEB 1, 1990	WJH	BCH	1"=30'	15A-05

Owner/Developer:  
 PLEASANT HILLS LTD PARTNERSHIP  
 10324 BALTIMORE NATIONAL PIKE  
 CENTENNIAL SQUARE  
 ELLICOTT CITY MD 21043  
 (301) 461-6777






Owner/Developer:  
 PLEASANT HILLS LTD PARTNERSHIP  
 10324 BALTIMORE NATIONAL PIKE  
 CENTENNIAL SQUARE  
 ELLICOTT CITY MD 21043  
 (301) 461-6777

**STREET GRADERS AND SEDIMENT CONTROL PLAN**  
**PLEASANT HILLS**  
 44 ELECTION DISTRICT  
 HOWARD COUNTY, MARYLAND  
 TAX MAP 612 PARCELS

Sheet 4 of 7  
 PROJECT NO. 15A-05  
 DATE 7/1/90

1609

F-90-05



Following initial soil disturbance or redistribution, permanent or temporary stabilization shall be completed within: 1) seven (7) calendar days for all perimeter sediment control structures, dikes, swales, ditches, perimeter slopes and all slopes greater than 3:1; 2) fourteen (14) days for all other disturbed or graded areas on project site.

**DEVELOPER'S CERTIFICATE:**  
 I certify that all development and construction will be done according to this plan and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspections by the Howard Soil Conservation District.

**ENGINEER'S CERTIFICATE:**  
 I certify that this plan for erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District.

Approved: Howard County Department of Public Works  
 Chief, Land Development Division  
 Approved: Howard County Department of Planning and Zoning  
 Division of County Planning and Land Development

**\* INFILTRATION TRENCH:**  
 3.3.6.1. Construction Specifications

**3.3.6.2. Trench Preparation**  
 An infiltration trench shall not be constructed or placed in service until all of the contributing drainage area has been stabilized and approved by the responsible inspector.

**3.3.6.3. Fabric Layout**  
 The filter fabric roll must be cut to the proper width prior to installation. The cut width must include sufficient material to conform to trench perimeter and to allow for 6-inch minimum top overlap. Place the fabric roll over the trench and unroll a sufficient length to allow placement of the fabric down into the trench. Stones or other anchoring objects should be placed on the fabric at the edge of the trench to keep the lined trench open during windy periods. When overlaps are required between rolls, the upstream roll shall lap a minimum of 2 feet over the downstream roll in order to provide a shingled effect. The overlap ensures fabric continuity or to ensure that the fabric conforms to the excavation surface during aggregate placement and compaction.

**3.3.6.4. Stone Aggregate Placement and Compaction**  
 The stone aggregate should be placed in lifts and compacted using plate compactors. As a rule of thumb, a maximum loose lift thickness of 12 inches is recommended. The compaction process ensures fabric conformity to the excavation sides, thereby reducing the potential for soil piping, fabric clogging, and settlement problems.

**3.3.6.5. Overlapping and Covering**  
 Following the stone aggregate placement, the filter fabric shall be folded over the stone aggregate to form a 6" minimum longitudinal lap. The desired fill soil or stone aggregate shall be placed over the lap at sufficient intervals to maintain the lap during subsequent backfilling.

**3.3.6.6. Contamination**  
 Care shall be exercised to prevent natural or fill soils from intermixing with the stone aggregate. All contaminated stone aggregate shall be removed and replaced with uncontaminated stone aggregate.

**3.3.6.7. Voids Behind Fabric**  
 Voids can be created between the fabric and excavation sides and shall be avoided. Removing boulders or other obstacles from the trench walls is one source of such voids. Natural soils should be placed in these voids at the most convenient time during construction to ensure fabric conformity to the excavation sides. Soil piping, fabric clogging, and possible surface subsidence will be avoided by this remedial process.

**3.3.6.8. Unstable Excavation Sides**  
 Vertically excavated walls may be difficult to maintain in areas where the soil moisture is high or where soft cohesive or cohesionless soils predominate. These conditions may require laying back of the side slopes to maintain stability; trapezoidal rather than rectangular cross sections may result.

**3.3.6.9. Vegetative Buffer**  
 A vegetative buffer of at least 20 feet (wider, if possible) shall be used to intercept surface runoff from all impervious areas.

**3.3.6.10. Traffic Control**  
 Heavy equipment and traffic shall be restricted from travelling over the infiltration area to minimize compaction of the soil.

**3.3.6.11. Observation Well**  
 An observation well, as described in subsection 3.3.4.8 and Figure 3-5 shall be provided. The depth of the well at the time of installation will be clearly marked on the well cap.




**3.3.7. Maintenance**  
 Infiltration trenches shall be designed to minimize maintenance. However, it is recognized that all infiltration facilities are subject to clogging by sediment, oil, grease, grit and other debris. In addition, the performance and longevity of these structures is not well documented. Consequently, a monitoring observation well is required for all infiltration structures.

The observation well shall be monitored periodically. For the first year after completion of construction, the well should be monitored on a quarterly basis and after every large storm. It is recommended that a log book be maintained indicating the rate at which the facility dewater after large storms and the depth of the well for each observation. Once the performance characteristics of the structure have been verified, the monitoring schedule can be reduced to an annual basis, unless the performance data indicate that a more frequent schedule is required.

Sediment build-up in the top foot of stone aggregates or the surface inlet should be monitored on the same schedule as the observation well. A monitoring well in the top foot of stone aggregate will be required when the trench has a stone surface. Sediment deposited shall not be allowed to build up to the point where it will reduce the rate of infiltration into the trench.

**SEDIMENT CONTROL NOTES**


- A minimum of 24 hours notice must be given to the Howard County Office of Inspection and Permits prior to the start of any construction. (892-2437)
- All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL.
- Following initial soil disturbance or redistribution, permanent or temporary stabilization shall be completed within: a) 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all slopes greater than 3:1; b) 14 days as to all other disturbed or graded areas on the project site.
- All sediment trapping basins shown must be fenced and warning signs posted around their perimeter in accordance with VOL. 1, CHAPTER 12, OF THE HOWARD COUNTY DESIGN MANUAL, STORM DRAINAGE.
- All disturbed areas must be stabilized within the time period specified above in accordance with the 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for permanent seedings (Sec. 51) and temporary seedings (Sec. 50) and mulching (Sec. 52). Temporary stabilization with mulch alone can only be done when recommended seeding dates do not allow for proper germination and establishment of grasses.
- All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.
- Site Analysis: Total Area of Site 52.6403 Acres  
 Area Disturbed 9.100 Acres  
 Area to be paved 1.20 Acres  
 Area to be vegetatively stabilized 6.40 Acres  
 Total Cut 108,190 Cu. Yds.  
 Total Fill 6,190 Cu. Yds.  
 Offsite water/obscure area location 100,000 Cu. Yds.
- Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
- Additional sediment controls must be provided, if deemed necessary by the Howard County Sediment Control Inspector.
- On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the inspection agency is received.




**GENERAL NOTES**

- Total area: 52.6403 acres
- Property zoned: Rural
- Private water supply and sewage disposal systems.
- Area of dedication: 2.8367
- MS-96 granted for the purpose of extending maximum cul de sac length to 2000 ft.
- Soils maps #15 and #11.
- Deed references: Liber 586, Folio 424
- Number of lots: 13 residential.
- Area of lots: 49.8038 acres.
- Average lot size: 3.8311 acres.
- Setbacks: Front 75 feet  
 Side 60 feet street  
 30 feet lot
- Bear 60 feet
- All utility areas are to remain.
- Boundary survey and topography by: Development Consultants Group, Inc. 17904 Georgia Avenue, Suite 102 Olney, MD 20832 (301) 924-4579
- Flag or pipe stem lots shall not be further subdivided into lots accommodating additional residences unless a public road can be constructed according to County standards on a minimum 50 foot right of way to be deeded to the county.
- For flag or pipe stem lots, refuse collection, snow removal and road maintenance are provided to the junction of the flag or pipe stem and road right of way and not onto the flag or pipe stem.
- Driveways which serve two or more lots must meet the requirements of the Howard County Fire Department.
- Wetlands based on a study by: William Bridgeland Wildlife Biologist 437 Falling Spring Ct. Reisterstown, MD 21136 (301) 833-7794
- No clearing, grading or construction is permitted within wetland or stream buffers.
- Bench Mark #1: Geodetic control number 3626001, concrete monument set 0.3' below Macadam, elevation 778.02, state plane coordinates N540767.826, E775435.074 shown in plan view.
- Bench Mark #2: Geodetic control number 3426001, concrete monument set 6126.871 feet from #3626001.
- All upland areas are to be permanently stabilized before construction of infiltration trenches occur.
- No disturbance over 30,000 square feet on any adjacent lots is to occur without an approved custom erosion control plan and a copy of a wetland analysis at the time the plan is submitted.
- All driveways on Lons Corner Road and Watkins Way to be built as per Howard County Standard R6.06 with culvert. Lot 6 does not require culvert at crest of vertical curve. All culverts to be 18" x 11" except Lot 4 to be 25" x 16". Driveway culverts to be responsibility of property owners.
- See sheet 1 of 9 for typical section of Watkins Way centerline station 0+00 to 7+44.28.


NOTE: Developer will pay fee for open space lots per Bill #25.




PROFILE LONG CORNER - SIGHT DISTANCE  
SCALE: HORIZONTAL 1"=100'  
VERTICAL 1"=10'  
POSTED SPEED 30 MPH




OBSERVATION WELL DETAIL  
(NTS)



AREA "A" - RIGHT SIDE OF WATKINS WAY  
SCALE: HORIZONTAL 1"=50'  
VERTICAL 1"=5'



AREA "B" - LEFT SIDE OF WATKINS WAY  
SCALE: HORIZONTAL 1"=50'  
VERTICAL 1"=5'



TYPICAL INFILTRATION TRENCH SECTION  
SCALE 1"=5'

Following initial soil disturbance or redisturbance, permanent or temporary stabilization shall be completed within: 1) seven (7) calendar days for all perimeter sediment control structures, dikes, swales, ditches, perimeter slopes and all slopes greater than 3:1; 2) fourteen (14) days for all other disturbed or graded areas on project site.  
NOTE: The contractor or developer shall contact the construction inspection (survey division) 24 hours in advance of commencement of work at 792-7272.

DEVELOPER'S CERTIFICATE:  
"I certify that all development and construction will be done according to this plan, and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspections by the Howard Soil Conservation District."  
Date: 4/18/90


ENGINEER'S CERTIFICATE:  
"I certify that this plan for erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District."  
Date: 6/6/1990

Approved: Howard County Department of Public Works  
Chief, Land Development Division  
Date: 7/27/90  
Branville W. Williams  
Chief, Bureau of Highway  
Date: 7/27/90  
Approved: Howard County Department of Planning and Zoning  
Chief, Division of Community Planning and Land Development  
Date: 7/27/90



Owner/Developer:  
PLEASANT HILLS LIP PARTNERSHIP  
10324 B BALTIMORE NAT'L FIVE  
CENTENNIAL SQUARE  
ELLICOTT CITY MD 21043  
(301)461-6777

NO.	REVISIONS	DATE



**DEVELOPMENT CONSULTANTS GROUP, INC.**  
17904 GEORGIA AVENUE # 102  
OLNEY, MARYLAND 20832  
301-924-4570

PROFILES & SECTIONS W/DS 1-13  
PLEASANT HILLS  
4th ELECTION DISTRICT  
HOWARD COUNTY MARYLAND  
TAX MAP 12 PARCEL 5  
DATE: JUNE 90  
DRAWN: ACH  
CHECKED: N.S.  
SCALE: AS SHOWN  
PROJECT NO.: 154-05  
Sheet 6 of 7

F-90-65

Following initial soil disturbance or redistribution, permanent or temporary stabilization shall be completed within: 1) seven (7) calendar days for all perimeter sediment control structures, dikes, swales, ditches, perimeter slopes and all slopes greater than 3:1; 2) fourteen (14) days for all other disturbed or graded areas on project site.

NOTE: The contractor or developer shall contact the construction inspection (survey division) 24 hours in advance of commencement of work at 792-7272.

DEVELOPER'S CERTIFICATE:  
 I/We certify that all development and construction will be done according to this plan, and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspections by the Howard Soil Conservation District.

*Paul E. Koenig* 4/18/90  
 Date

ENGINEER'S CERTIFICATE:  
 I certify that this plan for erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District.










*Neil Schwertz* 4/16/90  
 Date

Approved: Howard County Department of Public Works  
*John M. ...* 7/23/90  
 Chief, Land Development Division Date

*Draville M. ...* 7/23/90  
 Chief, Bureau of Highway Date

*...* 11-2-90  
 Chief, Bureau of Engineering Date

Approved: Howard County Department of Planning and Zoning  
*...* 4/14/90  
 Chief, Division of County Planning and Land Development Date



DRAINAGE AREA MAP  
 SCALE 1"=200'

1607

Owner/Developer:  
 PLEASANT HILLS LTR PARTNERSHIP  
 10024 B BALTIMORE NAT'L PARK  
 CENTENNIAL SQUARE  
 FLYCOTT CITY MD 21043  
 (301)461-6777

NO.	REVISIONS	DATE



**DEVELOPMENT CONSULTANTS GROUP, INC.**


17904 GEORGIA AVENUE # 102  
 OLNEY, MARYLAND 20832  
 301-924-4570

LOTS 1-13  
 FLOOD PLAIN SECTIONS & FLOOD PLAIN STUDY  
**PLEASANT HILLS**  
 4<sup>th</sup> ELECTION DISTRICT  
 HOWARD COUNTY, MARYLAND  
 TAX MAP 12 PARCEL 5

DATE: 6-90-40  
 DRAWN: WF 89-016  
 CHECKED: F 89-023  
 SCALE: AS SHOWN

Sheet 7 of 7  
 PROJECT NO. 154-03

F-90-65



VICINITY MAP  
SCALE: 1"=2000'

Following initial soil distribution or redistribution or permanent or temporary stabilization shall be completed within: 1) seven (7) calendar days for all perimeter sediment control structures, dikes, swales, ditches, perimeter slopes and all slopes greater than 3:1 2) fourteen (14) days for all other disturbed or graded areas on project site.

NOTE: The contractor or developer shall contact the construction inspection (survey division) 24 hours in advance of commencement of work at 792-7272.

DEVELOPER'S CERTIFICATION:  
I/We certify that all development and construction will be done according to this plan, and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspections by the Howard Soil Conservation District.

*Paul T. Kavanagh* 4/18/90  
Date

ENGINEER'S CERTIFICATION:  
I certify that this plan for erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District.

*Neil Schwartz* 06/21/98  
Date  
Neil Schwartz #11449

Requirements:

*James M. Felt* 7/5/90  
Date  
Soil Conservation Service

*Clayton A. King* 7/5/90  
Date  
This development plan is approved for Soil Erosion and Sediment Control by the Howard Soil Conservation District.

*Alan M. Duggan* 7/13/90  
Date  
Approved by Howard County Department of Public Works  
Chief, Land Development Division

*Franklin W. Weiland* 7/24/90  
Date  
Chief, Bureau of Highway

*James R. Gray* 11/2/90  
Date  
Chief, Bureau of Engineering

*Paul J. J. ...* 11/15/90  
Date  
Approved by Howard County Department of Planning and Zoning  
Chief, Division of Community Planning and Land Development




DL SHAFIRO  
L.1084, F.137

STATE OF MARYLAND  
L.622, F.72

STATE OF MARYLAND  
L.622, F.484

PLAN  
SCALE: 1"=100'




GENERAL NOTES

1. AREA: 92.6268 AC.
2. ZONE: RURAL
3. TOPOGRAPHY FROM COUNTY RECORDS.
4. DEED REFERENCE: L. 726, F. 424
5. SOIL MAP: S
6. TAX MAP: 6 E 12
7. PARCEL: 5
8. NO. OF LOTS: 13
9. AREA OF LOTS: 49.87 AC.
10. AREA OF PAVEMENT: 2.83 AC.
11. PRIVATE WATER SUPPLY & SEWAGE DISPOSAL SYSTEM TO BE UTILIZED.
12. CUL-DE-SAC LENGTH WAIVER TO BE REQUESTED.

1609

Owner	NO.	REVISIONS	DATE
DEANATHILLS LTD. PARTNERSHIP 10324 B BALTIMORE NAT'L CENTENNIAL SQUARE BELLICOT CITY, MD 21043 (301) 461-6777			



**DEVELOPMENT CONSULTANTS GROUP, INC.**  
17904 GEORGIA AVENUE # 102  
OLNEY, MARYLAND 20832  
301-924-4570

LOT'S 1-13  
STORM DRAIN DRAINAGE AREA MAP  
**PLEASANT HILLS**  
4th ELECTION DISTRICT  
HOWARD COUNTY, MARYLAND  
TAX MAP: 12, PARCEL: 5

DATE	BY	CHECKED	SCALE	SHEET
JUN 02 1998	WF 89-010	ACH	1"=100'	8 of 9

F-90-65



Following listed soil disturbance or construction, permanent or temporary stabilization shall be completed within: 1) seven (7) calendar days for all perimeter sediment control structures, dikes, swales, ditches, perimeter slopes and all slopes greater than 3:1; 2) fourteen (14) days for all other disturbed or graded areas on project site.

NOTES: The contractor or developer shall contact the construction inspection (survey division) 24 hours in advance of commencement of work at 302-7272.

DESIGNER'S CERTIFICATION: I, *W. H. Schatz*, certify that all development and construction will be done according to this plan, and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspections by the Howard County Conservation District.

DATE: *06/24/90*

SEAL:


REVIEWER'S CERTIFICATION: I, *W. H. Schatz*, certify that this plan for erosion and sediment control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Board of Soil Conservation Districts.

DATE: *06/24/90*

APPROVED: *John M. Heber*, 7/5/90, Chief, Bureau of Planning and Land Development

APPROVED: *W. H. Schatz*, 7/5/90, Chief, Bureau of Engineering

APPROVED: *Dr. W. W. McLeod*, 7/24/90, Chief, Bureau of Planning and Land Development



**STANDARD AND SPECIFICATIONS FOR VEGETATIVE STABILIZATION OF CHANNELS AND STEEP SLOPES**





**Definition:** Installing jute or excelsior matting on a prepared seed - or planting - bed of a channel or steep slope to be stabilized with vegetation.

**Purpose:** To aid in controlling erosion on critical sites during establishment period of protective vegetation.

**Conditions Where Practice Applies:** In channels where designed flow exceeds 3.5 feet per second; on short, steep slopes where erosion hazard is high and planting is likely to be slow to establish adequate protective cover; on tidal or stream banks where moving water is likely to wash out new vegetative plantings.

**MATERIALS:**

- Jute mat** shall be cloth of a uniform plain weave of undyed and unbleached single jute yarn, 48 inches in width plus or minus 1 inch and weighing an average of 1.2 pounds per linear yard of cloth with a tolerance of plus or minus 5 percent, with approximately 78 warp ends per width of cloth and 41 weft ends per linear yard of cloth. The yarn shall be of a loosely twisted construction having an average twist or not less than 1.6 turns per inch and shall not vary in thickness by more than one-half its normal diameter.
- Excelsior mat** shall be wood excelsior, 48 inches in width plus or minus 1 inch and weighing 0.8 pounds per square yard plus or minus 10 percent. The excelsior material shall be covered with a netting to facilitate handling and to increase strength.
- Glass fiber matting** of bonded textile glass fibers with an average fiber diameter of 8 to 12 microns, 2 to 4 inch strands of fiber bonded with phenol formaldehyde resin. Mat shall be roll type, water permeable, minimum thickness 1/8 inch, maximum thickness 1/4 inch, density not less than 3 pounds per cubic foot.
- Staples** - staples for anchoring soil stabilizing materials shall be No. 11 gauge wire or heavier. Their length shall be 6 to 10 inches. Use the longer staples on loose, unstable soils.



U.S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE  
COLLEGE PARK, MARYLAND

INLET PROTECTION DETAIL

STANDARD DRAWING  
IPD-1

21.04

**Laying Jute Matting:** (If instructions have been followed, all needed erosion stops will have been installed, and the jute matting will be laid on a friable seedbed free from clods, rocks, roots, etc., that might cause bridging.)

Most channels will require multiple widths of jute matting, two widths being the most commonly used. Unroll matting starting at the upper end of the channel allowing a 4 inch overlap of matting along center of channel.

**Securing Jute Matting:** Bury the top ends of jute matting in a narrow trench, minimum of 6 inch depth, similar to that used for erosion stops. Backfill trench and tamp firmly to conform to channel cross-section. Secure with a row of staples about 4 inches down slope from the trench. Spacing between staples is 6 inches.

Next, staple the 4 inch overlap in channel center using an 18 inch spacing between staples. Before stapling the outer edges of the matting, make sure the matting is smooth and in firm contact with the soil. Staples shall be placed 2 feet apart along the outer edge of matting.

Where one roll of jute matting ends and another begins, the end of the top strip shall overlap the upper end of the lower strip by 4 inches, shiplap fashion.

Where matting crosses erosion stops, reinforce with a double row of staples spaced six (6) inches apart in a staggered pattern on either side of erosion stop. Likewise, overlaps joining the length of matting together and the discharge end of the matting liner should be similarly secured with 2 double rows of staples.

**INSTALLATION REQUIREMENTS:**

**Site Preparation:** After site has been shaped and graded to approved design, prepare a friable seedbed relatively free from clods and rocks more than 1 1/2 inches in diameter, and any foreign material that will prevent contact of the protective mat with the soil surface.

**Planting:** Lime, fertilize, and seed in accordance with seeding or other type of planting plan, except when using jute matting on a seeded area, apply approximately one-half the seed after laying the mat. The protective matting can be laid over sprigged areas where small grass plants have been planted. Where ground covers are to be planted, lay the protective matting first and then plant through the matting according to design of planting.

**Erosion Stops:** (For use on steep, highly erodible watercourses) Erosion stops are made of glass fiber strips, excelsior matting strips or tightly folded jute matting blanket or strips. They are placed in narrow trenches 6 to 12 inches deep across the channel and left flush with the soil surface. They are to cover the full cross-section of designed flow.

**How Used:** Under jute or excelsior matting.

**Location:**

1. Approximately 3 feet down channel from point of entry of a concentrated flow such as from culverts, tributary channels or diversions.
2. At points where change in gradient or course of channel occurs.
3. Spacing of erosion stops on long slopes will vary from 20 to 100 feet depending upon the erodibility of the soil and velocity and volume of flow.

**Final Check**

1. Make sure matting is uniformly in contact with the soil.
2. All lap joints are secure.
3. All staples are flush with the ground.
4. All disturbed areas seeded.

**CONSTRUCTION SEQUENCE**

1. Obtain necessary permits.
2. Notify County 24 hours prior to commencement of construction.
3. Clear and grub for SCE, earth dikes and trap.
4. Install SCE, inlet 1-2 and pipe to S1 (provide inlet protection). Install earth dike along Long Corner Road as shown.
5. Clear and grub for grading and paving of Long Corner Road only.
6. Grade for Long Corner Road and install driveway culvert, bituminous paving; stabilize disturbed areas.
7. Start building sediment traps, install dikes at the top of the slopes as shown, install inlets and storm drain pipes to Trap #2.
8. Clear and grub for Watkins Way. Grade for Watkins Way.
9. Install bituminous paving, curb and gutter and driveway culverts. Stabilize disturbed areas.
10. Remove sediment control devices when approved by Sediment Control Inspector, continue storm drain installation from trap to the infiltration area and outfall as shown on the storm drain plan. Stabilize all disturbed areas.

Owner, Developer: PLEASANT HILLS LIP PARTNERSHIP 10314 B BALTIMORE NAT'L PIKE CENTONNIAL SQUARE PULCOTT CITY, MD 20448 (301) 411-1111	NO.	REVISIONS	DATE

**DEVELOPMENT CONSULTANTS GROUP, INC.**  
17904 GEORGIA AVENUE # 102  
OLNEY, MARYLAND 20832  
301-924-4570

LOT 10-13  
PLEASANT HILLS  
4th ELECTION DISTRICT  
HOWARD COUNTY, MARYLAND  
TAX MAP 12 PARCEL 5

DATE: JUL 00  
DRAWN: BAH  
CHECKED: NSG  
SCALE: AS SHOWN

Sheet 9 of 9  
PROJECT NO. 154-05  
F-90-65

1609