

POND SUM	IMARY TAE	BLE	
DRAINAGE AREA T	O FACILITY	41.43 Ac.	
	2YR	10YR	100YR
ALLOWABLE RELEASE RATE	41.52 cfs	105.34 cfs	184.80 cf
COMPUTED INFLOW	46.46 cfs	108.70 cfs	
DISCHARGE FROM FACILITY	39.01 cfs	99.38 cfs	183.60 cf
DISCHARGE FROM SITE	41.00 cfs	105.19 cfs	186.39 cf
PROP. WATER SURFACE ELEV.	350.5	351.4	352.0
STORAGE IN FACILITY HAZARD CLASS 'B'	0.47 AF	0.60 AF	1.19 AF

# STORMWATER MANAGEMENT FACILITY

water that the

# SEQUENCE OF CONSTUCTION

- (NOTE: THIS SEQUENCE TO BE PHASED WITH NO. 4 OF SEQUENCE OF CONSTRUCTION AT RIGHT) L BEGIN EXCAVATION FOR STORMWATER MANAGEMENT FACILITY POOL AREA. INSTALL 24" CMP DIVERSION PIPE (OR APPROVED EQUAL) TO DIVERT STREAM FLOW AWAY FROM PRINCIPAL SPILLWAY WORK AREA TO CREATE A DRY WORKING ENVIRONMENT.
- 2. CONSTRUCT CUT- OFF TRENCH AND FILTER DIAPHRAM BELOW CONCRETE CRADLE (REFER TO NOTES UNDER TYPICAL EMBANKMENT SECTION ON SHEET NO. 7).
- 3. CONSTRUCT CONCRETE CRADLE, PRINCIPAL SPILLWAY AND APRON.
- 4. REDIRECT STREAM FLOW TO PRINCIPAL SPILLWAY
  STRUCTURE. REMOVE PIVERSION PIPE INSTALLED
  UNDER SERVENCE NO. I.
  5. PROCEED WITH CORE, FILTER DIAPHRAM AND EMBANKMENT
  CONSTRUCTION
- NOTE: FOR DETAILS RELATED TO STREAM CONSTRUCTION REFER TO MARYLAND'S GUIDELINES TO WATER WAY CONSTRUCTION, BY MARYLAND DEPARTMENT OF THE ENVIRONMENT WATER RESOURCES ADMINISTRATION.

### SEQUENCE OF CONSTRUCTION

2) INSTALL STABILIZED CONSTRUCTION ENTRANCE INSTALL SILT FENCE, SUPER SILT FENCE, EARTH DIKE, SEDIMENT TRAP AND TREE PROTECTION FENCE.

4) CONSTRUCT STORMWATER MANAGEMENT FACILITY. MASS GRADE SITE AND STABILIZE ACCORDING TO TEMPORARY SEEDBED NOTES.

5) CONSTRUCT WATER LINE, SANITARY SEWER LINE AND STORM DRAIN SYSTEM.

AFTER STABILIZATION AND WITH APPROVAL OF HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS SEDIMENT CONTROL INSPECTOR, REMOVE TEMPORARY STREAM

ACCORDANCE WITH PERMANENT SEEDBED NOTES.

7) CONSTRUCT CURB AND GUTTER, PAVEMENT AND UPON APPROVAL OF THE HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS SEDIMENT CONTROL INSPECTOR REMOVE ALL REMAINING SEDIMENT CONTROL DEVICES AND STABILIZE ANY REMAINING DISTURBED AREAS IN

#### STORMWATER MANAGEMENT FACILITY SEDIMENT CONTROL DATA STORMWATER MANAGEMENT FACILITY WILL BE UTILIZED FOR SEDIMENT CONTROL DURING GRADING OPERATIONS.

DRAINAGE AREA 4.4 Ac. STORAGE REQUIRED 15,840 cf (3600 cf x 4.4 Ac.) STORAGE PROVIDED 31,581 cf (STORAGE PROVIDE TO FIRST WEIR OPENING ELEV. 349.10) BOTTOM ELEVATION 349.1 CREST ELEVATION CLEAN OUT ELEVATION DISTANCE FROM TOP OF

"I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND

RELEASE STUCTURE TO

C.O. ELEVATION

EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT." BY THE ENGINEER:

"I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT." Donald Mason THIS DEVELOPMENT PLAN IS APPROVED FOR EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

NATURAL DESOURCES CONSERVATION SERVICES REVIEWED FOR HOWARD SOIL CONSERVATION DISTRICT AND MEETS TECHNICAL 6/2/97 DATE:

APPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

610-97 CHIEF, BUREAU OF HIGHWAYS DATE

HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING Kirland Blood

CHIEF, DIVISION OF LAND DEVELOPMENT Me Commens

CHIEF, DEVELOPMENT ENGINEERING DIVISION

REVISION NO DATE

TSA GROUP, INC. planning • architecture • engineering • surveying

DES:

8480 Baltimore National Pike • Ellicott City, Maryland 21043 • (410)465-6105

OAKHURST HARRY AND HELEN KNISLEY (FORMERLY KNISLEY PROPERTY) SECTION 1 - AREA 1 LOTS 1-41 9513 GUILFORD ROAD COLUMBIA, MARYLAND 21046 LOCATION: TAX MAP 42 - PARCEL 69 6th ELECTION DISTRICT HOWARD COUNTY, MARYLAND DEVELOPER: SDC GROUP INC. GRADING AND SEDIMENT CONTROL PLAN P.O. BOX 417

S-94-20, P-95-28, WP-96-49 ELLICOTT CITY, MARYLAND 21041 DATE: SEPTEMBER 29, 1996 PROJECT NO. 0527 (410) 465-4244 DRN: SCALE: AS SHOWN DRAWING  $\frac{4}{}$  OF  $\frac{11}{}$ 



ESTABLISHMENT OF GRASSES.

INSPECTION AGENCY IS MADE.

- . A MINIMUM OF 48 HOURS NOTICE MUST BE GIVEN TO THE HOWARD COUNTY DEPARTMENT OF INSPECTIONS AND PERMITS SEDIMENT CONTROL DIVISION PRIOR TO THE START OF ANY CONSTRUCTION.
- 2. ALL VEGETATIVE AND STRUCTURAL PRACTICES ARE TO BE INSTALLED ACCORDING TO THE PROVISIONS OF THIS PLAN AND ARE TO BE IN CONFORMANCE WITH THE 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL AND REVISIONS THERETO.
- 3. FOLLOWING INITIAL SOIL DISTURBANCE OR REDISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN: A) 7 CALENDAR DAYS FOR ALL PERIMETER SEDIMENT CONTROL STRUCTURES, DIKES, PERIMETER SLOPES AND ALL SLOPES GREATER THAN 3:1, B) 14 DAYS AS TO ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE.
- 4. ALL SEDIMENT TRAPS/BASINS SHOWN MUST BE FENCED AND WARNING SIGNS POSTED AROUND THEIR PERIMETER IN ACCORDANCE WITH VOL. 1, CHAPTER 12, OF THE HOWARD COUNTY DESIGN MANUAL, STORM DRAINAGE.
- ALL DISTURBED AREAS MUST BE STABILIZED WITHIN THE TIME PERIOD SPECIFIED ABOVE IN ACCORDANCE WITH THE 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR PERMANENT SEEDINGS (SEC. 51) SOD (SEC. 54), TEMPORARY SEEDING (SEC. 50) AND MULCHING (SEC. 52). TEMPORARY STABILIZATION WITH MULCH ALONE CAN ONLY BE DONE WHEN RECOMMENDED SEEDING DATES DO NOT ALLOW FOR PROPER GERMINATION AND
- ALL SEDIMENT CONTROL STRUCTURES ARE TO REMAIN IN PLACE AND ARE TO BE MAINTAINED IN OPERATIVE CONDITION UNTIL PERMISSION FOR THEIR REMOVAL HAS BEEN OBTAINED FROM THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR.

	BEEN OBTAINED TROW THE HOWARD COOKET SEDIMENT	CONTROL INSP	LCTOR.
7.	SITE ANALYSIS:	0.40	
	TOTAL AREA OF SITE	6.48	ACRES
	AREA DISTURBED (on site )	6.11	ACRES
	AREA DISTURBED (Guilford Road)	0.89	ACRES
	TOTAL AREA DISTURBED	7.00	ACRES
	AREA TO BE ROOFED OR PAVED	1.09	ACRES
	AREA TO BE VEGETATIVELY STABILIZED	5.91	ACRES
	TOTAL CUT	10442	CU YDS
	TOTAL FILL	20339	CU YDS
	OFFSITE BORROW	11589	CU YDS
8.	ANY SEDIMENT CONTROL PRACTICE WHICH IS DISTURBED	BY GRADING	ACTIVITY FOR

- PLACEMENT OF UTILITIES MUST BE REPAIRED ON THE SAME DAY OF DISTURBANCE.

  9. ADDITIONAL SEDIMENT CONTROLS MUST BE PROVIDED, IF DEEMED NECESSARY BY
- THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR.

  10. ON ALL SITES WITH DISTURBED AREAS IN EXCESS OF 2 ACRES, APPROVAL OF THE INSPECTION AGENCY SHALL BE REQUESTED UPON COMPLETION OF INSTALLATION OF

PERIMETER EROSION AND SEDIMENT CONTROLS, BUT BEFORE PROCEEDING WITH ANY OTHER EARTH DISTURBANCE OR GRADING. OTHER BUILDING OR GRADING INSPECTION

11. TRENCHES FOR THE CONSTRUCTION OF UTILITIES ARE LIMITED TO THREE PIPE LENGTHS OR THAT WHICH CAN BE BACK FILLED AND STABILIZED WITHIN ONE WORKING DAY, WHICHEVER IS SHORTER.

APPROVALS MAY NOT BE AUTHORIZED UNTIL THIS INITIAL APPROVAL BY THE

#### TEMPORARY SEEDBED PREPARATION

APPLY TO GRADED OR CLEARED AREAS LIKELY TO BE REDISTURBED WHERE A SHORT-TERM VEGETATIVE COVER IS NEEDED.

SEEDBED PREPARATION: LOOSEN UPPER THREE INCHES OF SOIL BY RAKING, DISCING OR OTHER ACCEPTABLE MEANS BEFORE SEEDING, IF NOT PREVIOUSLY LOOSENED.

SOIL AMENDMENTS: APPLY 600 LBS PER ACRE 10-10-10 FERTILIZER (14 LBS/1000 SQ FT).

SEEDING: FOR PERIOD MARCH 1 THROUGH APRIL 30 AND FROM AUGUST 15 THROUGH NOVEMBER 15, SEED WITH 2-1/2 BUSHELS PER ACRE OF ANNUAL RYE (3.2 LBS/1000 SQ FT). FOR THE PERIOD MAY 1 THROUGH AUGUST 14, SEED WITH 3 LBS PER ACRE OF WEEPING LOVEGRASS (.07 LBS/1000 SQ FT). FOR THE PERIOD NOVEMBER 16 THROUGH FEBRUARY 28, PROTECT SITE BY APPLYING 2 TONS PER ACRE OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING, OR USE SOD.

MULCHING: APPLY 1-1/2 TO 2 TONS PER ACRE (70 TO 90 LBS/1000 SQ FT) OF UNROTTED SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. ANCHOR MULCH IMMEDIATELY AFTER APPLICATION USING MULCH ANCHORING TOOL OR 218 GALLONS PER ACRE (5 GAL/1000 SQ FT) OF EMULSIFIED ASPHALT ON FLAT AREAS. ON SLOPES, 8 FT. OR HIGHER, USE 348 GALLONS PER ACRE (8 GAL/1000 SQ FT) FOR ANCHORING.

REFER TO THE 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR RATE AND METHODS NOT COVERED.

# PERMANENT SEEDBED PREPARATION

SEEDBED PREPARATION: LOOSEN UPPER THREE INCHES OF SOIL BY RAKING, DISCING OR OTHER ACCEPTABLE MEANS BEFORE SEEDING, IF NOT PREVIOUSLY


SOIL AMENDMENTS: IN LIEU OF SOIL TEST RECOMMENDATIONS, USE ON OF THE FOLLOWING SCHEDULES:


- 1. PREFERRED APPLY 2 TONS PER ACRE DOLOMITIC LIMESTONE (92 LBS/1000 SQ FT) AND 600 LBS PER ACRE 10-10-10 FERTILIZER (14 LBS/1000 SQ FT) BEFORE SEEDING. HARROW OR DISC INTO UPPER THREE INCHES OF SOIL. AT TIME OF SEEDING, APPLY 400 LBS PER ACRE 30-0-0- UREAFORM FERTILIZER (9 LBS/1000 SQ
- 2. ACCEPTABLE APPLY 2 TONS PER ACRE DOLOMITIC LIMESTONE (92 LBS/1000 SQ FT) AND 1000 LBS PER ACRE 10-10-10 FERTILIZER (23 LBS/1000 SQ FT) BEFORE SEEDING. HARROW OR DISC INTO UPPER THREE INCHES OF SOIL.

SEEDING: FOR THE PERIODS MARCH 1 THROUGH APRIL 30 AND AUGUST 1 THROUGH OCTOBER 15, SEED WITH 60 LBS PER ACRE (1.4 LBS/1000 SQ FT) OF KENTUCKY 31 TALL FESCUE PER ACRE AND 2 LBS PER ACRE (.05 LBS/1000 SQ FT) OF WEEPING LOVEGRASS. DURING THE PERIOD OF OCTOBER 16 THROUGH FEBRUARY 28, PROTECT SITE BY: OPTION (1) 2 TONS PER ACRE OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING. OPTION (2) USE SOD. OPTION (3) SEED WITH 60 LBS PER ACRE OF KENTUCKY 31 TALL FESCUE AND MULCH WITH 2 TONS PER ACRE OF WELL ANCHORED STRAW.

MULCHING: APPLY 1-1/2 TO 2 TONS PER ACRE (70 TO 90 LBS/1000 SQ FT) OF UNROTTED SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. ANCHOR MULCH IMMEDIATELY AFTER APPLICATION USING MULCH ANCHORING TOOL OR 218 GALLONS PER ACRE (5 GAL/1000 SQ FT) OF EMULSIFIED ASPHALT ON FLAT AREAS. ON SLOPES 8 FEET OR HIGHER, USE 348 GALLONS PER ACRE (8 GAL/1000 SQ FT) FOR ANCHORING.

MAINTENANCE: INSPECT ALL SEEDED AREAS AND MAKE NEEDED REPAIRS, REPLACEMENTS AND RESEEDINGS.





ANCHOR POSTS MUST BE INSTALLED TO A DEPTH OF NO LESS THAN 1/3 OF

NOTES: BLAZE ORANGE PLASTIC MESH

PROTECTIVE SIGNAGE IS ALSO REQUIRED.

THE TOTAL HEIGHT OF THE POST. BOTTOM

FOREST PROTECTION DEVICE ONLY.
 RETENTION AREA WILL BE SET AS PART OF THE REVIEW PROCESS.
 BOUNDARIES OF RETENTION AREA SHOULD BE STAKED AND FLAGGED FLAGGED PRIOR TO INSTALLING DEVICES.


TEMPORARY TREE PROTECTION FENCE

NOT TO SCALE

DES: GWF

DRN:

4. AVOID ROOT DAMAGE WHEN PLACING ANCHOR POSTS.
5. DEVICE SHOULD BE PROPERLY MAINTAINED DURING CONSTRUCTION



TSA GROUP, INC.
planning • architecture • engineering • surveying

8480 Baltimore National Pike • Ellicott City, Maryland 21043 • (410)465-6105

DWNER:

HAPPY AND HELEN KNISLEY

PROJECT:


OAKHURST


HARRY AND HELEN KNISLEY (FORMERLY KNISLEY PROPERTY) 9513 GUILFORD ROAD SECTION 1 - AREA 1 LOTS 1-41 COLUMBIA. MARYLAND 21046 LOCATION: TAX MAP 42 - PARCEL 69 6th ELECTION DISTRICT HOWARD COUNTY, MARYLAND DEVELOPER: ΠTLE: SEDIMENT CONTROL SDC GROUP INC. NOTES AND DETAILS P.O. BOX 417 S-94-20, P-95-28, WP-96-49 ELLICOTT CITY, MARYLAND 21041 DATE: SEPTEMBER 29, 1996 (410) 465-4244 PROJECT NO. 0527 MAY 22, 1997

SCALE: AS SHOWN

0

DRAWING  $\frac{5}{}$  OF  $\frac{11}{}$ 





#### STORMWATER MANAGEMENT NOTES

#### Site Preparation

Areas designated for borrow areas, embankment, and structural works shall be cleared, grubbed and stripped of topsoil. All trees, vegetation, roots and other objectionable material shall be removed. Channel banks and sharp breaks shall be sloped to no steeper than 1:1.

Areas to be covered by the reservoir will be cleared of all trees. brush, logs, fences, rubbish and other objectionable material unless otherwise designated on the plans. Trees, brush and stumps shall be cut approximately level with the ground surface. For dry stormwater management ponds, a minimum of a 50 foot radius around the inlet structure shall be cleared.

All cleared and grubbed material shall be disposed of outside and below the limits of the dam and reservoir as directed by the owner or his representative. When specified, a sufficient quantity of topsoil will be stockpiled in a suitable location for use on the embankment and other designated areas.

#### Earth Fill

Material - The fill material shall be taken from approved designated borrow areas. It shall be free of roots, stumps, wood, rubbish, stones greater than 6", frozen or other objectionable materials. Fill material for the center of the embankment and cut off trench shall conform to Unified Soil Classification GC, SC, CH, or CL. Consideration may be given to the use of other materials in the embankment if design and construction are supervised by a geotechnical engineer.

Placement - Areas on which fill is to be placed shall be scarified prior to placement of fill. Fill materials shall be placed in maximum 8 inch thick (before compaction) layers which are to be continuous over the entire length of the fill. The most permeable borrow material shall be placed in the downstream portions of the embankment. The principal spillway must be installed concurrently with fill placement and not excavated into the embankment.

Compaction — The movement of the hauling and spreading equipment over the fill shall be controlled so that the entire surface of each lift shall be traversed by not less than one tread track of the equipment or compaction shall be achieved by a minimum of four complete passes of a sheepsfoot, rubber tired or vibratory roller. Fill material shall contain sufficient moisture such that the required degree of compaction will be obtained with the equipment used. The fill material shall contain sufficient moisture so that if formed into a ball it will not crumble yet not be so wet that water can be squeezed out.

Where a minimum required density is specified, it shall not be less than 95% of maximum dry density with a moisture content within +/-2% of the optimum. Each layer of fill shall be compacted as necessary to obtain that density, and is to be certified by the Engineer at the time of construction. All compaction is to be

#### determined by AASHTO Method T-99. Cut Off Trench — The cutoff trench shall be excavated into

impervious material along or parallel to the centerline of the embankment as shown on the plans. The bottom width of the trench shall be governed by the equipment used for excavation, with the minimum width being four feet. The depth shall be at least four feet below existing grade or as shown on the plans. The side slopes of the trench shall be 1 to 1 or flatter. The backfill shall be compacted with construction equipment, rollers, or hand tampers to assure maximum density and minimum permeability.

#### Structure Backfill

Backfill adjacent to pipes or structures shall be of the type and quality conforming to that specified for the adjoining fill material. The fill shall be placed in horizontal layers not to exceed four inches in thickness and compacted by hand tampers or other manually directed compaction equipment. The material needs to fill completely all spaces under and adjacent to the pipe. At no time during the backfilling operation shall driven equipment be allowed to operate closer than four feet, measured horizontally, to any part of a structure. Under no circumstances shall equipment be driven over any part of a concrete structure or pipe, unle there is a compacted fill of 24" or greater over the structure or

# Pipe Conduits

All pipes shall be circular in cross section.

Reinforced Concrete Pipe - All of the following criteria shall apply for reinforced concrete pipe:

- Materials Reinforced concrete pipe shall have bell and spigot joints with rubber gaskets and shall equal or exceed ASTM Designation C-361. An approved equivalent is AWWA Specification C-302.
- Bedding All reinforced concrete pipe conduits shall be laid in a concrete bedding for their entire length. This bedding shall consist of high slump concrete placed under the pipe and up the sides of the pipe at least 10% of its outside diameter with a minimum thickness of 3 inches, or as shown on the
- Laying pipe Bell and spigot pipe shall be placed with the bell end upstream. Joints shall be made in accordance with recommendations of the manufacturer of the material. After the joints are sealed for the entire line, the bedding shall be placed so that all spaces under the pipe are filled. Care shall be exercised to prevent any deviation from the original line and grade of the pipe. The first joint must be located within 2 feet from the riser.
- Backfilling shall conform to "Structure Backfill"
- 5. Other details (anti-seep collars, valves, etc.) shall be as shown on the drawings.

Polyvinyl Chloride (PVC) Pipe - All of the following criteria shall apply for polyvinyl chloride (PVC) pipe:

- Materials PVC pipe shall be PVC—1120 or PVC—1220 conforming to ASTM D—1785 or ASTM D—2241.
- Joints and connections to anti-seep collars shall be
- Bedding The pipe shall be firmly and uniformly bedded throughout its entire length. Where rock or soft, spongy or other unstable soil is encountered, all such material shall be removed and replaced with suitable earth compacted to provide adequate support.
- 4. Backfilling shall conform to "Structure Backfill."

completely watertight.

Other details (anti-seep collars, valves, etc.) shall be as shown on the drawings.

# Concrete

Concrete shall meet the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 608, Mix No.

# Rock Riprap

All rock shall be dense, sound, and free from cracks, seams, and other defects conducive to accelerated weathering. The rock fragments shall be angular to subrounded in shape. The least dimension of an individual rock fragment shall be not less than one third the greatest dimension of the fragment.

# The rock shall have the following properties:

when sodium sulfate is used.

- Bulk specific gravity (saturated surface-dry basis) not less
- Absorption not more than three percent Soundness: Weight loss in five cycles not more than 20 percent

Bulk specific gravity and absorption shall be determined according to ASTM C 127. The test for soundness shall be performed according

The riprop shall be placed to the required thickness in one operation. The rock shall be delivered and placed in a manner that will insure the riprap in place shall be reasonably homogeneous with the larger rocks uniformly distributed and firmly in contact one to another with the smaller rocks filling the voids between the larger rocks. Filter cloth shall be placed under all riprap and shall meet the requirements of Maryland Department of Transportation, State Highway Administration Standard Specifications for Construction and Materials, Section 919.12.

#### Care of Water during Construction


All work on permanent structures shall be carried out in areas free from water. The Contractor shall construct and maintain all temporary dikes, levees, cofferdams, drainage channels, and stream diversions necessary to protect the areas to be occupied by the permanent works. The contractor shall also furnish, install, operate, and maintain all necessary pumping and other equipment required for removal of water from the various parts of the work and for maintaining the excavations, foundation, and other parts of the work free from water as required or directed by the engineer for constructing each part of the work. After having served their purpose, all temporary protective works shall be removed or leveled and graded to the extent required to prevent obstruction in any degree whatsoever of the flow of water to the spillway or outlet works and so as not to interfere in any way with the operation or maintenance of the structure. Stream diversions shall be maintained until the full flow can be passed through the permanent works. The removal of water from the required excavation and the foundation shall be accomplished in a manner and to the extent that will maintain stability of the excavated slopes and bottom of required excavations and will allow satisfactory performance of all construction operations. During the placing and compacting of material in required excavations, the water level at the locations being refilled shall be maintained below the bottom of the excavation at such locations which may require draining the water to sumps from which the water shall be pumped.

#### Stabilization

All borrow areas shall be graded to provide proper drainage and left in a sightly condition. All exposed surfaces of the embankment, spillway, spoil and borrow areas, and berms shaft be stabilized by seeding, liming, fertilizing and mulching in accordance with the Maryland Soil Conservation Service Standards and Specifications for Critical Area Planting (MD-342) or as shown on the accompanying drawings.


#### Erosion and Sediment Control

Construction operations will be carried out in such a manner that erosion will be controlled and water and air pollution minimized. State and local laws concerning pollution abatement will be followed. Construction plans shall detail erosion and sediment control measures to be employed during the construction process.




GRAVEL JACKET -CONCRETE ANTI-FLOTATION COLLAR 1.5' SQUARE 6" DEWATERING PIPE DETAIL

NO SCALE



PROFILE THROUGH FOREBAY STONE WEIR NOT TO SCALE



STRUCTURE	d50	LENGTH (L)	WIDTH (W)	THICKNESS (T)
HW-2	0.75'	20.0'	11.5'	1.50'
* HW1	0.75'	30.0'	14.0'	1.50'

OUTLET PROTECTION DETAIL NOT TO SCALE

# noisture, density, size, proportion DEPTH (FT.) BORING & SAMPLING NOTES SURFACE (elevation 346.0±) 0.0 Brownish tan wet clayey Siit, Trace to some decomposed rock Grange brown and greyleh tan molet clayey dift and decempased rack agments (ML) TD 0

IP-1

	IP-2		
SOIL DESCRIPTION color, moisture, density, size, proportion	STRA. DEPTH	DEPTH (FT.)	BORING & SAMPLING NOTES
SURFACE (elevation 352.0±)		0.0	4"± TOPSOIL
Greyish tan moist to wet sandy Slit, same clay and gravel (ML)	1.0		PERCHED WATER TABLE AT 2.5'
Orange brown and tan wet clayey sand and gravel, trace grayleh slity clay seames (SC/GM)	4.5		WATER BEARING SILTY SANDS AND GRAVELS
Orange brown and dark brown wet sandy silt and decomposed rock (Mi.)	6.0	5 —	STREAM 15' NORTH FROM TP-2
Orange brown and grayish tan silty clay and decomposed fragments (CL)	8.0		BECAUSE ONLY LITTLE WATER WAS GETTING INTO HOLE PROCEEDED WITH INFILTRATION
Gray moist sandy silt and little decomposed rock fragments (ML)	10.0	10 —	TEST AT 6.0'
Test Pit terminated		15 -	
		20	

	P-3		
SOIL DESCRIPTION color, moisture, density, size, proportion	STRA. DEPTH	DEPTH (FT.)	BORING & SAMPLING NOTES
SURFACE (devotion 349.0±)		0.0	6°± TOPSOIL
Tan moist to wet cloyey Silt and decomposed rock (ML)	1.5		WATER AT 3.5"
Tan and clayey very wet elity clay, some decomposed rock fragments (CL)	3.0		
Grayish tan very wet to saturated	5.0	_ =	TEST DEPTH AT 5.0"
silty clay, trace fine sand and gravel		<b>5</b>	NO FILTRATION TEST RUN
Test Pit terminated		10	

	IP-	<u>-5</u>	
SOIL DESCRIPTION color, moisture, density, size, proportion	STRA. DEPTH	DEPTH (FT.)	BORING & SAMPLING NOTES
SURFACE (elevation 347.0±)  Brown tan wet to saturated clayey slit	ļ	0.0	6"± TOPSOIL
some decomposed rock fragments (ML)  Brown tan saturated sandy slit and	2.5 3.0	=	WATER AT ELEVATION 2.5"
Grayish moist to wet sity clay (CL)	5.0	5	BOTTOM OF POND AT 344.0
Test Pit terminated			INFILTRATION TEST NOT RUN TO WATER IN PIT AT TEST DEPTI
		10 -=	
		_=	
		15 —	
		-	
		20	
SOIL	BORI	NG L	ogs

NOT TO SCALE

RECORD OF BOIL EXPLORATION

SOIL DESCRIPTION STRA. DEPTH SAMPLE OF NO. PREC. SURFACE 0.0 BLOWS 6" NO. PREC. Brown, vary mosk, measure soff set.


14" Cover to to 1.0" at

**GFA-CONT. PLIGHT AUGS** 

little fine sand, trace roots and gravel

ange brown with black, moist me

Green, moist, dense, sity fine sand



(18"HW


EX. 18" CMP

Q<sub>10</sub>=6.74 cfs

V. =4.95 for

. INVERT TO BE VERIFIED

BY CONTRACTOR




Q<sub>10</sub>=8.74 cfs

V<sub>f</sub> =4.95 fpe

V<sub>D</sub> =10.42 fps

S. =0.80%




SELECT FILL 95%

V<sub>s</sub> =5.67 fps

V<sub>D</sub> =7.61 fpm

S. =1.06%

30° RCCP CL IV ● 0.50%



ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT."

"I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A

PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

James R. Mufley &

OF THE HOWARD SOIL CONSERVATION DISTRICT."

WATURAL RESOURCES CONSERVATION SERVICE

DEVELOPMENT ENGINEERING DIVISION

CHIEF, DIVISION OF LAND DEVELOPMENT

THE HOWARD SOIL CONSERVATION DISTRICT.

Kirkere Blood

REQUIREMENTS

DES:

V<sub>c</sub> =3.43 fps

S. =0.20%

\_=5.83 fps

M-1

( HW-2

V<sub>f</sub> =4.01 fps

S. =0.23%

V<sub>D</sub> =10.73 fpe

GABION SLOPE

4/29/97

4/29/97


6/2/97 DATE:


6/2/97


VIC DATE

0/12/97

DATE









S-94-20 NOTES AND DETAILS P.O. BOX 417 P-95-28 STORM DRAIN PROFILES ELLICOTT CITY, MARYLAND 21041 WP-96-49 DATE: MAY 22,1997 (410) 465-4244 PROJECT NO. 0527 DRN: SCALE: AS SHOWN DRAWNG 8 OF 11

(X)





#### FOREST PROTECTION PROCEDURES - Post-Construction Phase

#### The following measures shall be taken:

- 1.) Corrective measures if damages were incurred due to negligence:
  - a.) Stress reduction
  - b.) Removal of dead or dying trees. This may be done only if trees pose an immediate safety hazard

#### 2.) Removal of temporary structures:

- a.) No burial of discarded materials will occur on-site within the conservation area.
- b.) No open burning within 100 feet of a wooded area.
- c.) All temporary forest protection structures will be removed after construction.
- d.) Remove temporary roads by removing stone or broadcasting mulch; pre-construction elevation should be maintained.
- e.) Aerate compacted soil.
- f.) Replant disturbed sites with trees, shrubs and/or herbaceous plants.
- g.) Retain signs for conservation areas or specimen trees.
- h.) A County official shall inspect the entire site.
- 3.) Future protection measures:
  - a.) Howard County and the developer shall arrange for the dedication of an appropriate forest conservation easement at a later date.

#### FOREST PROTECTION PROCEDURES - Preconstruction Phase

Stress Reduction and Protection of Specimen Trees Isolated from Forest Retention Areas and General Forest Retention Areas (As They May Apply)

Isolated specimen trees that are to be preserved will be examined to determine if stress reduction techniques are needed. Protective measures and their evaluation criteria are provided on this plan only if they are employed herein.

#### Root Pruning

#### Evaluation Criteria

Will the critical root zone be affected by construction activities such as grade changes, digging for foundations and roads or utility installation?

### Design Considerations

- a.) Prune prior to construction as shown on the plan (see Figure "Root Pruning Detail.")
- b.) Prune root with a clean cut using proper pruning equipment such as a vibratory knife.
- c.) Exact location of pruning trench should be identified, and immediately back-filled to cover exposed roots after pruning with soil removed other topsoil, peat moss, or other suitable
- material or with other high organic soil. d.) For trees over 15" in diameter, root pruning may be done up to
- one year in advance of construction. e.) Tree(s) will be monitored for signs of stress

# Crown Reduction or Pruning

dead, damaged, or diseased limbs?

# Evaluation Criteria

Has the root system been significantly reduced (>30%) or are there

# Design Considerations

- a.) Reduce only at specified times of the year: Flowering trees only after flowering and before bud set Non-Flowering trees - in late winter, early spring or mid
- b.) No more than 1/3 of the crown should be removed at one time using acceptable pruning methods (see Figure "Crown Reduction Detail.") c.) Monitor for signs of stress

# Watering

# Evaluation Criteria

Will construction activities alter the hydrology of the site? Has or will root pruning occur?

# Design Considerations

a.) Water only as necessary b.) Monitor for signs of stress (see Figure "Tree Planting and Maintenance Calendar")

#### <u>Fertilizing</u> Evaluation Criteria

Is or will the tree(s) be under stressful conditions? Has or will root pruning occur?

# Design Considerations

- a.) Use low nitrogen and slow release fertilizers. b.) Apply in late fall or early spring (see Figure "Tree Planting
- and Maintenance and Calendar") c.) For small trees (<3" in diameter), use broadcast method. d.) For larger trees (>3" in diameter), use punch hole method or pressurized injection method (see Figure "Application of
- Fertilizers by Injection.") e.) Do not apply fertilizer any closer than 3' from tree trunk for pressurized injection method.

# f.) Monitor for signs of stress.

# Delineation of the Critical Root Zone


Calculation of the CRZ for Isolated Specimen Trees:

# 1.5 feet of protective radius per inch of DBH


# 41 " Elm = 61.5'

# Protection of the Critical Root Zone

Upon determining the CRZ, blaze orange protective fencing (see Figure "Protective Fencing") shall be erected one foot from the limits of the CRZ so as to completely surround the tree or trees to be protected. No disturbance, storage, parking, or alteration of drainage of any kind shall be permitted within the CRZ Protective Area except prior allowable root pruning. Signs designating a specimen tree protective area shall be placed atop the protective fencing at a minimum interval of 25 feet (see Figure "Signage"). No signs are to be attached to the specimen tree itself.



WIDTH = AUGERED HOLE 18" MINIMUM PLANTING FIELD DETAIL




SYCAMORE/OAK TULIP POPLAR


RED MAPLE


TO BE PLANTED


IN RANDOM DISTRIBUTION PATTERN

RANDOM PLANTING DETAIL










PROTECTIVE FENCING



Notes:


1. Retention Areas will be set as part of the review process.


2. Soundaries of Retention Areas should be stated diagged paior to trenching.

3. Exact location of trench should be identified.

4. Trench should be immediately backfilled with soll removed or other high organic set.

5. Roots should be cleanly cull using vibratory knills or other acceptable equipment.





Notes:

1. Only prune at specified times

2. No mase than 30% of crown to be semoved at one time.

#### PLANTING SPECIFICATIONS AND NOTES

# I. SITE PREPARATION AND SOILS

- 1.) Disturbance of soils should be limited to the Planting Field for each plant. Planting hole will be a minimum 18" auger hole, dug to the depth of the root ball. As shown on the detail view, a Planting Field of 18 " diameter is recommended.
- 2.) In areas of steep slopes or erodible soils, soil disturbance will be limited to the Planting Field which is equal to the 18" diameter auger hole.
- 3.) Soil mix for all plants shall be native soil with no soil amendments, unless a soils analysis determines that soil amendments are required (disturbed sites). Natural amendments, such as organic mulch or leaf mold compost, are preferred.

#### II. PLANT STORAGE AND INSPECTION

- 1.) For container grown nursery stock, planting should occur within two weeks after delivery to site.
- 2.) Planting stock should be inspected prior to planting. Plants not conforming to standard nurseryman specifications for size, form, and vigor, roots, trunk wounds, insects and disease should be replaced.

#### III. SOIL AMENDMENTS

1.) Amendments are not recommended in the planting field as studies have shown that roots will be encouraged to stay within the amended soils.

# IV. PLANT INSTALLATION

- 1.) Container grown stock should be removed from the container and roots gently loosened from the soil. If the roots encircle the root ball, substitution is required. J-shaped or kinked root systems should also be rejected. ROOTS MAY NOT BE TRIMMED ON SITE.
- 2.) The Planting Field should be prepared as specified (see detail). Stock must be planted in random pattern (see detail). Native dug soils should be used to backfill Planting Field. Set plant material no more than 1 " above existing ground and no lower than existing ground. Gently pack native soil around plant to eliminate all air pockets. After whip and container installation, rake soils evenly over the Planting Field and cover hole with three inches of composted hardwood mulch. Water to settle soil and provide moisture, as needed.
- 3.) Prune whips to encourage branching. Container stock will be pruned to eliminate broken and dead branches.
- 4.) Newly planted trees may need watering depending on weather conditions. During the next two years watering may be required during summer and dry months. Any watering should consider for recent rainfall patterns.
- 5.) Staking of stock is not required, if preferred stock type
- 6.) Side dressing fertilization 1 year after planting may be warranted.

# V. MAINTENANCE SCHEDULE

Landscaper should conduct an inspection at the following intervals: 6 months after planting, 1 year after planting and 2 years after planting. The purpose of inspection is to evaluate survival rate with reference to the survival required at the end of the two year period (75% minimum).

Regular visits during the first growing season (yr 1) are to assess the success of the plantings and determine if supplemental watering or other actions are necessary. Early spring visits will determine winter kill and autumn visits will determine summer

- Assess tree mortality of planting stock, remove and replace any dead or diseased plantings for the first 2 growing
- 3.) Volunteer seeding of native, local and endemic vegetation is to be expected. Do not discourage this effort unless it is negatively effecting the planted stock.
- Landscaper shall remove or control aggressive, noxious, invasive species (i.e. Multiflora Rose, Japanese Honeysuckle, and all herbaceous vegetation) within a 3-foot radius surrounding the planted woody nursery stock for 2 years after planting.
- 5.) The landscaper shall be responsible to remove down and dead material that is smothering planting stock. Naturally occurring material that is not affecting planted stock shall not be removed.
- Mowing is one of the most effective means to control exotic and/or invasive species. No mowing shall occur during the wildlife nesting period of early April through mid-July. The landscaper is responsible for mowing and/or weed wacking and/or applying herbicide around planting stock, if needed for 2 growing seasons after planting.

M.A. DIRCKS & CO., INC. Environmental Consulting Services

410-526-7388

15228 Old Hanover Road Upperco, MD 21155 mary a Direks

#### PLANT LIST


INDICATOR

YTQ			SPECIES	5	STATUS	SIZE	
Open s	Space	lot	40 (outside of	existing	tree lin	e):	
14			<u>Viburnum</u> <u>dentat</u> <b>Arrowwood</b>	<u>tum</u>	FACW	whip/container	
14			Acer rubrum Red maple		FAC	whip	
28			Mixed oaks (2 o Quercus alba palustris rubra prinus	different	species FACU FAC FACU UPL	required) whip	
14			Cornus florida		FACU	Whip/container	
Open s	Space	lot	41:	•			
6			Acer rubrum Red maple	,	FAC	2" caliper	
18			Mixed oaks (3 one of oaks of o	different	species FACU FAC FACU UPL	required) 2" caliper	
6			Cornus florida		FACU	2" caliper	
+NOME	C.						

0.8 ACRES AFFORESTATION REQUIRED.

#### PLANTING NOTES

- 1.) Planting stock should be 3' to 4' whips and 1 1/2 to 2 gallon container stock at a minimum. 2" caliper trees to be planted in open space lot 43.
- 2.) Only composted mulch may be used.
- 3.) Whips should be planted an average of 11 ft on center. (see random planting detail) 2" caliper trees to be planted at 20' x 20' individual spacing.



The pionting and care of frees is most successful when coordinated with the local climatic conditions. This colendor summortus some of the recommended itms harmes for basic retor totion and stress reduction activities.

6	PPROVED: HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS  PLICATION M. Lanelle HIEF, BUREAU OF HIGHWAYS  MS	6-10-97 DATE
A	PPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING HIEF, DIVISION OF LAND DEVELOPMENT -	6/12/87 DATE
ā	HIEF, DEVELOPMENT ENGINEERING DIVISION  VIC	6/11/97 DATE
DATE	REVISION	

planning • architecture • engineering • surveying  8480 Baltimore National Pike • Kliicott City, Maryland 21043 • (410)485-6105	TSA GROUP, INC.		
		 ***************************************	

owner:  HARRY AND HELEN KNISLEY  9513 GUILFORD ROAD	PROJECT: OAKHURST  (FORMERLY KNISLEY PROPERTY)  SECTION 1 - AREA 1 LOTS 1-42
COLUMBIA, MARYLAND 21046  DEVELOPER:	LOCATION:  TAX MAP 42 — PARCEL 69  6th ELECTION DISTRICT  HOWARD COUNTY, MARYLAND
SDC GROUP INC. P.O. BOX 417 ELLICOTT CITY, MARYLAND 21041	TITLE:  FOREST CONSERVATION PLAN S-94-20, P-95-28, WP-96-49
(410) 465-4244	DATE: DECEMBER 12,1996 PROJECT NO. 0527

SCALE:

AS SHOWN

DRAWING 11 OF 11

K-21-107