ROAD CONSTRUCTION PLAN WILLIAMS KNOLL SECTION I

GENERAL NOTES

- 1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST STANDARDS AND SPECIFICATIONS OF HOWARD COUNTY PLUS MSHA STANDARDS AND SPECIFICATIONS IF APPLICABLE.
- 2. THE CONTRACTOR SHALL NOTIFY THE DEPARTMENT OF PUBLIC WORKS/CONSTRUCTION INSPECTIONS DIVISION AT (410) 313-1880 AT LEAST FIVE (5) WORKING DAYS PRIOR TO THE START OF WORK.
- 3. THE CONTRACTOR SHALL NOTIFY THE FOLLOWING UTILITIES OR AGENCIES AT LEAST FIVE (5) DAYS PRIOR TO ANY EXCAVATION WORK:

MISS UTILITY
C&P TELEPHONE COMPANY
HOWARD COUNTY BUREAU OF UTILITIES
AT&T CABLE LOCATION DIVISION
BALTIMORE GAS & ELECTRIC
STATE HIGHWAY ADMINISTRATION
HOWARD COUNTY DEPT. OF PUBLIC WORKS/
CONSTRUCTION INSPECTION DIVISION

1-800-257-7777
725-9976
313-4900
393-3533
685-0123
531-5533

4. PROJECT BACKGROUND:
LOCATION: 1ST ELECTION DISTRICT, TAX MAP 38, PARCELS 229, 230, & 231
DEED REFERENCE: LIBER 3336, FOLIO 0272, LIBER 1021, FOLIO 482.
ZONING: R-SC, R-12
TOTAL TRACT AREA: 19.9 AC.±

NUMBER OF PROPOSED LOTS: 41 (33 BUILDABLE)
DATE PREVIOUS PLANS APPROVED AND DPZ REFERENCE #:
- S-95-08, MAY 5, 1995.

P-96-20, SEPTEMBER 17.1996. WP-96-69, FEBRUARY 23, 1996

- AA-96-19 - MDE PERMIT/TRACKING #:199765725

- 5. TWO FOOT CONTOUR TOPOGRAPHY AND EXISTING CONDITIONS BASED ON AN AERIAL SURVEY BY WINGS AERIAL MAPPING CO., INC. FLOWN IN 1993. DOWNS RIDGE ROAD PLANS F-96-120 WERE ALSO USED FOR EXISTING TOPOGRAPHY.
- HORIZONTAL AND VERTICAL DATUMS BASED ON MARYLAND STATE COORDINATE SYSTEM (NAD 83).

STA No. 38D5 N 558,378.5683 EL.= 193.750 E 1,386,524.3031 STA No. 38A9 N 561,056.3802 EL.= 233.455


- 7. STREET LIGHTS WILL BE REQUIRED IN THIS DEVELOPMENT IN ACCORDANCE WITH THE DESIGN MANUAL STREET LIGHT PLACEMENT AND THE TYPE OF FIXTURE AND POLE SELECTED SHALL BE IN ACCORDANCE WITH THE LATEST HOWARD COUNTY DESIGN MANUAL, VOLUME III (1993) AND AS MODIFIED BY "GUIDELINES FOR STREET LIGHTS IN RESIDENTIAL DEVELOPMENTS (JUNE 1993)." THE JUNE 1993 POLICY INCLUDES GUIDELINES FOR LATERAL AND LONGITUDINAL PLACEMENT. A MINIMUM SPACING OF 20' SHALL BE MAINTAINED BETWEEN ANY STREET LIGHT AND ANY TREE.
- 8. WATER AND SEWER ARE PUBLIC, CONTRACT #: 14-3620-D
- 9. STORMWATER MANAGEMENT CONTROL WILL BE PROVIDED BY THE METHOD OF EXTENDED DETENTION AND BIORETENTION. STORMWATER MANAGEMENT FACILITY WILL BE PRIVATE.
- 10. GEOTECHNICAL REPORT PREPARED BY HERBST/BENSON & ASSOCIATES DATED DECEMBER 5, 1996.
- 11. ONE (1) 150 WATT HPS VAPOR PENDANT FIXTURE (CUT-OFF) TO BE MOUNTED ON BG&E POLE #_____USING A 20' ARM. DIRECT ARM TOWARDS CENTER OF INTERSECTION.
 #1 ABEL ST. STA 0+40, 30' LEFT ±
 FOUR (4) STREET LIGHTS: 100 WATT "TRADITIONAIRE" POST TOP
 FIXTURE MOUNTED ON 14' BLACK FIBERGLASS POLE AT THE FOLLOWING LOCATIONS:

#2 ABEL ST. STA 3+00, 15' RIGHT ±
#3 ABEL ST. STA 5+95, 15' RIGHT ±
#4 ABEL ST. STA 9+86, 15' RIGHT ±

#5 ABEL ST. STA 11+87, 16' LEFT ±

- 12. FLOODPLAIN DELINEATION BASED ON STUDY BY MILDENBERG, BOENDER & ASSOC. DATED JUNE 26, 1996, AND APPROVED SEPTEMBER 26, 1996.
- 13. EXISTING UTILITIES LOCATIONS ARE BASED ON AS-BUILT DRAWINGS ON RECORD AT HOWARD COUNTY.
- 14. TRAFFIC CONTROL DEVICES, MARKINGS, AND SIGNING SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD). ALL STREET AND REGULATORY SIGNS SHALL BE IN PLACE PRIOR TO THE PLACEMENT OF ANY ASPHALT.
- 15. HOUSES NOT CONTROLED BY THE SWM POND WILL HAVE DRY WELLS AT SDP STAGE.
- 16. COMPACTION IN FILL AREAS TO BE 95% DETERMINED PER AASHTO T-180.
- 17. SEE F-96-120 FOR THE DOWNS RIDGE (ADJACENT-P197) ROAD PLANS.
- 18. CONTRACTOR TO VERIFY THE LOCATION OF ALL EXISTING UTILITIES ON SITE PRIOR TO COMMENSING CONSTRUCTION.
- 19. THE USE OF 25 MPH DESIGN SPEED FOR ABEL STREET APPROVED BY DEVELOPMENT ENGINEERING DIVISIONON ON 2/23/96
- 20. FOREST CONSERVATION EASEMENT(S) HAS BEEN ESTABLISHED TO FULFILL THE REQUIREMENTS OF SECTION 16.1200 OF HOWARD COUNTY FOREST CONSERVATION ACT. NO CLEARING, GRADING, OR CONSTRUCTION IS PERMITTED WITHIN THE FOREST CONSERVATION EASEMENT, EXCEPT AS SHOWN ON AN APPROVED ROAD CONSTRUCTION DRAWING OR SITE DEVELOPMENT PLAN. HOWEVER, FOREST MANAGEMENT PRACTICES AS DEFINED IN THE DEED OR CONSERVATION EASEMENT ARE ALLOWED.


FIRST ELECTION DISTRICT HOWARD COUNTY, MARYLAND



VICINITY MAP

SCALE: 1'=1000'

SHEET INDEX TITLE SHEET ROAD PLANS AND PROFILES ROAD PLANS AND PROFILES GRADING AND SEDIMENT CONTROL PLAN GRADING AND SEDIMENT CONTROL PLAN EROSION AND SEDIMENT CONTROL NOTES & DETAILS STORM DRAIN PROFILES STORM DRAIN PROFILES STORMWATER MANAGEMENT DETAILS & PROFILES STORMWATER MANAGEMENT DETAILS & PROFILES STORMWATER MANAGEMENT DETAILS & PROFILES STORMWATER MANAGEMENT SPECIFICATIONS 13 LANDSCAPE PLAN LANDSCAPE PLAN DRAINAGE AREA MAP FOREST CONSERVATION AND REFORESTATION PLAN



<u>DEVELOPER</u>

JNSD, LC 5570 STERRETT PLACE, SUITE 201 COLUMBIA , MARYLAND 21044 (410) 997-3815, (301) 596-3877

	P.E. NO.:
SIGNATURE	DATE:
ONSITE INSPECTIONS AND MATE CONSTRUCTION. THE ONSITE IN ARE THOSE INSPECTIONS AND TOO COMMONLY ACCEPTED ENGINEER IMPLY A GUARANTEE BY THE EIRELIEVE ANY OTHER PARTY FROM	DECLARE A PROFESSIONAL OPINION BASED UPON RIAL TESTS WHICH ARE CONDUCTED DURING ISPECTIONS AND MATERIAL TESTS TESTS DEEMED SUFFICIENT AND APPROPRIATE RING STANDARDS. CERTIFY DOES NOT MEAN OR NIGNEER NOR DOES AND ENGINEER'S CERTIFICATION DIM MEETING REQUIREMENTS IMPOSED BY CONTRACT, INCLUDING MEETING COMMONLY ACCEPTED
BY THE DEVELOPER:	
ACCORDING TO THESE PLANS, A THE CONSTRUCTION PROJECT W DEPARTMENT OF THE ENVIRONM CONTROL OF SEDIMENT AND ER ENGAGE A REGISTERED PROFES AND PROVIDE THE HOWARD SOI PLAN OF THE POND WITHIN 30 PERIODIC ON—SITE INSPECTIONS	LOPMENT AND/OR CONSTRUCTION WILL BE DONE AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED WILL HAVE A CERTIFICATE OF ATTENDANCE AT A MENT APPROVED TRAINING PROGRAM FOR THE ROSION BEFORE BEGINNING THE PROJECT. I SHALL SIGNAL ENGINEER TO SUPERVISE POND CONSTRUCTIVIL CONSERVATION DISTRICT WITH AN "AS-BUILT" DAYS OF COMPLETION. I ALSO AUTHORIZE BY THE HOWARD SOIL CONSERVATION DISTRICT."
James of Me	ahr 10-5-97
James L. New PRINTED NAME OF DEVELOPER	Ubara 18-3-97 DATE
BY THE ENGINEER:	
NOTIFIED THE DEVELOPER THAT	HE HOWARD SOIL CONSERVATION DISTRICT. I HAVE HE/SHE MUST ENGAGE A REGISTERED PROFESSION
OF COMPLETION."	
OF COMPLETION."	AS-BUILT PLAN OF THE POND WITHIN 30 DAYS
SIGNATURE OF ENGINEER PRINTED NAME OF ENGINEER THESE PLANS HAVE BEEN REVI	EWED FOR THE HOWARD SOIL CONSERVATION SICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION
SIGNATURE OF ENGINEER PRINTED NAME OF ENGINEER THESE PLANS HAVE BEEN REVI	EWED FOR THE HOWARD SOIL CONSERVATION SICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION
SIGNATURE OF ENGINEER PRINTED NAME OF ENGINEER THESE PLANS HAVE BEEN REVII DISTRICT AND MEET THE TECHN SOIL EROSION AND SEDIMENT CO.	EWED FOR THE HOWARD SOIL CONSERVATION SICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION
CONSERVATION DISTRICT WITH OF COMPLETION." SIGNATURE OF ENGINEER PRINTED NAME OF ENGINEER THESE PLANS HAVE BEEN REVISIONSTRICT AND MEET THE TECHN SOIL EROSION AND SEDIMENT OF USDA — MATURAL RESOURCES THESE PLANS FOR SMALL PONE	DATE O / 319
CONSERVATION DISTRICT WITH OF COMPLETION." SIGNATURE OF ENGINEER PRINTED NAME OF ENGINEER THESE PLANS HAVE BEEN REVII DISTRICT AND MEET THE TECHN SOIL EROSION AND SEDIMENT OF LIBERT CONTROL MEET THE REQUIREMENT CONTR	DATE AS-BUILT PLAN OF THE POND WITHIN 30 DAYS AS-BUILT PLAN OF
CONSERVATION DISTRICT WITH OF COMPLETION." SIGNATURE OF ENGINEER PRINTED NAME OF ENGINEER THESE PLANS HAVE BEEN REVII DISTRICT AND MEET THE TECHN SOIL EROSION AND SEDIMENT OF CONTROL MEET THE REQUIREMENT OF CONTROL MEET	DATE AS-BUILT* PLAN OF THE POND WITHIN 30 DAYS DATE DATE AS-BUILT* PLAN OF THE POND WITHIN 30 DAYS DATE DATE AS-BUILT* PLAN OF THE POND WITHIN 30 DAYS DATE DATE AS-BUILT* PLAN OF THE POND WITHIN 30 DAYS AS-BUILT* PLAN OF THE POND WITHIN 30 DAYS DATE DATE AS-BUILT* PLAN OF THE POND WITHIN 30 DAYS AS
CONSERVATION DISTRICT WITH OF COMPLETION." SIGNATURE OF ENGINEER PRINTED NAME OF ENGINEER THESE PLANS HAVE BEEN REVII DISTRICT AND MEET THE TECHN SOIL EROSION AND SEDIMENT OF LIBERT CONTROL MEET THE REQUIREMENT CONTR	DATE AS-BUILT* PLAN OF THE POND WITHIN 30 DAYS AS-BUILT* PLAN OF THE POND WITHIN 30 DAYS AS-BUILT* PLAN
CONSERVATION DISTRICT WITH OF COMPLETION." SIGNATURE OF ENGINEER PRINTED NAME OF ENGINEER THESE PLANS HAVE BEEN REVII DISTRICT AND MEET THE TECHN SOIL EROSION AND SEDIMENT OF THESE PLANS FOR SMALL PONIC CONTROL MEET THE REQUIREMENT OF PROVED: DEPARTMENT OF PROV	DATE AS-BUILT* PLAN OF THE POND WITHIN 30 DAYS AS-BUILT* PLAN OF THE POND WITHIN 30 DAYS AS-BUILT* PLAN
CONSERVATION DISTRICT WITH OF COMPLETION." SIGNATURE OF ENGINEER PRINTED NAME OF ENGINEER THESE PLANS HAVE BEEN REVIED ISTRICT AND MEET THE TECHN SOIL EROSION AND SEDIMENT OF THE SEDIMENT OF THE PROPERTY	DATE EWED FOR THE HOWARD SOIL CONSERVATION HICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION SONTROL. CONSERVATION SERVICE D. CONSTRUCTION, SOIL EROSION AND SEDIMENT INTS OF THE HOWARD SOIL CONSERVATION DISTRICT. LISTRICT DATE UBLIC WORKS LOCAL 10-24-97 DATE PLANNING AND ZONNING 10/30/97
CONSERVATION DISTRICT WITH OF COMPLETION." SIGNATURE OF ENGINEER PRINTED NAME OF ENGINEER THESE PLANS HAVE BEEN REVII DISTRICT AND MEET THE TECHN SOIL EROSION AND SEDIMENT OF USDA — MATURAL RESOURCES THESE PLANS FOR SMALL PONIC CONTROL MEET THE REQUIREMENT OF PROVINCE OF THE PROVIN	DATE EWED FOR THE HOWARD SOIL CONSERVATION HICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION SONTROL. CONSERVATION SERVICE D. CONSTRUCTION, SOIL EROSION AND SEDIMENT INTS OF THE HOWARD SOIL CONSERVATION DISTRICT. LISTRICT DATE UBLIC WORKS LOCAL 10-24-97 DATE PLANNING AND ZONNING 10/30/97
CONSERVATION DISTRICT WITH OF COMPLETION." SIGNATURE OF ENGINEER PRINTED NAME OF ENGINEER THESE PLANS HAVE BEEN REVIED ISTRICT AND MEET THE TECHN SOIL EROSION AND SEDIMENT OF THE SEDIMENT OF THE PROPERTY	DATE EWED FOR THE HOWARD SOIL CONSERVATION HICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION CONTROL. CONSERVATION SERVICE D. CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL. D. CONSTRUCTION, SOIL EROSION AND SEDIMENT CONTROL. DISTRICT DATE UBLIC WORKS PLANNING AND ZONNING 10/30/97

95136
illustration
S.D.
scale
date
AS SHOWN

description

9, 230 & 231, BLOCK 8

TION I, LOTS 1-41

RCEL A

HOWARD COUNTY, MARYLAND

AND BULK PAF STRICT

WILLLIAMS


FIRST ELECTION DIST

DER & ASSOC., INC.

rs Planners Surveyors

ive, Suite 202, Ellicott City, Maryland 21042

MILDENBE!
BOENDER
Engineers Plant



INC.


TAX MAP 38, P/O PARCELS 229, 230 & 231, BLOCK 8

WILLLIAMS KNOLL, SECTION I., LOTS 1-41


AND BULK PARCEL A


HOWARD COUNTY, MARYLAND


| | MILDENBERG, BOENDER & ASSOC., IN Engineers Planners Surveyors 5072 Dorsey Hall Drive, Suite 202, Ellicott City, Maryland 2



SSOC.







APPLY TO GRADED OR CLEARED AREAS NOT SUBJECT TO IMMEDIATE FURTHER DISTURBANCE WHERE A PERMANENT LONG-LIVED VEGETATIVE COVER IS NEEDED.

SEEDBED PREPARATION: LOOSEN UPPER THREE INCHES OF SOIL BY RAKING, DISKING OR OTHER ACCEPTABLE MEANS BEFORE SEEDING, IF NOT PREVIOUSLY LOOSENED.

SOIL AMENDMENTS: IN LIEU OF SOIL TEST RECOMMENDATIONS, USE ONE OF THE FOLLOWING SCHEDULES: 1) PREFERRED - APPLY 2 TONS PER ACRES DOLOMITIC LIMESTONE (92 LBS/1000 SQ.FT.) AND 600 LBS. PER ACRE 10-10-10 FERTILIZER (14 LBS/1000 SQ.FT.) BEFORE SEEDING. HARROW OR DISK INTO UPPER THREE INCHES OF SOIL. AT TIME OF SEEDING, APPLY 400 LBS. PER ACRE 30-0-0 UREAFORM FERTILIZER (9 LBS./1000 SQ.FT.). 2) ACCEPTABLE - APPLY 2 TONS PER ACRE DOLOMITIC LIMESTONE (92 LBS./1000

SQ.FT.) AND 1000 LBS. PER ACRE 10-10-10 FERTILIZER (23 LBS./1000 SQ.FT.) BEFORE SEEDING. HARROW OR DISK INTO UPPER THREE INCHES OF SOIL.

SEEDING - FOR THE PERIODS MARCH 1 THRU APRIL 30, AND AUGUST 1 THRU OCTOBER 15, SEED WITH 60 LBS. PER ACRE 1.4 LBS/1000 SQ.FT.) OF KENTUCKY 31 TALL FESCUE. FOR THE PERIOD MAY 1 THRU JULY 31, SEED WITH 60 LBS. KENTUCKY 31 TALL FESCUE PER ACRE AND 2 LOBS. PER ACRE (.05 LBS./1000 SQ.FT.) OF WEEPING LOVEGRASS. DURING THE PERIOD OF OCTOBER 16 THRU FEBRUARY 28, PROTECT SITE BY: OPTION (1) - 2 TONS PER ACRE OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING. OPTION (2) - USE SOD. OPTION (3) -SEED WITH 60 LBS./ACRE KENTUCKY 31 TALL FESCUE AND MULCH WITH 2 TONE/ACRE WELL ANCHORED STRAW.

MULCHING - APPLY 1-1/2 TO 2 TONS PER ACRE (70 TO 90 LBS./1000 SQ.FT) OF UNROTTED SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. ANCHOR MULCH IMMEDIATELY AFTER APPLICATION USING MULCH ANCHORING TOOL OR 218 GALLONS PER ACRE (5 GAL/1000 SQ.FT.) OF EMULSIFIED ASPHALT ON FLAT AREAS. ON SLOPES 8 FEET OR HIGHER, USE 348 GALLONS PER ACRE (8 GAL/1000 SQ.FT.) FOR ANCHORING.

MAINTENANCE - INSPECT ALL SEEDING AREAS AND MAKE NEEDED REPAIRS, REPLACEMENTS AND RESEEDINGS.

TEMPORARY SEEDING NOTES

APPLY TO GRADED OR CLEARED AREAS LIKELY TO BE REDISTURBED WHERE A SHORT-TERM VEGETATIVE COVER IS NEEDED. SEEDBED PREPARATION: LOOSEN UPPER THREE INCHES OF SOIL BY RAKING, DISKING OR OTHER ACCEPTABLE MEANS BEFORE SEEDING, FOR NOT PREVIOUSLY LOOSENED.

SOIL AMENDMENTS: APPLY 600 LBS. PER ACRE 10-10-10 FERTILIZER (14 LBS./1000 SQ.FT.)

SEEDING: FOR PERIODS MARCH 1 THRU APRIL 30 AND FROM AUGUST 15 THRU OCTOBER 15, SEED WITH 2-1/2 BUSHEL PER ACRE OF ANNUAL RYE (3.2 LBS./1000 SQ.FT.) FOR THE PERIOD MAY 1 THRU AUGUST 14, SEED WITH 3 LBS. PER ACRE OF WEEPING LOVEGRASS (.07 LBS./1000 SQ.FT.). FOR THE PERIOD NOVEMBER 16 THRU NOVEMBER 28, PROTECT SITE BY APPLYING 2 TONS PER ACRÉ OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING, OR USE SOD.

MULCHING: APPLY 1-1/2 TO 2 TONS PER ACRE (70 TO 90 LBS./1000 SQ.FT.) OF UNROTTED WEED FREE SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. ANCHOR MULCH IMMEDIATELY AFTER APPLICATION USING MULCH ANCHORING TOOL OR 218 GAL PER ACRE (5 GAL/1000 SQ.FT.) OF EMULSIFIED ASPHALT ON FLAT AREAS. ON SLOPES 8 FEET OR HIGHER, USE 348 GAL PER ACRE (8 GAL/1000 SQ.FT.) FOR ANCHORING.

REFER TO THE 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR ADDITIONAL RATES AND METHODS NOT COVERED.

HOWARD SOIL CONSERVATION DISTRICT STANDARD SEDIMENT CONTROL NOTES

- 1) A MINIMUM OF 48 HOURS NOTICE MUST BE GIVEN TO THE HOWARD COUNTY DEPARTMENT OF INSPECTIONS, LICENSES AND PERMITS, SEDIMENT CONTROL DIVISION PRIOR TO THE START OF NAY CONSTRUCTION, (313-1855).
- ALL VEGETATIVE AND STRUCTURAL PRACTICES ARE TO BE INSTALLED ACCORDING TO THE PROVISIONS OF THIS PLAN AND ARE TO BE IN CONFORMANCE WITH THE MOST CURRENT "MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL", AND REVISIONS THERETO.
- FOLLOWING INITIAL SOIL DISTURBANCE OR REDISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN: A) 7 CALENDAR DAYS FOR ALL PERIMETER SEDIMENT CONTROL STRUCTURES, DIKES, PERIMETER SLOPES AND ALL SLOPES GREATER THAN 3:1, B) 14 DAYS AS TO ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE.
- ALL SEDIMENT TRAPS/BASINS SHOWN MUST BE FENCED AND WARNING SIGNS POSTED AROUND THEIR PERIMETER IN ACCORDANCE WITH VOL. 1, CHAPTER 12, OF THE HOWARD COUNTY DESIGN MANUAL, STORM DRAINAGE.
- ALL DISTURBED AREAS MUST BE STABILIZED WITHIN THE TIME PERIOD SPECIFIED ABOVE IN ACCORDANCE WITH THE 1991 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR PERMANENT SEEDING (SEC.51), SOD (SEC. 54). TEMPORARY SEEDING (SEC. 50) AND MULCHING (SEC.52). TEMPORARY STABILIZATION WITH MULCH ALONE CAN ONLY BE DONE WHEN RECOMMENDED SEEDING DATES DO NOT ALLOW FOR PROPER GERMINATION AND ESTABLISHMENT OF GRASSES.
- ALL SEDIMENT CONTROL STRUCTURES ARE TO REMAIN IN PLACE AND ARE TO BE MAINTAINED IN OPERATIVE CONDITION UNTIL PERMISSION FOR THEIR REMOVAL HAS BEEN OBTAINED FROM THE HOWARD
- 7) SITE ANALYSIS: ___ ACRES TOTAL AREA OF SITE: AREA DISTURBED: ACRES AREA TO BE ROOFED OR PAVED AREA TO BE VEGITATIVELY STABILIZED . ACRES 16,500 CU. YDS. 16,500 CU. YDS. TOTAL CUT TOTAL FILL TOTAL WASTE/BORROW AREA LOCATION
- ANY SEDIMENT CONTROL PRACTICE WHICH IS DISTURBED BY GRADING ACTIVITY FOR PLACEMENT OF UTILITIES MUST BE REPAIRED ON THE SAME DAY OF DISTURBANCE.
- 9) ADDITIONAL SEDIMENT CONTROL MUST BE PROVIDED, IF DEEMED NECESSARY BY THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR. 10) ON ALL SITES WITH DISTURBED AREAS IN EXCESS OF 2 ACRES, APPROVAL OF THE INSPECTION AGENCY
- SHALL BE REQUESTED UPON COMPLETION OF INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS, BUT BEFORE PROCEEDING WITH ANY OTHER EARTH DISTURBANCE OR GRADING. OTHER BUILDING OR GRADING INSPECTION APPROVALS MAY NOT BE AUTHORIZED UNTIL THIS INITIAL APPROVAL BY THE INSPECTION AGENCY IS MADE.
- 11) TRENCHES FOR THE CONSTRUCTION OF UTILITIES IS LIMITED TO THREE PIPE LENGTHS OR THAT WHICH CAN BE BACK FILLED AND STABILIZED WITHIN ONE WORKING DAY, WHICHEVER IS SHORTER.

SEQUENCE OF CONSTRUCTION

1. OBTAIN GRADING PERMIT.

2. CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE. (1 DAYS)
3. CLEAR AND GRUB AREAS SURROUNDING SEDIMENT CONTROL FEATURES. (2 DAYS) 4. CONSTRUCT PERMANENT STORMWATER MANAGEMENT POND AND SEDIMENT BASIN TO TEMPORARY GRADES TRAP AND STABILIZE USING TEMPORARY SEEDING METHOD.

(5 DAYS) 5. BLOCK THE TWO 2.5' WIERS AT SWM POND RISER. (1 DAY)

- 6. CONSTRUCT SILT FENCE AND EARTH DIKES, STABILIZE EARTH DIKES WITH TEMPORARY SEEDING. (3 DAYS)
- 7. INSTALL FOREST PROTECTION DEVICES (FOR MAINTENANCE AND INSPECTION SEE FOREST CONSERVATION SHEET). (1 DAYS) 7. CLEAR SITE PER LIMIT INDICATED PLEASE NOTE THAT NO CLEARING IS TO
- BE DONE UNTILL THE SEDIMENT CONTROL MEASURES IN F-97-154 HAVE BEEN 8. CONSTRUCT SITE TO GRADES INDICATED ON THE PLANS. CONSTRUCT
- STORM DRAIN SYSTEM, DRAINING TO SWM POND, AND UTILITIES. (14 DAYS)
- 9. CONSTRUCT REMAINDER OF STORM DRAIN SYSTEM. (15 DAY) 11. RECONSTRUCT OUTLET OF SEDIMENT BASIN TO CONNECT TO STORM
- DRAIN SYSTEM. (1 DAY) 12. UPON STABILIZATION OF GRADED AREAS, ALL ACCUMULATED SEDIMENT
- SHALL BE REMOVED FROM THE STORM DRAIN SYSTEM. (1 DAY) 13. DURING CONSTRUCTION, SEDIMENT SHALL BE REMOVED FROM THE SEDIMENT TRAPS AND STORMWATER MANAGEMENT POND WHEN THEIR
- CLEANOUT ELEVATIONS HAVE BEEN REACHED. 14. STABILIZE ALL RIGHT OF WAY AREAS WITH PERMANENT SEEDING. (1 DAY)
- 15. INSPECT ALL SEDIMENT CONTROL DEVICES DAILY AND AFTER EACH RAINFALL, REPAIR AS NECESSARY.
- 16. WHEN ALL CONTRIBUTING AREAS TO SEDIMENT CONTROL DEVICES HAVE BEEN PERMANENTLY STABILIZED, AND AFTER THE APPROVAL OF THE INSPECTOR , REMOVE SEDIMENT CONTROL DEVICES, GRADE AREAS DISTURBED, AND PROVIDE PERMANENT SEED AND MULCH AND CONSTRUCT
- 17. CONTRACTOR SHALL REMOVE SEDIMENT AND FLUSH STORM DRAIN SYSTEM AT END OF CONSTRUCTION PERIOD. (1 DAY)

POND TO FINAL GRADE. (1 DAY)

MAX. DRAINAGE AREA = 1/4 ACRE

- 18. CONSTRUCTOR SHALL DEWATER THE STORMWATER MANAGEMENT POND AND REMOVE ACCUMULATED SEDIMENTS. REPLACE THE PERFORATED PIPES SERVING AS DEWATERING DEVICES AND RECONSTRUCT THE RISER AS PER THE PLANS. (1 DAY)
- 18. FOLLOWING INITIAL SOIL DISTURBANCE OR REDISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN A.) 7 CALENDAR DAYS FOR ALL PERIMETER SLOPES AND
- GREATER THAN 3:1 B.) 14 DAYS FOR ALL OTHER DISTURBED GRADED AREAS ON THE PROJECT SITE.

DETAIL 23C - CURB INLET PROTECTION (COG OR COS INLETS:

. Attach a continuous piece of wire mesh (30° minimum width by throat length plus

4") to the 2" x 4" welr (measuring throat length plus 2") as shown on the standard

2. Place a continuous piece of Geotextile Class E the same dimensions as the wire mesh over the wire mesh and securely attach it to the 2" x 4" weir.

3. Securely notil the 2° X 4° weir to a 9° long vertical spacer to be located between the weir and the inlet face (max. 4° apart).

4. Place the assembly against the inlet throat and nail (minimum 2' lengths of $2^{\circ} \times 4^{\circ}$ to the top of the weir at spacer locations). These $2^{\circ} \times 4^{\circ}$ anchors shall extend across the inlet top and be held in place by sandbags or alternate weight.

5. The assembly shall be placed so that the end spacers are a minimum 1' beyond

6. Form the 1/2 * x 1/2 * wire mesh and the geotextile fabric to the concrete gutter and

DETAIL 12 - EMERGENCY SPILLWAY

n= manning's Coefficient of Roughness.

Hp= Difference in elevation between the crest of the emergency spillway and the control section and water surface of the reservoir, in feet.

b= Bottom width of emergency spillway at the control section, in feet. (8' Minimum)

0= Total discharge, in cfs.

Y= Velocity, in feet per second, that will exist in the channel below the control section, at design Q, if constructed to slope (S) that is shown. (Ymax = 5 fps.)

S= Flottest slope (S), in X, allowable for the channel below the control section.

X= Minimum length of the channel below the control section, in feet.

Hinimum Z = 2

1. For a given Hp a decrease in the exit slope from S as given in the table decreases the spillway discharge but increasing the exit slope from S does not increase the discharge. If an exit slope (Se) steeper than S is used, then the velocity (Ve) in the exit channel will increase according to the following

2. Data to the right of the heavy vertical lines on Table 14 should be used with caution, as the resulting sections will be either poorly proportioned or have velocities in excess of 5 ft./sec.

Minimum Z = 2

Ve = V (---)

FLOV

PROFILE ALONG CENTERLINE

DF EMERGENCY SPILLVAY

CROSS SECTION OF EMERGENCY

PAGE MARYLAND DEPARTMENT OF ENVIRONMEN
C - 10 - 20 VATER MANAGEMENT ADMINISTRATION

- E.S.CREST=136.0'

against the face of the curb on both sides of the injet. Place clean 3/4 " x 1 1/2

stone over the wire mesh and geotextile in such a manner to prevent water from

7. This type of protection must be inspected frequently and the filter cloth


8. Assure that storm flow does not bypass the inlet by installing a temporary

entering the injet under or ground the geotextile.

PLAN VIEW OF EMERGENCY

NOTES

OF 2" X 4"



DETAIL 15 - RISER BASE DETAIL

Construction Specifications

The riser shall have a base attached with a watertight connection and shall have sufficient weight to prevent flotation of the riser. Two approved bases for risers 10° or less in height are:

2. A 1/4' minimum thickness steel plate attached to the riser by a continuous weld around the circumference of the riser to form a watertight connection. The plate shall have 2' of stone, gravel, or compacted earth placed on it to prevent flotation. In either case, each side of the square base shall be

Note: For risers greater than ten feet high computations shall be made to design a base which will prevent floatation. The minimum factor of safety shall be 1.20 (downward forces = 1.20 x upward forces).

1. A concrete base 18' thick with the riser embedded 9' in the base.


FLOY

⁻179.50

4. Stone - crushed aggregate (2" to 3") or reclaimed or recycled concrete equivalent shall be placed at least 6" deep over the length and width of the

5. Surface Vater - all surface water flowing to or diverted toward construction entrances shall be piped through the entrance, maintaining positive drainage. Pipe installed through the stabilized construction entrance shall be protected with a nountable bern with 5:1 slopes and a minimum of 6° of stone over the pipe. Pipe has to be sized according to the drainage. When the SCE is located at a high spot and has no drainage to convey a pipe will not be necessary. Pipe should be sized

6. Location - A stabilized construction entrance shall be located at every point where construction traffic enters or leaves a construction site. Vehicles leaving the site must travel over the entire length of the stabilized construction entrance. U.S. DEPARTMENT OF AGRICULTURE PAGE MARYLAND DEPARTMENT OF ENVIRONMENT SUIL CONSERVATION SERVICE F - 17 - 3 VATER MANAGEMENT ADMINISTRATION



DETAIL 1 - EARTH DIKE

b | 2:1 SLOPE OR FLATTER

DETAIL 14 - TYPICAL ANTI-SEEP COLLARS

COLLAR VELDED IN PLACE ON BARREL SECTION

ANTI-SEEP COLLAR DESIGN

COLLAR FOR FLANGE JOINT PIPE


USE "MASTIK" OR EQUIVALENT BETVEEN PLATE AND FRAME

U.S. DEPARTMENT OF AGRICULTURE

FENCE POST SPACING SHALL NOT EXCEED 1 CENTER TO CENTER

__FILTER CLOTH-_

INDED FILTER CLOTH 8*





2. Chain link fence shall be fastened securely to the fence posts with wire ties. The lower tension wire, brace and truss rods, drive anchors and post caps are not Construction Specifications . Fence posts shall be a minimum of 36' long driven 16' minimum into the

 Filter cloth shall be fastened securely to the chain link fence with ties spaced every 24° at the top and mid section. ground. Wood posts shall be $11/2^{\circ} \times 11/2^{\circ}$ square (minimum) cut, or $13/4^{\circ}$ diameter (minimum) round and shall be of sound quality hardwood. Steel posts will be standard T or U section weighting not less than 1.00 pond per linear

Geotextile shall be fastened securely to each fence post with wire ties or staples at top and hid-section and shall neet the following requirements Tensile Strength Tensile Modulus 50 lbs/in (min.) 20 lbs/in (min.) Flow Rate 0.3 gal ft*/ minute (max.) Test: NSNT 322

Where ends of geotextile fabric come together, they shall be overlapped, olded and stapled to prevent sediment bype 4. Silt Fence shall be inspected after each rainfall event and naintained when U.S. DEPARTMENT OF AGRICULTURE STILL CONSERVATION SERVICE PAGE HARYLAND DEPARTMENT OF ENVIRONMENT E - 15 - 3 VATER MANAGEMENT ADMIDISTRATION





4. ROOT DAMAGE SHOULD BE AVOIDED. 5. PROTECTIVE SIGNAGE MAY ALSO BE USED. 6. DEVICE SHOULD BE MAINTAINED THROUGHOUT CONSTRUCTION.

SPECIFICATIONS.

DATE: ____ CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ONSITE INSPECTIONS AND MATERIAL TESTS WHICH ARE CONDUCTED DURING CONSTRUCTION. THE ONSITE INSPECTIONS AND MATERIAL TESTS ARE THOSE INSPECTIONS AND TESTS DEEMED SUFFICIENT AND APPROPRIATE COMMONLY ACCEPTED ENGINEERING STANDARDS. CERTIFY DOES NOT MEAN OR IMPLY A GUARANTEE BY THE ENGINEER NOR DOES AND ENGINEER'S CERTIFICATION RELIEVE ANY OTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING COMMONLY ACCEPTED INDUSTRY PRACTICES.

AS-BUILT CERTIFICATION

I HEREBY CERTIFY THAT THE FACILITY SHOWN ON THIS PLAN WAS CONSTRUCTED AS SHOWN ON THE "AS-BUILT" PLANS AND MEETS THE APPROVED PLANS AND

BY THE DEVELOPER: "I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT." JNSD,LC

SIGNATURE OF DEVELOPER PRINTED NAME OF DEVELOPER

BY THE ENGINEER: "I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS 10/3/97

SIGNATURE OF ENGINEER HILL MAT THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION

APPROVED: DEPARTMENT OF PLANNING AND ZONNING 10/30/97 Cendy Hanutter CHIEF, DIVISION OF LAND DEVELOPMENT CHIEF, DEVELOPMENT ENGINEERING DIVISION

DETAIL 5 - RIP-RAP INFLOW PROTECTION RRP PERSPECTIVE VIEW Construction Specifications 1. Rip-rap lined inflow channels shall be 1' in depth, have a trapezoidal

cross section with 2:1 or flatter side slopes and 3' (min.) botton width. The channel shall be lined with 4' to 12' rip- rap to a depth of 18'. 2. Filter cloth shall be installed under all rip-rap. Filter cloth shall

3. Entrance and exit sections shall be installed as shown on the detail

4. Rip-rap used for the lining may be recycled for permanent outlet protection if the basin is to be converted to a stormwater management 5. Gabion Inflow Protection may be used in lieu of Rip-rap Inflow

6. Rip-rap should blend into existing ground. 7. Rip-rap Inflow Protection shall be used where the slope is between 4:1 and 18:1, for slopes flatter than 10:1 use Earth Dike or Temporary Smale

PAGE 8 - 6 - 2 MARYLAND DEPARTMENT OF ENVIRONMENT VATER MANAGEMENT ADMINISTRATION

DIKE A a-DIKE HEIGHT 18" 6-DIKE WIDTH V V V V V V V c-FLOW WIDTH 4-FLOW DEPTH STANDARD SYMBOL A-2 B-3 -·-/-·-. Seed and cover with straw mulch 2. Seed and cover with Erosino Control Matting or line with sod.

3. 4° - 7" stone or recycled concrete equivalent pressed into 1. All temporary earth dikes shall have uninterrupted positive grade to an outlet. Spot elevations may be necessary for grades less than 1%. 2. Runoff diverted from a disturbed area shall be conveyed to a sediment 3. Runoff diverted from an undisturbed area shall outlet directly into an undisturbed, stabilized area at a non-erosive velocity. 4. All trees, brush, stumps, obstructions, and other objectional material shall be removed and disposed of so as not to interfere with the proper The dike shall be excavated or shaped to line, grade and cross section as required to meet the criteria specified herein and be free of bank projections or other irregularities which will impede normal flow.

6. Fill shall be compacted by earth moving equipment

7. All earth removed and not needed for construction shall be placed so that it will not interfere with the functioning of the dike.

8. inspection and maintenance must be provided periodically and after U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE PAGE MARYLAND DEPARTMENT OF ENVIRONMENT A -- 1 - 6 VATER MANAGEMENT ADMINISTRATION <u>OWNERS</u> PARCEL 229

JNSD, LC

PARCELS 230 & 231 5570 STERRETT PLAC, SUITE 201 MICHAEL & SUSAN MULLENDORE COLUMBIA, MARYLAND 21044 6154 HANOVER ROAD (410) 997-3815, (301) 596-3877 HANOVER, MARYLAND 21076

JNSD, LC

DEVELOPER

5570 STERRETT PLAC, SUITE 201 COLUMBIA, MARYLAND 21044 (410) 997-3815, (301) 596-3877

V RG,

DETAIL

, E

231 L0.

公田

SON

0

X MAP 38, WILLLIAM,

LLL, BÜL.

AND

EROSIO

PERMANENT SEEDING NOTES

SEEDING. HARROW OR DISK INTO UPPER THREE INCHES OF SOIL.

APPLY TO GRADED OR CLEARED AREAS NOT SUBJECT TO IMMEDIATE FURTHER DISTURBANCE WHERE A PERMANENT LONG-LIVED VEGETATIVE COVER IS NEEDED.

SEEDBED PREPARATION: LOOSEN UPPER THREE INCHES OF SOIL BY RAKING, DISKING OR OTHER ACCEPTABLE MEANS BEFORE SEEDING, IF NOT PREVIOUSLY LOOSENED.

SOIL AMENDMENTS: IN LIEU OF SOIL TEST RECOMMENDATIONS, USE ONE OF THE FOLLOWING SCHEDULES: PREFERRED - APPLY 2 TONS PER ACRES DOLOMITIC LIMESTONE (92 LBS/1000 SQ.FT.) AND 600 LBS. PER ACRE 10-10-10 FERTILIZER (14 LBS/1000 SQ.FT.) BEFORE SEEDING. HARROW OR DISK INTO UPPER THREE INCHES OF SOIL. AT TIME OF SEEDING, APPLY 400 LBS. PER ACRE 30-0-0 UREAFORM FERTILIZER (9 LBS./1000 SQ.FT.). ACCEPTABLE - APPLY 2 TONS PER ACRE DOLOMITIC LIMESTONE (92 LBS./1000 SQ.FT.) AND 1000 LBS. PER ACRE 10-10-10 FERTILIZER (23 LBS./1000 SQ.FT.) BEFORE

SEEDING - FOR THE PERIODS MARCH 1 THRU APRIL 30, AND AUGUST 1 THRU OCTOBER 15, SEED WITH 60 LBS. PEF ACRE 1.4 LBS/1000 SQ.FT.) OF KENTUCKY 31 TALL FESCUE. FOR THE PERIOD MAY 1 THRU JULY 31, SEED WITH 60 LBS. KENTUCKY 31 TALL FESCUE PER ACRE AND 2 LOBS. PER ACRE (.05 LBS./1000 SQ.FT.) OF WEEPING LOVEGRASS. DURING THE PERIOD OF OCTOBER 16 THRU FEBRUARY 28, PROTECT SITE BY: OPTION (1) - 2 TONS PER ACRE OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING. OPTION (2) - USE SOD. OPTION (3) -SEED WITH 60 LBS./ACRE KENTUCKY 31 TALL FESCUE AND MULCH WITH 2 TONE/ACRE WELL ANCHORED STRAW.

MULCHING - APPLY 1-1/2 TO 2 TONS PER ACRE (70 TO 90 LBS./1000 SQ.FT) OF UNROTTED SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. ANCHOR MULCH IMMEDIATELY AFTER APPLICATION USING MULCH ANCHORING TOOL OR 218 GALLONS PER ACRE (5 GAL/1000 SQ.FT.) OF EMULSIFIED ASPHALT ON FLAT AREAS. ON SLOPES 8 FEET OR HIGHER, USE 348 GALLONS PER ACRE (8 GAL/1000 SQ.FT.) FOR ANCHORING.

MAINTENANCE - INSPECT ALL SEEDING AREAS AND MAKE NEEDED REPAIRS, REPLACEMENTS AND RESEEDINGS.

TEMPORARY SEEDING NOTES

APPLY TO GRADED OR CLEARED AREAS LIKELY TO BE REDISTURBED WHERE A SHORT-TERM VEGETATIVE COVER IS NEEDED. SEEDBED PREPARATION: LOOSEN UPPER THREE INCHES OF SOIL BY RAKING, DISKING OR OTHER ACCEPTABLE MEANS BEFORE SEEDING, FOR NOT PREVIOUSLY LOOSENED.

SOIL AMENDMENTS: APPLY 600 LBS. PER ACRE 10-10-10 FERTILIZER (14 LBS./1000 SQ.FT.)

SEEDING: FOR PERIODS MARCH 1 THRU APRIL 30 AND FROM AUGUST 15 THRU OCTOBER 15, SEED WITH 2-1/2 BUSHEL PER ACRE OF ANNUAL RYE (3.2 LBS./1000 SQ.FT.) FOR THE PERIOD MAY 1 THRU AUGUST 14. SEED WITH 3 LBS. PER ACRE OF WEEPING LOVEGRASS (.07 LBS./1000 SQ.FT.). FOR THE PERIOD NOVEMBER 16 THRU NOVEMBER 28, PROTECT SITE BY APPLYING 2 TONS PER ACRE OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING, OR USE SOD.

MULCHING: APPLY 1-1/2 TO 2 TONS PER ACRE (70 TO 90 LBS./1000 SQ.FT.) OF UNROTTED WEED FREE SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. ANCHOR MULCH IMMEDIATELY AFTER APPLICATION USING MULCH ANCHORING TOOL OR 218 GAL PER ACRE (5 GAL/1000 SQ.FT.) OF EMULSIFIED ASPHALT ON FLAT AREAS. ON SLOPES 8 FEET OR HIGHER, USE 348 GAL PER ACRE (8 GAL/1000 SQ.FT.) FOR ANCHORING.

REFER TO THE 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR ADDITIONAL RATES AND METHODS NOT COVERED.

HOWARD SOIL CONSERVATION DISTRICT STANDARD SEDIMENT CONTROL NOTES

- 1) A MINIMUM OF 48 HOURS NOTICE MUST BE GIVEN TO THE HOWARD COUNTY DEPARTMENT OF INSPECTIONS, LICENSES AND PERMITS, SEDIMENT CONTROL DIVISION PRIOR TO THE START OF NAY CONSTRUCTION, (313-1855).
- 2) ALL VEGETATIVE AND STRUCTURAL PRACTICES ARE TO BE INSTALLED ACCORDING TO THE PROVISIONS OF THIS PLAN AND ARE TO BE IN CONFORMANCE WITH THE MOST CURRENT "MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL", AND REVISIONS THERETO.
- 3) FOLLOWING INITIAL SOIL DISTURBANCE OR REDISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN: A) 7 CALENDAR DAYS FOR ALL PERIMETER SEDIMENT CONTROL STRUCTURES, DIKES, PERIMETER SLOPES AND ALL SLOPES GREATER THAN 3:1, B) 14 DAYS AS TO ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE.
- 4) ALL SEDIMENT TRAPS/BASINS SHOWN MUST BE FENCED AND WARNING SIGNS POSTED AROUND THEIR PERIMETER IN ACCORDANCE WITH VOL. 1, CHAPTER 12, OF THE HOWARD COUNTY DESIGN MANUAL, STORM DRAINAGE
- 5) ALL DISTURBED AREAS MUST BE STABILIZED WITHIN THE TIME PERIOD SPECIFIED ABOVE IN ACCORDANCE WITH THE 1991 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR PERMANENT SEEDING (SEC.51). SOD (SEC. 54), TEMPORARY SEEDING (SEC. 50) AND MULCHING (SEC.52). TEMPORARY STABILIZATION WITH MULCH ALONE CAN ONLY BE DONE WHEN RECOMMENDED SEEDING DATES DO NOT ALLOW FOR PROPER GERMINATION AND ESTABLISHMENT OF GRASSES.
- 6) ALL SEDIMENT CONTROL STRUCTURES ARE TO REMAIN IN PLACE AND ARE TO BE MAINTAINED IN OPERATIVE CONDITION UNTIL PERMISSION FOR THEIR REMOVAL HAS BEEN OBTAINED FROM THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR.
- 7) SITE ANALYSIS: TOTAL AREA OF SITE: ____ ACRES AREA DISTURBED: AREA TO BE ROOFED OR PAVED AREA TO BE VEGITATIVELY STABILIZED ____ ACRES TOTAL CUT 16,500 CU. YDS. TOTAL FILL TOTAL WASTE/BORROW AREA LOCATION
- 8) ANY SEDIMENT CONTROL PRACTICE WHICH IS DISTURBED BY GRADING ACTIVITY FOR PLACEMENT OF UTILITIES MUST BE REPAIRED ON THE SAME DAY OF DISTURBANCE.
- 9) ADDITIONAL SEDIMENT CONTROL MUST BE PROVIDED, IF DEEMED NECESSARY BY THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR.
- 10) ON ALL SITES WITH DISTURBED AREAS IN EXCESS OF 2 ACRES, APPROVAL OF THE INSPECTION AGENCY SHALL BE REQUESTED UPON COMPLETION OF INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS. BUT BEFORE PROCEEDING WITH ANY OTHER EARTH DISTURBANCE OR GRADING. OTHER BUILDING OR GRADING INSPECTION APPROVALS MAY NOT BE AUTHORIZED UNTIL THIS INITIAL APPROVAL BY THE INSPECTION AGENCY IS MADE.
- 11) TRENCHES FOR THE CONSTRUCTION OF UTILITIES IS LIMITED TO THREE PIPE LENGTHS OR THAT WHICH CAN BE BACK FILLED AND STABILIZED WITHIN ONE WORKING DAY, WHICHEVER IS SHORTER.

SEQUENCE OF CONSTRUCTION

1. OBTAIN GRADING PERMIT.

2. CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE. (1 DAYS) 3. CLEAR AND GRUB AREAS SURROUNDING SEDIMENT CONTROL FEATURES. (2 DAYS) 4. CONSTRUCT PERMANENT STORMWATER MANAGEMENT POND AND SEDIMENT BASIN TO TEMPORARY GRADES TRAP AND STABILIZE USING TEMPORARY SEEDING METHOD. DETAIL 15 - RISER BASE DETAIL

Construction Specifications

The riser shall have a base attached with a watertight connection and shall have sufficient weight to prevent flotation of the riser. Two approved bases for risers 10° or less in height are:

2. A 1/4' minimum thickness steel plate attached to the riser by a continuous weld around the circumference of the riser to form a watertight connection. The plate shall have 2' of stone, gravel, or compacted earth placed on it to prevent flotation. In either case, each side of the square base shall be

Note: For risers greater than ten feet high computations shall be made to design a base which will prevent floatation. The minimum factor of safety shall be 1.20 (downward forces = 1.20 x upward forces),

1. A concrete base 18' thick with the riser embedded 9' in the base.

FLOV

DRAW-DOWN DEVICE

EXISTING PAVEMENT

EARTH FILL

PIPE AS NECESSARY

RRP

- 5. BLOCK THE TWO 2.5' WIERS AT SWM POND RISER. (1 DAY)
- 6. CONSTRUCT SILT FENCE AND EARTH DIKES, STABILIZE EARTH DIKES
- WITH TEMPORARY SEEDING. (3 DAYS) 7. INSTALL FOREST PROTECTION DEVICES (FOR MAINTENANCE AND INSPECTION SEE FOREST CONSERVATION SHEET). (1 DAYS)
- 7. CLEAR SITE PER LIMIT INDICATED PLEASE NOTE THAT NO CLEARING IS TO BE DONE UNTILL THE SEDIMENT CONTROL MEASURES IN F-97-154 HAVE BEEN INSTALLED. (10 DAYS)
- 8. CONSTRUCT SITE TO GRADES INDICATED ON THE PLANS. CONSTRUCT STORM DRAIN SYSTEM, DRAINING TO SWM POND, AND UTILITIES. (14 DAYS)
- 9. CONSTRUCT REMAINDER OF STORM DRAIN SYSTEM. (15 DAY) 11. RECONSTRUCT OUTLET OF SEDIMENT BASIN TO CONNECT TO STORM
- DRAIN SYSTEM. (1 DAY) 12. UPON STABILIZATION OF GRADED AREAS, ALL ACCUMULATED SEDIMENT
- SHALL BE REMOVED FROM THE STORM DRAIN SYSTEM. (1 DAY) 13. DURING CONSTRUCTION, SEDIMENT SHALL BE REMOVED FROM THE SEDIMENT TRAPS AND STORMWATER MANAGEMENT POND WHEN THEIR

CLEANOUT ELEVATIONS HAVE BEEN REACHED.

- 14. STABILIZE ALL RIGHT OF WAY AREAS WITH PERMANENT SEEDING. (1 DAY)
- 15. INSPECT ALL SEDIMENT CONTROL DEVICES DAILY AND AFTER EACH RAINFALL, REPAIR AS NECESSARY.
- 16. WHEN ALL CONTRIBUTING AREAS TO SEDIMENT CONTROL DEVICES HAVE BEEN PERMANENTLY STABILIZED, AND AFTER THE APPROVAL OF THE INSPECTOR , REMOVE SEDIMENT CONTROL DEVICES, GRADE AREAS DISTURBED, AND PROVIDE PERMANENT SEED AND MULCH AND CONSTRUCT POND TO FINAL GRADE. (1 DAY)
- 17. CONTRACTOR SHALL REMOVE SEDIMENT AND FLUSH STORM DRAIN SYSTEM AT END OF CONSTRUCTION PERIOD. (1 DAY)
- 18. CONSTRUCTOR SHALL DEWATER THE STORMWATER MANAGEMENT POND AND REMOVE ACCUMULATED SEDIMENTS. REPLACE THE PERFORATED PIPES SERVING AS DEWATERING DEVICES AND RECONSTRUCT THE RISER AS PER THE PLANS. (1 DAY)
- 18. FOLLOWING INITIAL SOIL DISTURBANCE OR REDISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN A.) 7 CALENDAR DAYS FOR ALL PERIMETER SLOPES AND GREATER THAN 3:1

earth or asphalt dike to direct the flow to the inlet.


PLAN VIEW OF EMERGENCY


Minimum Z = 2


Ve = V (--)

LEGEND

B.) 14 DAYS FOR ALL OTHER DISTURBED GRADED AREAS ON







DETAIL 14 - TYPICAL ANTI-SEEP CULLARS

COLLAR VELDED IN PLACE ON BARREL SECTION


ANTI-SEEP COLLAR DESIGN

COLLAR FOR FLANGE JOINT PIPE

USE 'MASTIK' (
EQUIVALENT
BETWEEN PLATE
AND FRAME

U.S. DEPARTMENT OF AGRICULTURE

TO JOINT 1 THIOL OT THIOLOGY



PARCEL 229 JNSD, LC


5570 STERRETT PLAC, SUITE 201

(410) 997–3815, (301) 596–3877

COLUMBIA, MARYLAND 21044

PARCELS 230 & 231 6154 HANOVER ROAD HANOVER, MARYLAND 21076

DEVELOPER MICHAEL & SUSAN MULLENDORE 5570 STERRETT PLAC, SUITE 201 COLUMBIA, MARYLAND 21044 (410) 997-3815, (301) 596-3877 2 CHIEF, DEVELOPMENT ENGINEERING DIVISION &



AND ANTI-VURTEX DEVICE

ISOMETRIC VIEW

SUPPORT BAR SIZE 3/4 DIAMETER MINIMUM, BARS ARETO BE VELDET TO THE TOP OF THE RISER OR ATTACHED BY STRAPS TO THE TOP OF THE RISER

DETAIL 22 - SILT FENCE

(minimum) round and shall be of sound quality hardwood. Steel posts will be

2. Geotextile shall be fastened securely to each fence post with wire ties

or staples at top and mid-section and shall meet the following requirement:

50 lbs/in (min.)

20 (bs/in (min.)

. Where ends of geotextile fabric come together, they shall be overlapped,

4. Silt Fence shall be inspected after each rainfall event and maintained when

0.3 gal ft*/ minute (max.) Test: MSMT 322

SECTION A-A

PERSPECTIVE VIEW

STAPLE/


Tensile Modulus

Filtering Efficiency 75% (min.)

folded and stapled to prevent sediment bypass

JOINING TWO ADJACENT SILT

FENCE SECTIONS



AS-BUILT CERTIFICATION I HEREBY CERTIFY THAT THE FACILITY SHOWN ON THIS PLAN WAS CONSTRUCTED AS SHOWN ON THE "AS-BUILT" PLANS AND MEETS THE APPROVED PLANS AND P.E. NO.: SIGNATURE DATE: ____ CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ONSITE INSPECTIONS AND MATERIAL TESTS WHICH ARE CONDUCTED DURING

CONSTRUCTION. THE ONSITE INSPECTIONS AND MATERIAL TESTS
ARE THOSE INSPECTIONS AND TESTS DEEMED SUFFICIENT AND APPROPRIATE COMMONLY ACCEPTED ENGINEERING STANDARDS. CERTIFY DOES NOT MEAN OR IMPLY A GUARANTEE BY THE ENGINEER NOR DOES AND ENGINEER'S CERTIFICATION RELIEVE ANY OTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING COMMONLY ACCEPTED INDUSTRY PRACTICES.

BY THE DEVELOPER:

"I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT." JNSD,Le

SIGNATURE OF DEVELOPER Janes L. Newbarn, menter PRINTED NAME OF DEVELOPER

BY THE ENGINEER:

"I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION." 10/3/97

ATURE OF ENGINEER
L- TACOB HILL MAT THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION

CONTROL MEET THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT.

Hamittan 10/30/97

6 of 16

MILDENBI BOENDER

0 1

J

0;

10. RC

田

~ NX

OLL, BU

X MAP WILLL

INC.

SSOC.

V


स श

CON


Z

OIS

ERO



MILDENBERG, BOENDER & ASSOC





O PARC KNOL ND B STORM

MILDENBERG, BOENDER &


7 of 16

F-97-110






ASSOC.




9 of 16

FIRST ELECTION DIST STORMWATER



SSOC.

MILDENBEH BOENDER



VILLLIAMS KNOLL, SECTION I., LOTS 1-41

AND BÜLK PARCEL A.

HOWARD COUNTY, MARYLAND

STORMWATER MANAGEMENT DETAILS & PROFILES


SOENDER & ASSOC., INC.

Engineers Planners Surveyors

ey Hall Drive, Suite 202, Ellicott City, Maryland 21042

| | MILDENBE | BOENDER | BOENDER | Engineers | Plan | For 2 Dorsey | Hall Drive, Suite | Con 2006 | Part | Con 2007 | Con

10.0F 16



SSOC. MILDENBERG, BOENDER & A

PROFILES

STORMW

SITE PREPARATION

AREAS DESIGNATED FOR BORROW AREAS, EMBANKMENT, AND STRUCTURAL WORKS SHALL BE CLEARED. GRUBBED AND STRIPPED OF TOPSOIL. ALL TREES, VEGETATION, ROOTS AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED. CHANNEL BANKS AND SHARP BREAKS SHALL BE SLOPED TO NO STEEPER THAN 1:1

AREAS TO BE COVERED BY THE RESERVOIR WILL BE CLEARED OF ALL TREES, BRUSH, LOGS, RUBBISH AND OTHER OBJECTIONABLE MATERIAL UNLESS OTHERWISE DESIGNATED TO THE PLANS. TREES, BRUSH AND STUMPS SHALL BE CUT APPROXIMATELY LEVEL WITH THE GROUND SURFACE. FOR DRY STORMWATER MANAGEMENT PONDS, A MINIMUM OF A 50 FOOT RADIUS AROUND THE INLET STRUCTURE SHALL BE CLEARED.

ALL CLEARED AND GRUBBED MATERIAL SHALL BE DISPOSED OF OUTSIDE AND BELOW THE LIMITS OF THE DAM AND RESERVOIR AS DIRECTED BY THE OWNER OR HIS REPRESENTATIVE. WHEN SPECIFIED, A SUFFICIENT QUALITY OF TOPSOIL WILL BE STOCKPILED IN A SUITABLE LOCATION FOR USE ON THE EMBANKMENT AND OTHER DESIGNATED AREAS.

EARTH FILL

MATERIAL - THE FILL MATERIAL SHALL BE TAKEN FROM APPROVED DESIGNATED BORROW AREAS. IT SHALL BE FREE OF ROOTS, STUMPS, WOOD, RUBBISH, STONES GREATER THAN 6", FROZEN OR OTHER OBJECTIONABLE MATERIALS. FILL MATERIAL FOR THE CENTER OF THE EMBANKMENT AND CUT OFF TRENCH SHALL CONFORM TO UNIFIED SOIL CLASSIFICATION GC, SC, CH, OR CL. CONSIDERATION MAY BE GIVEN TO THE USE OF OTHER MATERIALS IN THE EMBANKMENT IF DESIGN AND CONSTRUCTION ARE SUPERVISED BY A GEOTECHNICAL

PLACEMENT- AREAS ON WHICH FILL IS TO BE SHALL BE SCARIFIED PRIOR TO PLACEMENT OF FILL. FILL MATERIALS SHALL BE PLACED IN MAXIMUM 8 INCH THICK (BEFORE COMPACTION) LAYERS WHICH ARE TO BE CONTINUOUS OVER THE ENTIRE LENGTH OF THE FILL. THE MOST PERMEABLE BORROW MATERIAL SHALL BE PLACED IN THE DOWNSTREAM PORTIONS OF THE EMBANKMENT. THE PRINCIPAL SPILLWAY MUST BE INSTALLED CONCURRENTLY WITH FILL PLACEMENT AND NOT EXCAVATED INTO THE EMBANKMENT.

COMPACTION- THE MOVEMENT OF AND SPREADING EQUIPMENT OVER THE FILL SHALL BE CONTROLLED SO THAT THE ENTIRE SURFACE OF EACH LIFT SHALL BE TRAVERSE BY NOT LESS THAN ONE TREAD TRACK OF THE EQUIPMENT OR COMPACTION SHALL BE ACHIEVED BY A MINIMUM OF FOUR COMPLETE PASSES OF A SHEEPSFOOT, RUBBER TIRED OR VIBRATORY ROLLER. FILL MATERIAL SHALL CONTAIN SUFFICIENT MOISTURE SUCH THAT THE REQUIRED DEGREE OF COMPACTION WILL BE OBTAINED WITH THE EQUIPMENT USED. THE FILL MATERIAL SHALL CONTAIN SUFFICIENT MOISTURE SO THAT IF FORMED INTO A BALL IT WILL NOT CRUMBLE YET NOT BE SO WET THAT WATER CAN BE SQUEEZED OUT.

WHERE A MINIMUM REQUIRED DENSITY IS SPECIFIED, IT SHALL NOT BE LESS 95% OF MAXIMUM DRY DENSITY WITH A MOISTURE CONTENT WITHIN+- 2% OF THE OPTIMUM. EACH LAYER OF FILL SHALL BE COMPACTED AS NECESSARY TO OBTAIN THAT DENSITY, AND IS TO BE CERTIFIED BY THE ENGINEER AT THE TIME OF CONSTRUCTION. ALL COMPACTION IS TO BE DETERMINED BY AASHTO METHOD T-99

CUT OFF TRENCH- THE CUFF OFF TRENCH SHALL BE EXCAVATED INTO IMPERVIOUS MATERIAL ALONG OR PARALLEL TO THE CENTERLINE OF THE EMBANKMENT AS SHOWN ON THE PLANS. THE BOTTOM WIDTH OF THE TRENCH SHALL BE GOVERNED BY THE EQUIPMENT USED FOR EXCAVATION, WITH THE MINIMUM WIDTH BEING FOUR FEET. THE DEPTH SHALL BE AT LEAST FOUR FEET BELOW EXISTING GRADE OR AS SHOWN ON THE PLANS. THE SIDE SLOPES OF THE TRENCH SHALL BE 1 TO 1 OR FLATTER. THE BACKFILL SHALL BE COMPACTED WITH CONSTRUCTION EQUIPMENT, ROLLERS, OR HAND TAMPERS TO ASSURE MAXIMUM DENSITY AND MINIMUM PERMEABILITY.

STRUCTURE BACKFILL

BACKFILL ADJACENT TO PIPES OR STRUCTURES SHALL BE OF THE TYPE AND QUALITY CONFORMING TO THAT SPECIFIED FOR THE ADJOINING FILL MATERIAL. THE FILL MATERIAL SHALL BE PLACED IN HORIZONTAL LAYERS NOT TO EXCEED FOUR INCHES IN THICKNESS AND COMPACTED BY HAND TAMPERS OR OTHER MANUALLY DIRECTED COMPACTION EQUIPMENT. THE MATERIAL NEEDS TO FILL COMPLETELY ALL SPACES UNDER AND ADJACENT TO THE PIPE. AT NO TIME DURING THE BACKFILLING OPERATION SHALL DRIVEN EQUIPMENT BE ALLOWED TO OPERATE CLOSER THAN FOUR FEET, MEASURED HORIZONTALLY, TO ANY PART OF A STRUCTURE UNDER NO CIRCUMSTANCES SHALL EQUIPMENT BE DRIVEN OVER ANY PART OF A CONCRETE FILL OF 24" OR GREATER OVER THE STRUCTURE OR PIPE.

PIPE CONDUITS

ALL PIPES SHALL BE CIRCULAR IN CROSS SECTION.

CORRUGATED METAL PIPE- ALL OF THE FOLLOWING CRITERIA SHALL APPLY FOR CORRUGATED METAL PIPE: MATERIALS- (STEEL PIPE)- THIS PIPE AND ITS APPURTENANCE SHALL BE GALVANIZED AND FULLY BITUMINOUS COATED AND SHALL CONFORM TO THE REQUIREMENTS OF AASHTO SPECIFICATION M-190 TYPE A WITH WATERTIGHT COUPLING BANDS. ANY BITUMINOUS COATING DAMAGED OR OTHERWISE REMOVED SHALL BE REPLACED WITH COLD APPLIED BITUMINOUS COATING COMPOUND. STEEL PIPES WITH POLYMERIC COATINGS SHALL HAVE A MINIMUM COATING THICKNESS OF 0.01 INCH (10 MIL) ON BOTH SIDES OF THE PIPE. THE FOLLOWING COATINGS OR AN APPROVED EQUAL MAY BE USED: NEXON, PLASTI-COTE, BLAC-KLAD, AND BETH-CU-LOY. COATED CORRUGATED STEEL PIPE SHALL MEET THE REQUIREMENTS OF AASHTO M-245 AND M-246.

MATERIALS- (ALUMINUM COATED STEEL PIPE)- THIS PIPE AND ITS APPURTENANCES SHALL CONFORM TO THE REQUIREMENTS OF AASHTO SPECIFICATION M-274 WITH WATERTIGHT COUPLING BANDS OR FLANGES. ANY ALUMINUM COATING DAMAGED OF OTHERWISE REMOVED SHALL BE REPLACED WITH COLD APPLIED BITUMINOUS COATING COMPOUND.?

MATERIALS-(ALUMINUM PIPE)- THIS PIPE AND ITS APPURTENANCES SHALL CONFORM TO THE REQUIREMENTS OF AASHTO SPECIFICATION M-196 OR M-211 WITH WATERTIGHT COUPLINGS BANDS OR FLANGES. ALUMINUM SURFACES THAT ARE TO BE IN CONTACT WITH CONCRETE SHALL BE PAINTED WITH ONE COAT OF ZINC CHROMATE PRIMER. HOT DIP GALVANIZED BOLTS MAY BE USED FOR CONNECTIONS. THE PH OF THE SURROUNDING SOILS SHALL BE BETWEEN 4 AND 9.

2. COUPLING BANDS, ANTI-SEEP COLLARS, END SECTIONS, ETC., MUST BE COMPOSED OF THE SAME MATERIAL AS THE PIPE. METALS MUST BE INSULATED FROM DISSIMILAR MATERIALS WITH USE RUBBER OR PLASTIC INSULATING MATERIALS AT LEAST 24 MILS IN THICKNESS.

3. CONNECTIONS- ALL CONNECTIONS WITH PIPES MUST BE COMPLETELY WATERTIGHT. THE DRAIN PIPE OR BARREL CONNECTION TO THE RISER SHALL BE WELDED ALL AROUND WHEN THE PIPE AND RISER ARE METAL ANTI-STEEP COLLARS SHALL BE CONNECTED TO THE PIPE IN SUCH A MANNER AS TO BE COMPLETELY WATERTIGHT. DIMPLE BANDS ARE NOT CONSIDERED TO BE WATERTIGHT.

ALL CONNECTIONS SHALL USE A RUBBER OF NEOPRENE GASKET WHEN JOINING PIPE SECTIONS. THE END OF EACH PIPE SHALL BE-ROLLED AND ADEQUATE NUMBER OF CORRUGATIONS TO ACCOMMODATE THE BAND MDTH. THE FOLLOWING TYPE CONNECTIONS ARE ACCEPTABLE FOR PIPE LESS THAN 24" IN DIAMETER: FLANGES ON BOTH ENDS OF THE PIPE, A 12" WIDE STANDARD LAP TYPE BAND WITH 12" WIDE BY 3/8" THICK CLOSED CELL CIRCULAR NEOPRENE GASKET; AND A 12" WIDE HUGGER TYPE BAND WITH O-RING GASKETS HAVING MINIMUM DIAMETER OF 1/2" GREATER THAN THE CORRUGATION DEPTH. PIPES 24: IN DIAMETER AND LARGER SHALL BE CONNECTED BY A 24" LONG ANNULAR CORRUGATED BAND USING RODS AND LUGS. A 12" WIDE BY 3/8" THICK CLOSED CELL CIRCULAR NEOPRENE GASKET WILL BE INSTALLED ON THE END OF EACH PIPE FOR A TOTAL OF 24"

HELICALLY CORRUGATED PIPE SHALL HAVE EITHER CONTINUOUSLY WELDED SEAMS OR HAVE LOCK SEAMS WITH INTERNAL CAULKING OR A NEOPRENE BEAD.

4. BEDDING- THE PIPE SHALL BE FIRMLY AND UNIFORMLY BEDDED THROUGHOUT ITS ENTIRE LENGTH. WHERE ROCK OR SOFT, SPONGY OR OTHER UNSTABLE SOIL IS ENCOUNTERED ALL SUCH MATERIAL SHALL BE REMOVED AND REPLACED WITH SUITABLE EARTH COMPACTED TO PROVIDE ADEQUATE SUPPORT.

5. BACKFILLING SHALL CONFORM TO "STRUCTURE BACKFILL."

6. OTHER DETAILS (ANTI-SEEP COLLARS, VALVES, ETC.) SHALL BE AS SHOWN ON THE DRAWINGS.

REINFORCED CONCRETE PIPE- ALL OF THE FOLLOWING CRITERIA SHALL APPLY FOR REINFORCED CONCRETE

1. MATERIALS-REINFORCED CONCRETE PIPE SHALL HAVE BELL AND SPIGOT JOINTS WITH RUBBER GASKETS AND SHALL EQUAL OR EXCEED ASTM DESIGNATION C-361. 2. BEDDING- ALL REINFORCED CONCRETE PIPE CONDUITS SHALL BE LAID IN A CONCRETE BEDDING FOR THEIR

THE SIDES OF THE PIPE AT LEAST 10% OF ITS OUTSIDE DIAMETER WITH A MINIMUM THICKNESS OF 3 INCHES, OR AS SHOWN ON THE DRAWINGS. 3. LAYING PIPE- BELL AND SPIGOT PIPE SHALL BE PLACED WITH THE BELL END UPSTREAM. JOINTS SHALL

ENTIRE LENGTH. THIS BEDDING SHALL CONSIST OF HIGH SLUMP CONCRETE PLACED UNDER THE PIPE AND UP

BE MADE IN ACCORDANCE WITH RECOMMENDATIONS OF THE MANUFACTURER OF THE MATERIAL. AFTER THE JOINTS ARE SEALED FOR THE ENTIRE LINE, THE BEDDING SHALL BE PLACED SO THAT ALL SPACES UNDER THE PIPE ARE FILLED. CARE SHALL BE EXERCISED TO PREVENT ANY DEVIATION FROM THE ORIGINAL LINE AND GRADE OF THE PIPE. THE FIRST JOINT MUST BE LOCATED WITHIN 2 FEET FROM THE RISER.

4. BACKFILLING SHALL CONFORM TO "STRUCTURE BACKFILL."

5. OTHER DETAILS (ANTI-SEEP COLLARS, VALVES, ETC.) SHALL BE AS SHOWN ON THE DRAWINGS.

POLYVINYL CHLORIDE (PVC) PIPE- ALL OF THE FOLLOWING CRITERIA SHALL APPLY FOR POLYVINYL CHLORIDE

1. MATERIALS-PVC PIPE SHALL BE PVC-1120 OR PVC-1220 CONFORMING TO ASTM D-1785 OR ASTM D-2241.

2. JOINTS AND CONNECTIONS TO ANTI-SEEP COLLARS SHALL BE COMPLETELY WATERTIGHT.

3. BEDDING- THE PIPE SHALL BE FIRMLY AND UNIFORMLY BEDDED THROUGHOUT ITS ENTIRE LENGTH. WHERE ROCK OR SOFT, SPONGY OR OTHER UNSTABLE SOIL IS ENCOUNTERED, ALL SUCH MATERIAL SHALL BE REMOVED AND REPLACED WITH SUITABLE EARTH COMPACTED TO PROVIDE ADEQUATE SUPPORT.

4. BACKFILLING SHALL CONFORM TO "STRUCTURE BACKFILL."

5. OTHER DETAILS (ANTI-SEEP COLLARS, VALVES, ETC.) SHALL BE AS SHOWN ON THE DRAWINGS.

CONCRETE SHALL MEET THE REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION, STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION 905.

THE RIPRAP SHALL BE PLACED TO THE REQUIRED THICKNESS IN ONE OPERATION. THE ROCK SHALL BE DELIVERED AND PLACED IN A MANNER THAT WILL INSURE THE RIPRAP IN PLACE SHALL BE REASONABLY HOMOGENOUS WITH THE LARGER ROCKS UNIFORMLY DISTRIBUTED AND FIRMLY IN CONTACT ONE TO ANOTHER WITH THE SMALLER ROCKS FILLING THE VOIDS BETWEEN THE LARGER ROCKS. FILTER CLOTH SHALL BE REPLACED UNDER ALL RIPRAP AND SHALL MEET THE REQUIREMENTS OF MARYLAND DEPARTMENT OF TRANSPORTATION, STATE HIGHWAY ADMINISTRATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, SECTION

CARE OF WATER DURING CONSTRUCTION

ALL WORK ON THE PERMANENT STRUCTURES SHALL BE CARRIED OUT IN AREAS FREE FROM WATER. THE CONTRACTOR SHALL CONSTRUCT AND MAINTAIN ALL TEMPORARY DIKES, LEVEES, COFFERDAMS, DRAINAGE CHANNELS, AND STREAM DIVERSIONS NECESSARY TO PROTECT THE AREAS TO BE OCCUPIED BY THE PERMANENT WORKS. THE CONTRACTOR SHALL ALSO FURNISH, INSTALL, OPERATE AND MAINTAIN ALL NECESSARY PUMPING AND OTHER EQUIPMENT REQUIRED FOR REMOVAL OF WATER FROM THE VARIOUS PARTS OF THE WORK AND FOR MAINTAINING THE EXCAVATIONS, FOUNDATION AND OTHER PARTS OF THE WORK FREE FROM WATER AS REQUIRED OR DIRECTED BY THE ENGINEER FOR CONSTRUCTING EACH PART OF THE WORK. AFTER HAVING SERVED THEIR PURPOSE, ALL TEMPORARY PROTECTIVE WORKS SHALL BE REMOVED OR LEVELED AND GRADED TO THE EXTENT REQUIRED TO PREVENT OBSTRUCTION IN ANY DEGREE WHATSOEVER OF THE FLOW OF WATER TO THE SPILLWAY OR OUTLET WORKS AND SO AS NOT TO INTERFERE IN ANY WAY WITH THE OPERATION OR MAINTENANCE OF THE STRUCTURE. STREAM DIVERSIONS SHALL BE MAINTAINED UNTIL THE FULL FLOW CAN BE PASSED THROUGH THE PERMANENT WORKS. THE REMOVAL OF WATER FROM THE REQUIRED EXCAVATION AND THE FOUNDATION SHALL BE ACCOMPLISHED IN A MANNER AND TO THE EXTENT THAT WILL MAINTAIN STABILITY OF THE EXCAVATED SLOPES AND BOTTOM OF THE REQUIRED EXCAVATIONS AND WILL ALLOW SATISFACTORY PERFORMANCE OF ALL AND CONSTRUCTION OPERATIONS. DURING THE PLACING AND COMPACTING OF MATERIAL IN REQUIRED EXCAVATIONS, THE WATER LEVEL AT THE LOCATIONS BEING REFILLED SHALL BE MAINTAINED BELOW THE BOTTOM OF THE EXCAVATION AT SUCH LOCATIONS WHICH MAY REQUIRE DRAINING THE WATER TO SUMPS FROM WHICH THE WATER SHALL BE PUMPED.

ALL BORROW AREAS SHALL BE GRADED TO PROVIDE PROPER DRAINAGE AND LEFT IN A SLIGHTLY CONDITION. ALL EXPOSED SURFACES OF THE EMBANKMENT, SPILLWAY, SPOIL AND BORROW AREAS, AND BERMS SHALL BE STABILIZED BY SEEDING, LIMING, FERTILIZING AND MULCHING IN ACCORDANCE WITH THE MARYLAND SOIL CONSERVATION SERVICE STANDARDS AND SPECIFICATIONS FOR CRITICAL AREA PLANTING (MD-342) OR AS SHOWN ON THE ACCOMPANYING DRAWINGS.

EROSION AND SEDIMENT CONTROL

STABILIZATION

CONSTRUCTION OPERATIONS WILL BE CARRIED OUT IN SUCH A MANNER THAT EROSION WILL BE CONTROLLED AND WATER AND AIR POLLUTION MINIMIZED. STATE AND LOCAL LAWS CONCERNING POLLUTION ABATEMENT WILL BE FOLLOWED. CONSTRUCTION PLANS SHALL DETAIL EROSION AND SEDIMENT CONTROL MEASURES TO BE EMPLOYED DURING THE CONSTRUCTION PROCESS.

OPERATION, MAINTENANCE AND INSPECTION

INSPECTION OF THE POND(S) SHOWN HEREON SHALL BE PERFORMED AT LEAST ANNUALLY, IN ACCORDANCE WITH THE CHECKLIST AND REQUIREMENTS CONTAINED WITHIN USDA, SCS "STANDARDS AND SPECIFICATIONS FOR PONDS" (MD-378). THE POND OWNER(S) AND THE HEIRS SUCCESSORS OR ASSIGNS SHALL BE RESPONSIBLE FOR THE SAFETY OF THE POND AND THE CONTINUED OPERATION, SURVEILLANCE, INSPECTION, AND MAINTENANCE THEREOF. THE POND OWNER(S) SHALL PROMPTLY NOTIFY THE SOIL CONSERVATION DISTRICT OF ANY UNUSUAL OBSERVATIONS THAT MAY BE INDICATIONS OF DISTRESS SUCH AS EXCESSIVE SEEPAGE, TURBID SEEPAGE, SLIDING OR SLUMPING.

SWM ROUTINE MAINTENANCE REQUIREMENTS


- 1. SILT SHALL BE REMOVED WHEN ACCUMULATION EXCEEDS SIX(6) INCHES IN FOREBAY OR POND 2. ACCUMULATED PAPER, TRASH AND DEBRIS SHALL BE REMOVED AS NECESSARY
- 3. ANNUAL INSPECTION AND REPAIR, IF REQUIRED, OF THE STRUCTURE SHALL BE PERFORMED

SWM NON-ROUTINE MAINTENANCE REQUIREMENTS


- INSPECT SIDE SLOPES OF FACILITY AND REPAIR WHEN NECESSARY. 2. REMOVE WOODY VEGITATION AS REQUIRED.
- 3. REPAIR TRASH RACKS AS REQUIRED.
- 4. REPAIR RIP RAP OUTFALL PROTECTION WHEN NECESSARY.
- 5. INSPECT EMBANKMENT FOR SEEPAGE.

<u>NOTES</u>

- 1- SOFT LOOSE FILL MUST BE REMOVED FROM BENEATH THE EMBANKMENT, OUTLET PIPE. AND STRUCTURE AND REPLACED BY APPROVED CONTROLLED EMBANKMENT. SUITABILITY OF MATERIAL TO BE DETERMINED ON SITE BY GEOTECHNICAL ENGINEER.
- 2- WATER TO BE REMOVED BY PUMPING IF ENCOUNTERED DURING THE CONSTRUCTION OF THE CORE TRENCH.



LOTS: 21, 22 - 2 DRY WELLS PER HOUSE






TABLE 2

TEST PIT LOGS

Test Pit	Depth From	(Ft) To	Descriptions and Remarks	MILLIAMS	ICAL STUDY KNOLL OUNTY, MARYLAND	
TP-5	0.0	0.7	Topsoil (Root mat & peat)			TABLE 2
	0.7	9.6*	Red-gray mottled moist Silty CLAY, trace mf sand with			TEST PIT LOGS
	9.6		ironstone seams (CH:Clay) Refusal on Ironstone Layer	Test Pit No.	Depth (Ft.) From To	Descriptions and Remarks
			At completion; water and caved 0 6.0'	<u> 77-1</u>	0.0 1.3 1.3 4.0	Topsoil (rootmat & peat) Brown moist cf SAND, some
TP-6	0.0	1.0	Topsoil (Root mat & peat) Reddish brown moist CLAY & SILT, little mf sand, trace gravel (CL:Silty Clay)		4.0 12.0	clayey silt (SM:Sandy Loam) Brown-tan moist of SAND, little silt, trace gravel (SM:Loamy Sand)
	4.0	12.0	Brown-white moist cm SAND, and gravel, some clay & silt (SM:Sandy Loam)			At completion; water seepage 0 4.0'
			At completion; hole dry	TP-2	0.0 1.3 1.3 5.5	Topsoil (root mat & peat) Reddish brown moist to very
TP-7	0.0 1.0 8.0	1.0	Topsoil (Root mat & peat) Brown moist SILT & CLAY, some cf sand, with ironstone seams (ML:Silt Loam) Backhoe refusal on ironstone layer At completion; hole dry		5.5 12.0	moist of SAND, some silt & clay, with thin ironstone seams (SM:Sandy Loam) Tan moist of SAND, little silt, trace gravel (SM:Sandy Loam) At completion; water seepage @ 5.5
TP-8	0.0 1.0 5.0	1.0	Topsoil (Root mat & peat) Brown moist Silty CLAY, trace cf sand, trace gravel (CH:Clay) Red-gray mottled Silty CLAY, trace sand (CH:Clay)		0.0 0.7 0.7 6.0	Topsoil (root mat & peat) Brown moist of SAND, little clayey silt, trace gravel with thin ironstone seams (SM:Loamy Sand) Pit could not be advanced due to running sand
			At completion; hole dry			At completion; water @ 5.5'
site. I	nforma	ated sever tion for me expavato	al hours previous to our arrival on materials below the 6-foot depth or.	C	0.0 0.7 0.7 4.0	Topsoil (Root mat & peat) Brown very moist of SAND, some clayey silt, little gravel (SM:Sandy Loam)
				·	12.0	Red-gray mottled moist silty CLAY, trace mf sand (CH:Clay) At completion; hole dry

Description and Remarks

<u>OWNERS</u>

PARCELS 230 & 231

6154 HANOVER ROAD

MICHAEL & SUSAN MULLENDORE

HANOVER, MARYLAND 21076

TP-9	0.0	0.7	Topsoil
	0.7	1.5	Brown moist SILT & CLAY, some cf sand, trace gravel (ML:Silt Loam)
	1.5	10.0	Brown gray moist SILT & CLAY, and cf sand (CL:Loam)
	10.0	12.0	Brown moist of SAND, some gravel, with ironstone seams (SM:Sandy Loam)
			At completion; seepage @ 1.5' & 10.8'
TP-10	0.0	0.5	Topsoil
	0.5		Brown moist SILT & CLAY, some cf sand (ML:Silt Loam)
	3.0	12.0	Tan moist of SAND, trace silt (SP:Sand)
			At completion; hole dry
TP-11	0.0	0.5	Topsoil (sod & peat)
	0.5	3.0	Brown moist of SAND, some silt, trace gravel (SM:Loam)
	3.0	12.0	Tan moist mf SAND, trace silt (SP-SM:Sand)
			At completion; hole dry

TABLE 2 TEST PIT LOGS

Test Pit Depth (Ft.)

From To

1.b-A	0.0	0.7	105011
	0.7	1.5	Brown moist SILT & CLAY, some cf sand, trace gravel
			(ML:Silt Loam)
	15	10.0	Brown gray moist SILT & CLAY,
	1.5	10.0	and cf sand (CL:Loam)
	10.0	12.0	Brown moist of SAND, some
	10.0	12.0	gravel, with ironstone
			seams (SM:Sandy Loam)
			seams (Sri: Sandy Loam)
			At completion; seepage @ 1.5'
			& 10.8'
_			
TP-10	0.0		Topsoil
	0.5	3.0	Brown moist SILT & CLAY,
			some cf sand (ML:Silt Loam)
	3.0	12.0	Tan moist of SAND, trace
			silt (SP:Sand)
			hh mamulahiam, hala dan
			At completion; hole dry
TP-11	0.0	0.5	Topsoil (sod & peat)
	0.5		Brown moist of SAND, some
			silt, trace gravel (SM:Loam)
	3.0	12.0	Tan moist mf SAND, trace silt
			(SP-SM: Sand)
			At completion; hole dry

PARCEL 229 JNSD, LC 5570 STERRETT PLAC, SUITE 201 COLUMBIA, MARYLAND 21044 (410) 997–3815, (301) 596–3877

DEVELOPER

JNSD, LC 5570 STERRETT PLAC, SUITE 201 COLUMBIA, MARYLAND 21044 (410) 997-3815, (301) 596-3877

CERTIFY MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED UPON ONSITE INSPECTIONS AND MATERIAL TESTS WHICH ARE CONDUCTED DURING CONSTRUCTION. THE ONSITE INSPECTIONS AND MATERIAL TESTS
ARE THOSE INSPECTIONS AND TESTS DEEMED SUFFICIENT AND APPROPRIATE COMMONLY ACCEPTED ENGINEERING STANDARDS. CERTIFY DOES NOT MEAN OR IMPLY A GUARANTEE BY THE ENGINEER NOR DOES AND ENGINEER'S CERTIFICATION RELIEVE ANY OTHER PARTY FROM MEETING REQUIREMENTS IMPOSED BY CONTRACT, EMPLOYMENT, OR OTHER MEANS, INCLUDING MEETING COMMONLY ACCEPTED INDUSTRY PRACTICES. BY THE DEVELOPER: "I/WE CERTIFY THAT ALL DEVELOPMENT AND/OR CONSTRUCTION WILL BE DONE ACCORDING TO THESE PLANS, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I SHALL ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS OF COMPLETION. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTIONS BY THE HOWARD SOIL CONSERVATION DISTRICT." UNSD, LC James & Newhon 10-3-97 James L. Newburn
PRINTED NAME OF DEVELOPER BY THE ENGINEER: "I CERTIFY THAT THIS PLAN FOR POND CONSTRUCTION, EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS. THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT. I HAVE NOTIFIED THE DEVELOPER THAT HE/SHE MUST ENGAGE A REGISTERED PROFESSIONAL ENGINEER TO SUPERVISE POND CONSTRUCTION AND PROVIDE THE HOWARD SOIL CONSERVATION DISTRICT WITH AN "AS-BUILT" PLAN OF THE POND WITHIN 30 DAYS CONSERVATION." 10/3/97 THESE PLANS HAVE BEEN REVIEWED FOR THE HOWARD SOIL CONSERVATION DISTRICT AND MEET THE TECHNICAL REQUIREMENTS FOR SMALL POND CONSTRUCTION 10/20/80

AS-BUILT CERTIFICATION

I HEREBY CERTIFY THAT THE FACILITY SHOWN ON THIS PLAN WAS CONSTRUCTED

AS SHOWN ON THE "AS-BUILT" PLANS AND MEETS THE APPROVED PLANS AND

SIGNATURE


, **U** 80 100 m C_{L}^{c} X. OZ STORMW

ATION

ATER


0 V TILDENBERC POENDER &


 $12 \, \text{or} \, 16$



VBERG, ER &


 $13 \, \text{of} \, 16$






231, LOTS AA KNOLL, AND BUI

ASSOC.,



SEC OF BU

 $15 \, \text{of} \, 16$



 $15 \, \text{of} \, 16$

CHIEF, DIVISION OF LAND DEVELOPMENT

CHIEF, DEVELOPMENT ENGINEERING DIVISION

DATE

BASIC SITE DATA	ACF	RES
GROSS SITE AREA	20.67	ACRES
POWER LINE RIGHT-OF-WAY		ACRES
AREA WITHIN 100 YEAR FLOODPLAIN	0.06	ACRES
AREA WITHIN AGRICULTURAL USE OR		
PRESERVATION PARCEL	_	
NET TRACT AREA	19.94	ACRES
LAND USE CATEGORY		
(R-RLD, R-RMD, R-SC, C/I/O, I)	R-	·SC
INFORMATION FOR CALCULATIONS		
A. NET TRACT AREA	10 04	ACDEC

DOMINANT VEGETATION

PINUS VIRGINIANA, ACER RUBRUM,

LIRIODENDRON TULIPIFERA, ACER RUBRUM

PINUS VIRGINIANA, QUERCU FALCATA.

QUERCUS PRINUS, QUERCUS RUBRA.

QUERCUS ALBA, QUERCUS RUBRA

LIRIODENDRON TULIPIFERA

QUERCUS ALBA

LEGEND

SLOPES 25% AND GREATER

DENOTES FOREST PRESERVATION SIGNAGE

DENOTES FOREST STAND CLASSIFICATION

- WHIP OR TREE

CONVEX BOTTOM

TREE PLANTING DETAIL

CONTAINER GROWN

__ 3"-4" MULCH

EXISTING-TOPSOIL

3' TO 5'

SLOPES 15% TO 25%

PRESERVATION PARCEL	AREA WITHIN AGRICULTURAL USE OR	. 0.00 ACKES
NET TRACT AREA		
LAND USE CATEGORY (R-RLD, R-RMD, R-SC, C/I/O, I)		
INFORMATION FOR CALCULATIONS A. NET TRACT AREA	LAND USE CATEGORY	
A. NET TRACT AREA	(R-RLD, R-RMD, R-SC, C/I/O, I)	. R-SC
A. NET TRACT AREA	INFORMATION FOR CALCULATIONS	
B. REFORESTATION THRESHOLD (20% X A) 3.99 ACRES C. AFFORESTATION MINIMUM (15% X A) 2.99 ACRES D. EXISTING FOREST ON NET TRACT AREA 19.47 ACRES	A MICE TRACE AREA	46.64.46555
C. AFFORESTATION MINIMUM (15% X A) 2.99 ACRES D. EXISTING FOREST ON NET TRACT AREA 19.47 ACRES	A. NET TRACT AREA	. 19.94 ACRES
D. EXISTING FOREST ON NET TRACT AREA 19.47 ACRES	B. REFORESTATION THRESHOLD (20% X A)	. 3.99 ACRES
D. EXISTING FOREST ON NET TRACT AREA 19.47 ACRES	C. AFFORESTATION MINIMUM (15% X A)	2.99 ACRES
F FOREST AREAS TO DE CLEADED 10.14 ACRES	D. EXISTING FOREST ON NET TRACT AREA	. 19.47 ACRES
E. TOREST AREAS TO BE CLEARED 10.14 ACRES	E. FOREST AREAS TO BE CLEARED	. 18.14 ACRES
	D. EXISTING FOREST ON NET TRACT AREA	. 19.47 ACRES

REFORESTATION THRESHOLD (20% X A). **3.99 ACRES** EXISTING FOREST ON NET TRACT AREA. 19.47 ACRES FOREST AREAS TO BE CLEARED. FOREST AREAS TO BE RETAINED 18.14 ACRES FOREST AREAS RETAINED ABOVE REFORESTATION THRESHOLD....

INFORMATION FOR CALCULATIONS

NET TRACT AREA...

GENERAL CONDITION

GOOD

GOOD

GOOD


GOOD

TOTAL REFORESTATION REQUIRED...



ACRES 19.94 ACRES

KEY	DBH	DESCRIPTION	CONDITION
В	32"	TULIP POPLAR	GOOD
С	40"	TULIP POPLAR	GOOD
D	36"	RED OAK	FAIRLY GOOD



VICINITY MAP Scale: 1'' = 2000'

THERE SHALL BE NO CLEARING, GRADING, CONSTRUCTION OR DISTURBANCE OF VEGETATION IN THE FOREST CONSERVATION EASEMENTS EXCEPT AS PERMITTED BY THE HOWARD COUNTY FOREST CONSERVATION PROGRAM.

THERE SHALL BE NO CLEARING, GRADING, CONSTRUCTION, SOIL COMPACTION, OR EXCAVATION, INTRODUCTION OF TOXIC CHEMICALS OR OTHER DISTURBANCES DETRIMENTAL TO THE LIVE SPECIMEN TREES OR CRITICAL ROOT ZONES FOR THESE TREES EXCEPT AS PERMITTED BY THE HOWARD COUNTY FOREST CONSERVATION

PLANTING SPECIFICATIONS AND NOTES SITE PREPARATION AND SOILS

PROTECTIVE FENCING IS TO BE INSTALLED AS A FIRST ORDER OF BUSINESS PER PLAN LOCATIONS. PROTECTIVE FENCING WILL NOT NECESSARY ALONG THOSE PERIMETERS WHERE SILT FENCE HAS BEEN INSTALLED FOR SEDIMENT CONTROL.

2. DISTURBANCE OF SOILS SHOULD BE LIMITED TO THE PLANTING FIELD FOR EACH PLANT. SOIL MIX FOR ALL PLANTS EXCEPT ERICACEOUS MATERIAL: SOIL MIX SHALL CONSIST OF EXISTING NATIVE TOPSOIL MIXTURE AT EACH PLANTING FIELD LOCATION INTO WHICH THE CONTRACTOR SHALL

THOROUGHLY INCORPORATE 25% BY VOLUME OF COMPOSTED SLUDGE. SOIL MIX FOR ERICACEOUS MATERIAL: SOIL MIX SHALL CONSIST OF EXISTING NATIVE TOPSOIL MIXTURE AT EACH PLANTING FIELD LOCATION INTO WHICH THE CONTRACTOR SHALL THOROUGHLY INCORPORATE 25% BY VOLUME PEAT MOSS.

ALL MIXING IN 3 AND 4 SHALL BE LIMITED TO CONTAINER GROWN OR BALL AND BURLAP STOCK ONLY AND CONFINED TO THE PLANTING FIELD AND IMMEDIATE ADJACENT SOIL SURFACE AREA AND SHALL BE DONE TO THE SATISFACTION OF THE DESIGN TEAM OR ENGINEER.

PLANT STORAGE AND INSPECTION

1. FOR CONTAINER GROWN NURSERY STOCK, PLANTING SHOULD OCCUR WITHIN 2 WEEKS AFTER DELIVERY TO THE SITE. FOR BALL AND BURLAP NURSERY STOCK, PLANTING SHOULD OCCUR WITHIN THREE DAYS AFTER DELIVERY TO THE SITE. 3. PLANTING STOCK SHOULD BE INSPECTED PRIOR TO PLANTING. PLANTS

SIZE, FORM, VIGOR, ROOTS, TRUNK WOUNDS, INSECTS AND DISEASE SHOULD BE REPLACED. UNTIL PLANTED, ALL PLANT STOCK SHALL BE KEPT IN A SHADED, COOL, AND MOISTENED ENVIRONMENT

NOT CONFORMING TO STANDARD NURSERYMAN SPECIFICATIONS FO

PLANT INSTALLATION

THE PLANTING FIELD SHOULD BE PREPARED AS SPECIFIED (SEE DETAIL). NATIVE STOCKPILED SOILS SHOULD BE USED FOR SOIL MIX AND BACKFILL FOR PLANTING FIELD. AFTER PLANT INSTALLATION, RAKE SOILS EVENLY OVER THE PLANTING FIELD AND COVER WITH AT LEAST 4 INCHES OF MULCH. WATER, GENEROUSLY, TO SETTLE SOIL BACKFILLED AROUND TREES.

PLANTING FIELD DIAMETERS SHOULD BE REDUCED OR PLANTING FIELD MOVED IF IT APPEARS THAT EXCESSIVE EXISTING ROOT DAMAGE MAY OCCUR DURING DIGGING OPERATION NEAR EXISTING FOREST. 3. CARE SHALL BE TAKEN WHEN DIGGING PLANTING FIELDS NOT TO CHOP THROUGH LARGER EXISTING ROOTS FROM EXISTING MATURE TREES. IF ROOTS GREATER THAN 1/2 INCH ARE ENCOUNTERED DIG AROUND THEM AS MUCH AS POSSIBLE TO MINIMIZE IMPACT TO EXISTING TREES.

CONSERVATION

FOREST

PRESERVATION

AREA

TREES FOR YOUR

FUTURE

FOREST

CONSERVATION

REFORESTATION

PROJECT

TREES FOR YOUR

FUTURE

CONTAINER GROWN STOCK SHOULD BE REMOVED FROM THE CONTAINER AND ROOTS GENTLY LOOSENED FROM THE SOIL. IF THE ROOTS ENCIRCLE THE ROOT BALL, SUBSTITUTION IS STRONGLY RECOMMENDED. J-SHAPED OR KINKED ROOT SYSTEMS SHOULD ALSO BE NOTED. ROOTS MAY NOT BE TRIMED ON SITE, DUE TO THE INCREASED CHANCES OF SOIL BORNE

5. FOR BALL AND BURLAP STOCK, PLACE TREE IN PREPARED PLANTING FIELD AND REMOVE WIRE AND/OR STRING FROM ROOT BALL. THEN PEEL BACK BURLAP TO BASE OF ROOT BALL AND COVER ENTIRE ROOT BALL WITH TOPSOIL MIXTURE INDICATED ABOVE AND WATER GENEROUSLY. THE CONTRACTOR SHALL EVENLY DISPERSE SPECIES IN GROUPS OF TWO
(2) TO FIVE (5) PER SPECIES, OVER THE DESIGNATED AREA TO BE

PLANTED WHILE MAINTAINING AN AVERAGE RANDOM SPACING OF INDIVIDUAL TREES AT PROPER SPACING INDICATED IN THE PLANT LIST. ** A STRAIGHT GRID PATTERN SPACING IS TO BE AVOIDED. TREES SHALL BE PLANTED ON AN AVERAGE SPACING AS INDICATED IN THE PLANT LIST TO OBTAIN A MORE NATURAL APPEARANCE.
NEWLY PLANTED TREES MAY NEED WATERING AS MUCH AS ONCE A WEEK

FOR THE ENTIRE GROWING SEASON, DUE TO THE VERY DEEP, WELL DRAINED NATURE OF THE NATIVE SOILS FOUND ON THIS SITE COMBINED WITH THE LOOSENESS OF THE BACKFILLED AREA WITHIN THE PLANTING FIELD. THE NEXT TWO YEARS MAY REQUIRE WATERING ONLY A FEW TIMES A YEAR DURING SUMMER AND DRY MONTHS. AFTER THAT PERIOD, TREES SHOULD ONLY NEED WATER IN SEVERE DROUGHTS. ANY WATERING PLAN SHOULD COMPENSATE FOR RECENT RAINFALL PATTERNS.

** IN AREAS WHERE REFORESTATION IS ADJACENT TO PROJECT BOUNDARIES, LANDSCAPE SIZE PLANT MATERIAL MUST BE INSTALLED MUST BE INSTALLED FIRST, IN ORDER TO SATISFY PERIMETER BUFFER REQUIREMENTS.

1. DO NOT FERTILIZE NEWLY PLANTED TREES WITHIN THE FIRST GROWING SEASON AFTER PLANTING. DOING SO MAY CAUSE A SPURT OF CANOPY GROWTH WHICH THE ROOTS CANNOT SUPPORT AND ADD ADDITIONAL SHOCK TO THE ALREADY DISTURBED PLANT. NOTHING SHOULD BE ADDED TO THE SOIL WITHOUT TESTING IT FIRST

TO DETERMINE WHAT IS NEEDED.

3. IF AND WHEN IT IS TIME TO FERTILIZE, ORGANIC FERTILIZERS ARE PREFERRED TO SYNTHETIC FERTILIZERS. BONE MEAL OR SEAWEED BASED PRODUCTS ARE AVAILABLE COMMERCIALLY AND ARE RECOMMENDED. THEY HAVE THE ABILITY TO SUPPLY NUTRIENTS TO THE PLANT AS NEEDED WHILE MINIMIZING THE RISK OF EXCESS NUTRIENTS ENTERING THE FOREST SYSTEM AND WATER SUPPLY.

MAINTENANCE SCHEDULE

1. ANNUAL MAINTENANCE DURING THE GROWING SEASON, FOR A MINIMUM OF TWO (2) YEAR PERIOD.

2. INSPECT PLANTED STOCK FOR MORTALITY. REMOVE AND REPLACE ANY DEAD OR DISEASED PLANTINGS. 3. EXPECT VOLUNTEER SEEDING OF NATIVE, LOCAL AND ENDEMIC VEGETATION TO OCCUR. DO NOT DISCOURAGE THIS GROWTH UNLESS IT NEGATIVELY

EFFECTS THE PLANTED STOCK. 4. MANUALLY REMOVE AGGRESSIVE, NOXIOUS, INVASIVE SPECIES AND ALL HERBACEOUS VEGETATION WITHIN A 3-FOOT RADIUS SURROUNDING THE PLANTED WOODY NURSERY STOCK.

REMOVE AND DISPOSE OF ANY MAN-MADE TRASH, INCLUDING ITEMS CONTAINED WITHIN THE PLANTING AREA. DO NOT REMOVE DOWN AND DEAD MATERIAL NATURALLY OCCURRING OR ACCUMULATING, UNLESS IT IS SMOTHERING PLANTING STOCK OR INTERFERES WIHT THE REFORESTATION

6. A 75 PERCENT SURVIVAL OF PLANTED STOCK MUST BE ACHIEVED AT THE END OF THE 24 MONTH MANAGEMENT PERIOD. IF NOT, ADDITIONAL PLANTINGS WILL BE REQUIRED TO BRING THE PLANTED STOCK SURVIVAL

SUPERVISION

ALL FOREST CONSERVATION ACTIVITIES SHALL BY DONE UNDER THE DIRECT SUPERVISION OF SOMEONE FROM THE DESIGN TEAM OR OTHER "QUALIFIED PROFESSIONAL" AS DETERMINED BY THE REQUIREMENTS OF COMAR 08.19.06.01 AND THE MARYLAND DEPARTMENT OF NATURAL RESOURCES, PUBLIC LANDS AND FORESTRY DIVISION.

REFORESTATION PLANT LIST

. SPECIES	SHADE TOL.	MOIST. REGIME	WET. STATUS	MIN.O.C. SPACING	SIZE & REMARKS	
Acer rubrum Red Maple	VT	DW	FAC	20'	CONT/B & B 1" CAL.	
Fagus grandifolia American Beech	VT	М	FACU	20'	CONT/B & B 1" CAL.	
Nyssa sylvatica Black Gum	Т	MW	FAC	20'	CONT/B & B 1" CAL.	
Pinus virginiana Virginia Pine	МТ	М	. –	15'	CONT/B & B 8'-10' HT.	
Quercus alba White Oak	1	M-W	FAC+	20'	CONT/B & B 1" CAL.	
Quercus rubra Red Oak	MT	D-M	UPL	20'	CONT/B & B	

PROTECTIVE FENCE DETAIL

SIGNAGE DETAILS

NOT TO SCALE

BLAZE ORANGE PLASTIC MESH

Corest protection device only,

Ectevition area will be set as part of the remem process.

BECHNOWNESS OF RETERIOR AREA SHOULD BE STACED AND FLACED PRIOR TO INSTALLING

DEVELOPER

TOTAL 82 TREES

5570 STERRETT PLACE, SUITE 201 COLUMBIA, MARYLAND 21044 (410) 997-3815, (301) 596-3877

STEPHANIE DEMCHIK

MD DNR QUALIFIED PROFESSIONAL

APPROVED: DEPARTMENT OF PUBLIC WORKS APPROVED: DEPARTMENT OF PLANNING AND ZONNI

16 OF 16

CONSERVATIO FOREST

BLOCI D II

TATION

POWER LINE RIGHT-OF-WAY .. 0.67 ACRES AREA WITHIN 100 YEAR FLOODPLAIN.. 0.06 ACRES AREA WITHIN AGRICULTURAL USE OR PRESERVATION PARCEL.. 19.94 ACRES NET TRACT AREA... LAND USE CATEGORY (R-RLD, R-RMD, R-SC, C/I/O, I).

DOMINANT VEGETATION

INFORMATION FOR CALCULATIONS
A. NET TRACT AREA...... REFORESTATION THRESHOLD (20% X A)..... 3.99 ACRES AFFORESTATION MINIMUM (15% X A).......... 2.99 ACRES EXISTING FOREST ON NET TRACT AREA...... 19.47 ACRES

<u>LEGEND</u>

SLOPES 25% AND GREATER

DENOTES FOREST PRESERVATION SIGNAGE

DENOTES FOREST STAND CLASSIFICATION

WHIP OR TREE

- 3"-4" MULCH

EXISTING-TOPSOIL

3' TO 5'

SLOPES 15% TO 25%

REFORESTATION THRESHOLD (20% X A). EXISTING FOREST ON NET TRACT AREA. FOREST AREAS CLEARED BELOW REFORESTATION THRESHOLD..... 2.85 ACRES FOREST AREAS RETAINED ABOVE REFORESTATION THRESHOLD....

GENERAL CONDITION

GOOD

GOOD

GOOD

ĠOOD

INFORMATION FOR CALCULATIONS
A. NET TRACT AREA.....

CLEARING BELOW THE THRESHOLD REFORESTATION FOR CLEARING ABOVE THRESHOLD. _5.70 ACRES REFORESTATION FOR CLEARING BELOW THE THRESHOLD.... TOTAL REFORESTATION REQUIRED.. 9.57 ACRES

THERE SHALL BE NO CLEARING, GRADING, CONSTRUCTION OR DISTURBANCE OF VEGETATION IN THE FOREST CONSERVATION EASEMENTS EXCEPT ON PROPERTY BY THE HOWARD COUNTY

THERE SHALL BE NO CLEARING, GRADING, CONSTRUCTION, SOIL

OR OTHER DISTURBANCES DETRIMENTAL TO THE LIVE SPECIMEN

PERMITTED BY THE HOWARD COUNTY FOREST CONSERVATION

TREES OR CRITICAL ROOT ZONES FOR THESE TREES EXCEPT AS

COMPACTION, OR EXCAVATION, INTRODUCTION OF TOXIC CHEMICALS

PLANTING SPECIFICATIONS AND NOTES

PROTECTIVE FENCING IS TO BE INSTALLED AS A FIRST ORDER OF

NECESSARY ALONG THOSE PERIMETERS WHERE SILT FENCE HAS

3. SOIL MIX FOR ALL PLANTS EXCEPT ERICACEOUS MATERIAL: SOIL MIX

SHALL CONSIST OF EXISTING NATIVE TOPSOIL MIXTURE AT EACH

THOROUGHLY INCORPORATE 25% BY VOLUME OF COMPOSTED SLUDGE.

SOIL MIX FOR ERICACEOUS MATERIAL: SOIL MIX SHALL CONSIST OF

ALL MIXING IN 3 AND 4 SHALL BE LIMITED TO CONTAINER GROWN OR BALL AND BURLAP STOCK ONLY AND CONFINED TO THE PLANTING

FIELD AND IMMEDIATE ADJACENT SOIL SURFACE AREA AND SHALL BE

PLANT STORAGE AND INSPECTION

. FOR CONTAINER GROWN NURSERY STOCK, PLANTING SHOULD OCCUR

FOR BALL AND BURLAP NURSERY STOCK, PLANTING SHOULD OCCUR

3. PLANTING STOCK SHOULD BE INSPECTED PRIOR TO PLANTING. PLANTS

NOT CONFORMING TO STANDARD NURSERYMAN SPECIFICATIONS FOR

UNTIL PLANTED, ALL PLANT STOCK SHALL BE KEPT IN A SHADED,

PLANT INSTALLATION

1. THE PLANTING FIELD SHOULD BE PREPARED AS SPECIFIED (SEE DETAIL). NATIVE STOCKPILED SOILS SHOULD BE USED FOR SOIL MIX AND BACKFILL FOR PLANTING FIELD. AFTER PLANT INSTALLATION, RAKE SOILS EVENLY OVER THE PLANT OF FIELD AND COVER WITH AT

LEAST 4 INCHES OF MULCH. WATER, GENEROUSLY, TO SETTLE SOIL

PLANTING FIELD DIAMETERS SHOULD BE REDUCED OR PLANTING FIELD MOVED IF IT APPEARS THAT EXCESSIVE EXISTING ROOT DAMAGE MAY

CARE SHALL BE TAKEN WHEN DIGGING PLANTING FIELDS NOT TO CHOP

THROUGH LARGER EXISTING ROOTS FROM EXISTING MATURE TREES. IF ROOTS GREATER THAN 1/2 INCH ARE ENCOUNTERED DIG AROUND THEM AS MUCH AS POSSIBLE TO MINIMIZE IMPACT TO EXISTING TREES.

FOREST

CONSERVATION

REFORESTATION

PROJECT

TREES FOR YOUR

FUTURE

OCCUR DURING DIGGING OPERATION NEAR EXISTING FOREST.

DONE TO THE SATISFACTION OF THE DESIGN TEAM OR ENGINEER.

PLANTING FIELD LOCATION INTO WHICH THE CONTRACTOR SHALL

EXISTING NATIVE TOPSOIL MIXTURE AT EACH PLANTING FIELD

LOCATION INTO WHICH THE CONTRACTOR SHALL THOROUGHLY

BEEN INSTALLED FOR SEDIMENT CONTROL.

INCORPORATE 25% BY VOLUME PEAT MOSS.

WITHIN 2 WEEKS AFTER DELIVERY TO THE SITE.

WITHIN THREE DAYS AFTER DELIVERY TO THE SITE.

FOR EACH PLANT.

SHOULD BE REPLACED.

BACKFILLED AROUND TREES.

CONSERVATION

FOREST

PRESERVATION

AREA

TREES FOR YOUR

FUTURE :

COOL, AND MOISTENED ENVIRONMENT.

BUSINESS PER PLAN LOCATIONS. PROTECTIVE FENCING WILL NOT


DISTURBANCE OF SOILS SHOULD BE LIMITED TO THE PLANTING FIELD

SITE PREPARATION AND SOILS

FOREST CONSERVATION PROGRAM

SPECIMEN TREES TO REMAIN

KEY	DBH	DESCRIPTION	CONDITION
В	32"	TULIP POPLAR	GOOD
С	40"	TULIP POPLAR	GOOD
D	36"	RED OAK	FAIRLY GOOD



VICINITY MAP Scale: 1'' = 2000'

19.94 ACRES

3.99 ACRES

19.47 ACRES

4. CONTAINER GROWN STOCK SHOULD BE REMOVED FROM THE CONTAINER AND ROOTS GENTLY LOOSENED FROM THE SOIL. IF THE ROOTS ENCIRCLE THE ROOT BALL, SUBSTITUTION IS STRONGLY RECOMMENDED. J-SHAPED OR KINKED ROOT SYSTEMS SHOULD ALSO BE NOTED. ROOTS MAY NOT BE TRIMMED ON SITE, DUE TO THE INCREASED CHANCES OF SOIL BORNE FOR BALL AND BURLAP STOCK, PLACE TREE IN PREPARED PLANTING

FIELD AND REMOVE WIRE AND/OR STRING FROM ROOT BALL. THEN PEEL BACK BURLAP TO BASE OF ROOT BALL AND COVER ENTIRE ROOT BALL WITH TOPSOIL MIXTURE INDICATED ABOVE AND WATER GENEROUSLY. 6. THE CONTRACTOR SHALL EVENLY DISPERSE SPECIES IN GROUPS OF TWO
(2) TO FIVE (5) PER SPECIES, OVER THE DESIGNATED AREA TO BE PLANTED WHILE MAINTAINING AN AVERAGE RANDOM SPACING OF INDIVIDUAL TREES AT PROPER SPACING INDICATED IN THE PLANT LIST. **
7. A STRAIGHT GRID PATTERN SPACING IS TO BE AVOIDED. TREES SHALL BE

OBTAIN A MORE NATURAL APPEARANCE. NEWLY PLANTED TREES MAY NEED WATERING AS MUCH AS ONCE A WEEK FOR THE ENTIRE GROWING SEASON, DUE TO THE VERY DEEP, WELL DRAINED NATURE OF THE NATIVE SOILS FOUND ON THIS SITE COMBINED WITH THE LOOSENESS OF THE BACKFILLED AREA WITHIN THE PLANTING FIELD. THE NEXT TWO YEARS MAY REQUIRE WATERING ONLY A FEW TIMES A YEAR DURING SUMMER AND DRY MONTHS. AFTER THAT PERIOD, TREES SHOULD ONLY NEED WATER IN SEVERE DROUGHTS. ANY WATERING PLAN SHOULD COMPENSATE FOR RECENT RAINFALL PATTERNS.

 ∞

0

30 TIOI

FARC KNO

MAP 3 WILL

PLANTED ON AN AVERAGE SPACING AS INDICATED IN THE PLANT LIST

** IN AREAS WHERE REFORESTATION IS ADJACENT TO PROJECT BOUNDARIES. LANDSCAPE SIZE PLANT MATERIAL MUST BE INSTALLED MUST BE INSTALLED FIRST, IN ORDER TO SATISFY PERIMETER BUFFER REQUIREMENTS.

FERTILIZING

1. DO NOT FERTILIZE NEWLY PLANTED TREES WITHIN THE FIRST GROWING SEASON AFTER PLANTING. DOING SO MAY CAUSE A SPURT OF CANOPY GROWTH WHICH THE ROOTS CANNOT SUPPORT AND ADD ADDITIONAL SHOCK TO THE ALREADY DISTURBED PLANT. NOTHING SHOULD BE ADDED TO THE SOIL WITHOUT TESTING IT FIRST TO DETERMINE WHAT IS NEEDED. 3. IF AND WHEN IT IS TIME TO FERTILIZE, ORGANIC FERTILIZERS ARE

PREFERRED TO SYNTHETIC FERTILIZERS. BONE MEAL OR SEAWEED BASED PRODUCTS ARE AVAILABLE COMMERCIALLY AND ARE RECOMMENDED. THEY HAVE THE ABILITY TO SUPPLY NUTRIENTS TO THE PLANT AS NEEDED WHILE MINIMIZING THE RISK OF EXCESS NUTRIENTS ENTERING THE FOREST SYSTEM AND WATER SUPPLY.

MAINTENANCE SCHEDULE

1. ANNUAL MAINTENANCE DURING THE GROWING SEASON, FOR A MINIMUM OF TWO (2) YEAR PERIOD. 2. INSPECT PLANTED STOCK FOR MORTALITY. REMOVE AND REPLACE ANY DEAD OR DISEASED PLANTINGS. EXPECT VOLUNTEER SEEDING OF NATIVE, LOCAL AND ENDEMIC VEGETATION TO OCCUR. DO NOT DISCOURAGE THIS GROWTH UNLESS IT NEGATIVELY EFFECTS THE PLANTED STOCK.

MANUALLY REMOVE AGGRESSIVE. NOXIOUS. INVASIVE SPECIES AND ALL HERBACEOUS VEGETATION WITHIN A 3-FOOT RADIUS SURROUNDING THE PLANTED WOODY NURSERY STOCK. REMOVE AND DISPOSE OF ANY MAN-MADE TRASH, INCLUDING ITEMS CONTAINED WITHIN THE PLANTING AREA. DO NOT REMOVE DOWN AND DEAD MATERIAL NATURALLY OCCURRING OR ACCUMULATING, UNLESS IT IS SMOTHERING PLANTING STOCK OR INTERFERES WIHT THE REFORESTATION


A 75 PERCENT SURVIVAL OF PLANTED STOCK MUST BE ACHIEVED AT THE END OF THE 24 MONTH MANAGEMENT PERIOD. IF NOT, ADDITIONAL PLANTINGS WILL BE REQUIRED TO BRING THE PLANTED STOCK SURVIVAL RATE UP TO 75%.

ALL FOREST CONSERVATION ACTIVITIES SHALL BY DONE UNDER THE DIRECT SUPERVISION OF SOMEONE FROM THE DESIGN TEAM OR OTHER "QUALIFIED PROFESSIONAL" AS DETERMINED BY THE REQUIREMENTS OF COMAR 08.19.06.01 AND THE MARYLAND DEPARTMENT OF NATURAL RESOURCES, PUBLIC LANDS AND FORESTRY DIVISION.

REFORESTATION PLANT LIST

	1121 0112	~~~~				
QTY.	SPECIES	SHADE TOL.	MOIST. REGIME	WET. STATUS	MIN.O.C. SPACING	SIZE & REMARKS
17	Acer rubrum Red Maple	VT	DW	FAC	20'	CONT/B & B 1" CAL.
11	Fagus grandifolia American Beech	VT	М	FACU	20'	CONT/B & B 1" CAL.
11	Nyssa sylvatica Black Gum	T	M-W	FAC	20'	CONT/B & B 1" CAL.
16	Pinus virginiana Virginia Pine	МТ	М	. -	15'	CONT/B & B 8'-10' HT.
11	Quercus alba White Oak	1	M-W	FAC+	20'	CONT/B & B 1" CAL.
16	Quercus rubra Red Oak	MT	D-M	UPL	20'	CONT/B & B 1" CAL.

SIGNAGE DETAILS NOT TO SCALE



DEVELOPER 5570 STERRETT PLACE, SUITE 201 COLUMBIA, MARYLAND 21044 (410) 997-3815, (301) 596-3877

TOTAL 82 TREES

STEPHANIE DEMCHIK

ionest protection device only. 2. rectention area will be set as part of the review process. 3. Bourdaness of retention area should be staked and flagued prior to installing

MD DNR QUALIFIED PROFESSIONAL