

MATCH LINE A-A (SEE SHEET 8)

**LEGEND**

- LIMIT OF DISTURBANCE ----- LOD -----
- EXISTING EASEMENT LINE -----
- EXISTING MAJOR CONTOURS -----
- EXISTING MINOR CONTOURS -----
- PROPOSED CONTOURS -----
- EXISTING TREE TO BE SAVED -----
- EDGE OF TREELINE -----
- EDGE OF WETLAND -----
- WETLAND BUFFER (25') -----
- WATERS OF THE UNITED STATES ----- WUS -----
- PROPERTY LINE -----
- EXISTING ROAD EDGE -----
- EXISTING SEWER LINE ----- S -----
- STONE TOE PROTECTION -----
- BOULDER CLUSTER -----
- RIFFLE GRADE CONTROL -----
- EXISTING TREE -----
- EXISTING/PROPOSED 100-YR WSE\* -----
- IMPACTS TO EXISTING FCE -----

**STONE TOE PROTECTION**

FROM STATION	TO STATION	OFFSET*
3+00	3+90	L
3+00	4+46	R
4+22	5+37	L
5+10	6+51	R

\*FACING DOWNSTREAM, MEASURED FROM BASELINE OF CONSTRUCTION

NOTE: THE HYDROLOGIC AND HYDRAULIC FLOOD ANALYSES AND FLOOD DELINEATION SHOWN HERE ON WAS BASED ON A 100-YEAR, 24-HOUR RAINFALL AMOUNT OF 8.51 INCHES BASED ON NOAA ATLAS 14 RAINFALL DATA. SUCH A RAINFALL AMOUNT EXCEEDS THE HOWARD COUNTY REQUIREMENT OF 7.2-INCHES. DUE TO THIS, THE FLOODPLAIN ELEVATIONS AND LIMITS EXCEEDED THE HOWARD COUNTY REQUIREMENTS.

**RIFFLE GRADE CONTROL**

FROM STATION	TO STATION
3+00	3+30

**BOULDER CLUSTER**

NAME	STATION	OFFSET*
B1	3+49	R
B2	3+70	L
B3	3+85	R

\*FACING DOWNSTREAM, STATION FROM BASELINE OF CONSTRUCTION

NO.	REVISIONS DESCRIPTION	DATE

936 RIDGEBROOK ROAD  
 SPARKS, MARYLAND 21152  
 TELEPHONE: (410) 316-7800  
 FAX: (410) 316-7818  
 www.kci.com



**HI TECH DRIVE  
 STREAM RESTORATION**  
 PATAPASCO VALLEY BUSINESS CENTER  
 SECTION 3, AREA 3  
 HOWARD COUNTY DEPARTMENT OF RECREATION AND PARKS  
 STREAMWATER MANAGEMENT DIVISION  
 6757 COLUMBIA GATEWAY DRIVE  
 COLUMBIA, MARYLAND 21046  
 PARCEL 285-TAX MAP 38-ZONING M-2  
 HOWARD COUNTY, MARYLAND

**GRADING PLAN**

SCALE: 0 0.25 0.5 1 2 4 8 16 FEET  
 1" = 20'

DATE: NOVEMBER 8, 2010  
 KCI JOB NO.: 01-043223.26  
 CAPITAL PROJECT NO.: D - 1122  
 PERMIT ISSUE:  
 CONSTRUCTION ISSUE:

PROFESSIONAL CERTIFICATION. I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 38311. EXPIRATION DATE: JANUARY 06, 2012


APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

*John P. ...* 3/1/11  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

*Kevin ...* 3/10/11  
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE


*Thomas ...* 3/10/11  
 DIRECTOR DATE





NO.	REVISIONS DESCRIPTION	DATE

936 RIDGEBROOK ROAD  
 SPARKS, MARYLAND 21152  
 TELEPHONE: (410) 316-7800  
 FAX: (410) 316-7818  
 www.kci.com



**HI TECH DRIVE  
 STREAM RESTORATION**  
 PATAPSCO VALLEY BUSINESS CENTER  
 SECTION 3, AREA 3  
 HOWARD COUNTY DEPARTMENT OF RECREATION AND PARKS  
 STORMWATER MANAGEMENT DIVISION  
 875 COLUMBIA GATEWAY DRIVE  
 ELK LANE, MARYLAND 21046  
 PARCEL ELECTION DISTRICT 01043223.26  
 HOWARD COUNTY, MARYLAND

**GRADING PLAN**

SCALE: 0 0.25 0.5 1 2 3 4 5 10  
 1" = 20'  
 DATE: NOVEMBER 8, 2010  
 KCI JOB NO.: 01-043223.26  
 CAPITAL PROJECT NO.: D - 1122  
 PERMIT ISSUE:  
 CONSTRUCTION ISSUE:  
 SHEET NO.: 9 OF 25

PROFESSIONAL CERTIFICATION. I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 38311. EXPIRATION DATE: JANUARY 06, 2012.

APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

*[Signature]* 3/9/11  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

*[Signature]* 3/10/11  
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE

*[Signature]* 3/10/11  
 DIRECTOR DATE

**STONE TOE PROTECTION**

FROM STATION TO STATION	OFFSET*	
11+41	12+89	R
13+23	14+60	R
14+30	14+60	L

\*FACING DOWNSTREAM, MEASURED FROM BASELINE OF CONSTRUCTION

**IMBRICATED WALL**

FROM STATION TO STATION	OFFSET*	
12+98	13+47	L

\*FACING DOWNSTREAM, MEASURED FROM BASELINE OF CONSTRUCTION

**RIFFLE GRADE CONTROL**

FROM STATION TO STATION	
12+62	12+85
14+35	14+59

NOTE: THE HYDROLOGIC AND HYDRAULIC FLOOD ANALYSES AND FLOOD DELINEATION SHOWN HERE ON WAS BASED ON A 100-YEAR, 24-HOUR RAINFALL AMOUNT OF 8.51 INCHES BASED ON NOAA ATLAS 14 RAINFALL DATA. SUCH A RAINFALL AMOUNT EXCEEDS THE HOWARD COUNTY REQUIREMENT OF 7.2-INCHES. DUE TO THIS, THE FLOODPLAIN ELEVATIONS AND LIMITS EXCEEDED THE HOWARD COUNTY REQUIREMENTS.


**LEGEND**

- LIMIT OF DISTURBANCE ----- L00
- EXISTING EASEMENT LINE -----
- EXISTING MAJOR CONTOURS -----
- EXISTING MINOR CONTOURS -----
- PROPOSED CONTOURS -----
- EXISTING TREE TO BE SAVED (Symbol)
- EXISTING TREE TO BE REMOVED (Symbol)
- EDGE OF TREELINE -----
- EDGE OF WETLAND ----- WUS
- WATERS OF THE UNITED STATES -----
- PROPERTY LINE -----
- EXISTING ROAD EDGE -----
- EXISTING SEWER LINE -----
- IMBRICATED WALL (Symbol)
- STONE TOE PROTECTION (Symbol)
- RIFFLE GRADE CONTROL (Symbol)
- TREE SAVE AREA (Symbol)
- EXISTING TREE (Symbol)
- EXISTING/PROPOSED 100-YR WSE\* (Symbol)










MATCH LINE A-A (SEE SHEET 14)

NOTE: THE HYDROLOGIC AND HYDRAULIC FLOOD ANALYSES AND FLOOD DELINEATION SHOWN HERE ON WAS BASED ON A 100-YEAR, 24-HOUR RAINFALL AMOUNT OF 8.51 INCHES BASED ON NOAA ATLAS 14 RAINFALL DATA. SUCH A RAINFALL AMOUNT EXCEEDS THE HOWARD COUNTY REQUIREMENT OF 7.2-INCHES. DUE TO THIS, THE FLOODPLAIN ELEVATIONS AND LIMITS EXCEEDED THE HOWARD COUNTY REQUIREMENTS.

**LEGEND**

- |                             |       |     |                                  |             |
|-----------------------------|-------|-----|----------------------------------|-------------|
| LIMIT OF DISTURBANCE        | ---   | LOD | SINGLE STONE TOE PROTECTION      | ----->>>>>> |
| EXISTING EASEMENT LINE      | ----  |     | RIFFLE GRADE CONTROL             | ----->>>>>> |
| EXISTING MAJOR CONTOURS     | ----- |     | STABILIZED CONSTRUCTION ENTRANCE | ----->>>>>> |
| EXISTING MINOR CONTOURS     | ----- |     | SANDBAG DAM                      | ----->>>>>> |
| PROPOSED CONTOURS           | ----- | 387 | SILT FENCE                       | ----->>>>>> |
| EXISTING TREE TO BE SAVED   | ⊗     |     | SF                               | ----->>>>>> |
| EXISTING TREE TO BE REMOVED | ⊗     |     | (P)                              | ----->>>>>> |
| EDGE OF TREELINE            | ----- |     | INTAKE HOSE AND DISCHARGE PIPE   | ----->>>>>> |
| EDGE OF WETLAND             | ----- |     | ORANGE SAFETY FENCE              | ----->>>>>> |
| WETLAND BUFFER (25')        | ----- |     | FILTER BAG                       | ----->>>>>> |
| PROPERTY LINE               | ----- |     | WATERS OF THE UNITED STATES      | ----->>>>>> |
| EXISTING ROAD EDGE          | ----- |     | EXISTING/PROPOSED 100-YR WSE     | ----->>>>>> |
| EXISTING SEWER LINE         | ----- |     |                                  |             |
| IMBRICATED WALL             | ----- |     |                                  |             |



PROFESSIONAL CERTIFICATION. I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 38311. EXPIRATION DATE: JANUARY 04, 2012.

APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

*John P. Roberts* 2/24/11  
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

*Thomas E. Ruttie* 3/10/11  
CHIEF, DIVISION OF LAND DEVELOPMENT DATE

*Thomas E. Ruttie* 3/10/11  
DIRECTOR DATE

Reviewed for HOWARD SCD and meets Technical Requirements.

This development plan is approved for soil erosion and sediment control by the HOWARD SOIL CONSERVATION DISTRICT.

*John P. Roberts*  
HOWARD SCD  
2/24/11  
Date

NO.	REVISIONS DESCRIPTION	DATE

936 RIDGEBROOK ROAD  
SPARKS, MARYLAND 21152  
TELEPHONE: (410) 316-7800  
FAX: (410) 316-7818  
www.kci.com

**KCI**  
TECHNOLOGIES

**HI TECH DRIVE  
STREAM RESTORATION  
CONTROL PLAN**

PATAPSCO VALLEY BUSINESS CENTER  
SECTION 3, AREA 3  
HOWARD COUNTY DEPARTMENT OF RECREATION AND PARKS  
STORMWATER MANAGEMENT DIVISION  
8751 COLUMBIA GATEWAY DRIVE  
COLUMBIA, MARYLAND 21046  
PARCEL: 855-TAX MAPS ZONING: M-2  
HOWARD COUNTY, MARYLAND


**EROSION AND  
SEDIMENT  
CONTROL  
PLAN**

SCALE: 0 20 40  
INCHES  
1" = 20'

DATE: NOVEMBER 8, 2010  
KCI JOB NO.: 01-043223.26  
CAPITAL PROJECT NO.: D-1122  
PERMIT ISSUE:  
CONSTRUCTION ISSUE:

SHEET NO.: 13 OF 25  
SDP-10-095





- ### SEQUENCE OF CONSTRUCTION
- THE CONTRACTOR SHALL NOTIFY "MISS UTILITY" AT 1-800-257-7777, HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS/BUREAU OF ENGINEERING/ CONSTRUCTION INSPECTION DIVISION (410)-313-1880 AND DEPARTMENT OF THE ENVIRONMENT WATER MANAGEMENT ADMINISTRATION (410)-537-3510 AT LEAST FIVE (5) DAYS PRIOR TO BEGINNING ANY WORK.
  - CONTRACTOR SHALL TAKE EXTRA PRECAUTION FOR TRANSPORTING MATERIALS FROM THE STORAGE AREA TO THE CONSTRUCTION SITE. CONTRACTOR SHALL MINIMIZE THE IMPACT ON EXISTING TREES, WETLANDS, U.S. WATERS, EXISTING UTILITY AND OTHER EXISTING FEATURES.
  - CONTRACTOR SHALL CAUTION THE TRUCK DRIVERS TO TAKE EXTRA PRECAUTION WHILE DRIVING IN THE ACCESS AREA WITHIN THE LIMIT OF DISTURBANCE SO THAT IMPACTS ON STREAMBED, SIDE SLOPES, EXISTING TREES, U.S. WATERS, AND ANY EXISTING FEATURES CAN BE MINIMIZED.
  - ALL NECESSARY EASEMENTS AND/OR RIGHT OF WAYS SHALL BE REQUIRED PRIOR TO THE START OF THE JOB.
  - ALL IN STREAM WORK SHALL BE DONE IN STRICT ACCORDANCE WITH THE PUMP AROUND CRITERIA.
  - INSTALL SCE, SILT FENCE FOR ALL PHASE AREAS (1, 2 & 3) AS SHOWN ON THE PLAN OR AS DIRECTED BY THE SEDIMENT CONTROL INSPECTOR. ANY RUTTING, EROSION OR DISTURBANCE SHALL BE STABILIZED WITH STONE OR PROTECTED WITH SILT FENCE AT THE INSPECTOR'S DISCRETION.
- PHASE 1: (STA. 11+00 TO STA. 15+00 MAIN CHANNEL)**
- INSTALL SAND BAGS, PUMP, DEWATERING DEVICE, INTAKE PIPE AND DISCHARGE PIPE ON MAIN CHANNEL STARTING FROM STA. 15+00 GOING UPSTREAM.
  - UPON INSPECTOR'S APPROVAL OF EROSION CONTROL DEVICES AND CONDITIONS, COMMENCE IN-STREAM WORK.
  - PERFORM STREAM GRADING AND STREAM RESTORATION WORK ON MAIN CHANNEL FROM STA. 15+00 TO STA. 11+00. STABILIZE ALL DISTURBED AREAS AT FINAL GRADE. CONTRACTOR SHALL DISTURB ONLY THAT MUCH AREA WHICH CAN BE BROUGHT TO FINAL GRADE AND STABILIZED BY THE END OF EACH DAY.
  - WITH PERMISSION FROM INSPECTOR, REMOVE THE PUMP AROUND SYSTEM AND STABILIZE THE AREA DISTURBED BY THIS PHASE. PROCEED WITH PHASE 2.
- PHASE 2: (STA. 2+75 TO STA. 5+00 MAIN CHANNEL)**
- INSTALL SAND BAGS, PUMP, DEWATERING DEVICE, INTAKE PIPE AND DISCHARGE PIPE ON MAIN CHANNEL AT STA. 2+75.
  - UPON INSPECTOR'S APPROVAL OF EROSION DEVICES AND CONDITIONS, COMMENCE IN STREAM WORK.
  - PERFORM STREAM GRADING AND STREAM RESTORATION WORK ON MAIN CHANNEL FROM STA. 2+75 TO STA. 5+00. STABILIZE ALL DISTURBED AREAS AT FINAL GRADE. CONTRACTOR SHALL DISTURB ONLY THAT MUCH AREA WHICH CAN BE BROUGHT TO FINAL GRADE AND STABILIZED BY END OF EACH DAY.
  - WITH PERMISSION FROM INSPECTOR REMOVE THE PUMP AROUND SYSTEM AND STABILIZE THE AREA DISTURBED BY THIS PHASE. PROCEED WITH PHASE 3.
- PHASE 3: (STA. 5+00 TO STA. 9+75 MAIN CHANNEL)**
- INSTALL SAND BAGS, PUMP, DEWATERING DEVICE, INTAKE PIPE AND DISCHARGE PIPE ON MAIN CHANNEL AT STA. 5+00.
  - UPON INSPECTOR'S APPROVAL OF EROSION CONTROL DEVICES AND CONDITIONS, COMMENCE IN STREAM WORK.
  - PERFORM STREAM GRADING AND STREAM RESTORATION WORK FROM ON MAIN CHANNEL FROM STA. 5+00 TO STA. 9+75. STABILIZE ALL DISTURBED AREAS AT FINAL GRADE. CONTRACTOR SHALL DISTURB ONLY THAT MUCH AREA WHICH CAN BE BROUGHT TO FINAL GRADE AND STABILIZED BY END OF EACH DAY.
  - WITH PERMISSION FROM INSPECTOR, REMOVE THE PUMP AROUND SYSTEM AND STABILIZE THE AREA DISTURBED BY THIS PHASE.

### LEGEND

LIMIT OF DISTURBANCE	---	LOD
EXISTING EASEMENT LINE	---	
EXISTING MAJOR CONTOURS	---	
EXISTING MINOR CONTOURS	---	
PROPOSED CONTOURS	---	387
EXISTING TREE TO BE SAVED	⊙	
EXISTING TREE TO BE REMOVED	⊗	
EDGE OF TREELINE	---	
WATERS OF THE UNITED STATES	WUS	
WETLAND BUFFER (25')	---	
PROPERTY LINE	---	
EXISTING ROAD EDGE	---	
EXISTING SEWER LINE	S	
IMBRICATED WALL	▣	
SINGLE STONE TOE PROTECTION	▤	
RIFFLE GRADE CONTROL	▨	
STABILIZED CONSTRUCTION ENTRANCE	▩	
SANDBAG DAM	⊖	
SILT FENCE	---	SF
PUMP	⊕	
INTAKE HOSE AND DISCHARGE PIPE	---	
ORANGE SAFETY FENCE	---	OSF
FILTER BAG	⊗	
EXISTING/PROPOSED 100-YR WSE*	---	

\*MINIMAL CHANGES BETWEEN EXISTING AND PROPOSED 100-YR WSE. SEE THE HI TECH DRIVE STREAM HYDROLOGY AND HYDRAULICS REPORT FOR FURTHER INFORMATION.

PROFESSIONAL CERTIFICATION. I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 38311. EXPIRATION DATE: JANUARY 06, 2013.

APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

*[Signature]* 3/11/11  
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

*[Signature]* 3/10/11  
CHIEF, DIVISION OF LAND DEVELOPMENT DATE

*[Signature]* 3/10/11  
DIRECTOR DATE

Reviewed for HOWARD SCD and meets Technical Requirements.

This development plan is approved for soil erosion and sediment control by the HOWARD SOIL CONSERVATION DISTRICT.

*[Signature]* 2/24/11  
HOWARD SCD Date

NOTE: THE HYDROLOGIC AND HYDRAULIC FLOOD ANALYSES AND FLOOD DELINEATION SHOWN HERE ON WAS BASED ON A 100-YEAR, 24-HOUR RAINFALL AMOUNT OF 8.51 INCHES BASED ON NOAA ATLAS 14 RAINFALL DATA. SUCH A RAINFALL AMOUNT EXCEEDS THE HOWARD COUNTY REQUIREMENT OF 7.2-INCHES. DUE TO THIS, THE FLOODPLAIN ELEVATIONS AND LIMITS EXCEEDED THE HOWARD COUNTY REQUIREMENTS.

20' 0' 20' 40'

GRAPHIC SCALE  
1" = 20'

NO.	REVISIONS DESCRIPTION	DATE

936 RIDGEBROOK ROAD  
SPARKS, MARYLAND 21152  
TELEPHONE: (410) 316-7800  
FAX: (410) 316-7818  
www.kci.com

HI TECH DRIVE  
STREAM RESTORATION  
PATAPSCO VALLEY BUSINESS CENTER  
SECTION 3, AREA 3  
HOWARD COUNTY DEPARTMENT OF RECREATION AND PARKS  
STORMWATER MANAGEMENT DIVISION  
6757 COLUMBIA GATEWAY DRIVE  
PARCEL 285 TAX MAP 38, ZONING M-2  
HOWARD COUNTY, MARYLAND

EROSION AND SEDIMENT CONTROL PLAN

SCALE: 1" = 20'

DATE: NOVEMBER 8, 2010

KCI JOB NO.: 01-043223.26

CAPITAL PROJECT NO.: D - 1122

PERMIT ISSUE:

CONSTRUCTION ISSUE:

SHEET NO.: 15 OF 25  
SDP-10-095

HOWARD SOIL CONSERVATION DISTRICT

TEMPORARY SEEDING NOTES \*\*

Apply to graded or cleared areas likely to be re-disturbed where a short-term vegetative cover is needed.

**Seedbed preparation:** -- Loosen upper three inches of soil by raking, disking or other acceptable means before seeding, if not previously loosened.

**Soil Amendments:** -- Apply 600 lbs/acre 10-10-10 fertilizer (14 lbs/1000 sq. ft.).

**Seeding:** -- For periods March 1 - April 30 and from August 15 - October 15, seed with 2-1/2 bushel per acre of annual ryegrass (3.2 lbs/1000 sq. ft.). For the period May 1 - August 14, seed with 3 lbs/acre of weeping lovegrass (.07 lbs/1000 sq. ft.). For the period November 16 - February 28, protect site by applying 2 tons/acre of well anchored straw mulch and seed as soon as possible in the spring, or use sod.

**Mulching:** -- Apply 1-1/2 to 2 tons/acre (70 to 90 lbs/1000 sq. ft.) of unrotted weed-free, small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool. No asphalt emulsion shall be used for anchoring. Only a non-toxic, latex backing material is allowed.

Refer to the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for additional rates and methods not covered.

HOWARD SOIL CONSERVATION DISTRICT

PERMANENT SEEDING NOTES \*\*

Apply to graded or cleared areas not subject to immediate further disturbance where a permanent long-lived vegetative cover is needed.

**Seedbed Preparation:** Loosen upper three inches of soil by raking, disking or other acceptable means before seeding, if not previously loosened.

**Soil Amendments:** In lieu of soil test recommendations, use one of the following schedules:

1. **Preferred** -- Apply 2 tons/acre dolomitic limestone (92 lbs/1000 sq. ft.) and 600 lbs/acre 10-10-10 fertilizer (14 lbs/1000 sq. ft.) before seeding. Harrow or disk into upper three inches of soil. At time of seeding, apply 400 lbs/acre 30-0-0 ureaform fertilizer (9 lbs/1000 sq. ft.).

2. **Acceptable** -- Apply 2 tons/acre dolomitic limestone (92 lbs/1000 sq. ft.) and 1000 lbs/acre 10-10-10 fertilizer (23 lbs/1000 sq. ft.) before seeding. Harrow or disk into upper three inches of soil.

**Seeding** - For the periods March 1 - April 30, and August 1 - October 15, seed with 60 lbs/acre (1.4 lbs/1000 sq. ft.) of Kentucky 31 Tall Fescue. For the period May 1 - July 31, seed with 60 lbs Kentucky 31 Tall Fescue per acre and 2 lbs/acre (.05 lbs/100sq. ft.) of weeping lovegrass. During the period of October 16 - February 28, protect site by: **Option 1** - Two tons per acre of well anchored straw mulch and seed as soon as possible in the spring. **Option 2** - Use sod. **Option 3** - Seed with 60 lbs/acre Kentucky 31 Tall Fescue and mulch with 2 tons/acre well anchored straw.

**Mulching** - Apply 1-1/2 to 2 tons per acre (70 to 90 lbs/1000 sq. ft.) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool. No asphalt emulsion shall be used for anchoring. Only a non-toxic, latex tacking material is allowed.

**Maintenance** - Inspect all seeding areas and make needed repairs, replacements and reseedings.

\*\* Contractor shall perform a soil test at the site as a first order of business. The results shall be reviewed by Department of Recreation and Parks to determine appropriate soil amendments and fertilization needs for this project. No fertilizer or soil amendments shall be added without approval of Department of Recreation and Parks.

HOWARD SOIL CONSERVATION DISTRICT  
STANDARD SEDIMENT CONTROL NOTES

1. A minimum of 48 hours notice must be given to the Howard County Department of Public Works, Construction Inspections, prior to the start of any construction.

2. All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the most current MARYLAND STANDARDS AND SPECIFICATION FOR SOIL EROSION AND SEDIMENT CONTROL and revisions thereto.

3. Following initial soil disturbance or re-disturbance, permanent or temporary stabilization shall be completed within: a) 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all Slopes greater than 3:1, b) 14 days as to all other disturbed or graded areas on the project site.

4. All sediment traps/basins shown must be fenced and warning signs posted around their perimeter in accordance with Vol 1, Chapter 12 of the HOWARD COUNTY DESIGN MANUAL, Storm Drainage.

5. All disturbed areas must be stabilized within the time period specified above in accordance with the 1994 MARYLAND STANDARDS AND SPECIFICATION FOR SOIL EROSION AND SEDIMENT CONTROL for permanent seeding (Sec. 51), sod (Sec. 54), temporary seeding (Sec. 50) and mulching (Sec. 52). Temporary stabilization with mulch alone can only be done when recommended seeding dates do not allow for proper germination and establishment of grasses.

6. All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.

7. Site Analysis:	
Total Area of Site	2.46 Acres
Area Disturbed	2.46 Acres
Area to be roofed or paved	0.00 Acres
Area to be vegetatively stabilized	2.16 Acres
Total Cut	1965 Cu. Yds.
Total Fill	1219 Cu. Yds.
Offsite waste/borrow area location	None Proposed

8. Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.

9. Additional sediment control must be provided, if deemed necessary by the Howard County Sediment Control Inspector.

10. On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the inspection agency is made.

11. Trenches for the construction of utilities is limited to three pipe lengths or that which shall be back-filled and stabilized by the end of each work day, whichever is shorter.

\*Offsite waste/borrow site shall have an approved sediment control plan.

21.0 STANDARD AND SPECIFICATIONS FOR TOPSOIL

**Definition**  
Placement of topsoil over a prepared subsoil prior to establishment of permanent vegetation.

**Purpose**  
To provide a suitable soil medium for vegetative growth. Soils of concern have low moisture content, low nutrient levels, low pH, materials toxic to plants, and/or unacceptable soil gradation.

Conditions Where Practice Applies

- This practice is limited to areas having 2:1 or flatter slopes where:
  - The texture of the exposed subsoil/parent material is not adequate to produce vegetative growth.
  - The soil materials so shallow that the rooting zone is not deep enough to support plants or furnish continuing supplies of moisture and plant nutrients.
  - The original soil to be vegetated contains material toxic to plant growth.
  - The soil is so acidic that treatment with limestone is not feasible.

II. For the purpose of these Standards and Specifications, areas having slopes steeper than 2:1 require special consideration and design for adequate stabilization. Areas having slopes steeper than 2:1 shall have the appropriate stabilization shown on the plans.

Construction and Material Specifications

I. Topsoil salvaged from the existing site may be used provided that it meets the standards as set forth in these specifications. Typically, the depth of topsoil to be salvaged for a given soil type can be found in the representative soil profile section in the soil survey published by USDA-SCS in cooperation with Maryland Agricultural Experimental Station.

- Topsoil Specifications - Soil to be used as topsoil must meet the following:
  - Topsoil shall be a loam, sandy loam, clay loam, silt loam, sandy clay loam, loamy sand. Other soils may be used if recommended by an agronomist or soil scientist and approved by the appropriate approval authority. Regardless, topsoil shall not be a mixture of contrasting textured subsoils and shall contain less than 5% by volume of cinders, stones, slag, coarse fragments, gravel, sticks, roots, trash, or other materials larger than 1 1/2" in diameter.
  - Topsoil must be free of plants or plant parts such as Bermuda grass, quackgrass, Johnson grass, nutsedge, poison ivy, thistle, or others as specified.
  - Where the subsoil is either highly acidic or composed of heavy clays, ground limestone shall be spread at the rate of 4-8 tons/acre (200-400 pounds per 1,000 square feet) prior to the placement of topsoil. Lime shall be disturbed uniformly over designated areas and worked into the soil in conjunction with tillage operations as described in the following procedures.

III. For sites having disturbed areas under 5 acres:

- Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section \* - Vegetative Stabilization Methods and Materials.

IV. For sites having disturbed areas over 5 acres:

- On soil meeting Topsoil specifications, obtain test results dictating fertilizer and lime amendments required to bring the soil into compliance with the following:
  - pH for topsoil shall be between 6.0 and 7.5. If the tested soil demonstrates a pH of less than 6.0, sufficient lime shall be prescribed to raise the pH to 6.5 or higher.
  - Organic content of topsoil shall be not less than 1.5 percent by weight.
  - Topsoil having soluble salt content greater than 500 parts per million shall not be used.
  - No sod or seed shall be placed on soil which has been treated with soil sterilants or chemicals used for weed control until sufficient time as elapsed (14 days min.) to permit dissipation of phyto-toxic materials.
- Topsoil substitutes or amendments, as recommended by a qualified agronomist or soil scientist and approved by the appropriate approval authority, may be used in lieu of natural topsoil.
- Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section \* - Vegetative Stabilization Methods and Materials.

V. Topsoil Application

- When topsoiling, maintain needed erosion and sediment control practices such as diversions, Grade Stabilization Structures, Earth Dikes, Slope Silt Fence and Sediment Traps and Basins.
- Grades on the areas to be topsoiled, which have been previously established, shall be maintained, albeit 4" - 8" higher in elevation.
- Topsoil shall be uniformly distributed in a 4" - 8" layer and lightly compacted to a minimum thickness of 4". Spreading shall be performed in such a manner that sodding or seeding can proceed with a minimum of additional soil preparation and tillage. Any irregularities in the surface resulting from topsoiling or other operations shall be corrected in order to prevent the formation of depressions or water pockets.
- Topsoil shall not be placed while the topsoil or subsoils is in a frozen or muddy condition, when the subsoils is excessively wet or in a condition that my otherwise be detrimental to proper grading and seedbed preparation.

MGWC 1.2: PUMP-AROUND PRACTICE

Temporary measure for dewatering in-channel construction sites

DESCRIPTION

The work shall consist of installing a temporary pump around and supporting measures to divert flow around in-stream construction sites.

IMPLEMENTATION SEQUENCE

Sediment control measures, pump-around practices, and associated channel and bank construction shall be completed in the following sequence (refer to Detail 1.2):

1. Construction activities including the installation of erosion and sediment control measures shall not begin until all necessary easement and/or right-of-ways have been acquired. Utilities should be marked in the field prior to construction. The contractor is responsible for any damage to existing utilities that may result from construction and should repair the damages at his/her own expense to the county's or utility company's satisfaction.

2. The contractor must notify the Maryland Department of the Environment or WMA sediment control inspector at least a minimum of 48 hours before beginning construction. Additionally, the contractor shall inform the local environmental protection and resource management inspection and enforcement division and the provider of local utilities a minimum of 48 hours before starting construction.

3. The contractor shall conduct a pre-construction meeting on site with the WMA sediment control inspector, the county project manager, and the engineer to review limits of disturbance, erosion and sediment control requirements, and the sequence of construction. The contractor shall stake out all limits of disturbance prior to the pre-construction meeting so they may be reviewed. The participants must also designate the contractor's staging areas and flag all trees within the limit of disturbance, which will be removed for construction access. Trees should not be removed within the limit of disturbance without approval from the WMA or local authority.

4. Construction shall not begin until all sediment and erosion control measures have been installed and approved by the engineer and the sediment control inspector. The contractor must stay within the limits of the disturbance as shown on the plans and minimize disturbance within the work area whenever possible.

5. Upon installation of all sediment control measures and approval by the sediment control inspector and the local environmental protection and resource management inspection and enforcement division, the contractor shall begin work at the upstream section and proceed downstream beginning with the establishment of stabilized construction entrances. In some cases, work may begin downstream if appropriate. The sequence of construction must be followed unless the contractor gets written approval for deviations from the WMA or local authority. The contractor shall only begin work in an area which can be completed by the end of the day including grading adjacent to the channel. At the end of each workday, the work area must be stabilized and the pump around removed from the channel.

6. Sandbag dikes shall be situated at the upstream and downstream ends of the work area as shown on the plans, and stream flow should be pumped around the work area. This pump shall discharge into a stable velocity dissipator made of riprap or sandbags.

7. Water from the work area must be pumped to a sediment filtering measure such as a dewatering basin, sediment bag, or other approved source. The measure shall be located such that the water drains back into the channel below the downstream sandbag dike.

8. Traversing a channel reach with equipment within the work area where no work is proposed shall be avoided. If equipment has to traverse such a reach for access to another area, then timber mats or similar measures shall be used to minimize disturbance to the channel. Temporary stream crossings shall be used only when necessary and only where noted on the plans or specified. (See Section 4, Stream Crossings, Maryland Guidelines to Waterway Construction).

9. All stream restoration measures must be installed as indicated by the plans and all banks graded in accordance with the grading plans and typical cross-sections. All grading must be stabilized at the end of each day with seed and mulch or seed and matting as specified on the plans.

10. After an area is completed and stabilized, the clean water dike must be removed. After the first sediment flush, a new clean water dike shall be established upstream from the old sediment dike. Finally, upon establishment of a new sediment dike below the old one, the old sediment dike shall be removed.

11. A pump around must be installed on any tributary or storm drain outfall, which contributes baseflow to the work area. This shall be accomplished by locating a sandbag dike at the downstream end of the tributary or storm drain outfall and pumping the stream flow around the work area. This water must discharge onto the same velocity dissipator used for the main stem pump around.

12. If a tributary is to be restored, construction should take place on the tributary before work on the main stem reaches the tributary confluence. Construction in the tributary, including pump around practices, shall follow the same sequence as for the main stem of the river or stream. When construction on the tributary is completed, work on the main stem shall resume. Water from the tributary shall continue to be pumped around the work area in the main stem.

13. The contractor is responsible for providing access to and maintaining all erosion and sediment control devices until the sediment control inspector approves their removal.

14. After construction, all disturbed areas must be regraded and revegetated as per the planting plan.

NO.	REVISIONS DESCRIPTION	DATE

936 RIDGEBROOK ROAD  
SPARKS, MARYLAND 21152  
TELEPHONE: (410) 316-7800  
FAX: (410) 316-7818  
WWW.KCI.COM



HI TECH DRIVE  
STREAM RESTORATION  
PATAPSCO VALLEY BUSINESS CENTER  
SECTION 3, AREA 3  
HOWARD COUNTY DEPARTMENT OF RECREATION AND PARKS  
STORMWATER MANAGEMENT DIVISION  
6751 COLUMBIA GATEWAY DRIVE  
COLUMBIA, MARYLAND 21046  
PARCEL IDENTIFICATION: 18-03-01-0001-0001  
HOWARD COUNTY, MARYLAND

EROSION AND  
SEDIMENT  
CONTROL  
NOTES

SCALE:	N/A
DATE:	NOVEMBER 8, 2010
KCI JOB NO.:	01-043223.26
CAPITAL PROJECT NO.:	D - 1122
PERMIT ISSUE:	
CONSTRUCTION ISSUE:	

PROFESSIONAL CERTIFICATION. I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 39311. EXPIRATION DATE: JANUARY 06, 2012.

APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

*John K. Bluteau* 3/9/11  
CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

*Keith Schuch* 3/10/11  
CHIEF, DIVISION OF LAND DEVELOPMENT DATE

*Thomas E. Beutler* 3/10/11  
DIRECTOR DATE

Reviewed for HOWARD SCD and meets Technical Requirements.

This development plan is approved for soil erosion and sediment control by the HOWARD SOIL CONSERVATION DISTRICT.


*John K. Bluteau*  
HOWARD SCD  
Date: 2/24/11

PLOTTED: 11:10 AM on Monday, January 03, 2011  
BY: Howard County Dept. of Planning and Zoning  
FILE: 01-043223.26\_SDP-10-095.dwg





MATCH LINE A-A (SEE SHEET 18)



NO.	REVISIONS DESCRIPTION	DATE

936 RIDGEBROOK ROAD  
 SPARKS, MARYLAND 21152  
 TELEPHONE: (410) 316-7800  
 FAX: (410) 316-7818  
 www.kci.com

HI TECH DRIVE  
 STREAM RESTORATION  
 PATAPSCO VALLEY BUSINESS CENTER  
 SECTION 3, AREA 3  
 HOWARD COUNTY DEPARTMENT OF RECREATION AND PARKS  
 STORMWATER MANAGEMENT DIVISION  
 6751 COLUMBIA GATEWAY DRIVE  
 COLUMBIA, MARYLAND 21046  
 PARCEL 285-TAX MAP 38, ZONING M-2  
 HOWARD COUNTY, MARYLAND

**LANDSCAPE PLAN**

SCALE: 0 0.25 0.5 1.0 INCHES  
 1" = 20'

DATE: NOVEMBER 8, 2010  
 KCI JOB NO.: 01-043223.26  
 CAPITAL PROJECT NO.: D - 1122  
 PERMIT ISSUE:  
 CONSTRUCTION ISSUE:

SHEET NO.: 19 OF 25

PROFESSIONAL CERTIFICATION. I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 36311. EXPIRATION DATE: JANUARY 06, 2012.

APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

*John J. ...* 3/9/11  
 CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE

*Kent ...* 3/10/11  
 CHIEF, DIVISION OF LAND DEVELOPMENT DATE

*Thomas E. ...* 3/10/11  
 DIRECTOR DATE



- LEGEND**
- LIVE STAKES ZONE
  - RIPARIAN ZONE
  - TURF ZONE
  - FLOODPLAIN ZONE







MATCH LINE A-A (SEE SHEET 22)



MATCH LINE B-B (SEE SHEET 24)

NOTE:  
SEE SHEET 25 OF 25 FOR ADDITIONAL INFORMATION REGARDING THE FOREST CONSERVATION PLAN.

**LEGEND**

PROPERTY LINES	---	EXISTING FOREST CONSERVATION EASEMENT (FCE)	---
EXISTING ROAD EDGE	---	FOREST STAND TREELINE	---
EXISTING SEWER LINE	---	SPECIMEN TREE WITH CRITICAL ROOT ZONE	⊙
EXISTING MINOR CONTOURS	---	SPECIMEN TREE TO BE REMOVED	⊗
EXISTING MAJOR CONTOURS	---	15 TO 25% SLOPES	---
PROPOSED MINOR CONTOURS	---	25% AND STEEPER SLOPES	---
PROPOSED MAJOR CONTOURS	---	STUDY AREA BOUNDARY (LIMITS OF DISTURBANCE)	---
EXISTING EASEMENTS	---	TREE PROTECTION FENCING	---
WATERS OF THE UNITED STATES	WUS	EXISTING FCE FOREST CLEARING IMPACTS	---
STREAM BUFFER	---	FOREST TO BE CLEARED	---
EXISTING NONTIDAL WETLAND	---		
25-FOOT NONTIDAL WETLAND BUFFER	---		
SOILS BOUNDARY AND MAP UNIT LABELS	RUB		
EXISTING/PROPOSED 100-YR WSE*	---		

\*MINIMAL CHANGES BETWEEN EXISTING AND PROPOSED 100-YR WSE. SEE THE HI TECH DRIVE STREAM HYDROLOGY AND HYDRAULICS REPORT FOR FURTHER INFORMATION.

STATE OF MARYLAND  
KATHY J. MILLER  
PROFESSIONAL ENGINEER  
No. 88311  
EXPIRES 12/31/12

APPROVED: HOWARD COUNTY DEPT. OF PLANNING AND ZONING

Chief, Development Engineering Division: *[Signature]* 3/9/11  
 Chief, Division of Land Development: *[Signature]* 3/10/11  
 Director: *[Signature]* 3/10/11

THIS PLAN WAS PREPARED BY  
 HARMONY MILLER  
 KCI TECHNOLOGIES  
 MINOR QUALIFIED PROFESSIONAL STATUS  
 (2/21/2008)

*[Signature]* 04 JAN 2011  
 SIGNATURE DATE

NO.	REVISIONS DESCRIPTION	DATE

936 RIDGEBROOK ROAD  
 SPARKS, MARYLAND 21152  
 TELEPHONE: (410) 316-7800  
 FAX: (410) 316-7818  
 WWW.KCI.COM

HI TECH DRIVE  
 STREAM RESTORATION  
 PATAPSCO VALLEY BUSINESS CENTER  
 SECTION 3, AREA 3  
 HOWARD COUNTY DEPARTMENT OF RECREATION AND PARKS  
 STORMWATER MANAGEMENT DIVISION  
 6751 COLUMBIA GATEWAY DRIVE  
 COLUMBIA, MARYLAND 21046  
 PARCEL SELECTOR: 01-043223.26 ZONING: M-2  
 HOWARD COUNTY, MARYLAND

**FOREST CONSERVATION PLAN**

SCALE: 0 0.25 0.5 1 2 10 INCHES  
 1" = 20'

DATE: NOVEMBER 8, 2010  
 JOB NO: 01-043223.26  
 CAPITAL PROJECT NO: D - 1122  
 PERMIT ISSUE:  
 CONSTRUCTION ISSUE:

SHEET NO.: 23 OF 25  
 SDP-10-095



