

2 NO FLOOR

ARLINGTON

ELEVATION


REAR

FRONT

PLAN

19T FLOOR

BASEMENT



2. Length - As effective, but not less than 30 feet.

3. Thickness - Not less than eight (8) inches.

REAR

FRONT


PLAN

GARAGE

4. Width - Not less than full width of all points of ingress or egress. 5. Washing - When necessary, wheels shall be cleaned to remove sediment prior to entrance onto public right-of-way. When washing is required, it shall be done on an area stabilized with crushed stone which drains into an approved sediment trap or sediment basis. All sediment shall be prevented from entering any storm drain, ditch, or watercourse through use of sand bags, gravel, boards or other approved methods.

6. Maintenance - The entrance shall be maintained in a condition which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair and/or cleanout of any measures used to trae sediment. All sediment spilled, dropped, washed or tracked onto public rights-of-way must be removed immediately.

STABILIZED CONSTRUCTION



FENCE: WOVEN WIRE, 14 M GA.

MIRIFI 100X

LAUREL EROSION

CONTROL CLOTH

BIDIM POLYFILTER X OR EQUAL

FILTER CLOTH: FILTER X

MAX G' MESH OPENING.

46 MIN. FENCE POST-MESH STACING WITH FILTER CLOTH SECTION

CONSTRUCTION NOTES

WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE 7. FILTER CLOTH TO BE PRETENED SECURELY TO WOVEN WIRE FENCE WITH WIRE THES SPACED EVERY 74" AT TOP AND MID SECTION

* DRAINAGE AREA LESS THAN YE ACRE

2 PLOOP

IN PLOOR

ELEVITION


REAR 4.58

REAR 4.95

HOUSE SCHEMATICS


PLANS

SILT FENCE



NO SCALE





DRIVEWAY APRON DETAIL

GENERAL NOTES

- 1. SEDIMENT CONTROL PLAN AND STORM WATER MANAGEMENT POND FOR HERITAGE
- WOODS SECT. I AREA ! HAS BEEN APPROVED UNDER F-83:05 2. A MINIMUM OF 24 HOURS NOTICE MUST BE GIVEN TO THE HOWARD COUNTY OFFICE OF INSPECTION AND PERMITS PRIOR TO THE START OF ANY CONSTRUCTION
- (992-2070). 3. ALL SEDIMENT CONTROL STRUCTURES WILL BE INSTALLED IN ACCORDANCE WITH "THE STANDARDS AND SPECIFICATIONS FOR SOIL EROSIONS AND SEDIMENT CON-
- TROL IN DEVELOPING AREAS" AS PREPARED BY THE U.S. DEPARTMENT OF AGRI-CULTURE SOIL CONSERVATION SERVICE. 4. SITE GRADING WILL BEGIN ONLY AFTER ALL PERIMETER SEDIMENT CONTROL
- MEASURES HAVE BEEN INSTALLED AND ARE IN A FUNCTIONING CONDITION. ALL DISTURBED AREAS ARE TO BE DRESSED AND STABILIZED ACCORDING TO THE PERMANENT SEEDING SCHEDULES AS SOON AS PROPER WEATHER CONDITIONS
- EXIST FOR THE ESTABLISHMENT OF A PERMANENT VEGETATIVE COVER. 6. FERTILIZER AND LIME RATES MAY BE CHANGED THROUGH AUTHORIZATION BY THE HOWARD SOIL CONSERVATION DISTRICT IF SOIL TESTS DETERMINE A REDUCTION
- IN THE SPECIFIED RATES IS JUSTIFIED. REFERENCES CALLED FOR ON THE SEDIMENT CONTROL CONSTRUCTION PLAN AND DETAILS ARE MADE TO "THE STANDARDS AND SPECIFICATIONS FOR SOIL EROSION
- AND SEDIMENT CONTROL IN DEVELOPING AREAS." 8. ON SITE INSPECTION AND MAINTENANCE OF ALL SEDIMENT CONTROL MEASURES
- AND PROPER ESTABLISHMENT OF ALL PLANNED VEGETATIVE MEASURES WILL BE THE RESPONSIBILITY OF THE DEVELOPER OR HIS REPRESENTATIVE ON THE SITE. ON A CONTINUING DAY TO DAY BASIS. 9. THE CONTRACTOR SHALL KEEP ALL PUBLIC ROADS FREE OF SEDIMENT DEPOSITS
- LEFT FROM TRAFFIC LEAVING CONSTRUCTION SITE. 10. FOLLOWING INITIAL SOIL DISTURBANCE OR REDISTURBANCE, PERMANENT OR
- TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN: 1) 7 CALENDAR DAYS FOR ALL PERIMETER SEDIMENT CONTROL STRUCTURES, DIKES, SWALES, DITCHES, PERIMETER SLOPES AND ALL SLOPES GREATER THAN 3:1; 2) 14 DAYS AS TO ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE.

PERMANENT SEEDING

FINAL STABILIZATION WILL TAKE PLACE AS SOON AS POSSIBLE AS WEATHER CONDITIONS PERMIT. AS FOLLOWS:

- A. APPLY DOLOMITIC LIMESTONE AT THE RATE OF 2 TONS PER ACRE (ONE TON PER ACRE IF APPLICATION OF TON PER ACRE WAS MADE FOR TEMPORARY SEEDING).
- B. APPLY 0-20-20 FERTILIZER AT THE RATE OF 600 LBS. PER ACRE HARROW OR DISC LIME AND 0-20-20 FERTILIZER INTO THE SOIL TO A MINIMUM DEPTH OF 3" LAWNS OR HIGH MAINTENANCE AREAS WILL BE DRAGGED AND LEVELED WITH A YORK RAKE, AT THE TIME OF SEEDING APPLY 400 POUNDS OF 38-0-0 UREAFORM FERTILIZER AND 500 LBS. OF 10-20-20 OR EQUIVALENT FER-TILIZER PER ACRE.
- C. SEED WITH A MIXTURE OF CERTIFIED "MERION" KENTUCKY BLUEGRASS 40 LBS. PER ACRE: COMMON KENTUCKY BLUEGRASS @ 40 LBS. PER ACRE; RED FESCUE, PENNLAWN OR JAMESTOWN @ 20 LBS. PER ACRE.
- D. MULCH WITH UNWEATHERED SMALL GRAIN STRAW AT THE RATE OF 1 1/2 to 2 TONS PER ACRE AND ANCHOR WITH A CUTBACK ASPHALT OR EMULSIFIED ASPHALT AT THE RATE OF 5 GAL. PER 1000 SQ. FT.
- E. SEED ALL SLOPES WITH A MIXTURE OF CERTIFIED KENTUCKY 31 TALL FESCUE @ 50 LBS. PER ACRE AND INOCULATED KOREAN LESPEDEZA @ 15 LBS. PER ACRE.

APPROVED DIVISION OF LAND DEVELOPMENT & **ZOHING ADMINISTRATION** HOWARD COUNTY, MARYLAND DATE 8-17-84

SEQUENCE OF CONSTRUCTION

- OBTAIN A GRADING PERMIT INSTALL STABILIZED CONSTRUCTION ENTRANCE(S)
- INSTALL SEDIMENT CONTROL DEVICES AND STABILIZE IN ACCORDANCE WITH TEMP SEEDING NOTES COMPLETE SITE WORK AND STABILIZE ALL DISTURBED AREAS IN ACCORDANCE WITH
- PERMANENT SEEDING NOTES UPON APPROVAL OF THE SOIL CONSERVATION INSPECTOR, REMOVE SEDIMENT CONTROL

DEVICES AND STABILIZE ALL AREAS IN ACCORDANCE WITH PERMANENT SEEDING NOTES

APPROVED: FOR PUBLIC WATER AND PUBLIC SEMERAGE SYSTEMS, HOWARD COUNTY HEALTH DEPARTMENT BY THE DEVELOPER: "I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN, AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CER-TIFICATE OF ATTENDANCE AT A DEPARTMENT OF NATURAL RESOURCES APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT." 7.20.84 BY THE ENGINEER: "I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT 7.20.84 Howard REVIEWED FOR AND MEETS TECHNICAL REQUIREMENTS 8-31-84 SOIL CONSERVATION SERVICE THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT APPROVED: FOR PUBLIC WATER, PUBLIC SEWERAGE, STORM DRAINAGE SYSTEMS AND PUBLIC ROADS. HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS 9-6-84 DATE 9.5-84 CHIEF, BUREAU OF ENGINEERING DATE HOWARD COUNTY OFFICE OF PLANNING AND ZONING. 9-10-84 CHIEF, DIVISION OF LAND DEVELOPMENT AND ZONING NO DATE REVISION TRACY, SCHULTE & ASSOCIATES INC. planning • architecture • engineering PROJECT HERITAGE WOODS SECTION ONE AREA ONE LOTS 27 THRU 50. SECURITY DEVELOPMENT CORP 8450 BALTIMORE NATIONAL PIKE ELLICOTT CITY, MD 21043 LOCATION TAX MAP 42 6TH ELECTION DISTRICT HOWARD COUNTY, MARYLAND DEVELOPER SEDIMENT CONTROL SECURITY DEVELOPMENT CORP 845C BALTIMORE NATIONAL PIKE

NOTES & DETAILS

SCALE AS SHOWN

DATE JULY 20.1984 | PROJECT NO 0984 SDP

DRAWING ?

SDP # 85-11

ELLICOTT CITY, MD. 21043

DES. RJW

2 re-bars, steel pickets, or 2" x 2" stakes 1 1/3' to 2' AMCHORING DETAIL Cometruction Specifications shall be placed in a row with ends tightly abutting the hales shall be securely anchored in place by stakes or ra-bars driven through the bales. The first stake in each bale shall be angled toward previously laid bale to force bales together.

Impection shall be frequent and repair or replacement shall be ARDMORE 5. Bales shall be removed when they have served their usefulness so as not to block or impede storm flow or drainage. BASEMENT STRAW BALE DIKE ELEVATION CONCRETE ENTRANCE