



CONSTRUCTION SPECIFICATIONS:
 Bales shall be stacked at the top of a slope or on the contour and in a row with ends tightly abutting the adjacent bales.
 Each bale shall be embedded in the soil a min. of 4" and placed so the bindings are horizontal.
 Bales shall be securely anchored in place by either 2 stakes or re-bars driven thru the bale. The 1st stake in each bale shall be driven forward the previously laid bale at an angle to force the bales together. Stakes shall be driven flush with the bales.
 Inspection shall be frequent and repair replacement shall be made promptly as needed.
 Bales shall be removed when they have served their usefulness so as not to block or impede storm flow or drainage.

STRAW BALE DIKE DETAIL (SBD)
 NO SCALE




CONSTRUCTION SPECIFICATIONS:
 Woven wire fence to be fastened securely to fence posts with wire ties or staples.
 Filter cloth to be fastened securely to woven wire fence with ties spaced every 24" at top and mid section.
 When 2 sections of filter cloth adjoin each other they shall be overlapped by 6" and stapled.
 Maintenance shall be performed as needed and material removed when "bulges" develop in silt fence.
 POSTS: Steel either T or U Type or 2" Hardwood.
 FENCE: Woven Wire, 1/4" Gauge, 6" Max. Mesh Opening.
 FILTER CLOTH: Filter, 100% 100% Silt/Lime/TAN or Approved.
 PREFABRICATED UNIT: Geo-Fab or Reference, or Approved equal.


SILT FENCE DETAIL (S)
 NO SCALE



DRIVEWAY ABUTTING STD. 7" COMB. CURB & GUTTER
 No Scale




TYPICAL HOUSE
 NO SCALE



CONSTRUCTION SPECIFICATIONS:
 1. Stone size - Use 2" stone or reclaimed or recycled concrete equivalent.
 2. Length - As required, but not less than 50 feet, except on a single residence lot where a 30 foot minimum length would apply.
 3. Thickness - Not less than six (6) inches.
 4. Width - Ten (10) foot minimum, but not less than the full width of points where ingress or egress occurs.
 5. Filter Cloth - Will be placed over the entire area prior to placing of stone. Filter will not be required on a single family residence lot.
 6. Surface Water - All surface water flowing or diverted toward construction entrances shall be piped across the entrance. If piping is impractical, a mountable berm with 5:1 slopes will be permitted.
 7. Maintenance - The entrance shall be maintained in a condition which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair and/or clearing of any measures used to trap sediment. All sediment applied, dropped, washed or tracked onto public rights-of-way must be removed immediately.
 8. Washing - Wheels shall be cleaned to remove sediment prior to entrance onto public rights-of-way. When washing is required, it shall be done on an area stabilized with stone and which drains into an approved sediment trapping device.
 9. Periodic inspection and needed maintenance shall be provided after each rain.

STABILIZED CONSTRUCTION ENTRANCE (SCE)
 NO SCALE



PERMANENT SEEDING NOTES
 Apply to graded or cleared areas not subject to immediate further disturbance where a permanent long-lived vegetative cover is needed.
Seedbed Preparation: Loosen upper three inches of soil by raking, discing or other acceptable means before seeding.
Soil Amendment: In lieu of soil test recommendations, use one of the following schedules:
 1) Preferred - Apply 2 tons per acre dolomitic limestone (92 lbs/1000 sq ft) and 500 lbs per acre 10-10-10 fertilizer (14 lbs/1000 sq ft) before seeding. Harrow or disc into upper three inches of soil. At time of seeding, apply 400 lbs per acre 30-0-0 ureaform fertilizer (9 lbs/1000 sq ft).
 2) Acceptable - Apply 2 tons per acre dolomitic limestone (92 lbs/1000 sq ft) and 1000 lbs per acre 10-10-10 fertilizer (23 lbs/1000 sq ft) before seeding. Harrow or disc into upper three inches of soil.

Seeding - For the periods March 1 thru April 30, and August 1 thru October 15, seed with 60 lbs per acre (1.4 lbs/1000 sq ft) of Kentucky 31 Tall Fescue. For the period May 1 thru July 31, seed with 60 lbs Kentucky 31 Tall Fescue per acre and 2 lbs per acre (.05 lbs/1000 sq ft) of weeping lovegrass. During the period of October 16 thru February 28, protect site by: Option (1) 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring. Option (2) Use sod. Option (3) Seed with 60 lbs/acre Kentucky 31 Tall Fescue and mulch with 2 tons/acre well anchored straw.
Mulching - Apply 1 1/2 to 2 tons per acre (70 to 90 lbs/1000 sq ft) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gallons per acre (5 gal/1000 sq ft) of emulsified asphalt on flat areas. On slopes 8 feet or higher, use 348 gallons per acre (8 gal/1000 sq ft) for anchoring.

TEMPORARY SEEDING NOTES
 Apply to graded or cleared areas likely to be redisturbed where a short-term vegetative cover is needed.
Seedbed Preparation: Loosen upper three inches of soil by raking, discing or other acceptable means before seeding.
Soil Amendment: Apply 600 lbs per acre 10-10-10 fertilizer (14 lbs/1000 sq ft).
Seeding: For periods March 1 thru April 30 and from August 15 thru November 15, seed with 25 bushel per acre of annual ryegrass (3.2 lbs/1000 sq ft). For the period May 1 thru August 14, seed with 3 lbs per acre of weeping lovegrass (.07 lbs/1000 sq ft). For the period November 16 thru February 28, protect site by applying 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring, or use sod.
Mulching: Apply 1 1/2 to 2 tons per acre (70 to 90 lbs/1000 sq ft) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gal per acre (5 gal/1000 sq ft) of emulsified asphalt on flat areas. On slopes, 8 ft or higher, use 348 gal per acre (8 gal/1000 sq ft) for anchoring.

Refer to the 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for rate and methods not covered.


GENERAL NOTES:
 1. The Land included in this plan is zoned: R-20.
 2. All coordinates are extensions made from the Maryland State Plane Coordinate System. Bearings refer to true north and are based on the Maryland Bureau of Control Surveys Point "Columbia Resert 1966" N121095.04 E 846139.78.
 3. Tax Map No. 42.
 4. All Roadways are Public & Existing.
 5. Any damage to county owned rights of way shall be corrected at the Developer's expense.
 6. Total No. of Lots: 1
 7. Storm Water Management provided in Central Facility. See Dorsey Hall, Section 3, Area 1, F-81-27.
 NOTE: Approved Road Construction Plans shall be used for installation of Public Utilities. Public Water and Sewer shown for reference only. See Water & Sewer Plans, Cont. 24-0264-D.

LEGEND:
 1. Contour Interval 2' F.
 2. Existing Contour - 570
 3. Proposed Contour - 570
 4. Spot Elevation +705
 5. Direction of Drainage
 6. Ex. Trees to be Saved
 7. Straw Bale Dike or Silt Fence SBD/S
 8. Stabilized Construction Entrance SCE

CONSTRUCTION SEQUENCE:

CONSTRUCTION SEQUENCE:	No. of Days
A. Obtain Grading Permit and Install Sediment and Erosion Control Devices and Stabilize.	5
B. Excavate for Foundations and Rough Grade.	10
C. Construct Structures, Sidewalks and Driveways.	40
D. Final Grade and stabilize in accordance with Stds. & Specs.	10
E. Upon approval of the sediment control inspector, remove sediment and erosion control and stabilize.	5

1) A minimum of 24 hours notice must be given to the Howard County Office of Inspection and Permits prior to the start of any construction. (992-24377)
 2) All negative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL.
 3) Following initial soil disturbance or redisturbance, permanent or temporary stabilization shall be completed within: a) 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all slopes greater than 3:1, b) 14 days as to all other disturbed or graded areas on the project site.
 4) All sediment traps/basins shown must be fenced and warning signs posted around their perimeter in accordance with Vol. 1, Chapter 12, of the HOWARD COUNTY DESIGN MANUAL, Storm Drainage.
 5) All disturbed areas must be stabilized within the time period specified above in accordance with the 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for permanent seedings (Sec. 51) and (Sec. 52), temporary seedings (Sec. 50) and mulching (Sec. 52.) Temporary stabilization with mulch alone can only be done when recommended seeding dates do not allow for proper permission and establishment of grasses.
 6) All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.
 7) Site Analysis:
 Total Area of Site 0.3404 Acres
 Area Disturbed 0.2863 Acres
 Area to be roofed or paved 0.0728 Acres
 Area to be vegetatively stabilized 0.1755 Acres
 Total Cut 608 Cu. yds
 Total Fill 44 Cu. yds
 Offsite waste/borrow area location N/A
 8) Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
 9) Additional sediment control must be provided, if deemed necessary by the Howard County DMW sediment control inspector.
 10) On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the inspection agency is made.
 11) If houses are to be constructed on an "As-Sold" basis, at random, Single Lot Sediment Control as shown below shall be implemented. N/A
 12) All pipes to be blocked at the end of each day (see detail below). N/A
 13) The total amount of straw bale dikes/silt fence equals 210 L.F.



LOT NO.	STREET	ADDRESS
347	4213	Purple Twilight Way

SUBDIVISION NAME	SECT. T/AREA	LOT/PARCEL #
DORSEY HALL	1/5	347

PLAT # or L.P.	BLOCK #	ZONE	TAX ZONE	MAP FILE	ELEC. DIST.	CENSUS TR.
4877	21	R-20	2A	2ND	0223-01	

WATER CODE	SEWER CODE
FO8	5830000

Reviewer for: Howard S.C.I.
 Name: [Signature]
 Add. State Technical Requirements: B-1-85
 Date: [Signature]
 U.S. Conservation Service
 THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD COUNTY ENGINEER DISTRICT.
 Approved: [Signature] Date: 7-19-85

APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE SYSTEMS, HOWARD COUNTY HEALTH DEPARTMENT
 COUNTY HEALTH OFFICER: [Signature] DATE: 7-19-85
 APPROVED: HOWARD COUNTY OFFICE OF PLANNING & ZONING
 PLANNING DIRECTOR: [Signature] DATE: 7-19-85
 CHIEF DIVISION OF LAND DEVELOPMENT AND ZONING ADMINISTRATION
 APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE, STORM DRAINAGE SYSTEMS AND PUBLIC ROADS, HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
 DIRECTOR: [Signature] DATE: 8-5-85
 CHIEF BUREAU OF ENGINEERING: [Signature] DATE: [Signature]

DEVELOPER'S/BUILDER'S CERTIFICATE
 I hereby certify that all development and construction will be done according to the plan filed with and approved for erosion and sediment control and that all erosion and sediment control measures involved in the construction project will have a Certificate of Approval from the Dept. of Natural Resources Approval. I hereby authorize periodic on-site inspection by the Howard County Conservation District or their authorized agents, as are deemed necessary.
 Signature of Developer/Builder: [Signature] Date: 6-26-86
ENGINEER'S CERTIFICATE
 I hereby certify that this plan for Erosion and Sediment Control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District.
 Signature of Engineer: [Signature] Date: 6-24-85

CLARK • FINEFROCK & SACKETT
 ENGINEERS • PLANNERS • SURVEYORS
 11315 LOCKWOOD DRIVE • SILVER SPRING, MARYLAND 20904 • (301) 593-3400
SITE DEVELOPMENT AND SEDIMENT & EROSION CONTROL PLAN
 LOT 347
DORSEY HALL
 SECTION 1 AREA 5
 2ND ELECTION DISTRICT
 HOWARD COUNTY, MARYLAND
 FOR: JOEL MOSTROM
 116 Kettle Court
 Baltimore, Md. 21207
 DATE: JUNE '85
 SCALE: AS SHOWN
 DRAWING: 10/1
 JOB NO.: 85-064
 FILE NO.: 85-064-X
 S.D.P. 85-237