

GENERAL NOTES




- All materials and construction to be in accordance with the Howard County Road Construction Code and Specifications.
- This plan is covered by Final Development Plan: Phase 199-A
- Any damage to county owned rights-of-way shall be corrected at the developer's expense.
- Installation of Traffic Control Devices shall be in accordance with the latest edition of the "Manual of Uniform Traffic Control Devices"
- Topography was compiled from field survey
- All Coordinates are based on Howard County Geodetic Control Traverse which is based on the Maryland State Plane Coordinate System.
- Information concerning underground utilities was obtained from available records, but the contractor must determine the exact location and elevation of mains by digging test pits, by hand, at all utility crossings well in advance of construction.
- The contractor or developer shall contact the Construction Inspection/Survey Division 24 hrs in advance of commencement of work at 792-2690.
- All downspouts shall be handled by one of the following methods:
 - Downspout to splash blocks and discharged to ground having good percolation.
 - Downspout in front of units, piped to curb.
 - Downspout connected to storm drain.
- The developer agrees to work with the Department of Licenses and Inspections to resolve any problems caused by roof water discharge.
- This plan is subject to Water Quality Certification 88-040.
- Stormwater Management Quantity Control has been waived for this project. See F-88-151.
- See Howard County Office of Planning & Zoning File No's: 8-88-59C; WP-88-85; F-88-56; F-89-05; F-89-175; WP-89-119.

SITE ANALYSIS

- Area of Parcel: 6.006 Acres
- Zoning: New Town Apartments
- Ho. Co. Files: S-88 59 (Sketch Plan) WP-88 85 P.Plan Variance FDP Phase 199-A
- No Units Permitted: 38
- No Units Proposed: Condominium Townhouses 36
- Parking Spaces Required: 72
- Parking Spaces Provided: Private Parking (4/Unit)* 144
Guest Parking Areas 14
Total 158
- * Two on Driveways and Two in Double Garage.
- Green Area Provided: 2.6 Acres
- Building Coverage Permitted: No Limit
- Building Coverage Proposed: 1.7 Ac. or 28%

SHEET No.	DRAWING INDEX
1 OF 13	SITE DEVELOPMENT PLAN
2 OF 13	REVISED SITE DEVELOPMENT PLAN
3 OF 13	SITE DEVELOPMENT PLAN & SEWER PROFILES
4 OF 13	SITE DEVELOPMENT PLAN STORM DRAIN PROFILES
5 OF 13	SITE DEVELOPMENT PLAN PAVING DETAILS
6 OF 13	SITE DEVELOPMENT PLAN WATER QUALITY DETAILS
7 OF 13	SITE DEVELOPMENT PLAN DRAINAGE AREA MAP
8 OF 13	SEWERMENT & EROSION CONTROL PLAN
9 OF 13	SEWERMENT & EROSION CONTROL PLAN
10 OF 13	REVISED LANDSCAPE PLANTING PLAN
11 OF 13	LANDSCAPE PLANTING PLAN
12 OF 13	RETAINING WALL PLAN, PROFILES, & DETAILS
13 OF 13	RETAINING WALL SPECIFICATIONS

LEGEND



UNIT No.	STREET ADDRESS
1-C	5105 Harper's Farm Road
2-A	5107
3-A	5109
4-A	5111
5-A	5113
6-A	5115
7-B	5117
8-B	5119
9-C	5121
10-B	5123
11-A	5125
12-A	5127
13-A	5129
14-A	5131
15-A	5133
16-C	5137
17-A	5139
18-A	5141
19-B	5143
20-C	5147
21-A	5149
22-A	5151
23-B	5153
24-A	5155
25-A	5157
26-A	5159
27-A	5161
28-A	5163
29-B	5165
30-C	5167
31-A	5169
32-A	5171
33-A	5173
34-A	5175
35-A	5177
36-A	5179 Harper's Farm Road

Coordinates shown herein are based upon traverse controls for Columbia established by Maps Inc., in 1965 and by Purdom and Jeschke in 1968, which controls were tied to Maryland Bureau of Control Survey Monuments and to U.S. Coast and Geodetic Survey Monuments in the Columbia area.

No.	REMOVE & REPLACE EXIST RETAINING WALL	DATE
Δ		4/17/18

APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE SYSTEMS, HOWARD COUNTY HEALTH DEPARTMENT
 COUNTY HEALTH OFFICER: [Signature] DATE: 7-3-89

APPROVED: HOWARD COUNTY OFFICE OF PLANNING & ZONING
 PLANNING DIRECTOR: [Signature] DATE: 7-19-89
 CHIEF, DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT: [Signature] DATE: 5/11/85

APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE, STORM DRAINAGE SYSTEMS AND PUBLIC ROADS, HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
 DIRECTOR: [Signature] DATE: 6-30-89
 CHIEF BUREAU OF ENGINEERING: [Signature] DATE: 7-5-89

APPROVED: DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT
 HOWARD COUNTY, MARYLAND
 DATE: 3-29-89

SEE SHEET 2 OF 13 FOR RETAINING WALL LOCATION. SEE SHEETS 12 OF 13 AND 13 OF 13 FOR RETAINING WALL DETAILS.


Note: Extreme Care to be utilized when working in area of existing 26" Gas Line. Test pits to be dug by hand to locate main at all crossings well in advance of construction.

CLARK • FINEFROCK & SACKETT, INC.
 ENGINEERS • PLANNERS • SURVEYORS
 7135 MINSTREL WAY • COLUMBIA, MD. 21045 • (301) 381-7500 - BALTO. • (301) 621-8100 - WASH.

DESIGNED	JLS	SCALE	1"=30'
DRAWN	KIN	DRAWING	10F13
CHECKED	JLS	JOB NO.	87-119
DATE	1-10-89	FILE NO.	87-119 X

SITE DEVELOPMENT PLAN FOR CONDOMINIUM TOWNHOUSES PARCEL A-1 COLUMBIA VILLAGE OF HARPERS CHOICE TAX MAP #29 TAX MAP PARCELS 59460 5TH ELECTION DISTRICT HOWARD COUNTY, MARYLAND

OWNER/DEVELOPER: TALK'S HOMES AT HOBBITS GLEN CONDOMINIUM 16 BOX 250 SCUMPSVILLE, MD 21150 TUMS 410-313-8608



GENERAL NOTES



- All materials and construction to be in accordance with the Howard County Road Construction Code and Specifications.
- This plan is covered by Final Development Plan: Phase 199-A
- Any damage to county owned rights-of-way shall be corrected at the developer's expense.
- Installation of Traffic Control Devices shall be in accordance with the latest edition of the "Manual of Uniform Traffic Control Devices"
- Topography was compiled from field survey
- All Coordinates are based on Howard County Geodetic Control Traverse which is based on the Maryland State Plane Coordinate System.
- Information concerning underground utilities was obtained from available records, but the contractor must determine the exact location and elevation of mains by digging test pits, by hand, at all utility crossings well in advance of construction.
- The contractor or developer shall contact the Construction Inspection/Survey Division 24 hrs in advance of commencement of work at 792-2850.
- All downspouts shall be handled by one of the following methods:
 - Downspout to splash blocks and discharged to ground having good percolation.
 - Downspout in front of units, piped to curb.
 - Downspout connected to storm drain.
- The developer agrees to work with the Department of Licenses and Inspections to resolve any problems caused by roof water discharge.
- This plan is subject to Water Quality Certification 88-040
- Stormwater Management Quantity Control has been waived for this project. See F-88-151.
- See Howard County DEPT. of Planning & Zoning File No.'s: B-88-50C; WP-88-85, F-88-56; F-89-05; F-89-175.

SITE ANALYSIS


	(Previously approved SDP Sheet 10P9)	(Revised Site Analysis SDP Sheet 1A of 3)
1. Area of Parcel:	6.006 Acres	No Change
2. Zoning:	New Town Apartments	
3. Ho. Co. Files:	S-88-59 (Sketch Plan) WP-88-85 P.Plan Variance FDP Phase 199-A	
4. No. Units Permitted:	38	34 (units 3-36)
5. No. Units Proposed:	Condominium Townhouses	34
6. Parking Spaces Required:	72	68 (2sp/unit)
7. Parking Spaces Provided:	Private Parking (4/Unit)* Guest Parking Areas Total	136 (4sp/unit) 14 150
8. Green Area Provided:	2.6 Acres	No Change
9. Building Coverage Permitted:	No Limit	
10. Building Coverage Proposed:	1.7 Ac. or 28%	

No.	REVISION	DATE
1	REMOVES & REPLACES EXIST RETAINING WALL	4/17/89

LEGEND



UNIT No.	STREET ADDRESS
3	5109 HARPERS FARM ROAD
4	5111
5	5113
6	5115
7	5117
8	5119
9	5121
10	5123
11	5125
12	5127
13	5129
14	5131
15	5133
16	5137
17	5139
18	5141
19	5143
20	5147
21	5149
22	5151
23	5153
24	5155
25	5157
26	5159
27	5161
28	5163
29	5165
30	5167
31	5169
32	5171
33	5173
34	5175
35	5177
36	5179 Harper's Farm Road



APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE SYSTEMS.
HOWARD COUNTY HEALTH DEPARTMENT

Joyce M. Boyd M.P.E. DATE: 6-10-91
COUNTY HEALTH OFFICER

APPROVED: HOWARD COUNTY DEPT. OF PLANNING & ZONING




David H. Heltz DATE: 6/13/91
DIRECTOR

Walter J. M. ... DATE: 6/13/91
CHIEF DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT

APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE, STORM DRAINAGE SYSTEMS AND PUBLIC ROADS
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

Roman J. ... DATE: 6/6/91
DIRECTOR

... DATE: 6-5-91
CHIEF BUREAU OF ENGINEERING



Extreme care to be utilized when working in area of ex. 2.0" Gas Line. Test pits to be dug by hand to locate main at all crossings well in advance of construction.

NOTE: This plan supersedes previously approved sheet 10P9 for lots 3-36, SDP 88-135. The grading on this sheet supersedes the grading on sheet 7 of 9 & lots 9-36.

Subdivision Name:	COLUMBIA Village of Harpers Choice	Stot./Area	7/1	PARCEL	A-1
Plan No.:	B413	Block No.:	16 & 17	ZONE	APT'S
Water Code:	1-02	Sanitar Code:	6740000	Elec. Dist.:	5th
				Census Tr.:	6052.01

CLARK • FINEFROCK & SACKETT, INC.
ENGINEERS • PLANNERS • SURVEYORS

7135 MINSTREL WAY • COLUMBIA, MD 21045 • (301) 381-7500 - BALTO • (301) 621-8100 - WASH

DESIGNED: MJP
DRAWN: BAL
CHECKED: WHT
DATE: MAY 1, 1991

REVISED SITE DEVELOPMENT PLAN FOR CONDOMINIUM TOWNHOUSES UNITS 3-36 PARCEL A-1 COLUMBIA VILLAGE OF HARPERS CHOICE SECTION 7 AREA 1



5TH ELECTION DISTRICT HOWARD COUNTY, MARYLAND

FOR: TALLEY HOMES AT HARPERS CHOICE GREEN CAMPUS MOUNTAINS TO BOX 450 STEARNSVILLE, MD 21350 410-313-8503

SCALE: 1" = 30'
DRAWING: 2 OF 13
JOB NO.: 91-033
FILE NO.: 91-033 X


Note: Connect proposed endwall 6-1A to existing endwall. Place Rip Rap to meet existing concrete channel and extend rip rap to top of existing stream banks, as shown.

LIMIT OF DISTURBED AREA




SEWER PROFILES
 SCALES: HORIZ. 1"=50'
 VERT. 1"=5'

- WATER & SEWER NOTES**
- All Sewer Pipe shall be PVC, C.S.P.X, or V.C.P.X. unless otherwise noted.
 - All construction methods and materials for on-site private water and sewer systems shall follow the current edition of the Howard County Standard Plumbing Code, supplemented by the Howard County Standard Details and Specifications where necessary.
 - Areas where water house connections are to be built shall be at final grade and connections shall be laid with a minimum of 3'-5" of cover.
 - Sewer house connections shall be built to within 5 feet of buildings at 2% unless noted otherwise on plan.



PLAN
 SCALE: 1"=30'





APPROVED
 HOWARD COUNTY
 MARYLAND
 DATE: 3-29-89

APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE SYSTEMS, HOWARD COUNTY HEALTH DEPARTMENT
 COUNTY HEALTH OFFICER: [Signature] DATE: 7-3-89

APPROVED: HOWARD COUNTY OFFICE OF PLANNING & ZONING
 PLANNING DIRECTOR: [Signature] DATE: 7-19-89

APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE, STORM DRAINAGE SYSTEMS AND PUBLIC ROADS, HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
 DIRECTOR: [Signature] DATE: 6-30-89


CHIEF BUREAU OF ENGINEERING: [Signature] DATE: 7-5-89



DEVELOPER'S CERTIFICATE

"I/We certify that all development and construction will be done according to this plan of development and plan for erosion and sediment control and that all responsible personnel involved in the construction project will have a Certificate of Attendance at a Dept. of Natural Resources Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District or their authorized agents, as and deemed necessary."

[Signature] DATE: 1-10-89



ENGINEER'S CERTIFICATE

"I hereby certify that this plan for Erosion and Sediment Control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District."

[Signature] DATE: 1-10-89

Reviewed for: Howard S.C.D.
 Name: [Signature]
 and meets Technical Requirements
 Signature: [Signature] DATE: 6/22/89
 U.S. Soil Conservation Service
 THE DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.
 [Signature] DATE: 6/22/89

CLARK • FINEFROCK & SACKETT, INC. ENGINEERS • PLANNERS • SURVEYORS 7135 MINSTREL WAY • COLUMBIA, MD. 21045 • (301) 381-7800 - BALTO. • (301) 621-8100 - WASH.		SCALE: As Shown
DESIGNED	JLS	SITE DEVELOPMENT PLAN & SEWER PROFILES PARCEL 2-1 COLUMBIA VILLAGE OF HARPERS CHOICE TAX MAP # 29 TAX MAP PARCEL # 59460 5TH ELECTION DISTRICT HOWARD COUNTY, MARYLAND OWNER/DEVELOPER: TAILOR'S HOMES AT HOBBS (L&J) COMPANY: 410-312-8608
DRAWN	KIW	
CHECKED	JLB	
DATE	1-10-89	
FILE NO.	87-119-X	

STRUCTURE SCHEDULE A



NO.	TYPE	INV. IN	INV. OUT	TOP ELEVATION		REMARKS	LOCATION
				UPPER	LOWER		
S-1A	C-Endwall	415.836	415.636	-	420.03	No. Co. Std. SD 5-21 42"Ø	See Plan
I-1	D-Inlet	418.72	417.82	18.70	426.33 24.92	See Detail	4'x5'
I-2	D-Inlet	421.64	421.42	428.35 00	See Detail	4'x5'	"
M-2A	Shallow Brick Manhole	422.36	422.36	427.85 78	No. Co. Std. G 5-05	4'x5'	"
I-3	D-Inlet	423.00	422.88	429.33 26.64	See Detail	4'x5'	"
M-4	Shallow Brick Manhole	428.00	427.90	434.00	No. Co. Std. G 5-05	4'x4'	"
FC-4A	Field Connection	-	-	-	36"X16" CMP Tee 16ga.	"	"
FC-5	Field Connection	-	-	-	36"X15" CMP Tee 16ga.	"	"
M-6	Precast Manhole	437.01	436.91	445.95	No. Co. Std. G 5-13 5'RD	4 Str. Sta. 13159	1' Lt.
FC-6A	Field Connection	-	-	-	No. Co. Std. SD 2-01 15"X36"	See Plan	"
M-7	Precast Manhole	438.77	438.55	450.80	No. Co. Std. G 5-13 5'RD	4 Str. Sta. 10124	3' Rt.
I-8	D-Inlet	439.77	439.782	450.33 49.42	See Detail	4'x4'	See Plan
I-9	D-Inlet	-	441.00	440.32 448.33 47.72	See Detail	4'x4'	See Plan
I-10	A-5 Inlet w/Deflectors	-	442.00	451.19	See Def. Water Quality Control Str.	4 Str. Sta. 15178	8' Rt.
I-11	A-5 Inlet	-	440.00	448.50	" " " "	" " " "	" " " "
I-12	A-10 Inlet	-	438.40	445.90	" " " "	4 Str. Sta. 13178	12' Lt.
I-13	A-10 Inlet	428.00	427.59	431.98	" " " "	4 Str. Sta. 1189	12' Lt.
I-14	A-10 Inlet w/Deflectors	433.00	432.46	437.84 436.54	" " " "	" " " "	" " " "
M-15	Shallow Brick Manhole	439.46	439.36	444.00	No. Co. Std. G 5-05 48"Ø	4 Str. Sta. 4150	19.5' Rt.
I-16	D-Inlet	-	440.00	443.83	" " SD 4-11 W-2'6"	See Plan	"
I-17	A-10 Inlet	434.1	433.59	439.82 439.19	" " SD 4-02 W-2'6"	See Plan	"
I-17A	Ex. Inlet	424.21	423.56	420.33 20.40	No. Co. Std. SD 4-15 Y-2'7"	See Plan	"
I-17B	C-Inlet	421.07	420.82	424.00	No. Co. Std. SD 4-11 2'-6"Ø	See Plan	"
I-18	D-Inlet	-	428.20	431.83	No. Co. Std. SD 4-11 2'-6"Ø	See Plan	"

See Ho. Co. Std. SD 4-83 for Inlet Deflectors
 * Provide Slots in all Sides
 Δ All Inverts to be fully developed.
 ○ Convert Ex. Inlet to a D-Inlet. See Ho. Std. SD. 4-11 for top slab and slots.
 □ Construct Inlet to meet ex curb & gutter.

PIPE SCHEDULE


SIZE	TYPE	LENGTH
15"	CMP 16ga.	104 LF
15"	RCP CL II	160 LF
15"	RCP CL II	148 LF
18"	RCP CL II	135 LF
30"	RCP CL II	44 LF
36"	RCP CL II	333 LF
36"	CMP 16ga.	278 LF
42"	RCP CL II	276 LF
42"	RCP CL II	148 LF

* 2 1/2" x 1/2" Corrugations.



STORM DRAINAGE PROFILES

SCALES: HORIZ. 1"=50'
 VERT. 1"=5'



APPROVED
 DIVISION OF COMMUNITY PLANNING & LAND DEVELOPMENT
 HOWARD COUNTY, MARYLAND
 DATE: 3-29-89

APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE SYSTEMS.
 HOWARD COUNTY HEALTH DEPARTMENT
 COUNTY HEALTH OFFICER: [Signature] 7-3-89
 DATE: 7-3-89

APPROVED: HOWARD COUNTY OFFICE OF PLANNING & ZONING
 PLANNING DIRECTOR: [Signature] 7-19-89
 DATE: 7-19-89

CHIEF, DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT.
 DATE: 6-30-89

APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE, STORM DRAINAGE SYSTEMS AND PUBLIC ROADS
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
 DIRECTOR: [Signature] 7-5-89
 DATE: 7-5-89

CHIEF BUREAU OF ENGINEERING

Reviewed for: Howard S.C.D.
 and meets Technical Requirements
 Signature: [Signature] Date: 6/22/89
 U.S. Soil Conservation Service

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

Signature: [Signature] Date: 6/22/89
 Approved

DEVELOPER'S/BUILDER'S CERTIFICATE
 I/We certify that all development and construction will be done according to this plan of development and plan for erosion and sediment control and that all responsible personnel involved in the construction project will have a Certificate of Attendance at a Dept. of Natural Resources Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District as their authorized agents, as herein provided.

Signature: [Signature] Date: 1/10/89

ENGINEER'S CERTIFICATE
 I hereby certify that this plan for Erosion and Sediment Control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District.

Signature: [Signature] Date: 1-10-89


CLARK • FINEFROCK & SACKETT, INC.
 ENGINEERS • PLANNERS • SURVEYORS
 7135 MINSTREL WAY • COLUMBIA, MD. 21045 • (301) 381-7500 - BALTO. • (301) 621-8100 - WASH.

SITE DEVELOPMENT PLAN
STORM DRAIN PROFILE
COLUMBIA
 VILLAGE OF HARPERS CHOICE
 TAX MAP #29 TAX MAP PARCELS 59E 60
 5TH ELECTION DISTRICT
 HOWARD COUNTY, MARYLAND

SCALE: AS SHOWN
 DRAWING: 4 OF 13
 JOB NO: 87-119
 FILE NO: 87-119-X


OWNER/DEVELOPER: TALLEY HOMES AT HOBBS CREEK
 CONDOMINIUM PO BOX 250 SEASONSVILLE, MD 21150
 410-313-3608

DATE: 1-10-89



PROFILE - PRIVATE DRIVE

SCALE: HORIZ. 1"=50'
VERT. 1"=5'




Bituminous Conc. Surface	1"
Bituminous Conc. Base	2"
Prime	1"
5" Crusher Run Base Course	5"
or	4"
Dense Graded Stabilized Aggregate Base Course	4"


ALTERNATE PAVING SECTION FOR PARKING AREAS (SECTION P-1)

Bituminous Conc. Surface	1 1/2"
Bituminous Conc. Base	2 1/4"
Prime	1"
8" Crusher Run Base (Placed in 2 Courses)	8"
or	6"
Dense Graded Stabilized Aggregate Base Course	6"


ALTERNATE PAVING SECTION FOR PUBLIC ROADS (SECTION P-2)




TYPICAL PAVING SECTION



DRIVEWAY ABUTTING CLOSED SECTION WITH CONCRETE SIDEWALK



TYPICAL PAVING STONE SECTION AT CURB & GUTTER



TYPICAL PAVING STONE SECTION AT BITUMINOUS CONCRETE

APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE SYSTEMS, HOWARD COUNTY HEALTH DEPARTMENT
 COUNTY HEALTH OFFICER: [Signature] DATE: 7-3-89
 APPROVED: HOWARD COUNTY OFFICE OF PLANNING & ZONING
 PLANNING DIRECTOR: [Signature] DATE: 7-19-89
 CHIEF DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT: [Signature] DATE: 3-15-89
 APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE, STORM DRAINAGE SYSTEMS AND PUBLIC ROADS, HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
 DIRECTOR: [Signature] DATE: 6-30-89
 CHIEF BUREAU OF ENGINEERING: [Signature] DATE: 7-5-89

APPROVED
 DIVISION OF COMMUNITY PLANNING & LAND DEVELOPMENT
 HOWARD COUNTY, MARYLAND
 DATE: 3-22-89



CLARK • FINEFROCK & SACKETT, INC. ENGINEERS • PLANNERS • SURVEYORS 7135 MINSTREL WAY • COLUMBIA, MD 21045 • (301) 381-7500 - BALTO • (301) 621-8100 - WASH		
DESIGNED JLB	SITE DEVELOPMENT PLAN PAVING DETAILS PARCEL A-1 COLUMBIA VILLAGE OF HARPERS CHOICE TAX MAP #29 TAX MAP PARCELS 59 & 60 5TH ELECTION DISTRICT HOWARD COUNTY, MARYLAND OWNER/DEVELOPER: TALLEY HOMES AT HARBORVIEW GLEN CONDOMINIUMS, P.O. BOX 250 SEANSONVILLE, MD 21150 410-313-8608	SCALE As Shown
DRAWN KIW		5 OF 13
CHECKED JLS		JOB NO. 87-113
DATE 1-10-89		FILE NO. 87-113-X



APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE SYSTEMS,
HOWARD COUNTY HEALTH DEPARTMENT

John Pyle 7-3-89
COUNTY HEALTH OFFICER DATE

APPROVED: HOWARD COUNTY OFFICE OF PLANNING & ZONING


Mark U. Campbell 7-15-89
PLANNING DIRECTOR DATE
CHIEF, DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT

APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE
STORM DRAINAGE SYSTEMS AND PUBLIC ROADS
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

Robert M. Bennett 6-30-89
DIRECTOR DATE
William E. R. ... 7-5-89
CHIEF BUREAU OF ENGINEERING DATE

APPROVED
DIVISION OF
COMMUNITY PLANNING
& LAND DEVELOPMENT
HOWARD COUNTY,
MARYLAND
3-29-89


PLAN
SCALE: 1"=100'



CLARK • FINEROCK & SACKETT, INC. ENGINEERS • PLANNERS • SURVEYORS 7135 MINSTREL WAY • COLUMBIA, MD 21045 • (301) 381-7500 - BALTO. • (301) 621-8100 - WASH.		
DESIGNED	JLS	SCALE
DRAWN	KIW	1"=100'
CHECKED	JLS	DRAWING
DATE	1-10-89	7 OF 13
		JOB NO.
		87-119
		FILE NO.
		87-119-X



LEGEND:



No.	REVISION	DATE
1	REMOVE & REPLACE EXIST RETAINING WALL	4/17/8

TRAP#3 SIST (ST-V)
 D.A. = 0.70 Acre
 Storage Req'd = 0.71(1800) = 1260 cf
 Storage Provided = 1260 cf
 Top of Stone Crest = 444.0
 Bottom Elev = 439.0
 Clean Out Elev = 441.0
 Depth = 4'
 Bottom Dimensions = 31' X 5'
 1:1 Side Slopes in Cut.

TRAP#5 SIST (ST-III)
 D.A. = 4.3 Acre
 Storage Req'd = 4.3(1800) = 7740 cf
 Storage Provided = 7936 cf
 Slot Elev = 431.0
 Bottom Elev = 427.0
 Clean Out Elev = 429.0
 Depth = 4'
 1:1 Side Slopes in Cut


TRAP#1 SIST (ST-III)
 D.A. = 1.8 Acres
 Storage Req'd = 1.8(1800) = 3240 cf
 Storage Provided = 3240 cf
 Depth = 4'
 Slot Elev = 427.0
 Bottom Elev = 423.0
 Clean Out Elev = 425.0
 Bottom Dimensions = 50' X 11'
 1:1 Side Slopes in Cut.

TRAP#2 SIST (ST-III)
 D.A. = 0.70 Acre
 Storage Req'd = 0.71(1800) = 1260 cf
 Storage Provided = 1260 cf
 Depth = 4'
 Slot Elev = 447.0
 Bottom Elev = 443.0
 Clean Out Elev = 445.0
 Bottom Dimensions = 17' X 11'
 1:1 Side Slopes in Cut.

TRAP#4 SIST (ST-III)
 D.A. = 0.80 Acre
 Storage Req'd = 0.81(1800) = 1440 cf
 Storage Provided = 1440 cf
 Depth = 4'
 Slot Elev = 449.0
 Bottom Elev = 445.0
 Clean Out Elev = 447.0
 Bottom Dimensions = 20' X 11'
 1:1 Side Slopes in Cut.

DEVELOPER'S/SUBMITTER'S CERTIFICATE
 I/we certify that all development and construction will be done in accordance with this plan of development and plan for erosion and sediment control and that all responsible personnel involved in the construction of this project will have a Certificate of Attendance at a Dept. of Natural Resources Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District or their authorized agents as may be deemed necessary.

ENGINEER'S CERTIFICATE
 I hereby certify that this plan for Erosion and Sediment Control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District.






Reviewed for: Howard B.G.D. Name
 and meets Technical Requirements
 Signature: Stephen M. ... Date: 4/23/89
 U.S. Soil Conservation Service

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.
 Approved: Stephen M. ... Date: 4/23/89

APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE SYSTEMS, HOWARD COUNTY HEALTH DEPARTMENT
 COUNTY HEALTH OFFICER: [Signature] DATE: 7-3-89
 APPROVED: HOWARD COUNTY OFFICE OF PLANNING & ZONING
 PLANNING DIRECTOR: [Signature] DATE: 7-19-89
 CHIEF, DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT
 APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE, STORM DRAINAGE SYSTEMS AND PUBLIC ROADS, HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
 DIRECTOR: [Signature] DATE: 6-30-89
 CHIEF BUREAU OF ENGINEERING: [Signature] DATE: 7-5-89

APPROVED
 DIVISION OF COMMUNITY PLANNING & LAND DEVELOPMENT
 HOWARD COUNTY, MARYLAND
 DATE: 3-29-89


Note:
 Extreme Care to be Utilized when working in area of existing 20" Gas Line. Test pits to be dug by hand to locate main at all crossings well in advance of construction.



CLARK • FINEFROCK & SACKETT, INC.
 ENGINEERS • PLANNERS • SURVEYORS
 7135 MINSTREL WAY • COLUMBIA, MD 21045 • (301) 381-7570 - BALTO. • (301) 621-8100 - WASH.

DESIGNED	JLS	SCALE	1"=30'
DRAWN	KIW	PROJECT	8 OF 13
CHECKED	JLS	TITLE	PARCEL A-1 COLUMBIA VILLAGE OF HARPERS CHOICE TAX MAP #29 TAX MAP PARCELS 59#60 5th ELECTION DISTRICT HOWARD COUNTY, MARYLAND
DATE	1-10-89	JOB NO.	87-119
		FILE NO.	87-119-SE



OWNER/DEVELOPER: THOMAS HOMES AT HOBBS GLEN LANDMARKS, 10000 BOY RD SEASONS WOODS, MD 21050 410-313-8608



II. Procedure
A. Swales, ditchline or yard inlet protection.

- Excavate completely around inlet to a depth of 18" below notch elevation.
- Drive 2 x 4 post 1' into ground at four corners of inlet. Place nail strips between posts on ends of inlet. Assemble top portion of 2 x 4 frame using overlap joint shown. Top of frame (weir) must be 6" below edge of roadway adjacent to inlet.
- Stretch wire mesh tightly around frame and fasten securely. Ends must meet at post.
- Stretch filter cloth tightly over wire mesh, the cloth must extend from top of frame to 18" below inlet notch elev. Fasten securely to frame. Ends must meet at post, be overlapped and folded, then fastened down.
- Backfill around inlet in compacted 6" layers until layer of earth is even with notch elevation on ends and top elevation on sides.
- If the inlet is not in a low point, construct a compacted earth dike in the ditchline below it. The top of this dike is to be at least 6" higher than the top of frame (weir).
- This structure must be inspected frequently and the filter fabric replaced when clogged.


INLET PROTECTION



SILT FENCE DETAIL (S)


APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE SYSTEMS, HOWARD COUNTY HEALTH DEPARTMENT.
 APPROVED: HOWARD COUNTY OFFICE OF PLANNING & ZONING.
 APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE, STORM DRAINAGE SYSTEMS AND PUBLIC ROADS, HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS.

APPROVED
 DIVISION OF COMMUNITY PLANNING & LAND DEVELOPMENT
 HOWARD COUNTY, MARYLAND
 DATE 3-29-89




CONSTRUCTION SPECIFICATIONS:
 1. Area under embankment shall be cleared, grubbed and stripped of any vegetation and root mat. The area shall be compacted to 95% of maximum dry density.
 2. The filter cloth shall be placed over the embankment and secured with a minimum of 12" of compacted earth on each side.
 3. The stone used in the outlet shall be small rip rap 4" to 8" in diameter with a thickness of 2" appropriate placed in the outlet.
 4. The structure shall be inspected after each rain and repairs made as needed.
 5. Construction operations shall be carried out in such a manner that erosion and water pollution is minimized.
 6. The structure shall be removed and the area stabilized when the drainage area has been properly stabilized.

STONE OUTLET SEDIMENT TRAP (S.O.S.T.) ST. I




CONSTRUCTION SPECIFICATIONS:
 1. Sediment shall be removed and the trap restored to its original dimensions when sediment has accumulated to the design depth for the trap. Removed sediment shall be deposited in a suitable area and in such a manner that it will not erode.
 2. The volume of sediment storage shall be 800 cu yd/acre of contributing drainage.
 3. The structure shall be inspected after each rain and repairs made as needed.
 4. Construction operations shall be carried out in such a manner that erosion and water pollution is minimized.
 5. The sediment trap shall be removed and the area stabilized when the constructed drainage area has been properly stabilized.
 6. All cut slopes shall be 1:1 or flatter.

STORM INLET SEDIMENT TRAP (S.I.S.T.) ST. III




CONSTRUCTION SPECIFICATIONS:
 1. ALL TEMPORARY SWALES SHALL HAVE UNINTERRUPTED POSITIVE GRADE TO AN OUTLET.
 2. DIVERTED RUNOFF FROM A DISTURBED AREA SHALL BE CONVEYED TO A SEDIMENT TRAPPING DEVICE.
 3. DIVERTED RUNOFF FROM AN UNDISTURBED AREA SHALL OUTLET DIRECTLY INTO AN UNDISTURBED STABILIZED AREA AT NON-EROSIVE VELOCITY.
 4. ALL TREES, BRUSH, STUMPS, OBSTRUCTIONS, AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED AND DISPOSED OF SO AS NOT TO INTERFERE WITH THE PROPER FUNCTIONING OF THE SWALE.
 5. THE SWALE SHALL BE EXCAVATED OR SHAPED TO LINE, GRADE, AND CROSS SECTION AS REQUIRED TO MEET THE CRITERIA SPECIFIED HEREIN AND BE FREE OF BANK PROJECTIONS OR OTHER IRREGULARITIES WHICH WILL IMPAIR NORMAL FLOW.
 6. FILLS SHALL BE COMPACTED BY EARTH MOVING EQUIPMENT.
 7. ALL EARTH REMOVED AND NOT NEEDED ON CONSTRUCTION SHALL BE PLACED SO THAT IT WILL NOT INTERFERE WITH THE FUNCTIONING OF THE SWALE.
 8. STABILIZATION SHALL BE AS PER THE CHART BELOW:

TYPE OF TREATMENT	CHANNEL GRADE	FLOW CHANNEL STABILIZATION
1	0.5-3.0%	SEED AND STRAW MULCH
2	3.1-5.0%	SEED AND STRAW MULCH
3	5.1-8.0%	SEED WITH JUTE OR EXCELSTOR; SOIL
4	8.1-20%	LINED 4-8" RIP-RAP



CONSTRUCTION SPECIFICATIONS:
 1. All dikes shall be constructed by earth-moving equipment.
 2. All dikes shall have positive drainage to an outlet.
 3. Top width may be wider and side slopes may be flatter if desired, to facilitate passing by construction traffic.
 4. Posts shall be spaced at 10' intervals along the length of the dike.
 5. Earth dikes shall have an outlet that functions with a minimum of erosion. Runoff shall be conveyed to a sediment trapping device such as a sediment trap or sediment basin where either the dike is at the drainage area above the dike or not adequately stabilized.
 6. Stabilization shall be: (A) in accordance with standard specifications for seed and straw mulch or straw mulch if not in seeding season, (B) flow channel as per chart below.

EARTH DIKE DETAIL (E.D.)



CONSTRUCTION SPECIFICATIONS:
 1. Stone size - Use 2" stone, or reclaimed or recycled concrete equivalent.
 2. Length - As required, but not less than 50' (except on a simple residence lot where a 30' minimum length would apply).
 3. Thickness - Not less than six (6) inches.
 4. Width - Ten (10) feet minimum, but not less than the full width of paths where ingress or egress occurs.
 5. Filter Cloth - Will be placed over the entire area prior to placing of stone. Filter will not be required on simple family residences.
 6. Surface Water - All surface water flowing or diverted toward construction entrances shall be piped across the entrance. If piping is impractical, a mounded berm with 3:1 slopes will be permitted.
 7. Maintenance - The entrance shall be maintained in a condition which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone. In conditions demand and repair and/or cleanup of any means used to trap sediment. All sediment applied, dropped, washed or tracked onto public rights-of-way must be removed immediately.
 8. Washing - Wheels shall be cleaned to remove sediment prior to entrance onto public rights-of-way. When washing is required, it shall be done on an area stabilized with stone and which drains into an approved sediment trapping device.
 9. Periodic inspection and needed maintenance shall be provided after each rain.

STABILIZED CONSTRUCTION ENTRANCE (SCE)

DEVELOPER'S/BUILDER'S CERTIFICATE
 I/We certify that all development and construction will be done according to this plan of development and plan for erosion and sediment control and that all responsible personnel involved in the development project will have a Certificate of Attendance at a Dept. of Natural Resources Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize personnel authorized by the Howard Soil Conservation District or their authorized agents, as are deemed necessary.

ENGINEER'S CERTIFICATE
 I hereby certify that this plan for Erosion and Sediment Control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District.

PERMANENT SEEDING NOTES
 Apply to graded or cleared areas not subject to immediate further disturbance where a permanent long-lived vegetative cover is needed.
Seedbed Preparation: Loosen upper three inches of soil by raking, discing or other acceptable means before seeding, if not previously loosened.
Soil Amendments: In lieu of soil test recommendations, use one of the following schedules:
 1) Preferred - Apply 2 tons per acre dolomitic limestone (92 lbs/1000 square ft) and 600 lbs per acre 10-10-10 fertilizer (14 lbs/1000 sq ft) before seeding.
 2) Acceptable - Apply 2 tons per acre dolomitic limestone (92 lbs/1000 sq ft) and 1000 lbs per acre 10-10-10 fertilizer (23 lbs/1000 sq ft) before seeding.
Seeding: For the periods March 1 thru April 30, and August 1 thru October 15, seed with 60 lbs per acre (1.4 lbs/1000 sq ft) of Kentucky 31 Tall Fescue. For the period May 1 thru July 31, seed with 60 lbs Kentucky 31 Tall Fescue per acre and 2 lbs per acre (.05 lbs/1000 sq ft) of weeping lovegrass. During the period of October 16 thru February 28, protect site by: Option (1) 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring. Option (2) Use sod. Option (3) Seed with 60 lbs/acre Kentucky 31 Tall Fescue and mulch with 2 tons/acre well anchored straw.
Mulching: Apply 1 1/2 to 2 tons per acre (70 to 90 lbs/1000 sq ft) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gallons per acre (5 gal/1000 sq ft) of emulsified asphalt on flat areas. On slopes 8 feet or higher, use 348 gallons per acre (8 gal/1000 sq ft) for anchoring.
Maintenance: Inspect all seeded areas and make needed repairs, replacements and reseeding.

TEMPORARY SEEDING NOTES
 Apply to graded or cleared areas likely to be redisturbed where a short-term vegetative cover is needed.
Seedbed Preparation: Loosen upper three inches of soil by raking, discing or other acceptable means before seeding, if not previously loosened.
Soil Amendments: Apply 600 lbs per acre 10-10-10 fertilizer (14 lbs/1000 sq ft).
Seeding: For periods March 1 thru April 30 and from August 1 thru November 15, seed with 24 bushel per acre of annual ryegrass (3.2 lbs/1000 sq ft). For the period May 1 thru August 14, seed with 3 lbs per acre of weeping lovegrass (.07 lbs/1000 sq ft). For the period November 16 thru February 28, protect site by applying 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring, or use sod.
Mulching: Apply 1 1/2 to 2 tons per acre (70 to 90 lbs/1000 sq ft) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gal per acre (5 gal/1000 sq ft) of emulsified asphalt on flat areas. On slopes, 8 ft or higher, use 348 gal per acre (8 gal/1000 sq ft) for anchoring.
 Refer to the 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for rate and methods not covered.

Construction Sequence

Phase I	NO OF DAYS
1. Obtain grading permit.	7
2. Construct Temp. Cart Paths. See Sheet 2 of 5.	1
3. Construct Storm Drainage I-1 - I-17, S-1A thru I-3, Temporary 18" Perf. CMP's and line existing stream channel.	14
4. Install Trap #1, concurrently with construction of Str. I-2, S-6, I-PD, S-B.D.'s. Access to temp cart path to be maintained throughout construction.	7
5. Grade entrance to private drive to Sta 3+00, and temporarily stabilize slopes and disturbed areas outside travelled way.	30
6. Construct water main.	7
7. Construct relocated cart path and remove temp. cart path.	7
8. Fine grade and construct paving to Sta 3+00.	30
9. Stabilize all disturbed areas during Phase I construction in accordance with Stds. and Specs.	7
10. Upon approval of the Sediment Control Inspector, remove sediment & erosion control measures and stabilize.	7

Phase II	NO OF DAYS
1. Construct remaining storm drainage, temp. 30" CMP, excavate for Trap #5, and temporarily divert water from existing swale as shown in plan.	30
2. Construct remaining sediment and erosion controls including traps 2 thru 4. Throats of inlets I-10, I-11, I-12, I-13, and I-14 to be bricked shut.	30
3. Clear and rough grade site.	30
4. Construct remaining water lines and construct sewer.	30
5. Install utilities.	30
6. Fine grade and construct paving.	120
7. Construct building, driveways and walks.	300
8. Fine grade and stabilize all disturbed areas onsite in accordance with stds. and specs.	30
9. Upon approval of the sediment control inspector, remove sediment & erosion control measures and stabilize.	30

Reviewed for Howard S.C.D. and meets Technical Requirements
 Signature: James M. Nelson Date: 4-7-89
 U.S. Soil Conservation Service

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

Signature: Stephen P. Fisher Date: 4-7-89
 Approved

STATE OF MARYLAND
 DEPARTMENT OF NATURAL RESOURCES
 SOIL CONSERVATION DISTRICT

4-7-89

SEDIMENT CONTROL NOTES:

- A minimum of 24 hours notice must be given to the Howard County Office of Inspection and Permit prior to the start of any construction. (992-2437)
- All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL.
- Following initial soil disturbance or redistribution, permanent or temporary stabilization shall be completed within a 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all slopes greater than 3:1. 14 days as to all other disturbed or graded areas on the project site.
- All sediment traps/basins shown must be fenced and warning signs posted around their perimeter in accordance with Vol. 1, Chapter 12, of the HOWARD COUNTY DESIGN MANUAL, Storm Drainage.
- All disturbed areas must be stabilized within the time period specified above in accordance with the 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for permanent seeding (Sec. 51) and sod (Sec. 54), temporary seeding (Sec. 50) and mulching (Sec. 52). Temporary stabilization with mulch alone can only be done when recommended seeding rates do not allow for proper germination and establishment of grasses.
- All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.
- Site Analysis:
 Total Area of Site: 6.006 Acres
 Area Disturbed: 7.5 Acres
 Area to be roofed or paved: 2.6 Acres
 Area to be vegetatively stabilized: 2.9 Acres
 Total Cut: 20,000 Cu. Yds
 Total Fill: 17,430 Cu. Yds
 Offsite waste/borrow area location: YODS 3/1 PARCEL E and area adjacent to Cedar Lane
- All sediment control practices which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
- Additional sediment control must be provided, if deemed necessary by the Howard County DPM sediment control Inspector.
- On all sites with disturbed areas in excess of 2 acres, approval of the Inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the Inspection agency is made.
- If houses are to be constructed on an "As-Built" basis, at random, Single Lot Sediment Control as shown below shall be implemented. N/A
- All pipes to be blocked at the end of each day (see detail below). N/A
- The total amount of straw bale dikes/silt fence equals 100 L.P.

CLARK • FINEROCK & SACKETT, INC.
 ENGINEERS • PLANNERS • SURVEYORS
 7105 MINSTREL WAY • COLUMBIA, MD 21046 • (410) 381-7530 - BALTO • (410) 621-8100 - WASH

SEDIMENT & EROSION CONTROL PLAN

DESIGNED: JLS
 DRAWN: KIW
 CHECKED: JLS
 DATE: 1-10-89

PARCEL A-1 COLUMBIA
 VILLAGE OF HARPER'S CHOICE
 TAX MAP # 29 TAX MAP PARCELS 59460
 5TH ELECTION DISTRICT
 HOWARD COUNTY, MARYLAND

SCALE: AS SHOWN
 DRAWING: 9 OF 13
 JOB NO: 87-119
 FILE NO: 87-119-SE

OWNER/DEVELOPER: TALLEY HOWARD AT HARPER'S CHOICE
 CONDOMINIUM TO BOX 350 JEFFERSONVILLE, MD 21150
 410-312-8608


DATE: 1-10-89

PLANT SCHEDULE


KEY	PLANT NAME	SIZE	QTY.	REMARKS	KEY	PLANT NAME	SIZE	QTY.	REMARKS
	SHADE TREES					FLOWERING TREES / SHRUBS			
⊕	DOOR RUBRUM 'STOPPER GLORY'	2 1/2" CAL	20	B&B HEAVY HEADS	⊗	CORNUS KOLSA	2-2 1/2" CAL	7	B&B HEAVY HEADS
⊕	DOOR RUBRUM 'STOPPER GLORY'	2 1/2" CAL	7		⊗	CORNUS FLORIDA	8"	8	
⊕	DOOR RUBRUM 'STOPPER GLORY'	2 1/2" CAL	4		⊗	CRATAEGUS PHAEOLOPELUM	8"	8	
⊕	DOOR RUBRUM 'STOPPER GLORY'	2 1/2" CAL	13		⊗	ATELANCHER CANADENSIS	8-10" HT.	3	
⊕	DOOR RUBRUM 'STOPPER GLORY'	2 1/2" CAL	3		⊗	PRUNUS CERASIFERA	2-2 1/2" CAL	10	
⊕	DOOR RUBRUM 'STOPPER GLORY'	2 1/2" CAL	4		⊗	PRUNUS YEDDENIS	8-10" HT.	12	
⊕	DOOR RUBRUM 'STOPPER GLORY'	2 1/2" CAL	7						
⊕	DOOR RUBRUM 'STOPPER GLORY'	2 1/2" CAL	9						
⊕	DOOR RUBRUM 'STOPPER GLORY'	2 1/2" CAL	35						
⊕	DOOR RUBRUM 'STOPPER GLORY'	2 1/2" CAL							
⊕	DOOR RUBRUM 'STOPPER GLORY'	2 1/2" CAL							

NOTES:
 • CONTRACTOR SHALL VERIFY LOCATION OF UNDERGROUND UTILITIES PRIOR TO DIGGING.
 • ALL PLANTING SHALL BE DONE IN ACCORDANCE WITH COLUMBIA, H.C.D. PLANTING SPECIFICATIONS.


LEGEND



VICINITY MAP
SCALE: 1"=2000'



NOTE
 "This plan is an amendment to previously approved Sheet 9 of 9 SDP-87-129"



NOTE:
 THIS PLAN SUPERSEDES SHEET 9 OF 9 FOR UNITS 34 THRU 36 SDP 87-129

Subdivision Name: COLUMBIA	Sheet / Area: 7/1	PARCEL: A-1
Plan No. 8d13	Block No. 16 & 17	ZONE: P.T. APTS.
Water Code: 1-02	Sewer Code: 6740000	

HARPERS FARM ROAD
 PB 15
 F 25

No.	REVISION	DATE
1	REMOVE & REPLACE EXIST RETAINMENT WALL	4/17/18

APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE SYSTEMS.
 HOWARD COUNTY HEALTH DEPARTMENT
 County Health Officer: *Joyce M. Boyles*, DATE: 6-10-91

APPROVED: HOWARD COUNTY DEPT. OF PLANNING & ZONING
 Director: *James H. Smith*, DATE: 6/13/91

APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE,
 STORM DRAINAGE SYSTEMS AND PUBLIC ROADS
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
 Director: *Thomas J. Smith*, DATE: 6/16/91

CHIEF BUREAU OF ENGINEERING: *OD GHA*, DATE: 6-5-91

APPROVED
 PLANNING BOARD
 OF HOWARD COUNTY
 DATE: 3-29-89

Conifers
 NO SCALE
 LIMIT OF DISTURBANCE
 REMOVE & REPLACE EXIST
 ACER SAKCHARUM 'GREEN MOUNTAIN'
 SUGAR MAPLE 2.5" CAL B&B.



Extreme care to be utilized when working in area of ex. 20" Gas Line. Test pits to be dug by hand to locate main at all crossings well in advance of construction.



KEY	PLANT NAME	SIZE	QNTY.	REMARKS	KEY	PLANT NAME	SIZE	QNTY.	REMARKS
SHADE TREES					FLOWERING TREES/SHRUBS				
⊕	ACER RUBRUM	2 1/2' CAL.	20	B&B HEAVY HEAD	⊕	CORNUS KOUSA	20" CAL	7	B&B HEAVY HEAD
⊕	ACER SACCHARUM	12-14' HT.	7		⊕	CORNUS FLORIDA		8	
⊕	FRAXINUS P. LAEVOLEATA MARSHALL'S		3		⊕	CRATAEGUS PHAENOPYRUM		8	40'
⊕	TILIA CORDATA GREENUPPIE		13		⊕	AMELANCHIER CANADENSIS	8-10' HT.	3	
⊕	QUERCUS RUBRA		3		⊕	PRUNUS CERASIFERA THUNDERCLOUD	20" CAL.	10	40'
⊕	ZELKOVA SERRATA		4		⊕	PRUNUS SERRATA KWANZAN	8-10' HT.	15	
⊕	EVERGREEN TREES				⊕	PRUNUS YEDENSIS		12	
⊕	PICEA ABIES	6-8' HT.	7			YOSHINO CHERRY			
⊕	PRUNUS THUNDERBOLT		3		- NOTES - CONTRACTOR SHALL VERIFY LOCATION OF UNDERGROUND UTILITIES PRIOR TO DIGGING. ALL PLANTING SHALL BE DONE IN ACCORDANCE WITH COLUMBIA HCD PLANTING SPECIFICATIONS.				
⊕	TSUGA CANADENSIS		25						
⊕	TSUGA CANADENSIS	8-10' HT.	8						
⊕	TSUGA CANADENSIS		8						

LEGEND

Contour Interval 2 FT
 Existing Contour (---)
 Proposed Contour (---)
 Spot Elevation (---)
 Direction of Drainage (---)
 Proposed Storm Drain (---)
 100 YR Flood Plain Elev. (---)



SEE SHEET 2 OF 13 FOR RETAINING WALL LOCATION.
 SEE SHEETS 12 OF 13 AND 13 OF 13 FOR RETAINING WALL DETAILS.
 SEE SHEET 10 OF 13 FOR LANDSCAPE PLANTING REPLACEMENT.

NO.	REVISION	DATE
1	REMOVE & REPLACE EXIST RETAINING WALL	4/17/88

APPROVED FOR PUBLIC WATER AND PUBLIC SEWERAGE SYSTEMS
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

John P. ... 7-3-89
 DATE

APPROVED FOR PLANNING & LAND DEVELOPMENT
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

Clark V. ... 7-17-89
 DATE

APPROVED FOR PUBLIC WATER AND PUBLIC SEWERAGE
 STORM DRAINAGE SYSTEMS AND PUBLIC ROADS
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS

Robert ... 6-20-89
 DATE

William ... 7-5-89
 DATE

APPROVED
 DIVISION OF
 COMMUNITY PLANNING
 & LAND DEVELOPMENT
 HOWARD COUNTY,
 MARYLAND
 DATE 3-29-89

CLARK • FINEFROCK & SACKETT, INC.
 ENGINEERS • PLANNERS • SURVEYORS


LANDSCAPE PLANTING PLAN


COLUMBIA
 VILLAGE OF HARPERS CHOICE
 HOBBITS GLEN GOLF COURSE
 5TH ELECTION DISTRICT
 HOWARD COUNTY, MARYLAND

OWNER/DEVELOPER: TALEX HOMES AT HOBBITS GLEN
 CONDOMINIUMS PO BOX 800 STAYBROOKVILLE, MD 21150
 410-213-8608


SCALE: 1"=30'
 DRAWING: 11 OF 13
 JOB NO: 87-119
 FILE NO: 87-119-15

1-10-89







RETAINING WALL PROFILE
 GRID TYPE - MIRAFI 2XT OR EQUIV. GRID LENGTH - AS SHOWN



RETAINING WALL PLAN



Typical Guard Rail Installation Detail

PROFESSIONAL CERTIFICATE
 I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME AND THAT I AM A FULLY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 33398, EXPIRATION DATE 11-29-2018.
 JUSTIN A. FRIZEL
 PROFESSIONAL ENGINEER
 No. 33398
 4-12-18

APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING
 CHIEF, DEVELOPMENT ENGINEERING DIVISION
 CHIEF, DIVISION OF LAND DEVELOPMENT
 DIRECTOR

7/18/18
 7-19-18
 7-23-18

No.	Date	Revision	By
5-8-18		RETAINING WALL DETAILS	

OWNER: TALLE HOMES AT HOBBITS GLEN CONDOMINIUMS
 PO BOX 250 SIMPSONVILLE, MD 21150

DEVELOPER: HARDIN-KIGHT ASSOCIATES, INC.
 GEOTECHNICAL CONSULTANTS
 7524 WB&A ROAD, SUITE 100
 GLEN BURNIE, MARYLAND
 (410) 553-0802
 (410) 553-0808

Designed By: JFD	Title: Retaining Wall Plan, Profile, and Details	Date: 5/8/2018
Checked By: JAF	Project: CONDOMINIUM TOWNHOUSES PARCEL A-1 COLUMBIA VILLAGE OF HARPERS CHOICE TAX MAP #29 TAX MAP PARCELS 59 & 60 5th ELECTION DISTRICT	Project No: 18118
Scale: 1" = 5'	5117 HARPERS FARM ROAD HOWARD COUNTY, MARYLAND	Drawing No: 12 of 13

SECTION 1: DIAMOND PRO MODULAR RETAINING WALL SYSTEMS
PART 1: GENERAL

- 1.1 Scope**
 Work includes furnishing and installing modular concrete block retaining wall units to the lines and grades designated on the construction drawings and as specified herein.
- 1.2 Applicable Sections of Related Work**
 Geogrid Wall Reinforcement (see Section 2)
- 1.3 Reference Standards**
 A. ASTM C1372 Standard Specification for Segmental Retaining Wall Units.
 B. ASTM C1262 Evaluating the Freeze thaw Durability of Manufactured CMU's and Related concrete Units
 C. ASTM D698 Moisture Density Relationship for Soils, Standard Method
 D. ASTM D422 Gradation of Soils
 E. ASTM C140 Sample and Testing concrete Masonry Units
- 1.4 Delivery, Storage, and Handling**
 A. Contractor shall check the materials upon delivery to assure proper material has been received.
 B. Contractor shall prevent excessive mud, cementitious material, and like construction debris from coming in contact with the materials.
 C. Contractor shall protect the materials from damage. Damaged material shall not be incorporated in the project (ASTM C1372).

PART 2: MATERIALS

- 2.1 Modular Wall Units**
 A. Wall units shall be Diamond Pro Retaining Wall units as produced by a licensed manufacturer.
 B. Wall units shall have minimum 28 day compressive strength of 3000 psi (20.7 MPa) in accordance with ASTM C1372. The concrete units shall have adequate freeze-thaw protection with an average absorption rate in accordance with ASTM C1372 or an average absorption rate of 7.5 lb/ft³ (120 kg/m³) for northern climates and 10 lb/ft³ (160 kg/m³) for southern climates.
 C. Exterior dimensions shall be uniform and consistent. Maximum dimensional deviations on the height of any two units shall be 0.125 in. (3 mm).
 D. Wall units shall provide a minimum of 110 lbs total weight per square foot of wall face area (555 kg/m²). Fill contained within the units may be considered 80% effective weight.
 E. Exterior face shall be textured. Color as specified by owner.
- 2.2 Wall Stone**
 A. Material must be well-graded compactable aggregate, 0.25 in. to 1.5 in., (6 mm - 38 mm) with no more than 10% passing the #200 sieve. (ASTM D422)
 B. Material behind and within the blocks may be the same material.
- 2.3 Infill Soil**
 A. Infill material shall be site excavated soils when approved by the on-site soils engineer unless otherwise specified in the drawings. Unsuitable soils for backfill (heavy clays or organic soils) shall not be used in the reinforced soil mass. Poorly graded sands, expansive clays and/or soils with a plasticity index (PI) >20 or a liquid limit (LL) >40 should not be used in wall construction.
 B. The infill soil used must meet or exceed the designed friction angle and description noted on the design cross sections, and must be free of debris and consist of one of the following inorganic USCS soil types: GP, GW, SW, SP, SM meeting the following gradation as determined in accordance with ASTM D422.
- | Sieve Size | Percent Passing |
|--------------------|-----------------|
| 3-inch (76 mm) | 100 |
| 3/4-inch (19 mm) | 75 - 100 |
| No. 40 (0.425 mm) | 0 - 70 |
| No. 200 (0.075 mm) | 0 - 35 |
- C. No. 57 stone may be used as infill material, if desired.
 D. Where additional fill is required, contractor shall submit sample and specifications to the wall design engineer or the onsite soils engineer for approval and the approving engineer must certify that the soils proposed for use has properties meeting or exceeding original design standards.

PART 3: WALL CONSTRUCTION

- 3.1 Excavation**
 A. Contractor shall excavate to the lines and grades shown on the construction drawings. Contractor shall use caution not to over-excavate beyond the lines shown, or to disturb the base elevations beyond those shown.
 B. Contractor shall verify locations of existing structures and utilities prior to excavation. Contractor shall ensure all surrounding structures are protected from the effects of wall excavation.
- 3.2 Foundation Soil Preparation**
 A. Foundation soil shall be defined as any soils located beneath a wall.
 B. Foundation soil shall be excavated as dimensioned on the plans and compacted to a minimum of 95% of Standard Proctor (ASTM D698) prior to placement of the base material.
 C. Foundation soil shall be examined by the on-site soils engineer to ensure that the actual foundation soil strength meets or exceeds assumed design strength. Soil not meeting the required strength shall be removed and replaced with acceptable material.
- 3.3 Base**
 A. The base material shall be the same as the Wall Stone material (Section 2.2) or a low permeable granular material.
 B. Base material shall be placed as shown on the construction drawing. Top of base shall be located to allow bottom wall units to be buried to proper depths as per wall heights and specifications.
 C. Base material shall be installed on undisturbed native soils or suitable replacement fills compacted to a minimum of 95% Standard Proctor (ASTM D698).
 D. Base material shall be a 4 in. (100 mm) minimum depth for walls under 4 ft (1.2 m) and a 6 in. (150 mm) minimum depth for walls over 4 ft (1.2 m).
- 3.4 Unit Installation**
 A. The first course of wall units shall be placed on the prepared base with the raised lip facing up and out and the front edges tight together. The units shall be checked for level and alignment as they are placed.
 B. Ensure that units are in full contact with base. Proper care shall be taken to develop straight lines and smooth curves on base course as per wall layout.
 C. Fill all cores and cavities and a minimum of 12 in. (300 mm) behind the base course with wall stone. Use infill soils behind the wall stone and approved soils in front of the base course to firmly lock in place. Check again for level and alignment. Use a plate compactor to consolidate the area behind the base course. All excess material shall be swept from top of units.
 D. Install next course of wall units on top of base course. Position blocks to be offset from seams of blocks below. Perfect "running bond" is not essential, but a 3 in. (75 mm) minimum offset is recommended. Check each block for proper alignment and level. Fill all cavities in and around wall units and to a minimum of 12 in. (300 mm) depth behind block with wall stone. For taller wall application the depth of wall stone behind the block should be increased; walls from 15 ft (4.57 m) to 25 ft (7.62 m) should have a minimum of 2 ft (0.61 m) and walls above 25 ft (7.62 m) should have a minimum of 3 ft (0.9 m). Spread infill soil in uniform lifts not exceeding 8 in. (200 mm) in uncompacted thickness and compact to 95% of Standard Proctor (ASTM D698) behind the consolidation zone.
 E. The consolidation zone shall be defined as 3 ft (0.9 m) behind the wall. Compaction within the consolidation zone shall be accomplished by using a hand operated plate compactor and shall begin by running the plate compactor directly on the block and then compacting in parallel paths from the wall face until the entire consolidation zone has been compacted. A minimum of two passes of the plate compactor are required with maximum lifts of 8 in. (200 mm). Expansive or fine-grained soils may require additional compaction passes and/or specific compaction equipment such as a sheepsfoot roller. Maximum lifts of 4 inches (100 mm) may be required to achieve adequate compaction within the consolidation zone. Employ methods using lightweight compaction equipment that will not disrupt the stability or batter of the wall. Final compaction requirements in the consolidation zone shall be established by the engineer of record.
 F. Install each subsequent course in like manner. Repeat procedure to the extent of wall height.
 G. As with any construction work, some deviation from construction drawing alignments will occur. Variability in construction of SRWs is approximately equal to that of cast-in-place concrete retaining walls. As opposed to cast-in-place concrete walls, alignment of SRWs can be simply corrected or modified during construction. Based upon examination of numerous completed SRWs, the following recommended minimum tolerances can be achieved with good construction techniques.
Vertical Control - ±1.25 in. (32 mm) max. over 10 ft (3 m) distance
Horizontal Location Control - straight lines ±1.25 in. (32 mm) over a 10 ft (3 m) distance.
Rotation - from established plan wall batter: 2.0°
Bulging - 1.0 in. (25 mm) over a 10 ft (3.0 m) distance

3.5 Additional Construction Notes

- A. Water management is of extreme concern during and after construction. Steps must be taken to ensure that drain pipes are properly installed and vented to daylight and a grading plan has been developed that routes water away from the retaining wall location. Site water management is required both during construction of the wall and after completion of construction.

SECTION 2: GEOGRID REINFORCEMENT SYSTEMS

PART 1: GENERAL

- 1.1 Scope**
 Work includes furnishing and installing geogrid reinforcement, wall block, and backfill to the lines and grades designated on the construction drawings and as specified herein.
- 1.2 Applicable Section of Related Work**
 Section 1: Diamond Pro Modular Retaining Wall Systems.
- 1.3 Reference Standards**
 See specific geogrid manufacturer's reference standards.
 Additional Standards:
 A. ASTM D4595 - Tensile Properties of Geotextiles by the Wide-Width Strip Method
 B. ASTM D5262 - Test Method for Evaluating the Unconfined Creep Behavior of Geogrids
 C. ASTM D6638 Grid Connection Strength (SRW-U1)
 D. ASTM D6916 SRW Block Shear Strength (SRW-U2)
 E. GRI-GG4 - Grid Long Term Allowable Design Strength (LTADS)
 F. ASTM D6706 - Grid Pullout of Soil
- 1.4 Delivery, Storage, and Handling**
 A. Contractor shall check the geogrid upon delivery to assure that the proper material has been received.
 B. Geogrid shall be stored above -10 F (-23 C).
 C. Contractor shall prevent excessive mud, cementitious material, or other foreign materials from coming in contact with the geogrid material.

PART 2: MATERIALS

- 2.1 Definitions**
 A. Geogrid products shall be of high density polyethylene or polyester yarns encapsulated in a protective coating specifically fabricated for use as a soil reinforcement material.
 B. Concrete retaining wall units are as detailed on the drawings and shall be Diamond Pro Retaining Wall Units.
 C. Drainage material is free draining granular material as defined in Section 1, 2.2 Wall Stone.
 D. Infill soil is the soil used as fill for the reinforced soil mass.
 E. Foundation soil is the in-situ soil.
- 2.2 Products**
 Geogrid shall be the type as shown on the drawings having the property requirements as described within the manufacturer's specifications.
- 2.3 Acceptable Manufacturers**
 A manufacturer's product shall be approved by the wall design engineer.

PART 3: WALL CONSTRUCTION

- 3.1 Foundation Soil Preparation**
 A. Foundation soil shall be excavated to the lines and grades as shown on the construction drawings, or as directed by the on-site soils engineer.
 B. Foundation soil shall be examined by the on-site soils engineer to assure that the actual foundation soil strength meets or exceeds assumed design strength.
 C. Over-excavated areas shall be filled with compacted backfill material approved by on-site soils engineer.
 D. Contractor shall verify locations of existing structures and utilities prior to excavation. Contractor shall ensure all surrounding structures are protected from the effects of wall excavation.
- 3.2 Wall Construction**
 Wall construction shall be as specified under Section 1, Part 3, Wall Construction.
- 3.3 Geogrid Installation**
 A. Install Diamond Pro wall to designated height of first geogrid layer. Backfill and compact the wall stone and infill soil in layers not to exceed 8 in. (200 mm) lifts behind wall to depth equal to designed grid length before grid is installed.
 B. Cut geogrid to designed embedment length and place on top of Diamond Pro Block to back edge of lip. Extend away from wall approximately 3% above horizontal on compacted infill soils.
 C. Lay geogrid at the proper elevation and orientations shown on the construction drawings or as directed by the wall design engineer.
 D. Correct orientation of the geogrid shall be verified by the contractor and on-site soils engineer. Strength direction is typically perpendicular to wall face.
 E. Follow manufacturer's guidelines for overlap requirements. In curves and corners, layout shall be as shown on Sheet 10 of this design.
 F. Place next course of Diamond Pro Block on top of grid and fill block cores with wall stone to lock in place. Remove slack and folds in grid and stake to hold in place.
 G. Adjacent sheets of geogrid shall be butted against each other at the wall face to achieve 100 percent coverage.
 H. Geogrid lengths shall be continuous. Splicing parallel to the wall face is not allowed.
- 3.4 Fill Placement**
 A. Infill soil shall be placed in lifts and compacted as specified under Section 1, Part 3.4, Unit Installation.
 B. Infill soil shall be placed, spread and compacted in such a manner that minimizes the development of slack or movement of the geogrid.
 C. Only hand-operated compaction equipment shall be allowed within 3 ft (0.9 m) behind the wall. This area shall be defined as the consolidation zone. Compaction in this zone shall begin by running the plate compactor directly on the block and then compacting in parallel paths to the wall face until the entire consolidation zone has been compacted. A minimum of two passes of the plate compactor are required with maximum lifts of 8 in. (200 mm).
 D. When fill is placed and compaction cannot be defined in terms of Standard Proctor
 E. Density, then compaction shall be performed using ordinary compaction process and compacted so that no deformation is observed from the compaction equipment or to the satisfaction of the engineer of record or the site soils engineer.
 F. Tracked construction equipment shall not be operated directly on the geogrid. A minimum fill thickness of 6 in. (150 mm) is required prior to operation of tracked vehicles over the geogrid. Turning of tracked vehicles should be kept to a minimum to prevent tracks from displacing the fill and damaging the geogrid.
 G. Rubber-tired equipment may pass over the geogrid reinforcement at slow speeds, less than 10 mph (16 Km/h). Sudden braking and sharp turning shall be avoided.
 H. The infill soil shall be compacted to achieve 95% Standard Proctor (ASTM D698). Compaction tests shall be taken at 3 ft (0.9 m) behind the block and at the back of the reinforced zone. The frequency shall be as determined by the on-site soils engineer or as specified on the plan. Soil tests of the infill soil shall be submitted to the on-site soils engineer for review and approval prior to the placement of any material. The contractor is responsible for achieving the specified compaction requirements. The on-site soils engineer may direct the contractor to remove, correct or amend any soil found not in compliance with these written specifications.

3.5 Special Considerations

- A. Geogrid can be interrupted by periodic penetration of a column, pier or footing structure.
 B. Diamond Pro walls will accept vertical and horizontal reinforcing with rebar and grout.

SECTION 3: WATER MANAGEMENT

PART 1: GENERAL DRAINAGE

- 1.1 Surface Drainage**
 A. At the end of each day's construction and at final completion, grade the backfill to avoid water accumulation behind the wall or in the reinforced zone.
 B. Surface water must not be allowed to pond or be trapped in the area above the wall or at the toe of the wall.
 C. Existing slopes adjacent to retaining wall or slopes created during the grading process shall include drainage details so that surface water will not be allowed to drain over the top of the slope face and/or wall. This may require a combination of berms and surface drainage ditches.
 D. Irrigation activities at the site shall be done in a controlled and reasonable manner. If an irrigation system is employed, the design engineer or irrigation manufacture shall provide details and specification for required equipment to ensure against over irrigation which could damage the structural integrity of the retaining wall system.
 E. Surface water that cannot be diverted from the wall must be collected with surface drainage swales and drained laterally in order to disperse the water around the wall structure.
- 1.2 Grading**
 A. Establish final grade with a positive gradient away from the wall structure. Concentrations of surface water runoff shall be managed by providing necessary structures, such as paved ditches, drainage swales, catch basins, etc.
 B. Grading designs must divert sources of concentrated surface flow, such as parking lots, away from the wall.
- 1.3 Drainage System**
 A. All walls will be constructed with a minimum of 12 in. (300 mm) of wall stone directly behind the wall facing.
 B. The drainage collection pipe, drain pipe, shall be a 4 in. (100 mm) perforated or slotted PVC, or corrugated HDPE pipe as approved by engineer of record.
 C. All walls will be constructed with a 4 in. (100 mm) diameter drain pipe placed at the lowest possible elevation within the 12 in. (300 mm) of wall stone. This drain pipe is referred to as a toe drain.
- 1.4 Toe Drain**
 A. For site configurations with bottoms of the base on a level plane it is recommended that a minimum one percent gradient be maintained on the placement of the pipe with outlets on 50 ft (15 m) centers, or 100 ft (30 m) centers if pipe is crowned between the outlets. This would provide for a maximum height above the bottom of the base in a flat configuration of no more than 6 in. (150 mm).
 B. For rigid drain pipes with drain holes the pipes should be positioned with the holes located down. Diamond Pro does not require that toe drain pipes be wrapped when installed into base stone complying with the specified wall stone material.
 C. Pipes shall be routed to storm drains where appropriate or through or under the wall at low points when the job site grading and site layout allows for routing. Appropriate details shall be included to prevent pipes from being crushed, plugged, or infested with rodents.
 D. On sites where the natural drop in grade exceeds the one percent minimum, drain pipes outlets shall be on 25 foot (7.7 m) centers maximum, as shown on Sheet 10 of this design. This will provide outlets in the event that excessive water flow exceeds the capacity of pipe over long stretches.
- 1.5 Concentrated Water Sources**
 A. All roof downspouts of nearby structures shall be sized with adequate capacity to carry storm water from the roof away from the wall area. They shall be connected to a drainage system in closed pipe and routed around the retaining wall area.
 B. Site layout must take into account locations of retaining wall structures and all site drainage paths. Drainage paths should always be away from retaining wall structures.
 C. Storm sewers and catch basins shall be located away from retaining wall structures and designed so as not to introduce any incidental water into the reinforced soil mass.
 D. A path to route storm sewer overflow must be incorporated into the site layout to direct water away from the retaining wall structure.


Retaining Wall General Notes

Construction Notes

1. Soil loadings considered in this design and calculations are based on the following parameters:

	Friction Angle	Cohesion	Unit Weight	Soil Type
Infill Soil	28°	0 PSF	125 PCF	Well compacted silty sand
Retained Soil	28°	0 PSF	125 PCF	Well compacted silty sand
Foundation Soil	28°	0 PSF	125 PCF	Well compacted silty sand

2. Actual soil parameters must meet or exceed these listed conditions to be used in wall construction.
3. Hydrostatic loading is not considered in this analysis. Sufficient drainage must be provided such that hydrostatic loading (pore pressure) does not develop in the reinforced zone.
4. Analysis assumes fill placement in 8 inch (200 mm) lifts compacted to 95% standard proctor. Compaction test frequency shall be determined by the engineer or as otherwise specified.
5. Retaining walls must be installed and constructed according to the red line drawings. The retaining wall plan view is for wall identification only.
6. A qualified engineer or technician shall supervise the wall construction to verify field and site soil conditions.
- Surface Drainage Notes**
 1. Rainfall and other water sources such as irrigation activities can be defined as surface water.
 2. Site grading shall be designed to route surface water around and away from the wall.
 3. The internal drainage system of the retaining wall is designed to remove incidental water that infiltrates into the soil behind the wall. Adequate storm water drainage systems are required to completely drain the area around the retaining wall structure.
 4. Drain piping, toe drain, should be located at the back of the stone drain field behind the wall as close to the bottom of the wall as allowed while still maintaining a positive gradient for drainage to daylight, or to a storm water management system.
 5. Ground water can be present within the soil due to surface infiltration or water table fluctuation. If ground water is encountered during construction, an adequate drainage system must be installed or the wall design must consider the presence of water within the soil mass.
 6. All water collection devices such as roof downspouts, storm sewers, and curb gutters must be designed to accommodate maximum flow rates and outlet outside the retaining wall area.



APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING

CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE: 2/13/18

CHIEF, DIVISION OF LAND DEVELOPMENT DATE: 7-19-18

DIRECTOR DATE: 7-23-18

No.	Date	Revision	By
	5-8-18	RETAINING WALL NOTES	

OWNER DEVELOPER

TALLES HOMES AT HOBBITS GLEN CONDOMINIUMS
 PO BOX 250 SIMPSONVILLE, MD 21150

HARDIN-KIGHT ASSOCIATES, INC.
 GEOTECHNICAL CONSULTANTS
 7524 WB&A ROAD, SUITE 100
 GLEN BURNIE, MARYLAND
 (410) 553-0802
 (410) 553-0808

Designed By:	Title:	Retaining Wall Specifications	Date:
JFD			5/8/2018
Checked By:	Project:	CONDOMINIUM TOWNHOUSES PARCEL A-1 COLUMBIA VILLAGE OF HARPERS CHOICE TAX MAP #29 TAX MAP PARCELS 59 & 60 5th ELECTION DISTRICT	Project No:
JAF			18118
Scale:	NTS	5117 HARPERS FARM ROAD HOWARD COUNTY, MARYLAND	Drawing No:
			13 of 13