
SHEET INDEX

- 1. COVER SHEET
- 2. OPEN SPACE PATHWAY LAYOUT
- 3. SEDIMENT CONTROL & CONSTRUCTION DETAIL SHEET 4. BRIDGE DETAIL SHEET.

OAKLAND RIDGE INDUSTRIAL PARK OPEN SPACE MASTER PLAN

COLUMBIA PARK AND RECREATION ASSOCIATION



GENERAL PLAN NOTE:

THESE PLANS WERE PREPARED FOR PATHWAY CONSTRUCTION ONLY. THESE PLANS WERE PREPARED FOR THE COLUMBIA PARK AND RECREATION ASSOCIATION. ALL SITE PLAN REQUIREMENTS WERE BASED ON PREVIOUS MEETINGS AND AGREEMENTS AS DOCUMENTED PER THE ENCLOSED CORRESPONDENCE. PLEASE CONTACT THE HOWARD COUNTY DIVISION OF COMMUNITY PLANNING AND LAND DEVELOPMENT FOR MODIFICATIONS TO THE STANDARD S.D.P. PROCESS FOR C.A.'s PATHWAYS.

TOPOGRAPHY SHOWN ON THIS DRAWING HAS BEEN TRACED FROM TOPOGRAPHIC SURVEYS AND MAPS PREPARED BY HOWARD COUNTY. THE OWNER OR ARCHITECT DO NOT IN ANY WAY GUARANTEE THE INFORMATION SHOWN HEREON, NOR DOES ANY INFORMATION SHOWN OR LACK

RESPONSIBILITY FOR LOCATIONS AND IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE LOCATIONS OF ALL UTILITIES WITHIN THE LIMITS OF

THE CONTRACTOR SHALL NOTIFY THE FOLLOWING UTILITIES OR AGENCIES AT LEAST FIVE

BALTIMORE GAS & ELECTRIC COMPANY

WORK WHICH WOULD NOT ALLY BE REQUIRED TO COMPLETE THE PROJECT SHALL NOT RELIEVE THE CONTRALTOR OF HIS RESPONSIBILITY TO PERFORM SUCH WORK. ALL UTILITIES ARE TO BE RETAINED UNLESS MARKED OTHERWISE AND APPURTENANCES ARE TO BE ADJUSTED TO FINISHED GRADE,

THE CONTRACTOR SHALL REPAIR AND MAINTAIN EXISTING SEDIMENT CONTROL DEVICES REAS WITHIN THE LIMIT OF CONSTRUCTION ARE STABILIZED. AT THA POLIT, ALL SEDIMENT CONTROL DEVICES SHALL BE REMOVED AND AREAS RESTORED AND STABILIZED UPON APPROVAL BY THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR. THE MEASURES REQUIRED IN THE APPROVED SEDIMENT CONTROL PLAN SHALL APPLY AS IF SHOWN ON ALL PLANS.

THE CONTRACTOR SHALL CONTACT THE CONSTRUCTION INSPECTION SURVEY DIVISION 24 HOURS IN ADVANCE OF COMMENCEMENT OF WORK AT 992-2417 OR 992-2418. 6. THE DEVELOPER IS RESPONSIBLE FOR THE ACQUISITION OF ALL EASEMENTS, RIGHTS AND OR RIGHTS-OF-WAY THAT MAY BE REQUIRED FOR THE SEDIMENT AND EROSION CONTROL PRACTICES, STORMWATER MANAGEMENT PRACTICES AND THE DISCHARGE OF STORMWATER ONTO OR ACROSS ADJACENT OR DOWNSTREAM PROPERTIES INCLUDED IN THIS PLAN. HE IS ALSO RESPONSIBLE FOR THE ACQUISITION OF ALL EASEMENT, RIGHTS AND/OR RIGHTS-OF-WAY THAT MAY BE REQUIRED FOR GRADING AND/OR WORK ON ADJACENT

PRIOR TO START OF ANY CONSTRUCTION, CONTRACTOR SHALL STAKEOUT ALL CONSTRUCTION AND VERIFY ALL OFFSETS, SETBACKS, EXISTING UTILITY LOCATIONS (HORIZONTAL AND

8. CONTRACTOR SHALL USE DIMENSIONS SHOWN. SCALING OF THESE PLANS IS DISCOURAGED UNLESS DIRECTED BY CIVIL ENGINEER. 19. THE CONTRACTOR SHALL TEST PIT EXISTING UTILITIES, WHERE DIRECTED BY THE

PROPERTIES INCLUDED IN THIS PLAN.

ENGINEER, A MINIMUM OF TWO WEEKS IN ADVANCE OF CONSTRUCTION OPERATIONS. U. ALL PIPE ELEVATIONS SHOWN ARE INVERT ELEVATIONS.

1. THE DEVELOPER MUST REQUEST THAT THE DEPARTMENT OF INSPECTIONS AND PERMITS APPROVE WORK COMPLETED IN ACCORDANCE WITH THE APPROVED EROSION AND SEDIMENT CONTROL PLAN, THE GRADING OR BUILDING PERMIT, AND THE ORDINANCE. ON ALL SITES WITH DISTURBED AREAS IN EXCESS OF 2 ACRES, APPROVAL OF THE

DEPARTMENT OF INSPECTIONS AND PERMITS SHALL BE REQUIRED ON COMPLETION OF INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS, BUT BEFORE PROCEEDING WITH ANY OTHER EARTH DISTURBANCE OR GRADING. OTHER BUILDING OR GRADING INSPECTION APPROVALS MAY NOT BE AUTHORIZED UNTIL THE INITIAL APPROVAL BY THE DEPARTMENT OF INSPECTIONS AND PERMITS IS GIVEN.

3. APPROVAL SHALL BE REQUESTED ON FINAL STABILIZATION OF ALL SITES WITH DISTURBED AREAS IN EXCESS OF 2 ACRES BEFORE REMOVAL OF CONTROLS. 4. ANY DAMAGE TO COUNTY RIGHTS-OF-WAY AND PAVING OF PUBLIC ROADS SHALL BE

FEFAURED IMMEDIATELY AT THE CONTRACTORS EXPENSE IN ACCORDANCE WITH THE HOWARD COUNTY SPECIFICATIONS AND STANDARDS. 5. All Fill Shall be rolled to a minimum degree of compaction of 95% of the DRY UNIT WHIGHT AS DETERMINED BY ASTM D-698.

ALL CONCRETE FOR SITE WORK SHALL BE CLASS 2 CONCRETE AND SHALL BE IN ACCORDANCE WITH THE MARYLAND STATE HIGHWAY ADMINISTRATION SPECIFICATIONS AS

STRUCTURES NOTED FOR REMOVAL SHALL BE REMOVED ENTIRELY AND COMPLETELY. REMOVAL OF UTILITIES OR MATERIALS THAT ARE BELOW GRADE SHALL HAVE THE SURFACE ABOVE RESTORED TO MATCH ADJACENT GRADES.

8. ALL DISTURBED AREAS SHALL BE STABILIZED WITH PERMANENT SEED AND MULCH IN THE DETERMINED APPROVAL OF WAIVER WP-91-173 ON JUNE 5,1991 FROM "HE HOWARD COUNTY SUBDIV : IN AND LAND DEVELOPMENT REGULATIONS, SECTION 10.116c6. THIS WAIVER IS FOR PERFORMING PATHWAY CONSTRUCTION WITHIN WETLANDS, . ' WETLAND BUFFERS, AND 75' STREAM BUFFERS. "N. CLEARING, GRADING OR CONSTRUCTION IS PERMITTED WITHIN THE WETLAND OR SIREAM SUFFERS EXCEPT AS APPROVED PER WAIVER PETITION, WP . 91-173.

1. APPLICABLE DEPARTMENT OF PLANNING AND ZONING FILES: F-91-100, FDP-36A, WP-91-91,
STORMAN OF PLANNING AND ZONING FILES: F-91-100, FDP-36A, WP-91-91,
STORMAN OF PLANNING AND ZONING FILES: F-91-100, FDP-36A, WP-91-91,
BOX OF THE TOTAL CONTROL OF PROVIDE ENFORCEMENT.

35. PATHWAY USE RESTRICTIONS: NO MOTORIZED VETICLES:
HOWARD COUNTY POLICE TO PROVIDE ENFORCEMENT. FDP-25-A-17. FDP+3, FDP-1, FDP-36, SDP-91-77, F-79-117, SDP-80-133, Signable 39. SDP-88-39, SDP-89-74, SDP-81-306, SDP-83-78.

A. SEDIMENT AND EROSION CONTROL SHALL BE IN ACCORDANCE WITH THE AGREEMENT MADE BETWEEN COLUMBIA ASSOCIATION AND HSCD DATED 3/2/87, 4 KE MSED MAY 1991. A WAIVER HAS BEEN AFFRONED FOR STORMWATER MANAGEMENT QUANTITY AND QUALITY


1. 401 PELMIT REL 4: 89 - WO-0647: 404 REF # 89 - 2619-3: DNR REF # 89-WC-0940


RESPONDIBLE PERSONNEL CERTIFICATION HEREBY CERTIFY THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE FROM A MODELLE TO THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT."

CERTIFICATION BY THE ENGINEER "I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDI-

CERTIFICATION BY THE DEVELOPER "I CERTIFY THAT ALL DEVELOPMENT AND OR CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT AND PLAN FOR EROSION AND SEDIMENT CONTROL AND I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT OF THEIR AUTHOR-IZATION AGENTS, AS DEEMED NECESSARY."

DENIS ELLIS





KCI TECHNOLOGIES, INC. ENGINEERS · PLANNERS · SURVEYORS 13992 BALTIMORE AVENUE / SUITE 300 LAUREL, MD. 20707

PHONE: (301) 792-8086

STORM DRAINAGE SYSTEMS AND PUBLIC ROADS. HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS. APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE SYSTEMS, HOWARD COUNTY HEALTH DEPARTMENT

PLANN

COLUMBIA, MD. 21046 PHONE: (301) 381-0020 ADDRESS CHART STREET ADDRESS 9180 Red Branch Road INDUSTRIAL PARK PLAT BLOCK ZONE TAX/ZONE MAP ELEC. DIST. CENSUS


COLUMBIA PARK & RECREATION ASSOCIATION

SEWER CODE COVER SHEET AS SHOWN CHECKED: PZ SDH OAKLAND RIDGE PROJ. NO.: DATE: INDUSTRIAL PARK 1687108C MARCH 99 OPEN SPACE MASTER PLAN

OWNER/DEVELOPER

SUITE 300

9861 BROKEN LAND PARKWAY



SEDIMENT AND EROSION CONTROL NOTES

*** - - ×

ON THE PROJECT SITE

A MINIMUM OF 24 HOURS NOTICE MUST BE GIVEN TO THE HOWARD COUNTY SEDIMENT CHATE I E VISION PRIOR TO THE START OF ANY CONSTRUCTION. (880-3450) ALL VEGETATIVE AND STRUCTURAL PRACTICES ARE TO BE INSTALLED ACCORDING TO THE PROVISIONS TO THIS PLAN AND ARE TO BE IN CONFORMANCE WITH THE 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL.

FOLLOWING THE INITIAL SOIL DISTURBANCE OR REDISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETE WITHIN: A) SEVEN (7) CALENDAR DAYS AS TO THE SURFACE OF ALL PERIMETER SLOPES, AND ALL SLOPES GREATER THAN 3 HORIZONTAL TO 1 VERTICAL (3:1) AND B) FOURTEEN (14) DAYS AS TO ALL OTHER DISTURBED OR GRADED AREAS

AL. SEDIMENT TRAPS/BASIN SHOWN MUST BE FENCED AND WARNING SIGNS POSTED AROUND THEIR PERIMETER IN ACCORDANCE WITH VOLUME 1, CHAPTER 12 OF HOWARD COUNTY DESIGN MANUAL STORM ORAINAGE.

ALL DISTURBED AREAS MUST BE STABILIZED WITHIN THE TIME PERIOD SPECIFIED ABOVE IN ACCORDANCE WITH THE 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR PERMANENT SEEDINGS (SEC. 51), SOD (SEC. 54), TEMPORARY SEEDING (SED. 50), AND MULCHING (SEC. 52). TEMPORARY STABILIZATION WITH MULCH ALONE CAN ONLY BE DONE WHEN RECOMMENDED SEEDING DATES DO NOT ALLOW FOR PROPER GERMINATION AND ESTABLISHMENT OF GRASSES.

ALL SEDIMENT CONTROL STRUCTURES ARE TO REMAIN IN PLACE AND ARE TO BE MAINTAINED IN OPERATIVE CONDITION UNTIL PERMISSION FOR THEIR REMOVAL HAS BEEN OBTAINED FROM THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR

ANY SEMIMENT MONTROL PRACTICE WHICH IS DISTURBED BY GRADING ACTIVITY FOR PLACE-MEN" OF UTILITIES MUST BE REPAIRED ON THE SAME DAY OF DISTURBANCE. ADDITIONAL SEDIMENT CONTROLS MUST BE PROVIDED IF DEEMED NECESSARY BY THE HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS SEDIMENT CONTROL INSPECTOR.

ON ALL SITES, DISTURBED AREAS IN EXCESS OF 2 ACRES APPROVAL OF THE INSPECTION AGENCY SHALL BE REQUESTED UPON COMPLETION OF INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS, BUT BEFORE PROCEEDING WITH ANY OTHER EARTH DISTURBANCE OR RADING OTHER BUILDING OR GRADING INSPECTION APPROVALS MAY NOT BE AUTHORIZED THIS INITIAL APPROVAL BY THE INSPECTION AGENCY IS MADE.

STATES TO TIPE CLARYLAND STANDARDS AND SPECIFICATIONS FOR THE STIL EROSION AND SETTMENT CONTROL" FOR THE STANDARD DETAILS AND DETAILED SPECI ACATIONS OF EACTICE SPECIFIED HEREIN.

WILE THE APPROVAL OF THE SEDIMENT CONTROL INSPECTOR, MINOR FIELD ADJUSTMENTS CAN AN ATTEM BE MADE TO INSURE THE CONTROL OF ANY SEDIMENT. CHANGES IN SEDIMENT CONTROL PRANCIBLES REQUIRE PRIOR APPROVAL OF THE SEDIMENT CONTROL INSPECTOR AND THE HOWARD SOIL CONSERVATION DISTRICT. AND HANGE TO THE GRADING PROPOSED ON THIS PLAN REQUIRES RE-SUBMISSION TO HOWARD

SOIL CONSERVATION DISTRICT FOR APPROVAL. ONIROL WILL BE PROVIDED FOR ALL DISTURBED AREAS. REFER TO 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL PP 62.01 THE BOLD' FOR ACCEPTABLE METHODS AND SPECIFICATIONS FOR JUST CONTROL.

ANY MARIATION FROM THE SEQUENCE OF OPERATIONS STATED ON THIS PLAN REQUIRES THE APPROVAL OF THE SEDIMENT CONTROL INSPECTOR AND THE HOWARD TATEL . PRIOR TO THE INITIATION OF THE CHANGE.

AN ANALYSIS EARTH LEFT IDLE FOR PERIODS EXCEEDING 30 DAYS SHALL BE STABILIZED ACTION TO TEMPORARY STABILIZATION SPECIFICATIONS. A THE END OF EACH WORKING DAY ALL SEDIMENT CONTROL PRACTICE WILL BE INSPECTED AND THE IN OPERATIONAL CONDITION.

AT THIS TIME, WE BELIEVE THAT SECTIONS 404 OR 401 OF THE GUEAN WATER ACT DO NOT FITTE WILL CATE

FIGHER IS RESPONSIBLE FOR THE ACQUISITION OF ALL EASEMENTS, RIGHTS, AND/ - - HIS-OF-WAYS THAT MAY BE REQUIRED FOR THE SEDIMENT AND EROSION CONTROL PRACTICES, STORMWATER MANAGEMENT PRACTICES AND THE DISCHARGE OF STORMWATER ONTO THE ACROSS ACCIONT OR DOWNSTREAM PROPERTIES INCLUDED IN THIS PLAN. HE IS ALSO SESS NSIBLE FOR THE ACQUISITION OF ALL EASEMENTS, RIGHTS AND/OR RIGHTS-OF-WAYS 18 MAY BE REQUIRED FOR GRADING AND/OR WORK ON ADJACENT PROPERTIES INCLUDED


MINITION BOL APPROVALS ON THIS PLAN EXTEND ONLY TO AREAS AND PRACTICES S EROPOSED WORK.

AND A LANGUE THE PLAN FOR SEDIMENT AND EROSION CONTROL DOES NOT RELIEVE THE ANT FROM COMPLYING WITH ANY FEDERAL/STATE/COUNTY REQUIREMENTS N. N. C. SN. FRONMENTAL ISSUES.

SEDIMENT CONTROL

the FOLLOWING CERTIFICATION BLOCKS ON SEDIMENT CONTROL PLANS:

FRITIFY THAT ALL DEVELOPMENT AND OR CONSTRUCTION WILL BE DONE ACCORDING TO THIS AN AN THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE THE ALE OF ATTLEDANCE AT A DEPARTMENT OF NATURAL RESOURCES APPROVED TRAINING FROCKAS THE CONTROL OF SEDIMENT AND EROSION BEFORE THE BEGINNING OF THE PROJECT. ALSO A HORIZE TERRODIC ON SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT."



TYPICAL PAVING SECTION PROPOSED PATHWAY

PERMANENT SEEDING NOTES

APPLY TO GRADED OR CLEARED AREAS NOT SUBJECT TO IMMEDIATE FURTHER DISTURBANCE WHERE A PERMANENT LONG-LIVED VEGETATIVE COVER IS NEEDED. SEEDBED PREPARATION: LOOSEN UPPER THREE INCHES OF SOIL BY RAKING, DISCING OR OTHER ACCEPTABLE MEANS BEFORE SEEDING, IF NOT PREVIOUSLY LOOSENED. SOIL AMENDMENTS: LIEU OF SOIL TESTS RECOMMENDATIONS, USE ONE OF THE FOLLOWING

1. PREFERRED - APPLY 2 TONS PER ACRE DOLOMITIC LIMESTONE (92 LBS./ 1000 SQ.FT.) AND 600 LBS PER ACRE 10-10-10 FERTILIZER (14 LBS./ 1000 SQ.FT.) BEFORE SEEDING. HARROW OR DISC INTO UPPER THREE INCHES OF SOIL AT TIME OF SEEDING. APPLY 400 LB. PER ACRE 30-0-0 UREAFORM FERTILIZER (9 LBS./1000 SQ.FT.) 2. ACCEPTABLE - APPLY 2 TONS PER ACRE DOLOMITIC LIMESTONE (92 LBS./ 1000 SQ.FT.) BEFORE SEEDING. HARROW OR DISC INTO UPPER THREE

SEEDING - FOR THE PERIODS MARCH 1 THRU APRIL 30, AND AUGUST 1 THRU OCTOBER 15, SEED WITH 60 LBS PER ACRE (1.4 LBS./1000 SQ.FT.) OF KENTUCKY 31 TALL FESCUE. FOR THE PERIOD MAY 1 THRY JULY 31. SEED WITH 60 LBS. KENTUCKY 31 TALL FESCUE PER ACRE AND 2 LBS. PER ACRE (.05 LBS./100 SQ.FT.) OF WEEPING LOVEGRASS. DURING THE PERIOD OF OCTOBER 16 THRU FEBRUARY 28, PROTECT SITE BY: OPTION (1) 2 TONS PER ACRE OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING. OPTION (2) USE SOD. OPTION (3) SEED WITH 60 LBS /ACRE KENTUCKY 31 TALL FESCUE AND MULCH WITH 2 TONS/ACRE WELL ANCHORED STRAW.

MULCHING - APPLY 1 1/2 TO 2 TONS PER ACRE (70 TO 90 LBS./1000 SO.FT.) OF UNROTTED SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. ANCHOR MULCH IMMEDIATELY AFTER APPLICATION USING MULCH ANCHORING TOOL OR 218 GALLONS PER ACRE (5 GAL/1000 SQ.FT.) OF EMULSIFIED ASPHALT ON FLAT AREAS. ON SLOPES 8 FEET OR HIGHER, USE 348 GALLONS PER ACRE (8 GAL./1000 SQ.FT.)

MAINTENANCE - INSPECT ALL SEEDED AREAS AND MAKE NEEDED REPAIRS, REPLACEMENTS AND RESEEDINGS.

APPLY TO GRADED OR CLEARED AREAS LIKELY TO BE REDISTURBED WHERE A SHORT-TERM VEGETATIVE COVER IS NEEDED

SEEDBED PREPARATION: LOOSEN UPPER THREE INCHES OF SOIL BY RAKING, DISCING OR OTHER ACCEPTABLE MEANS BEFORE SEEDING, IF NOT PREVIOUSLY LOOSENED.

SOIL AMENDMENTS: APPLY 60 LBS PER ACRE 10-10-10 FERTILIZER (14 LBS./1000 SQ.FT.) SEEDING: FOR THE PERIODS MARCH 1 THRU APRIL 30, AND AUGUST 15 THRU NOVEMBER 15, SEED WITH 2 1/2 BUSHEL PER ACRE OF ANNUAL RYE (3.2 LBS./100 SQ.FT.) FOR THE PERIOD OF MAY 1 THRU AUGUST 14, SEED WITH 3 LBS PER ACRE OF WEEPING LOVEGRASS (.07 LBS./1000 SQ.FT.) FOR THE PERIOD OF NOVEMBER 16 THRU FEBRUARY 28, PROTECT SITE BY APPLYING 2 TONS PER ACRE OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING, OR

MULCHING: APPLY 1 1/2 TO 2 TONS PER ACRE (70 TO 90 LBS./1000 SQ.FT.) OF UNROTTED SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. ANCHOR MULCH IMMEDIATELY AFTER APPLICATION USING MULCH ANCHORING TOOL OR 218 GALLONS PER ACRE (5 GAL./1000 SQ.FT.) OF EMULSIFIED ASPHALT ON FLAT AREAS. ON SLOPES 8 FEET OR HIGHER, USE 348 GALLONS PER ACRE (8 GAL./1000 SQ.FT.) FOR ANCHORING. REFER TO THE 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR RATE AND METHODS NOT COVERED.

REFER TO THE 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR RATE AND METHODS NOT COVERED.

A. SITE ANALYSIS:

1. PROPOSED PATHWAY 7.10 L.F. TOTAL
2. PROPOSED BRIDGE CROSSING 2.0 TOTAL 3. FUTURE TOT LOT C.C TOTAL
4. FUTURE PLAY MEADOW

TOTAL 5. FUTURE SITTING AREA AT OVERLOOK TOTAL DISTURBED AREA PATHWAY CONSTRUCTION =

TO LEFXIN NOTE OF A STRIPE THOOK SER (NO AC) 7 The transaction S.F (10) " TOTAL HAFA TO BU VECOTION " STATE OF THE TANK THE TO. 65 Apr.

WOVEH WHE PENCE GAIN IN VE GALVE, MAX 6" MESS 608. PERSPECTIVE VIEW _36" MIN. FENCE POS WOVEN WIRE FENCE (14 /2 GA. MIN., MAX.
6" MESH SPACING) WITH FILTER CLOTH OVER CONSTRUCTION NOTES FOR FABRICATED SILT FENCE Moven wire fence to PS fastened securely to fence posts with thre ties or staples POSTS: STEEL EITHER T OR U 2. FILTER CLOTH TO BE FAS ONED SECURELY TO FENCE: Noven wire, 14: Ga. 6 Hax. Hesh Opening MOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP AND 1 ID SECTION. . MEN THO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVER-LAPPED BY SIX INCHES AND FOLDED. FILTER CLOTH: FILTER X 4. Maintenance shall be performed as yeeded and material removed when bulges" develop in the silt fence. PREFABRICATED UNIT: GEOFAB, ENVIROFENCE, OR APPROVED U.S. DEPARTMENT OF AGRICULTURE SILT FENCE SOIL CONSERVATION SERVICE COLLEGE PARK, MARYLAND

TYPICAL EARTH DIKE PLACEMENT CONTRACTOR SHALL PROVIDE MOUNTABLE
STONE BERM ACCESS PER CONSTRUCTION CONTRACTOR SHALL PROVIDE CURLEX SLOPE
STABILIZATION AT ALL SLOPED AREAS
ADJACENT TO BRIDGE CONSTRUCTION. ENTRANCE SPECIFICATION BOTH SIDES TYP. TYPICAL SILT FENCE PLACEMENT SLOPE PROPOSED BRIDGE SLOPE_ I TYP. BRIDGE INSTALLATION PLAN

SCALE: 1/8"= 1'-0"

EMBED APPROX. 8' OF FILTER CLOTH, BACKFILL TRENCH WITH EARTH, COMPACT THOROUGHLY, TRENCH APPROX. I. FILTER CLOTH FABRIC TO BE 4".DEEP x 6" WIDE FASTENED SECURELY TO FENCE POST BY USE OF WIRE FIES OR HOG RINGS. 2 PER POST SURFACE DRAIN OR MEDIAN DITCHES

SIDE DITCHES

SIGNATURE OF DEVELOPER

DENIS ELLIS

PROVIDE I TUCK OR SUITABLY

REINFORCED TOP END SECTION

32' MIN. FENCE POSTS

DRIVEN A MIN. 12" INTO

GROUND, SIZE AND TYPE AS PER SLOPE SILT


GEDTEXTILE ICLASS F

FENCE (S.S.F.)

CHANNEL SILT FENCE AT STEAM CROSSING

CSF - CSF PLAN VIEW SYMBOL

N.T.S.




TYPICAL PATHWAY CROSS SECTION I SCALE : 1/4" = 1'-0"

LIMIT OF DISTURBANCE IC

PROPOSED

PATHWAY 6'



STABILIZED CONSTRUCTION ENTRANCE

not to scale

be removed immediately. Mashing - Wheels shall be cleaned to remove sediment prior to entrance onto public rights-of-way. When washing is required, it shall be done on an area stabilized with stone and which drains into an approved sediment trapping Periodic inspection and needed maintenance shall be provided after each rain. STABILIZED CONSTRUCTION Standard SEQUENCE OF CONSTRUCTION

1) Obtain grading permit. Notify MDE at least (10) days prior to starting any work. (1) Day 2) Notify the Howard County Sediment Control Division at least 48 hours prior to stating any work at 880-3450. 3) Clear and grub for sediment and erosion control measures

Install silt tence along the pathway section to be constructed. Place silt fence on the downhill side of the proposed pathway. In accordance with the Howard County Soil Conservation District, Division of Licenses and Permits and the 1983 Maryland Standards and Specifications for Soil Erosion and Sediment Control and all latest revisions.

only. Clear only for (1) days work or 1000'/day.

Notify Howard County Department of Permits and Licenses, Sediment Control Division, upon completion of said installation.

to existing grades.

stabilize those areas.

The proposed pathway alignment shall be field staked and approved by the engineer. 7 Once approval is given by the Howard County Department (4 Days)

of Permits and Licenses and the Sediment Control Inspector, clear and grub areas for pathway construction. 8 Grade for pathway construction as close as possible

Maintain positive drainage to sediment control devices. (2 Days) No slopes are to exceed 3:1. Immediately stabilize all rough graded areas.

10 Install pathway asphalt as required to maintain (5 Days) positive drainage flow. With permission from the Howard County Sediment Control (1 Day) Inspector, remove all erosion control devices and

Specific Terms

STANDARD SYMBOL

DIKE B

SEED AND STRAW MULCH

ENGINEERING DESIGN

SEED USING JUTE, OR EXCELSION; SOD; 2" STONE

21 SLOPE OR FLATTER

CONSTRUCTION SPECIFICATIONS

FLOW CHANNEL STABILIZATION

A. STONE TO BE 2 INCH STONE, OR RECYCLED CONCRETE EQUIVALENT, IN A LAYER AT LEAST 3 INCHES IN THICKNESS AND BE PRESSED INTO THE SOIL WITH CONSTRUCTION EQUIPMENT.

B. RIP—RAP TO BE 4—8 INCHES IN A LAYER AT LEAST 8 INCHES THICKNESS AND PRESSED INTO THE SOIL WITH CONSTRUCTION EQUIPMENT.

THE SOIL.

(APPROVED EQUIVALENTS CAN BE SUBSTITUTED FOR ANY OF THE ABOVE MATERIALS.

PERIODIC INSPECTION AND REQUIRED MAINTENANCE MUST BE PROVIDED AFTER EACH RAIN EVENT

U.S. DEPARTMENT OF AGRICULTURY 50H. CONSERVATION SERVICE COLLEGE PARK, MARYLAND

(1) Day

(l Day)

DIKE A

A. All work performed under this agreement shall comply fully with the requirements of the most current Maryland Standards and Specifications for Soil Erosion and Sediment Control and/or specific requirements which may be issued by HSCD.

The second second

. ROADS

4/1/92

4.1.92 N

HI ! WORK:

OL EWERAGE : SM

of HOWAL COUNTY

WARD OF CINTY REALTH OF SATMENTS

B. No work covered by this agreement shall be started until written as defined herein) has been received from HSCD.

WARD SINTY

C. CA shall be responsible for arranging for immediate repair or replace. existing erosion or sediment control measures which are removed, has existing rendered ineffective by work covered under this agreement.

D. This agreement applies to earth disturbing activities necessary for the construction of recreational pathways which may be surfaced with bires and paving, concrete, stone or mulch.

E. The following grading limitations are imposed:

1) Earth work is limited to grubbing, cutting and filling (exce herein) necessary to construct pathways.

2) Fill must be properly compacted, fill height not to exceed a feet, and be not steeper than 33 percent, (3:1).

3) Cut slopes may not exceed 2:1, 50 percent.

4) Grading may not impair surface drainage, create an eros. discharge sediment into any adjacent waterway.

5) Grading or filling in wetlands and/or the 100 year flood; her approved by the appropriate permitting agency (DNR, WPA, WPA, In cases where these conditions cannot be met, CA must contain for specific recommendations. (This may involve preparation plan by CA).

F. Sediment and erosion control measures will be performed as follow

1) Sediment control measures shall be placed as clearing and the progresses on a day-to-day basis.

Equipment entrances must be stabilized with stone to provent * tracking of sediment onto public streets. If tracking secure, ...

- 9" | PATHWAY 6 cleanup is required. EXISTING GROUND TYPICAL SILT FENCE LOCATION CONTRACTOR SHALL PROVIDE CURLEX SLOPE STABILIZ-ATION AT ALL SLOPED AREAS AJACENT TO PATHWAYS THAT EXCEED 25%, -12" CR-6 BASE COURSE -- 4" band sn surface course -- COMPACTED SUBGRADE 95 % TYPICAL PATHWAY CROSS SECTION

WITHIN NON-TIDAL WETLAND AREAS SCALE : 1/4" = 1'-0"

LIMIT OF DISTURBANCE 10'

OWNER/DEVELOPER MB A - ARK IN HE REATION ASSOCIATION HAR BROKEN IN PARKWAY LUMBIA, ME 2 46 PHCNE (301)38 [1,2] ADORES HAR Jakland + Ne Industrial Park 6023.02

ALL PONSIBLE PERSONNEL CERTIFICATION THEBY CERTIFY THAT ANY RESPONSIBLE PERSONNEL SURVEY IN THE CONSTRUCTION PROJECT WILL HAVE THE FINATE OF ATTENDANCE FROM A MD PEPT THE ENGINEERS APPROVED TRAINING PROGRAM to for JONTROL OF SEDIMENT AND EROSION BEFORE

HE INNING THE PROJECT." DENIS

"I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDI-


VIJAY BALUSU

01-28-92

CERTIFICATION BY THE ENGINEER

CERTIFICATION BY THE DEVELOPER "I CERTIFY THAT ALL DEVELOPMENT AND OR CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT AND PLAN FOR EROSION AND SEDIMENT CONTROL AND I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT OF THEIR AUTHOR-IZATION AGENTS, AS DEEMED NECESSARY."

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION REVIEWED FOR HO



PREPARED BY: KCI TECHNOLOGIES, INC.

ENGINEERS PLANNERS SURVEYORS 3992 BALTIMORE AVENUE SUITE 300 AUREL, MD 20707 PHONE: (301) 792-8086

DETAIL SHEET


OAKLAND RIDGE INDUSTRIAL PARK DREN SPACE MASTER PLAN

FIE ME

.

160 1150 M/11 Jm

SOP .91.105



(3)1/2x5"LAG BOLTS


BOLT 6x6" SLEEPERS TOGETHER WITH
(4) 1/2 x 10" LAG BOLTS 2'-0" O.C.

3 BRIDGE DESIGN LOAD NOT TO EXCEED 3 TONS.

TYPICAL 26 FOOT BRIDGE DETAILS


WARD COUNTY LEFT ARTMENT BLIC WORKS APPROVEDS FOR PUBLIC WATER AND POSITION SEWERAGE (YOUR MO HOWARD COUNTY HEALTH LIPARTMENT

> APPROVED PLANNING BOOKS of HOWARD COUNTY DATE 6.25.91




END PLATE SIDE VIEW


'ATTACH 6x6 SLEEPER TO 6x6 POST USING 2"x2"x4" .64L ANGLE IRON AND (3) 1/2x5" LAG BOLTS.



END VIEW FOOTING DETAIL SECTION B-B



DECK FRAMING PLAN



TOP CHORD

NOTE: THE HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS REVIEWS BRIDGE DRAWINGS FOR LINE, GRADE AND FLOODPLAIN IMPACT ONLY. THE DEPARTMENT OF LICENSES AND PERMITS PERFORMS RELATED STRUCTURAL REVIEW.

RESPONSIBLE PERSONNEL CERTIFICATION CERTIFY THAT ANY RESPONSIBLE PERSONNEL 54 1 VFI IN THE CONSTRUCTION PROJECT WILL HAVE PTER ATE OF ATTENDANCE FROM A MO DEET HE ENVIRONMENT APPROVED TRAINING PROGRAM
HE CONTROL OF SEDIMENT AND EROSION BEFORE FF NNING THE PROJECT." SIGNATULE OF DEVELOPER 1/27/92 DATE

CERTIFICATION BY THE ENGINEER "I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDI-

SIGNATURE OF ENGINEER

VIJAY BALUSU

CERTIFICATION BY THE DEVELOPER "I CERTIFY THAT ALL DEVELOPMENT AND OR CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN OF DEVELOPMENT AND PLAN FOR EROSION AND SEDIMENT CONTROL AND I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT OF THEIR AUTHOR-IZATION AGENTS, AS DEEMED NECESSARY." SIGNATURE OF DEVELOPER 1/21/92 DATE

DENIS ELLIS

AND SEDIMENT CONTROL BY THE HOWARD SOIL COMBERVATION

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION

DESCRIPTION

PREPARED BY KCI TECHNOLOGIES, INC.

1/2" Her Hur E FLAT WASHER NO COUNTREDINK

No COUNTERSINK

SPLIT RING CONNECTION DETAIL

1 5"+8" Deck

1/2" · 8" HEN HEND BOURS & FLAT WASHES BOTH EMPS NO COMMERCENTIAL

STLIT PING GrANGETON BOTH SIPES OF FOST SEE DETAIL 1-6 FOR RING SIZE

SEE DETAIL 1-6 FOR RING SIZE

SECTION A-A

OWNER/DEVELOPER

COLUMBIA, MD 21046 PHONE (301) 38--

Oakland Kida.

Inductinal

SUITE 300

9861 BROKEN LANT PARKWAY


COLUMBIA PARK & RECREATION ASSOCIATED &


ENGINEERS - PLANNERS - SURVEYORS 13992 BALTIMORE AVENUE / SUITE 300 LAUREL, MD. 20707 PHONE: (301) 792-8086

BRIDGE DETAIL SHEET

OAKLAND RIDGE INDUSTRIAL PARK OPEN SPACE MASTER PLAN 6023.02

-H(FΣ,





PLANTING SPECIFICATIONS AND NOTES

SITE PREPARATION AND SOILS

1. Silt fences for sediment and erosion control are to be installed as a first order of business.

ultimate application to the mitigation area.

- 2. Both areas are to be cleared of existing vegetation and grubbed if needed leaving as much topsoil intact as possible.
- 3. Exposed topsoil shall be salvaged from within the project limits of work as indicated on the plan and stockpiled for
- 4. Contractor shall then grade areas according to plan keeping in mind that finished grades on plan include topsoil mixtures; 6 inches for emergent plant community above water line and a minimum of 8 inches for all other plant communities within wetland planting areas.
- 5. Topsoil mixture for all plant material: 200 lb. dehydrated raw manure and ten 5.5 cu. ft. bale humus to 12 cu. yds of on site furnished topsoil. Composted sludge in the amount of 4.0 cu. yds. may be substituted for the raw manure, peat moss or peat humus.
- 6. Soil mix for all plants except ericaceous material: Soil mix shall consist of existing topsoil mixture at each planting pit location into which the contractor shall thoroughly incorporate 33% by volume of composted sludge.
- 7. Soil mix for ericaceous material: Soil mix shall consist of existing topsoil mixture at each planting pit location into which the contractor shall thoroughly incorporate 33% by volume peat moss.
- 8. All mixing in 6 and 7 shall be limited to shrub and/or tree ball and burlap or container grown stock only and confined to the planting pit and immediate adjacent soil surface area and shall be accomplished to the satisfaction of the design team or Engineer.

LIMITS OF WORK

1. The construction procedure shall not damage wetlands outside of the grading limits or damage areas designated to be undisturbed on the plans that occur within the project limits. Any damage shall be restored by the Contractor at his expense and to the satisfaction of the design team or Engineer.

WETLAND PLANT AVAILABILITY

- 1. Plant species required are normally available from standard landscape nursery sources. The Contractor must make arrangements with competent wetlands restoration specialists to insure a supply of the required material.
- 2. The Contractor and/or his subcontractor should be aware of the site design conditions and should take all prudent steps to insure that the plant material specified on the plans is acclimated to wetland conditions prior to delivery to the job site. If the material is available from sources where wetland conditions ar duplicated at he nursery, the Contractor should favor these sources as the supplier.
- 3. Rootstock of wetland plant material should be kept moist during the transport from the source to the job site and until planted.

FERTILIZING

- 1. Emergent plants below the water line should not be fertilized at this time.
- 2. Emergent plants above the water line shall be fertilized using 16-6-12 (3 to 4 month slow release) or equal approved by design team or Engineer.
- 3. Fertilizer for wetland trees and shrubs shall be a 21 gr. tightly compressed, long-lasting slow release (2 year) planting tablet with a minimum guaranteed analysis of 20-10-5.
- 4. Fertilizer for container grown material shall apply the following rates:
 - 1 gal. container 1 ea. 21 gr. tablets
 - 3 gal. container 2 ea. 21 gr. tablets
 - 5 gal. container 3 ea. 21 gr. tablets 7 gal. container 5 ea. 21 gr. tablets
- 5. B & B or Container stock shall be positioned in the planting hole. Backfill halfway up the root mass. Place tablet(s) beside the root mass approx. 1 inch from the root tips. Do not place tablets in the bottom of the hole. Complete backfill, tamp and water.

PLANTING SCHEDULE

1. It is recommended that the planting be done early in the spring.

HYDROLOGY

1. Hydrology to support the mitigation will be achieved by grading into existing water table and blending into existing wetlands. Additional water will come from rainfall and run-off from surrounding area.

PEST CONTROL

- 1. All planted oak trees shall be protected from gypsy moth damage by using gypsy moth repellant tape or other suitable means after planting.
- 2. A nylon line fence shall be installed to prevent waterfowl depredation. Stakes shall be placed at the PCA/open water interface with approximately four (4) rows of nylon line. A second nylon line fence shall be installed at the PCA/PCB interface.

HETLAND PLANTING PROCEDURES AND ESTABLISHMENT

- 1. Plant Community A, Palustrine Emergent, below existing water line in both Areas 1 and 2, shall be planted according to planting depths and spacing as shown in Plant List on Specifications and Detail sheet. Species should be evenly dispersed over entire designated area in groups of twenty (20) to thirty (30) per species.
- 2. Plant Community B, Palustrine Emergent, above existing water line in both Areas 1 and 2, shall be planted according to spacings as shown in Plant List on Specifications and Detail sheet. Species shall be evenly dispersed over entire designated area in groups of twenty (20) to thirty (30) per species.
- 3. Plant Community C, Shrub, shall consist of shrubs only. Shrubs are to be planted over entire designated area at an average spacing of five (5) feet. Contractor shall avoid planting in a straight grid pattern. Shrubs shall be planted within a range of four (4) to six (6) feet apart to create a more natural and non-mechanical appearance when completed.
- 4. Plant community D, Shrub/Scrub, shall consist of planting area according to specifications for Plant Community C (No. 3) first. After this, trees are to be planted over entire area at an average spacing of twenty (20) feet (15 to 25 feet apart) to create a natural appearance.
- 5. For all shrub planting areas, Contractor shall evenly disperse species in groups of 3 to 5 per species over entire designated
- 6. For trees planted in No. 4, Contractor shall evenly disperse species over entire area to be planted but not in groups.
- 7. Plant Community E, Palustrine Forested, shall consist of planting trees over the entire designated area at an average of ten (10) feet (8' to 12' apart).
- 8. Avoid planting in a straight grid pattern.
- 9. For trees planted in #7 (Plant Community E), Contractor shall evenly disperse species in groups of two (2) to four (4) per species over the entire designated area to be planted.
- 10. All trees planted in all areas shall be planted using Tubex Tree Shelters to aid in their growth and as a deterrent to beaver predation (See Tubex Procedure and Notes).
- 11. For Plant Community E, shrubs shall be planted among the tress singly in every opening between trees being sure to evenly disperse all species over entire designated area.
- 12. For Plant Community C, D, and E, staying within designated areas, Contractor shall hand seed all areas with TesTech Seed Mix consisting of: 25% Red Sop, Agrostis alba; 15% Deertongue, Dichanthelium clandestinum; 15% Perennial Rye; 10% Rough Blumgrass, Poa trivialis; 100 Wild Rye, Elymus virginicus; 10% Gama Grass, Tripsacum dactyloides, 05% Slender Wheatgrass, Agropyron trachycaulum; 05% Dutch White Clover, Trifolium
- 13. All woody plants specified in this plan are to be container grown. When planting a container grown tree or shrub, cut the container loose and remove the plant. Gently separate potbound roots so that they can grow into the prepared planting area. Severely encircled roots may have to be cut with a knife. The preparation of the planting area is critical to woody plant survival and vigorous growth. Rather than digging a hole, prepare the planting area at least three times the diameter of the root ball. Set the plant in the center of the area so that the upper surface of the root ball is level with the surrounding soil.
- 14. Plant Community F, Upland Forest, shall serve as a forested buffer to the newly created wetlands. It is to be seeded according to the stabilization Permanent Seeding Notes while simultaneously seeding with Wildlife Nurseries-Wildflower Seed Mixture consisting of at least twelve (12) different species. Recommended seeding rate of four (4) lbs. per acre at \$40.00 per lb.
- 15. After completion of No. 14 upland trees shall be planted evenly dispersing species over entire area in species groups of two (2). An average spacing of ten feet (8 to 12 feet) should be used at random to insure a natural appearance.
- 16. Plant Community G, Upland Herbaceous, shall be planted according to No. 14 but without trees. This area is to remain in an open field condition and serve as a buffer to the newly created wetlands.

MAINTENANCE SCHEDULE

- 1. Annual maintenance during the growing season, for a three year period.
- 2. Assess tree mortality of planting stock, remove and replace any dead or diseased plantings.
- 3. Volunteer seeding of native, local and endemic vegetation is to be expected. Do not discourage this effort unless it is negatively effecting the planted stock.
- 4. Remove through manual means (grubbing, pulling, cutting) aggressive, noxious, invasive species (ie. phragmites, cattail, Japanese knotweed, mile-a-minute) and all herbaceous vegetation within a 3-foot radius surrounding the planted woody nursery
- 5. Remove and dispose of man-made trash, including items contained within flotsam drift lines. Do not remove down and dead material naturally occurring or accumulating, unless it is smothering planting stock.

OPTIONAL LONG TERM EVALUATION

1. This site can be considered successful if after the fifth growing season, a comprehensive point intercept sampling procedure reveals that a prevalence ecological index (PI) of 3.0 or less is expressed within the mitigation site. (PI of <= 3.0 is a plant community consisting of 50% or greater, native, indigenous and endemic hydrophytic vegetation. A qualifying index will also confirm viable wetland hydrology).

EMERGENTS (PLANT COMMUNITY A-below water line)

| QTY | SYMBOL | SPECIES | INDICATOR STATUS | PLANTING DEPTH | SPACING |
|-----|--------|---|---------------------|-------------------|---------------|
| 155 | Pc | Pontederia cordata Pickerelweed | OBL | 0-1' | 3 ° OC |
| 155 | Pv | Peltandra virginica Arrow Arum | OBL | 0-1' | 3 ' 0C |
| 353 | Sc | Saururus cernuus Lizards Tail | OBL | 0-1' | 2 'OC |
| 353 | Sa | Scirpus americanus Common Three-Square | OBL | 0-0.5' | 2 'OC |
| 353 | Ip | Iris pseudoacorus Yellow Iris | OBL | 0-0.5' | 2'0C |
| 353 | Iv | Iris versicolor Blue Flag | OBL | 0-0.5' | 2'OC |
| 353 | Ac | Acorus calamus Sweet Flag | OBL | 0-0.5' | 2 ° OC |
| 353 | Lo | Leersia oryzoides Rice Cutgrass | OBL | 0-3# | 2'0C |

Note: Bare root or container

EMERGENTS (PLANT COMMUNITY B-above water line)

| QTY | SYMBOL | SPECIES | INDICATOR STATUS | AV ERA GI SPACIN | E G REMARKS |
|-----|--------|---------------------------------------|---------------------|----------------------------|----------------------|
| 256 | Sc | Scirpus cyperinus Woolgrass | FACW | 3.0'OC | Bare root or cont |
| 580 | Ic | Impatiens capensis Jewelweed | FACW | 2.0'OC | Bare root or cont |
| 580 | Lo | Leersia oryzoides Rice Cutgrass | OBL | 2.0'00 | Bare root or cont |
| 580 | Lc | Lobelia cardinalis Cardinal Flower | FACW+ | 2.0'00 | Bare root or cont |
| 580 | Pv | Panicum virgatum Switchgrass | FAC | 2.0'00 | Bare root or cont |
| 580 | Ed | Eupatorium dubium Joe-Pye-Weed | FACW | 2.0°OC | Bare root or cont |
| | | | | | |

TURTOLOGO LUCROLOG

SHRUBS (PLANT COMMUNITY C and D)

QTY SYMBOL SPECIES

| 4 | | 0.20120 | SINIUD | 91 92 | KERAKKS |
|----------|----|--|--------|--------------|-------------|
| 93 | Iv | Ilex verticillata Winterberry | Pacy+ | 18-24" | BBB or cont |
| 93 | Vđ | Viburnum dentatum Arrowwood | FAC | 18-24" | BBB or cont |
| 93 | Lb | Lindera benzoin Spicebush | PACH+ | 18-24" | BBB or cont |
| 93 | Sc | Sambucus canademsis Common Elderberry | Facm+ | 18-24" I | BBB or cont |
| 93 | Vc | Vaccinium corymbosom Highbush Blueberry | FACW+ | 18-24" j | BBB or cont |
| 93 | Rv | Rhododendron viscosum Swamp Azalea | OBL | 18-24" I | BBB or cont |
| | | | | | |

STATIS

TREES (PLANT COMMUNITY E)

| QTY | SYMBOL | SPECIES | NDICATOR STATUS | SIZE | REMARKS |
|-----|--------|--|--------------------|------|-------------|
| 40 | Ar | Acer rubrum Red Maple | FAC | 3-4' | BBB or cont |
| 40 | Fp | Fraxinus pennsylvanica Green Ash | FACW | 3-4' | BBB or cont |
| 40 | Pt | Pinus taeda Loblolly Pine | FAC- | 3-4' | BBB or cont |
| 40 | Io | Ilex opaca American Holly | FACU+ | 3-4' | BBB or cont |
| 40 | Qp | Quercus palustris Pin Oak | FACW | 3-4' | BBB or cont |
| 40 | Po | Platanus occidentalis American Sycamore | FACW- | 3-4' | BBB or cont |

| QTY | SYMBOL | SPECIES | INDICATOR STATUS | SIZE | REMARKS |
|-----|--------|---|---------------------|------|-------------|
| 13 | Ps | Pinus strobus White Pine | PACU | 3-4' | BBB or cont |
| 13 | Rp | Robinia pseudo-acacia Black locust | FACU- | 3-4' | BBB or cont |
| 13 | Cc | Carya cordiformis Bitternut Hickory | NI | 3-4' | BBB or cont |
| 13 | Ма | Magnolia acuminata Cucumber Magnolia | FACU | 3-41 | BBB or cont |
| 13 | Qm | Quercus muhlenbergii Chinquapin Oak | NI | 3-4' | BBB or cont |

TUBEX PROCEDURES AND SPECIFICATIONS

- 1. Drive the stake into the ground 1.5" from the tree to a depth of 12-14". In open fields, drive the stake on the windward side of the seedling for added support. In shady areas, drive the stake on the north side to prevent the stake from shading the tree.
- 2. Guide the TUBEX down the stake, making sure to loop the tie(s) over the stake as you go.
- 3. Gently slip the TUBEX over the tree. Be sure to keep the tree free of the ties as you lower the TUBEX into place.
- 4. Drive the base of the TUBEX 1" into the ground. This is critical. It forms an air-tight seal, to capture transpired water vapor. The easiest way to do this is by placing a 5x5" or bigger board over the shelter and wrapping it with a mallet. When pounding TUBEX into the sod, first loosen the ground and matted roots.
- 5. Pull the ties tight.

PLANTIC


ne.

TUBEX INSTALLATION

SUPPLEMENTAL

INFORMATION

6. Place protective mesh over the top of the TUBEX to prevent entry by birds. They can become trapped and die inside the tubes without the mesh covering.



GROUND LINE CONSTRUCT 3' SAUCER RIMFLOOD SAME AS IN WITH WATER TWICE WITHIN 24 HOURS

SHRUB PLANTING DETAIL

HO SCALE APPROVED: HOWARD COUNTY DEPARTMENT OF PLANNING AND ZONING. aina Irummanui

CHIEF DIVISION OF LAND RESEARCH DATE NO REVISION OWNER / DEVELOPER COLUMBIA PARKS AND RECREATION ASS. SUITE 300 9861 BROKEN LAND FARKWAY COLUMBIA, MARYLAND 21046 PROJECT OAKLAND RIDGE INDUSTRIAL CENTER

MITIGATION PLAN AT LAKE ELKHORN AREA TAX MAP 36 ZONED-NEW TOWN

GTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND

DETAILS & SPECIFICATIONS

M.A. DIRCKS & CO., INC. 2986 PEBBLE BEACH DRIVE

FLUCOTT CITY,MP. 21042 WILDHAN ENVIRONMENTAL SERVICES



JAYKANT D. PAREKH *10148

PROJECT NO 100200 DATE MAY 2, 1994 SCALE: A5 SHOWN DRAWING NO. 7 OF 7

5DP-21-105

DRAWN BY R.B.W.

DESIGNED BY RBW.+M.A.D.