

# STANDARD SYMBOL:

### CONSTRUCTION SPECIFICATIONS

- STONE SIZE: USE 2" STONE, OR RECYCLED CONCRETE EQUIVALENT. LENGTH: AS REQUIRED, BUT NOT LESS THAN 50 FEET (EXCEPT ON A RESIDENCE LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY.)
- 3. THICKNESS: NOT LESS THAN SIX (6) INCHES.
  4. WIDTH: TEN (10) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH
- AT POINTS WHERE INGRESS OR EGRESS OCCURS.


  5. FILTER CLOTH: WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE. FILTER CLOTH WILL NOT BE REQUIRED ON A
- SINGLE FAMILY RESIDENCE. 6. SURFACE WATER: ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES
- WILL BE PERMITTED.

  7. MAINTENANCE: THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT
- OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED, OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.
- 8. WASHING: WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS-OF-WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.

  9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAINFALL.

# STABILIZED CONSTRUCTION ENTRANCE (SCE)

NO SCALE



## CONSTRUCTION SPECIFICATIONS

- All dikes shall be compacted by earth moving equipment.
  All dikes shall have positive dramage to an outlet.
  Top width may be wider and side slopes may be flatter if desired to facilitate
- crossing by construction traffic.

  Field location should be adjusted as needed to utilize a stabilized safe outlet.

  Earth dikes shall have an outlet that functions with a minimum of erosion. Runoff shall be conveyed to a sediment trapping device such as a sediment trap or sediment basin where either the dike channel or the drainage area above the dike are not
- adquately stabilized.

  Stabilization shall be: (A) In accordance with standard specifications for seed and straw mulch or straw mulch if not in seeding season, (B) Flow channel as per

FLOW CHANNEL STABILIZATION

TYPE OF TREATMENT	CHANNEL GRADE	DIKE A	DIKE B
1 2	0.5-3.0 <b>%</b> 3.1-5.0 <b>%</b>	SEED AND STRAW MULCH SEED AND STRAW MULCH	SEED AND STRAW MULCH SEED USING JUTE, OR EXCELSIOR; SOD; 2" STONE
3	5.1-8.0 <b>%</b>	SEED WITH JUTE, OR SOD; 2" STONE.	LINED RIP—RAP 4"-8"
4	8.1-20 <b>%</b>	LINED RIP-RAP 4"-8"	ENGINEERING DESIGN
A. Stone to inches in	o be 2 inch sto n thickness and	ne, or recycled concrete equiv be pressed into the soil with	alent, in a layer at least 3 construction equipment.

Represent uncorress and perpressed into the soil with construction equipment.

B. Rip Rap to be 4–8 inches in a layer at least 8 inches thick and pressed into the soil. C. Approved equivalents can be substituted for any of the above materials

11-28-91

19-23-91

TA

EARTH DIKE (ED)

NO SCALE

APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE SYSTEMS HOWARD COUNTY HEALTH DEPARTMENT

APPROVED: HOWARD COUNTY DEPT. OF PLANNING & ZONING

APPROVED: FOR PUBLIC WATER AND PUBLIC SEWERAGE.

STORM DRAINAGE SYSTEMS AND PUBLIC ROADS


HOWARD COUNTY DEPARTMENT OF RUBLIC WORKS


COUNTY HEALTH OFFICER

AND LAND DEVELOPMENT

HIEF BUREAU OF ENGINEERING

DIVISION OF COMMUNITY PLANNING






## CROSS-SECTION "A"-"A"

OPTION: A one foot layer of 2" stone may be placed on the upstream side of the riprap in place of the embedded filter cloth. CONSTRUCTION SPECIFICATIONS FOR ST-V

- Area under embankment shall be cleared, grubbed and stripped of any vegetation andd root mat. The pool area shall be cleared. The fill material for the embankment shall be free of roots and other woody vegetation as
- well as over-sized stones, rocks, organic material or other objectionable material. The embankement shall be compacted by traversing with equipment while it is being constructed.
- Al cut and fill slopes shell be 2:1 or flatter. The stone used in the outlet shall be riprap 4"-8" along with a 1' thickness of 2" aggregate placed on the up-grade side on the small riprap or embedded filter cloth in the riprap.
- Sediment shall be removed and the trap restored to it's original dimensions when the sediment has accumulated to 1/2 the design depth of the trap.
- The structure shall be inspected after each rain and repairs made as needed. Construction operations shall be carried out in such a manner that erosion and water pollution is minimized. The structure shall be removed and the area stabilized when the drainage area has been properly stabilized.

# STONE OUTLET SEDIMENT TRAP (ST-V)

NO SCALE



STANDARD SYMBOL: — S — S — S —

CONSTRUCTION NOTES FOR FABRICATED SILT FENCE

- WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES
- FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED
- EVERY 24" AT TOP AND MID SECTION. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVER-
- LAPPED BY SIX INCHES AND FOLDED.


  MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN
  "BULGES" DEVELOP IN THE SILT FENCE.

STEEL EITHER T OR U TYPE OR 2" HARDWOOD. FENCE: WOVEN WIRE, 14 GA., 6" MAX. MESH OPENING. FILTER CLOTH: FILTER X, MIRAFI 100X, STABILINKA T140N, OR APPROVED EQUAL. PREFABRICATED UNIT: GEOFAB, ENVIROFENCE, OR APPROVED EQUAL.

> SILT FENCE (S) NO SCALE

# PROPOSED HOUSE

NOTE: Single lot detail cannot be utilized if any two lots sharing common property lines are to be disturbed at the same time or on any lots showing an existing sediment trap.



PERMANENT SEEDING NOTES

SEEDBED PREPARATION: Loosen upper three inches of soil by raking, discing or other

400 lbs. per acre 30-0-0 ureaform fertilizer (9 lbs/1000 sq.ft.)

July 31, seed with 60 lbs. Kentucky 31 Tall Fescue per acre and 2 lbs per acre

A PERMANENT LONG-LIVED VEGETATIVE COVER IS NEEDED.

acceptable means before seeding, if not previously loosened.

Harrow or disc into upper three inches of soil.

for anchorina.

for anchorina.

APPLY TO GRADED OR CLEARED AREAS NOT SUBJECT TO IMMEDIATE FURTHER DISTURBANCE WHERE

SOIL AMENDMENTS: In lieu of soil test recommendations, use one of the following schedules:

Harrow or disc into upper three inches of soil. At the time of seeding, apply

2) Acceptable- Apply 2 tons per acre dolomatic limestone (92 lbs/1000 sg ft.) and

1000 lbs. per acre 10-10-10- fertilizer (23 lbs./1000 sg ft.) before seeding.

SEEDING: For the periods March 1 thru April 30, and August 1 thru October 15, seed with 60lbs per acre (1.4 lbs/1000 sq ft) of Kentucky 31 Tall Fescue. For the period May 1 thru

(.05 lbs/1000 sq ft) of weeping lovegrass. During the period of October 16 thru February 28, protect site by: Option (1) 2 tons per acre well anchored straw mulch and seed as

MULCHING: Apply 1 1/2 to 2 tons per acre (70 to 90 lbs/1000 sq ft) of unrotted small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 218 gallons per acre (5 gal/1000 sq ft) of emulsified asphalt on flat areas. On slopes 8 feet or higher, use 348 gallons per acre (8 gal/1000 sq ft)

SEEDBED PREPARARTION: Loosen upper three inches of soil by raking, discing, or other acceptable

SEEDING: For periods March 1 thru April 30 and from August 15 thru November 15, seed

with 2 1/2 bushel per acre of annual rye (3.2 lbs./1000 sq ft). For the period May 1 thru August 14, seed with 3 lbs per acre of weeping lovegrass (.07 lbs/1000 sq ft). For the period November 16 thru February 28, protect site by applying 2 tons per acre of well

MULCHING: Apply 1 1/2 to 2 tons per acre (70 to 90 lbs/1000 sq ft) of unrotted small

grain straw immediately after seeding. Anchor mulch immediately after application using

REFER TO THE 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND

mulch anchoring tool or 218 gallons per acre (5 gal/1000 sq ft) of emulsified asphalt on flat areas. On slopes 8 feet or higher, use 348 gallons per acre (8 gal/1000 sq ft)

soon as possible in the spring. Option (2) Use sod. Option (3) Seed with 60 lbs/acre Kentucky 31 Tall Fescue and mulch with 2 tons/acre well anchored straw.

MAINTENANCE: Inspect all seeded areas and make needed repairs, repaicements and

SOIL AMENDMENTS: Apply 600 lbs per acre 10-10-10 fertilizer (14lbs/1000 sq ft).

anchored straw mulch and seed as soon as possible in the spring, or use sod.

TEMPORARY SEEDING NOTES

means before seeding, if not previously loosened.

SEDIMENT CONTROL FOR RATE AND METHODS NOT COVERED.

1) Preferred - Apply 2 tons per acre dolomitic limestone (92 lbs/100 sgft.) and 600 lbs per acre 10-10-10 fertilizer (14 lbs./1000 sq.ft.) before seeding.

NO SCALE

## SEDIMENT AND EROSION CONTROL NOTES

- 1. A minimum of 24 hours notice must be given to the Howard County Office of Inspection and Permits prior to the start of
- any construction. (992–2437). All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the 1983 MARYLAND STANDARDS AND SPECS. FOR SOIL EROSION AND SEDIMENT CONTROL.
- 3. Following initial soil disturbance or redisturbance, permanent or temporary stabilization shall be completed within: a) 7 calendar days for all perimeter sediment control stuctures, dikes, perimeter slopes and all slopes greater than 3:1, b) 14 days as to all other disturbed or graded areas on the
- project site. 4. All sediment traps/basins shown must be fenced and warning signs posted around their perimeters in accordance with Vol.1 Chapter 12, of the HOWARD COUNTY DESIGN MANUAL, Storm
- All disturbed areas must be stabilized within the time period specified above in accordance with the 1983 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for permanent seedings (Sec.51) sod (Sec.54), temporary seeding (Sec.50) and mulching (Sec 52). Temporary stabilization with mulch alone can only be done when recommended seeding dates
- grasses.
  6. All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County

Sediment Control Inspector.

do not allow for proper germination and establishment of

- 7. SITE ANALYSIS: Total Area of Site:\_ Area Disturbed: Area to be roofed or paved: Area to be vegetatively stabilized.;
  - Offsite Waste/Borrow Area Location:
- 8. Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.

Additional sediment control must be provided, if deemed

- necessary by the Howard County DPW Sediment Control Inspector. 10. On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the inspection agency
- 11. If houses are to be constructed on an "as sold" basis, at random, Single Family Sediment Control, as shown below shall be implemented.
- 12. All pipes to be blocked at the end of each day (see detail
- this sheet). N/A this sheet). IV/N 13. The total amount of silt fence= 2760 LF
- \* It is the responsibility of the contractor to identify the spoil/borrow site, notify and gain approval from HSCD of the site and its grading permit no. at time
- 14. It is the responsibility of the builder to clean any sediments within the permanent stormwater Management Facility that were caused by the house construction proposed on these plans

## CONSTRUCTION SEQUENCE:

NO. OF DAYS

- A. Obtain grading permit and install sediment and erosion control devices,
- Tree Protection Fences and Stabilize. \* B. Excavate for foundations, rough grade and temporarily stabilize.
- Construct structures, sidewalks and driveways. Final grade and stabilize in accordance with Stds. and Specs. Upon approval of the sediment control inspector, remove sediment and erosion control devices and stabilize.

\*Delay construction of houses on lots: 96 \$ 102 See single lot sediment control detail, this sheet.

SINGLE LOT SEDIMENT CONTROL PLAN

(OR SILT FENCE)

APPICABLE PER SILT FENCE SPECS.

## DEVELOPER'S/BUILDER'S CERTIFICATE


to this plan of development and plan for sediment and erosion control and that all responsible personnel involved in the construction project will have a Training Program for the Control of Sediment and Erosion before beginning



*8-5-9|* Date

## ENGINEER'S CERTIFICATE

I hereby certify that this plan for Sediment and Erosion Control represents a practical and workable plan based on my personal knowledge of the site condtions and that it was prepared in accordance with the requirements of the Howard Soil Conserva-





THE HOWARD RESEARCH AND DEVELOPMENT LAND COMPANY 10275 LITTLE PATUXENT PARKWAY COLUMBIA, MARYLAND 21044

7135 MINST	CLARK • FINEFROCK & SACKETT, INC.  ENGINEERS • PLANNERS • SURVEYORS  TREL WAY • COLUMBIA, MD. 21045 • (301) 381-7500 — BALTO. • (301) 621-8	
DESIGNED KIWM	SEDIMENT AND EROSION CONTROL DETAILS LOTS 28-30, 55-57,96-102, 111-116,105,139 & 138	SCALE AS SHOWN
DRAWN J.R.	COLUMBIA  VILLAGE OF RIVER HILL  SECTION 1 AREA 3	DRAWING 6 OF 6
CHECKED KIWM	5ECTION T AREA 5 5TH ELECTION DISTRICT HOWARD COUNTY, MARYLAND	JOB NO. 91-086
AUG 91	FOR: HALLMARK BUILDERS P.O. BOX 1018 COLUMBIA, MD 21044	FILE NO. 91-086 SEE

US Soil Conservation Service THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT

"I/We certify that all development and construction will be done according Certificate of Attendance at a Department of the Environment Approved the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District or their authorized agents, as are deemed

SDP 92 21