

NOTES:

- Site Analysis:**
 - Total Area of Parcel: 16,307 sq. ft.
 - Present Zoning of Property: R-20 (Residential - Single)
 - Proposed use of structures: Residential/Single Family Detached
 - Number of parking spaces required: 2
 - Number of parking spaces provided: 2
 - Building coverage of site: 1750 sq. ft. or 11%
- Typical Minimum Building Setbacks:**
 - Front:
 - Lots less than 18,000 S.F. 40 Feet
 - Rear: 30 Feet
 - Side: 10 Feet
 - Corner Lot: 30 Feet
 - Lot Coverage: 30% Maximum
- All work shown on these plans shall be done in accordance with Howard County Standards, Specifications and Details for Construction Volume IV.
- The Contractor shall notify the Department of Public Works, Bureau of Construction Inspection of (410) 313-1880 at least five (5) days prior to the start of work.
- The Contractor shall notify "Miss Utility" at 1-800-257-7777 at least Party-eight (8) hours prior to any excavation work.
- Any damage to existing public right-of-ways, existing paving, existing curb and gutter, existing utilities, etc. shall be corrected at the contractor's expense.
- The existing utilities shown hereon are located from construction drawings of record F 93-36 and W 5 Contract No. 14 3889. The approximate location of existing utilities are shown for the Contractor's information and convenience. The Contractor shall locate existing utilities to his own satisfaction and well in advance of any construction activities. Additionally, the Contractor shall take all necessary precautions to protect all existing utilities and maintain uninterrupted service.
- Topography shown is taken from aerial survey March 16, 1989. Two foot contour intervals are shown.
- Horizontal and vertical datums are related to the Maryland State Plane Coordinate System as projected from Howard County Control Station Nos. 2645005 and 2645006. (NAD 83). Boundary Survey by LDE 1988.
- Stormwater management study for this site was reviewed under 93-36.
- Previous submissions F 93-36, 14-3284, Approved Sept 93, P 90-28, approved 3/16/92.
- Bench Mark: Control station 2645005 B1. 291.929 - conc. monument 03' below surface.







**HOWARD SOIL CONSERVATION DISTRICT
SEMI-ANNUAL SEDIMENT CONTROL REPORT**

- A minimum of 48 hours notice must be given to the Howard County Department of Inspection, Licenses and Permits, Sediment Control Division prior to the start of any construction, (300-3458).
- All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in accordance with the most current "STANDARD SPECIFICATIONS AND DETAILS FOR SOIL EROSION AND SEDIMENT CONTROL", and revisions thereto.
- Following initial soil disturbance or disturbance, permanent or temporary stabilization shall be completed within: a) 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all slopes greater than 3:1, b) 14 days as to all other disturbed or graded areas on the project site.
- All sediment transportations shown must be fenced and warning signs posted around their perimeter in accordance with Vol. 1, Chapter 12, of the HOWARD COUNTY DESIGN MANUAL, Storm Drainage.
- All disturbed areas must be stabilized within the time period specified above in accordance with the 1993 HANDBOOK OF STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL, for permanent seeding (Sec. 51), and (Sec. 56), temporary seeding (Sec. 50) and mulching (Sec. 52). Temporary stabilization with mulch alone can only be used when commercial seeding sites do not allow for proper germination and establishment of grasses.
- All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.
- Site Analysis:**
 - Total Area of Site: 16.31 Acres
 - Area Disturbed: 2.50 Acres
 - Area to be roofed or paved: 0.00 Acres
 - Area to be vegetatively stabilized: 0.00 Acres
 - Total Cut: 0.00 Cu. Yds.
 - Total Fill: 0.00 Cu. Yds.
 - Offsite water/cross area location: N/A
- Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
- Additional sediment control must be provided, if deemed necessary by the Howard County Sediment Control Inspector.
- On all sites with disturbed areas in excess of 2 acres, removal of the inactive utility controls, but before proceeding with any other earth disturbance or grading, including any grading inspection approvals may not be made until the written approval by the inspection agency is made.
- Trenches for the construction of utilities is limited to three pipe lengths or that which can be back filled and stabilized within one working day, whichever is shorter.

Maintenance

- Repair all damages caused by soil erosion and construction equipment at or before the end of each working day.

Item	Sequence of Construction	Duration
1	Obtain grading permit	2 days
2	Install SCE	1 day
3	Install silt fences	1 day
4	Clear and grub site	1 week
5	Grade site	1 week
6	Stabilize site	1 week
7	Perimeter control to remain in place until removal is authorized by the grading inspector	



30	7360 Gardenview Drive
Lot No. 30	Street Address
	Address Chart

LAND DESIGN ENGINEERING, INC.
 8035 Columbia 100 Parkway Unit N. Columbia, Md. 21045
 (410) 713-1070 (301) 596-3421 (410) 715-0481 (Fax)

Designed: **GL**
 Drawn: **M.L.M.**
 Checked: **RM**
 Date: **10/93**

Marshalee Woods Section 1
 Lot 30 Parcel 593
 Tax Map 37 Election District
 Howard County, Maryland
 Previous Submittals: F 93-36

OWNER/DEVELOPER
 Grayson Homes, Inc.
 8025 Chevrolet Drive
 Ellicott City, MD 21042 (410) 461-5900

ENGINEER'S CERTIFICATE

"I hereby certify that this plan for Erosion and Sediment Control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with requirements of the Howard Soil Conservation District."

Podolph May Jr. 10/26/93
 Signature of Engineer Date

DEVELOPER'S CERTIFICATE

"I hereby certify that all development and/or construction will be done according to these plans, and that any responsible personnel involved in the construction project will have a Certificate of Attendance of a Department of the Environment approved training program for the control of sedimentation and erosion before beginning the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District or their authorized agents, as are deemed necessary."

W. Steven Bell 10/26/93
 Signature of Developer Date

Reviewed for Howard County Soil Conservation District and meets technical requirements

Patricia Taylor 10/26/93
 U.S. Soil Conservation Service Date

This development is approved for Erosion and Sediment Control by the Howard Soil Conservation District.

APPROVED: *Sherry J. [Signature]* 10/26/93
 Howard Soil Conservation District Date

APPROVED: Department of Public Works for Public Water and Public Sewerage Storm Drainage Systems and Public Roads

James A. [Signature] 10/26/93
 Director Public Works Date

APPROVED: Howard County Health Department for Public Water and Public Sewerage systems

James M. [Signature] 10/26/93
 Health Officer Date

APPROVED: Department of Planning and Zoning

James [Signature] 11/6/94
 Planning Director Date

Chim [Signature] 11/6/94
 Chief, Division of Land Development and Research Date

REVISIONS

No.	Date	Description
1	8-17-95	WOODLEIGH MODEL, OWNER'S DEVELOPER
2	2-29-96	Townsend Model, Remove Note RE: Sec 120

Property of: **Goodier Builders, Inc.** Section/Area: **1** Parcel No.: **593**

Plot No.	Block No.	Zone	Tax/Zone	Et. Dist.	Conserv. Tract
10983	5	R-20	37	18	6011.01

Water Code: **0 04** Sewer Code: **2153000**