



1/4-A

1511.59 SF = 5030.63 SF
0.3 Min. Lot Size (1 Car Gar.)
1690.23 SF = 5634.10 SF
0.3 Min. Lot Size (2 Car Gar.)
1671.84 SF = 5571.97 SF
0.3 Min. Lot Size (1 Car Gar.) w/10'x16' Deck
1850.23 SF = 6167.43 SF
0.3 Min. Lot Size (2 Car Gar.) w/10'x16' Deck




1/4-B

1585.11 SF = 5283.69 SF
0.3 Min. Lot Size (1 Car Gar. w/Nook)
1763.75 SF = 5879.17 SF
0.3 Min. Lot Size (2 Car Gar. w/Nook)
1745.11 SF = 5817.03 SF
0.3 Min. Lot Size (1 Car Gar. w/Nook) w/10'x16' Opt. Deck
1923.75 SF = 6412.50 SF
0.3 Min. Lot Size (2 Car Gar. w/Nook) w/10'x16' Opt. Deck




1/4-CA

1501.85 SF = 5006.16 SF
0.3 Min. Lot Size (1 Car Gar.)
1680.49 SF = 5601.63 SF
0.3 Min. Lot Size (2 Car Gar.)
1661.85 SF = 5539.50 SF
0.3 Min. Lot Size (1 Car Gar.) w/10'x16' Opt. Deck
1840.49 SF = 6134.97 SF
0.3 Min. Lot Size (2 Car Gar.) w/10'x16' Opt. Deck



1/4-CB*



1740.32 SF = 5801.07 SF
0.3 Min. Lot Size
1984.32 SF = 6614.40 SF
0.3 Min. Lot Size w/10'x16' Opt. Deck And 2' Opt. Exts.
1838.59 SF = 6128.63 SF
0.3 Min. Lot Size
1928.59 SF = 6661.96 SF
0.3 Min. Lot Size w/10'x16' Deck



1/4-D

1577.98 SF = 5259.93 SF
0.3 Min. Lot Size
1737.98 SF = 5793.27 SF
0.3 Min. Lot Size w/10'x16' Opt. Deck

LEGEND



VICINITY MAP

Scale: 1"=200'

BENCHMARKS:

Howard County Monument 2964 Intersection of MD. Route 108 and Trotter Road
Howard County Monument 2965 an additional 2,544'± Northeastly along MD. Route 108 away from Site

DIMENSION 5


1838.59 SF = 6128.63 SF
0.3 Min. Lot Size
1928.59 SF = 6661.96 SF
0.3 Min. Lot Size w/10'x16' Deck

ADDRESS CHART

| LOT NUMBER | STREET ADDRESS |
|------------|---------------------------|
| 25 | 5765 WHISTLING WINDS WALK |
| 35 | 5760 WHISTLING WINDS WALK |
| 34 | 5756 WHISTLING WINDS WALK |
| 36 | 5752 WHISTLING WINDS WALK |
| 175 | 5769 WHISTLING WINDS WALK |
| 176 | 5773 WHISTLING WINDS WALK |
| 177 | 5777 WHISTLING WINDS WALK |


SHEET INDEX

| DESCRIPTION | SHEET No. |
|-----------------------------------------|------------|
| SITE DEVELOPMENT PLAN | 1 & 2 of 3 |
| SEDIMENT/EROSION CONTROL PLAN & DETAILS | 3 of 3 |




2/3-A

1412.22 SF = 4707.40 SF
0.3 Min. Lot Size (1 Car Gar.)
1590.86 SF = 5302.87 SF
0.3 Min. Lot Size (2 Car Gar.)
1780.86 SF = 5836.19 SF
0.3 Min. Lot Size (1 Car Gar.) w/10'x16' Opt. Deck
1750.86 SF = 5836.20 SF
0.3 Min. Lot Size (2 Car Gar.) w/10'x16' Opt. Deck




2/3-CA

1482.93 SF = 4943.09 SF
0.3 Min. Lot Size (1 Car Gar.)
1642.03 SF = 5476.93 SF
0.3 Min. Lot Size (1 Car Gar.) w/10'x16' Opt. Deck
1661.57 SF = 5530.57 SF
0.3 Min. Lot Size (2 Car Gar.)
1821.57 SF = 6071.89 SF
0.3 Min. Lot Size (2 Car Gar.) w/10'x16' Opt. Deck




2/3-B

1564.50 SF = 5215.00 SF
0.3 Min. Lot Size (1 Car Gar. w/Nook)
1780.14 SF = 5803.80 SF
0.3 Min. Lot Size (2 Car Gar. w/Nook)
1010.14 SF = 3297.14 SF
0.3 Min. Lot Size (2 Car Gar. w/Nook) And 10'x16' Opt. Deck
1724.50 SF = 5746.93 SF
0.3 Min. Lot Size (1 Car Gar. w/Nook) And 10'x16' Opt. Deck




2/3-CB*

1809.30 SF = 6071.47 SF
0.3 Min. Lot Size
2049.30 SF = 6831.00 SF
0.3 Min. Lot Size w/10'x16' Opt. Deck




GRANADA

1601.33 SF = 5337.77 SF
0.3 Min. Lot Size
1803.33 SF = 6011.10 SF
0.3 Min. Lot Size w/10'x16' Opt. Deck And Opt. 2' Ext.




GRANADA I

1664.01 SF = 5444.70 SF
0.3 Min. Lot Size
1865.35 SF = 6217.83 SF
0.3 Min. Lot Size w/10'x16' Opt. Deck And Opt. 2' Ext. And 10'x16' Opt. Deck




NEWPORT

1827.31 SF = 6091.03 SF
0.3 Min. Lot Size
2028.65 SF = 6762.17 SF
0.3 Min. Lot Size w/10'x16' Opt. Deck And Opt. 2' Ext.



NEWPORT II

1601.33 SF = 5337.77 SF
0.3 Min. Lot Size
1803.33 SF = 6011.10 SF
0.3 Min. Lot Size w/10'x16' Opt. Deck And Opt. 2' Ext. And 10'x16' Opt. Deck



GRANADA II

1744.01 SF = 5813.37 SF
0.3 Min. Lot Size
1945.35 SF = 6484.50 SF
0.3 Min. Lot Size w/10'x16' Opt. Deck And 10'x16' Opt. Deck

DIMENSION 6

Vista
Newport II
1/4-A, 1/4-CA,
1/4-B, 1/4-CB,
2/3-A, 2/3-CA,
2/3-B, 2/3-CB,

DIMENSION 5

1/4-B (no opt. Nook)
2/4A
GRANADA
GRANADA II
NEWPORT II
VISTA

GENERAL NOTES:

- Subject property is zoned: NTSFLD per 10-18-93 Comprehensive Zoning Plan.
- The total area included in this submission is: 1.34 Acres.
- The total number of lots included in this submission is: 7
- Improvement to property: Single Family Detached
- The maximum lot coverage permitted is: 30%
- Department of Planning and Zoning reference file numbers: S-93-21, F-95-12, F-96-102, F-98-122, FDP Phase 222 A, Part V, F-99-161
- Utilities shown as existing are taken from approved Water and Sewer plans Contract #34-3586-D, approved Road Construction plans F-96-102, and actual field survey.
- Any damage to county owned rights-of-way shall be corrected at the developer's expense.
- All roadways are public and existing.
- The existing topography was taken from Road Construction Plans prepared by Morris & Ritchie Associates in January 1996.
- The coordinates shown hereon are based upon the Howard County Geodetic Control which is based upon the Maryland State Plane Coordinate System - Howard County Monuments Numbers: 2964 & 2965
- The contractor shall notify the Department of Public Works/ Division of Construction Inspection at (410) 313-1880 at least twenty-four (24) hours prior to the start of work.
- The contractor shall notify "Miss Utility" at 1-800-257-7777 at least 48 hours prior to any excavation work.
- For driveway entrance details, refer to Ho. Co. Design Manual Volume IV details R.6.03 #
- In accordance with FDP-Phase 222A Part V bay windows, vestibules, porches or balconies or chimneys not more than 10 feet in width may project not more than 4 feet into any setbacks; porches and decks may project not more than 3 feet into the front or rear setbacks. Exterior stairways or araways may not encroach into any building restriction line.
- Stormwater Management is provided per: F-96-102. Quantity Stormwater Management for Section 4. Area 5 is provided by three facilities; the Refurbished SWM Pond*1 South of Linden Lanthicum Lane (F-96-89). The Culvert at Great Star Drive (F-96-110) and SWM pond*4 in Section 4. Area 4 (F-96-130) Quality Management for this section will be provided by three facilities: a Forbay North of SWM pond*1 (F-96-89), A Shallow marsh facility at the end of Wild Orange Gate and an Extended Detention facility within pond*4 (F-96-130). The Subdivision is located in the Patuxent River area Sub-basin and is a Class I watershed.
- SHC Elevations shown are at the Property lines.

OWNER / DEVELOPER
THE HOWARD RESEARCH AND DEVELOPMENT CORP.
10275 LITTLE PATUXENT PARKWAY
COLUMBIA, MARYLAND 21044

| SUBMISSION NAME | SECTION/AREA | LOTS/PARCELS |
|--------------------------------|--------------------|---------------------|
| COLUMBIA VILLAGE OF RIVER HILL | 4/5 | 25, 33-35 & 175-177 |
| PLAT NO. 1971B 12867 | BLOCK NO. 1 | ZONE NTSFMD |
| | TAX MAP NO. 35 | ELECTION DIST. 5TH |
| | | CENSUS TRACT 6055 |
| WATER CODE 1-12 | SEWER CODE 6652500 | |

CLARK • FINEFROCK & SACKETT, INC.
ENGINEERS • PLANNERS • SURVEYORS
7135 MINSTREL WAY • COLUMBIA, MD 21045 • (410) 381-7500 BALT. • (301) 621-8100 WASH.

DESIGNED: DM
DRAWN: BH
CHECKED: JME
DATE: 3-24-99

SITE DEVELOPMENT PLAN
LOTS 25, 33-35 & 175-177
COLUMBIA VILLAGE OF RIVER HILL
SECTION 4 AREA 5
FIFTH (5th) ELECTION DISTRICT
HOWARD COUNTY, MARYLAND

FOR: ALLAN HOMES, INC.
10260 OLD COLUMBIA ROAD
RIVERSIDE CORPORATE PARK
COLUMBIA, MD 21046

SCALE: 1" = 30'
DRAWING: 1 of 3
JOB NO.: 99-021
FILE NO.: 99-021-X


APPROVED: DEPARTMENT OF PLANNING & ZONING
5/24/99
5/29/99
6/2/99


SPECIAL NOTES:

This Plan is for house siting and lot grading only. Improvements shown within the rights-of-way on this S.D.P. are not to be used for construction. For construction, see approved Road Construction Plans (F-97-125) and/or approved Water & Sewer Plans Contract # 34-3576-D.

SPECIAL NOTE FOR USE-IN-COMMON DRIVEWAYS

- Driveways shall be provided prior residential occupancy to insure safe access for fire and emergency vehicles per the following minimum requirements:
- Width - 12 feet (14 feet when serving more than one residence).
 - Surface - 6 inches of compacted crusher run base w/ tar and chip coating.
 - Geometry - Maximum 15% grade, maximum 10% grade change and minimum of 45-foot turning radius.
 - Structures - (culvert/bridges) - Capable of supporting 25 gross tons (H25 loading).
 - Drainage Elements - Capable of safely passing 100 yd. flood with no more than 1 foot depth over driveway surface.
 - Structure Clearances - minimum 12 feet.
 - Maintenance - Sufficient to insure all weather use.
- PAVING SECTION FOR USE-IN-COMMON DRIVEWAYS
N.T.S.








OWNER / DEVELOPER
 THE HOWARD RESEARCH AND DEVELOPMENT CORP.
 10275 LITTLE PATUXENT PARKWAY
 COLUMBIA, MARYLAND 21044

APPROVED - DEPARTMENT OF PLANNING & ZONING
[Signature] 5/24/99
 CHIEF, DEVELOPMENT ENGINEERING DIVISION
[Signature] 5/20/99
 CHIEF, DIVISION OF LAND DEVELOPMENT
[Signature] 6/8/99
 DIRECTOR



| | | |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------|----------------------|
| CLARK • FINEFROCK & SACKETT, INC. ENGINEERS • PLANNERS • SURVEYORS 7135 MINSTREL WAY • COLUMBIA, MD 21045 • (410) 381-7500 BALT. • (301) 621-8100 WASH. | | |
| DESIGNED DM | SITE DEVELOPMENT PLAN LOTS 25, 33, 34, 35, 175, 176 & 177 | SCALE 1" = 30' |
| DRAWN ZH/BP | COLUMBIA VILLAGE OF RIVER HILL | DRAWING 2 of 3 |
| CHECKED JME | SECTION 4 AREA 5 FIFTH (5th) ELECTION DISTRICT HOWARD COUNTY, MARYLAND | JOB NO. 99-021 |
| DATE 3-24-00 | FOR: ALLAN HOMES, INC. 10260 Old Columbia Road, Rivers Corporate Park Columbia, Maryland 21046 | FILE NO. 99-021-X |


SDP-99-115



Reviewed for: **HOWARD S.C.D.**
and meets Technical Requirements
Chris Summers 5-19-99
Signature Date
U.S. National Resources Conservation Service

THIS DEVELOPMENT PLAN IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.
John P. Rowan 5-19-99
Approved

APPROVED: DEPARTMENT OF PLANNING & ZONING
Chris Summers 5/19/99
CHIEF, DEVELOPMENT ENGINEERING DIVISION
Chris Summers 5/19/99
CHIEF, DIVISION OF LAND DEVELOPMENT
Chris Summers 6/14/99
DIRECTOR



21.0 STANDARDS AND SPECIFICATIONS FOR TOPSOIL

Definition
Placement of topsoil over a prepared subsoil prior to establishment of permanent vegetation.

Purpose
To provide a suitable soil medium for vegetable growth. Soils of concern here are low moisture content, low nutrient levels, low pH, moderate toxic to plants, and/or unacceptable soil gradation.

Conditions Where Practice Applies

- This practice is limited to areas having 2:1 or flatter slopes where:
 - The texture of the exposed subsoil/parent material is not adequate to produce vegetable growth.
 - The soil material is so shallow that the rooting area is not deep enough to support plants or ferns, containing supplies of moisture and plant nutrients.
 - The original soil to be vegetated contains material toxic to plant growth.
 - The soil is so acidic that treatment with lime is not feasible.
- For the purpose of these Standards and Specifications, areas having slopes steeper than 2:1 require special consideration and design for adequate stabilization. Areas having slopes steeper than 2:1 shall have the appropriate stabilization shown on the plans.

Construction and Material Specifications

- Topsoil salvaged from the existing site may be used provided that it meets the standards set forth in these specifications. Typically, the depth of topsoil to be salvaged for a given type can be noted in the representative soil profile section in the Soil Survey conducted by USDA-SCS in cooperation with Maryland Agricultural Experiment Station.
- Topsoil Specifications - Soil to be used as topsoil must meet the following:
 - Topsoil shall be a loam, sandy loam, clay loam, silt loam, sandy clay loam, loamy sand, or silty loam. Topsoil shall not be a mixture of contrasting textures and shall contain less than 5% by volume of chert, stone, slag, coarse fragments, gravel, sticks, roots, twigs, or other materials larger than 1 and 1/2" in diameter.
 - Topsoil must be free of plants or plant parts such as Bermuda grass, quackgrass, Johnsongrass, rindgrass, Ivy, thistle, or others as specified.
 - Where the subsoil is either highly acidic or composed of heavy clay, limestone or soil with a spread at the rate of 4-8 tons/acre (200-400 pounds per 1,000 sq ft) prior to the placement of topsoil. The soil shall be distributed uniformly over designated areas and worked into the soil in conjunction with tillage operations as described in the following procedure.
 - Topsoil shall be uniformly distributed in a 4" to 6" layer and lightly worked to a minimum depth of 6". Spreading shall be performed in such a manner that settling or settling in excess of a minimum of 50% of total topsoil shall not occur. Any irregularities in the surface resulting from spreading or other operations shall be corrected in order to prevent the formation of depressions or water pools.
 - Topsoil shall not be placed with the topsoil or subsoil in a furrow or machine track, when the subsoil is excessively wet or in a condition that may otherwise be detrimental to proper grading and seedbed preparation.

PERMANENT SEEDING NOTES

APPLY TO GRADED OR CLEARED AREAS NOT SUBJECT TO IMMEDIATE FURTHER DISTURBANCE WHERE A PERMANENT LONG-LIVED VEGETATIVE COVER IS DESIRED.

SEEDBED PREPARATION: Loosen upper three inches of soil by raking, harrow or other acceptable means before seeding, if not previously loosened.

SOIL AMENDMENTS: In lieu of soil test recommendations, use one of the following schedules:

- 1) Preferred - Apply 2 tons per acre dolomitic limestone (42 lbs/1000 sq ft.) and 400 lbs per acre 10-10-10 fertilizer (14 lbs/1000 sq ft.) before seeding. Harrow or disc this upper three inches of soil. At the time of seeding, apply 400 lbs per acre 50-50-50 urea-formaldehyde fertilizer (14 lbs/1000 sq ft.).
- 2) Acceptable - Apply 2 tons per acre dolomitic limestone (42 lbs/1000 sq ft.) and apply 1000 lbs per acre 10-10-10 fertilizer (28 lbs/1000 sq ft.) before seeding. Harrow or disc this upper three inches of soil.

SEEDING: For the periods March 1 thru April 30, and August 1 thru October 31, use 40 lbs per acre (14 lbs/1000 sq ft.) of Kentucky 31 Tall Fescue, for the period May 1 thru July 31, use 40 lbs of the Kentucky 31 Tall Fescue per acre and 2 lbs. per acre (28 lbs/1000 sq ft.) of creeping timothy. During the period of October 1 thru February 28, protect site by seeding 2 tons per acre well-rotted straw mulch and seed as soon as possible in the spring, Option (2) Use and Option (3) Seed with 40 lbs/acre Kentucky 31 Tall Fescue and mulch with 2 tons/acre well-rotted straw.

PULCHING: Apply 1 1/2 to 2 tons per acre (70 to 100 lbs/1000 sq ft.) of inverted small grain straw immediately after seeding. Another mulch immediately after application using mulch anchoring tool or 200 gal/acre (8 gal/1000 sq ft.) of erlenmeyer mulch on flat areas. On slopes 8 feet or higher, use 340 gal/acre (68 gal/1000 sq ft.) for anchoring.

MAINTENANCE: Inspect all seeded areas and make needed repairs, replacements and reseedings.

TEMPORARY SEEDING NOTES

SEEDBED PREPARATION: Loosen upper three inches of soil by raking, harrow or other acceptable means before seeding, if not previously loosened.

SOIL AMENDMENTS: Apply 400 lbs. per acre 10-10-10 fertilizer (14 lbs/1000 sq ft.).

SEEDING: For the periods March 1 thru April 30 and from August 15 thru November 15, seed with 2 1/2 tons per acre annual ryegrass (28 lbs/1000 sq ft.) For the period May 1 thru August 14, seed with 3 tons per acre of annual ryegrass (42 lbs/1000 sq ft.). For the period November 1 thru February 28, protect site by applying 2 tons per acre well-rotted straw mulch and seed as soon as possible in the spring, or seed.

PULCHING: Apply 1 1/2 to 2 tons per acre (70 to 100 lbs/1000 sq ft.) of inverted small grain straw immediately after seeding. Another mulch immediately after application using mulch anchoring tool or 200 gal/acre (8 gal/1000 sq ft.) of erlenmeyer mulch on flat areas. On slopes 8 feet or higher, use 340 gal/acre (68 gal/1000 sq ft.) for anchoring.


REFER TO THE 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR RATE AND METHODS NOT COVERED.

SEDIMENT AND EROSION CONTROL NOTES

- A minimum of 48 hours notice must be given to the Howard County Department of Inspectors, Licenses and Permits, Sediment Control Division prior to the start of any construction (318-1855).
- All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the 1994 MARYLAND STANDARDS AND SPECS. FOR SOIL EROSION AND SEDIMENT CONTROL, and revisions thereto.
- Following initial soil disturbance or re-disturbance, permanent or temporary stabilization shall be completed within:
 - a) calendar days for all perimeter sediment control structures, ditches, perimeter slopes and all slopes greater than 3:1
 - b) 14 days on all other disturbed or graded areas on the project site.
- All sediment traps/basins shown must be fenced and warning signs posted around their perimeters in accordance with Vol. I, Chapter 7, of the HOWARD COUNTY DESIGN MANUAL, Storm Drainage.
- All disturbed areas must be stabilized within the time period specified above, in accordance with the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL, for permanent seedings, soil, temporary seedings and mulching (See G.).
- Temporary stabilization with mulch alone can only be done when recommended seeding rates do not allow for proper germination and establishment of grasses.
- All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.
- SITE ANALYSIS:**


| | |
|-------------------------------------|-----------------|
| Total Area of Site: | 134 Acres |
| Area Disturbed: | 0.34 Acres |
| Area to be vegetatively stabilized: | 1.03 Acres |
| Total Cut: | 102,671 cu. yd. |
| Total Fill: | 3024 cu. yd. |
- Offsite Host/Borrow Area Location: _____
- Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
- Additional sediment control must be provided, if deemed necessary by the Howard County Sediment Control Inspector.
- On all sites with disturbed areas in excess of 2 acres, approval of the Inspection Agency shall be requested upon completion of October 15th, February 28, protect site by seeding 2 tons per acre well-rotted straw mulch and seed as soon as possible in the spring, or seed.
- Trenches for the construction of utilities is limited to three pipe lengths or less which shall be back-filled and stabilized within one working day, whichever is shorter.
- The total amount of silt fence = 667 LF
- The total amount of super silt fence = 178 LF
- The total amount of super diversion fence = 516 LF

*It is the responsibility of the contractor to identify the spot/areas site and notify and gain approval from the sediment control inspector of the site and its grading permit number at the time of construction.



CONSTRUCTION SEQUENCE

| NO. | NO. OF DAYS |
|----------------------------------------------------------------------------------------------------------------|-------------|
| 1. Obtain grading permit. | 7 |
| 2. Install tree protection fence. | 1 |
| 3. Install sediment and erosion control devices and stabilize. | 10 |
| 4. Excavate for foundations, rough grade and temporary stabilize. | 30 |
| 5. Construct structures, sidewalks and driveways. | 12 |
| 6. Final grade, install Erosion Control Matting and stabilize in accordance with standards and specifications. | 14 |
| 7. Upon approval of the sediment control inspector, remove sediment and erosion control devices and stabilize. | 7 |
| 8. Delay construction of houses on lots. | N/A |



DEVELOPER'S/BUILDER'S CERTIFICATE

I/We certify that all development and construction will be done according to this plan of development and plan for sediment and erosion control and that all responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of the Environment, Approved Training Program for the Control of Sediment and Erosion before beginning the project. I also authorize periodic on-site inspection by the Howard Soil Conservation District or their authorized agents, as are deemed necessary.

G. Allen Waschak 3-24-99
NAME DATE

ENGINEER'S CERTIFICATE

I hereby certify that this plan for Sediment and Erosion Control represents a practical and workable plan based on my personal knowledge of the site conditions and that it was prepared in accordance with the requirements of the Howard Soil Conservation District.

Richard J. Stepp 5/5/99
RICHARD J. STEPP DATE



CLARK • FINEFROCK & SACKETT, INC.
ENGINEERS • PLANNERS • SURVEYORS

7135 MINSTREL WAY • COLUMBIA, MD 21045 • (410) 381-7500 BALT. • (301) 621-8100 WASH.

| DESIGNED | SCALE |
|----------|------------------------------------------------------------------------------------------------------|
| DM | 1" = 30' |
| DRAWN | DRAWING |
| ZH/BP | 3 OF 3 |
| CHECKED | JOB NO. |
| JME | 99-021 |
| DATE | FILE NO. |
| 3-24-00 | FOR: ALLAN HOMES, INC. 10260 Old Columbia Road, Rivers Corporate Park Columbia, Maryland 21046 |

SDP 99-115