


#### EMBEDDING DETAIL



## ANCHORING DETAIL

# CONSTRUCTION SPECIFICATIONS

- l. Bales shall be placed in a row with ends tightly abutting the adjacent bales.
- 2. Each bale shall be embedded in the soil a minimum of 4".
- 3. Bales shall be securely anchored in place by stakes or re-bars driven thru the bales. The first stake in each bale shall be analed toward previously laid bale to force bales together.
- 4. Inspection shall be frequent and repair or replacement shall be made promptly as needed.
- 5. Bales shall be removed when they have served their usefulness so as not to block or impede storm flow or drainage.

Standard Symbol - ————S.B.D.———

### STRAW BALE DIKE DETAIL

Not to Scale

TRAVERSE DESCRIPTION							
△POINT	NORTH	EAST	BEARING	DISTANCE			
10100	523,285.309	857,084.793					
10101	523,122.190	857,320.030	S 55°-19'-07"E	286.67			
10102	522,855,046	857,093.932	S 40°-14'-35" W	349.98'			
10103	522,745.452	857,167.506	S 33°-52'-29"E	132.00'			
500	522,918.293	857,275.242					
	W-7-100						
			<b>P</b> -11 <b>P</b> -33.				
	l						

	QUANTITIES		TYPE	SUPPLIER
ITEM	ESTIM.	AS BUILT	MATERIAL	SOFFLIER
A-I 8 Inch Sanitary Sewer	336 L.F.			
A-2 8 Inch Sanitary Sewer D.I.P.	54 L.F.			,
A-3 Standard Sewer Manholes	I EA.			
A-4 Vertical Feet Standard Sanitary Manholes	2 V.F.			
A-5 Shallow Depth Sewer Manholes	2 EA.			
B-I 6 Inch Sanitary Sewer House Connection	20 L.F.			

RESTORATION SCHEDULE						
LOCATION	LENGTH	MATERIAL				
Existing MH 4606 to Sta. 0+82	82 Feet	Pavement-6 Inch Thickness				
Sta. 0+82 to MH I	4 Feet	Concrete & Masonry				
MH I to Sta. 0+47	47 Feet	Sod				
Sta. 0+47 to MH 2	7 Feet	Pavement-2 Inch Thickness & Curb				
MH 2 to Sta. I+88	188 Feet	Pavement-2 Inch Thickness				
Sta. I+88 to MH 3	60 Feet	Pavement-6 Inch Thickness & Curb				

### SOIL EROSION AND SEDIMENT CONTROL NOTES:

- The Contractor will comply with all requirements of Sediment and Erosion Control set forth in the Contract Drawings, 1983 "Maryland Standards Specifications for Soil Erosion and Sediment Control', and Volume IV-Section 219 of the Howard County Design Manual, Volume IV.
- The Contractor shall not pump from excavated areas directly into the Howard County Storm Drainage System or any Natural Water Course. Where ground water is encountered during construction, the Contractor shall provide portable or excavated Sediment Traps to prevent Silted Trench water from entering Storm Drainage Systems or natural waterways.
- All excavated material shall be placed on the high side of the trench whenever possible, and confined to an area where it will not obstruct the normal flow or drainage courses.
- 4. All swales shall be equipped with a Sediment Retention Device to trap sediment and filter water leaving the Right-of-Way prior to entering any running stream.
- The Contractor shall provide Straw Bale Dikes normal to surface water flow around all vehicle and equipment staging areas as shown in "Detail of a Straw Bale Dike" enclosed in specifications.
- Road side ditches and drainage pipes shall be restored to a condition following completion of construction.
- The Contractor shall dispose of spoils in accordance with good Soil Conservation practice and in such a manner that none can be carried into any drainage facility or water course. The Contractor shall be responsible for disposing of all spoil or excess excavated material on a site approved by the Soil Conservation District. Documentation of approval and site shall be provided to the Engineer prior to beginning work.
- The Howard County Soil Conservation District must be notified in writing by the Contractor as to where excess material will be disposed from the project, copies shall be provided to the Engineer.
- Continuos inspection and maintenance of all Sediment and Erosion Control Devices will be required.
- 10. The Contractor shall provide additional Soil Erosion and Sediment Control as required by the Sediment Control Inspector, as the work progresses or requires.
- The Contractor shall notify in writing, a Howard County Sediment Control Division representative at least three (3) days prior to starting work. Please contact: Howard County 992-2436. Copies shall be provided to the Engineer.
- 12. The Contractor shall place a stabilized construction entrance as shown in the Howard County Standard Details, G6.11 where shown on the PLANS unless otherwise directed by the Engineer.
- Sediment Removal— all trapped sediment is to be removed and disposed of at the authorized landfills prior to removal of Sediment Control Structures.
- Following initial soil disturbance, or redisturbance, permanent or temporary stabilization shall be completed within:
  - Seven (7) calendar days for all perimeter Sediment Control Structures, dikes, swales, ditches, perimeter slopes and all slopes greater than 3:1.
  - Fourteen (14) days as to all other disturbed or graded areas on the project site.

ENGINEER'S CERTIFICATION I CERTIFY THAT THIS PLAN FOR EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE HOWARD COUNTY SOIL CONSERVATION DISTRICT. blu Wallace 4.19.88

WALLACE, MONTGOMERY & ASSOCIATES 1544 YORK ROAD LUTHERVILLE, MARYLAND 21093 (301) 494-9093

REVIEWED FOR HOWARD COUNTY S.C.D. MEETS TECHNICAL REQUIREMENTS.

THIS DEVELOPMENT PLAN IS APPROVED FOR THE SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD COUNTY CONSERVATION DISTRICT.

HOWARD COUNTY S.C.D.

DEPARTMENT OF PUBLIC WORKS HOWARD COUNTY, MARYLAND

WALLACE, MONTGOMERY & ASSOCIATES 1544 YORK ROAD LUTHERVILLE, MARYLAND 21093 (301) 494-9093

DES: J.C.W. John Waltace

DRN: ら.W.ら. 1 CHANGED CONT IT FROM 1789 TO 1759 PERM HARIKA 4.4.8 DATE: 6-29-88 DATE 600 SCALE MAP NO. 25

DETAILS OF SEWER EXTENSION

BLOCK NO.

COURT HOUSE DRIVE ROUTINE SEWER EXTENSION CAPITAL PROJECT S 6688 **CONTRACT NO. 10-1759** ELECTION DISTRICT NO. 2 HOWARD COUNTY, MARYLAND

SCALE SHOWN

SHEET 2 of 2