


MATCHLINE (SEE SHEET GROS)



THIS DEVELOPMENT IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

John R. Blanton
HOWARD SCD
DATE: 9/29/11

PROFESSIONAL CERTIFICATION. I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. 31281, EXPIRATION DATE: JANUARY 24, 2013.

9/29/11

LOT 117
HOWARD COUNTY
DEPT. PARKS RECREATION
TAX MAP 30 PARCEL 393
L. 1751 F. 331
NE BRAMPTON PARKWAY
PLAT NO. 7497

LOT 78
PAUL GULOTTA
TAX MAP 30 PARCEL 393
L. 9103 F. 321
4907 N RAWCLIFFE CT
PLAT NO. 7497

LOT 21
HOWARD COUNTY
DEPT. PARKS RECREATION
TAX MAP 31 PARCEL 14
L. 1892 F. 520
RED APPLE WAY
PLAT NO. 8161

NOTES:
1. NOTE: REMOVE WOODY DEBRIS FROM STREAM AND ADJACENT TO STREAM AT DIRECTION OF ENGINEER. WOODY DEBRIS WITHIN CHANNEL BUT OUTSIDE OF LIMIT OF DISTURBANCE SHALL BE REMOVED BY HAND. NO TREES SHALL BE CLEARED UNLESS ABSOLUTELY NECESSARY TO ACCESS OR PERFORM WORK. TREES WITH FENCING AS SHOWN SHALL NOT BE REMOVED.
2. ALL TREES SHOWN SHALL NOT BE DISTURBED UNLESS SHOWN TO BE REMOVED ON PLANS, OR WITH THE APPROVAL OF THE ENGINEER.

NO.	REVISIONS DESCRIPTION	DATE

936 RIDGEBROOK ROAD
SPARKS, MARYLAND 21152
TELEPHONE: (410) 316-7800
FAX: (410) 316-7818
www.kci.com

KCI
TECHNOLOGIES

THRESHFIELD COURT
STREAM RESTORATION PROJECT

CAPITAL PROJECT D-1158
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
300 EAST COLUMBIA, 2ND FLOOR
BETHESDA, MD 20814

GRADING PLAN


SCALE: 1" = 20'
DATE: SEPTEMBER 2011
KCIJOB NO.: 01-081795.53
CAPITAL PROJECT NO.: D-1158
PERMIT ISSUE:
CONSTRUCTION ISSUE:

GR04
SHEET NO.: 10 OF 27

KCI FILE: M:\2008\01081795.53

ED-17-2011

MATCHLINE (SEE SHEET ES02)



MATCHLINE (SEE SHEET ES04)

THIS DEVELOPMENT IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.


John R. Poluto
 HOWARD SCD
 DATE: 9/29/11



PROFESSIONAL CERTIFICATION: I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. 31201. EXPIRATION DATE: JANUARY 24, 2013

NO.	REVISIONS DESCRIPTION	DATE

936 RIDGEBROOK ROAD
 SPARKS, MARYLAND 21152
 TELEPHONE: (410) 316-7800
 FAX: (410) 316-7818
 www.kci.com



THRESHFIELD COURT
 STREAM RESTORATION PROJECT

CAPITAL PROJECT D-1158
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
 PERMITTING AND CONSTRUCTION MANAGEMENT DIVISION
 6751 COLUMBIA AVENUE
 COLUMBIA, MD 21046



EROSION AND
 SEDIMENT
 CONTROL
 PLAN

SCALE: 1" = 20'
 DATE: SEPTEMBER 2011
 KCI JOB NO.: 01-081795.53
 CAPITAL PROJECT NO.: D-1158
 PERMIT ISSUE:
 CONSTRUCTION ISSUE:

ES03
 SHEET NO.: 16 OF 27

EP-12-005


PLOTTED: 09/27 AM 10:00 Thursday, September 29, 2011
 PLOTTER: HP DesignJet 2400 Plotter
 FILE: M:\2008\081795.53\Drawings\ES-1003_Threshfield.dwg



SUPER SILT FENCE

Design Criteria


Slope	Slope Steepness	Slope Length (maximum)	Silt Fence Length (maximum)
0 - 10%	0 - 10:1	Unlimited	Unlimited
10 - 20%	10:1 - 5:1	200 feet	1,500 feet
20 - 33%	5:1 - 3:1	100 feet	1,000 feet
33 - 50%	3:1 - 2:1	100 feet	500 feet
50% +	2:1 +	50 feet	250 feet



TEMPORARY ACCESS CULVERT

Construction Specifications

- Restrictions - No construction or removal of a temporary access culvert will be permitted between October 1 through April 30 for Class III and Class IV Trout Waters or between March 1 through June 15 for non-trout waterways.
- Culvert Strength - All culverts shall be strong enough to support their cross-sectional area under maximum expected loads.
- Culvert Size - The size of the culvert pipe shall be the largest pipe diameter that will fit into the existing channel without major excavation of the waterway channel or without major approach fills. If a channel width exceeds 3 feet, additional pipes may be used until the cross-sectional area of the pipes is greater than 60 percent of the cross-sectional area of the existing channel. The minimum size culvert that may be used is a 12\"/>
- Culvert Length - The culvert(s) shall extend a minimum of one foot beyond the upstream and downstream toe to the aggregate placed around the culvert. In no case shall the culvert exceed 40 feet in length.
- Filter Cloth - Filter cloth shall be placed on the streambed and streambanks prior to placement of the pipe culvert(s) and aggregate. The filter cloth shall cover the streambed and extend a minimum six inches and a maximum one foot beyond the end of the culvert and bedding material. Filter cloth reduces settlement and improves crossing stability.
- Culvert Placement - The invert elevation of the culvert shall be installed on the natural streambed grade to minimize interference with fish migration (free passage of fish).
- Culvert Protection - The culvert(s) shall be covered with a minimum of one foot of aggregate. If multiple culverts are used they shall be separated by at least 12\"/>
- Stabilization - All areas disturbed during culvert installation shall be stabilized within 14 calendar days of the disturbance in accordance with the Standard for "Critical Area Stabilization With Permanent Seeding."




FILTER BAG SPECIFICATIONS

- Filter bag shall be made of non-woven geotextile with a minimum surface area of 225 square feet per side.
- All structural seams shall be sewn with a double stitch using a double needle machine with high strength thread. Seam strength shall withstand 100 lb/in using ASTM D-4884 test method.
- Filter bag shall have a nozzle large enough to accommodate a four(4) inch diameter pump discharge hose.
- Nozzle shall be sealed tightly around the pump discharge hose with a strap or similar device to prevent unfiltered water from escaping.
- Filter bag shall be placed on a level or gently sloping (5% maximum) area.
- Filter bag shall be placed upon a base of straw bales or three (3) inches of clean stone to promote dewatering through bottom surface of the filter bag.
- Pumping rates shall be controlled to prevent excessive pressure within the filter bag. As the bag becomes filled with sediment the pumping rate shall be reduced.
- The filter bag shall be dewatered, removed and disposed of upon completion of pumping operations or after it has reached capacity, whichever occurs first. The dewatered sediment from the bag shall be spread in an upland area and stabilized within 24 hours.
- The geotextile fabric shall meet the following minimum requirements with properties determined in accordance with the following procedures:

WEIGHT	10 OZ/YD	ASTM D-3778
GRAB TENSILE	210 LBS.	ASTM D-4632
PUNCTURE	750 LBS.	ASTM D-4833
FLOW RATE	70 GAL/MIN/FT ²	ASTM D-4491
PERMEABILITY (SEC)	1.5	ASTM D-4991
UV RESISTANCE	70%	ASTM D-4355
APPARENT OPENING SIZE (AOS)	40-80	ASTM D-4751

NOTE: ALL WATER COLLECTED WITHIN THE LIMIT OF DISTURBANCE (WITH THE EXCEPTION OF WATER DIVERTED AROUND THE WORK AREA) SHALL BE PUMPED THROUGH THE FILTER BAG.



MOWC 1.2: PUMP-AROUND PRACTICE

Temporary measure for dewatering in-channel construction sites


DESCRIPTION

The work should consist of installing a temporary pump around and supporting measures to divert flow around in-stream construction sites.

IMPLEMENTATION SEQUENCE

Sediment control measures, pump-around practices, and associated channel and bank construction should be completed in the following sequence (refer to Detail 1.2):

- Construction activities including the installation of erosion and sediment control measures should not begin until necessary easements and/or right-of-way have been acquired. All existing utilities should be marked in the field prior to construction. The contractor is responsible for any damage to existing utilities that may result from construction and should report the damage of his/her own expense to the county's or utility company's satisfaction.
- The contractor should notify the Maryland Department of the Environment or WMA sediment control inspector at least 5 days before beginning construction. Additionally, the contractor should inform the local environmental protection and resource management inspection and enforcement division and the provider of local utilities a minimum of 48 hours before starting construction.
- The contractor should conduct a pre-construction meeting on site with the WMA sediment control inspector, the county project manager, and the engineer to review limits of disturbance, erosion and sediment control requirements, and the sequence of construction. The contractor should state out of limits of disturbance prior to the pre-construction meeting so they may be reviewed. The participants will designate the contractor's staging areas. Trees should not be removed within the limit of disturbance without approval from the WMA or local authority.
- Construction should not begin until sediment and erosion control measures have been installed and approved by the engineer and the sediment control inspector. The contractor should stay within the limits of the disturbance as shown on the plans and minimize disturbance within the work area whenever possible.
- Upon installation of all sediment control measures and approved by the sediment control inspector and the local environmental protection and resource management inspection and enforcement division, the contractor should begin work at the upstream section and proceed downstream beginning with the establishment of stabilized construction entrances. In some cases, work may begin downstream if appropriate. The sequence of construction must be followed unless the contractor gets written approval for deviations from the WMA or local authority. The contractor should only begin work in an area which can be completed by the end of the day including grading adjacent to the channel. At the end of each workday, the work area must be stabilized and the pump around removed from the channel. Work should not be conducted in the channel during rain events.
- Sandbag dikes should be situated at the upstream and downstream ends of the work area as shown on the plans, and stream flow should be pumped around the work area. The pump should discharge into a stable velocity dissipator made of rip rap or sandbags.
- Water from the work area should be pumped to a sediment filtering measure such as a dewatering basin, sediment bag, or other approved source. The measure should be located such that the water drains back into the channel below the downstream sandbag dike.
- Traversing a channel reach with treatment within the work area where no work is proposed should be avoided. If equipment has to traverse such a reach for access to another area, then timber mats or similar measures should be used to minimize disturbance to the channel. Temporary stream crossings should be used only when necessary and only where noted on the plans or specified. (See Section 4, Stream Crossings, Maryland Guidelines to Waterway Construction).
- All stream restoration measures should be installed as indicated by the plans and at banks graded in accordance with the grading plans and typical cross-sections. All grading must be stabilized at the end of each day with seed and mulch or seed and matting as specified on the plans.
- After an area is completed and stabilized, the clean water dike should be removed. After the first sediment flush, a new clean water dike should be established between the old sediment dike. Finally, upon establishment of a new sediment dike below the old one, the old sediment dike should be removed.
- A pump around must be installed on any tributary or storm drain outlet, which contributes baseflow to the work area. This should be accomplished by locating a sandbag dike at the downstream end of the tributary or storm drain outlet and pumping the stream flow around the work area. This water should discharge onto the same velocity dissipator used for the main stem pump around.
- If a tributary is to be restored, construction should take place on the tributary before work on the main stem reaches the tributary confluence. Construction in the tributary, including pump around practices, should follow the same sequence as for the main stem of the river or stream. When construction on the tributary is completed, work on the main stem should resume. Water from the tributary should continue to be pumped around the work area in the main stem.
- The contractor is responsible for providing access to and maintaining erosion and sediment control devices until the sediment control inspector approves their removal.
- After construction, all disturbed areas should be regraded and revegetated as per the planting plan.



SILT FENCE

Silt Fence Design Criteria

Slope Steepness	Silt Fence Length (Maximum)	
	Slope Length	Silt Fence Length
Flatter than 50:1	unlimited	unlimited
50:1 to 10:1	125 feet	1,000 feet
10:1 to 5:1	100 feet	750 feet
5:1 to 3:1	60 feet	500 feet
3:1 to 2:1	40 feet	250 feet
2:1 and steeper	20 feet	125 feet

Note: In areas of less than 2% slope and sandy soils (USDA general classification system, soil Class A) maximum slope length and silt fence length will be unlimited. In these areas a silt fence may be the only perimeter control required.

THIS DEVELOPMENT IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.

John P. Roberts
 HOWARD SCD
 DATE: 9/29/10

PROFESSIONAL CERTIFICATION: I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 31201, EXPIRATION DATE: JANUARY 24, 2013

STATE OF MARYLAND
 PROFESSIONAL ENGINEER
 NO. 31201

THRESHIELD COURT
 STREAM RESTORATION PROJECT

EROSION & SEDIMENT CONTROL NOTES & DETAILS

SCALE: AS SHOWN
 DATE: SEPTEMBER 2011
 KCI JOB NO.: 01-081795.53
 CAPITAL PROJECT NO.: D-1158
 PERMIT ISSUE:
 CONSTRUCTION ISSUE:

ES05
 SHEET NO.: 18 OF 27

9/29/10

936 RIDGEBROOK ROAD
 SPARKS, MARYLAND 21152
 TELEPHONE: (410) 316-7800
 FAX: (410) 316-7818
 www.kci.com

KCI TECHNOLOGIES

CAPITAL PROJECT D-1158
 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
 STREAM RESTORATION MANAGEMENT DIVISION
 670 COLUMBIA ROAD, 2ND FLOOR
 COLLEGE PARK, MD 20740

KCI FILE: M-A-2008-01081795.53

SEQUENCE OF CONSTRUCTION

HOWARD COUNTY CONSERVATION DISTRICT
STANDARD SEDIMENT CONTROL NOTES

- OBTAIN GRADING PERMIT. STREAM CLOSURE PERIOD IS MARCH 1-JUNE 15, INCLUSIVE. MDE PERMIT TRACKING #20116117/11-NT-0283. PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITIES, A VIDEO TAPE AND PHOTOGRAPHS OF THE PROPOSED WORK AREA SHALL BE TAKEN. (1 DAY)
 - CONTRACTOR SHALL COORDINATE AN ON-SITE PRE-CONSTRUCTION MEETING WHICH SHALL INCLUDE, BUT NOT BE LIMITED TO, THE COUNTY PROJECT MANAGER, THE ENGINEER, A REPRESENTATIVE FROM MDE, AND A REPRESENTATIVE FROM HOWARD COUNTY CONSTRUCTION INSPECTION. THE LIMIT OF DISTURBANCE SHALL BE STAKED PRIOR TO THE MEETING. (1 DAY)
 - NOTIFY THE MARYLAND DEPARTMENT OF THE ENVIRONMENT'S NONTIDAL WETLANDS AND WATERWAYS INSPECTIONS AND COMPLIANCE DIVISION AT LEAST FIVE (5) DAYS PRIOR TO ANY EARTH MOVING CONSTRUCTION WITHIN NONTIDAL WETLANDS AND/OR THEIR BUFFERS. THE CONTRACTOR SHALL NOTIFY "MISS UTILITY" AT 1-800-257-7777 AT LEAST FIVE (5) WORKING DAYS PRIOR TO ANY WORK BEING DONE. THE CONTRACTOR SHALL NOTIFY THE HOWARD COUNTY CONSTRUCTION INSPECTION DIVISION (410-313-1880) A MINIMUM OF 24 HOURS PRIOR TO THE START OF ANY CONSTRUCTION. (5 DAYS)
 - CONSTRUCT ORANGE SAFETY FENCE AS SHOWN ON THE PLANS. HOWARD COUNTY STORMWATER MANAGEMENT DIVISION SHALL REVIEW AND APPROVE THE LOCATION OF THE ORANGE SAFETY FENCE PRIOR TO ANY EARTH MOVING OR REMOVING OF EXISTING TREES OR SHRUBS. (1 WEEK)
 - WORK WILL PROCEED FROM UPSTREAM TO DOWNSTREAM. PERFORM ITEMS 6-11 BELOW FOR EACH OF THE WORK AREAS AS SHOWN ON THE PLANS. WORK AREAS ARE THOSE AREAS ISOLATED FROM THE REMAINING CHANNEL BY A PUMP AROUND PRACTICE, INCLUDING THE WESTERN TRIBUTARY.
 - CONSTRUCT STABILIZED CONSTRUCTION ENTRANCES AS NEEDED FOR THE ACTIVE WORK AREAS AND ESTABLISH CONTROLS AROUND THE TEMPORARY STOCKPILE/STAGING AREAS. (5 DAYS)
 - CLEAR AND GRUB ONLY AS NECESSARY FOR INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND DEVICES FOR THE ACTIVE WORK AREA, INCLUDING PUMP AROUND PRACTICES. INSTALL TEMPORARY CULVERT ACCESS AND STABILIZE THE AREA DISTURBED BY THE INSTALLATION. SEDIMENT-LADEN WATER SHALL NOT BE DISCHARGED DIRECTLY INTO THE STREAM. (5 DAYS)
 - CONSTRUCT UPSTREAM SAND BAG DAM WITHIN THE ACTIVE WORK AREA. THIS INCLUDES SAND BAG DAMS WITHIN THE TRIBUTARIES. PLACE PUMP AROUND HOSE ON THE CHANNEL BANK AS SHOWN ON THE PLANS. BEGIN PUMP AROUND OPERATION FOR ACTIVE WORK AREA ONLY, DISCHARGING ONTO SAND BAGS AT OUTFALL. (EACH WORK DAY)
 - CONSTRUCT DOWNSTREAM SAND BAG DAM WITHIN THE ACTIVE WORK AREA. SEDIMENT-LADEN WATER SHALL NOT BE DISCHARGED DIRECTLY INTO THE STREAM. DEWATERING ENTRAPPED AREA BEHIND SAND BAGS TO A FILTER BAG DEWATERING DEVICE PRIOR TO DISCHARGE IN TO THE STREAM. (EACH WORK DAY)
 - CONSTRUCT GRADING AND RESTORATION STRUCTURES FROM UPSTREAM TO DOWNSTREAM WITHIN EACH WORK AREA. STABILIZE DISTURBED AREAS AT THE END OF EACH DAY. REMOVE SAND BAG DIVERSIONS AT THE END OF EACH WORKING DAY. (2 WEEKS EACH WORK AREA; TOTAL OF 8 WEEKS)
 - CONSTRUCT DOWNSTREAM SAND BAG DAM WITH DEWATERING DEVICE BEHIND SAND BAGS WITHIN THE EASTERN TRIBUTARY. CONSTRUCT GRADING AND RESTORATION STRUCTURES FROM UPSTREAM TO DOWNSTREAM. STABILIZE DISTURBED AREAS AT THE END OF EACH DAY. (10 DAYS)
 - INSTALL LANDSCAPING AS SPECIFIED ON THE PLAN. (5 DAYS)
 - UPON COMPLETION OF CONSTRUCTION ACTIVITIES IN EACH WORK AREA, AND WITH APPROVAL FROM THE SEDIMENT CONTROL INSPECTOR, REMOVE PUMP AROUND PRACTICES AND BEGIN WORK IN THE NEXT WORK AREA. (1 DAY)
 - WHEN VEGETATION IS ESTABLISHED AND WITH PERMISSION OF THE HOWARD COUNTY SEDIMENT CONTROL INSPECTOR, REMOVE ALL REMAINING EROSION AND SEDIMENT CONTROL MEASURES AND PERMANENTLY STABILIZE THOSE AREAS DISTURBED BY THIS PROCESS. (3 DAYS)
 - CONDUCT FINAL "AS-BUILT" SURVEY OF STREAM RESTORATION MEASURES AND STREAM PROFILE WITHIN RESTORATION AREAS AND SUBMIT "AS-BUILT" PLANS TO THE DEPARTMENT OF PUBLIC WORKS, STORMWATER MANAGEMENT DIVISION WITHIN 30 DAYS OF COMPLETION OF CONSTRUCTION. (30 DAYS)
- NOTE: HARVESTING AND INSTALLATION OF LIVE STAKES SHALL ONLY OCCUR DURING THE DORMANT SEASON, I.E. NOVEMBER 1 THROUGH MARCH 1.

- A minimum of 48 hours notice must be given to the Howard County Department of Inspections. Licenses and Permits, Sediment Control Division prior to the start of any construction (410 313-1855).
 - All vegetative and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the most current MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL and revisions thereto.
 - Following initial soil disturbance or re-disturbance, permanent or temporary stabilization shall be completed within: a) 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes and all slopes greater than 3:1, b) 14 days as to all other disturbed or graded areas on the project site.
 - All disturbed areas must be stabilized within the time period specified above in accordance with the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for permanent seeding (Sec. 51), sod (Sec. 54), temporary seeding (Sec. 50) and mulching (Sec. 52). Temporary stabilization with mulch alone can only be done when recommended seeding dates do not allow for proper germination and establishment of grasses.
 - All sediment control structures are to remain in place and are to be maintained in operative condition until permission for their removal has been obtained from the Howard County Sediment Control Inspector.
6. Site Analysis:
- | | | |
|------------------------------------|------------------|----------|
| Total Area of Site | 2.99 | Acres |
| Area Disturbed | 2.99 | Acres |
| Area to be roofed or paved | 0.00 | Acres |
| Area to be vegetatively stabilized | 2.99 | Acres |
| Total Cut | 575 | Cu. Yds. |
| Total Fill | 1257 | Cu. Yds. |
| Offsite waste/borrow area location | To Be Determined | |
- Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
 - Additional sediment control must be provided, if deemed necessary by the Howard County Sediment Control Inspector.
- * Offsite waste/ borrow area, if needed, shall have an approved erosion and sediment control plan and active permit.

HOWARD SOIL CONSERVATION DISTRICT
TEMPORARY SEEDING NOTES

Apply to graded or cleared areas likely to be re-disturbed where a short-term vegetative cover is needed.

Seedbed preparation: -- Loosen upper three inches of soil by raking, disking or other acceptable means before seeding, if not previously loosened.

Soil Amendments: -- Apply 600 lbs/acre 10-10-10 fertilizer (14 lbs/1000 sq. ft.).

Seeding: -- For periods March 1 - April 30 and from August 15 - October 15, seed with 2-1/2 bushel per acre of annual rye (3.2 lbs/1000 sq. ft.). For the period May 1 - August 14, seed with 3 lbs/acre of weeping lovegrass (.07 lbs/1000 ft.). For the period November 16 - February 28, protect site by applying 2 tons/acre of well anchored straw mulch and seed as soon as possible in the spring, or use sod.

Mulching: -- Apply 1-1/2 to 2 tons/acre (70 to 90 lbs/1000 sq. ft.) of unrotted weed-free, small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool. No asphalt emulsion shall be used for anchoring. Only a non-toxic, latex backing material is allowed.

Refer to the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for additional rates and methods not covered.

HOWARD SOIL CONSERVATION DISTRICT
PERMANENT SEEDING NOTES

Apply to graded or cleared areas not subject to immediate further disturbance where a permanent long-lived vegetative cover is needed.

Seedbed Preparation: Loosen upper three inches of soil by raking, disking or other acceptable means before seeding, if not previously loosened.

Soil Amendments: In lieu of soil test recommendations, use one of the following schedules:

- Preferred** -- Apply 2 tons/acre dolomitic limestone (92 lbs/1000 sq. ft.) and 600 lbs/acre 10-10-10 fertilizer (14 lbs/1000 sq. ft.) before seeding. Harrow or disk into upper three inches of soil. At time of seeding, apply 400 lbs/acre 30-0-0 ureaform fertilizer (9 lbs/1000 sq. ft.)
- Acceptable** -- Apply 2 tons/acre dolomitic limestone (92 lbs/1000 sq. ft.) and 1000 lbs/acre 10-10-10 fertilizer (23 lbs/1000 sq. ft.) before seeding. Harrow or disk into upper three inches of soil.

21.0 STANDARD AND SPECIFICATIONS FOR TOPSOIL

Definition
Placement of topsoil over a prepared subsoil prior to establishment of permanent vegetation.

Purpose
To provide a suitable soil medium for vegetative growth. Soils of concern have low moisture content, low nutrient levels, low pH, materials toxic to plants, and/or unacceptable soil gradation.

Conditions Where Practice Applies

- This practice is limited to areas having 2:1 or flatter slopes where:
 - The texture of the exposed subsoil/parent materials is not adequate to produce vegetative growth.
 - The soil material is so shallow that the rooting zone is not deep enough to support plants or furnish continuing supplies of moisture and plant nutrients.
 - The original soil to be vegetated contains material toxic to plant growth.
 - The soil is so acidic that treatment with limestone is not feasible.
- For the purpose of these Standards and Specifications, areas having slopes steeper than 2:1 require special consideration and design for adequate stabilization. Areas having slopes steeper than 2:1 shall have the appropriate stabilization shown on the plans.

Construction and Material Specifications


- Topsoil salvaged from the existing site may be used provided that it meets the standards as set forth in these specifications. Typically, the depth of topsoil to be salvaged for a given soil type can be found in the representative soil profile section in the Soil Survey published by USDA-SCS in cooperation with Maryland Agricultural Experiment Station.
- Topsoil Specifications - Soil to be used as topsoil must meet the following:
 - Topsoil shall be a loam, sandy loam, clay loam, silt loam, sandy clay loam, loamy sand. Other soils may be used if recommended by an agronomist or soil scientist and approved by the appropriate approval authority. Regardless, topsoil shall not be a mixture of contrasting textured subsoils and shall contain less than 5% by volume of cinders, stones, slag, coarse fragments, gravel, sticks, roots, trash, or other materials larger than 1 1/2" in diameter.
 - Topsoil must be free of plants or plant parts such as bermuda grass, quackgrass, Johnsongrass, nutsedge, poison ivy, thistle, or others as specified.
 - Where the subsoil is either highly acidic or composed of heavy clays, ground limestone shall be spread at the rate of 4-6 tons/acre (200-400 pounds per 1,000 square feet) prior to the placement of topsoil. Lime shall be distributed uniformly over designated areas and worked into the soil in conjunction with tillage operations as described in the following procedures.
- For sites having disturbed areas under 5 acres:
 - Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section I - Vegetative Stabilization Methods and Materials.
- For sites having disturbed areas over 5 acres:
 - On soil meeting Topsoil specifications, obtain test results dictating fertilizer and lime amendments required to bring the soil into compliance with the following:
 - pH for topsoil shall be between 6.0 and 7.5. If the tested soil demonstrates a pH of less than 6.0, sufficient lime shall be prescribed to raise the pH to 6.5 or higher.
 - Organic content of topsoil shall be not less than 1.5 percent by weight.
 - Topsoil having soluble salt content greater than 500 parts per million shall not be used.
 - No sod or seed shall be placed on soil which has been treated with soil sterilants or chemicals used for weed control until sufficient time as elapsed (14 days min.) to permit dissipation of phyto-toxic materials.

Note: Topsoil substitutes or amendments, as recommended by a qualified agronomist or soil scientist and approved by the appropriate approval authority, may be used in lieu of natural topsoil.

- Place topsoil (if required) and apply soil amendments as specified in 20.0 Vegetative Stabilization - Section I - Vegetative Stabilization Methods and Materials.

V. Topsoil Application

- When topsoiling, maintain needed erosion and sediment control practices such as diversions, Grade Stabilization Structures, Earth Dikes, Slope Silt Fence and Sediment Traps and Basins.
- Grades on the areas to be topsoiled, which have been previously established, shall be maintained, albeit 4" - 8" higher in elevation.
- Topsoil shall be uniformly distributed in a 4" - 8" layer and lightly compacted to a minimum thickness of 4". Spreading shall be performed in such a manner that sodding or seeding can proceed with a minimum of additional soil preparation and tillage. Any irregularities in the surface resulting from topsoiling or other operations shall be corrected in order to prevent the formation of depressions or water pockets.
- Topsoil shall not be placed while the topsoil or subsoil is in a frozen or muddy condition, when the subsoil is excessively wet or in a condition that may otherwise be detrimental to proper grading and seedbed preparation.



MGWC 1.5: SANDBAG/STONE CHANNEL DIVERSION

DESCRIPTION

The work should consist of installing sandbag or stone flow diversions for the purpose of erosion control when construction activities occur within the stream channel.

EFFECTIVE USES & LIMITATIONS

Diversions are used to isolate work areas from flow during the construction of in-stream projects. Diversions which have an insufficient flow capacity can fail and severely erode the disturbed channel section under construction. Therefore, in-channel construction activities should occur only during periods of low rainfall. This temporary measure may not be practical in large channels.

MATERIAL SPECIFICATIONS

Material for sandbag and stone stream diversions should meet the following requirements:

- Riprap: Riprap should be washed and have a minimum diameter of 6 inches (0.15 meters). Sandbags: Sandbags should consist of materials which are resistant to ultra-violet radiation, tearing, and puncture and should be woven tightly enough to prevent leakage of the fill material (i.e., sand, fine gravel, etc.). Sheet piling: Sheet piling should consist of polyethylene or other materials which are impervious and resistant to puncture and tearing.

INSTALLATION GUIDELINES


All erosion and sediment control devices, including dewatering basins, should be implemented as the first order of business according to a plan approved by the WMA or local authority. Installation should proceed from upstream to downstream during periods of low flow. If necessary, silt fence or straw bales should be installed around the perimeter of the work area.

Sandbag/stone diversions can be used independently or as components of other stream diversion techniques. Installation of this measure should proceed as follows (refer to Detail 1.5):

- The diversion structure should be installed from upstream to downstream.
- The height of the sandbag/stone diversion should be a function of the duration of the project in the stream reach. For projects with a duration less than 2 weeks, the height of the diversion should be one half the streambank height, measured from the channel bed, plus 1 foot (0.3 meters) or bankfull height, whichever is greater. For projects of longer duration, the top of the sandbag or stone diversion should correspond to bankfull height. For diversion structures utilizing sandbags, the stream bed should be hand prepared prior to placement of the base layer of sandbags in order to ensure a water tight fit. Additionally, it may be necessary to prepare the bank in a similar fashion.
- All excavated material should be deposited and stabilized in an approved area outside the 100-year floodplain unless otherwise authorized by the WMA.
- Sediment-laden water from the construction area should be pumped to a dewatering basin.
- Sheeting on the diversion should be positioned such that the upstream portion covers the downstream portion with at least a 18-inch (0.45 meters) overlap.
- Sandbag or stone diversions should not obstruct more than 45% of the stream width. Additionally, bank stabilization measures should be placed in the constricted section if accelerated erosion and bank scour are observed during the construction time or if project time is expected to last more than 2 weeks.
- Prior to removal of these temporary structures, any accumulated sediment should be removed, deposited and stabilized in an approved area outside the 100-year floodplain unless authorized by the WMA.
- Sediment control devices are to remain in place until all disturbed areas are stabilized in accordance with an approved sediment and erosion control plan and the inspecting authority approves their removal.

THIS DEVELOPMENT IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.


John D. Hunter
HOWARD SCD
9/29/11
DATE



PROFESSIONAL CERTIFICATION. I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 31201, EXPIRATION DATE: JANUARY 24, 2013

NO.	REVISIONS DESCRIPTION	DATE

936 RIDGEBROOK ROAD
SPARKS, MARYLAND 21152
TELEPHONE: (410) 316-7800
FAX: (410) 316-7818
www.kci.com



THRESHIELD COURT
STREAM RESTORATION PROJECT
CAPITAL PROJECT D-1158
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
STORMWATER MANAGEMENT DIVISION
1000 COLUMBIA AVENUE
COLUMBIA, MD 21046

EROSION & SEDIMENT CONTROL NOTES & DETAILS

SCALE:	AS SHOWN
DATE:	SEPTEMBER 2011
KCI JOB NO.:	01-081795.53
CAPITAL PROJECT NO.:	D-1158
PERMIT ISSUE:	
CONSTRUCTION ISSUE:	
	ES06
	SHEET NO.: 19 OF 27

EP-12-006

PLOTTED: 09/26/11, 10:41 AM, Thursday, September 29, 2011
By: Kelsey Peter, Division: POC3, Water Resources OMA, Emp
FILE: M:\2008\01081795.53\Drawings\SES-POD6 - Threshfield.dgn




675

E 13650000
N 572800

Brampton Hills
Acct. 1402294044
F 85-052

E 13653000
N 572800



Brampton Hills
Acct. 130217082
F 85-052

E 13653000
N 572800


LEGEND	
LIVE STAKE ZONE 2376 SF / 0.055 AC	
HERBACEOUS ZONE 3644 SF / 0.084 AC	
RIPARIAN FOREST ZONE 8855 SF / 0.203 AC	



PROFESSIONAL CERTIFICATION. I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. 31201, EXPIRATION DATE: JANUARY 24, 2013

NO.	REVISIONS DESCRIPTION	DATE

936 RIDGEBROOK ROAD
SPARKS, MARYLAND 21152
TELEPHONE: (410) 316-7800
FAX: (410) 316-7818
www.kci.com



THRESHFIELD COURT
STREAM RESTORATION PROJECT
CAPITAL PROJECT D-1158
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
STREETWORKS AND MAINTENANCE DIVISION
1000 COLUMBIA AVE
COLUMBIA, MD 21046

LANDSCAPE PLAN

SCALE: 1" = 20'
DATE: SEPTEMBER 2011
KCI JOB NO.: 01-081795.53
CAPITAL PROJECT NO.: D-1158
PERMIT ISSUE:
CONSTRUCTION ISSUE:

LS01
SHEET NO.: 20 OF 27

MATCHLINE (SEE SHEET LS01)

Brampton Hills
 Acct: 1402294148
 E-85-052

E 13656000
 N 572200


Brampton Hills
 Acct: 1402324148
 E-87-172

E 13654000
 N 572200



LEGEND

LIVE STAKE ZONE 3,840 SF / 0.084 AC	
HERBACEOUS ZONE 7,262 SF / 0.161 AC	
RIPARIAN FOREST ZONE 22,680 SF / 0.521 AC	
TURF GRASS ZONE 7,012 SF / 0.161 AC	
ALTERNATING ROUGHNESS PLANTING ZONE 150 SF / 0.003 AC	



MATCHLINE (SEE SHEET LS03)

PROFESSIONAL CERTIFICATION, I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. 31201, EXPIRATION DATE: JANUARY 24, 2013.

PLOTTED: 11:09:53 AM on Thursday, September 29, 2011
 BY: Kristy Potter Division: P003 Water Resources OMA, Emp
 1008109726: 25:53 Drawing: PLS_P002 - Threshfield.dgn

NO.	REVISIONS DESCRIPTION	DATE
<p>936 RIDGEBROOK ROAD SPARKS, MARYLAND 21152 TELEPHONE: (410) 316-7800 FAX: (410) 316-7818 www.kci.com</p>		
<p>THRESHFIELD COURT STREAM RESTORATION PROJECT</p> <p>CAPITAL PROJECT D-1158 HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS 8701 COLUMBIA, GAITHERSBURG, MD 20878</p>		
<p>LANDSCAPE PLAN</p>		
SCALE:	1" = 20'	
DATE:	SEPTEMBER 2011	
KCIJOB NO.:	01-081795.53	
CAPITAL PROJECT NO.:	D-1158	
PERMIT ISSUE:		
CONSTRUCTION ISSUE:		
<p>LS02</p>		
<p>SHEET NO.: 21 OF 27</p>		

EP-12-006

MASTER PLANT SCHEDULE

LIVE STAKES (SHEETS 20-23 OF 27) (12,839 SQ FT / 0.29 AC)

Qty	Botanical Name	Common Name	Size	Form	Spacing/Rate
803	<i>Cornus racemosa</i>	Gray Dogwood	3' Length 1"-1.5" dia.	Dormant stems	2' O.C.
803	<i>Cornus amomum</i>	Silky Dogwood	3' Length 1"-1.5" dia.	Dormant stems	2' O.C.
803	<i>Alnus incana ssp. rugosa</i>	Speckled Alder	3' Length 1"-1.5" dia.	Dormant stems	2' O.C.
803	<i>Salix nigra</i>	Black Willow	3' Length 1"-1.5" dia.	Dormant stems	2' O.C.

RIPARIAN ZONE (SHEETS 20-23 OF 27) (58,676 SQ FT / 1.35 AC)

Qty	Botanical Name	Common Name	Size	Form	Spacing/Rate
97	<i>Amelanchier canadensis</i>	Serviceberry	3'-5' Height	Container	10'-12' O.C.
97	<i>Betula nigra</i>	River Birch	5'-6' Height	5 Gal. Container	10'-12' O.C.
97	<i>Acer rubrum</i>	Red Maple	5'-6' Height	5 Gal. Container	10'-12' O.C.
97	<i>Quercus bicolor</i>	Swamp White Oak	5'-6' Height	3 Gal. Container	10'-12' O.C.
97	<i>Platanus occidentalis</i>	American Sycamore	5'-6' Height	3 Gal. Container	10'-12' O.C.

PERMANENT SEEDING FOR LIVE STAKES, HERBACEOUS SEED, ALTERNATING ROUGHNESS, AND RIPARIAN ZONE, AND HERBACEOUS PERENNIAL (SHEETS 20-23 OF 27) (83,894 SQ FT / 1.93 AC)

Botanical Name	Common Name	Application Rate (lbs/ac)	% of Mix	Quantity (lbs)	Remarks
<i>Panicum virgatum</i>	Switchgrass	18.0	24%	34.7	-
<i>Poa palustris</i>	Fowl Bluegrass	30.0	40%	57.9	-
<i>Panicum clandestinum</i>	Deer Tongue Grass	18.0	24%	34.7	-
<i>Bromus ciliatus</i>	Fringed Brome	9.0	12%	17.4	-

Total Application Rate of 75 lbs / ac

SEED TOTAL 144.7 lbs

ALTERNATING ROUGHNESS PLANTINGS (SHEETS 21-23 OF 27) (1,089 SQ FT / 0.03 AC / 120 LF)

Qty	Botanical Name	Common Name	Size	Type	Form	Spacing/Rate
4	<i>Platanus occidentalis</i>	American Sycamore	7' - 9' Height	Tree	Container	10' O.C.
4	<i>Acer rubrum</i>	Red Maple	7' - 9' Height	Tree	Container	10' O.C.
5	<i>Alnus incana ssp. rugosa</i>	Speckled Alder	3' Height	Shrub	Container	6' O.C.
5	<i>Viburnum dentatum</i>	Southern Arrowwood	3' Height	Shrub	Container	6' O.C.
150	<i>Cornus amomum</i>	Silky Dogwood	3' Length 1"-1.5" dia.	Live Stake	Dormant stems	5/cluster
150	<i>Cornus sericea</i>	Redosier Dogwood	3' Length 1"-1.5" dia.	Live Stake	Dormant stems	5/cluster
150	<i>Salix sericea</i>	Silky Willow	3' Length 0.5"-1.5" dia.	Live Stake	Dormant stems	5/cluster
150	<i>Salix nigra</i>	Black Willow	3' Length 0.5"-1.5" dia.	Live Stake	Dormant stems	5/cluster
60	<i>Alnus incana ssp. rugosa</i>	Speckled Alder	6' Length 2.5"-5.5" dia.	Live Pole	Dormant stems	1/cluster
60	<i>Salix sericea</i>	Silky Willow	6' Length 2.5"-5.5" dia.	Live Pole	Dormant stems	1/cluster

Note: Alternate Roughness Planting locations shall be staked for approval by the engineer, prior to installation.

FORESTED NONTIDAL WETLAND ZONE (SHEETS 22-23 OF 27) (4,618 SQ FT / 0.11 AC)

Qty	Botanical Name	Common Name	Size	Form	Spacing/Rate
19	<i>Salix nigra</i>	Black Willow	5' Height	Container	10'-12' O.C.
19	<i>Acer rubrum</i>	Red Maple	5' Height	Container	10'-12' O.C.

PERMANENT WETLAND SEED MIX (to be used within Wetland Planting Zone) (SHEETS 22-23 OF 27) (4,618 SQ FT / 0.11 AC)


Botanical Name	Common Name	Application Rate (lbs/ac)	% of Mix	Quantity (lbs)	Remarks
<i>Carex vulpinoidea</i>	Fox Sedge	5	25	0.55	-
<i>Elymus virginicus</i>	Virginia Wild Rye	6.6	33	0.73	-
<i>Carex scoparia</i>	Blunt Broom Sedge	2	10	0.22	-
<i>Carex lurida</i>	Lurid Sedge	2	10	0.22	-
<i>Scirpus atrovirens</i>	Green Bulrush	1.6	8	0.18	-
<i>Verbena hastata</i>	Swamp Verbena	1	5	0.11	-
<i>Onoclea sensibilis</i>	Sensitive Fern	0.6	3	0.07	-
<i>Scirpus pungens</i>	Common Three-Square	0.4	2	0.04	-
<i>Eupatorium fistulosum</i>	Joe Pye Weed	0.4	2	0.04	-
<i>Lobelia cardinalis</i>	Cardinal Flower	0.4	2	0.04	-

*Seed at 20 lbs per acre


SEED TOTAL 2.20 lbs

HERBACEOUS PERENNIAL (SHEET 23 OF 27) (1,396 SQ FT / 0.03 AC)


Qty	Botanical Name	Common Name	Size	Form	Spacing/Rate
155	<i>Carex blanda</i>	Common Woodland Sedge	1-quart	Container	18-24" O.C.
155	<i>Carex vulpinoidea</i>	Fox Sedge	1-quart	Container	18-24" O.C.
155	<i>Chrysanthemum latifolium</i>	Wild Oats	1-quart	Container	18-24" O.C.
155	<i>Iris virginica</i>	Virginia Iris	1-quart	Container	18-24" O.C.




SHRUB PLANTING DETAIL
NOT TO SCALE




TREE PLANTING DETAIL
NOT TO SCALE



TREE SHELTER
NOT TO SCALE



POST PLANTING DETAIL
NOT TO SCALE




TREE AND SHRUB RANDOM SPACING
NOT TO SCALE

TURF GRASS ZONE (SHEETS 21-22 OF 27) (19,667 SQ FT / 0.45 AC)

Qty (lbs)	Botanical Name
90	SHA Special Purpose Seed Mix 920.06.07 (b)



Application Rate of 200 lbs / ac

DETAIL 2.4 LIVE STAKES




SECTION VIEW

LIVE STAKES SHALL BE SPACED 2 TO 3 FEET (0.6 TO 0.9 METERS) APART TO GIVE A DENSITY OF 2 TO 4 CUTTINGS PER SQUARE YARD (0.8 SQUARE METERS).




TYPICAL PLAN VIEW
NATURAL FIBER MATTING WITH LIVE STAKES
NOT TO SCALE



HERBACEOUS PERENNIAL DETAIL
NOT TO SCALE

NO.	REVISIONS DESCRIPTION	DATE
1	ENTIRE SHEET	SEPT. 2011

936 RIDGEBROOK ROAD
SPARKS, MARYLAND 21152
TELEPHONE: (410) 316-7800
FAX: (410) 316-7818
www.kci.com



THRESHIELD COURT
STREAM RESTORATION PROJECT
CAPITAL PROJECT D-1158
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
1000 EAST-COLUMBIA AVENUE
COLUMBIA, MD 21046

LANDSCAPE NOTES AND DETAILS

SCALE:	
DATE:	SEPTEMBER 2011
KCI JOB NO.:	01-081795.53
CAPITAL PROJECT NO.:	D-1158
PERMIT ISSUE:	
CONSTRUCTION ISSUE:	

L001
SHEET NO.: 24 OF 27

EP-12-005

PLOTTED: 09/29/11 AM 10:51:34 Threshield Court Stream Restoration Project
 BY: Kristy Porter Division P053 Water Resources OMA
 FILE: M:\2008\01081795.53\Drawings\LD-P005 - Threshield.dgn



PROFESSIONAL CERTIFICATION. I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 31201, EXPIRATION DATE JANUARY 24, 2013

PLOTTED: 09:57 AM on Thursday, September 29, 2011
By: Kishy Potter, Division: P053, Water Resources QMA, Emp
FILE: M:\2008\01081795.53\Drawings\FCP01-Threshfield.dgn

THIS PLAN WAS PREPARED BY:
JENNIFER BIRD
KCI TECHNOLOGIES
MDNR QUALIFIED PROFESSIONAL
STATUS
(SEPTEMBER 2011)

SIGNATURE _____

DATE _____



VICINITY MAP
SCALE: 1" = 2000'

FOREST STAND B
BLACK CHERRY/
BLACK WILLOW
65,454 SF / 3.80 AC.
PRIORITY RETENTION


LEGEND	
EXISTING CONTOURS	CRITICAL ROOT ZONE
PROPOSED CONTOURS — 300 —	15% TO 25% SLOPES
WATERS OF THE U.S. — WUS —	25% OR GREATER SLOPES
50' STREAM BUFFER — SB —	STUDY AREA BOUNDARY
NONTIDAL WETLAND EDGE	EXISTING STORM DRAIN
25' NONTIDAL WETLAND BUFFER	EXISTING SANITARY SEWER
PROPERTY LINE	EXISTING FENCE
100-YR FLOODPLAIN LINE — — — — —	LIMIT OF DISTURBANCE — LOD —
SOILS BOUNDARY	ORANGE SAFETY (TREE PROTECTION) FENCE — OSF —
EXISTING TREE LINE	SANDBAG DIVERSION
SPECIMEN TREE	DISCHARGE HOSE
SAMPLE PLOT (1/10 ACRE)	FOREST TO BE REMOVED
HO. CO. DEPT. OF REC. & PARKS FOREST CONSERVATION EASEMENT	15' WOODY VEGETATION FREE ZONE



MATCHLINE (SEE SHEET FCP2)

NO.	REVISIONS DESCRIPTION	DATE

936 RIDGEBROOK ROAD
SPARKS, MARYLAND 21152
TELEPHONE: (410) 316-7800
FAX: (410) 316-7818
www.kci.com



THRESHFIELD COURT
STREAM RESTORATION PROJECT

CAPITAL PROJECT D-1158
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
STORMWATER MANAGEMENT DIVISION
8701 COLUMBIA, MD 21048

FOREST CONSERVATION PLAN

SCALE:	1" = 40'
DATE:	SEPTEMBER 2011
KCI JOB NO.:	01-081795.53
CAPITAL PROJECT NO.:	D-1158
PERMIT ISSUE:	
CONSTRUCTION ISSUE:	


FCP1
SHEET NO.: 25 OF 27

LEGEND

EXISTING CONTOURS		CRITICAL ROOT ZONE	
PROPOSED CONTOURS		15% TO 25% SLOPES	
WATERS OF THE U.S.		25% OR GREATER SLOPES	
50' STREAM BUFFER		STUDY AREA BOUNDARY	
NONTIDAL WETLAND EDGE		EXISTING STORM DRAIN	
25' NONTIDAL WETLAND BUFFER		EXISTING SANITARY SEWER	
PROPERTY LINE		EXISTING FENCE	
100-YR FLOODPLAIN LINE		LIMIT OF DISTURBANCE	
SOILS BOUNDARY		ORANGE SAFETY (TREE PROTECTION) FENCE	
EXISTING TREE LINE		SANDBAG DIVERSION	
SPECIMEN TREE		DISCHARGE HOSE	
SPECIMEN TREE TO BE REMOVED		FOREST TO BE REMOVED	
SAMPLE PLOT (1/10 ACRE)		PROPOSED DPR FOREST CONSERVATION EASEMENT	
HO. CO. DEPT. OF REC. & PARKS FOREST CONSERVATION EASEMENT		15' WOODY VEGETATION FREE ZONE	




MATCHLINE (SEE SHEET FCPI)



FOREST STAND A
BLACK CHERRY/
BLACK WILLOW
116,337 SF./ 2.67 AC.
PRIORITY RETENTION

FOREST STAND B
BLACK CHERRY/
BLACK WILLOW
165,454 SF./ 3.80 AC.
PRIORITY RETENTION




THIS PLAN WAS PREPARED BY:
JENNIFER BIRD
KCI TECHNOLOGIES
MDNR QUALIFIED PROFESSIONAL STATUS
(SEPTEMBER 2011)

SIGNATURE _____
DATE _____

NO.	REVISIONS DESCRIPTION	DATE

936 RIDGEBROOK ROAD
SPARKS, MARYLAND 21152
TELEPHONE: (410) 316-7800
FAX: (410) 316-7818
www.kci.com



THRESHFIELD COURT
STREAM RESTORATION PROJECT

CAPITAL PROJECT D-1158
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
STREET LIGHTING OPERATIONS DIVISION
9001 COLUMBIA, MD 21046

FOREST CONSERVATION PLAN

SCALE: 1" = 40'
DATE: SEPTEMBER 2011
KCI JOB NO.: 01-081795.53
CAPITAL PROJECT NO.: D-1158
PERMIT ISSUE:
CONSTRUCTION ISSUE:

FCP2

SHEET NO.: 26 OF 27

EP-12-005

PLOTTED: 10:58 AM on Thursday, September 29, 2011
BY: Kristy Potter, Division POC3, Water Resources GMA, Emp
FILE: M:\2008\081795\Drawings\FCP2_Threshfield.dgn

Specimen Trees			
ID	Species	Size	Condition
SP-1	White oak (<i>Quercus alba</i>)	30"	Excellent
SP-2	Tulip poplar (<i>Liriodendron tulipifera</i>)	31.5"	Excellent
SP-3	Red maple (<i>Acer rubrum</i>)	56.5"	Fair
SP-4	Pin oak (<i>Quercus prinus</i>)	33"	Good
SP-5	Tulip poplar (<i>Liriodendron tulipifera</i>)	60"	Excellent

Soils			
Mapping Unit	Description	Hydric (Y/N)	Kf Value
Ha	Hatboro-Codorus silt loam, 0-3% slopes	Yes	0.37
LaC	Legore silt loam, 8-15% slopes	No	0.02
UFA	Urban land-Fallsington complex, 0-2% slopes	Yes	None
GhB	Glenc-Urban land complex, 0-8% slopes	No	None
MoB	Mount Lucas silt loam, 3-8% slopes	Yes	0.32

FOREST CONSERVATION NOTES

- The LOD was used as the total tract area and as the net tract area (NTA) for forest conservation calculations as approved under waiver petition WP- .
- 2.08 acres of clearing will be within the 100-year floodplain. These areas will be replanted as seen on the landscape plans, sheets 20, 21, 22, and 23 of 24 and the landscape notes and details on sheet 24 of 24.
- All efforts to minimize the area of disturbance will be made.
- The 0.36 acres of forest mitigation will be satisfied through fee-in-lieu. Fee-in-lieu will be paid at \$0.75/sf. (15,682 sf. x \$0.75 = \$11,761.50).

GENERAL NOTES

- Project area is located on one property owned by Howard County Recreation and Parks (Map 30 & 31, Grid 12 & 7, Parcel 393 & 014).
- Existing Zoning: Howard open space
- Existing land use: Residential - Rural Medium Density
- Waters of the U.S. were delineated by KCI Technologies, Inc. on January 3 and 5, 2011. Waters of the U.S. shown represent the verified USACE/MDE water resource boundaries.
- Total area of nontidal wetlands within the project area: 0.63 AC.
- Total linear feet of perennial and intermittent streams: 2,895 LF
- Total forested area within limits of disturbance: 2.17 acres
- There are no Critical Habitat Areas within the project area. No rare, threatened or endangered species were encountered during the field investigations. In addition, correspondence with the Maryland Historic Trust, the U.S. Fish and Wildlife Service, and the Maryland Department of Natural Resources indicate there are no records of historic resources or sensitive natural resources within the affected area.
- No specimen trees will be removed.
- Tree Save is shown on trees within the LOD because an attempt will be made to save these trees. Trees will only be removed if necessary for grading or access.
- The coordinates shown hereon are based on Howard County geodetic control, which is based upon the Maryland State Plane Coordinate System. Howard County monument numbers 30EC and 31GB were used for this site. The existing topography is taken from field run survey with one foot contour intervals prepared by KCI Technologies, Inc., in January 2011.
- All wetland and WUS systems denoted with an asterisk (*) continue beyond the limits of the study area.

KCI Technologies, Inc. 9/23/2011


Forest Conservation Worksheet Threshold Stream Restoration Project

Net Tract Area		
A. Total Tract Area	(D x 15%)	A = 2.00 ac.
B. Area within 100-year Floodplain		B = 1.08 ac.
C. Area to Remain in Agricultural Production		C = 0.00 ac.
D. Net Tract Area (D-(A-B-C))		D = 1.31 ac.
Land Use Category : Institutional Development Areas		
E. Afforestation Threshold (D x 15%)		E = 0.20 ac.
F. Conservation Threshold (D x 20%)		F = 0.26 ac.
Existing Forest Cover		
G. Existing Forest Cover (excluding floodplain)		G = 0.16 ac.
H. Area of Forest Above Afforestation Threshold (1) If G<E then H=0 and I=0, go to L (2) If G>E then H=G-E, go to I		H = 0.00 ac.
I. Area of Forest Above Conservation Threshold (1) If G<F then I=0, go to L (2) If G>F then I=G-F, go to J		I = 0.00 ac.
Break Even Point		
J. Forest Retention Above Threshold with no Mitigation (1) If I>0 then J=(0.2 x I) + F, go to K (2) If I=0, J=0, go to L		J = 0.00 ac.
K. Clearing Permitted Without Mitigation (K=G-J)		K = 0.00 ac.
Proposed Forest Clearing		
L. Total Area of Forest to be Cleared		L = 0.16 ac.
M. Total Area of Forest to be Retained (M=G-L)		M = 0.00 ac.
Planting Requirements		
N. Reforestation for Clearing Above the Conservation Threshold (1) If L=K then N=0, P=0, Q=0, R=0, S=0, go to T (2) If L<K then N=L x 0.25, P=0, go to Q (3) If L>K then N=L x .025, go to P		N = 0.00 ac.
P. Reforestation for Clearing Below the Conservation Threshold (1) If G>F and M<F then P=0, Q=0, go to R (2) If G>F and M<F then P=2.0 x (F-M), Q=0, go to R (3) If G<F then P=2.0 x L, Q=0, go to R		P = 0.32 ac.
Q. Credit for Retention Above the Conservation Threshold (1) If M<F then Q=M-F, go to R (2) If M<F then Q=0, go to R		Q = 0.00 ac.
R. Total Reforestation Required (1) If Q>N and M<E then R=0, S=0, go to T (2) If Q<N and M<E then R=(N-P)-Q, S=0, go to T (3) If Q<N and M<E then R=N+P, go to S		R = 0.32 ac.
S. Total Afforestation Required (1) If G<E and M<E then S=E-G, go to T (2) If G<E and M<E then S=0, go to T		S = 0.04 ac.
T. Total Reforestation and Afforestation Requirement T=(R+S)		T = 0.36 ac.

StateFCW.xls


Page 1 of 1

EXHIBIT G-15




ROOT PRUNING
NOT TO SCALE

EXHIBIT G-14



CROWN REDUCTION
NOT TO SCALE




FOREST CONSERVATION SIGNAGE

NOT TO SCALE

- NOTES:
- BOTTOM OF SIGN TO BE HIGHER THAN TREE PROTECTION FENCE.
 - SIGNS TO BE PLACED 50 TO 100' APART. CONDITIONS ON SITE AFFECTING VISIBILITY MAY WARRANT PLACING SIGNS CLOSER OR FARTHER APART WITHIN THE ACCEPTABLE NOTED RANGE.
 - ATTACHMENT OF SIGNS TO TREES IS PROHIBITED.
 - SIGNS MAY BE REMOVED FROM RESIDENTIAL LOTS UPON ISSUANCE OF USE AND OCCUPANCY RETENTION FOREST ONLY.
 - ALL SIGNAGE MUST REMAIN DURING THE MAINTENANCE PERIOD.
 - THE SIGNS NOTIFY CONSTRUCTION WORKERS AND FUTURE RESIDENTS OF THE NEARLY PLANTED MATERIAL, IMPROVING THE TREES' SURVIVAL RATES.
 - SIGNS MAY BE ADAPTED BY RESIDENTS FOR IDENTIFICATION OF FOREST RETENTION AREAS.

Anchor posts should be minimum 2" steel U-channel or 2"x2" timber at least 6' in length.

Highly visible flagging should be attached to the tops of the anchor posts.



BLAZE ORANGE PLASTIC MESH SAFETY FENCE/TREE PROTECTION DETAIL

NOT TO SCALE

- PLACEMENT OF ORANGE HIGH VISIBILITY FENCE:
- ORANGE HIGH VISIBILITY FENCE SHALL BE MANUALLY INSTALLED ALONG THE LIMITS OF DISTURBANCE, WHERE THAT LIMIT IS WITHIN 50' OF THE FOREST CONSERVATION/ FOREST BUFFER EASEMENTS AND SHALL FUNCTION AS A FOREST PROTECTION DEVICE.
 - RETENTION AREA WILL BE SET AS PART OF THE REVIEW PROCESS.
 - BOUNDARIES OF THE RETENTION AREA SHALL BE STAKES AND FLAGGED PRIOR TO INSTALLING THE DEVICE.
 - ROOT DAMAGE SHALL BE AVOIDED.
 - PROTECTIVE SIGNAGE MAY ALSO BE USED.
 - DEVICE SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.


THIS PLAN WAS PREPARED BY:
JENNIFER BIRD
KCI TECHNOLOGIES
MDNR QUALIFIED PROFESSIONAL
STATUS
(SEPTEMBER 2011)

SIGNATURE _____

DATE _____

NO.	REVISIONS DESCRIPTION	DATE

936 RIDGEBROOK ROAD
SPARKS, MARYLAND 21152
TELEPHONE: (410) 316-7800
FAX: (410) 316-7818
www.kci.com



THRESHIELD COURT
STREAM RESTORATION PROJECT

CAPITAL PROJECT D-1158
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
11000 COLUMBIA AVENUE
SPRINGFIELD, MARYLAND 21158

FOREST CONSERVATION PLAN NOTES AND DETAILS

SCALE: AS SHOWN

DATE: SEPTEMBER 2011

KCI JOB NO.: 01-081795.53

CAPITAL PROJECT NO.: D-1158

PERMIT ISSUE:

CONSTRUCTION ISSUE:

FCP3

SHEET NO.: 27 OF 27

EP-12-005

PLOTTED: 09:59 AM on Thursday, September 29, 2011
BY: Kristy Potter, Division: P003, Water Resources O&M, Emp. # 200800010001795.53, Drawings: CP - Notes and Details.dgn




Acct# 1402294044
F-85-052

E 13650000
N 572800

E 13653000
N 572800

675



LEGEND	
LIMITS OF DISTURBANCE	LOD
EXISTING CONTOUR	350
PROPOSED CONTOUR	350
PROP. 100-YEAR FLOODPLAIN	(Dashed line)
EX. 100-YEAR FLOODPLAIN	(Dashed line)
PROPERTY LINE	(Dashed line)
EASEMENT LINE	(Dashed line)
WETLAND LINE	(Dashed line)
WATERS OF U.S.	(Dashed line)
WETLAND BUFFER	(Dashed line)
FENCE	(Symbol)
SEWER LINE	(Symbol)
SEWER MANHOLE	(Symbol)
STORM DRAIN	(Symbol)
EX. TREE	(Symbol)
EX. TREE TO BE REMOVED	(Symbol)
CONSTRUCTION BASELINE	(Symbol)
ALTERNATING ROUGHNESS	(Symbol)
STONE TOE PROTECTION	(Symbol)
RIFFLE GRADE CONTROL	(Symbol)
COBBLE STONES	(Symbol)
BOULDERS	(Symbol)
STABILIZED CONSTRUCTION ENTRANCE	(Symbol)
SILT FENCE	SF
SUPER SILT FENCE	SSF
ORANGE SAFETY FENCE	OSF
SANDBAG DIVERSION	(Symbol)
PUMP	(Symbol)
FILTER BAG	FB
DISCHARGE HOSE	(Symbol)
TREE PROTECTION FENCE	TPF
EXISTING ROAD/ PARKING LOT	(Symbol)
EXISTING WOODS	(Symbol)

NOTES:
1. REMOVE WOODY DEBRIS FROM STREAM AND ADJACENT TO STREAM AT DIRECTION OF ENGINEER. WOODY DEBRIS WITHIN CHANNEL BUT OUTSIDE OF LIMIT OF DISTURBANCE SHALL BE REMOVED BY HAND.
2. ALL TREES SHOWN SHALL NOT BE DISTURBED UNLESS SHOWN TO BE REMOVED ON PLANS, OR WITH THE APPROVAL OF THE ENGINEER.


THIS DEVELOPMENT IS APPROVED FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT.
John R. Robertson
HOWARD SCD
9/29/11
DATE

PROFESSIONAL CERTIFICATION: I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. 31201. EXPIRATION DATE: JANUARY 24, 2013

MATCHLINE (SEE SHEET GR02)

NO.	REVISIONS DESCRIPTION	DATE

936 RIDGEBROOK ROAD
SPARKS, MARYLAND 21152
TELEPHONE: (410) 316-7800
FAX: (410) 316-7818
www.kci.com



THRESHFIELD COURT
STREAM RESTORATION PROJECT
CAPITAL PROJECT D-158
HOWARD COUNTY DEPARTMENT OF PUBLIC WORKS
STORMWATER MANAGEMENT DIVISION
8701 COLUMBIA, MD 21048

GRADING PLAN

SCALE:	1" = 20'
DATE:	SEPTEMBER 2011
KCI JOB NO.:	01-081795.53
CAPITAL PROJECT NO.:	D-1158
PERMIT ISSUE:	
CONSTRUCTION ISSUE:	

GR01
SHEET NO.: 7 OF 27